

This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + Refrain from automated querying Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search


Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at http://books.google.com/





150 1 - 11/1-2





A

SYSTEM OF MINERALOGY.

		•
•		
	·	
•		
-		

SYSTEM

OF

MINERALOGY,

COMPRISING THE

MOST RECENT DISCOVERIES:

INCLUDING

FULL DESCRIPTIONS OF SPECIES AND THEIR LOCALITIES, CHEMICAL ANALYSES
AND FORMULAS, TABLES FOR THE DETERMINATION OF MINERALS,
WITH A TREATISE ON MATHEMATICAL CRYSTALLOGRAPHY
AND THE DRAWING OF FIGURES OF CRYSTALS.

ILLUSTRATED BY SIX HUNDRED WOOD CUTS.

By JAMES D. DANA, A. M.

Marker of the Soc. Cass. Nat. Cur. of Moscow, the Soc. Philomathique of Paris, the Geological Soc. of London, the American Academy of Arts and Sciences at Boston, etc.

Silliman Professor of Natural History, Yale College.

" Hæc studia nobiscum peregrinantur, rusticantur."

FOURTH EDITION, REWRITTEN, REARRANGED, AND ENLARGED.

VOLUME I.

NEW YORK AND LONDON:
PUBLISHED BY GEORGE P. PUTNAM & CO.

1854.

THOMAS J. STAFFORD, PRINTER, NEW HAVEN, CONN.

PREFACE.

Is the Preface to the last edition of this Treatise, the classification of fineals then adopted was announced as only a temporary expedient. The mean of Mohs, valuable in its day, had subserved its end; and in throwing off its shackles for the more consistent principles flowing from recent tess in Chemistry, the many difficulties in the way of perfecting a new distinction led the author to an arrangement which should "serve the arrangement of the student without pretending to strict science."

A dassification on chemical principles was however proposed in the latter part of the volume, in which the Berzelian method was coupled with crystallegraphy, in a manner calculated to display the relations of species in composition as well as form, and prominently "exhibit the various cases of isomorphism and pleomorphism among Minerals." The progress of Science is afforded the means of giving greater precision and simplicity to this amangement, until now it seems entitled to become the authorized method of a System of Mineralogy. Whether regarded from a physical or chemical point of view, the groupings appear in general to be a faithful exhibition of the true affinities of the species.

The mind uneducated in Science may revolt at seeing a metallic mineral, a galena, side by side with one of unmetallic lustre, as blende; and some systems, in accordance with this prejudice, place these species in separate orders. Like the jeweller, without as good reason, the same works have the diamond and sapphire in a common group. But it is one of the sublime lessons taught in the very portals of Chemistry, that nature rests no grand distinctions on lustre, hardness, or color, which are mere externals, and this truth should be acknowledged by the Mineralogist rather than defied. Others, while recognizing the close relations of the carbonates of lime, iron, zine and manganese, (calcite, spathic iron, smithsonite and diallogite,) or of the silicates of lime, iron, manganese, (wollastonite, augite, rhodonite,) are somewhat startled by finding silicate of zinc, or silicate of copper, among the silicates of the earths or of other oxyds. But the distinction of "useful" and "useless," or "ores" and "stones," although bearing on "economy," is not Science.

The advantages which the arrangement of the last edition afforded those interested in mining and metallurgy, is secured in the present volumes by an index to the useful ores, in which their distinctive characters and their rela-

tive importance in the Arts are mentioned, and references are given to the pages where the full descriptions are to be found.

During the four years since the appearance of the last edition, the Science of Mineralogy has increased in species from 625 to 660; and this notwithstanding the bankruptcy of some 45 of the number. The important work of RAMMELSBERG on Chemical Mineralogy, has been continued in a fifth Supplement, issued in 1853. A similar review of the Progress of the Science by Dr. Gustav Adolph Kenngott, conducted with like thoroughness, though with less criticism, has appeared in Vienna, and already two large volumes have been issued, one reviewing the Science for the years 1844 to 1849, the other, for 1850 and 1851. During this period also, Professor GUSTAV ROSE has published his Krystallo-chemische Mineral-System (1853); Professor Von Kobell, a work on Mineralogical Nomenclature (1853), and a new edition of his excellent Tables for the Determination of Minerals, (1853); Dr. Franz Leydolt and Professor Adolf Macharschek, of Vienna, their elements of Mineralogy based on the system of Mohs (1853); Dr. Kenngott of Vienna, "Das Mohs'sche Mineralsystem" (1853), and also a portfolio of plates of figures for the construction of Models of crystals (1854); Professor Quenstedt of Tubingen, the first part of a Treatise on Mineralogy (1854); Dr. C. F. NAUMANN, a revised edition of his invaluable Elements of Crystallography (1854); Dr. FRIEDERICH PFAFF of Erlangen, Elements of the Mathematical Relations of Crystals (1853); F. H. Schrö-DER of Clausthal, Dr. RAMMELSBERG of Berlin, and Jos. Pecirka of Prague, smaller Manuals on the same subject, (1852, 1853); Dr. J. ZIMMERMANN of Stuttgart, a small "Tashenbuch der Mineralogie" (1852); NICOLAI VON Korscharov, the able Crystallographer of St. Petersburg, the first numbers of his "Mineralogie Russlands," in quarto, (1853, 1854); H. J. BROOKE and W. H. MILLER, a new and original Treatise under the title of Phillips's Mineralogy (1852); C. F. PLATTNER, an enlarged edition of his extended Treatise on the Blowpipe (1853): besides the great work of Dr. Gustav Візсног, on Chemical and Physical Geology, begun in 1846, now numbering 2950 pages, (the last issue in 1853), and yet wanting another part to be complete; also G. H. Otto Volger's Essays on the Development of Minerals, (Studien zur Entwicklungsgeschichte der Mineralien,) as the basis of Scientific Geology and a rational Mineral Chemistry, (Zürich, 1854); and von WALTERSHAUSEN'S Treatise on the Volcanic Rocks of Sicily and Iceland. Moreover, various valuable papers have been issued in Scientific Journals and Transactions abroad, by Haidinger, Rammelsberg, Breithaupt, Scheerer, VON KOBELL, ROSE, BUNSEN, HERMANN, VON RATH, HAUSMANN, SANDBERGER, Wöhler, Baer, Kenngott, Schabus, Korscharov, Scacchi, Meneghini, DELESSE, DAMOUR, DEVILLE, DESCLOIZEAUX, SENARMONT, CHAPMAN, MALLET,

7

soor, PERCY, and other able investigators. In this country have appeared THER & WHITNEY'S Report on the Geology and Mineralogy of the Lake sperior Region, (1851 and 1853); and J. D. Whitney's Mineral Wealth the United States (1854). Moreover, Dr. J. LAWRENCE SMITH and G. J. Buse, have labored with important results in American Mineralogy, clearway many doubtful species; and other researches have been pubabed by T. S. HUNT, F. A. GENTH, J. C. BOOTH, J. D. WHITNEY, C. U. SHEPARD, J. W. MALLET, W. P. BLAKE, M. H. BOYE and T. H. GARRETT. Of all these Publications, BISCHOF'S "Lehrbuch" stands first in importance. Vineralogy was well nigh a lifeless Science, having only powers of increase by accretion, like the objects of which it treats,-the addition of a new Mineal now and then being the great event of interest in its progress. BISCHor, by his elaborate researches and profound views, has given it a new im-He makes every analysis of a Mineral an important element in the study of Mineral history, showing the necessity of their multiplication, and sell exposing the leanness of Chemical formulas when given as a substitute for analyses. The associations and collocations of Minerals, their changes from exposure to atmospheric and other agencies, and even the infinitesimal agredients in their constitution, are all made to bear on the question of the orgin and progress of Mineral and Rock Formations. A Mineral species is to have a history of its own,-its perfect state, its liabilities to alteration and decay, its successive changes, and again its renovation or its metamorphosis into a new species. These views taken in their wide extent, constrate the proper basis of the Science of Geology, and should have their full exposition in a work on that Science. But the elements of the subject are with propriety indicated in a Mineralogical Treatise. While dwelling with beeved emphasis on the researches of BISCHOF, we should not forget that others have labored in the same department, prominent among whom, are HADDINGER, VOLGER, BREITHAUPT, BLUM, BUNSEN and DELESSE.

The work next in importance, more especially in its bearing on the crystallization of Minerals, is the "Elementary Introduction to Mineralogy," by Brooks & Miller. It stands preëminent for its original measurements, and is thorough revision of the angles of Crystals, and will remain a permanent surce of information on these points.

In the preparation of the present edition, the author takes pleasure in mixing special acknowledgments to the work of Bischof, for facts and principle relating to the Chemistry of the alteration of Minerals; to Rammels-ing's Supplement to his Chemical Mineralogy, a work whose earlier parts entributed largely to the preceding edition of this Treatise; to Kenngott's and Kenschanov's publications; and to the critical observations in the "Mineralystem" of G. Rose. Frequent use has also been made of the work of Brooke & Miller, in the crystallography of the species, from which the

angles and planes of crystals have often been cited. The various Scientific Periodicals of Russia, Germany, Italy, France and Britain, some of them down to June last, have been searched for their facts, and every effort has been made to post the work up to the day of publication.

American Mineralogy owes much to the careful revision it has received at the hands of Messrs. Smith & Brush; and the author would express his special personal obligations to each of these Chemists. From Dr. F. A. Genth, of Philadelphia, he has derived generous aid both in suggestions and results of researches. Mr. T. S. Hunt has kindly contributed several new analyses throwing much light on the minerals of Canada; and valuable observations and analyses have been received from J. D. Whitney and Professor Booth. Many and various have been the favors, in the way of new facts, opinions and recent discoveries, which the author owes to Mr. Louis Sæmann of Paris. He is also largely indebted to Robert P. Greo, Jr., of Manchester, England, for information respecting the Mineralogy of Great Britain, liberally furnished from a work by him and W. G. Lettsom, now in the press.

The author would also express his gratitude to Messis, T. S. Hunt, C. M. Wheatley, B. Silliman Jr., L. Wilder, T. F. Seal, W. T. Vaux, L. Stadtmuller, and G. J. Brush, for the privilege of figuring Crystals of American Species in their possession. Similar favors were received from the lamented J. E. Teschemacher of Boston, who ever rejoiced to devote himself and his cabinet to the progress of the Science, and continued his communications with the author, until the day before his death in November last.

In the preparation of this edition, the subject of Crystallography has been revised and simplified. A system of notation for the figures of Crystals, both brief and simple, has been adopted; and many new and original figures have been introduced. The homeomorphous relations of mineral species have been worked out with considerable care, in order to arrive at their true fundamental forms, and trace the bearing of the subject on their composition and classification. The Table of atomic weights has been corrected according to the most recent results, and the percentages of the formulas have been recalculated to correspond with it. The subject of pseudomorphs is treated at some length, and along with the descriptions of the species, a paragraph is devoted to the altered forms which each presents. These changes, together with the remodeling of the classification, and the large additions throughout, render the Treatise more properly a new work, than a revised edition.

NEW HAVEN, Sept. 1, 1854.

TABLE OF CONTENTS.

INTRODUCTION.

RELATIONS OF MINERALOGY TO THE OTHER NATURAL SCIENCES,	17 19
PART L	
CRYSTALLOLOGY, OR THE SCIENCE OF THE STRUCTURE OF MINERALS.	
Section I. Crystallography.	
General Characters of Cristals,	21
L STETEMS OF CRYSTALLISATION,	28
L Modifications of Crystals,	82
Laws of Symmetry, and resulting Forms,	88
1. Monometric System,	84
2. Dimetric System,	89
8. Trimetric System,	41
4. Monoclinic System,	48
5. Triclinic System,	44
6. Hexagonal System,	45
Law of Numerical Proportion in the Modifications of Crystals,	49
Zones of Planes,	58
Symbols of Planes,	56
Mathematical Crystallography,	62
Mathematical Crystallography,	98
	108
	110
	122
2	

4	ı	٠.	•	
1		1		

CONTENTS.

	Crystalline St							•		•	•
II. CRYSTALLIN				OUS	VARIE	TIES,	•		•	•	
III. Pseudomor	PHOUS CRYSTAL	3, .	•	•	•	•		•	•		
	Section	N II.	Cı	RYST	ALIA	GEN	Y.				
I. PRACTICAL C	DRYSTALLOGENY,	, .									. :
I. Practical (II. Theoretica	L CRYSTALLOGE	NY,									:
Formation	lline Molecules of Simple and	Comp	ound	Cry	stals,						:
Formation	of Secondary	Planes	and	Orig	in of	Clea	vage,				
	•						_				
		-									
		P A	рτ	, ,	T						
		IA	IL I	1	1.						
	PHYSICAL	PROP	ERTI	ES	OF B	MINE	RAL	S.			
			,								
	DEPENDING OF										
Lustre, .											. :
Color,		•									
Dichroism,	Pleochroism,										
Diaphanei	ty,					•					
Refraction	, Polarization,										
Phosphore	scence, .										
II. Елествісіту	, MAGNETISM, .										
II. HEAT, .											
V. Specific Gr	AVITY,										
V. CHARACTERS											
Hardness,											
									. •		
Fracture,							٠.		•	٠.	
I. TANTE,											
I. Opor,	•		•				٠.		•	•	
. (7)	• • •	•		•	•	•	•	•	•	•	
		_									
	J	PAI	R T	I	ΙΙ.						
				. un	4 T 434	~ 1.º			•		
	CHEN	HCAL	MI	1 P. P.	ALUM	• • •					
	CHEN	IICAL	MII	NEK.	ALU	<i>J</i> 1 .					
. Composition		IICAL	MII.	ner.	ALU(<i>3</i> 1 .					. 1

CONTENTS.	11
Table of Atomic Weights,	184
Chemical Formulas of Minerals,	
2 Relations of Minerals as exhibited in the Principles of Isomorphism,	
and Dimorphism,	189
Isomorphous Groups of Elements,	190
Dimorphism, Trimorphism, Pleomorphism,	191
Methods of Determining true Affinities in Form,	192
List of Homœomorphous Groups,	195
Monometric System,	195
Dimetrie System,	197
Hexagonal System,	198
Trimetric System,	199
Monoclinic and Triclinic Systems,	204
Origin of Homosomorphism,	204
Bearing of the subject on Chemical Composition and Formulas,	206
Cause of Dimorphism,	209
FIGURAL EXAMINATION OF MINERALS,	210
Chemical Tests,	, 210
Artion with the Blowpipe,	218
P-EUDOMORPHS AND METAMORPHIC CHANGES IN MINERALS,	222
Kinds of Pseudomorphs,	222
Table of Pseudomorphs,	228
attace of Pseudomorphic or Metamorphic Changes,	227
Analysis of Sea, Spring, and River Water,	229
Source of Saline Ingredients of Waters,	280
Kinds of reactions, or methods of Composition and Decompo-	
sition,	281
Artificial Formation of Minerals,	286
Crystallized Furnace Products,	287
Association of Minerals,	288
PART IV.	
MANAYANT	•
TAXONOMY.	
MINERALOGICAL SPECIES,	241
1 CLASSIFICATION OF MINERALS,	244
(lassification of the Elements,	245
Fundamental Points in the Classification of Compounds,	246
General Review of the Classification of Minerals,	249
II Nomenclature,	255

CONTENTS.

PART V.

n	Report D	MIN	TTVP	MINTED	ATAGY.

DETERMINATIVE MINERALOGY.		
Introductory Observations,		. 261
		
VOLUME II.		
PART VI.		
DESCRIPTIVE MINERALOGY.		
DESCRIPTIONS OF SPECIES,		. 7
SUPPLEMENT—CATALOGUE OF AMERICAN LOCALITIES OF MINERALA,		
APPENDIX,		
AMNOTATED INDEX TO THE USEFUL ORDS,	•	
O		

ABBREVIATIONS.

Act. Soc. Sci. Fenn.-Acta Societatis scientifice Fennice; at Abo, Finland. Afh. i Fys., or Afhandl.—Afhandlingar i Fysik, Kemi och Mineralogi, by Hisinger and Berzelius, 6 vols. 1806 to 1816. Stockholm.

Am. J. Sci.—American Journal of Science and Arts, commenced in 1819; conducted

by B. Silliman-associated with B. Silliman, Jr., since 1838; and also with J. D. Dana since Jan. 1846. 1st series tri-monthly, vols. 1 to 49, with vol. 50, an Index to the preceding; 2d series bi-monthly, vols. 1 (1846) to 18 (close of 1854); the 10th containing an Index to the first 10 volumes of the series.

Ann. Chem. u. Pharm .- Annalen der Chemie und Pharmacie, by F. Wöhler and J. Liebig. In monthly numbers of about 180 pages, 4 vols. a year. Vol. xc. (or xiv of New Ser.), commenced with April, 1854.

Ann. Chim. - Annales de Chimie. 96 vols. 1789-1815. Paris.

Ann. Ch. Phys. [2] and [3].—Annales de Chimie et de Physique, 2d series, 1816—1840, 78 vols. (3 vols. a year); 3d ser. since 1841; with 1854, volume xl,

began.

Ann. Lyc. N. H. New York.—Annals of the Lyceum of Natural History of New

York. The 6th volume was begun with 1854.

Ann. d. M. (or Mines) .- Annales des Mines, a monthly of 180 pages, now making 3 vols. a year; 1st ser., 13 vols., 1816—1826, Paris; 2d ser., 10 vols.; 1827—1831, 2 vols. a year; 3d ser., vols. 1832—1841; 4th ser. began in 1842; 5th ser. in 1852. Index to 4th ser. published in 1853.

1842; 5th ser. in 1852. Index to 4th ser. published in 1853.

Ann. des. M. Russ.—Annales des Mines Russes.

Ann. Phil.—Annals of Philosophy, by Th. Thomson. 16 vols. London, 1813—
1820; new series, by R. Phillips, 12 vols. London, 1821—1826, (afterwards united with the Philosophical Magazine, edited by Taylor and Phillips.

Archiv. d. Pharm.—Archiv der Pharmacie, 8vo., Hannover.

Arsb. Berz.—Arsberättelse om Framstegen i Kemi och Mineralogie af Jac. Berzelius; from 1821 to 1847. The Jahresbericht, etc., is the German translation.

B. w. H. Ztg.—Berg. und. Huttenmänsche Zeitung.
B. & M.—Brooke and Miller.—Elementary Introduction to Mineralogy, 700 p. 8vo. London, 1852.

Bauma, Zeitsch.—Zeitschrift für Physik und Mathematik, by Baumgartner and v.

Ettingshausen, Vienna, 1826—1832; Zeitschrift für Physik und verwandte Wissenschaften, by Baumgartner and von Holger. Vienna, 1832.

Beck, Min. N. Y.—Mineralogy of New York, by L. C. Beck, 536 pp. 4to. Albany,

1842.

Berichte Mitth. Fr. Nat. zu Wien,-Berichte über die Mittheilungen von Freunden der Naturwissenschaften in Wien, (Vienna), gesammelt und herausgegeben von W. Haidinger, vols. I to VII, 1846 to 1851.

Berzelius.

Berth. T. des Ess.-Traité des Essais par la voie sèche by Berthier. 2 vols. Paris, 1835.

Beud-Beudant; Traité élémentaire de Mineralogie. 2d edit. 2 vols. 8vo. Paris,

Bischof Geol. (or Lehrb.)-Lehrbuch der chemischen und physikalischen Geologie von Dr. Gustav Bischof, 2vols., 1846-1854, (last part not yet issued), Bonn. Bib. Univ. Gen.—Bibliothéque Universelle de Genève. 1st ser. 1816-1835; 2d ser. 1836-1845; 3d series, since 1846, with the literary and scientific parts separate, the latter under the title, "Archives des Sciences Physiques et Naturelles."

Bost. Jour. Nat. Hist .- Journal of the Boston Society of Natural History, since

1834. Boston.

Breit.—Breithaupt.—Handbuch der Mineralogie. 3 vols. Leipzig.

Breit.—Breithaupt.—Handbuch der Mineralogie. 3 vols. Leipzig.

Edinburgh. 1st ser.,

Brewst J.—Edinburgh Journal of Science, by D. Brewster. Edinburgh. 1st ser., 10 vols., 1824—1829; 2d ser., 6 vols., 1829—1832.

Bull. Soc. Geol. de Fr.—Bulletin de la Société Géologique de France, since 1830, forming 1 vol. a year. New series begun in 1843. Tome xi, for the year 1854.

Bull. Soc. Nat. Mosc.—Bulletin of the Society of Naturalists of Moscow.

Chem. Gaz.—Chemical Gazette, or Journal of Practical Chemytery, conducted by

Wm. Francis. Published twice a month in a pamphlet of 24 pages, 1 volume a year. London. Commenced Jan. 1843.

Compt. Rend.—Comptes Rendus hebdomadaires des Séances de l'Académie des Sciences. Paris. Weekly, and forming two volumes annually in quarto; since 1835.

Crell's Ann.-Chemische Annalen by Crell. 40 vols., 1784-1804. Helmstädt and Leipzig.

Deville, Etudes.—Etudes Geologiques des Iles Canaries. Paris.

Duf.-Dufrénoy.-Traite de Mineralogie. 3 vols. 8vo. with a fourth volume of

plates. Paris, 1844—1847.

Edinb. Phil. J.—Edinburgh Philosophical Journal, by Brewster and Jameson. 14 vols. Edinburgh, 1819-1826.

Edinb. N. Phil. J., or Jameson's Jour., by Prof. Jameson, continued tri-monthly since 1826. 2 vols. a year. Vol. lvi, commenced with the year 1854.

Gilb. Ann.—Annalen der Physik, by Dr. L. W. Gilbert. 76 vols., 1799—1824.

Leipzig. From vols. 31 to 60, a new series, (1809—1818); from vols. 61 to to 76, another series, (1819—1824), under the title, "Annalen der Physik und der physikalischen Chemie."

Glocker Min. Jahresh.—Mineralogische Jahreshefte by Glocker. 1 vol. 1835. Nürnberg; part of a volume in 1837.
 H.—Hady.—Traité de Mineralogie. 2d ed. 2 vols. and atlas. Paris, 1822.
 Haid.—W. Haidinger, author of a Handbuch der bestimmenden Mineralogie, Wien, 1845; and also of the English translation of Mohs's Mineralogy.

Haid. Ber.—See Berichte, etc., on the preceding page.

Halle Zeitschr.—Zeitschrift für die gesammten Naturwissenschaften herausg. von dem Naturw. Vereine für Sachsen u. Thuringen in Halle, redigirt von C. Giebel u. W. Heintz; begun in 1853, 2 vols. a year.

Hausman—Hausmann. Haudbuch der Mineralogie, 2 vols. Göttingen, 1845.

His. Min. Schwed-Mineralgeographie von Schweden by Hisinger; a translation by Wöhler. Leipzig, 1826.

Hitchcock Geol. Mass.—Geological Report of Massachusetts, by E. Hitchcock, pp.

830. 4to. Boston, 1833.

J.—Jameson.—System of Mineralogy. 4th edit. Edinburgh, 1824. Also Manual of Mineralogy from the Encyclopædia Britannica, 1837.

Jackson, Geol. Rep. N. H .- Geological Report of New Hampshire, by C. T. Jackson. 376 pp. 4to, with plates. Also author of a Report on the Geology of Maine, and another on the Geology of Rhode Island.

Jahrb. k. k. Geol. Reichs.-Jahrbuch der kaiserlich-königlichen geologische Reichs-

anstalt, vols. I-IV. Wien, 1850, 1851, 1852, 1853.

Jahresb.—Jahresbericht, etc.—Translation of Berzelius's Annual Scientific Report, by C. Gmeliu, and afterwards by Wöhler. Commenced in 1822, and continued to 1847.

John Unters.-Chemische Untersuchungen der Mineralkörper, by John. Berlin, 1808-1816.

Jour. Acad. Nat. Sci. Philad .- Journal of the Academy of Natural Sciences of Phila-

delphia; since 1817. 8 vols. to 1842; new series begun in 1848.

Jour. des. Mines.—Journal des Mines, 38 vols., 1794—1815. Paris.

J. f. pr. Ch.—Journal für praktische Chemie, by Dr. O. L. Erdmann and R. F. Marchand; Leipzig, twice a month, in parts of 64 pages each, and 3 vols. a year. From 1834 to 1836, (vols. i to ix), under Erdmann and SchweiggerSeidel; 1837, (vols. x, xi, xii), under Erdmann alone; 1838-1850 under Erdmann and Marchand; 1851, 1852, Erdmann alone; 1853 and since, Erdmann and Gustav Werther. The vol. lxi commenced with the year 1854.

Joy, Inaug. Dissert.-Miscellaneous Chemical Researches, Inaugural Dissertation,

etc., 50 pp., 8vo. Göttingen, 1853. Gel. Anzeig.—Gelehrte Anzeigen—etc., München (Munich).

Karaten Archiv.-Archiv für Mineralogie, Geognosie, Bergbau und Hüttenkunde.

Berlin, since 1829.

Keller u. Ted.—Nordamerikanischen Monatsbericht für Natur- und Heilkunde, redigirt von Dr. W. Keller and Dr. H. Tiedemann; 4 vols., 1850, 1851. Philadelphia.

Klop. Beit.-Beiträge zur chemischen Kenntniss der Mineralkörper, by Klaproth.

6 vols. Berlin, 1795—1815.

V. Ac. H.—Konigl. Vetenskaps-Academiens Handlingar, (Transactions of the Royal Swedish Academy).

Kob .- Von Kobell. - Grundzüge der Mineralogie von Franz von Kobell. Nürnberg, 1838.

Lampadius Handb.-Handbuch zur chem. Analyse d. Mineralkunde. Freiberg, 1791; Nachtrag, 1818.

L'Institut.-L'Institut, Journal Universel des Sciences et des sociétés savantes en

France et à l'étranger. 1 volume a year since 1833. Paris.

Leonh. Bronn, Jahrb.—Jahrbuch für Mineralogie, Geognosie, &c., by von Leonhard and Bronn, 1830—1832; Neues Jahrbuch, &c., since 1833; monthly; 1

Lieb. u. Kopp.—Liebig und Kopp's Jahresbericht, 1847—1853.

Logan Geol. Rep.—Logan's Reports on the Geology of Canada, Montreal, 1849—1853.

Min. N. Y. by Beck.—Report on the Mineralogy of the State of New York. 1 vol. 4to. Albany, 1842.

M.—Mohs. Naturgeschichte des Mineralreiches, von F. Mohs. 2d edit., in 2 parts

or volumes. Vienna, 1836—1838.

Nord. Bidrag.—Bidrag till närmare Kännedom af Finnlands Mineralier, by Nordenskiöld. Stockholm, 1820.

Ofe. K. V. Ak. Förh.—Ofversigt af Kongl. Vetenskaps-Akademiens Förhandlingar.

Ofe. K. V. Ak. Forh.—Olversigt af Kongl. Vetenskaps-Akademiens Forhandlingar.
 Stockholm. (Bulletin of the Royal Academy).
 Phil. Mag. [2].—Philosophical Magazine or Annals of Chemistry, by Taylor & Phillips, 11 vols. London, 1827—1832.—Phil. Mag. [3].—London and Edinburgh Philosophical Magazine and Journal of Science, by Brewster, Taylor and Phillips, (new and united series). London, 1832—1850.—Phil. Mag. [4], 1851; vol. vii, began with Jan., 1854.
 Phil.—Wm. Phillips.—Elementary Treatise on Mineralogy, 8vo. London, 1823; also 1837; also by Fr. Alger, Boston, 1844.—See also, B. and M.
 Phil. Trans.—Philosophical Transactions of the Royal Society of London since 1865.

1665.

Pogg. Ann.—Annalen der Physik und Chemie, by Dr. J. C. Poggendorff. Continued from 1824; monthly; 3 vols. a year. Published for a while at Berlin, and now at Leipzig. Vol. xei commenced with 1854. A general index is published for volumes 1 to 60, to the close of 1843; and another in 1854 for vols, lxi to xc.

Proc. Amer. Assoc.—Proceedings of the American Association for the Advancement of Science, vols. i to vi; i of meeting at Philadelphia; ii, at Cambridge; iii, at Charleston, S. C.; iv, at New Haven; v, at Cincinnati; vi,

at Albany.

Quart. Jour .- Quarterly Journal of Science and Arts of Royal Institution. 30

vols. London, 1816—1830.

Quart. Jour. Chem. Soc.—The Quarterly Journal of the Chemical Society of London, edited for the Society by E. Ronalds. Commenced in 1848, and published tri-monthly, in parts, 96 pages each. Volume vii commenced with April, 1854.

Ramm. Handw.—Handwörterbuch des chemischen Theils der Mineralogie, von C. F.

Rammelsberg. 3 vols., 1841. Berlin. Supplements 1, 2, 3, 4, 5, about Angust, in the years 1843, 1845, 1847, 1849, 1853.

Rec. Gen. Sci.—Records of General Science, by R. D. Thomson. 4 vols. London,

1885, 1886.

Rogers's Geol. Rep. N. J.—Geological Report of New Jersey, by H. D. Rogers, 300

pp. 8vo. Philadelphia, 1840.

Rose's Kryst-Chem. Min.—Das Krystallo-Chemische Mineralsystem of G. Rose, 156 pp. 8vo. Leipzig, 1852.

Scheer. Jour.—Allgemeines Journal der Chemie, by Scheerer. 10 vols. Leipzig,

1799-1803.

Schweig. Jour.-Journal für Physik und Chemie by Schweigger, and afterwards

with Schweigger-Seidel. 69 vols, 1811 to 1833 at Nürnberg and Halle.

Shep.—C. U. Shepard, Treatise on Mineralogy. 12mo. New Haven, Ct. 1st part,
an Introduction to the Science, 1 vol., 1823; 2d part, 2 vols., 1835; 2d
edit. (of 1st part), 1844; 1st half of 3d edition, 1852.*

Sitzungsb. Wien.—Sitzungsberichte der Kaiserlichen Akademie der Wissenschaften; Math.-Nat. Classe. Wien (Vienna). Vol. xi began with June of 1853. Skand. nat. S. i Stockholm.—Transactions of the Scandinavian Society of Natural

Science at Stockholm.

Stromeyer's Unters.-Untersuchungen über die Mischung der Mineralkörper. Göt-

tingen, 1822.

Suckow.—Die Verwitterung im Mineralreiche.

Thom. Min.—Outlines of Mineralogy, by Dr. Th. Thomson. 2 vols. 8vo. London,

Ullmann Syst. tab. Ueb .- Systematisch-tabellarische Uebersicht der mineralogischeinfachen Fossilien, by Ullmann. Kassel and Marburg, 1814, with occasional issues of a later date.

Verh. Min. St. Petersb.—Verhandlungen der kaiserlich russischen mineralogischen

Gesellschaft, zu St. Petersburg.

Volger, Entwick.—Studien zur Entwickelungsgeschichte der mineralien als Grundlage einer wissenschaftlichen Geologie und rationellen Mineralchemie,

von G. H. Otto Volger, 548 pp., 8vo., with 1 plate. Zurich, 1854.
Waltershausen's Vulk. Gest.—Ueber die vulkanischen Gesteine in Sicilien und Island und ihre submarine Umbildung, von W. Sartorius von Waltershausen, 582

pp. 8vo. Göttingen, 1853.
Wolff, Foss. Ekeberg.—E. Th. Wolff de Compositione fossilium Ekebergitis, Scapolithi et Mejonitis; Dissertatio inauguralis Chemica, Berolini; 1843. W .- Werner.

U. S., United States; Ala, Alabama; Ark., Arkansas; C. E., Canada East; C. W., Canada West; Cal., California; Ct. or Conn., Connecticut; Del., Delaware; Ga., Georgia; Ill., Illinois; Ind., Indiana; Ky., Kentucky; La., Louisiana; Mass., Massachusetts; Md., Maryland; Me., Maine; Mich., Michigan; Miss., Mississippi; Mo., Missouri; N. C. or N. Car., North Carolina; N. H., New Hampshire; N. J., New Jersey; N. Y., New York; O., Ohio; Pa. or Penn., Pennsylvania; R. I., Rhode Island; S. C. or S. Car., South Carolina; Tenn., Tennessee; Va., Virginia; Vt., Vermont.

^{*} This new edition of Prof. Shepard's Treatise should have been honorably mentioned at the top of page 7, (Preface). It is greatly to be regretted, on account of Prof. Shepard's extensive acquaintance with American Mineralogy, that the work is still incomplete.

INTRODUCTION.

The productions of our globe naturally distribute themselves into three grand divisions, the Animal, the Vegetable, and the Mineral or Inorganic; and our knowledge of the various kinds of objects in these departments constitutes the natural sciences, Zoology, Botany, and Mineralogy.

The first two divisions include all beings possessed of vitality: beings which increase by an assimilation of nutritive substances taken internally; which arrive at maturity by a series of successive developments; whose parts are mutually dependent, and cannot be separated without destroying the perfection of the individual; which, after a certain period, lose the capability of continuing the usual functions of life, and consequently die. The powers of vitality being no longer present to counteract decomposition, death is soon followed by a complete destruction of the original living being.

The third division, on the contrary, contains those natural objects that are not possessed of life; objects which increase by accretion merely, or an external addition of particles unaltered by any powers of assimilation in the object; which are equally perfect in the embryo state or at the earliest commencement of their formation, and in the enlarged individual; whose individuality is not destroyed by a separation of parts; whose formation is originally the result of chemical attraction, and, consequently, they are not, from their nature, necessarily liable to decomposition.

There is thus a strong line of demarkation in nature between

those bodies which live, grow, and die, and those which exist only by virtue of chemical and cohesive forces.

The whole range of inorganic substances, whether made by art or existing in the earth's crust, fall into the last division, for they are produced by the same laws, and by like modes of aggregation. They constitute the Inorganic Kingdom. Minerals, as the term is used, are those species of this vast kingdom, that occur readymade in the earth's crust. They exist by no different forces from the compound that proceeds from the laboratory; for it matters not whether sulphuric acid and lime come together in the workshop of art or nature; whether the hand of man bring the materials into juxtaposition, a running brook, a mineral spring, or a volcanic fumarole: the result in both cases is gypsum, identical in chemical, physical, and crystallographic characters. In many cases art has not yet found out the methods of imitating nature, and some of the requisites, as indefinite time, unlimited mass, weak and prolonged electric forces, and peculiar juxtaposition of elements and compounds, are not readily commanded by the chemist. Still the forces are the same in kind, and in this respect the inorganic kingdom is single and undivided. The Science of Mineralogy hence treats of only a small part of the third kingdom of nature. It includes here and there a species from the systemthat is, those species that happen to have been formed by outdoor processes. The limits of the department are not based on any grand points of difference between these and other inorganic compounds; they are assumed, in order to present together a collection of facts, which the student conveniently considers in one connection-facts relating to the natural productions of our globe.

It is important, at the outset, that the distinctions here laid down be fully appreciated; for very partial views of nature are received, when minerals are supposed to constitute a complete system in themselves. The explorer of some contracted territory might as well claim the species he finds to constitute exclusively a kingdom, as one who takes a wider portion or the whole of the earth's surface.

The scope of the word mineral is conventional. It is convenient to include under it, all inorganic natural objects which are proper chemical compounds, whether solid, liquid, or gaseous; and this convenience is a sufficient ground for the course. Moreover the

physical conditions of solidity, liquidity, gaseity, are not even specific distinctions in the wide inorganic kingdom, and hence afford no reasonable or necessary limit to the mineral department.

Mineralogy is closely related to the Science of Geology. The former considers minerals as independent bodies; the latter, in their dependent relations, constituting soils and various rocks. It is the object of Mineralogy to describe the individual qualities of the several mineral species, while Geology treats of them only as associated in the structure of the earth.

To an intermediate department, Chemical Geology, belongs the discussion of the origin and formation of minerals, both as simple species and as aggregated in rock masses.

MINERALOGY:

SUBDIVISIONS OF THE SUBJECT ADOPTED IN THE FOLLOWING TREATISE.

The aggregation of inorganic matter depends on a power called crystallization, or crystallogenic attraction, by the action of which minerals receive a regular structure and take on certain forms called crystals. This power is universal, like vitality in the animal and vegetable kingdoms, and hence an inorganic species has as much its characteristic form as a plant or animal. Under the head of Crystallology, or, the Science of the Structure of Minerals, this subject occupies Part I. of the following treatise. Crystallology includes two sections; 1. Crystallography, or, descriptions of the crystalline forms of minerals; 2. Crystallogeny, or, the origin of the forms and structure of crystals.

The properties of minerals come next under consideration:-

First, those depending on the transmission and reflection of Light and Heat, on Electricity, Magnetism, Gravity, Cohesion, and also their relations to the senses of taste and smell, or their Taste and Odor. These, the Physical Properties of Minerals, constitute the subject of Part II.

Next follow:—

Part III. On the Chemical Characters and Relations of Minerals. Part IV. On Taxonomy, or Classification.

Part V. Determinative Mineralogy, or Tables for the determination of Species.

Part VI. Full descriptions of the species, under the head of Descriptive Mineralogy.

In treating of the properties of minerals, a work on Mineralogy is necessarily brief. A full discussion of the relations of crystals to light, heat, and electricity, would lead us out of our proper science into Physics; for it is by means of crystals that many of the fundamental laws of light, heat, and electricity, are exhibited. These subjects are considered, therefore, only so far as they afford aid in discriminating among minerals, and throw light on the characters of species.

MINERALOGY.

PART I.

CRYSTALLOLOGY,

OR THE SCIENCE OF THE STRUCTURE OF MINERALS.

SECTION I.

CRYSTALLOGRAPHY.

A crystal is an inorganic solid bounded by plane surfaces symmetrically arranged, and resulting from the forces of the constituent molecules.

In its original signification, this term was applied only to crystals of quartz, which the ancient philosophers believed to be water congealed by intense cold. Hence the term, from xpuorallos, ice.* It now includes all those regular solids that owe their formation to the attraction that produced the xpudrallos of the ancients, or which, like that, possess a regular form, whatever may be the color or the degree of transparency or opacity.

In brilliancy of lustre and symmetry of form, crystals, as they are found in nature, sometimes rival the most splendid gems from the hands of the lapidary. They occur of all sizes, from the merest

densari. Contraria huic causa crystallum facit, gelu vehementiore concreto.

^{*} Diodorus II. p. 168, Wess.—τούς γαρ αρυστάλλους λίθους έχειν την σύστασιν εξ ύδανος εαθαροί παγέντος, σύχ ύπο ψυχους, άλλ' όπο θείου πυρος δυναμεως.
Seneca, Quest. Nat. III. 25: Unde autem flat ejusmodi lapis apud Græcos ex ipso

nomine apparet. Kporrokhor enim appellant seque hunc perlucidum lapidem quam illam glaciem ex qua fieri lapis ereditur. Aqua enim cœlestis minimum in se terreni habens, quum induruit longioris frigoris pertinacia spissatur magis ac magis donec omni aere excluso in se tota compressa est, et humor qui fuerat, lapis effectus est.

Plinius, Hist. Nat. XXXVII. 2: Murrhina—humorem putant sub terra calore

microscopic point, to a yard or more diameter. A single crystal of quartz now at Milan, is three and a quarter feet long, and five and a half in circumference; and its weight is estimated at eight hundred and seventy pounds. One of the gigantic beryls from Acworth, New Hampshire, measures four feet in length, and two and a half in circumference; and another at Grafton, is over four feet long, and thirty-two inches in one of its diameters, and does not weigh less than two and a half tons. But the highest perfection of form and transparency are found only in crystals of small size.

Variety and Constancy of Form.—Each mineral, as has been remarked, has its own mode of crystallization, by which it may be distinguished, just as we distinguish a plant by its characters and mode of growth. For example, a crystal of calc spar is known at once by its angles, wherever it may have been found, and also by a peculiarity of internal structure. The same is true for other species: consequently, measurement of angles and examination of structure have become important means of distinguishing minerals. The constancy of angle between similar planes in the same species, is a fact of the highest importance in the science: it is not absolutely perfect, owing to some causes hereafter to be stated, yet

it admits of but little variation.

The variety of form presented by a single mineral, may be very great. Calc spar is found in double pyramids, in prisms, rhombo-hedrons, and many other forms; pyrites, in cubes, octahedrons, dodecahedrons; and so with other species. But however great the number, all the forms in each case are referable to a single type, and little skill is required to trace out extreme simplicity amid apparent complexness: for all the various modifications take place according to a simple unvarying law. Thus a multiplicity of crystalline shapes is produced for each species. It is the object of Crystallography to point out the number and relations of these forms, and their internal structure; and thence to explain the manner in which the study of them is available in science. All inorganic compounds-those of art as well as minerals-may take on a crystalline structure; and hence, this subject has the widest bearing, for it is the science of structure in the whole inorganic world. Even the shapeless mass has a regular internal structure in its minute grains, of the same identical character with that of the crystal of like composition and species.

In treating of the subject of Crystallography, we take up, first, the normal forms and structure of simple crystals, discussing (1) the Systems of Crystallization; (2) the Modifications of form in Crystals; (3) Cleavage or internal structure; (4) Distortions and Irregularities; (5) the Modes of Measurement. We next pass to abnormal forms-that is, (6) Twin or Compound Crystals; then (7) to

Mineral Aggregates; and (8) to Pseudomorphous Crystals.

I. SYSTEMS OF CRYSTALLIZATION.

The internal structure of crystals—especially their cleavage led early crystallographers to the recognition of thirteen Primary Forms. There are crystals, as those of galena, whose internal structure is cubical, the mineral affording cubes on dissection; there are others, as fluor spar, that afford the regular octahedron in a similar manner; and there are others, as blende, whose cleavages yield dodecahedrons. In view of this fundamental character, which is one of the most unvarying and profoundly essential of a species. all of these forms, the cube, octahedron and dodecahedron have equal claims to be regarded as primary in the inorganic kingdom. In the same manner we arrive at the other so-called primary forms.

But viewed without reference to structure, several of these forms are essentially identical; and they may all be included under six Systems of Crystallization. In many species no internal structure is apparent; and in many others it is ambiguous, or affords two or more distinct forms at the same time; so that often a primary form cannot be recognized. Whereas the system of crystallization is in each case distinct and certain, being based on simple mathematical relations of the planes. The subject of Crystallography is much simplified by this classification of crystalline forms, and greater precision is given to the description of species.

In treating of the subject of Crystallography, the parts of crys-

tals especially considered, are as follows:-

1. Faces or planes: which are of various forms, triangular, square, rectangular, trapezoidal, polygonal. A series of three or more planes, making with one another parallel intersections, is

called a zone.

2. Edges: formed by the meeting of planes, and either rectangular, obtuse, or acute. Edges are said to be similar, when the planes, by the meeting of which they are formed, are respectively equal, and equally inclined to one another, unlike or dismillar, when not thus equal.

3. Plane angles: the angles of the faces.

4. Interfacial angles: the mutual inclinations of two planes.


5. Solid angles: the meeting of three or more planes, and either trihedral, tetrahedral, polyhedral. Solid angles are said to be similar when included by the same number of plane angles, equal each to each, and equally inclined to one another.

6. Axes: lines connecting points diagonally opposite, as the apices of opposite solid angles, the centers of opposite edges, or of opposite faces. In Crystallography there are three axes employed, (excepting for hexagonal forms), and these axes are either at right angles with one another, producing orthometric forms, or oblique, producing clinometric forms,* and they may be either all equal, or but two equal, or all unequal.

In order to illustrate the relations of the six systems of crystallization, we may briefly mention, by way of introduction, the char-

acters of some of the simpler solids.

1. Prisms having a 4-sided base.—When the base is square and the prism erect, as in f. 2, the form is a Right Square Prism; the four lateral planes are equal rectangles, either longer or shorter than the breadth, according to the height of the prism, and the basal edges are unlike the lateral. If these lateral planes equal the basal, and like them are squares, the form is a cube, (f. 1), bounded by six equal squares. When the base is a rectangle instead of a square, the prism is a Right Rectangular Prism, (f. 3). In each of the forms mentioned the solid angles are eight in




number, and are equal and rectangular. The edges, which are twelve in number, vary with the shape of the base and the height of the prism. In the cube the twelve are equal; in the square prism the eight basal are equal, (four at each base), but they differ from the lateral; in the rectangular prism, two at each base differ in length from the other two, and hence there are three sets of edges, four in each.

Again, the base may be a rhomb, a form in which the sides are equal; an erect prism with such a base is a Right Rhombic Prism, (f. 4). As two of the angles in the base are obtuse, and two acute, the solid angles corresponding differ in like manner, two at each base; and so also the lateral edges are two obtuse and two acute. But the four lateral faces, like the basal edges, will be equal.

If, instead of a rhomb, the base is a rhomboid, a figure in which

† The following figures represent the forms of bases alluded to :-



The square and rhomb have equal sides: the rectangle and rhomboid have only the opposites equal.


^{*} Orthometric, from opder, straight, and perpos, measure; clinometric, from show, to incline, and perpos.

two opposite sides are unequal to the other two, the four lateral faces will correspond to the basal edges, and only the opposites









be equal. This form is the Right Rhomboidal Prism, (similar to f. 4, or like f. 5, if placed on one of its lateral planes).

Again, the base may be a rhomb, but the prism stand oblique on its base. Thus we have, as another form, an Oblique Rhombic Prism, (f. 6, a front view, and 7, a side view). As in the right rhombic prism, the basal edges are equal in length; but from the inclination of the prism, two of these edges at each base are obtuse, and two acute.

Such a prism may be longer or shorter than its breadth. If equal in length to its breadth, and the lateral planes just equal the basal, the form is bounded by six equal planes, like a cube, but

having oblique angles; it is called a Rhombohedron.

Again, an oblique prism may have a rhomboidal instead of a rhombic base, and is then an Oblique Rhomboidal Prism, (f. 8). The edges of each base are of four kinds, for two opposite are longer than the other two, and, of each pair, one is obtuse and the other acute. So also with the solid angles; the four are different at each base. In this solid, therefore, only diagonally opposite edges are similar—that is, are equal in length and in the included angles; and in the same manner, only opposite solid angles are equal, or consist of equal plane angles equally inclined. These particulars are readily understood from a model of the form.

2. Prisms having a six-sided base.—When the prism is a regular hexagon, and erect, it is called the Hexagonal Prism, (f. 9 or 10).

3. Octahedrons.—Octahedrons are 8-faced solids,—as the term implies, derived from examps, 8-times, and idga, face. These faces are triangles, as in f. 11, 12, 13, and the form is like two 4-sided pyramids united base to base. Holding an octahedron with a solid






angle uppermost, the upper and lower solid angles are called its rertical solid angles; the other four, its lateral or basal solid angles; and the horizontal plane in which the apices of the lateral solid angles lie, is the base of the octahedron.

In the Regular Octahedron (f. 11) the base is square, and the eight faces are equal equilateral triangles. The edges are twelve and all equal; the faces incline upon one another at an angle of 109° 28′ 16″, and have the plane angles all 60°. The solid angles are six, and mutually equal. Like the cube the solid is every way symmetrical.

When the base is square, and the vertical height greater or less than it is in the regular octahedron, (that is, the distance between the apices of the vertical solid angles greater or less than that be-



tween the apices of the lateral), the form is a Right Square Octahedron, (f. 12), having the faces isosceles triangles, but not equilateral. The four basal edges are equal and similar, but they differ in length from the eight equal pyramidal edges, and also in the angle of the including planes. The vertical solid angles also differ in the plane angles of which they consist from the lateral or basal.

The base in other octahedrons is rhombic, and in this case the form is called a Right Rhombic Octahedron, (f. 13): the length may be less or greater than the breadth. The basal edges are alike in length and other respects; but as the plane angles of the base are of two kinds, two obtuse and two acute, so the pyramidal edges

differ accordingly.

4. Dodccahedrons.—A dodecahedron is bounded by twelve faces; the name is from δωδεκα, twelve, and εδρα, face. In a common kind of dodecahedron, called the Rhombic Dodccahedron, these faces are equal rhombs, as shown in f. 14. Like the octahedron and cube, this solid is every way symmetrical. The interfacial angles are 120°; and the plane angles of the faces are 109° 28′ 16″ and 70° 31′ 44″. The edges are twenty-four and similar. The solid angles are fourteen in number, and of two kinds; eight obtuse, formed by the meeting of three obtuse plane angles, and six acute, enclosed each by four acute plane angles.

From these descriptions of the thirteen simplest forms among

crystals, we pass to the systems of crystallization.

The Systems of Crystallization are based on certain relations in the axes of these forms. In forms belonging to the same system, the axes are alike in number, and in their mutual intersections and general relations as to length.


1. Monometric or Tesseral System.

In the Monometric system, the three axes are rectangular in their intersections and equal.

The cube, regular octahedron, and rhombic dodecahedron, which are here included, are alike in their perfect symmetry: the height,

length, and breadth are equal, and their axes are equal and rectangular. In the cube (f. 1) these axes connect the centres of opposite faces; in the octahedron, (f. 11), the apices of opposite solid angles; in the dodecahedron, (f. 14), the apices of opposite acute solid angles. The relations of these forms, and the correspondence in their axes, will be understood after a brief notice of the transitions between the forms.

If the eight angles of a cube are sliced off evenly, keeping the planes equally inclined to the enclosing faces, we first obtain the form in f. 15, then that in f. 16, and finally a regular octahedron, and the last disappearing point of each face of the cube is



the apex of each solid angle of the octahedron. Hence, the axes of the former necessarily connect the apices of the solid angles of the latter.

By cutting off as evenly the twelve edges of another cube, the knife being equally inclined to the faces, we have the form in f. 17; then f. 18; and finally, the rhombic dodecahedron, (f. 14), with the axes of the cube connecting the same points in each.

These forms are thus mutually derivable. Moreover, they are often presented by the same mineral species, as is exemplified in galena, pyrites, and the diamond.

The process may be reversed, and the cube made from the octahedron or dodecahedron, as will be readily understood from a comparison, in order, of f. 11, 16, 15, 1, and f. 14, 18, 17, 1.

The octahedron also is changed to a rhombic dodecahedron by removing its twelve edges, (f. 19), and continuing the removal till the original faces are obliterated, thus producing the dodecahedron.

The name Monometric alludes to the equality of the axes, and is from $\mu ovos$, one, and $\mu \epsilon \tau \rho ov$, measure. Tesseral is from the Latin tessera, for cube or dice, and originally from the Greek word for four.*

2. Dimetric System.

In the Dimetric System, the three axes are rectangular in their intersections, and one, called the vertical, differs in length from the two lateral, which are equal.

^{*}Isometric system of Hausmann; Tessular of Mohs and Haidinger; Tesseral of Naumann; Regular of Weiss and G. Rose; Cubic of Dufrenoy and Miller.

The right square prism, (f. 2), and square octahedron, (f. 12), are of this system. The axes of the prism connect the centres of opposite faces, and cross at right angles. The octahedron has the same relation to the prism as the regular octahedron to the cube; the



axes connect the apices of opposite solid angles. A replacement of the angles of the prism, (f. 20), continued, leads to the octahedron. The vertical axis is a varying axis, and may be longer or shorter than the lateral. The name of the system alludes to the two kinds of axes, and is from bis, two-fold, and perpor, measure.*

3. Trimetric System.


In the Trimetric System, the three axes are rectangular in their

intersections, and unequal.

It includes the right rectangular prism, (f. 3), the right rhombic, (f. 4), and the rhombic octahedron, (f. 13). The three axes intersect at right angles, but are *unequal*. In the rectangular prism, the axes connect the centres of opposite faces; in the rhombic prism, the vertical connects the centres of the basal faces, the lateral the centres of opposite lateral edges; in the octahedron, the

axes connect the apices of opposite solid angles.

By the transitions of these solids, it appears that these positions of the axes correspond throughout. If the lateral edges of a rectangular prism are removed parallel to a vertical diagonal plane, the form becomes finally a rhombic prism, as shown in f. 3, 21, 22, 4; and so if the lateral edges of a rhombic prism are in like manner removed, (f. 22, 21, 3), the result is a rectangular prism. This relation of these two forms is also shown by the rhombic prism within, f. 21; the lateral faces of one prism are opposite the lateral edges of the other; and the centre of the face of the rectangular



prism, where the axis terminates, is a point identical with the termination of the corresponding axis in the rhombic prism. It is, hence, apparent that the positions assigned to the axes are not arbitrary, but depend on the actual relations of the forms. Both of these prisms occur often in the same mineral. The rhombic octahedron, (f. 13), moreover, is derived from the rectangular prism, by

^{*} Pyramidal of Mohs; Viergliedrige, or zwei-und-einaxige of Weiss; Tetragonal of Naumann; Monodimetric of Hausmann; Quadratic of von Kobell.

removing the solid angles of the latter, a process begun in f. 23; and it comes from a rhombic prism by removing the basal edges of the prism, as shown in f. 24. The axes are the same points precisely in the three forms. The longer lateral axis is called the macroliagonal, (from maxpos, long), and the other, the brackydiagonal, (from spaces, short). The name Trimetric alludes to the existence of axes of three kinds, (the three being unequal), and is from space three-fold, and masspor.*

4. Monoclinic System.

In the Monoclinic System, the three axes are unequal; one, called the vertical, (a), is inclined to one of the lateral, and at right angles with the other, (c); and the two lateral (b, c) are at right angles with one another.

It includes the right rhomboidal and oblique rhombic prisms. In the oblique rhombic prism, (f. 6), the vertical axis connects the centres of the bases, and the lateral the centres of opposite lateral edges; the lateral, b, c, intersect one another at right angles; the vertical is at right angles with c, but inclined to b. The axis c, which is at right angles with the other two, is called the *orthodiag-mal*, (from optos, straight); and the axis b, which is inclined to the vertical, is the *clinodiagonal*, (from xxxxx to incline).

In the right rhomboidal prism the axes connect the centres of posite faces. But they have the same relations as just explained: they are unequal, and there is one oblique intersection. To under-

stand the relations of these solids, the rhomboidal prism must be placed on a rectangular plane for its base, as in f. 5, and then the vertical axes in the forms correspond, as shown in f. 25, in which both forms are combined. The removal of the lateral edges of one prism produces finally the other prism, the relation being the same as between the right rectangular prism and right rhombic.



The name monoclinic is from moves, one, and xxww, to incline.

5. Triclinic System.‡

In the Triclinic System, the three axes are unequal, and all the intersections (a to b, a to c, and b to c) are oblique.

It includes the oblique rhomboidal prism, (f. 8). The name of the system is from spis, three-times, and xhuw.

[•] Prismatic or Orthotype of Mohs; Ein-und-einaxige of Weiss; Rhombic and Anisometric of Naumann; Binary of Weiss; Trimetric and Orthorhombic of Haus-

[†] Hemi-prismatic and Hemiorthotype of Moha; Zwei-und-eingliederige of Weiss; Momoclimohedral of Naumann; Klinorhombic of Kobell and Hausmann; Augitic of Haidinger; Oblique of Miller.

[†] Tetarto-prismatic of Mohs; Ein-und-eingliederige of Weiss; Triclinohedral of Saumann; Klino-rhomboidal of Kobell; Anorthic of Haidinger and Miller.


The Diclinic system has been indicated by Naumann, as occurring in an artificial salt. It differs from the triclinic in having two of the intersections (as a to b, and b to c) oblique, and one (a to c) rectangular. The prismatic form corresponding would be an oblique rectangular prism, resembling f. 8.

6. The Hexagonal System.*

In this system there are three equal lateral axes, intersecting at angles of 60°, and a vertical axis of varying length at right angles with the lateral.

It includes the hexagonal prism and rhombohedron. In the hexagonal prism the vertical axis connects the centres of the bases. The lateral axes connect the centres of the opposite lateral faces or opposite lateral edges, (f. 9, 10); in each case (as is seen from the character of a regular hexagon) the intersections are at angles of 60°.

In the rhombohedron two of the angles, diagonally opposite, consist of three equal plane angles; the line connecting the apices of these two angles is the vertical axis (a) of the rhombohedron, and the solid is said to be in position when this line is in a vertical position, (f. 26, 27, 28). The other six solid angles are similar, and are called the lateral angles. Placing the rhombohedron




in position, the apices of the six lateral solid angles are at equal distances around the vertical axes. There are also six lateral edges, alike symmetrical in position, around this axis; and there are three terminal edges meeting at each extremity of the vertical axis. Looking down from above on a rhombohedron thus placed, the symmetry of arrangement in the lateral edges is at once perceived; and it is readily understood that lines connecting the centres of opposite lateral edges, will be three in number, like those of the hexagonal prism, and will intersect at 60°. If the lateral edges are replaced by planes parallel to the vertical axis, a regular hexagonal prism, terminated by a three-sided pyramid, is

^{*} Rhombohedral of Moha: Sechagliedridge or drei-und einaxige of Weiss; Hexagonal of Naumann; Monotrinetric of Hausmann.

formed, as shown in f. 29; and if the lateral angles are removed in

an analogous manner, another similar form is produced, (f. 30). The two differ in the form of the planes R, at their extremities. When at the same time the vertical solid angle is removed, the terminal plane of the hexagonal prism is formed, (f. 31).

A hexagonal prism is reduced to a rhombohedron by removing alike



three alternate edges of one base, and three edges of the other base alternate with these, (f. 31), and continuing the removal till the original form is obliterated; or again, by removing in a corresponding manner the alternate solid angles.

ing manner the alternate solid angles.

The hexagonal prism and rhombohedron are consequently closely related forms; both are presented by calc spar and many other species.

Rhombohedrons are obtuse when the angle at the terminal edges is greater than 90°, (f. 26, 27); and acute when it is less, (f. 28). In the former case, the terminal solid angles are made by the meeting of three equal obtuse plane angles, and the lateral by the meeting of one obtuse and two acute plane angles. In acute rhombohedrons the terminal edges are acute; the lateral obtuse; the terminal solid angles are made by the meeting of three equal acute plane angles, and the lateral by the meeting of one acute and two obtuse plane angles. The cube is the intermediate form, having angles of 90°; when placed with an octahedral axis vertical, it has a position corresponding with that of the rhombohedron; the axis a in a rhombohedron of 90° (or cube) = $\sqrt{2}$ =1.224745.

Under these systems of crystallization, and the forms described, the variety of possible forms or dimensions is unlimited. The cube, regular octahedron, and rhombic dodecahedron, are of unvarying relative dimensions. But the right square prism has one axis (the vertical) unequal to the other two, and it may be longer or shorter in any proportions. The right rhombic prisms may be indefinitely various in the angles between the lateral faces; and the oblique prisms may differ in other angles also. Rhombohedrons may occur of every angle; and the hexagonal prism, like the right square prism, may be indefinitely varied in the relation between the vertical axis and the lateral.

By these modes, and also by differences of structure hereafter to be explained, the actual fundamental forms of crystallization become exceedingly numerous, although they belong to a few simple types. However numerous the kinds of substances existing in the inorganic kingdom, there is no limit, owing to this possible variation of dimensions, to the crystallographic distinctions which may exist among them.

In each system there is a prism whose sides are parallel to the

planes in which the axes lie, and whose edges equal the axes. Such is the square prism, f. 2, in the dimetric system; the rectangular prism, f. 3, in the trimetric; f. 5 in the monoclinic, etc.: such prisms are the type-prisms of the several systems. There is also in each system (excluding the monometric) another prism, like the rhombic prism, (f. 4), in the trimetric, or f. 6 in the monoclinic system, which has for its lateral faces vertical planes connecting the extremities of the lateral axes: these are distinguished as the axial or fundamental prisms. The type-prisms are diagonal to these, and are called also the diagonal prisms.*

II. MODIFICATIONS OF CRYSTALS.

In explaining further the laws of crystallography, we might adopt either the mathematical method of referring directly to the axes of the forms, or the less abstract mode of basing the statements of the laws and their explanations on the type-prisms. The latter mode, as it affords the mind distinct solids for contemplation and comparison, is much more simple to the learner, and is here adopted.

Moreover, as the edges of such prisms have the same directions and lengths as the axes, their relations to the derivative forms are more readily apprehended, than those of an assumed octahedron, or any other solid that might be taken as the type of the system.

As the number of forms among the crystals of a single species is often quite large, there is at first much apparent difficulty in tracing their connections, or distinguishing any symmetry of arrangement. The law governing these modifications is, however, of the utmost simplicity. In its application, it is necessary to have fully

The relations of the several forms of crystals are elegantly exhibited by means of models made of glass. They may be made from common window or plate glass, by cutting the glass in the form of the faces of the solid to be made, and then uniting them by means of glue. The author has generally found it convenient to have a small cord between two adjacent pieces of glass, as the adhesion between the glass and the cord, by means of the glue, is much stronger than between two pieces of glass and glue alone. The forms thus far finished, may be rendered much firmer, and, at the same time, the glue and cord concealed, by covering the edges with narrow strips of paper, cut for the purpose; colored glazed paper is preferable, as it is less easily soiled. The primaries, when completed, may be placed within a secondary, which afterwards can be closed up, and the edges papered. In this way, a primary may be enclosed within any of its secondaries so as to exhibit clearly the relations of the two solids. The plane angles of the faces in the monometric solids, are given in the following pages; by laying them off, a plane figure may be drawn, having the form of the desired face; by then placing the plate of glass over the figure, it may be cut with a diamond and a rule. Good glue is necessary for uniting the glass; gum arabic suffices for attaching the slips of paper. The axes may be made of colored thread. Mica may be employed in place of glass.

in mind what is understood by similar edges and angles, as explained on page 23. In the cube the edges are all similar in length, being equal and rectangular. In the right square prism, also, the edges are rectangular, yet the lateral are not equal to the basal in length, and therefore the two are dissimilar. In the right rhombic prism, the lateral edges are of the same length, but two are obtuse and two acute, and hence they are dissimilar; the basal edges are similar to one another, being all rectangular and of equal length, and also being included by planes respectively equal. This similarity of edges and angles is in each case a consequence of the similar axial relations of the planes.

I. LAWS OF SYMMETRY AND RESULTING FORMS.

The modifications of crystals take place according to the following simple laws:

I. All the SIMILAR parts of a crystal may be simultaneously and

imilarly modified.

II. Half the SIMILAR parts of a crystal may be similarly modified

independently of the other half.

The forms resulting according to the first law are termed holohedral forms, from ὁλος, all, ἐδρα, face. All similar edges or similar angles of the type prisms, according to this law, will be alike in the

number and positions of their planes.

The forms proceeding from the second law are termed hemihedral. According to it, half the similar parts are alike in their modifications, and unlike those of the other half; and the parts of either half thus modified are alternate or symmetrically related, so that the result is in general a symmetrical solid. The planes of one half are distinguished by the sign +, and those of the other by the

The examples under the law of hemihedrism may be classed as

follows, referring them to the type prisms of each system.

I. Those forms in which half the similar angles or edges are modified independ-

ently of the other half, producing-

In the MONOMETRIC and DIMETRIC systems, tetrahedral and sphenoidal forms, by the independent replacement of the alternate angles; their opposite faces are not parallel, and they are hence called inclined hemihedrons; as in Boracite, Copper pyrites. The replacement in the dimetric system of two opposite basal edges at one base, and the other two at the opposite base, is of the same kind; as in Edingtonite.

2. In the TRIMETRIC system, monoclinic forms, by the replacement of half the

milar parts of one base and the diagonally opposite of the other, unlike the other

half; as in Datholite, Humite.

2 In the TRIMETRIC and HEXAGONAL systems, hemimorphic forms, by independent replacements at the opposite extremities of the crystal; as in Topaz, Calamine, Tournaline.

4. In the RHOMBOHEDRAL System, by the replacements of the alternate basal edges or ingles of the rhombohedron-forms usually called tetartohedral or quarter forms, on the ground that mathematically the rhombohedron is hemihedral to the hexagonal prism, which is the type of the hexagonal system.

II. Those forms in which all the similar angles or edges are modified, but by half

the full or normal number of planes, producing—
1. In the MONOMETRIC system pyritohedral forms, by a replacement of the edges or angles; as in Pyrites. Such forms have opposite faces parallel, and are often called parallel hemihedrons.

In the DIMETRIC system, pyramidal and scalenoidal forms, by a replacement of the eight solid angles, according to two methods.

3. In the MEXAGONAL SYSTEM, pyramidal and gyroidal forms, by a replacement of the solid angles of the hexagonal prism, or the six lateral angles of the rhombohedron, according to two methods; as in Quartz and Apatite.

Explanations of these kinds of hemihedrism are given in the remarks which follow on the forms of the several systems of crystallization.

1. Monometric System.

1. Holohedral.—In accordance with the first law of symmetry, if a single edge of a cube, octahedron or dodecahedron, be truncated, all will be simultaneously truncated, (f. 17, 19, 43), for all are similar. If on an edge there is one plane inclined unequally to the adjoining faces, there will be two such planes, one inclined towards each face with like angles, as in f. 32; such edges are said to be beveled; moreover all the edges of these solids will be similarly beveled.*

a. Tetrahexahedron +. - A bevelment of the edges of a cube is represented in f. 32, and the result of a continuation of the process in f. 33. This form is bounded by twenty-four triangular faces.




Figure 34 is a similar solid, proceeding from a different angle of bevelment. The above name indicates the general resemblance to the cube or hexahedron, and at the same time expresses the number of its faces. It is derived from verpaxis, four times, if, six, and έδρα, face; the 4×6-faced solid.

The planes i2 in f. 35, which are observed to replace the solid angles of the octahedron inclining at the same time on its edges, when extended to the obliteration of the primary faces, produce the same form as above, (f. 33). The replacement of the six acute solid

+ Called Fluoroid, by Haidinger.


^{*} An edge is beveled, when replaced by two planes, which are respectively inclined at equal angles to the adjacent faces.

angles of the dodecahedron by four planes resting on its faces, (f. 36), if continued, results in the same solid.*

By varying the angle of bevelment of the cube, tetrahexahe-


drons of different angles may be produced.

b. Trisoctahedron.—The angles of the cube are represented as replaced by three planes in f. 37 and 47; in one, they incline on the primary faces; in the other, on the edges of the cube. The completed forms obtained by these replacements are seen in f. 39 and 49. Fig. 38 is an intermediate form, between 37 and 39, having also octahedral planes, (1). The resulting solids, though considerably unlike, have a general resemblance to octahedrons, with a three-sided pyramid substituted for each octahedral face. Like the octahedron, they are formed on the angles of the cube by a re-



placement by three planes instead of one, which accounts for their general resemblance to this solid. The name, trisoctahedron, is derived from \$75\$, three-times, \$\delta \times \otin \text{eight}\$, and \$\delta \theta \times\$, \$face, 3\times \text{-faced}\$ solid. The faces of one of these solids are four-sided, or tetragonal, those of the other, three-sided, or trigonal; they are, therefore, distinguished by the names tetragonal trisoctahedron and trigonal trisoctahedron. The usual name of the former is trapezohedron.

The tetragonal trisoctahedron or trapezohedron (f. 39) may be de-




rived from the octahedron, by replacing its angles by four planes, inclining on its faces, (f. 41 or 42); from the dodecahedron, by a truncation of its twenty-four edges, (f. 43, 44), or by replacing the solid angles, obtuse or acute, by planes inclined on the edges, (f. 45,

The system of notation used in the figures is explained on a following page. It may be observed here that the expressions, 22, 33, and the like, are to be read as if written, 2-2, 3-3; that i stands for infinity; and that there is thus a correspondence between the mathematical symbols for the planes, and the lettering.

† Leucitoid of Haidinger, referring to its being the form of Leucite.

which represents planes of the trapezohedron, 33.) The planes 33, on f. 41 and 45, result in the trapezohedron of f. 40; and the planes



22, of f. 42 and 43, in that of f. 39. The truncation of the shorter edges of tetrahexahedrons produce trapezohedrons, (f. 46, 33 being the trapezohedral planes on the tetrahexahedron $i\frac{3}{2}$); and others proceed from planes on the angles inclined on the same edge.

The trigonal Trisoctahedron (f. 49) has been observed to proceed from a cube by a replacement of the angles by three planes, as in f. 47. It proceeds from an octahedron by beveling its twelve



edges, (f. 48), and from a dodecahedron by a replacement of its eight obtuse solid angles, by three planes inclining on the faces.

c. Hexoctahedron.*—Figure 50 represents a cube, with six planes on each angle, and consequently forty-eight in all. The resulting solid is completed in f. 51. Here, for each face of the octahedron



is substituted a low six-sided pyramid. The name of this solid is derived from the Greek, έξακε, six-times, ἐκτα, eight, and εδρα, face, the 6×8-faced solid.

A replacement of the angles of the octahedron by eight planes, produces a similar solid. A bevelment of the twenty-four edges of

^{*} Adamantoid of Haidinger, alluding to its being a form of the diamond.

the dodecahedron, (f. 52), also necessarily produces a forty-eight-faced solid. Others, differing in their angles, may result from a replacement of the six acute solid angles of the dodecahedron by eight planes, or the eight obtuse by six planes.

2. Hemihedral.

The exemplifications of the law of hemihedrism, are of frequent

Figure 53 is an example of the first kind of hemihedrism, in which half the angles of the cube are modified, while the remaining half are unmodified.

Figure 67 is an instance of the second kind. All the edges are similarly replaced, but by one of the two beveling planes represented in f. 32. The plane i2 is enlarged in f. 68. From this last figure, it will be observed, that the suppressed planes are those which were alternate, and that two planes, i2, incline on each face,


O. The crystals have therefore a symmetrical character.

Another instance is observed in f. 73, in which each angle of the cube is replaced by three out of the six intermediaries in f. 50; that is, by half the number of planes which the first law would

require.

A. Tetrahedral hemihedrons.

a. Tetrahedron or Hemi-octahedron.—If half the angles of a cube are replaced by a single plane, (f. 53, 54), the resulting form is a fetrahedron or hemi-octahedron, (f. 55, 56, one (+) resulting from



the angles modified in f. 53, and the other (—) from a replacement of the other set of angles.) The same form may proceed from an octahedron by an extension of one half of its faces to the obliteration of the other half, (f. 57).

The plane angles of the tetrahedron are 60°; the interfacial

700 310 44'.





Figure 58 represents a combination of the faces of the tetrahedron with the faces i, (or those of a dodecahedron).

b. Hemi-trisoctahedrons.—The planes 22 in f. 37, when occurring on but half the angles, produce the solid in f. 59. The faces are trigonal, and the solid is called a cuproid.



The planes 2 in f. 47, when occurring on but half the angles of the cube and enlarged, form the solid in f. 60; its faces are tetragonal. It is the deltohedron of Haidinger.

Figure 61 represents the cuproid combined with the tetrahedron; f. 62, the same with planes of a tetrahexahedron, i3; f. 63, with planes of a dodecahedron; f. 64, with planes of a deltohedron, similar to f. 60.


c. Inclined or tetrahedral Hemi-hexoctahedron.—A solid of this kind is represented in f. 65. It is formed by a replacement of half the angles of the cube, by six planes, similar to those in f. 50. As the opposite faces are not parallel it is also a least faces.



allel, it is an inclined hemi-hexoctahedron. Figure 66 represents the same, with the faces of the tetrahedron.

B. Pyritohedral hemihedrons.


d. Hemi-tetrahexahedron, or Pentagonal Dodecahedron.—A cube is represented in f. 67, with but one of the two beveling



planes on each edge, given in f. 32. The same planes are enlarged in f. 68; f. 69 represents the completed solid; and f. 70 is the supplementary or — form. The second of the above names is commonly applied to this solid. It is the *pyritoid* of Haidinger.

Figures 71, 72, exhibit the planes on the octahedron, which, ex-

tended, give rise to f. 69.
b. Parallel or Pyritohedral Hemi-hexoctahedron.—When all the solid angles of the cube are replaced by three alternate planes but of six intermediaries, (f. 73), a form like that in f. 74 is pro-



duced. It has parallel opposite faces. It is the diploid of Haidinger. Figure 75 shows the same planes on an octahedron.

2. Dimetric System.


The modifications of the basal and lateral edges of a square prism, take place independently, owing to their dissimilarity. The lateral edges are included by equal planes, and, therefore, may be truncated or beveled, (f. 76, 78). The basal edges are similarly replaced; but being the intersections of unequal planes, they are never truncated or beveled. A plane on these edges, therefore, inclines unequally on the adjacent faces, (f. 80, 83).

The similar intermediary planes on each angle can be but two

in number, (f. 88).


The production of a square octahedron from the replacement of the angles of the square prism, is explained on page 28, (f. 20, 12). By giving different inclinations to the plane on the angles, other octahedrons are obtained of longer or shorter vertical axes.

A truncation of the lateral edges of the typical square prism, gives rise to another square prism, (f. 77), the axial prism. Bevelment of the same lateral edges, (f. 78), affords eight-sided




prisms, (f. 79), of different angles, according to the angle of bevelment.

The fundamental octahedron (f. 12) proceeds from the axial prism, by a replacement of the basal edges, (f. 80, 81); the basal edges of this square prism corresponding to the angles of the other: (compare f. 80 and 20). Another series of octahedrons is formed on the angles of the axial square prism, (f. 82), or the basal edges of the diagonal square prism, f. 83; f. 84 represents the octahedron 1i of f. 83, and also within this, that of 1i. The octa-



hedrons of one series replace the pyramidal edges of the other, (f. 85), or are situated on the angles basal or vertical, and incline on these edges, (f. 86), 1i or 2i being octahedral planes of one



series, and 1 of the other. Figure 87 represents the octahedron 1, combined with the lateral faces of the diagonal or type prism.

Two planes on each angle of a square prism, (as in f. 88), give rise to a double eight-sided pyramid, (f. 89), which may be of various proportions, according to the inclination. The same planes on the octahedron 1, either bevel the edges, (f. 90), or replace the angles



by two planes corresponding to each terminal edge. In this solid the terminal edges are of two kinds, one, the axial, (X), terminating in the poles of the lateral axes; the other, the diagonal, (Y), inter-

mediate in position.

The hemihedral forms are as follows:—1. The sphenoidal, corresponding to the tetrahedral of the monometric system, the alternate angles being replaced alike. Half the planes 1, of f. 20, produce the scalene pyramid represented in f. 91; and the other half, that of f. 92; and two planes on half of the angles, afford the form in f. 93. Figure 94 represents the sphenoid with the vertical planes of the diagonal square prism; and f. 95 shows the combination of

f. 93, with the octahedron 1i. 2. Pyramidal, produced by the occurrence of one of the two planes on each angle, (see f. 88), the










occurring plane at each extremity, about the edge of the prism, being on the same side of the edge, or in the same vertical line—as in f. 96. The resultant form is a square octahedron; occurs in Tungsten. Another kind of hemihedrism may occur, which is like the last, except that the plane at each extremity, about each









edge of the prism, is on different sides of the edge, as in f. 97; the resultant form is represented in f. 98. In 96, the plane is the left of one base, and (the prism being inverted) the right of the other, (or the reverse); in f. 97, the plane is the right of each base, (or the left).

3. Trimetric System.


The edges of the right rectangular prism are of three kinds, (being different in length), and those of each kind are, according to the law mentioned, independently modified, (f. 99, 103, 105). Moreover, none of them can be truncated or beveled, in consequence of the inequality of their including planes.

Planes on the angles incline unequally on the three adjacent, unequal planes. The angles are similar, and therefore will be

modified simultaneously, (f. 23).

The lateral edges of the right rhombic prism admit of truncation and bevelment, because of the equality of the lateral planes. The obtuse, however, are modified independently of the acute, (f. 101, 102). The obtuse solid angles, and the acute, are also independent in their modifications, (f. 107, 108). The replacements of the basal edges are similar and simultaneous, (f. 24).


On page 28 it is shown that a replacement of the lateral edges of the rectangular prism, (f. 21, 22), produces a right rhombic prism. By varying the inclination of the replacing planes, different rhombic prism are obtained. In f. 99, $i\bar{z}$, I, and $i\bar{z}$, are planes of three such prisms, I, being the prism represented in f. 4, and in the interior of f. 100, having the same axes as the rectangular prism; $i\bar{z}$ corresponding to the prism $i\bar{z}$ $i\bar{z}$, in f. 100,—(that is,



having the same angle between the planes, as $i\bar{2}$ $i\bar{2}$, in f. 99); and $i\bar{2}$ corresponding to the prism $i\bar{2}$ $i\bar{2}$, in f. 100. Figure 101, represents the rhombic prism I, with the same planes $i\bar{2}$, and f. 102,


with the planes vz.

A replacement of the basal edges produces other rhombic, prisms, which are horizontal in position, and are called *domes*, (from $\delta \omega \mu \eta$, or *domus*, house, or placed like the roof of a house). Figure 104 represents the dome corresponding to the planes 1i in f. 103; it is parallel to the *longer* lateral axis, and is called a macrodome, (from $\mu \alpha x \rho s c_0$, large and dome). Figure 105 contains planes (1i, 2i) of two domes parallel to the shorter lateral axis,




which are called brachydomes, (from Epazus, short and dome). These brachydomes are presented completed in f. 106, the outer being 2i, and the inner 1i. The former has the vertical axis twice that of the latter. In f. 107, the planes 1i and 1i, (f. 103, 105), are represented on a rhombic prism, the angles of which they replace.

The production of a rhombic octahedron, by replacing the angles



of a rectangular prism, or basal edges of a rhombic, is mentioned on page 28; (compare f. 23, 24, with 13). Other planes on the

angles produce other octahedrons. The planes 12, in f. 108, correspond to the octahedron of f. 109—(that is, have the same mutual inclinations as the faces of the latter); the longer lateral axis is



twice that of f. 13, or that of the dotted figure in 109. The planes \hat{z}_i in f. 110, in the same manner correspond to the octahedron in f. 111, in which, both the vertical axis and one of the lateral are twice the same in f. 13. The planes $2\bar{i}$, in f. 110, belong to a

macrodome different from that in f. 103, 104.


Hemihedrism, in the trimetric system, produces two kinds of forms. 1. Monoclinic, when the lower extremity of a crystal in front, and the diagonally?opposite, differ in their modifications from the upper extremity in front; the forms resemble those of the monoclinic system, but differ in having the angle between the vertical and lateral axes 90°. An example is shown under datholite and humite. 2. Hemimorphic, when all the similar parts of one base are modified alike, but unlike the corresponding parts of the other, as in calamine and topaz, (q. v.)

In this system, the angle between O and the vertical prismatic

planes, is 90°, and ii : ii = 90°.

4. Monoclinic System.


In the Monoclinic System the obliquity of the crystals (or of the vertical axis towards the clinodiagonal) makes the upper and lower parts in front different, one obtuse and the other acute, and they are independently modified, as in f. 112, 113. But the angle



of the vertical axis with the orthodiagonal being right, and therefore alike on opposite sides, the planes on the four lateral angles

of the oblique rhombic prism are alike, as in f. 114. The four planes 1i, in the last mentioned figure, make a clinodiagonal prism, or *clinodome*; the plane 1i, in f. 112, is a hemi-orthodome; and the same with -1i, f. 113.

The lateral edges are replaced as in the trimetric system. The relation of the two forms, in f. 5 and 6, is shown in f. 25. Octahedrons may result in this system as in the trimetric; but they consist of two sets of planes, or hemi-pyramids, as shown in f. 115, in which 1, 1, are on the obtuse angles of the outer prism, or correspond to the obtuse basal edges of the inner, while -1 are on the acute angles or edges. The completed oblique octahedron corresponds to the planes 1, 1, -1, as in f. 115, 116. The vertical axis a is oblique to b, the clinodiagonal, but at right angles



In this system, the angle between the plane O and ii, (f. 5), is 90° ; O on other prismatic planes is an oblique angle; ii on the faces of different clinodomes is


on the faces of different clinodomes is oblique: ii on ii, and all hemi-orthodomes, $=90^{\circ}$. The particular plane to be taken as O, or as I, may be a question for particular species; the O will always be one of the planes in the clinodiagonal section; while any prismatic planes not parallel to either diagonal, or any octahedral planes, may be taken as I. When there is no very distinct cleavage to guide to a decision, (and even when such cleavage exists,) it is common, though not always best, to assume those planes as the fundamental form, which will render the calculations and symbols of the planes most simple.

5. Triclinic System.

As only diagonally opposite edges or angles (f. 8) are similar in the Triclinic System, there can be in a triclinic crystal but two planes of a kind, as in f. 117, 118. The inclination of O on I,








differs from O on I'. The prism formed by planes on the prismatic edges of f. 8, parallel to the diagonals, has the same relation to the form in f. 8, as that of f. 5 to f. 6, of the monoclinic system; but unlike the prisms of the monoclinic system, O does not make

a right angle with any of the lateral planes; there are no right angles in triclinic forms. The replacement of the basal edges of the prism, in f. 8, by homologous planes, may produce an octahedron; but it will be included by four sets of planes, two of a kind, represented in f. 119. These planes occur independently on crystals, and, owing to their independence, actual octahedrons are not met with in nature.

6. Hexagonal System.

1. Holohedral.

a. In the hexagonal prism, (f. 10), the basal edges are alike and have similar modifications, and the same is true of the lateral edges, and the solid angles. When a similar plane occurs on each basal edge, (f. 120), or each basal angle, (f. 121), the resulting solid is




a double six-sided pyramid, (f. 122), called an isosceles dodecahedron, or a dihecagonal pyramid; it is the Quartzoid of Haidinger. Figure 121 represents planes of three different pyramids on the angles, viz., 12, 42, 22, which differ in the length of the vertical axis.

Each solid angle of the hexagonal prism, may be replaced by 123

two similar planes, (as in f. 123), and the extension of such planes produces a double twelve-sided yramid, (f. 124)—the berylloid. The berylloid has two kinds of terminal edges, one, X, the axinl; the other, Y, the diagonal.

The truncation of the lateral edges of the hexagonal prism




to the first; and bevelment leads to different twelve-sided prisms. In the rhombohedron, the vertical solid angles, as they are formed by the meeting of three equal planes and equal plane angles, may be truncated, or replaced by three or six similar planes. The edges, for a similar reason, may be either truncated or beveled. The terminal edges, however, are replaced independently of the lateral.

The lateral angles, six in number, are replaced simultaneously. Two like intermediary planes may occur on each.

The derivation of two six-sided prisms from a rhombohedron, has been explained on page 30; one, by a truncation of the six lateral edges, (f. 29); the other, by a replacement of the six lateral angles, by planes parallel to the vertical axis, (f. 30). The remaining parts of the primary faces on the first of the above prisms, are rhombic; those on the second, are pentagonal.

A truncation of the terminal edges of the rhombohedron, is observed in f. 125. Since these edges are six in number, three at one end of the crystal, alternating with three at the other, the solid formed by the extension of these planes, must be an oblique solid, contained under six equal faces: or, in a word, a rhombohedron. Moreover, because the lateral angles are six, and three alternate are nearer the lower extremity of the axis, and the remaining three near the upper extremity, the planes on these angles, if not parallel to the vertical axis, incline alternately above and below, (f. 126); and, therefore, by their extension, will give rise to rhombohedrons. These rhombohedrons will differ in the lengths of their vertical axes, as these planes vary their inclination. The nearer they approach to parallelism to the vertical axis, the longer the axis of the rhombohedron; and the six-sided prism formed on these angles may be considered a rhombohedron, with an infinite axis. Moreover, other rhombohedrons may be formed by replacing the terminal angles by three planes inclined on the faces or terminal




edges; and as the planes of such secondary rhombohedrons approach horizontality, they approximate to the terminal or trunca-

ting plane, O, which plane may be viewed as a rhombohedron with the axis=0.

In f. 127, the lateral edges of a rhombohedron are beveled; an extension of these beveling planes produces the solid represented in the dotted lines of this figure, which is called a scalenohedron. It is a solid included by twelve scalene faces. The twelve edges are of three kinds: 1, the longer terminal, Y; 2, the shorter terminal, X; 3, the basal, Z. By other beveling planes, (f. 128), other scalenohedrons are formed; and as the vertical axis increases, they pass into the diagonal hexagonal prism, i2, (f. 9). This prism may hence be considered a scalenohedron with an infinite axis.

Bevelments of the terminal edges (f. 129) give rise to other similar solids; and replacements of the lateral angles by two planes, (f. 130), afford still other scalenohedrons. Again, the replacement of the terminal edges of scalenohedrons, or of the



angles, by planes inclined on these edges, gives rise to different rhombohedrons. In f. 131 there are planes of the rhombohedron, 4R; in f. 132, planes of -5R; in f. 133, planes of $\frac{5}{2}R$; in f. 134, planes of -2R. A bevelment of the terminal edges, or a replacement of the angles by *two* planes inclined against each terminal edge, produces other scalenohedrons, (f. 133, 134).

When a rhombohedron has its lateral angles replaced, as in f. 126, and the plane is inclined to the vertical axis at the same angle as R, a dihexagonal pyramid or quartzoid results. Such is the origin of the pyramids of crystals of quartz.

In crystallographic calculations, the rhombohedron, scalenohedron, and related forms, are regarded as hemihedral modifications of the hexagonal prism, and we proceed now to speak of them in this relation.

2. Hemihedral.

As the rhombohedron results from a hexagonal prism by a replacement of the *alternate* basal edges (f. 31) or angles, it is in this relation hemihedral; and since either set of alternate edges of the prism may give rise to a series of rhombohedrons, it is usual


to distinguish one set by the sign +, and the other by the sign -. In the double pyramid of quartz, as just explained, we have a form in which both of these rhombohedrons, +R and -R, are

combined, producing a symmetrical solid.

The scalenohedrons have the same relation. To comprehend this form and other hemihedrons more fully, the holohedral form, in f. 123, may be again referred to. It is a hexagonal prism with two planes on the angles at either base, inclined on each face, one the right, (r), at the right upper angle of each face, the other the left, (l). In hemihedral forms, half of these planes are suppressed.

1. If, as in f. 135, the suppressed planes are those below, for the left face I, (f. 123), those above, for the middle I, those below, for the right, and so on, alternating around, the resulting forms are scalenohedrons; for each occurring pair, l, r, corresponds, as is seen, to a face (R) of the rhombohedron. This kind of hemihedrism is called the *rhombohedral*, by Naumann.

If the faces that are suppressed in f. 135, should be the occurring



faces, and the others were suppressed, the same solid would result in an inverse position. If the rhombohedral plane R, in f. 135, is taken as +R, then the scalenohedron, in the same figure, will be +, and the inverse one, -; for, in f. 135, the planes l, R, r, belong to the same axial sector; while R would not be in the same sector with the planes of the inverse scalenohedron. Where various scalenohedral planes occur together, there may be among them both + and -, with + or - rhombohedral planes.

2. In another kind of hemihedron, the occurring planes of the two, r, l, in f. 123, may be the r on each angle at one base, and the l on each at the other base, as in f. 136. This variety is exemplified in apatite. It is called the *pyramidal* hemihedrism by

Naumann, the resulting solid being a six-sided pyramid.

3. In another kind of hemihedron, the occurring planes may be the r of both bases, as in f. 137, or the l of both bases. This occurs in quartz, (see under that species), and is called the trape-cohedral by Naumann, the resulting solid, made up of such planes extended, being a trapezohedral double pyramid. It is also called gyroidal hemihedrism, the planes gyrating to the right or left at each base.

A triangular prism, a hemihedral form of the hexagonal prism, and also hemihedrons of twelve-sided prisms, are of frequent occurrence in Tourmaline.

3. Tetartohedral Forms.

Tetartohedral forms are true hemihedral, if the rhombohedron under which they occur, is taken as the type of the crystal; but referred to the hexagonal system, as is conveniently done in calculations, they are tetartohedral forms, or contain only one-fourth the

number of planes occurring under complete symmetry.

1. In one kind of tetartohedrism, the occurring planes are the alternate of those on the angles in f. 136—that is, only the alternate r's of one base, and the alternate l's, at the other. A form of this kind consists of six planes, and being oblique, is a kind of irregular mombohedron. It is found in Titanic Iron, and is called rhombohedral tetartohedrism.

2. In a second kind—the trapezohedral tetartohedrism of Naumann, (also gyroidal),—the occurring planes are the alternate r's at both bases, (f. 137), (or the alternate l's). It is observed in

Quartz. (See under that species).

3. There is also a third kind, in which the opposite extremities of a rhombohedrally modified prism are unlike in their modifications, as seen in Tourmaline. It is an example of hemimorphic tetartohedrism.


IL LAW OF NUMERICAL PROPORTION, IN THE MODIFICATIONS OF CRYSTALS.

This law gives a mathematical basis to the science, adding to symmetry of arrangement a numerical relation in the position of the planes. It is as follows:

The position of planes is related in some simple ratio to the relative lengths of the axes of a crystal.

For example.—In a cube the axes are equal. A plane on an edge, if extended to meet the axes, would cut two of these axes at some distance from the centre of the crystal. Now this distance for these axes will either be as 1:1, (i, f. 17), that is, a ratio of equality—a truncating plane; or a ratio of 1:2, (like i2, f. 32, 33), 1:3, (f. 34), 2:3, or some other simple ratio. There is no haphazard scattering of faces, but a complete subserviency to this simple law. If the axes are unequal, as in a trimetric form, then the ratio is of the same character, except that the relative lengths of the axes come into the consideration. Thus if a, b, are the axes, the ratios will be 1a:1b, $(1\bar{i}, f. 103, \text{ or } 1i, f. 112)$, or 1a:2b, 1a:3b, and so on.

To explain more precisely, let AA, BB, CC, f. 138, be three axes crossing at right angles, as in the monometric, dimetric, and trimetric systems; a, b, c, may stand for the halves of these axes, or for AS, BS, CS, respectively. All planes of a crystal meet (or will meet if extended) one, two, or three of these axes. A plane may pass through A, and be parallel to BB, CC, or through B, and be parallel to AA, CC; or



through C, and be parallel to AA, BB. Such planes meet one axis, at a distance 1, and the others only at an infinite distance, which is equivalent to being parallel to them. Hence the expression $1:\infty:\infty$ describes, in a general manner, the position of such planes; and it becomes more special by adding the letters marking the particular axes that are meant in each case, as $1a:\infty b:\infty c$, when parallel to b and c, $\infty a:\infty b:1c$, when parallel to a and b, etc. The faces of a cube, square prism, and rectangular prism, are of this kind. See also a.

Again, a plane may pass through the points B and C, and be parallel to AA', or through A and C, and be parallel to BB', or through A and B, and be parallel to CC'. Such planes meet two axes at a distance 1, and are parallel to the third; and hence $1:1:\infty$ is a general expression for them, (that is, for the first case, when the plane is parallel to AA, $1b:1c:\infty a$, or what is the same, $\infty a:1b:1c$; and so for the others). Or the plane which is parallel to AA, and cuts BB' and CC', may meet BB' at a distance from the centre, equal to 2b (=2BS) while it meets CC at the distance 1c, (=1CS). Then the expression $\infty a:2b:1c$ indicates the plane. If the ratio of b:c equals 3:1 instead of 2:1, the expression becomes $\infty a:3b:1c$. In the same manner, $3a:\infty b:1c$, would imply that the plane is parallel to BB', and meets AA at a distance 3a, while CC' is met at a distance 1c.

Again, if the plane passes through the points A, B, C, it has the parameters 1a:1b:1c; or if a, b, c, are equal, it becomes 1:1:1. But if A be removed to twice its distance from S, then the ratio would be 2a:1b:1c; or if B be removed to twice its distance from S, the ratio would be 1a:2b:1c; or if both A and C be so removed, it would be 2a:1b:2c. Thus, in all cases, whatever the position of the plane, the ratio admits of being expressed in simple numbers. The planes may not actually meet the axes, but would meet them in each case, (when not parallel to them), if the plane and the axes were extended; and thus meeting them, the ratios of the parameters would be as indicated; for these ratios, for a plane of given inclination, are the same, whether the intersections are nearer to, or farther from S, on the principle that a line parallel to the base of a triangle cuts the sides proportionally.

ma: nb: rc is a general expression for all planes, in which m, n,

r, may have any value, from unit to infinity.

Figure 106 shows the relations to the axes of the planes 17 and 27 of f. 105. Figure 109 is made up of the planes of f. 108, and

has the axes 1a:1b:2c, the octahedron within being the fundamental octahedron, with the ratio 1a:1b:1c. Figure 111 corresponds to the planes $2\bar{z}$ of f. 110, and has the axes 2a:1b:2c. In f. 100, the inner prism has the ratio $\infty a:1b:1c$; $i_2 i_{\bar{z}}$ is the form i_2 of f. 101, having the ratio $\infty a:1b:2c$; and $i_2 i_{\bar{z}}$ is the form i_2 of f. 102, having the ratio $\infty a:2b:1c$, as the drawing of the axes shows.

The annexed figure (f. 139) will further aid in elucidating

the principle above stated. It represents a rhorfbic prism with three planes on its basal edges; and for further illustration there are four planes on the angle to the right, besides two vertical planes, (the corresponding planes on the left side are not indicated). Within the rhombic prism there are the three axes, aa', bb', cc', crossing at S, the halves of which axes we call a, b, c, as above; b is the shorter lateral axis, and c the longer.

1. It is obvious that the vertical planes of the rhombic prism meet two of the lateral axes at the distance 1b, 1c, and are parallel to the vertical axis. Hence the expression for them

is $\infty a:1b:1c$.


2. The terminal plane is parallel to the lateral axes, and meets only the

vertical; or what is equivalent, it corresponds in position to the plane of the lateral axes, in which the vertical axis is zero. Hence it is designated $1a: \infty b: \infty c$; or 0a: 1b: 1c.

3. The plane \tilde{u} is parallel to a, the vertical axis, and also to b, the shorter lateral axis, and meets the axis c. Hence the expression $\infty a : \infty b : 1c$. The parallelism to bb' is apparent in the fact that the upper and lower edges of the plane are parallel to this same axis bb'.

4. Consider next, $\frac{1}{2}$, 1, 2, which are planes of as many octahedrons. These planes are inclined towards the three axes; and being on the edges of the rhombic prism, they have the same ratio for the lateral axes as that prism, that is, 1b:1c, and they differ in the length of the vertical axis, towards which they vary in inclination.

From b, c (which are connected by a dotted line) lines are drawn to points in the vertical axis; viz, to $\frac{1}{2}a$, a, 2a; $\frac{1}{2}a$ bisects the axis a; a is the extremity of the axis; and 2a is at double the distance of a from S. Hence of these triangular planes, the plane $\frac{1}{2}abc=\frac{1}{2}a:1b:1c$; abc=a:b:c; 2abc=2a:b:c. These three planes correspond to the three planes on the left basal edge of the prism, being parallel to them. So, also, the three triangular planes having bc' at base,



and $\frac{1}{2}a$, a, 2a, respectively as the apices, correspond to the three planes on the other basal edge. Hence the expressions for the planes are,

For 1, 1a: 1b: 1c. 1, 1a: 1b: 1c. 2, 2a: 1b: 1c.

All those forms which have for the lateral axes the ratio of unity, are described as belonging to the fundamental series.

For $\frac{1}{1}$, $\frac{1}{1}a$: ∞b : 1c. $\frac{1}{1}$, $\frac{1}{1}a$: ∞b : 1c. $\frac{2}{1}$, $\frac{2}{1}a$: ∞b : 1c.

The fact of parallelism to these particular planes, in an actual crystal, would be shown, in this as in other cases, by a measurement of the inclinations of these faces. Calculation, the axes being given, would afford the inclination to the plane of the lateral axes of the planes nnoo, nnpp, etc., and the correspondence with the observed inclinations would prove the identity; or from the observed inclination, the position of the plane nnoo could be determined, or what is equivalent, the length of the vertical axis.


But this parallelism of the planes, in the figure, is obvious, from the parallelism of certain lines. The planes nnpp and abc', which have the same vertical axis, meet in the line ac', and this line is parallel to np. Moreover, a plane abc' has the same intersection with nnpp. Consequently, the mutual inclinations of the planes abc', nnpp, abc', will be parallel to one another. Now abc' is the plane 1; and abc' another 1 on the back side of the crystal, meeting 1i. And if 1i corresponds to nnpp, it must make parallel intersections with the two planes 1, which, in fact, it does. There is the same evidence that 1i and 2i, are planes corresponding to nnoo and nnqq, as above represented.

6. There remain the planes 25 and 65. We extend the axis bb' to twice the distance bS, (to 2b); then connect 2b with c', and both with 2a. The plane thus outlined has the vertical axis 2a, one lateral 2b, the other 1c; and consequently is expressed by 2a:2b:1c; and this is the plane 25.

The triangular plane 2a 2b c' intersects nnqq, in the line c' 2a; at so also does the plane 2a b c'. The same course of reasoning s the above, shows that the intersections of nnqq or 2i with 2a b c' c' 2, must be parallel. Consequently, if 2i corresponds to 2a bc', it must make parallel intersections with 2 and 2i, which these. The same parallelism would happen, whatever the length i the axis b, and the above reasoning only determines the vertical sia. That the lateral axis b is, in this case, 2b, is shown by a correspondence between calculation and measurement.

The plane 12, is parallel to the vertical axis, but not to either of the lateral axes. By doubling bS, extending it to 2b, and connecting 5 with c', we have the position of the plane, it corresponding to 2s: 3b: 1c. The intersection of the plane 2a 2b c' with a vertical sine passing through 2b c', would be parallel to 2b c', and therefore informatal, (in a right prism). Hence the intersection of 2½ with 1, if 2½ corresponds to 2a 2b c', should be horizontal or parallel at 3c'; and as it is thus parallel and horizontal, 2b is correct for that plane.

LOWIS.—a. Oblique or Transverse Zones.—In f. 140, AA'(a), BB(b), CC'(c), are the three axes of a crystal. By connecting the extremities of these axes, the plane ABC is formed, which presponds to a ratio of equality for the axes—that is, 1a:1b:1c. Nake CD, DE, each equal OC; and connect A and B with



D and E. Then the planes ABC, ABD, ABE, are alike in the ratio of the axes a and b, but differ in the axis c, they cor-

responding respectively to 1a:1b:1c, 1a:1b:2c, 1a:1b:3c, CD being equal to 2OC, and OE to 3OC. So there may be any number of planes, in which the axis c shall increase until it reaches infinity; and, in this last case, the plane will be parallel to the axis c, as ABUV. Referring all these planes to the octahedron of the figure, the fundamental octahedron, they replace the edge AB at different inclinations, and all are alike in having the intersection with the face ABC, parallel to the edge AB, or to the edge of the vertical section through the axis b. Hence flows the following law:

following law:

I. All planes, whose intersections with an octahedral plane are parallel to the edge AB, in that octahedron, have the same ratio of a to b; or if parallel to the edge AC, they have the same ratio of

a to c.

If the octahedron, instead of being the fundamental octahedron, is that expressed by the ratio 2a:1b:1c, which differs from the fundamental octahedron in having the vertical axis twice as long, the ratio still holds; and the planes, if making parallel intersections to AB, would be 2a:1b:1c, 2a:1b:2c, 2a:1b:3c, and so on to $2a:1b:\infty c$, the last, the truncating plane, or that parallel to axis c. Or if they make parallel intersections to AC, so that the ratio a to c is constant, they may be 2a:1b:1c, 2a:2b:1c, 2a:3b:1c, and so on to $2a:\infty b:1c$, in which the last is parallel to the axis b.

Making OF half of OC, and connecting A and B with F, we have the plane AFB corresponding to $1a:1b:\frac{1}{2}c$; or making OI a quarter of OC, we have AIB, corresponding to $1a:1b:\frac{1}{2}c$; and so till c becomes zero, when the plane is identical with the axial plane ABA'B', or is a plane parallel to it, and its ratio is 1a:1b:0c. This last plane is a lateral plane of a rectangular or square prism.

There is thus a zone of planes indicated, lying between 1a:1b:

0c, on one side, and 1a:1b:0c, on the other—that is, in the trimetric system for example, between a vertical plane parallel to axis b and its opposite. In like manner, there is another zone parallel to the edge AC, between 1a: 0b:1c, on one side, and 1a:0b:1c, on the opposite, or between the other vertical plane of a rectangular prism and its opposite. And whatever the length of the axes of the octahedron, each edge may have its corresponding zone of planes. In the annexed figure, (f. 141), one of the zones of planes is represented: it lies between ii, (the smaller lateral plane of a rectangular prism), and its opposite; it is the same

illustrated in the preceding figure, (f. 140), $1\bar{s}$ being plane ABE; $1\bar{z}$, ABD; 1, plane ABC; 22, plane ABF; 44, plane 17 is the horizontal prism at the middle of the zone.

The fraction in $1a:1b:\frac{1}{4}c$, is avoided by doubling all the terms, making 2a:2b:1c, in which there is the same ratio for the axes. The plane GCH, (f. 140), is drawn to correspond to the expresson 2a : 2b : 1c, OG being equal to 2a, (or 2OA), and OH to 2b, for 20B); and it is seen that GCH and AFB are parallel planes in the figure, and therefore identical. So, in place of 1a: 1b: 1c, we may write 4a:4b:1c, this being equivalent to $1a:1b:\frac{1}{4}c$, the difference being that, while b is the unit axis in one, c is so in the other, and this difference is to be carefully observed. These planes on the octahedron, in f. 140, replace the angle C, and have the intersection with ACB parallel to AB. Hence the above law extends not only to planes about the edge AB, with parallel intersections, but to all planes making intersections parallel to the edge; and the same as to edge AC. The expression 1a:1b:0c, is equivalent to $\infty a:\infty b:1c$, (a re-

salt of dividing each term by 0); and this last is the one usually

employed for such vertical planes.

The zone (B) making intersections parallel to the edge AB, or the brachydiagonal section, in the octahedron 1a:1b:1c, will hence be, beginning with 1i and passing to ii, (f. 141), $1:1:\infty$. $1:1:3...1:1:2..1:1:1..1:1:\frac{1}{4}...1:1:\frac{1}{4}...1:1:0;$ or the equivalent, $1:1:\infty...1:1:3...1:1:2...1:1:1...$ $2:2:1..4:4:1..\infty:\infty:1$. The latter is the form adopted.

In the same manner, there may be a zone for any octahedron, ma: 1b: 1c; and the series (the second of the above) becomes, under this general expression, $m:1:\infty\ldots m:1:3\ldots m:1:2\ldots$ $m: 1:1 \dots 2m: 2:1 \dots 4m: 4:1 \dots \infty: \infty: 1$. Any other

values may be substituted for 3, 2, 4.

A corresponding zone, (C), making parallel intersections with AC, will be $1:\infty:1...1:3:1...1:2:1...1:1:1...2:1:2$ $\cdots 4:1:4\cdots \infty:1:\infty;$ or for any octahedron ma:1b:1c, it becomes $m: \infty: 1 \dots m: 3: 1 \dots m: 2: 1 \dots m: 1: 1 \dots 2m: 1: 2 \dots 4m: 1: 4 \dots \infty: 1: \infty$. When m becomes infinite, the two zones form a single series of vertical prisms, as for example, $z:1:\infty..\infty:1:3..\infty:1:2..\infty:1:1..\infty:2:1..\infty:4:1$ $...\infty:\infty:1.$ When axis b is infinite, the zone B becomes a vertical series of horizontal planes parallel to axis b; and when axis cis infinite, the zone C becomes a similar vertical series, parallel to The basal plane falls into each of these series. These vertical zones are two out of the many series that may exist in

b. Vertical Zones.—The planes $\frac{1}{2}abc$ and abc, in f. 139, are parts of a vertical series having intersections parallel to bc, and varying in the vertical axis. This series, as the vertical axis diminishes, finally terminates in the top plane 0a:1b:1c; and as it increases, ends in the vertical plane $\infty a:1b:1c$, or the vertical plane i. This is a zone of planes, having the general expression ma:1b:1c; it

includes the terminal plane, and the faces 1, 1, 2, i.

The planes 23 and 33 are in another zone. The fact of a horizontal intersection between them is proved as already explained, and it follows that all planes having, in like manner, the ratio for the lateral axes 2b:1c, will have herizontal intersections. This series is the zone m:2:1, (or ma:2b:1c.)

It follows also, that whatever the ratio of b to c, all planes of like ratio will have horizontal intersections, (the planes of the axes b: c being assumed to be horizontal), and consequently there will be

as many vertical zones as there may be values of b: c.

Again, the planes 111, 21, 21, 11 (f. 139) are in a similar zone parallel to axis b, in which, therefore, $b=\infty$; the general expression is $m:\infty:1$, (or $ma:\infty b:1o$). As the vertical axis increases, m increases, and when $m=\infty$, the plane is vertical. nnoo, nnpp, nngg, nnyy, illustrates the series; the last corresponds to the plane 3. A similar series, on the other edge and solid angle of the rhombic prism, would have the general expression $m:1:\infty$, (or $ma:1b:\infty c$.)

Hence, the second law:-

II. Planes which have their mutual intersections horizontal, (the plane of the lateral axes being horizontal), are identical in the

ratio between their lateral axes; and the converse.

A tabular view of these vertical zones is here presented. The 0 stands for the basal plane, in which each zone terminates above. The first column corresponds to a vertical zone parallel to axis c; the second, to other zones with 1b:nc as the ratio of the lateral axes, in which n has a different value for each possible zone; the third, for the fundamental series, in which the ratio of the lateral axes is 1b:1c; the fourth, for other zones having the ratio of the lateral axes nb:1c; the fifth, for the zone parallel to axis b. We have used l for any fraction less than a unit, m and n for numbers greater than a unit.

0				
7:1:40	$\overline{l}:\overline{1:n}$	l:1:1	l:n:1	$l:\infty:1$
1:1:2	1:1:n	1:1:1	1: n: 1	1: : 1
$m:1:\infty$	m:1:n	m:1:1	m:n:1	$m:\infty:1$
			$\infty:n:1$	

Expressions for planes in the different Crystallographic Systems.—The several systems of crystallization, since they differ in their axes, require each some peculiarity in the expressions used for their planes.

In the *Monometric* system, as the axes are all equal, there is correctly no vertical axis, and a=b=c. Either of the faces of a

whe is hence expressed by $\infty:1:\infty$; the truncation of an edge (see of a dodecahedron) by $\infty:1:1$; the truncation of an angle (ace of an octahedron) by 1:1:1; and m:1:1; m:m:n:n

: 1, for other planes.

In the *Dimetric* system, the *vertical* is a varying axis; but b=c. The vertical faces of the prism (f. 2) will be expressed by the same symbol as the faces of the cube, $\infty: 1:\infty$; the first term being considered here and elsewhere as referring to the axis a. The terminal plane is more conveniently considered as having the vertical axis reduced to zero, (0), as above illustrated. A prism diagonal with the prism just alluded to (or that truncating its edges, f. 77) will have the ratio $\infty:1:1$. Planes parallel to either axis b or c, on the basal edges, as in f. 83), will have alike the general expres-

sion, $m:\infty:1$.

In the Trimetric system, the lateral axes differ from one another, well as from the vertical. Hence one vertical face of the rectangular prism (f. 3) has the expression $\infty : 1b : \infty c$, and the other z: xb: 1c. This expression is made more concise by using in place of the letters, the mark - for the longer lateral axis, and for the shorter. Thus, considering b shorter than c, the expression $x:1b:\infty c$ becomes $\infty:\tilde{1}:\tilde{\infty}$; and $\infty: \infty b:1c$, becomes $\infty:\tilde{\infty}:$ i. which last means simply that the plane is parallel to the shorter lateral axis, this being *infinite*, (∞) . So in all other cases, the general formula ma:nb:rc, becomes $m:\tilde{n}:\tilde{r}$, signifying that the plane has for its parameters, m times the vertical axis, n times the shorter lateral, and r times the longer lateral, whatever in any case may be the values of m, n, r. The lateral planes of the rhombic prism have the ratio $\infty:1:1$.

In the Monoclinic system, one of the lateral axes is inclined to the vertical, and the other not. The expression ma:nb:rc, in this system, is abbreviated by using an accent for the inclined axis; thus the ratio becomes m:n:r. In the prism, f. 5, the right hand lateral plane has the expression $\alpha: \vec{\alpha}: 1$; and the front plane, the expression ∞ : $i : \infty$; while the planes on the edges, or the lateral plane of 6, have the ratio $\alpha:1:1$, the same as for the right rhombic prism. Again, the planes on the angles of f. 114, as they are parallel to the clinodiagonal, come under the general expression $m: \tilde{\omega}: 1$. Owing to the inclination of the vertical axis, the planes in front, above the plane of the axes BB, CC, differ from those below; and the two are distinguished by the signs for

plus and minus, as in f. 112, 113.

The Triclinic and Hexagonal systems will be the subject of

remarks on a following page.

System of Notation.—The ratios above given are inconveniently long for use in the descriptions of crystals, and have been abbreviated by Naumann. In all cases, one of the last two terms in these ratios may be a unit. Thus the ratio 6:3:2 is equal to $3:\frac{3}{2}:1$. We may therefore indicate the ratio of b to c by simply a single figure. Thus, $\frac{3}{4}$, in this case, is as explicit as $\frac{3}{4}$: 1, when we wish only the general expression. Hence, $3:\frac{3}{4}$ would express accurately the plane. Naumann writes the 3 (or number referring to the vertical axis) before a P, and the other figure after, thus, $3P_{\frac{3}{2}}$; so also $\infty P \infty$; ∞P , (for $\infty P 1$, the unit being implied); 3P, (for 3P 1, as in the last); and generally mPn, for any plane. In the monometric system, the letter O, (initial of Octahedron), is adopted in place of P. The letter has no special meaning, and the expression is as explicit and more concise, when written without it, thus, 3-3, istead of $3P_{\frac{3}{2}}$; 3 instead of 3P; ∞ - ∞ , instead of $\infty P \infty$; m-n, instead of mPn. In some cases, however, the use of the letter is convenient, and especially for hemihedral crystals.

In the *Trimetric* system, the expressions become ∞ : ∞ , corresponding to $\infty : \widecheck{\alpha} : 1$; 3-\(\vec{a}\), corresponding to $3 : \widecheck{\alpha} : 1$; m-n for m: 1: n, or m-\(\vec{n}\), for m : n : 1. Naumann writes mPn, or mPn. It is preferable to place the long or short mark over the figure referring to the longer or shorter, respectively, of the lateral axes, as $mP_{\bar{n}}$, or $mP_{\bar{n}}$.

In the *Monoclinic* system, m:1:n becomes m-n, (or mPn);

and $m: \hat{n}: 1$, becomes $m \cdot \hat{n}(mP\hat{n})$.

The symbol for a plane is used for the whole form which the planes of a kind constitute. Thus the general symbol for a plane of the regular octahedron (O or 1) is used to designate the octahedron; the general symbol of a face of the cube, $(\infty O \infty$, or $\infty - \infty$), indicates the cube as a whole.

The Zones alluded to on a preceding page, are well exhibited through these symbols. Thus, if we write I for any number less than a unit, and m and n for any numbers greater, the series in the dimetric and trimetric systems will be as follows:

Dimetric System.

0			
ı	l-n	l-œ	
1	1-n	1-00	
98	399 · 91	IN- 00	
z.	Ø. ∙ %	70 - 10	

Trimetric System.

0				
l-≅	l-n	ı	1-n	1.2
1.55	1-n	1	1-71	1-ळ
m-∞	m-n	774	1N-H	m-∞
တ-ဆ	00-%	89	œ.¥	œ- <u>∞</u>

In the table for the dimetric system, the column 1 is a series of octahedrons ending below in a square prism; 2, different series of 8-sided pyramids, m-n, one for each possible value of n, and ending below in corresponding 8-sided prisms; 3, series of octahedrons diagonal to those of column 1, and ending in the diagonal prism. The basal plane 0 is the upper termination of each series or zone.

The table includes an eighth of an upper half of the crystal, the same planes occurring in each of the eight sections.

In the table for the *trimetric* system, column 1 is the zone parallel to the macrodiagonal, consisting of macrodomes, and ending below in the vertical plane; 3, the fundamental zone; 5, the brachydiagonal zone; 2 and 4, zones, m-n, either side of the fundamental zone. The table includes a *fourth* of an upper half of a crystal, the same being repeated in each fourth around.

The monoclinic system is similarly presented in the following

table:

		0		
l-co	l-n	ı	l-n	l-ào
1-00	1-n	1	1- ù	1-à
1N-00	าก-าเ	m	m-n	m-∞`
oc-œ	00-M	8	∞-ñ	∞ - 3o
-174 · 00	-т-н	-m	-m-n	m-œ
-1-œ	-1-n	-1	-1-n	1-œ
-l-∞	-l-n	5-1	<i>-l-મ</i>	l-ù


Column 1 is the orthodiagonal zone, or series parallel to the orthodiagonal; 3, the fundamental series of octahedrons, the ratio of the lateral axes being 1b:1c, and containing also the fundamental mombic prism; 5, the clinodiagonal series; 2 and 4, zones between the fundamental zone and the orthodiagonal series on one side, and the clinodiagonal on the other, each having its rhombic prism. The middle horizonal line of planes, x-x, x-x, x-x, x-x, is a series of vertical prisms; the planes above it are +, those below are -, excepting in the 5th column, in which those above and below are alike as they are clinodomes, (see page 43). The table comprises a fourth of the crystal, including the parts below as well as those above the middle section.

The various secondary planes of crystals often have a general relation among themselves, which is worthy of more study than it has yet received. Under Humite, figures are given, (taken, with a change in the notation, from a paper by M. Scacchi), which show a remarkable arithmetical progression in the series of planes. Thus in one zone, there are the octahedral planes $\frac{3}{10}$, $\frac{3}{8}$, $\frac{3}{6}$, $\frac{3}{4}$, $\frac{3}{2}$; in another figure, the planes $\frac{2}{7}$, $\frac{2}{3}$, $\frac{1}{4}$; in a third, the series, $\frac{1}{12}$, $\frac{4}{13}$; and other examples of similar character are seen in the same figures. It is evident that the planes of each type belong together in one system and have a mutual dependence.

In other species similar series may be observed, although they have not hitherto been as clearly made out. Among the concur-

rent crystals of the same locality, many different forms often occur, which are due to a simplification merely of a specific type, by a dropping of one and another plane; and such forms, however various, constitute therefore but one system. At other localities there is often a very different series of planes, many of which are peculiar to the place, or occur only in the combination there observed. The mutual dependence of the planes is such that they essentially belong together as much as the different parts of a curve of a given equation. It is customary to mention the known combinations of forms of a species, enumerating even those which are mere simplifications of a given type, and giving the whole equal importance. The distinction of the various forms of each species into separate types of dependent series remains to be studied out.

The fact that the axes of crystals have specific dimensions, is at the basis of the relation by multiples upon which the arrangement of the planes depends. In the monometric system, as the axes are equal, the positions of the planes are independent of any given length. Thus, if we find a plane on an edge of a cube inclined to its face at an angle of 153° 26′, as Rb on ba, (f. 142), the ratio of



Pb to Pa (equivalent to the ratio of the axes of the plane ab) will be found to be 1:2, indicating that the plane has the ratio 1:2: α . In the triangle Pba, the angle Pab=153° 26' $-90^{\circ}=63^{\circ}$ 26'; and then the ratio Pa (=1): Pb:: R: tan 63° 26'=1:2.

But in the dimetric and other systems, the inclinations of the planes afford the ratios not simply of m:n, as in the monometric system, but of ma:nb, (or ma:n, making b=1), etc., the lengths of one or more of the axes being included in the ratio. In deciding upon the

planes to be considered those of the fundamental series, in a dimetric or trimetric crystal, and particularly upon the plane that will give the length of the fundamental vertical axis, or of the lateral axes, we may be, at times, guided by an octahedral cleavage, in which case the cleavage plane will be the face 1:1:1,-or $1:1:\infty$. In the trimetric system, there is often a vertical cleavage, parallel to the faces of a rhombic prism, which rhombic prism would be therefore the fundamental prism $\infty:1:1$; and when that is the case, the angle of the prism indicates at once the ratio of the lateral axes. If this angle, for example, is 100° , we have this angle of a rhomb to determine the ratio of the diagonals, (the lateral axes); the diagonals divide the rhomb into four right angled triangles, each having angles of 50° and 40° ; and hence the ratio b(=1):c::R: tan 50° , which gives the value of c.

In the majority of cases, for one or more of the axes, some plane

must be empirically assumed to be that based on the ratio of unity; and in deciding upon which, we may be guided often by finding some plane more frequent than others in occurrence; or by detecting analogies with some other species; or by the desirableness of having such a plane as will give the most simple expressions for the ratios of the other planes, an arbitrary criterion often convenient, rather than correct. We arrive in any case, at a ratio for the axes, upon which the whole structure of the crystal is based. If, for example, we obtain as the axial ratios of a:b, for a series of planes, 2.4:1, 1.2:1, 0.6:1, it matters little which plane is assimed as fundamental. If the first, then a=2.4, b=1; and then the planes will be in order, $1:1:\infty, \frac{1}{4}:1:\infty, \frac{1}{4}:1:\infty$. But if we take the second as the fundamental one, (as would probably be done), then a=1.2, b=1, and the ratios for the planes will be $2:1:\infty$, Both indicate the same general relation $1:1:\infty, \frac{1}{2}:1:\infty.$ among the planes. The calculation of the axes in such a case, by plane trigonometry, would be similar to that above. The inclination of the plane on the base of a crystal, subtracted from 180°, (or diminished by 90°), gives the angles of the triangle Pba, and then working the triangle by the equation, Pa (=1): $Pb::R: \tan Pab$, we have, as the result, a ratio like one of the above. Pursuing the same with another plane as a c, another ratio will be obtained, which is some multiple of the first.

In the trimetric and triclinic systems either of the three axes may be called the *vertical*, and authors are not all agreed on this point with regard to particular minerals. So also in the monoclinic system, where there is no cleavage to determine the plane 0P, or that of the lateral axes, this plane must be assumed from analogy or arbitrarily as the case may be. Still, in comparing the angles of different species, it is necessary to ascertain, by some facts or analogies, which are actually the *homologous* axes, as only such are prop-

erly related.

It is convenient to remember that when RPQ is a right angle, the sum of the angles Rca, Qac, is 270° ; or whatever the angle, RPQ, $Rca+Qac=180^{\circ}+RPQ$. If RPQ is 100° , then $Rca+Qac=280^{\circ}$. Another elementary fact in geometry of frequent use in crystallography is, that the sum of the two angles cPa and caP of the triangle cPa, equals the external angle Rca. So that Rca being known, Pac is found by subtracting aPc, the angle of the edge, from Rca.

Plane and spherical trigonometry may be used also for determining the axes from any given planes, and for ascertaining the angles from the axes. But the calculations by means of equations derived from analytical geometry are the most complete, and most general in their application; and to these we now proceed, presenting more in detail many points barely glanced at in the pre-

ceding pages.

I. ORTHOMETRIC SYSTEMS.*

I. GENERAL FORMULAS.

- 1. Inclinations between planes of different forms, or unlike planes.
- 1. The parameters of any plane have been stated to be an expression of the position of this plane with reference to the axes. Thus, in f. 40, the parameters of a plane ABC, are AO, BO, CO, or a:b:c, AA', BB', CC' being three rectangular axes, each bisected at O. The plane ABC' is similar in its parameters, except that the axis C'O is on the opposite side of O. Hence the ratio is a:b:-c.

For a like reason, the parameters of ACB' are a:-b:-c.

" AB'C " a:-b:c.

" A'BC " -a:b:c.

" A'BC " -a:b:-c.

" A'BC " -a:b:-c.

" A'BC " -a:b:-c.

" A'B' " -a:-b:-c.

In the employment of general formulas, and substituting the values of the parameters in the equations, the signs should be carefully regarded. In most cases that come up for calculation, the planes are in the same octant and are then of the same signs.

2. Representing the parameters of any plane by a:b:c, and also of any other plane by a':b':c', and placing W for the supplement of their mutual inclination,

Cos W=-
$$\frac{aa'bb'+cc'aa'+bb'cc'}{\sqrt{(a^3b^3+c^2a^3+b^3c^3)}\sqrt{(a^3b^3+c^3a^3+b^3c^3)}}$$

In using this equation, the actual values of the parameters are to be substituted for the letters. For the planes m - n, m' - n', in the same octant, in which the parameters would be ma : b : nc, and m'a : b : n'c,

$$ma$$
, b , nc are substituted severally for a , b , c . $m'a$, b , $n'c$ " a' , b' , c' .

- 2. Equations for determining the Parameters of planes by their intersections.
- 3. When in a zone of planes, a plane m'': n'': r'' makes parallel intersections between two planes m': n': r' and m: n: r, the relation of m, n, r, for either one of these planes may be ascertained, if their values for the other two planes are known, by means of the equation

$$\frac{1}{mn'r''} + \frac{1}{nr'm''} + \frac{1}{rm'n''} = \frac{1}{mn''r'} + \frac{1}{nr''m'} + \frac{1}{rm''n'}$$

The following pages are a condensed abstract from Naumann's very elaborate treatise on Crystallography.

In using the equation, the values of m and n, (or m, n, r), in two of the planes, are to be substituted for the letters, (not neglecting to note the signs as above explained, when the planes belong to different octants), and the equation then reduced. If r, r', r'', each equals 1, the equation becomes for the planes m-n, m''-n'', m'-n':—

$$\frac{1}{mn'} + \frac{1}{nm''} + \frac{1}{m'n''} = \frac{1}{mn''} + \frac{1}{nm'} + \frac{1}{m''n'}$$

This equation is simplified for other forms in the following table: the plane of which the relation for m'' and n'' is required, is supposed to make parallel intersections between a plane mentioned on the margin of the table and another over the column of formulas. For the first of the equations, the simplification consists in substituting m' for the n' in the general equation, since m'-m' is substituted for m'-n'; in the third, 1 is substituted for n'; in the fourth ∞ for n', and so on, the equation being reduced after the substitution. Several of these equations are deducible from the explanations on pages 53 to 56.

When ∞ enters into the equation, on reducing it, all the terms not containing ∞ as a coefficient are expunged, a result that follows necessarily, from dividing the whole equation by infinity; and if ∞^2 occurs, all but the terms containing ∞^2 are for a like reason

dropped.

a. Form m-n.

d. m, in which n=1.

```
1. m''(m-m') + n''(m'-m'')m=0.

2. m''(n''-n') + n''(n'-1) m=0.

3. 2m''-n''(m''+m)=0.

4. n''=1, m''>m.
m'-00
00-21
œ-2
                       5. n''=1, m'' < m.
6. \frac{m''}{m}=m.
1
                          \overline{n''}=m
                               e. m-\infty, in which n=\infty.
                        1. n''(m''-m) - m''n' = 0.
2. n''(m''-m) - m'' = 0.
00-n'
                             f. \infty-n, in which m = \infty.
                        1. m''(n''-n)+n''(n-1)=0.
1
                   g. \frac{(m-n)}{2} (in the Monometric System.)
\frac{(m'-n')}{2}
                  m''n'' (m'n+mn')-m'' (m+m') nn'+n'' (n'-n) mm=0.
\frac{(m')}{2}
                  m''n''(m'n+m)-m''(m+m')n-n''(n-1)mm'=0.
(1)
                  m''n''(m+n) - m''(m+1) n - n''(n-1) m = 0.
                                          h.\frac{(m-m)}{2}.
(m'-m')
                   2m''n''-m''(m+m')+n''(m'-m)=0
                   m''n''(m'+1)+m''(m+m')-n''(m-1)m'=0.
(1)
                    2m''n''-m''(m+1)-n''(m-1)=0.
```

- 3. General relation of Planes of Orthometric forms, in the same vertical zone.
- 4. The angles between the planes of any vertical zone, (m-n, m) or $m-\infty$, and the basal plane (0) of the type-prism being given, subtract each from 180° ; then the tangents of the resultant angles will vary as the values of m in the zone. That is, calling this angle for m-n, I, and for m'-n in the same zone, I', then—

Tan
$$I$$
: tan $I'=m:m'$; or if $m=1$, tan $I'=m'$ tan I .

The law holds for the hexagonal system, as well as the monometric, dimetric, and trimetric.

Either face of the type-prism in the rectangular systems, may be taken as the basal; and the planes of the zones which in this new position become vertical, (or their intersections horizontal), have essentially the same relation. In this case, the angle / is the inclination on the assumed base, and m is the coefficient of the axis

at right angles to this base, which axis becomes for the time the vertical.

II. MONOMETRIC SYSTEM.

1. Inclinations between planes of different forms.*

5. In the monometric system, since the axes are equal, (a=b=c=1), the values of m, n, in equations, stand for the axes. m-n is a general expression for holohedral planes or forms; $\frac{(m-n)}{2}$ for inclined hemihedrons, (as in f. 53 to 66), $\frac{[m-n]}{2}$ for parallel hemihedrons, (as f. 67 to 75).

6. The general equation for the mutual inclination of two planes m-m, m'-n', is

Cos
$$Q = \frac{mn' (nn'+1) + nn'}{\sqrt{(m^2 (n^2+1) + n^2)} \sqrt{(m'^2 (n'^2+1) + n'^2)}}$$

7. The following table contains this equation simplified for particular cases:

$$M = \sqrt{m^2 (n^2+1) + n^2}$$
, and (next page) $M' = \sqrt{m^{n} (n^{n^2}+1) + n^{n^2}}$

	20-20	1	∞-n'	m'-m'
371-7ı	nn- M	$\frac{m (n+1) + n}{M \vee 3}$	$\frac{m(nn'+1)}{M\sqrt{n^2+1}}$	$\frac{m (m'n+1) + n}{M\sqrt{(m'^2+2)}}$
2-11	$\sqrt[n]{\frac{n}{\sqrt{n^2+1}}}$	$\begin{vmatrix} n+1 \\ \sqrt{3} \sqrt{n^9+1} \end{vmatrix}$	$\frac{nn'+1}{\sqrt{(n^2+1)}(n'^2+1)}$	-

The angle between m-n and ∞ -n' is obtained by means of the equation opposite m-n and under ∞ -n'; and by making n'=1, this becomes the expression for m-n on ∞ , or the face of the dodecahedron.

From this table, the inclinations of any form on a face of the cube, octahedron, or dodecahedron, may be calculated.

8. For inclined hemihedrons, when the planes are both plus or both minus, the formula is the same as for holohedral forms; but when one is plus and the other minus, the formula becomes for

$$\operatorname{Cos} Q = \frac{mm'(nn'+1) - nn'}{\sqrt{m^3(n^2+1) + n^3} \sqrt{m'^3(n'^2+1) + n'^3}}$$

^{*}Besides the logarithms usually given in published tables, the following are required in using the formulas beyond. Log. $\sqrt{3}$ =0.2385606; log. $\sqrt{1}$ =9.7614394; leg. $\sqrt{2}$ =0.1505150; log. $\sqrt{1}$ =9.8494850.

and for $\frac{(m-2)}{2}$ on $-\frac{(1)}{2}$ or a tetrahedal face,

$$\operatorname{Cos} Q = -\frac{m (n+1) - n}{M \sqrt{3}}.$$

9. In parallel hemihedrons, for planes of like signs, the formula is the same as for holohedral forms; for analogous planes of unlike signs, $\frac{[m-n]}{2}$ on $-\frac{[m'-n']}{2}$

$$\begin{array}{ccc}
\text{Cos } Q = -\frac{m'n \ (mn'+1) + mn'}{MM'} \\
\text{For } \frac{[m-n]}{2} \text{ on } -\frac{[\infty-n']}{2} & \text{Cos } Q = -\frac{n \ (mn'+1)}{MV(n'^2+1)} \\
\text{For } \frac{[\infty-n]}{2} \text{ on } -\frac{[\infty-n']}{2} & \text{Cos } Q = -\frac{nn'}{V(n^2+1)} \frac{nn'}{V(n'^2+1)}
\end{array}$$

- 2. Inclinations between planes of the same form.
- 10. For m-n, using the letters A B C for the edges on which they are placed in figure 51, and N for $m^2n^2+m^2+n^2$,

$$\cos A = -\frac{mn (mn+2)}{N} \qquad \cos B = -\frac{m^2 (n^2+1) - n^2}{N}$$

$$\cos C = -\frac{n (2m^2+n)}{N}$$
For $x - n$, (f. 34),
$$\cos A = -\frac{n^2}{n^2+1} \qquad \cos C = -\frac{2n}{n^2+1}$$

$$\tan \frac{1}{2}C = \frac{n+1}{n-1}$$
For $m - m$, (f. 39),
$$\cos B = -\frac{m^2}{m^3+2} \qquad \cos C = -\frac{2m+1}{m^2+2}$$

$$\tan \frac{1}{2}B = vm^2+1$$
For m , (f. 49),
$$\cos A = -\frac{m^2+2m}{2m^3+1} \qquad \cos B = -\frac{2m^2-1}{2m^3+1}$$

$$\tan \frac{1}{2}B = mv^2$$

11. In inclined hemihedrons, as $(\frac{m-n}{2})$, f. 65, A' and C', are dedetermined by the same formulas as above.

$$\operatorname{Cos} B' = -\frac{mm \ (mn-2)}{\lambda^r}$$

12. In parallel hemihedrons, as $\frac{[m-n]}{2}$, f. 74, B'' is determined by the same formula as above.

$$\cos A'' = -\frac{m^2 (n^2-1)+n^2}{N}$$
 $\cos C' = -\frac{mn (m+n+1)}{N}$

MATHEMATICAL CRYSTALLOGRAPHY. For
$$\infty$$
-n, as in figure 69,
$$\cos A'' = -\frac{n^2-1}{n^2+1} \qquad \cos C'' = -\frac{n}{n^2+1}$$

3. Determination of m and n by inspection.

13. The following table gives data for determining the parameters of planes in monometric crystals by inspection. The first line would read, if written out in full, m-n has edge A truncated by m'-m' when $m'=\frac{2mn}{m+n}$ and if m-n=4-2, then $m'=\frac{2\times 4\times 2}{4+2}=\frac{16}{6}=\frac{8}{3}$ and m'-m', therefore, equals $\frac{n}{3}-\frac{n}{3}$. The same explanation answers for the rest of the table.*

a m-n. (f. 51). 1. Edge A truncated by m'-m', when	$m' = \frac{2mn}{m+n}$
2. Edge C truncated by m',	$m' = \frac{m(n+1)}{2n}$
3. Edge B truncated by \omega-n',	n'=n
4. Solid angle a truncated by rhombic plane ∞ , (f. 52),	$n=\frac{m}{m-1}$
5. Solid angle b truncated by 1,	$n = \frac{2m}{m+1}$
ha-m. (f. 39). S-A. a repl. by 4 pl., I-E. parallel to symmetrical diagonal of face,	$\frac{1}{2}m = \frac{m'n}{m' + n'}$
2. Edge C truncated by m',	$m' = \frac{m+1}{2}$
 S-A. a repl. by 2 pl. m', incl. on edge C, I-E. par. to edge B of m-m, Edge B truncated by \(\infty\)-n' S-A. a repl. by 2 pl. \(\infty\)-n', incl. on edge B; I-E. of opposite pl. with the same face of m-m parallel, 	m'=m n'=m
(f. 46), 6. S-A. σ repl. by 4 pl. ∞-n', incl. on B; I-E. par. to C,	$n' = \frac{1}{2}m$ $n' = m + 1$
7. S.A. a truncated by ∞ ; I-E. of opposite pl. with same face of m-m parallel; f. 43, 44, planes I,	<i>m</i> =2
e.m. (f. 49). 1. S-A. c repl. by 8 pl. m'-n'; I-E. of 2 pl. incl. on same face of m parallel,	$2m-\frac{m'(n'+1)}{n'}$
 S-A. c repl. by 4 pl. m'-m' incl. on edge A; I-E. of two pl. with same face of m parallel, 	m'=2m-1
3. Edge A truncated by m'-m',	$m' = \frac{2m}{m+1}$
4. S-A. c repl. by 4 rbc. pl. m'-m', incl. on A of m,	m'=m
5. S-A. c repl. by 4 rbc. pl. ∞-n' incl. on B,	$n' = \frac{m}{m-1}$

The following abbreviations are used in this and similar tables: Trunc. truncated; Repl., replaced; Bev., beveled; A., angle; S-A., solid angle; E., edge; l.E., edge of intersection of two planes; Par., parallel; Pl., planes; Inc., inclined; Rec., rhombic; Term., terminal.

- 4. Determination of m and n by calculation.
- 14. In the following formulas,
 - v—half the inclination of B on B over angle c, (fig. 51).
 - δ =half the inclination of B on B over angle α .

 δ' = the inclination of C on the horizonal basal section.

 ϵ = the inclination of C on the diagonal connecting S-A. b and its opposite. Tan $\epsilon = \frac{(n-1)V^3}{n+1}$.

1. In 111-n,

a.
$$\cos v = \frac{\cos \frac{1}{2}A\sqrt{2} + \cos \frac{1}{2}B}{\sin \frac{1}{2}B}$$
; $n = \tan v$; $m = \tan \frac{1}{2}B \sin v$.

b. Cos
$$\varepsilon = \frac{2 \cos \frac{1}{2}A + \cos \frac{1}{2}C}{\sin \frac{1}{2}C \times 8}$$
; $\delta' = 144^{\circ} 44' - \varepsilon$; $\tan \delta = \sin \delta' \tan \frac{1}{2}C$; $n = \tan (135^{\circ} - \delta)$; $\frac{m(n'+1)}{n} = \tan \delta' \sqrt{2}$.

c. Cos
$$\delta = \frac{\cos \frac{1}{2}C}{\cos \frac{1}{2}B}$$
; $v = 135^{\circ} - \delta$; $n = \tan v$; $m = \tan \frac{1}{2}B \sin v$.

From H (angle between face of cube and the form m-n) and A, B, or C,

$$\sin h' = \frac{\cos \frac{1}{4}A}{\sin H}; h = 45^{\circ} + H; n \frac{\cot H}{\sin h}.$$

Sin
$$v = \frac{\cos H}{\sin \frac{1}{2}B}$$
; $n \tan v$; $m = \tan \frac{1}{2}B\sin v$. $\frac{n-1}{n} = \frac{\cos \frac{1}{2}Cv^2}{\cos H}$; $\sin h = \frac{\cot H}{n}$; $m = n \tan h$.

From O (angle between face of octahedron and form m-n) and A or B,

Cos
$$\mu$$
 (= α -35° 16') = $\frac{\cos \theta}{\sin A_{\frac{1}{2}}}$; $\cot \beta = \frac{\cot \frac{1}{2}A}{\sin \alpha}$; $m = \frac{v^2}{\cot \alpha - \cot \beta}$; $n = \frac{v^2}{\cot \alpha + \cot \beta}$.

$$\cos \delta = \frac{\cos \theta \sqrt{3} - \cos \frac{1}{2}B}{\sin \frac{1}{2}B\sqrt{2}}; n = \tan (45^{\circ} + \delta); m = \tan \frac{1}{2}B\sin (45^{\circ} + \delta).$$

2. In m-m,

Cos
$$v = \cot \frac{1}{2}B$$
; $m = \tan v$; $\frac{1}{2}A = 90^{\circ}$.

$$\cos \epsilon = \cos \frac{1}{2}C\sqrt{3}$$
; $\delta' = 144^{\circ} 44' - \epsilon$; $m+1 = \tan \delta' \sqrt{2}$.

Also, $m = \cot H\sqrt{2}$; $m = \tan (O + 35^{\circ} 16') \sqrt{2}$.

3. In m.

$$m = \tan \frac{1}{2}B\sqrt{\frac{1}{2}}$$
. $\frac{1}{2}C = 90^{\circ}$.

Cos
$$\varepsilon = 2 \cos \frac{1}{2} A \sqrt{\frac{1}{3}}$$
; $\delta' = 144^{\circ} 44 - \varepsilon$; $m = \tan \delta' \sqrt{\frac{1}{2}}$.

Cot
$$H = \sin h$$
, and $m = \tan h$. $m = \tan (O + 54^{\circ} 44') \sqrt{\frac{1}{2}}$.

4. In x-n,

Cos
$$v = \cos \frac{1}{2}A\dot{v}^2$$
; $n = \tan v = \tan (135^{\circ} - \frac{1}{2}C)$.
 $n = \cot H$. Cos $Ov_{2}^{\circ} = \cos \delta$, and $n = \tan (\delta + 45^{\circ})$.

I.—HOLOHEDRAL FORMS.

	4	ı R	c	<i>H</i> .	0.	!
	٠,	0,	0,	0 /	o ,	
∞-∞ (f. 1)			90		125 16	
1 (f. 11)	`	109 28		125, 16		
∞ (f. 14)	120			1	144 44	
oo. <u>\$</u>	127 34	i e				Perofskite.
∞	129 47					Diamond, Perofskite.
∞ .3	138 49					Diamond, Perofskite, Blende.
∞-2 (f. 31)	143 8					Fluor, Salt, Garnet, Magne- tite, Red Copper, Gold, Percylite, Copper, Silver.
∞ · <u>5</u>	149 33	!	133 36	158 12	138 38	Fluor, Copper.
∞-8 (f. 34)	154 9	!	126 52	161 34	136 54	Fluor, Gray Copper, Amal-
(1. 1.1)		1	,			gam.
∞-4	160 15	ļ	118 4	165 58		
∞ -5	164 3 1		112 37	1 1		Red Copper Ore.
3.3		121 58				Galena.
ชี-ชี (f. 39)	İ	131 49	146 27	144 44	160 32	Sal-Ammoniac, Fluor, Anal- cime, Sodalite, Leucite, Pyrochlore, Pyrites, Franklinite, Dufrenoysite, Amalgam.
• •		198 48	119 38	147 15	157 25	Perofskite, Galena.
8-8 (f. 40)		144 54				Fluor, Spinel, Perofskite, Py- rochlore, Pyrites, Magne- tite, Galena, Gold, Silver.
3	162 39]	129 31	!	115 15	169 49	Garnet.
3 (£ 49)	152 44		!		100	Diamond, Fluor, Spinel,
(,	,		 			Franklinite, Perofskite, Magnetite, Cube Ore, Py- ritee, Hauerite, Red Cop- per, Amalgam, Skutteru- dite, Galena.
8	142 8	153 284	1	103 16		Fluor, Red Copper Ore, Gallena.
3-3 (f. 51)	158 18		İ			Diamond, Garnet, Magne- tite, Red Copper, Amal gam.
4-2	162 15	154 474	144 8	150 48	151 52	Fluor, Gold.
		160 32				Magnetite.
5 § 7-3	158 47	1	136 47	155 42		
y 3.11	166 57		• • • • • •	152 4		
1.2	100 D/	103 /	140 8	102 1	101 41	11401.

PLANE ANGLES.

	٠,	a. ,	ь		c.		
	0	,	. 0	,	0	,	
∞- 3 ∞-2	50		'		79	314	
∞- <u>2</u>	48	11	:		88	37	
∞-3	.46	301	j		86	59	
2-2	82	15	117	2	78	28	
8-8	81	26	112	53	84	16	
2			118	4	80	58	
3- 3 4-2	86	56					
4-2	85	50	56 54	214	39	48	

II.-HEMIHEDRAL FORMS.

1. Tetrahedral. 1 (f. 55, 56)	, A	l. _,	. 4	3	。	c.,	
	{ }		60	•			Blende, Tennantite, Gray Copper, Boracite.
3 2 2 (f. 60) 3	162	391	82	10	İ		Gray Copper.
2 (f. 60)	152	44	80				Diamond, Blende, Gray Copper.
3 ` ′	142	8	99	5			, and a second
3-3	i		93	22	160	15	Tennantite,
3-3 2-2 (f. 59)			:				Boracite, Tennantite, Gray Copper Bismuth Blende.
3-3			124	7	184	2	Gray Copper.
8- 3	:158	13	110	551	158	13	Diamond, Gray Copper.
4 2	162	15	124	51	144	8	Samuella, Villy Coppe
1. Pyritohedral.						•	
æ- 3 *	112	37	ļ		117	29	Pyrites.
∞-2 (f. 69)	126	52	I		113	35	Pyrites, Cobaltine, Gersdorffite.
œ-3	143	8			107	271	Pyrites, Hauerite.
∞-4	151	5 6			103	36 1	Cobaltine.
3-3 (f. 74)	115	23	149		141	47	Pyrites, Hauerite, Cobaltine.
				471	131	49	Pyrites.
4-2 5- 5	119		160				Pyrites.

III. DIMETRIC SYSTEM.

8. Inclination between planes of different forms.

16. In the dimetric system, for the inclination of m-n on m'-n', in which (as the axes b, c, are equal, and may be taken each as 1)

$$a:b:c=$$
 respectively $ma:n:1$, $a':b:c=$ " $m'a:n':1$,

In these pyritohedrons, A is the interfacial angle at the longer edge, and C that at either of the others.

Cos Q(the inclination sought)= $-\frac{mm'a^2(nn'+1)+nn'}{\sqrt{(m^2a^2(n^2+1)+n^2)}\sqrt{(m'^2a^2(n'^2+1)+n'^2)}}$

17. By substituting 1, ∞ , or 0, for m or n in different forms, we have the following more simple formulas for certain cases. In the table, $M = \sqrt{m^2 a^2 (n^2 + 1) + n^2}$.

	0	go-go	∞-n'	m′ ∞
1	n	mna	, ma(nn'+1)	$(mm'a^2+1)n$
m-n	M	M	$\overline{MV(n^2+1)}$	$M\sqrt{(m'^2a^2+1)}$
m	1 1	ma	ma(n'+1)	$mm'a^2+1$
"	$\sqrt{(2m^2a^2+1)}$	$\sqrt{(2m^2a^2+1)}$	$\overline{\nu(2m^2a^2+1)}\overline{\nu(n'+^21)}$	$V(2m^2a^2+1)V(m'^2a^2+1)$
	1 1	ma	mn'a	mm'a ² +1
m-∞	$\sqrt{(m^3a^2+1)}$	$\overline{\sqrt{m^3a^3+1)}\sqrt{2}}$	$\sqrt{(m^3a^3+1)\sqrt{(n'^3+1)}}$	$\sqrt{(m^2a^2+1)m}\sqrt{(^2a^2+1)}$
	i i	n	nn'+1	<u></u>
co-n	0	$\sqrt{n^2+1}$	$\overline{\nu^{(n^2+1)}\nu^{(n^2+1)}}$	

18. The inclination of m-n on 0 (or basal plane) will be obtained by making $\cos Q = -\frac{n}{M}$: so in other cases.

2. Inclinations between planes of the same form.

19. In the dimetric system, the forms m-n are double 8-sided pyramids, (f. 89); m and m- ∞ are octahedrons, like f. 12 and 84; ∞ -n are 8-sided prisms, (f. 79); ∞ and ∞ - ∞ are 4-sided prisms, (f. 77 and 2).

For X, Y, Z, in m-n, (see f. 89, in which the edge X is that connecting the vertical axis and a lateral axis),

Cos
$$\frac{1}{2}X = \frac{ma}{M}$$
Tan $\frac{1}{2}X = \frac{nV(m^{2}a^{2}+1)}{ma}$
Cos $\frac{1}{2}Y = \frac{ma(n-1)}{MV^{2}}$
Tan $\frac{1}{2}Y = \frac{V(m^{2}a^{2}(n+1)^{2}+2n^{2})}{ma(n-1)}$
Cos $\frac{1}{2}Z = \frac{n}{M}$
Tan $\frac{1}{2}Z = \frac{maV(n^{2}+1)}{n}$

20. The formulas become for

$$m \cdot m : \quad \text{Tan } \frac{1}{4}X = \frac{V(m^2a^2+1)}{a} \quad \text{Tan } \frac{1}{4}Y = \frac{V(a^2(m+1)^2+2)}{a(m-1)} \quad \text{Tan } \frac{1}{4}Z = aV(m^2+1).$$

$$m : \quad \text{Tan } \frac{1}{4}X = \frac{V(m^2a^2+1)}{ma} \quad \frac{1}{4}Y = 90^{\circ} \quad \text{Tan } \frac{1}{4}Z = maV2.$$

$$m \cdot x : \quad \frac{1}{4}X = 90^{\circ}. \quad \text{Tan } \frac{1}{4}Y = \frac{V(m^2a^2+2)}{ma} \quad \text{Tan } \frac{1}{4}Z = ma.$$

$$co-n : \quad \text{Tan } \frac{1}{4}X = n. \quad \text{Tan } \frac{1}{4}Y = \frac{n+1}{n-1} \quad \frac{1}{4}Z = 90^{\circ}.$$

21. Putting T for the angle of inclination of two planes of m-n, over the axial angle of the base, (F on F'', f. 89), and U for

the inclination of two planes over the next basal angle, (F')on F''),

$$\operatorname{Tan} \frac{1}{2} T = \frac{man}{\sqrt{(m^2 a^2 + n^2)}}$$
 $\operatorname{Tan} \frac{1}{2} U = \frac{ma(n+1)}{\sqrt{(m^2 a^2 (n-1)^2 + 2n^2)}}$

3. Determination of m and n by inspection.

22. Under this head, it should be noted, that planes with horizontal intersections (the lateral axes being in a horizontal plane) have n=n'.

That planes truncating or beveling the terminal edges of any form m'P, or the edge X of any m'Pn', have m=m'.

We again refer to the general laws on pages 53 to 56, which include many of the particular equations below.

The following table reads in the same manner as that under the monometric system; the first line, for example, is, m-n has its edge Y truncated by the plane m', when $m' = \frac{1}{m} \frac{(n+1)}{2n}$.

6.	zn	
上別州	(f. 89). 1. Edge Y truncated by plane m' , when	$m' = \frac{m (n+1)}{2n}$
	2. Term A. repl. by 4 rbc. pl. m', incl. on edge Y,	$m' = \frac{m}{n}$
	 Basal A. at Y repl. by 2 pl. m', incl. on Y; I-E. par. to X, (£90), 	m'=m
	4. Edge X trunc. by m'-∞.	m'==m
	5. Term-A. repl. by 4 rbc. pl. m' - ∞ , incl. on X ,	$m' = \frac{m(n-1)}{n}$
	 Basal A. at X repl. by 2 pl. m'-∞, incl. on X, I-E. parto Y, 	$m' = \frac{m(n+1)}{n}$
	7. Basal edge trunc. by ∞-n',	n'=n
`. #r'	(f. 62). 1. Term. edge bev. by m'-n', (f. 90),	m'=m
	2. Basal A. repl. by 4 pl. m'-n', I-E. par. to term. edges,	$\frac{m'}{n'} = m$
	 Term. edge trunc. by m'-∞, (f. 85), 	m'=m
	 Basal A. repl. by 2 pl. m'-∞, incl. on Term. E., I-E. of two pl. with same face of m parallel, (f. 86), 	m'==2m
C #R-30	1. Term. E. bev. by m'-n', (sim. to f. 90).	$m = \frac{m' (n'+1)}{n'}$
	 Basal A. rep. by 2 pl. m' incl. on Term-E.; I-E. of 2 pl. with same face of m- ∞ par. (sim. to f. 86), 	m'=m
	3. Term-E. trunc. by m'P, (f. 86).	$m' = \frac{1}{2}n$
	 Basal E. bev., or Term-A. repl. by 4 pl. m'-∞ with horizontal intersections. 	
1 (m)	(f. 91, 92). 1. Middle edges bev. by $\pm \frac{(m'-n')}{2}$	$\frac{m'}{n'}$
	2. Angles rep. by a pl. $-\frac{(m')}{2}$ I-E. par. to middle edges,	m'=m

3. Ang. repl. by 2 pl.
$$m'$$
- ∞ ; I-E. of 2 pl. with same face of $\frac{(m)}{2}$ parallel, $m'=2m$

- 4. Angles repl. by ∞.
- 5. Middle edges truncated by ∞ -2, (f. 94).
 - 4. Determination of m and n by Calculation.

23. Let
$$\mathbf{v}'=$$
 the inclination of X on base of pyramid m - n .

 $\mathbf{v}=$
 $\mathbf{v}=$ half the angle of the base which edge X meets.

 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$
 $\mathbf{v}=$

Tan v (angle $\frac{1}{2}X$ of $\infty - n$) = n. Tan δ (angle $\frac{1}{2}Y$ of $\infty - n$) = $\frac{n+1}{n-1}$.

Tan
$$v'=ma$$
. Tan $\delta'=\frac{ma(n+1)}{n\sqrt{2}}$.

a. In m-n,

$$\frac{\cos \frac{1}{2}X}{\sin \frac{1}{2}Z} = \frac{1}{V(n^2+1)} = \cos v.$$

$$\frac{\cos \frac{1}{2}Y}{\sin \frac{1}{2}Z} = \cos \delta.$$

$$\tan (\delta + 45^\circ) = n.$$

$$\frac{\cos \frac{1}{2}Z}{\sin \frac{1}{2}Y} = \cos \delta'.$$

$$\tan (\frac{\delta + 45^\circ}{2}) = n.$$

$$\frac{\cos \frac{1}{2}Z}{\sin \frac{1}{2}Y} = \cos \delta'.$$

$$ma = \frac{nV^2}{n+1} \tan \delta'.$$

$$ma = \frac{n}{V(\tan^{\frac{1}{2}}X - n^{\frac{1}{2}})}$$

Designating the inclination of m-n on face of the fundamental prism (∞) by p; and on that of the diagonal prism $(\infty-\infty)$ by q, we have

$$\frac{n+1}{n} = \frac{\cos p V^2}{\cos q} \qquad \text{or } \frac{\cot q}{n} = \cos \beta, \text{ and } ma = \frac{\cot q}{\sin \beta}$$

$$\operatorname{Sin} \mathbf{v} = \frac{\cos q}{\sin \frac{1}{2}Z} \qquad n = \tan \mathbf{v} \qquad ma = \tan \frac{1}{2}Z \sin \mathbf{v}.$$

$$n+1 = \frac{\cos p V^2}{\cos \frac{1}{2}X} \qquad \sin \mathbf{v}' = n \cot \frac{1}{2}X \qquad ma = \tan \mathbf{v}'.$$

$$\frac{n+1}{n-1} = \frac{\cos p}{\cos \frac{1}{2}Y} \qquad \sin \delta = \frac{\cos p}{\sin \frac{1}{2}Y} \qquad ma = \frac{nV^2}{n+1} \tan \delta'.$$

h. In m-m.

('cm v' =
$$\frac{1}{a} \cot \frac{1}{2} X$$
. $ma = \tan v'$.
('cm v = $a \cot \frac{1}{2} Z$. $m = \tan v = \frac{\tan \frac{1}{2} T V}{a} (a^2 + 1)$.

1991 that $\frac{1}{2}T \times \cot \frac{1}{2}T$, T, (and in the following cases, U and Z), the corresponding angle of the fundamental octahedron, 1.

$$(2m)^{m} = \frac{m}{m-1}.$$

$$(2m)^{2r} = \frac{1}{a} \cot \frac{1}{2} Y \sqrt{2}.$$

$$2m-1 = \frac{1}{a} \tan \delta' \sqrt{2}.$$

Cos
$$\delta = a\sqrt{\frac{1}{3}} \cot \frac{1}{3}Z$$
. $\frac{m}{m-1} = \tan (\delta + 45^{\circ})$.

$$2m-1 = \frac{v(a^{2}+2) \times \tan \frac{1}{2}U}{a}$$

$$2m-1 = \tan \frac{1}{3}U \times \cot \frac{1}{3}U'$$

$$d. \text{ In } m,$$

$$ma = \cot s. \qquad \cos s = \cot \frac{1}{2}X.$$

$$ma \tan \frac{1}{3}Z\sqrt{\frac{1}{3}}. \qquad m = \frac{\tan \frac{1}{2}Z}{\tan \frac{1}{2}Z}.$$

$$\epsilon. \text{ In } m-\infty,$$

$$ma = \cot s. \qquad \cos s = \cos \frac{1}{3}Y\sqrt{2}.$$

$$ma = \cot s. \qquad \cos s = \cos \frac{1}{3}Y\sqrt{2}.$$

$$ma = \cot \frac{1}{3}Z. \qquad m = \frac{\tan \frac{1}{3}Z}{\tan \frac{1}{3}Z}.$$

$$f. \text{ In } \infty-n, n = \tan \frac{1}{3}X. \qquad \frac{n+1}{n-1} = \tan \frac{1}{3}Y.$$

The angles of the different vertical prisms, in the dimetric system, are the same as those of the forms ∞ -n in the monometric system, as given on page 70—(forms ∞ - $\frac{5}{4}$ to ∞ -5).

IV. TRIMETRIC SYSTEM.

1. Inclinations between planes of different forms.

24. In the trimetric system the forms mPn are octahedrons: that is, for any particular plane mPn on a crystal there will be eight in all, and these extended, produce an octahedron like f. 13.

The inclination of a plane mPn, on another m'Pn', may be ascertained by means of the general formula, p. 62, by substituting being the longer lateral axis) when the forms are

$$m = \overline{n}$$
 and $m' = \overline{n}'$, md , nb for a , b .

 $m' = \overline{n}$, $m' = \overline{n}$,

25. a. For $m-\bar{n}$ on $m'-\bar{\infty}$, having the parameters a:b:c and x':x:c', the formula becomes

Cos
$$W = -\frac{b(aa' + cc')}{MV(a'^2 + c'^2)}$$
.

b. For $m = \overline{n}$ on $\infty = \overline{\infty}$, the formula becomes

$$Cos W = -\frac{ab}{M}$$
c. For $m = \overline{n}$ on $\infty = \overline{n}'$,
$$Cos W = -\frac{a(bb' + cc')}{MV(b'^2 + c^2)}$$

$$\cos W = -\frac{ab}{M}$$
.

$$\operatorname{Cos} W = \frac{a(bb' + cc')}{M\sqrt{(b''^2 + c''^2)}}.$$

A plane men may also be designated $\frac{m}{n} - \frac{1}{n}$, the two expressions ring equivalents, (p. 55); and in calculating the relations of one

plane with another, or their interfacial angles, it is often convenient to make the change from one expression to the other, in order to have the same lateral axis referred to in both.

2. Inclinations between planes of the same form.

26. The form m-n in the trimetric system is represented in the octahedron, f. 13, (except that we here make b the longer lateral axis). Placing X, Y, Z for the angles at the edges so marked, and writing as above,

 $\frac{1}{2}X$ supplement of m-n on $\infty-\check{\infty}$, and $\frac{1}{2}Y$ supplement of m-n on $\infty-\check{\infty}$.

27. Simplifying for the particular cases following:

		_	7.
u.]	In ∞,	$\operatorname{Tan} \frac{1}{2}X' = \frac{c}{b}$	$\operatorname{Tan} \frac{1}{4} Y' = \frac{b}{c}$
b .	∞- <u>n</u> ,	Tan $\frac{1}{2}X = \frac{nc}{b}$	$\operatorname{Tan} \tfrac{1}{2} Y = \tfrac{b}{nc}$
o.	∞- " ,	$\operatorname{Tan} \tfrac{1}{2} X = \tfrac{c}{nb}$	$Tan \frac{1}{2}Y = \frac{nb}{c}$
d.	<i>m</i> - ŏ,	$\operatorname{Tan} \frac{1}{2} Y = \frac{b}{ma}$	Tan $\frac{1}{2}Z = \frac{mc}{b}$
e.	1-‰,	$\operatorname{Tan}\tfrac{1}{3}Y'=\tfrac{b}{a}$	$\operatorname{Tan} \ \ \tfrac{1}{2}\mathbb{Z} = \frac{a}{b}$
f.	m-∞̃	$\operatorname{Tan} \frac{1}{4}X = \frac{c}{ma}$	$\operatorname{Tan} \frac{1}{2} Z = \frac{ma}{c}$
g.	1-œ	$\operatorname{Tan} \frac{1}{2}X' = \frac{c}{a}$	$\operatorname{Tan}\tfrac{1}{2}Z' = \frac{a}{c}$

3. Dimensions of forms.

28. Let α = the inclination of the macrodiagonal terminal edge on the vertical axis;

Let β = the inclination of the brachydiagonal terminal edge on the vertical axis;

Let γ = the inclination of a basal edge on the macrodiagonal;

Then for
$$m'$$
- n' , $a':b':c'=$

$$\begin{cases}
1: \tan \alpha : \tan \beta, \\ \cot \alpha : 1: \tan \gamma, \\ \cot \beta : \cot \gamma : 1.
\end{cases}$$

29. The angles α , β , γ are determined by the following equations:

$$Cos \alpha = \frac{\cos \frac{1}{2} Y}{\sin \frac{1}{2} X} \qquad Cos \beta = \frac{\cos \frac{1}{2} X}{\sin \frac{1}{2} Y}$$

Sin
$$\alpha = \frac{\cos \frac{1}{2}Z}{\sin \frac{1}{2}Z}$$
. Cos $\gamma = \frac{\cos \frac{1}{2}Z}{\sin \frac{1}{2}Z}$.
Sin $\beta = \frac{\cos \frac{1}{2}Z}{\sin \frac{1}{2}Z}$. Sin $\gamma = \frac{\cos \frac{1}{2}Z}{\sin \frac{1}{2}Z}$.

Tan $\beta = \tan \frac{1}{2}X \sin \alpha$; $\tan \alpha = \cot \frac{1}{2}Y \tan \beta$. Cot $\alpha = \tan \frac{1}{2}Z \sin \gamma$.

Sin $\alpha = \cot \frac{1}{2}X \tan \beta$; $\cos \alpha = \cot \frac{1}{2}X \tan \gamma$. Sin $\beta = \cot \frac{1}{2}Y \tan \alpha$; $\cos \beta = \cot \frac{1}{2}Y \cot \gamma$. Sin $\gamma = \cot \frac{1}{2}Z \cot \alpha$; $\cos \gamma = \cot \frac{1}{2}Y \cot \beta$.

30. By comparing the angles α , β , γ , with the corresponding angles of the fundamental form, by means of the relations of a, b, c, to these angles, the relative values of m and n for that form may be determined.

Distinguishing α , β , γ and X, Y, Z, of the derivative forms, by secents:

- (a.) In the form m, α being determined by one of the above equations, both for m and the fundamental form P, then $m = \cot \alpha'$ tan α ; so from β , $m = \cot \beta'$ tan β ; or from Z, $m = \tan \frac{1}{2}Z' \cot \frac{1}{2}Z$.
 - (b.) In $1-\bar{n}$, $n=\tan \frac{1}{2}X' \cot \frac{1}{2}X = \tan \beta' \cot \beta = \tan \gamma' \cot \gamma$.
 - (c.) In $1-\tilde{n}$, $n=\tan \alpha' \cot \alpha = \tan \frac{1}{2} Y' \cot \frac{1}{2} Y = \cot \gamma' \tan \gamma$.
 - (d.) In m = m, $m = \cot \frac{1}{2}X' \tan \frac{1}{2}X = \cot \beta' \tan \beta = \cot \gamma' \tan \gamma$.

For determining m and n, we deduce from the equations,

- (e.) For the forms ∞ and and $\infty \tilde{n}$ (§ 27 a, b), $n = \tan \frac{1}{2}X + \tan \frac{1}{2}X$; $n = \tan \frac{1}{2}Y + \tan \frac{1}{2}Y$.
- (f.) For the forms ∞ and ∞_{-n} , $n=\tan \frac{1}{2}X'+\tan \frac{1}{2}X$, $n=\tan \frac{1}{2}Y'+\tan \frac{1}{2}Y'$, in which the accented letters pertain to the form ∞ . Also,
 - (g.) From the equations for $m-\tilde{z}$ and $1-\tilde{z}$,

 $m = \tan \frac{1}{2} Y' + \tan \frac{1}{2} Y,$ $m = \tan \frac{1}{2} Z + \tan \frac{1}{2} Z'.$

(h.) From the equations for $m-\bar{\infty}$ and $1-\bar{\infty}$,

 $m=\tan \frac{1}{2}X'+\tan \frac{1}{2}X,$ $m=\tan \frac{1}{2}Z+\tan \frac{1}{2}Z'.$

4. Combinations in the Trimetric System.

31. On this subject see the general laws on pages 53 to 56, which contain many of the specific cases below.

In this system, as in the preceding, forms with a horizontal intersection have n=n. In a rhombic octahedron, mI' planes truncating or bevelling the terminal edges have m'=m; but as one edge is connected with the macrodiagonal, and the other with the brachydiagonal, the planes differ,—those of the macrodiagonal edge being $m-\bar{n}$ or $m-\bar{\infty}$, and those of the brachydiagonal are or $m-\bar{\infty}$.

In the following table, forms are said to be of the same kind,

when connected with the same axis, and consequently having the same mark, — or —, placed above their signs.

V. HEXAGONAL SYSTEM.

4. " repl. I-E. of m-n and ∞-ŏ,

32. In the hexagonal system there are three lateral axes intersecting at 60°. The form m-n completed is a double twelve-sided pyramid or berylloid, (f. 124); m and m-2 are double six-sided pyramids or quartzoids, (like f. 122 in form), the series m-2 intermediate to the series m, (see f. 121); ∞ and ∞ -2 are hexagonal prisms, respectively corresponding to the pyramids. ∞ -n, except when n=2 represents twelve-sided prisms. mR (equivalent to form $\frac{(m)}{2}$) stands for rhombohedrons, (R, fig. 126, and other rhombohedrons of the same series). The use of the signs + and - for rhombohedrons and scalenohedrons is explained on page 48. The scalenohedron has the general sign $\pm \frac{(m \cdot n)}{2}$. Designated with reference to the axis of that rhombohedron from which they are derived, they come under the expression mR^n , in which mequals the semi-axis of mR, and n is a coefficient, which multiplied into m will give the semi-axis of the form mR^n . The expression $\frac{(m\cdot n)}{2}$ is reduced to the form $m'R^{n'}$ by making

$$m' = \frac{m(2-n)}{n}$$
, and $n' = \frac{n}{2-n}$,

and conversely the latter is reduced to the former by making

$$m = m'n'$$
, and $n = \frac{2n'}{n'+1}$.

33. For each mR there is a series of scalenohedrons mR^n , corresponding to a replacement of the lateral edges of the rhombohedron mR, in which n may have any value; when this value

is infinite, the form is the prism $mR\infty$, and this is equivalent to x-2, since the prism is necessarily a prism diagonal to the fundamental prism. The latter sign is the one which is commonly

used for the prism.

The pyramidal hemihedral forms, represented in f. 136, p. 48, have the symbol $\frac{l}{r} \frac{(m-n)}{2}$ or $\frac{r}{l} \frac{(m-n)}{2}$, $\frac{l}{r}$ or $\frac{r}{l}$ being used according as the planes are to the left or right above. The gyroidal hemihedral forms, analogous to f. 137, p. 48, have the symbol $r \frac{(m-n)}{2}$ or $l \frac{(m-n)}{2}$. The corresponding tetartohedral forms have the same symbols, except that 4 is written for 2; or else the equivalent $\frac{m'R^{n'}}{2}$, with r or l prefixed.

1. Inclinations between planes of different forms.

34. The formula for
$$m$$
- n on m' - n' is as follows—making $M = \sqrt{(4m^2a^2(n^2-n+1)+3n^2)}$ and $M' = \sqrt{(4m'^2a^2(n'^2-n'+1)+3n'^2)}$.

$$Cos Q = -\frac{2mm'a^2(2nn'-n-n'+2)+3nn'}{MM'}$$

35. The following table contains the same for more simple cases.

	Q	90-n	m-2
R'-a	n'√8 M'	$\frac{m'a(2nn'-n-n'+2)}{M'v(n^2-n+1)}$	$\frac{n'(mm'a^2+1)\sqrt{8}}{M'\sqrt{(m^2a^2+1)}}$
m'-2	$\frac{1}{\sqrt{(m^2a^2\times 1)}}$	$\frac{m'an\sqrt{3}}{\sqrt{(m'^2a^2+1)\sqrt{(n^2-n+1)}}}$	$\frac{mm'a^2+1}{\sqrt{(m'^2a^2+1)\sqrt{(m^2a^2+1)}}}$
x-m'	0	$\frac{2nn'-n-n'+2}{2\sqrt{(n'^2-n'+1)}\sqrt{(n^2-n+1)}}$	

36. The formulas for the rhombohedral forms vary, as the forms are of like or unlike signs. In the following:—

$$N = \sqrt{(m^2a^2(3n^2+1)+3)}$$
 and $N' = \sqrt{(m'^2a^2(3n'^2+1)+3)}$.

37. The cosine of the inclination of

$$\begin{aligned}
& + mR^{n} \text{ on } + m'R^{n'} \\
& - mR^{n} \text{ on } - m'R^{n'} \\
& + mR^{n} \text{ on } - m'R^{n'} \\
& - mR^{n} \text{ on } + m'R^{n'} \\
& - mR^{n} \text{ on } + m'R^{n'} \\
\end{aligned} = - \frac{mm'a^{2}(3nn'\pm 1)\pm 3}{NN'}$$

the upper sign being used in each of these and the following quations, for the angles between planes inclined to the same pole of the vertical axis, and the lower for the angle between planes inclined towards different poles.

38. These simplified, become for

these simplified, become for
$$+mR^{\bullet}$$
 on $+m'R$ $=$ $-mm'a^{2}(3n\pm1)\pm3$ $-mR^{\bullet}$ on $-m'R$ $=$ $-mm'a^{2}(3n\pm1)\pm3$ $-mR^{\bullet}$ on $-m'R$ $=$ $-mm'a^{2}(3n\mp1)\pm3$ $-mR^{\bullet}$ on $+m'R$ $=$ $-mm'a^{2}(3n\pm1)\pm3$ $-mR^{\bullet}$ on $+m'R$ $=$ $-mR^{\bullet}$ $=$

$$mR^{n} \text{ on } m'-2 = -\frac{(mnm'a^{2}\pm 1)\sqrt{3}}{N\sqrt{(m'^{2}a^{2}+1)}} \cdot mR^{n} \text{ on } O = -\frac{\sqrt{3}}{N}.$$

39. Also when the forms $\frac{(m-n)}{2}, \frac{(m'-n')}{2}$, are of the same sign,

Cos
$$P = -\frac{2mm'a^2(2nn'\mp n\mp n'\pm 2)\pm 3nn'}{MM'}$$

40. When of different signs,

Cos
$$P = -\frac{2mm'a^2(nn' \pm n \pm n' \mp 2) \pm 3nn'}{M M'}$$
.

2. Inclination between planes of the same form.

41. For the form m-n (f. 124) we have for the inclinations between the planes, M having the value on the preceding page—

Cos
$$\frac{1}{2}X = \frac{ma(2-n)}{M}$$
. Cos $\frac{1}{2}Y = \frac{ma(n-1)\sqrt{3}}{M}$. Cos $\frac{1}{2}Z = \frac{n\sqrt{3}}{M}$.

42. a. Representing the inclination of two planes over the axial basal angle (that to which the edge X extends) by T, and that over the adjacent basal angle, (to which Y extends), by U,

Tan
$$\frac{1}{2}T = \frac{man\sqrt{3}}{\sqrt{(m^2a^2(2-n)^2+3n^2)}}$$
. Tan $\frac{1}{2}U = \frac{ma(n+1)}{\sqrt{3}\sqrt{(m^2a^2(n-1)^2+n^2)}}$.

b. For $m - \frac{m}{m-1}$; writing S for $\sqrt{(4a^2(m^2 - m + 1) + 3)}$

$$\cos \frac{1}{2}X = \frac{a(m-2)}{S}. \qquad \cos \frac{1}{2}Y = \frac{a\sqrt{3}}{S}. \qquad \cos \frac{1}{2}Z = \frac{\sqrt{3}}{S}.$$

$$\operatorname{Tan} \frac{1}{2}T = \frac{ma\sqrt{3}}{\sqrt{(a^2(m-2)^2+3)}}. \qquad \operatorname{Tan} \frac{1}{2}U = \frac{(2m-1)a}{\sqrt{3}\sqrt{(a^2+1)}}.$$

Tan
$$\frac{1}{2}T = \frac{ma\sqrt{3}}{\sqrt{(a^2(m-2)^2+3)}}$$
. Tan $\frac{1}{2}U = \frac{(2m-1)a}{\sqrt{3}\sqrt{(a^2+1)}}$

c. For m, in which Z=U.

Tan $\frac{1}{2}X = \frac{V(m^2a^3+1)V3}{ma}$. Tan $\frac{1}{2}Z = 2maV\frac{1}{8}$. Tan $\frac{1}{2}T = \frac{maV3}{V(m^3a^3+3)}$.

d. For m-2, in which Z=T,

Tan
$$\frac{1}{2}I' = \frac{\sqrt{(3m^2a^2+4)}}{ma}$$
. Tan $\frac{1}{2}Z = ma$. Tan $\frac{1}{2}U = \frac{ma\sqrt{3}}{\sqrt{(m^2a^2+4)}}$.

e. For z-n.

Tan
$$\frac{1}{2}X = \frac{n \cdot \sqrt{3}}{2-n}$$
. Tan $\frac{1}{2}Y = \frac{n+1}{(n-1)\sqrt{3}}$.

f. For $\frac{m \cdot n}{2}$ (p. 46), in which X is the shorter terminal edge, I' the longer, Z a basal edge (=T of m-n),

$$\operatorname{Cos} \frac{1}{2}X = \frac{\operatorname{man} V^{3}}{M}. \qquad \operatorname{Sin} \frac{1}{2}Z = \frac{\operatorname{man} V^{3}}{M}.$$

 $\sin \frac{1}{2}Z = \cos \frac{1}{2}X + \cos \frac{1}{2}Y = 2 \cos \frac{1}{2}(Y + X) \cos \frac{1}{2}(Y - X)$. For $\cos \frac{1}{2}Y$, the same formula as in m-n.

g. For
$$\pm \frac{(m)}{2}$$
 or $\pm mR$, in which $Y=180^{\circ}$,

$$\cos X = \frac{2m^2a^2 - 3}{4m^2a^2 + 3} = -\cos Z. \qquad \tan \frac{1}{2}X = \frac{\sqrt{(m^2a^2 + 3)}}{ma\sqrt{3}}.$$

In R, Tan $\frac{1}{2}X = \frac{\sqrt{(a^2+3)}}{a\sqrt{3}}$; and if $a^2 = \frac{3}{3}$, $X = 90^\circ$, and the rhombohedron is a cube.

Designating the inclination, in mR, of the inclined diagonal on the vertical axis, by a, and that of a terminal edge on the same

Cot $\alpha = 2ma\sqrt{1}$. Cot $\beta = ma\sqrt{1}$.

The plane angle A (angle at vertex) in mR, and the volume V, may be found by the equations,

$$\cos A = \frac{2m^2a^3 - 8}{2(m^2a^3 + 3)}. \qquad V = 4ma\sqrt{3}.$$

h. For mR^n , in which X, Y, Z, are used as above,

Tan
$$\frac{1}{2}X = \frac{V(m^2a^2(3n-1)^2+12)}{ma(n+1)V^3}$$

h. For
$$mR^n$$
, in which X , Y , Z , are used as above,

$$\operatorname{Tan} \frac{1}{2}X = \frac{V(m^2a^2(3n-1)^2+12)}{ma(n+1)V^3}.$$

$$\operatorname{Tan} \frac{1}{2}Y = \frac{V(m^2a^2(3n+1)^2+12)}{ma(n-1)V^3}.$$
Tan $\frac{1}{2}Z = \frac{manV^3}{V(m^2a^2+3)^3}$.

See also § f , above.

i. For
$$\infty R^n$$
,
 $\cos X = \frac{3n^2 - 6n - 1}{2(3n^2 + 1)}$. Cos $Y = \frac{3n^2 + 6n - 1}{2(3n^2 + 1)}$. Cos $Z = \frac{8n^2 - 1}{3n^2 + 1}$.

- 3. Determination of m and n by inspection.
- 43. a. As in other systems, forms m-n and m'-n', or mR^n and $m'R^{n'}$, making horizontal intersections, have n=n', (f. 121).

b. Two forms m-n and m'-n' making intersections parallel to a diagonal edge, have m=m', (f. 128).

c. Two forms mR^n and $m'R^{n'}$, whose lateral (called also, basal) edges are parallel, have m=m', (f. 128).

d. For each scalenohedron mR^n , (f. 127), there is (1) an inscribed rhombohedron m'R of like sign, (+ or -), whose lateral edges coincide with those of the scalenohedron; having m=m'.

(2). A rhombohedron m''R of like sign, whose terminal edges coincide with the shorter terminal edge (X) of the scalenohedron, having $m''=\frac{1}{2}m(3n-1)$, (4, f. 131; a rhombohedron having its terminal edges coincident with X, would have its faces parallel to planes 4 in this figure).

(3). A rhombohedron m'''R of unlike sign, whose terminal edges coincide with the longer terminal edge (Y) of the scalenohedron, having $m'''=\frac{1}{2}m(3n+1)$, (5, f. 132).

e. The rhombohedron m'R truncating edge Y of mR^n , has $m'=\frac{1}{4}m(3n+1)$, (f. 133).

The rhombohedron—m''R, truncating edge X of mR^n , has $m' = \frac{1}{4}m(3n-1)$, (f. 134).

 m^n , in the table below, is equivalent to mR^n .

```
f. m-n 1. Edge Y trunc. by plane m',
          2. Y-basal_angle repl. by m', I-E. par. to other
                term. E.
          3. Term. angle repl. by m', faces rhombs,
          4. Edge X trunc. by m-2,
                                                                                   2m(n+1)
          5. X-basal A. repl. by m'-2, I-E. par. to other term. E. m'=
                                                                            m'=\frac{2m(2n-1)}{n}
          6. Repl. of term. angle by m'-2, faces rhombs,
   g. m 1. Repl. of basal A. with 4 pl. m' \cdot n', I-E. par. to \underline{m'(n'+1)}_{-2}
                vertical on face of m,
          2. Repl. of basal A. with 4 pl. m'-n', I-E. par. to \frac{m'}{n'} = m
                term E. of m,

    Term. E. trunc. by m'-2, (f. 121), or bev. by m'-n', m'=m
    Basal angle repl. by m'-2, I-E. par. to vert. of m m'=4m

                 (42, £ 121),

    Bassl angle repl. by m'-2, I-E. par. to term. E. of
m, (22, f. 121),

          6. Term. angle repl. by m'-2, faces rhombs,
                                                                             m'(n'+1)_{\underline{\phantom{a}}}
h. m-2 1. Term. edge bevelled by m'-n',
          2. Basal A. repl. by 4 pl., I-E. par. to vert. on m-2, m'=m
                                     " I-E. par. to term. E. of m-2,
          4. Term. edge trunc. by m', (42 and 1, f. 121),

    Basal A. repl. by 2 pl. I-E. par to vert. on m-2,
(12 and 1, f. 124),

    Basal A. repl. by two planes m', I-E. par. to
term. E. of m-2,

          7. Term A. repl. by 6 rhombs. m',
i. mR<sup>a</sup> 1. m'a' of like sign, bevel edge X (f. 184),
2. " " Y (f. 188),
                                                                              m'(8n'-
                                                                              m'(8n'+1)=
          3. m'n' repl. basal A. by 2 pl. incl. on X, I-E. par.
          to edge Y of m<sup>a</sup>
4. Ibid. incl. on Y, I-E. par to X,
5. m<sup>a</sup> of unlike sign, bev. edge X, (f. 184),
6. m'a of unlike sign, repl. basal A, I-E. par to Y
                                                                             m'(8n'+1)=
m'(8n'-1)=
m'(8n'+1)=
                                                                              m'(8n'-1)=m(8n+1)
 k. mR 1. m'm' of like sign, bev. term. E. of m, (f. 131),
                                                                              \frac{1}{4}m'(3n'-1)=m
          2. m'a' of like sign, repl. lat. A, I-E. par. to incl.
                diag.
                                                                              }m'(3n'+1)=m
```

```
    m'" of like sign, replace lateral edges, m'=m
    m'" of unlike sign, bev. term. E. of m, (f. 132), ½m'(3n'+1)=m
    m'" of unlike sign, repl. lat. A, I-E.par. to incl.

                     diag.

m' of unlike sign, trunc. term. E, (f. 125),

m' of unlike sign, repl. bas. A, I-E. par. to incl.

diag. (sim. to f. 125),

m'-2, bev. term. E. of m,
                                                                                                                            \frac{1}{4}m'(3n'-1)=m
                                                                                                                            m' = \frac{1}{2}m
                                                                                                                           m'=2m
                                                                                                                           m'=1m
                                                                                                                           m' = \frac{1}{4}m
              9. m'-2, repl. bas. A, I-E. par to incl. diag.

    m-2, 1. Bev. of altern. term. E. by m'a'
    Trunc. of altern. term. E. by m'R,

                                                                                                                            \frac{1}{4}m'(8n'+1)=m
```

44. a. If a plane $m''R^{m''}$ forms parallel intersections with two planes mR^n and $m'R^{n'}$, then

$$m''n''(m-m')\pm m'n'(m''-m)-mn(m''-m')=0$$

using the upper sign, when the planes incline to the same pole of the vertical axis, and the lower when to opposite poles.

b. If the planes are m''-2, mR^n , $m'R^{n'}$, then

$$m''(m-m')+mm'(n+n')=0.$$

c. If the planes are $m''R^{nn'}$,— $m'R^{n}$, mR^{n} ,

$$m''n''(m+m')\mp m'n'(m''-m)-mn(m''+m')=0.$$

d. If the planes are m''-2, $-m'R^{n}$, mR^{n} ,

$$m''(m+m')-mm'(n\pm n')=0.$$

e. If the planes are $m''R^{n}''$, m'-2, mR^{n} ,

$$m''(n''-n)m\pm m'(m-m'')=0.$$

- 4. Determination of m, n, and axis a, by calculation.
- 45. a. From the angles X, Y, Z, of m-n,

$$\frac{ma(2-n)}{n\sqrt{3}} = \frac{\cos \frac{1}{2}X}{\cos \frac{1}{2}Z} = \frac{ma(n-1)}{n} = \frac{\cos \frac{1}{2}Y}{\cos \frac{1}{2}Z}.$$

$$\frac{2-n}{n-1\sqrt{3}} = \frac{\cos \frac{1}{2}X}{\cos \frac{1}{2}Y}$$

Cos $= \cos \frac{1}{2}X + \sin \frac{1}{2}Z$; and, $n + (2 - n) = \sqrt{3} \tan \nu$.

Cos
$$\checkmark$$
 = cos $\frac{1}{2}Z$ +sin $\frac{1}{2}X$; and, ma = tan \checkmark .
Cos δ = cos $\frac{1}{2}Y$ +sin $\frac{1}{2}Z$; and, $(n+1)$ + $(n-1)$ = \checkmark 3 tan δ .
Cos δ' = cos $\frac{1}{2}Z$ +sin $\frac{1}{2}X$; and, ma = tan δ' n \checkmark 3+ $(n+1)$.

$$\frac{2-n}{n-1} = \frac{\sqrt{3}\cos\frac{1}{2}X}{\cos\frac{1}{2}Y}; ma = \cot s; \cos s = \frac{n\sqrt{3}}{2-n}\cot\frac{1}{2}X.$$
Also, $ma = \tan\frac{1}{2}Z(\sin 150^{\circ} - \delta) = \tan Z\frac{1}{2}\sin v.$

b. From the angles X, Z, and U, of $m_{\overline{m-1}}^{m}$,

Sin $Z = \cos \frac{1}{2}Z' \cot \frac{1}{2}X\sqrt{3}$; $ma = \tan (\frac{1}{2}Z' + \frac{1}{5}')$; Z' is Z of 2-2. Cos $\delta = a \cot \frac{1}{2}Z$; $2m - 1 = \tan \delta \sqrt{3}$.

2
$$m-1=\tan \frac{1}{2}U^{\frac{\sqrt{3}}{a}}\sqrt{(a^2+1)};$$

Fince we have for U' in the form 2-2,

Tan $\frac{1}{2}U = a\sqrt{3} + \sqrt{(a^2+1)}$, therefore $2m-1=3 \tan \frac{1}{2}U \times \cot \frac{1}{2}U$, whence the value of m may be obtained. The inclination of 2-2 on a, (see f. 151 and 344 of Quartz), diminished by 90° is $\frac{1}{2}U'$; and that of any plane of the oblique series on a diminished by 900

is $\frac{1}{2}U$ for that plane.

Planes in the same series, between 2-2 and R, or 1, (f. 344), are of the form m-m; and taking the corresponding $\frac{1}{2}U$ of such a form, (that is, the angle m-m on i diminished by 90°), and working the above equation, the resulting value of m is the value in the form m-m.

c. From a pyramid m,

$$ma = \frac{\sqrt{3}}{2} \tan \frac{1}{2}Z. \qquad m = \frac{\tan \frac{1}{2}Z}{\tan \frac{1}{2}Z} = \frac{\tan \frac{1}{2}U}{\tan \frac{1}{2}U}.$$

 $ma = \cot \epsilon$; $\cos \epsilon = \sqrt{3} \cot \frac{1}{2}$

Z and U' are the corresponding angles in the pyramid P.

d. From a pyramid m-2,

$$m = \frac{\tan \frac{1}{2}Z}{a}$$
. $m = \frac{\tan \frac{1}{2}Z}{\tan \frac{1}{2}Z'}$. $a = \tan \frac{1}{2}Z''$.

ma=cot ϵ , when $\cos \epsilon = 2\cos \frac{1}{2}Y$.

Z' is the corresponding angle in the form 1-2.

e. From
$$\infty - n$$
, $\frac{n}{2-n} = \sqrt{\frac{1}{3}} \tan \frac{1}{3}X$; $\frac{n+1}{n-1} = \sqrt{3} \tan \frac{1}{3}Y$.

f. From a scalenohedron $\frac{(m-n)}{2}$,

$$n-1 = \frac{\cos \frac{1}{4}Y}{\cos \frac{1}{4}X}. \qquad n = \frac{\sin \frac{1}{4}Z}{\cos \frac{1}{4}X}. \qquad n = \frac{\sin \frac{1}{4}Z}{\sin \frac{1}{4}Z - \cos \frac{1}{4}Y}.$$
g. From a rhombohedron mR ,

$$ma = \frac{\sqrt{3} \cot a}{2} = \sqrt{3} \cot \beta$$
. $m = \frac{\cot a}{\cot a'} = \frac{\cot \beta}{\cot \beta'}$

.. log. $ma = \log$. cot $\alpha + 9.9375306 = \log$. cot $\beta + 0.2385606$. α and β are used as in page 81; and α' and β' are corresponding

Also, $a^2 = \frac{3(1+\cos X)}{2-4\cos X}$ gives the length of the vertical axis. It should be noted that cos X is minus when X is an obtuse angle.

Also, $\cos \xi = \cot \frac{1}{2}X\sqrt{\frac{1}{3}}$; and $ma = \cot \xi\sqrt{3}$.

h. From a scalenohedron mR^n ,

$$\frac{n-1}{n+1} = \frac{\cos \frac{1}{2}Y}{\cos \frac{1}{2}X}; \qquad \frac{n+1}{2n} = \frac{\cos \frac{1}{2}X}{\sin \frac{1}{2}Z}; \qquad \frac{n-1}{2n} = \frac{\cos \frac{1}{2}Y}{\sin \frac{1}{2}Z}.$$

From
$$X$$
, $\cos \beta = \frac{3n-1}{(n+1)\sqrt{3}} \cot \frac{1}{2} X$; and then $m = \frac{2\sqrt{3} \cot \beta}{a(3n-1)}$.

From
$$Y$$
, $\cos \alpha = \frac{3n+1}{(n-1)\sqrt{8}} \cot \frac{1}{2} Y$; and then $m = \frac{2\sqrt{8} \cot \alpha}{\alpha(3n+1)}$.

From
$$Z$$
, $\cos \beta' = \frac{1}{n\sqrt{8} \cot \frac{1}{2}Z}$; and then $m = \frac{\cot \beta' \sqrt{3}}{a}$.

From X of mR^n , and X' of $\frac{1}{2}m(3n-1)R$, $(3n-1)+(n+1)=\tan \frac{1}{2}X \cot \frac{1}{2}X'$

From Y of mR^n and X" of $\frac{1}{4}m(3n+1)R$,

 $(3n+1)+(n-1)=\tan \frac{1}{4} Y \cot \frac{1}{4} X$."

From Z' (the lateral edge-angle) of the inscribed rhombohedron, and X, Y, or Z,

 $n=\tan (\varphi - \frac{1}{2}Z') \cot \frac{1}{2}Z';$ when, $\sin \varphi = 2 \cos \frac{1}{2}X \cos \frac{1}{2}Z'.$

 $n=\tan (\varphi + \frac{1}{2}Z) \cot \frac{1}{2}Z'$; when $\sin \varphi = 2 \cos \frac{1}{2}X \cos \frac{1}{2}Z'$.


 $n=\tan \frac{1}{2}Z \cot \frac{1}{2}Z'$. nR_n , in which m is constant, n vari

In the series mR, mR^n , in which m is constant, n varies as the $\tan \frac{1}{2}Z$; an n in any mR^n of the series equals $\tan \frac{1}{2}Z$ of the mR^n divided by tangent half the corresponding angle of mR.

II. CLINOMETRIC SYSTEMS.

I. MONOCLINIC SYSTEM.

46. The annexed figure represents the form ±1, in the monoclinic system; a, b, c, are the axes. The inclination of a on bis oblique, and the angle is marked γ , (called C beyond); bis the clinodiagonal, c the orthodiagonal. The upper faces in front are +1, the lower -1; and so with any forms m, and also m-n and m-on they are relatively + and -, above and below the clinodiagonal. $\pm m$ - ∞ is a form truncating the edge Xabove or X' below, and ∞ - ∞ is mother in the same vertical series, on the front angle, parallel to the vertical axis. Planes pertaining to the clinodiagonal planes on the side angles and



edges of the octahedron) are designated m_{-n} , $m_{-\infty}$, $\infty_{-\infty}$; the planes $m_{-\infty}$ are the same above and below the orthodiagonal. The inner or rhombic prism in f. 25 is described by the expression (x, x); and the outer prism by (x, x), (x, x); the inner in f. 112 by (x, x), (x,

47. An octahedral plane in the preceding figure is inclined weach of the three axial planes or sections. Let the inclination

of +1 on the clinodiagonal section be designated by X; on the orthodiagonal section by Y; on the basal section by Z; and the corresponding inclinations of -1 by X', Y', Z'. The angles X, X', are each half the interfacial angles of the octahedron at the edges X, X'. Let us represent also the inclination of

Edge
$$X$$
 on a by μ , X on b by v , Y on a by α .

48. Then,

Tan
$$\begin{cases}
X = \frac{cV(a^2 + b^3 \mp 2ab \cos C}{ab \sin C} & \text{Tan } \begin{cases}
Y = \frac{b \sin CV(a^2 + c^3)}{c(a \mp b \cos C)}.
\end{cases}$$
Tan
$$\begin{cases}
Z = \frac{a \sin CV(b^3 + c^3)}{c(b \mp a \cos C)}.$$

The lower sign is used in each case for the angles X', Y', Z'.

49. In terms of the angles μ , μ' , π , σ , the tangents of the same angles are as follows:

$$\begin{array}{lll} \operatorname{Tan} & X = \frac{\tan \sigma}{\sin (C + \mu)} = \frac{\tan \pi}{\sin \mu}. & \operatorname{Tan} & Y = \frac{\tan \mu}{\sin \pi}. & \operatorname{Tan} & Z = \frac{\tan \left(C + \mu \right)}{\sin \sigma}. \\ \operatorname{Tan} & X' = \frac{\tan \sigma}{\sin \left(C - \mu' \right)} = \frac{\tan \pi}{\sin \mu'}. & \operatorname{Tan} & Y' = \frac{\tan \mu'}{\sin \pi}. & \operatorname{Tan} & Z' = \frac{\tan \left(C - \mu' \right)}{\sin \sigma}. \end{array}$$

It will sometimes be convenient to observe, that $C+\mu=180^{\circ}-\nu$, and $C-\mu'=\nu'$; and consequently, $\sin{(C+\mu)}=\sin{\nu}$, and $\sin{(C-\mu')}=\sin{\nu'}$.

50. The values of the angles μ , μ' , ν , ν' , π , σ , may be obtained by either of the following formulas:

$$\operatorname{Tan} \left\{ \begin{array}{l} \mu = \frac{b \sin C}{a \mp b \cos C}. & \operatorname{Tan} \pi = \frac{c}{a}. & \operatorname{Cos} \mu = \frac{\cos Y}{\sin X}. & \operatorname{Cos} \nu = \frac{\cos Z}{\sin X}. \\ \operatorname{Tan} \left\{ \begin{array}{l} \nu = \frac{a \sin C}{b \mp a \cos C}. & \operatorname{Tan} \sigma = \frac{c}{b}. & \operatorname{Cos} \mu' = \frac{\cos Y'}{\sin X'}. & \operatorname{Cos} \nu' = \frac{\cos Z'}{\sin X}. \\ \operatorname{Cos} \pi = \frac{\cos X}{\sin Y} = \frac{\cos X'}{\sin Y'}. & \operatorname{Cos} \sigma = \frac{\cos X}{\sin Z} = \frac{\cos X'}{\sin Z'}. \end{array} \right.$$

51. a. In the form ∞ ,

Tan
$$X = \frac{c}{b \sin C} = \tan X' = \cot Y;$$
 Tan $\begin{cases} Z = \mp \frac{\tan C V (b^3 + c^3)}{c} \end{cases}$
b. In $\pm 1 \cdot \omega$,
Tan $\frac{Y}{Y'} = \frac{b \sin C}{a \mp b \cos C}.$ Tan $\begin{cases} Z = \frac{a \sin C}{b \mp a \cos C}. \end{cases}$
c. In $1 \cdot \infty$,

Tan
$$X=\tan X' = \frac{c}{a \sin C}$$
 · Tan $Z=\tan Z' = \frac{a \sin C}{c} = \cot X$.
Tan $\frac{Y}{Y'} = \frac{\tan C V(a^3 + c^3)}{c}$

By writing ma for a these formulas apply to $\pm m$ - ∞ and m- ∞ .

d. The equation for Z in the prism ∞ , gives the inclination of the face of an oblique rhombic prism on its lateral faces, that is,

of plane 0 on ∞ , or any ∞ -n. The same angle may be obtained by the equations—putting II for the angle,

Cos
$$\Pi = \cos C \sin X$$
; Sin $\Pi = \frac{\cos X}{\cos \sigma}$.

The angle X here is the angle of that name in the prism ∞ -n, whose inclination on 0 is desired.

In any form m-n, Y is the supplement of the inclination of a face of m-n on ∞ - ∞ ; the angle of X is the supplement of the inclination of m-n on ∞ - ∞ ; the angle Z added to the angle between 0P and the corresponding ∞ -n (angle Π) equals the inclination of a face of m-n on $\infty-n$.

Determination of the lengths of the axes.

52. From C, and X in ∞ , $c=\tan X \sin C \times b$. From C and X, in $1-\infty$, $a=c+\tan X \sin C$. Also, for the relations of a:b:c,

$$1: \frac{\sin \mu}{\sin (C+\mu)}: \tan \sigma, \qquad 1: \frac{\sin \mu'}{\sin' (C-\mu')}: \tan \sigma.$$

$$\frac{\sin (C+\mu)}{\sin \mu}: 1: \tan \sigma, \qquad \frac{\sin (C-\mu')}{\sin \mu'}: 1: \tan \sigma.$$

$$a:b=\sin \mu:\sin \nu$$

For the angle C,

Tan
$$C=\frac{2 \sin \mu \sin \mu'}{\sin (\mu-\mu')}=\frac{2 \sin \nu \sin \nu'}{\sin (\nu-\nu')}$$
.

Rules for determining the signs of planes.

- 53. The rules deduced on pages 53 to 56 apply here, as well as to the other systems.
 - 1. Two forms whose faces inclined to the same pole of the vertical axis form
 - \bullet I-E parallel to the basal section, have n'=n.
- i. I-K. par. to the orthodisgonal E., and both planes pertaining to the clinodiogonal,

have
$$\frac{m'}{n}$$
; both to the orthodiagonal, $m'=m$; the two to different diagonals; $\frac{m'}{n}=m$,

'he accented letters referring to the form on the orthod. edge. c. I-E. par. to the clinod. E. and both partaining to the clinod., m'=m; both to the

whod,
$$\frac{m'}{m} = \frac{m}{n}$$
; the two to different diagonals, $m' = \frac{m}{n}$

- 2 Planes trunc. or bev. clined. E. of $\pm m \cdot \hat{n}$ belong to $\pm \frac{m}{n} \cdot \infty$, or $\pm \frac{m}{n} \cdot n'$.
- Rbe. pl. repl. clinod. A. of intersection of ±m and ∞, is ±2m-∞.
 Plane trunc. E. between+m or—m and ∞ inclined to different poles, is 2m-∞.
 Plane trunc. E. between +m or —m and the pairs and faces ∞-∞ or ∞-∞, is then or man. Hence, planes whose I-E. with 1 are par. to clinod. or orthod.

IL TRICLINIC SYSTEM.

54. All the axial intersections in this system are oblique. As in the trimetric system, the longer lateral axis and the axial section corresponding is called the *macrodiagonal*, the shorter the *brachydiagonal*. The fundamental octahedron (f. 119) has only opposite faces similar; the upper are respectively 1 and 1', and the lower -1 and -1'. The macrodiagonal and brachydiagonal planes may be distinguished by a long or short mark (- or -), as in the trimetric system, and the lower planes from the upper by prefixing a minus (—) to the former (or the reverse). The planes between the macrodiagonal and brachydiagonal vertical zones to the right from those to the left, may be distinguished by adding the accents.

Thus the vertical series of planes or zones will be as follows:

1. Brach.	2	8	4	5. Macr.	6	7	8
m-∞	m- n	m	m-n	m- 	m- <u>"</u>	m'	m-m'
∞-∞	∞- <u>%</u>	œ	∞- <u>-</u>	∞-∞	∞- <u>~</u> /	œ′	∞- <u>*</u>
—m- ŏ	-m-ĕ	— m	-m	—m-≅	-m-='	-m'	-m-~'

Determination of the interfacial angles of Triclinic forms.

14

1

55. a. Let the mutual inclination of the sectional planes of the fundamental form at their intersections in the axes a, b, c, be represented respectively by A, B, C; and the inclination of the axes by α , β , γ : that is, the inclination of α on b, by γ , a on c, by β , b on c, by α . Let also the inclinations of a face of the fundamental octahedron, on the macrodiagonal, brachydiagonal, and basal sections be represented by X, Y, Z, respectively, and finally the inclinations of the edge

$$X \text{ on } a \text{ by } \mu$$
 $Y \text{ on } a \text{ by } \pi$ $Z \text{ on } b \text{ by } \sigma$ $\alpha \text{ if } \alpha

b. The following are the values of the cosines of α , β , γ , in terms of the cosines and sines of the angles A, B, C:

$$\cos \alpha = \frac{\cos A + \cos B \cos C}{\sin B \sin C}. \qquad \cos \beta = \frac{\cos B + \cos A \cos C}{\sin A \sin C}.$$

$$\cos \gamma = \frac{\cos C + \cos A \cos B}{\sin A \sin B}.$$

c. The same angles may be determined by means of the values of μ , ν , and σ , &c. of any form, and the corresponding μ' , ν' , σ' , of the coordinate form. The following equations may be employed for this purpose:

Tan
$$\alpha = \frac{2 \sin \sigma \sin \sigma'}{\sin(\sigma - \sigma')} \frac{2 \sin r \sin r'}{\sin(\sigma - \sigma')}$$

Tan $\beta = \frac{2 \sin r \sin \pi'}{\sin(\sigma - \sigma')} = \frac{2 \sin \rho \sin \rho'}{\sin(\rho - \rho')}$

Tan
$$\gamma = \frac{2 \sin \mu \sin \mu'}{\sin (\mu - \mu')} = \frac{2 \sin \nu \sin \nu'}{\sin (\nu - \nu')}$$

56. The three sections, the macrodiagonal, brachydiagonal, and beed, divide the fundamental octahedron into three-sided pyrmids. If the plane in the basal section is considered the base, and the vertical solid angle of the octahedron the vertex, of one of these pyramids, its lateral interfacial angles are identical with the angles X, Y, A; and since the terminal edges are X, Y and the axis a, the plane angles at the summit are X:Y,X:a, and Y:a, of which, the last two angles equal respectively μ and π . If we make the vertex A a centre, and describe with any given radius an we on each of the faces, a spherical triangle is formed, whose angles equal the inclinations of the faces of the pyramid, viz, X, Y, A, and whose sides are measured by the plane angles at the vertex, two of which are μ and σ . In this spherical triangle, if the angles A, \mu, and \neq are given, (that is, two sides, \mu and \neq, and the included ngle A), the angles X and Y are readily determined by Napier's theorem.

1. Tan
$$\frac{1}{2}(X+Y) = \cot \frac{1}{2}A \frac{\cos \frac{1}{2}(\pi-\mu)}{\cos \frac{1}{2}(\pi+\mu)}$$
.

Tan $\frac{1}{2}(X-Y) = \cot \frac{1}{2}A \frac{\sin \frac{1}{2}(\pi-\mu)}{\sin \frac{1}{2}(\pi+\mu)}$.

Tan
$$\frac{1}{2}(X-Y) = \cot \frac{1}{2}A \frac{\sin \frac{1}{2}(\pi-\mu)}{\sin \frac{1}{2}(\pi+\mu)}$$

This gives the half sum and half difference of the angles X and Y, from which the angles themselves are easily obtained. In a **similar way are deduced** the following analogous formulas: 2. For X and Z, from B, v, and σ :

Tan
$$\frac{1}{2}(X+Z) = \cot \frac{1}{2}B \frac{\cos \frac{1}{2}(\sigma \rightarrow \nu)}{\cos \frac{1}{2}(\sigma + \nu)}$$

$$\operatorname{Tan} \frac{1}{2} (X - Z) = \cot \frac{1}{2} B \frac{\sin \frac{1}{2} (s - r)}{\sin \frac{1}{2} (s + r)}$$

3. For Y and Z, from C, ξ , and τ ,

Tan
$$\frac{1}{2}(Y+Z) = \cot \frac{1}{2}C \frac{\cos \frac{1}{2}(r-\rho)}{\cos \frac{1}{2}(r+\rho)}$$

Tan
$$\frac{1}{2}(Y-Z) = \cot \frac{1}{2}C \frac{\sin \frac{1}{2}(r-\rho)}{\sin \frac{1}{2}(r+\rho)}$$

57. When the angles X and Y in any particular form are denred, it will be necessary to obtain the values of \u03c4 and \u03c4 for that form, and with these values and the angle A, the desired angle may be obtained by the above equations. In a similar manner, Y and Z, and X and Z, may be known from σ and g, and σ and v. If Xand Y are determined, and v and g are known, Z may be obtained

by the equation, $\cos Z = \frac{\cos B}{\sin \psi} \sin (X - \psi); \text{ or } \cos Z = \frac{\cos C}{\sin \psi} \sin (Y - \psi),$ in which \downarrow is an angle to be determined by the equation,

Cot $\downarrow = \cos \nu \tan \beta$; or $\cos \downarrow = \cos \ell \tan C$.

By varying these formulas, X may be obtained when Y or Z is known, and Y, when X or Z is known.

58. The following trigonometrical formulas for the values of #, ν, π, β, σ, τ, may be employed to determine these angles. It must be observed, that when either of the angles α , β , γ , is obtuse, the cosine becomes minus:

Tan
$$\mu = \frac{b \sin \gamma}{a - b \cos \gamma}$$
; $\tan \nu = \frac{a \sin \gamma}{b - a \cos \gamma}$;
Tan $\sigma = \frac{c \sin \beta}{a - c \cos \beta}$; $\tan \rho = \frac{a \sin \beta}{c - a \cos \beta}$;
Tan $\sigma = \frac{c \sin a}{b - c \cos a}$; $\tan \sigma = \frac{b \sin a}{c - b \cos a}$.

59. These angles, as functions of the angles X, Y, Z, may be found by the following formulas:

$$\cos \mu = \frac{\cos Y + \cos X \cos A}{\sin X \sin A}; \cos \nu = \frac{\cos Z + \cos X \cos B}{\sin X \sin B};$$

$$\cos \sigma = \frac{\cos X + \cos Y \cos A}{\sin Y \sin A}; \cos \varrho = \frac{\cos Z + \cos Y \cos C}{\sin Y \sin C};$$

$$\cos \sigma = \frac{\cos X + \cos Z \cos B}{\sin Z \sin B}; \cos \sigma = \frac{\cos Y + \cos Z \cos C}{\sin Z \sin C};$$

Formulas analogous to the following, may also be employed:

$$\cos^{2}\frac{1}{2}\mu = \frac{\cos(S-X)\cos(S-A)}{\sin X \sin A},$$

in which $S=\frac{1}{2}(Y+X+A)$. Their advantage consists in their admitting more conveniently of the use of logarithms.

60. The following relations subsist between the interfacial angles,

and the angles of the sections:

Sin
$$X$$
: sin Y :: sin σ : sin μ ,
Sin Y : sin Z :: sin σ : sin ρ ,
Sin Z : sin X :: sin σ : sin σ ,

and consequently.

 $\sin \mu \sin \rho \sin \sigma = \sin \nu \sin \pi \sin \tau.$

If # is known, * may therefore be found by the equation, $\sin \pi = \sin \mu \sin X + \sin Y$.

Similar equations may be obtained for the angles v, p, &c.

61. a. Interfacial angles of a vertical hemiprism.—The angles σ and σ are first to be found from the values of b, c, and α , in the hemiprism, and then according to the Napierian theorem,

from σ , γ , and B, we determine X and Z; or from ϵ , β , and C, we determine Y and Z.

When X or Y has been found, the equation $A+X+Y=180^{\circ}$, will give the unknown angle.

b. Inclined macrodiagonal hemiprism.—From a, c, β , the angles

 π and ρ may be obtained, and then by the Napierian theorem, X and Y may be found, from π , γ , and A; Z and Y, from ρ , α , and C.

Finally we have $B+X+Z=180^\circ$.

c. Inclined brachydiagonal hemiprism.—From b, a, γ , the angles p and v may be found, and then by the Napierian theorem,

X and Y from μ , β , and A; X and Z from ν , α , and B; and $C+Y+Z=180^{\circ}$.

Determination of the dimensions of forms.

- 62. Several of the preceding formulas may assist in determining the lengths of the axes. The following proportions and equations are also important:
 - a. $\sin \mu : \sin \nu :: b : a$; $\sin \sigma : \sin \rho :: c : a$; $\sin \sigma : \sin \sigma :: c : b$.
 - b. When X and Y, in a vertical hemiprism, are known,

 $b:c:\sin Y\sin \beta:\sin X\sin \gamma$; $X+Y+A=180^{\circ}$.

- c When X and Z, in an inclined macrodiagonal hemiprism, are known,
 - $a:c:\sin Z\sin \alpha:\sin X\sin \gamma; X+Z+B=180^{\circ}.$
- d. When Y and Z, in an inclined brachydiagonal hemiprism, are known.

 $a:b::\sin Z\sin \alpha:\sin Y\sin \beta$; $Y+Z+C=180^{\circ}$.

63. When, in these several hemiprismatic forms, an edge is necesured that is not parallel to the axis of the hemiprism, the plane angle of the prismatic faces must first be found, and then the Naperian theorem may be applied as follows:

a. If Z is the angle given in the vertical prism,

Sin
$$v = \frac{\sin B \sin \gamma}{\sin Z}$$
, or, $\sin \xi = \frac{\sin C \sin \beta}{\sin Z}$;

and then,

Tan
$$\frac{1}{2} \sigma = \tan \frac{1}{2} (v-\gamma) \frac{\sin \frac{1}{2} (B+Z)}{\sin \frac{1}{2} (B-Z)},$$

or, $\tan \frac{1}{2} \sigma = \frac{1}{2} (\xi-\beta) \frac{\sin \frac{1}{2} (C+Z)}{\sin \frac{1}{2} (C-Z)}.$

b. If Y is given in the inclined macrodiagonal prism,

$$\sin \zeta = \frac{\sin A \sin \gamma}{\sin Y}, \text{ or } \sin \xi = \frac{\sin C \sin \alpha}{\sin Y}.$$

$$\tan \frac{1}{2} = \tan \frac{1}{2} (\zeta - \gamma) \frac{\sin \frac{1}{2} (A + Y)}{\sin \frac{1}{2} (A - Y)},$$

or,
$$\tan \frac{1}{2} \rho = \tan \frac{1}{2} (\xi - \alpha) \frac{\sin \frac{1}{2} (C+Y)}{\sin \frac{1}{2} (C-Y)}$$

c. If X is given in the inclined brachydiagonal hemiprism,


Sin
$$\xi = \frac{\sin A \sin \beta}{\sin X}$$
, or $\sin \nu = \frac{\sin B \sin \alpha}{\sin X}$.
Tan $\frac{1}{3} \mu = \tan \frac{1}{3} (\xi - \beta) \frac{\sin \frac{1}{3} (A + X)}{\sin \frac{1}{3} (A - X)}$,
or, $\tan \frac{1}{3} \nu = \tan \frac{1}{3} (\nu - \alpha) \frac{\sin \frac{1}{3} (B + X)}{\sin \frac{1}{3} (B - X)}$

64. Determination of the signs of forms.—The rules on pages 53 to 56 should here be referred to. The formulas and rules deduced for the preceding systems, will be found of essential importance, also, in this system of crystallization.

EXAMPLES.

This subject may be further elucidated by some examples of the mode of calculation.*

1. Monoclinic System.



 Red Copper Ore.—The annexed figure represents an octahedron with truncated and bevelled edges, and replaced angles.

A is a face of the octahedron =1.

P truncates a solid angle, and is therefore a face of a cube $= \infty - \infty$.

a' truncates an edge between two planes e, (form ∞); its sign is therefore 2-2, (§ 13, e).

To determine a" (m) we measure the inclination of e on a"=169° 32'. Subtracting 90°, 70° 32' remain, which equal half the interfacial angle a": a"= $\frac{1}{2}$ 2B, (f. 49); using the formula, § 14, 3, m=tan. $\frac{1}{2}B\sqrt{\frac{1}{2}}$, we find that m=2. The sign of a" is therefore, 2.

The faces o (m-n) bevel the edges of form ∞ , and therefore $(\S 13, e, 1) n = \frac{m}{m-1}$. To determine n, we measure the angle e: e and find its value $160^\circ 54^\circ$, the supplement of which, $19^\circ 6^\circ$, is the angle e; $(\S 14)$. But $\tan e = \frac{(n-1)\sqrt{3}}{n+1}$, and therefore by transposition $n = \frac{\sqrt{3} + \tan e}{\sqrt{3 - \tan e}}$.

Making $\epsilon = 19^{\circ}$ 6', and observing that $\tan 19^{\circ}$ 6'= $\frac{1}{3}$ V'3 we obtain $n = \frac{3}{2}$. And since $n = \frac{m}{n-1}$, $\frac{3}{2} = \frac{m}{m-1}$, .'. m = 3, and the ascertained sign is $3 - \frac{3}{2}$.

This could have been determined without measurement, if the planes o were so extended as to form an edge with the plane A. Two opposite planes o would then have made parallel intersections with Λ , and consequently, (§ 13, a, 5), we should have had

$$n=\frac{2m}{m+1}$$
. Therefore since also $n=\frac{m}{m-1}, \frac{m}{m-1}=\frac{2m}{m+1}$, from which we find $m=3$,

as before determined.

The signs of the planes collected together form the following description of the crystal: 1, 2, ∞ , 2-2 ∞ -2 3- $\frac{3}{2}$ ∞ - ∞ .


^{*} These examples are taken from Naumann's Treatise, excepting those of Columbite and Monazite.

: Gray Copper Ore.—This figure has a tetrahe-minanter. Its planes belong to the following

$$_{1}=\frac{m-m}{2}$$
, (f. 59); $=\infty$ (f. 14).

$$(=x-n', (f. 34, § 13, h, 2); -a'=\frac{(m'-m')}{2}$$

$$a = \frac{m}{2}$$
, (f. 60, 64, § 13, h, 1).



The intersection of a' with two planes e (∞) are parallel, and therefore, (§ 13, :1. ==2 and $\frac{(s-s)}{s} = \frac{(2-2)}{2}$. For the same reason, $-s' = -\frac{(2-2)}{2}$.

Be planes a 'truncate the shorter edges of $\frac{(2-2)}{2}$, and, therefore, a''= $\frac{(\frac{3}{2})}{2}(\S 13, h, 1)$.

The edges e: a' are parallel to the shorter edges of $\frac{(2-2)}{2}$, therefore, with respect

is the plane e',
$$(\frac{2}{8}, 13, h, 2)$$
, $n'=m+1$, and hence e'= ∞ -3.


The collected signs are, $\frac{(1)}{2}$, $\frac{(\frac{3}{2})}{2}$, ∞ , $\frac{(2\cdot2)}{2}$, $\frac{(2\cdot2)}{2}$, ∞ -3, ∞ - ∞ .

1 has Pyrites.—The several forms contained in this crystal are the following:

$$P = x - x$$
, f. 1. $a = 1$, f. 11. $a' = m'' - m''$, f. 39.

 $r = \frac{[m-n]}{2}$. $o' = \frac{[m'-n']}{2}$. $e' = \frac{[m-n']}{2}$. $e'' = \frac{[m-n'']}{2}$.

For measuring e' on P and subtracting 90° from hangle, we obtain the angle e' on e' over P, which have be and hence from § 14, 4, since n=tan v, we have = x-2 e' (x-2) truncates the edge o": o", as u, the longest edge of the form o"; therefore, \$12.5.) n'==2 and n==2. But o'makes parale zeroections with e' and a" and consequently by man of the general equation, § 3, for the parameter a plane forming parallel intersections with two nen we find o"=4-2



is the same manner also, it is found that a'=2-2, (§ 13, i. 3). Is consequence of the parallelism of the intersections of o', a' and o'', the planes o was the edges C(fig. 49) of the hemi-hexoctahedron o", and are inclined on the

regent edge B, (f. 74); and therefore from § 3,
$$n' = \frac{m'(m^2 - n)n}{(mn - 1 mn + m'(m - n^2)m}$$
. Sub-

extraing 4 for m, and 2 for n, and reducing the equation, we obtain $n' = \frac{1}{2}m'$.

If now the plane e' were no extended as to form an edge with o', this edge would parallel to the intersections of o' with a', and from the parallelism of these two

observing that a=1, e'=
$$\infty$$
-2 it is determined that $n=\frac{2m}{m-1}$. By equating


two values of m, it is found that m=2 and n=3 and the whole sign of o' is $\frac{13}{3}$. Also from § 13, i, 3, e"= $x-\frac{3}{2}$.

But as this intersection of e' with o' does not exist in the crystal, we must have resurse to a measurement. As above, we first ascertain by measurement that e'= $\frac{3}{2}$ Consequently, (§ 13, i, 3), o''=3- $\frac{3}{2}$ The expression for the crystal is, therefore,

1, 2-2,
$$\frac{\left[\frac{3-3}{2}\right]}{2}$$
, $\frac{\left[\frac{4-2}{2}\right]}{2}$, $\frac{\left[\frac{\infty-2\right]}{2}$, $\frac{\left[\frac{\infty-3}{2}\right]}{2}$, $\frac{\infty-\infty}{2}$.

2. Dimetric System.

Idocrase. - In this figure a, a, are faces of the fundamental octahedron.



Axis $a=\sqrt{2}$. Consequently, cos. Z=cos. X=-7 X=129° 31', and Z=74° 101'.

It is obvious that

 $P=0, e=\infty, M=\infty-\infty, e=1-\infty, (\S 22, b, 3.)$ Measurement gives the angle a': =146° 30' from which, if 90 be subtracted, we obtain 560 30'=1Z, and since (§ 23, d)

$$m = \frac{\tan \frac{1}{2}Z}{\tan \frac{1}{2}Z'} = \frac{\tan .56^{\circ}30'}{\tan .37^{\circ}5'} = 2$$
: therefore, a'=oc-

tahedron 2.

The planes e'', e' are of the general form ∞ -n. By measurement we find, M: $e''=153^\circ$ 30′, M: $e'=161^\circ$ 34′. Subtracting 90°, there remains the value of $\frac{1}{2}$ X for each form; and since n=tan. $\frac{1}{2}$ X, (§ 23 f), $e''=\infty$ -2.

Because the planes o', o'', and e'', have horizontal intersections, and e''= ∞ -2, both o' and o'', are of the form m-2. Because also o'v forms parallel intersections with M and a', (2), o'v=4-2. o', o'', o''', form parallel edges between M and a, and the same are parallel with e, and they are, therefore, of the general form m-m. Consequently, from the above, o'=2-2. As the mutual intersections of a'', o'v', o''', are parallel to one another, and also to the normal section, m'=m, and since o'v=4-2, o'''=4-4, and a''=4.

The planes of replace the basal angles of the pyramid L and their edges of intersections.

The planes or replace the basal angles of the pyramid 1, and their edges of intersection with the same a are parallel, or in other words, a truncates edge Y of the form or (m-n); therefore, $(\S 22, a, 1), m(n+1) = 2m'n$; or since m' = 1, m(n+1) = 2n. Again, since or replaces the edges between $e(1-\infty)$ and o', (2-2), m(n-1) = n,


(§ 3, a, 2). Therefore, m(n+1)=2m(n-1): n=3 and $0^{*}=3.3$.

Since the intersections of o' and o' are horizontal, n'=n, and consequently o'=3-3. To determine o' by measurement, we measure the angle o': M, from which by subtracting 90°, we obtain $\frac{1}{4}T$. Then by formula, $(\S 23, b)$, m=tan. $\frac{1}{4}T$ ×cot. $\frac{1}{4}T$, we determine m, as before, equal to 2.

The signs of the crystal thus developed are,

0, 1, 2, 4, \omega, 2-2, 4-2, \omega-2, \frac{3}{2}-3, 3-3, \omega-3, 4-4, 1-\omega, \omega-\omega.

3. Trimetric System.



Columbite. - In this figure we take a, as a face of the fundamental form. The values of its axes are, a=1 0584 =v1.12; b=1.206=v1.454; c=1. We have P=0; w = x-x; 1=x-x; and since the edge a; e is horizontal,

as seen in the crystal, ε=∞.

The angle M: ε=156° 6', and therefore ½ X in the prism ε (∞-n)=68° 6'. Half the same angle in the prism ε (∞)=39° 40': hence (§ 30, ε) n=3 and ε=∞-ξ.

Since δ', δ', bevel the longer terminal edge of a (1), they have the general sign Ym, (§ 31, b, 3), and because also δ' forms parallel intersections with ε (∞-ξ) and P (0), ô'=1-3.

ē truncates terminal edge of the pyramid 6', (1-3), and consequently e= 1- .

The planes ô" (m-m) replace the edge o': M, and therefore, (§ 31, b, 4) since ô'=1-3 By measurement of the interfacial angle M: è we find it to equal 150°

W; and hence since (§ 27, d) tan $\frac{1}{4}Z$ in the prism \dot{e} , $(m-\check{\omega})=ma+b$, we deduce, that - Now & truncates a terminal edge of the pyramid o', and consequently,

$$\delta'=2-n$$
; and since $\frac{m}{n}=\frac{1}{3}$; $n=6$ and $\delta''=2-6$.

The inclination of ē on M equals 157° 29', and hence \ Y in the prism ==67° 29'. Therefore, (§ 30, e) é= ∞-2.

The expression thus deduced for the crystal is as follows:

$$0,\,1,\,\infty,\,1\cdot \overline{g},\,\infty\cdot \overline{g},\,2\cdot \overline{g},\,2\cdot \overline{\omega},\,\overline{\omega}\cdot \overline{\omega},\,\,\infty\cdot \overline{\omega},\,\,\overline{\omega}\cdot \overline{z},\,\frac{1}{4}\cdot \overline{\omega},\,\,\overline{\omega}\cdot \overline{\omega}.$$

By substituting the values of the axes in the different forms for a, b, c, in the equatoos, § 26, the values of the angles of those forms may be obtained. In this manner we find for the fundamental pyramid, $X=102^{\circ}$ 58', $Y=117^{\circ}$ 51', $Z=107^{\circ}$ 56'. In the gramid 1-3' (\bar{o}') by writing a, b, b, c, for a, b, c, the same angles for this form may be land; and by substituting 2a, b, 6c, for a, b, c, the corresponding angles for the form $14(\bar{o}')$ may be obtained.

4. Hexagonal System.

1. Apatite. - The annexed figure represents a hexacount prism, with truncated lateral edges and re-paced basal edges and angles. The plane e may be sected as a face of the fundamental pyramid (1). Then

P=0, $M=\infty$, $\epsilon=\infty-2$,

struncates a terminal edge of 1, and therefore=1-2,

343, 9, 3). The edge a': e is parallel to a terminal edge of 1, since M is parallel to the edges of the plane a, which truncates edge; consequently, a'=2.2, (§ 43, g, 5).

The edge a: e' is parallel to a terminal edge of e';

brefore, since a=1-2, e'=1, (§ 43, g, 5).

a' (2-2) truncates a lateral edge of the pyramid e'' (m), and therefore, e''=2. The edge a'': e'' is parallel to a terminal edge of e'' (2); consequently, a''=4-2. Description of the crystal:

0, 1, 1, 2, 1-2, 2-2, 4-2, ∞-2. 1 Calcite. - The figure is secondary to a rhombedron. Its larger faces e' belong to a scalenois a face of the hexagonal prism ∞R .

The interfacial angle a': a, subtracted from 180°,


stale the inclination of a' on the axis, = the an-

(be a; and since $m = \frac{\cot a}{\cot a'}$, (§ 45, g), a' being the

corresponding angle in the primary a'=-2R.

The edges R: e', e': e', e': R, are parallel: conse-tantly, e': e', are faces of a scalenohedron, R^n , (§ 43, 31) But also the planes a' (-2R) truncate the state terminal edges of the scalenohedron. It fol-tantly, e': e', and $e' = R^3$, (§ 43, e). The terminal edges of the primary are truncated

7 = 1R, (§ 43, k, 6).
The plane e' forms a horizontal intersection with (AP) and is, therefore, of the general form mR's,
[4], a). Also, because it bevels the terminal edge the primary R, $\frac{1}{2}m'$ (3n'-1)=m, (§ 43, k, 1). m = 3, we have 4m' = m = 1 and $m' = \frac{1}{2}$, thereme, e'=1 R3.



149

M

M

n

a

The two adjacent planes $e'(\frac{1}{4}R^3)$ form parallel intersection with two faces of the rhombohedron a'', and therefore bevel its terminal edges; consequently, since $\frac{1}{2}m'(\frac{3m'+1}{2})=m$, (§ 43, k, 4), $a''=-\frac{5}{4}R$.

To obtain the value of the axis (a) from R on R, use equation, (§ 45, g), a2=


$$\frac{3(1+\cos X)}{2-4\cos X}$$

If $x=105^{\circ}$ 5', then since cos 105° 5' =-cos 74° 55 =-0.26022; therefore

$$a^2 = \frac{3(1 - 0.26022)}{2 + 4 \times 0.26022} = \frac{2.21934}{3.04088},$$

whence 0.8543=a (the desired axis).

Description of the crystal: R^3 . R^3 . ∞R . $-\frac{5}{4}R$. $-\frac{1}{4}R$. -2R. R.



3. Quartz.—In the annexed figure R, a'', are the planes of the fundamental pyramid (1). a''', $a^{i\gamma}$, $a^{i\gamma}$, are other paramids, and the obliquely situated planes are tetartohedral forms. a=prism co.

The edge R: e' being parallel to a terminal edge of the

fundamental pyramid, e'=2-2, (§ 43, g, 5).

Because the intersections of the planes o', o'', o''', o''*,

are parallel to e' they have the general sign m-

The signs of the planes $a^{\prime\prime\prime}$, $a^{i\gamma}$, $a^{i\gamma}$, $a^{i\gamma}$, may be determined by measuring the inclination $a:a^{\prime\prime\prime}$, $a:a^{i\gamma}$, $a:a^{i\gamma}$. They are thus found to be

are thus found to be
$$a^{v} = \frac{5}{3}$$
, $a^{iv} = 3$, $a^{\prime\prime\prime} = 4$.

The tetartohedral forms a^{\prime} , $a^{\prime\prime\prime}$, a^{iv} , have the general formula $i(\frac{m-n}{4})$, and a^{v} is $r(\frac{m-n}{4})$. Moreover, as $n = \frac{m}{m-1}$,

since the parallel intersections are parallel also to a terminal edge of 1. The inclinations of these planes on a, diminished by 90° , equal each the semi-angle U. Then from the equation for 2m-1 (§ 45, b), we obtain for quartz, $2m-1=2\cdot34$ tan $\frac{1}{4}U$. Hence to determine m for any plane, we have only to measure the angle between the plane and a, and subtract 90° ; this gives $\frac{1}{2}U$, and then the equation $2m-1=2\cdot34$ tan $\frac{1}{4}U$, gives m. Thus we obtain $o^{\ast} = \frac{(3-\frac{3}{2})}{4}, o' = \frac{(4-\frac{4}{3})}{4}, o'' = \frac{(5-\frac{5}{4})}{4}, o''' = \frac{(6-\frac{6}{3})}{4}, o^{i\ast} = \frac{(8-\frac{8}{7})}{4}.$

$$o^{*} = \frac{(3-\frac{3}{2})}{4}, o' = l(\frac{4-\frac{4}{3})}{4}, o'' = l(\frac{5-\frac{5}{3}}{4}), o''' = l(\frac{6-\frac{6}{3}}{4}), o^{i*} = l(\frac{8-\frac{8}{3}}{4})$$

Description of the crystal:

$$1, \frac{5}{3}, 3, 4, \infty, 2-2, r(\frac{3-\frac{3}{2}}{4}), t(\frac{4-\frac{4}{3}}{4}), t(\frac{5-\frac{5}{4}}{4}), t(\frac{6-\frac{5}{6}}{3}), t(\frac{8-\frac{8}{7}}{7})$$

5. Monoclinic System.



Monasite.—Assuming \tilde{e} as a face of the fundamental form, $\tilde{e}=\infty$. $\tilde{\infty}$, $\tilde{e}=\infty$. The general descriptive expressions for the remaining planes are as follow:

$$\tilde{a}=m-\omega$$
 $a=m-\tilde{\omega}$ $a'=m'-\tilde{\omega}$ $\tilde{e}'=\omega\cdot\tilde{n}$ $\tilde{a}=-m-\omega$ $\tilde{e}=-m$ $o'=m'-\tilde{n}$ $M=\omega\cdot n$

The plane $a(m-\hat{\infty})$ forms parallel intersections with \hat{e} and \hat{e} , which intersections, since they are parallel with the edge $\hat{e}:\hat{e}(\infty-\infty)$ are also parallel with the orthodiagonal edge of $\hat{e}(1)$. Hence, $\hat{e}=-1$ (§ 53, 1, b), and $a=1-\hat{\infty}$. (§ 53, 1, b); and also since M forms parallel intersections with \hat{e} and \hat{e} , $M = \infty (\S 53, 1, a).$

a truncates the edge between ē and ē, which is the clinodiagnal edge of 1, and therefore, a=1-w (§ 53, 1, e).

a in the same manner truncates the clinodiagonal edge of -1. Consequently, $i=1-\infty$, (§ 58).

The intersection of o'(m-n) with \tilde{o} (1) is parallel to the clinodiagonal edge of established on 1, consequently n=m (§ 53 5), and o'=m-m. Again, o' forms parallel intersections with $a(1-\tilde{o})$ and M, (∞) , and therefore its sign is of the general

form $m = \frac{m}{m-1}$. But from the above, n = m, and consequently $m = \frac{m}{m-1}$; from which we find m=2, and o=2.2

The edge $o': a' (m'-\tilde{\infty})$ is parallel to the orthodiagonal edge of $o'(2.\tilde{2})$ consequently m=2, (§ 53, 1, b), and $a'=2-\tilde{\infty}$.

The intersection of $o'(2-\tilde{p})$ with $\tilde{e}'(\infty-\tilde{p})$, is parallel to the basal section of $2-\tilde{p}$, apparent in the crystal, though not in the figure, a perspective representation of it); hence n'=2, (§ 53, 1, a), and $i'=\infty \cdot 2$.

Thus all the expressions for the planes of this crystal have been determined without a measurement. If the intersection of o' with M were not apparent in the out a measurement. If the intersection of o' with M were not apparent in the crystal, it would be necessary first to determine \dot{e}' by measuring the interfacial angles $M: \dot{e}$ and $\dot{e}': \dot{e}$; these angles 136° 35' and 11°° 51' diminished by 90° give the angles K in the two forms M (∞) and \dot{e}' , (∞ - \dot{n}'); and then, since tan 48° 35'=2 tan 27° 51', it follows that n'=2 and $\dot{e}'=\infty$. Thence since the intersection of o' with \dot{e}' is parallel to the basal section of o', (m-m), o'=2- $\frac{1}{2}$, (§ 53, 1, a), as before tend. The same might have been similarly determined by measuring the inclination of $\frac{1}{2}$ or a and a'tien of 1 on a and a.

For the calculation of the dimensions and angles of the crystal we have as data, 2-x: 1-x = 140° 40', x - x: -1-x = 126° 8', x - x: x = 136° 85'.

180°—140° 40′—39° 20′—
$$\mu$$
′,
180°—126° 8′ =53° 52′— μ ,
186° 35′—90°=46° 35′= X in ∞ .

Since 1- ∞ and $-1-\infty$ are coordinate forms, we may determine O by the equation to $C = \frac{2 \sin \mu \sin \mu'}{\sin (\mu - \mu')}$, whence we obtain $C = 70^{\circ} 14'$.

To determine the axes there are given the angles C, μ , and X in the form ∞ . If b=1. tan $X \sin C = c$, (§ 51, a); consequently, c=1.0265.

Again,
$$a = \frac{\sin(C + \mu)}{\sin \mu} = \frac{\sin 49^{\circ} 54'}{\sin 35^{\circ} 52'}$$
; therefore $a = 0.9471$.

a:b:c=0.9471:1:1.0265.

After thus determining the axes, the angles X, Y, Z, in the various forms, are readily stained by the equations, p. 86. For example, with regard to the form ± 1 , X and

I may be determined by the equations $\tan X = \frac{\tan \pi}{\sin \mu}$, $\tan X = \frac{\tan \pi}{\sin \mu}$, $\tan \pi$ having

first been found by the equation, $\tan \pi = \frac{c}{a}$. This gives $X=59^{\circ}41'$, which is half the

verfacial angle $\ddot{\mathbf{e}}$: $\ddot{\mathbf{e}}$. By means of the equations $\tan Y = \frac{\tan \mu}{\sin \pi}$, $\tan Y = \frac{\tan \mu}{\sin \pi}$, we obin Fand F, which are respectively the supplemental angles of ē on ē and ē on ē. lgain, by the equations, $\tan Z = \frac{\tan(C - \mu)}{\sin \sigma}$, $\tan Z = \frac{\tan(C - \mu)}{\sin \sigma}$, (s being found by the

Testion sin s = $\frac{c}{b}$), we find the angles Z, Z', which are the supplements of P on \tilde{e} and Pos & Y+Y=the inclination of e on e over an orthodiagonal terminal edge, and +Z=the inclination of e on e over a basal edge of the form±1.

In the form 2.2 whose axes have the ratio 2a, 2b, c, the angle µ is identical with the corresponding angle in 1. π is found by the equation $\tan \pi = \frac{c}{2a}$, and σ by the equation tan = 5 After the determination of these angles, X, Y, Z in this form, may be found by the same equations as above. The inclination of P on M may be determined by the equation for $\tan Z$ in the form ∞ , $\tan \left\{ \frac{Z}{Z'} = \mp \frac{\tan C \nu (b^2 + c^2)}{c} : (\S 51, a), \text{ which } c = 1 \right\}$ affords the supplement of the desired inclination; or by the equation, (§ 51, d), sin If (the sought angle) = $\frac{\cos X}{\cos x}$, or $\cos \Pi$ = $\sin X \cos \theta$, in which X is the angle X in the form M (x). The interfacial angle a : é is determined by the equation for tan

In a similar manner the angles of the other forms may be obtained.


ON THE DRAWING OF FIGURES OF CRYSTALS.

In the projection of crystals, the eye is supposed to be at an infinite distance, so that the rays of light fall from it on the crystal in parallel lines; and not diverging a in ordinary landscape perspective. If parallel lines were drawn from the vertices of the solid angles of a crystal, to a board placed behind it, and the points that formed on the board were connected by straight lines, as in the crystal, a representation of the crystal would be formed, constructed according to the mode of projection employed in crystallography. The plane on which the crystal is projected, a termed the plane of projection. This plane may be at right angles with the vertical axis, may pass through the vertical axis, or may intersect it at an oblique projections. The rays of light may fall perpendicularly on the plane of projection, or may be obliquely inclined to it; in the former case the projection is termed orthographic, in the second clinographic. In the horizontal position of the plane of projection, the projection is always orthographic. In the other positions, it may be either orthographic or clinographic. It has been usual to give the plane of projection an oblique position, and to use the orthographic mode of projection. It is however preferable to employ the vertical position and clinographic projection, and this method is clucidated in the following pages.

The projection of the axes of a crystal, is the first step preliminary to the projection of the axes in the monometric system, which are equal and intersect at right the projection of the axes in the monometric system, which are equal and intersect at right the projection of the axes in the orthographic may be obtained by varying

tion of the axes in the monometric system, which are equal and intersect at right angles. The projection of the axes in the other cases, may be obtained by varying the lengths of the projected monometric axes, and also, when oblique, their incli-

Monometric System.—When the eye is directly in front of a face of a cube, neither the sides nor top of the crystal are visible, nor the secondary planes that may be situated on the intermediate edges. On turning the crystal a few degrees from right



to left, a side lateral plane is brought in view, and by elevating the eye slightly, the terminal plane becomes apparent. Half the planes on the crystal are now visible, and consequently this is a convenient position for projecting it. In the following demonstration, the angle of revolution is designated of, and the angle of the elevation of the eye, r. Fig. 151 represents the normal position of the horizontal axes, supposing the eye to be in the direction of the axis BB; BB is seen as a mere point, while CC appears of its actual length. On revolving the whole through a number of degrees equal to BMB' (8) the axes have the position exhibited in the dotted lines. The projection of the semiaxis MB is now lengthened to MN, and that of the semiaxis MC is shortened to MH.

If the eye be elevated, (at any angle, s), the lines B'N, BM and C'H will be projected respectively below N, M and H, and the lengths of these projections (which we may designate b'N, bM, and c'H) will be directly proportional to the lengths of the lines B'N, BM, and C'H.

It is usual to adopt such a revolution and such an elevation of the eye as may be expressed by a simple ratio between the projected axes. Let us designate the ratio between the two axes as projected after the revolution alluded to (MN: MH) by 1: r; and the ratio of b'N to MN by 1: z. Now the character of the view will vary with the values assumed for r and z. Suppose r to equal 3 and z to equal 3, then proceed as follows:

Draw two lines AA', H'H (f.154) intersecting one another at right angles. Make MH=MH' = 1. Divide HH' into r parts, and through the points, N, N', thus determined, draw perpendiculars to HH'. On the left hand vertical, set

off, below H', a part H'R, equal to $\frac{1}{a}b = \frac{1}{a}$ H'M;

and from B draw RM, and extend the same to the vertical N'. B'B is the projection of the front horizontal axis.

Draw BS parallel with MH' and connect S, M. From the point T in which SM intersects BN, draw TC parallel with MH. A line (CC') drawn from C through M, and extended to the last vertical, is the projection of the side horizontal axis.

Lay off on the right vertical, a part HQ

equal to -MH, and make MA=MA'=MQ; AA' is the vertical axis.

The values of r and s commonly taken, are r=3, s=2, in which case, $t=18^{\circ}$ 26', and $s=9^{\circ}$ 28'. It is not usual to give s the value of 3, in which case $t=5^{\circ}$ 20'. This affords a terrower terminal plane. The angle $t=18^{\circ}$ is obtained by the equation $t=18^{\circ}$ 20'. The angle $t=18^{\circ}$ is obtained by the equation $t=18^{\circ}$ 20'.

The regular octahedron may now be drawn, by connecting the extremities of the horizontal axes, and then mitting them by right lines with the points A, A', as in f. 155. If lines be drawn through the points B and B', parallel with C C', and through C, C', rarallel with the axis BB', a plane tyre abod is formed, which is a horizontal section of the cube. Through

155 A B B

the points a, b, c, d, draw lines parallel with the vertical axis AA', and extend them such side of these points, to a distance equal to the vertical semiaxis MA. By consecting the upper and also the lower extremities of these perpendiculars by lines parallel with the lines ab, be, cd, da, the figure will represent a cube.

The cube may also be projected by drawing lines from M to the centre of each sign of the octahedron, and then extending these lines to double their length. Their extendities are the vertices of the angles of the cube.

It is convenient to have at hand an accurate figure of a cube drawn on a large scale, at may readily be used by methods explained beyond for making figures of the type prisms of either of the other systems. Such a figure may be made as above oplained. It may also be constructed with a graduated are, or a scale of signs as allows. Draw two lines as AA' and HH, f. 154, crossing at right angles; draw a bec'C, making an angle 3° 11' with H'H, and BB', making an angle 26° 34', with H'H, each crossing AA' in M. Then, M being the centre of each axis, make 14'41 inches in length, C'C 42's inches, BB 12 inches. From these axes the cube is


readily constructed. The axes are more exactly, AA' 4.245 in., CC' 4.088 in., BB'

Dimetric System.—In the dimetric system the vertical axis may be made to correspond to the dimensions in a dimetric crystal, by laying off on MA and MA', (taken as units), extended if necessary, a line equal to $a \div b$; or if b, the horizontal axis of the prism =1, the line should equal a (the vertical axis) simply. After determining thus the points A'', A''', the dimetric octahedron may be formed in the same manner as the regular octahedron above described, except the points A'', A''' should be substituted for A, A'. The method of describing the cube, already explained, may be employed also for the right square prism. Another right square prism may be represented by drawing lines parallel with the vertical axis, through the extremities of the horizontal axes, making them equal to the vertical axis, and moniting their extremities. Also another square octahedron may be constructed by connecting the points a, b, c, d, with the extremities of the vertical axis.

Trimetric System.—The monometric axes may be adapted to trimetric forms as follows: if the axis b=1, lay off MA'' and MA''' equal to a, and MC'', MC''' equal to c: if c=1, make MB'', MB''', equal to b. By connecting the extremities of the axes, as already explained, the rhombic octahedron may be constructed. The rectangular prism may be projected in the same manner as the cube; the rhombic prism in the same manner as the second square prism just described; and the rectangular octahedron in the same manner as the second dimetric octahedron explained in the last section.

In changing a figure of a cube (in which the edges \rightleftharpoons 1) to a square or rectangular prism ϖ - ϖ , it is only necessary to shorten or lengthen the edges to correspond with the axes of the new prism.

Monoclinic System.—The axes a and b in the monoclinic system are inclined to



one another at an oblique angle= γ . To project this inclination, and thus adapt the monometric axes to a monoclinic form, lay off on the axis MA, Ma= MA cos γ , and on the axis BB' (before or behind M, according as the inclination of b on a, in front, is acute or obtuse) $Mb=MB \times \sin \gamma$. From the points b and a, draw lines parallel respectively with the axes AA' and BB', and from their intersection D', draw through M, D'D, making MD=MD'. The line DD' is the clinodiagonal and the lines AA, C'C, DD' represent the axes in a monoclinic solid in which a=b=c=1. The points a and b and the position of the axis DD' will vary with the angle γ . The relative values of the axes may be given them as above explained; that is, if b=1, lay off in the direction of MA and MA' a line equal to a, and in the direction of MC and MC' a line equal to c. &c.

The right rhomboidal prism may be projected in the same manner as the cube or right rectangular prism, and the oblique rhombic prism, in the same manner as the right rhombic prism.

Diclinic System.*—In the diclinic system, the vertical section through the horizontal axes intersect one another at right angles, as in the preceding system, but the inclination of a to b (y) and a to c (β) are each oblique. This obliquity may be given the monometric axes as follows: Lay off on MA, (t. 156), $Ma=MA\times\cos \gamma$, and on the axis BB', (brachydiagonal), $Mb=MB'\times\sin \gamma$. By completing the parallelogram Ma D'b, the point D' is determined. Make MD=MD'; DD' is the projected brachydiagonal. Again lay off on MA, $Ma'=MA\times\cos\beta$, and on MC', to the left, $Me=MC'\times\sin\beta$. Draw lines from a' and c parallel to MC' and MA; E', the intersection of these lines, is one extremity of the macrodiagonal; and the line E'E,

^{*}The diclinic system differs from the triclinic in having only two of the axial intersections oblique instead of the three. As no example of it has been observed among minerals, and the forms are as well described in the triclinic system, it was not treated of in the earlier part of the work.

is which ME-ME', is the macrodiagonal. AA', DD', EE' are the axes in a diclinic form in which the axes are equal. From the observations on the preceding systems of crystallization, the method to be employed in giving the axes their relative whee in a particular diclinic form, is sufficiently obvious. The construction of

he oblique rectangular prism is analogous to that of the cube.

-The vertical sections through the horizontal axes in the triclinic Triclinic System .intern are obliquely inclined; also the inclination of the axis a to each axis b and c, is bique. In the adaptation of the monometric axes to the triclinic forms, it is therefore necessary, in the first place, to give the requisite obliquity to the mutual netination of the vertical sections, and afterwards to adapt the horizontal axes, as in the diclinic system. The inclination of these sections we may designate A, and sheretofore, the angle between a and b, γ , and a and c, β . BB' is the analogue of the brachydiagonal, and CC of the macrodiagonal. An oblique inclination may be given the vertical sections, by varying the position of either of these sections.

Remitting the brachydiagonal section ABA'B' to remain unaltered, we may vary the other section as follows:

Lay off on MB, Mb'=MB×cos A, and on the axis CG, (to the right or left of M, according as the state angle A is to the right or left), Mc=MC× in A; completing the parallelogram Mb' Dc, and drawing the diagonal MD, extending the e to D' so as to make MD'=MD, we obtain te line DD'; the vertical section passing through this line is the correct macrodiagonal nation. The inclination of a to the new marediagonal DD' is still a right angle; as also the inclination of a to b, their oblique inclinaissas may be given them by means of the same issaels employed in the diclinic system, ex-


ept that the axis D'D is to be substituted for The vertical axis AA' and the horizontal us EE' (brachydiagonal) and FF' (macro-ingual) thus obtained, are the axes in a tri-tice form, in which a=b=c=1. Different

serding to the method heretofore illustrated.

Herzgonal System.—In this system there are three equal horizontal axes, at right miles with the vertical. The normal position the horizontal axes is represented in f. 158. The eye, placed in the line of the axis YY, obeves two of the semiaxes, MZ and MU, proeted in the same straight line, while the third, IV. appears a mere point. To give the axes a we eligible position for a representation of le various plaues on a tetraxonal solid, we re-telve them from right to left through a certain mber of degrees d, and elevate the eye at an The dotted lines in the figure reprethe axes in their new situation, resulting ima a revolution through a number of degrees qual to &=YMY'. In this position the axis
It' is projected upon MP, MU' upon MN, and Designating the intermediate Z on MH. is I, that to the right II, that to the left III, the revolution is such as to give the pro-

Ť.

Different values may be given these axes,




prions of I and II, the ratio of 1: 2, the relations of the three projections will be *follows: I: II: III=1:2:3.

Let us take r (PM: HM) equal to 3, and s (b'P: PM) equal to 2, these being the nest convenient ratios for representing the hexagonal crystalline forms. wing will be the mode of construction:

1 Draw the lines AA, HH (f.159) at right angles with, and bisecting each other. Let 11=6, or HH=26. Divide HH into six parts by vertical lines. These lines, inding the left and right hand verticals, may be numbered from one to six, as in

the figure. In the first vertical, below H, lay off HS=1 b, and from S draw a line through M to the fourth vertical. YY' is the projection of the axis L



2. From Y draw a line to the sixth vertical and parallel with HH. From T, the extremity of this line, draw a line to N in the second vertical. Then from the point U in which TN intersects the fifth vertical, draw a line through M to the second ver-


tical; UU' is the projection of the axis H.

3. From R, where TN intersects the third vertical, draw RZ to the first vertical parallel with HH. Then from Z draw a line through M to the sixth vertical: this line ZZ' is the projection of the axis III.

4. For the vertical axis, lay off from N on the second vertical (f. 159) a line of any length, and construct upon this line an equilateral triangle; one side (NQ) of this triangle will intersect the first vertical at

A a distance, HV, from H, corresponding to Z'H in f.158; for in the triangle NHV, the angle HNV is an angle of 30°, and HN= #MH. MV is therefore the radius of the circle, (f. 158). Make therefore MA=MA'=MV; AA' is the vertical axis, and YY', UU', ZZ' are the projected horizontal

The vertical axis has been constructed equal to the horizontal axes. Its actual length in different hexagonal or rhombohedral forms may be laid off according to the method sufficiently explained. If lines be drawn through the extremities of the horizontal axes, parallel with the vertical axis, and the parts above and below be made equal to the vertical semiaxis, their extremities will be the vertices of the angles of a hexagonal prism, and by connecting them we obtain the projection of this solid. A double hexagonal pyramid, the isosceles dodecahedron, may be projected by connecting the extremities of the horizontal axes with each other, and also uniting them with the extremities of the vertical axis. By drawing lines through the extremities of each horizontal axis, parallel to a line connecting the
extremities of the other two axes, a plane hex-



agonal figure will be obtained, which is the section of a hexagonal prism diagonal with the one above referred to; and by connecting the angles of this hexagonal plane with extremities of the vertical axis, a second isosceles dodecahedron is projected.

To construct a rhombohedron, lay off verticals through the extremities of the horizontal axes, and make the parts both above and below these extremities, equal to the third of the vertical semiaxis, (f. 160). The points E, E, E', E', &c., are thus determined; and if the extremities of the vertical axis be connected with the points E or E', rhombohedrons in different positions, mR or -mR, will be constructed.

Delineation of Secondary Planes on the Primary Forms .- Previous to drawing the secondary planes on a primary, it becomes necessary to determine the direction the secondary planes on a primary, it becomes necessary to determine the direction of the intersections of these planes with the primary faces, and also in most cases, with other secondary planes. The principles of analytical geometry have afforded Naumann formulas for these intersections; but it would be giving this article too great an extension to enter into a full discussion of this method of determining intersections. It is in general sufficient to employ the method of construction.


In the employment of the plan of construction, the projection of the prism 0, ∞ - ∞ , is the most convenient preliminary step; that is, the cube in the monometric system, right square prism in the dimetric system, the rectangular prism in the trimetric, the right rhomboidal in the monoclinic, and the prism 0, ∞ - $\overline{\infty}$, ∞ - $\overline{\infty}$,

the diclinic and triclinic systems. This is advisable because in these forms the semi edges are equal and parallel to the vertical axis, and the basal edges, to the axes; and consequently in laying off the different planes, these edges

my be substituted for the axes

espose, for example, the right rectangular prism has been projected, (f. 161), and required to place on its angles the plane 2, whose parametric ratio is 2:1:1.
2 refers to the vertical axis, we lay off on the lateral edge (e) twice as many act of this edge as of each of the terminal edges, (è and è). Consequently, by ling a point in the edge e distant from a, the length of e, and a point in each e their respective lengths, and then joining these points, the conditions will be constructed. If the plane to be introduced with, and the plane 2P will be constructed. If the plane to be introduced were 4.2, the parametric ratio of which is 4:2:1, (in which 4 refers to introduced axis and 2 to the longer horizontal) we should in the same manner mark the large state of e, 2 of e, and 1 of e; if the plane were 42 (in which 2 refers to the the plane were 42 (in which 2 refers to the the plane were 42 (in which 2 refers to the spring state of e should be laid off, and 1 of e. By connecting appints thus determined, the plane 4-2 or 4-2 would be delineated. If the plane 2-2 (2: ∞:1), which represents a plane on the longer terminal edge, 2 parts thould be laid off, and 1 of e; from the determined points in e and e, lines are the drawn to the opposite edges parallel with the edge e, and by connecting the limit thus days the desired expression of the limit thus days the desired expression of the limit thus days the desired expression of the limit thus days the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the desired expression of the limit thus days are the limit that the days are the limit that the limit the limit thus days are the limit than the limit the limit the limit the limit the limit the limit the limit that the limit the limit the limit the limit that the limit the limit that the limit the limit the limit the limit that the limit th entremities of the lines thus drawn, the desired representation of a plane 2-will be completed. The same should be repeated on all the similar edges. This all suffice to illustrate the manner of substituting the edges for the axes, and also

Demanner of determining the intersection of planes, we may illustrate by an Suppose it were required to place the planes 1, 2, 4-2, and 2-2, on a right Suppose I were caused by the standard prisms should first be accurately projected by the standard which has been explained. One, of a size which may be considered areaient for a representation of the crystal, drawn with light pencil marks; the of larger dimensions, for the purpose of determining the direction of the intense; these intersections, when determined, are to be transferred to the larger. On f. 161 we may first lay down the plane 1, by drawing lines considered that there adoes about the angle. These lines are necessarily the centres of the three edges about the angle. These lines are necessarily called to the diagonals of the three faces; the triangle mno is therefore the plane By connecting the points m, b, n, the plane 2 is constructed; for the plane auts off 2 parts of e to 1 of each \bar{e} and \bar{e} , as the expression 2 requires. To lay (4:1:2), let the whole edge ab represent 4; then an ($\frac{1}{2}$ of \bar{e}) will represent the edge \bar{e} , and ap ($\frac{1}{2}$ of \bar{e}) will equal 1 part on \bar{e} , agreeably to the exponent 4:3:npb is therefore the plane 4:2. The perimeters of the planes npb (4:2)



al and (1) intersect one another in the points n and a; consequently the line of the points between these two planes must be situated between these points, and berefore the direction of the intersection of 1 and 4.7 is na.

The planes nmb (2) and npb (4-7) intersect in the line nb, and therefore the intersion of 2 and 4-7 is in the direction of nb.

In the form 2.1 whose axes have the ratio 2a, 2b, c, the angle u is identical with the corresponding angle in 1. π is found by the equation $\tan \pi = \frac{c}{2a}$, and σ by the equation tan $\sigma = \frac{c}{2h} = \frac{c}{2}$. After the determination of these angles, X, Y, Z in this form, may be found by the same equations as above. The inclination of P on M may be determined by the equation for $\tan Z$ in the form ∞ , $\tan \left\{ \frac{Z}{Z'} = \mp \frac{\tan C V(b^3 + c^3)}{c} : (\S 51, a), \text{ which } \right\}$ affords the supplement of the desired inclination; or by the equation, (§ 51, d), siz II (the sought angle) = $\frac{\cos X}{\cos \sigma}$, or $\cos \Pi$ = $\sin X \cos \theta$, in which X is the angle X in the form M (a). The interfacial angle a: è is determined by the equation for tan Yin 1-00.

In a similar manner the angles of the other forms may be obtained.


In the projection of crystals, the eye is supposed to be at an infinite distance, so that the rays of light fall from it on the crystal in parallel lines; and not diverging as in ordinary landscape perspective. If parallel lines were drawn from the vertices of the solid angles of a crystal, to a board placed behind it, and the points thus formed on the board were connected by straight lines, as in the crystal, a representation of the crystal would be formed, constructed according to the mode of projection employed in crystallography. The plane on which the crystal is projected, is termed the plane of projection. This plane may be at right angles with the vertical axis, may pass through the vertical axis, or may intersect it at an oblique angle. These different positions give rise, respectively, to the horizontal, vertical, and oblique projections. The rays of light may fall perpendicularly on the plane of projection, or may be obliquely inclined to it; in the former case the projection is termed orthographic, in the second clinographic. In the horizontal position of the plane of projection, the projection is always orthographic. In the other positions, it may be either orthographic or clinographic. It has been usual to give the plane of projection an oblique position, and to use the orthographic mode of projection. It is however preferable to employ the vertical position and clinographic projection, and this preferable to employ the vertical position and clinographic projection, and this method is clucidated in the following pages.

The projection of the axes of a crystal, is the first step preliminary to the projection of the crystal itself. It will be more convenient to illustrate first the projection of the crystal itself.

ON THE DRAWING OF FIGURES OF CRYSTALS.

tion of the axes in the monometric system, which are equal and intersect at right angles. The projection of the axes in the other cases, may be obtained by varying the lengths of the projected monometric axes, and also, when oblique, their incli-

Monometric System.—When the eye is directly in front of a face of a cube, neither the sides nor top of the crystal are visible, nor the secondary planes that may be situated on the intermediate edges. On turning the crystal a few degrees from right



attuated on the intermediate edges. On turning the crystal a new degrees from right to left, a side lateral plane is brought in view, and by elevating the eye slightly, the terminal plane becomes apparent. Half the planes on the crystal are now visible, and consequently this is a convenient position for projecting it. In the following demonstration, the angle of revolution is designated d, and the angle of the elevation of the eye, a Fig. 151 represents the normal position of the horizontal axes, supposing the eye to be in the direction of the axis BB; BB is seen as a mere point, while CC appears of its actual length. On revolving the whole through a number of degrees equal to BMB' (d) the axes have the position exhibited in the dotted lines. The projection of the semiaxis MB is now lengthened to MN, and that of the semiaxis MC is shortened to MH.

If the eye be elevated, (at any angle, s), the lines B'N, BM and C'H will be projected respectively be-

low N, M and H, and the lengths of these projections (which we may designate b'N, bM, and c'H) will be directly proportional to the lengths of the lines B'N, BM, and C'H.

It is usual to adopt such a revolution and such an elevation of the eye as may be expressed by a simple ratio between the projected axes. Let us designate the ratio between the two axes as projected after the revolution alluded to (MN: MH) by 1: r; and the ratio of b'N to MN by 1: s. Now the character of the view will vary with the values assumed for r and s. Suppose r to equal 3 and s to equal 2, then

proceed as follows:

Draw two lines AA', H'H (f.154) intersecting one another at right angles. Make MH=MH' =b. Divide HH' into r parts, and through the points, N, N', thus determined, draw perpendiculars to HH'. On the left hand vertical, set

off, below H', a part H'R, equal to -b=1H'M;

and from R draw RM, and extend the same to the vertical N'. B'B is the projection of the front horizontal axis.

Draw BS parallel with MH' and connect S, 4. From the point T in which SM intersects BN, draw TC parallel with MH. A line (CC') trawn from C through M, and extended to the left vertical, is the projection of the side horimutal axis.

Lay off on the right vertical, a part HQ equal to MH, and make MA=MA'=MQ; AA' is the vertical axis.

Q

The values of r and s commonly taken, are r=3, t=2, in which case, t=18° 26', and c = 9° 28'. It is not unusual to give s the value of 3, in which case s=6° 20'. This affords a sarrower terminal plane. The angle & sobtained by the equation $\cot \epsilon = r$, the angle ϵ by the equation $\cot \epsilon = r s$.

The regular octahedron may now be drawn, by connecting the extremitie of the horizontal axes, and then miting them by right lines with the points A, A', as in f. 155. If lines be tawn through the points B and B', arallel with C C', and through C, C', arallel with the axis BB', a plane was about is formed, which is a horizontal state of the control of th Through ental section of the cube.

the points a, b, c, d, draw lines parallel with the vertical axis AA', and extend them ad side of these points, to a distance equal to the vertical semiaxis MA. By containing the upper and also the lower extremities of these perpendiculars by lines with the lines ab, bc, cd, da, the figure will represent a cube.

The cube may also be projected by drawing lines from M to the centre of each stoof the octahedron, and then extending these lines to double their length. Their

momities are the vertices of the angles of the cube.

It is convenient to have at hand an accurate figure of a cube drawn on a large scale, as may readily be used by methods explained beyond for making figures of the perisms of either of the other systems. Such a figure may be made as above Draw two lines as AA' and HH, f. 154, crossing at right angles; draw a be CC making an angle 3° 11' with H'H, and BB', making an angle 26° 34', with H'H, each crossing AA' in M. Then, M being the centre of each axis, make 14' 41 inches in length, C'C 41 inches, BB 11 inches. From these axes the cube is

ished in their lengths, occupy the vertices of the solid angles. If therefore these points (the extremities of the interaxes) can be determined in the several crystalline forms, it will only remain to connect them, in order to form a projection of these solids. The principles of analytical geometry afford the means of determining how much the interaxes of the regular octahedron must be increased or diminished to equal the interaxes in these different forms. It is thus found that each half of a trigonal interaxis for any form mPn must be increased by that portion expressed in the fraction

$$\frac{2 \, mn - (m+n)}{mn + (m+n)};$$

and for each half of a rhombic interaxis, we have the corresponding fraction $\frac{n-1}{n+1}$.

By giving m and n different values from 0 to ∞ , the value of these interaxes for any monometric form may be obtained. The following values are thus deduced for several occurring forms:

	Trig. interax.	Rhombic interax.		Trig.	Interax.	Rhombic interax.
2 (f. 49) }	0	∞-2 (f.	33)	1	1/3
oo (f. 14) 1	0	∞-3 (f.	34)	5	+
3-3 (f. 51) 1	1/3	2-2 (f.	39)	+	+
4-2	5 7	1	3-3 (f.	40)	4	1

To construct the form 4-2, the octahedron is first to be projected, and its axes and interaxes drawn. Then add to each half of each trigonal interaxis, five-sevenths of its length; and to each half of each rhombic interaxis, one-third of its length. The extremities of the lines thus extended, are situated in the vertices of the solid angles of the hexoctahedron 4-2, and by connecting them, the projection of this

form is completed.

In the inclined hemihedral monometric forms—that is, those hemihedral forms whose opposite faces are inclined to one another and not parallel, as the tetrahedron, &c.—the rhombic interaxes do not terminate in the vertices of the solid angles, and may therefore be thrown out of view in the projection of these solids. The two halves of each trigonal interaxis, terminate in the vertices of dissimilar angles and are of unequal lengths. One is identical with the corresponding in the holohedral forms, and is called the holohedral portion of the interaxis; the other is the hemihedral portion. The length of the latter may be determined by adding to the half of the octahedral interaxis that portion of the same indicated in the formula

$$\frac{2 mn - (m-n)}{mn + (m-n)}$$

If the different halves of the trigonal interaxes be assumed at one time, as the holohedral, and again as the hemihedral portion, the reverse forms $\frac{(m-n)}{2}$ and $\frac{(m-n)}{2}$

may be projected. The following table contains the values of the above fraction for several of the inclined hemihedral forms, and also the corresponding values for the holohedral portion of the interaxis.


	Hol, interax.	Hem. interax.		Hol, interax.	Hem. inter
(1) 2 (£ 55)	0	2	$\frac{(2)}{2}$ (f. 60)	1	1
(2-2) 2 (f. 59)	+	2	$\frac{(3\cdot\frac{3}{2})}{2}$ (f. 65)	4	1
(3-3)		2	(4-2)	4	1
(2) 2 (sim. f.	60) 1	1	$\frac{(5-\frac{5}{3})}{2}$	3	+

The parallel hemihedrons (for example, the pantagonal dodecahedron, or hemitetraimhedron) contain a solid angle, situated in a line between the extremities of each part semiaxes, which is called an unsymmetrical solid angle. The vertices of these are at unequal distances from the two adjacent axes, and therefore are not in the line of the rhombic interaxes. The co-

coinates of this solid angle for any form, as [a-n], may be found by the formulas [a-1] and [a-1]. By means of these [a-1] and [a-1]. By means of these [a-1] and [a-1] in each of the axes may be determined.

of 166) in each of the axes may be determed: and if lines are drawn through a and in each semiaxis parallel to the other axes, the intersections c c', of these lines will be the vertices of the unsymmetrical solid an-

the marked c of the form $\frac{[m\cdot n]}{2}$ and $\frac{[m\cdot n]}{2}$ and $\frac{[m\cdot n]}{2}$.



The trigonal interaxes are of the same length as in the holohedral forms. The ultes of these interaxes, and of the coördinates of the unsymmetrical solid angle is different parallel hemihedrons, are contained in the following table:

	Trigonal interaxis.	Coord. of the unsym, sol. A.			Trigonal interaxis.	Coord, of the unsym, sol. A.	
[8-3] 2 (f. 74)	+	7	67	$\left[\frac{\infty - \frac{3}{2}}{2}\right]$ (sim. f. 69)	4 5	1 1 3	1
[4-2] 2	57	4	67	$\frac{\left[\infty-2\right]}{2} \text{ (f. 69)}$	1	+	1
[6-\$]	2 3	5	10	[∞-3]	5 4	2 3	1

Directric System.—In an octagonal pyramid, m.n., (f. 89), the interaxes, or diagnosis symmetrically intermediate between the horizontal axes, terminate in the beaxal basal angles. Their length exceeds the length of the interaxes of the octa-

below, by a portion equal to $\frac{n-1}{n+1}$. If therefore the octahedron m and its inter-

us be projected, and these interaxes be increased by a portion of their length ex-

residence in the fraction, $\frac{n-1}{n+1}$, they will equal the interaxes of the octagonal pyra-

This solid may then be projected by connecting the extremities of these services with the extremities of the horizontal axes, and joining all the angles of the retagonal base thus formed, with the extremities of the vertical axis.

Herogonal System.—The dihexagonal pyramid (f. 124) may be projected in the manner as the octagonal pyramid just described; that is, by increasing the

secures by a portion equal to $\frac{n-1}{n+1}$, uniting the points thus determined with the

became a laws, and connecting the angular points of the base thus projected, with

The endenobedron (f. 127 dotted lines)

The scale nobedron (f. 127 dotted lines) mR^n admits of a similar construction with a rhombohedron mR. The only variation required, is to multiply the vertical axis to number of units in n, after the points E and E' in the rhombohedron mR have been determined; then connect the points E, or the points E', with one analysis and with the extremities of the vertical axis.

III. CLEAVAGE.

The mineral mica, as is well known, easily splits into thin transparent plates or laminæ. This is often effected with little more difficulty than separating the leaves of a book, and at once suggests the idea, that like a book, this mineral may be composed of a great number of closely applied leaves. This property of mica depends on its crystallization, and the process of separation is termed cleavage. Galena is another instance of a mineral capable of easy cleavage. It differs from mica, however, in having three cleavage directions at right angles with one another. This mineral, therefore, instead of splitting into thin plates, breaks into small cubes. Calcereous spar also admits of easy cleavage, but yields rhombohedrons. The directions in which a crystal may be cleaved, are termed natural joints, and the slices obtained, are called lamina.

The facility with which cleavage may be obtained, is very unequal in different minerals. In some instances, as in the first above cited, the laminæ are separable by the fingers. In others, a slight blow of the hammer is sufficient; others require the application of a sharp-cutting instrument, and often some considerable skill in its When other means fail, it may sometimes be effected by heating the mineral and plunging it, when hot, into cold water. Attempts of this kind are occasionally effectual with quartz. In many instances, cleavage cannot be obtained by any means, owing to the strong cohesion of the laminæ. In these cases, however, the direction of cleavage is sometimes indicated by lines on the surface. It is often important to observe these lines when cleavage is possible, in order to determine its direction before applying the knife.

When cleavage is easily obtained, it is said to be eminent. The general laws, with respect to cleavage, are as follows:

1. Cleavage in crystals of the same species yields the same form

and angles.

2. Cleavage takes place parallel either to one or more of the faces of a fundamental form, or to its diagonals, or to some secondary planes.

3. Cleavage is obtained with equal ease or difficulty parallel to similar faces, and with unequal ease or difficulty parallel to dis-

similar faces.

4. Cleavage parallel to similar planes, affords planes of similar

lustre and appearance, and the converse.

According to the laws above stated, cleavage is obtained with equal ease or difficulty parallel to all the faces of a cube, octahedron, dodecahedron, or rhombohedron, which solids are contained under equal planes. The right square prism, right rhombic prism, and oblique rhombic prism, may be cleaved these ease similar Of ficulty, parallel to their lateral planes, since these are similar. Often, however, no cleavage can be effected in these prisms, except parallel to the bases, and, in many instances, not even in this direction. Frequently the cleavage is diagonal; in the square prism it will be alike in both vertical axial planes, but in the rhombic

prisms it will be unlike, since these planes are not equal.

The right rectangular, right rhomboidal, and oblique rhomboidal prisms, have the cleavage unequal parallel to their faces, if attainable at all in these directions; and according to the third law, the cleavage in the three directions will produce faces of unlike lastre and general appearance. This is exemplified in gypsum: in one direction, it is cleavable with great facility into thin laminæ of perfect transparency, and highly polished surfaces; in a second direction the crystalline laminæ first bend and then break, exhibiting a surface which is not smooth, nor possessed of much lustre; in a third direction, it is brittle, and breaks immediately on attempting to bend it, affording a surface smoother than the second, but not polished. In thick masses the second and third cleavages are scarcely attainable. Two of these cleavages incline at an oblique angle, but one is at right angles with the third.

Cleavage is said to be basal when in a form it is parallel to the base, (0); and lateral, when parallel to the lateral planes. Prismatic, when parallel to the lateral planes ∞ . Diagonal, in a mombic prism, when vertical and parallel to the planes ∞ - ∞ . In the trimetric system, macrodiagonal, if parallel to the longer diagonal; brachydiagonal, if parallel to the shorter diagonal. In the monoclinic system, clinodiagonal, if parallel to the inclined lateral axis; orthodiagonal, if parallel to the other lateral axis.

When rhombohedrons have a cleavage parallel to a plane truncating the vertical angle, it is described as basal, it being parallel to the base of the related hexagonal prism. When the cleavage sparallel to the faces of a rhombohedron, it is styled rhombohedral. Other cleavages are described by mentioning the particular plane

with which they correspond in direction.

M. A. Baudrimont has recently observed that the three primary rhombohedral cleavages of calc spar are not always absolutely equal, and, moreover, that there are other cleavages not before recognized. His observations seem to show, that while the fact that the vertical axis is normally an axis of symmetry, as demonstrated by the crystallization, and by optical, thermotic, and acoustic investgations, still extrinsic circumstances cause some variations from perfect symmetry in the cleavage, and also correspondingly in the lastre and transparency. The cleavages observed by him are as bllows:—

Parallel to the faces of the primary rhombohedron.
 Parallel to the longer diagonal of the primary faces.
 Parallel to the shorter diagonal of the primary faces.

4. Parallel to different secondary planes.

I. Of the first kind the cleavage may be,

a. Equal in three directions, (normal).—Rare. Iceland spar.

Equal in two directions. Less rare.
 Unequal in three directions. Common.

- II. Of the second kind, the cleavage may be, a. In a single direction. Quite common.
 - b. In two directions unequal. More rare.
 c. In three directions. Very rare.

III. Of the third kind,

a. In one direction. Very rare.

The cleavage parallel to the longer diagonal has long been noticed.

IV. IRREGULARITIES OF CRYSTALS.

The laws of crystallization, when unmodified by extrinsic causes, should produce forms of exact symmetry; the angles being not only equal, but also the homologous faces of crystals and the several dimensions. This symmetric harmony is, however, so uncommon, that it can hardly be considered other than an ideal perfection. Crystals are very generally distorted, and often the fundamental forms are so completely disguised, that an intimate familiarity with the possible irregularities is required, in order to unravel their complexities. Even the angles may vary rather widely in crystals that are seemingly pure.

The irregularities of crystals may be treated of under four heads: * 1. Imperfections of surface; 2. Variations of form and dimensions; 3. Internal imperfections and impurities; 4. Vari-

ations of angles.

I. IMPERFECTIONS IN THE SURFACES OF CRYSTALS.

1. Striated Surfaces.

The parallel furrows on the surfaces of crystals are called strice,

and such surfaces are said to be striated.

Each little ridge on a striated surface is enclosed by two narrow planes more or less regular. These planes often correspond in position to the secondary or primary planes of the crystal, and we may suppose these ridges to have been formed by a continued oscillation in the operation of the causes that give rise, when acting uninterruptedly, to enlarged planes. By this means, the surfaces of a crystal are marked in parallel lines, with a succession of narrow planes meeting at an angle and constituting the ridges referred to.

^{*} Many of the following facts, with the general arrangement of them, are extracted from Naumann's work on Crystallography.

This combination of different planes in the formation of a surface has been termed the oscillatory combination. The horizontal strike on prismatic crystals of quartz, (f. 189 and 193), are examples of this combination, in which the oscillation has taken place between the prismatic and pyramidal planes. As the crystals lengthened, there was apparently a continual effort to assume the terminal pyramidal planes, which effort was interruptedly overcome by a strong tendency to an increase in the length of the prism. In this manner, crystals of quartz are often tapered to a point, without

the usual pyramidal terminations.

Cubes of pyrites are generally striated in such a way that the striæ on adjacent faces are at right angles with one another, as in the accompanying figure. These lines are parallel to the intersections of the primary surfaces with the planes of a pentagonal dodecahedron, (f. 67, 68, and 69), the most common secondary of pyrites; and they have evidently resulted from an oscillation between the primary and this secondary.

Iron Pyrites.

Diagonal striæ sometimes occur on the faces of a cube, showing an oscillatory combination between the cube and octahedron. The rhombic dodecahedron is often striated parallel either with the longer or the shorter diagonal of its faces; the former resulting from an oscillatory combination of the dodecahedron with the regular octahedron, and the latter with the cube

or planes bevelling the edges of the cube, as in Aplome. The accompanying figure represents distorted crystal of magnetic iron from Haddam, Ct., illustrating the oscillation between the octahedron and dodecahedron. The faces of trapezohedral garnets are often striated parallel with the symmetrical diagonal, showing an oscillation with the dodecahedron.

Rhom bohedrons of chabazite and red silver are often striated parallel to the terminal edges, indicating an oscillatory combination



between the primary faces and a secondary plane replacing these edges. Prisms of tourmaline are very commonly bounded by three con-

vex surfaces, owing to an oscillatory combination of the planes I

and i2. (See under Tourmaline).

It is obvious that the irregularities described must at times affect the angle of inclination between planes. The interfacial ingles of a rhombic prism are thus made more obtuse, being tometimes increased 15 or 20 degrees, and occasionally, as just stated, the angles are lost in a curved surface. This seldom leads to important error, since the striations generally show that the faces are not simple planes. Tremolite, Tourmaline, &c., are examples. The striations on the lateral surfaces of foliated minerals like mica and gypsum, are merely the edges of laminæ.

The interposition of foreign substances in parallel lines also produce striations. Brewster attributes to this source the parallel di-

agonal lines in some rhombohedral crystals of calc spar.

Besides striations, the surfaces of crystals are sometimes formed of minute crystals; such are the faces of octahedral crystals of fluor, consisting of minute cubes. Cubes of galena occur at Rossie having truncated angles and edges, in which the surfaces are covered with cubic prominences, the sides of which are parallel to the planes on the angles. These surfaces were probably eroded by some solvent or chemical agent.* Angular markings are also often observed, as on quartz crystals, beryls, &c., indicating the internal structure of the crystal.

2. Cavernous Crystals.

Crystals not unfrequently occur with a deep pyramidal depression occupying the place of each plane, as

pression occupying the place of each plane, as is often observed in common salt, alum and sulphur. The annexed figure represents a cavernous cube of salt. In the solution of crystals, the same form is sometimes obtained, owing to the fact that the centres of the faces yield sooner than the edges and angles. A remarkable cavernous crystal of pyrites, from Almerode, is described by Hausmann. It is an elongated cube with its upper edges replaced by faces of the

dodecahedron; but instead of a corresponding replacement of the lateral edges, a deep rectangular channel occupies the place of each. It resembles a cruciform crystal of Harmotome; but the striations


show that is not compound.

Crystals of gold are often thus cavernous. Sometimes the octahedrons occur with a triangular cavity, in place of each face. The same is met with in other species. They may often be imitated in metallic species by pouring off the fused metal just after crystallization begins; the diagonal planes of the crystal joining opposite edges are entire, while the faces are wanting, showing that the cohesion in the latter is weaker.

Other crystals with cavernous faces are produced by an increase of a crystal on certain sides or planes, and not on others, as in f. 170, of calcite, in which, after the crystal had reached considerable size, it was enlarged on the planes R and not on a. In f. 171, also calcite, a six-sided prism tapering above nearly with a curve, was

^{*} For a paper of great interest by Brewster on the optical figures produced by the action of solvents on the surfaces of crystals, see Phil. Mag. (4), v. 16, Jan. 1851.

afterwards, by a subsequent process, capped with a flat rhombohedral crystal of the same species. It is from Bristol, Ct.





3. Curved Surfaces.

Curved surfaces resulting from what is termed oscillatory combination, have already been noticed. Other curvatures proceed from a curvature in the laminæ constituting the crystal. Crystals of diamond have convex faces, and they are sometimes almost spheres, (f.185, and f. 266 under Diamond). This mode of curvature, in which all the faces are equally convex, is less common than that in which a convex surface is opposite and parallel to a corresponding concave surface. Rhombohedrons of spathic iron and pearl spar are usually thus curved, as is shown under spathic tron. The saddle-shaped crystals of the same mineral, are remarkable instances of several curvatures in the same face.

A singular curvature is shown in the accompanying figure of white iron pyrites. The conical crystals of brown zinc blende and the lenticular and conical crystals of gypsum, are other examples. Crystals of quartz are sometimes curved and twisted. When this takes place in the left-handed and right-handed crystals, the twist is to the right or left, according as the crystal is right or left-handed.*

The surfaces of crystals are sometimes rounded, in consequence of having been partially fused, or dissolved. The globular quartz of St. Lawrence Co., N. Y., is supposed by Prof. Emmons to have been thus rounded.

Prismatic crystals of quartz are sometimes aggregated by their sides, and thus form plates, with the terminations of the crystals on the opposite surfaces. As the crystals continue enlarging at the extremities, these expand, while the confined sides can receive madditions; and the consequence sometimes is that crystals are formed with the prismatic sides concave, the prism being smallest

[•] Fig. 151 of quartz, is a left-handed crystal, as is apparent from the relative strations of the planes.

at middle and largest at the base of the pyramid. It is not usual that such crystals are easily separated from one another, but this sometimes happens.


II. VARIATIONS IN THE FORMS AND DIMENSIONS OF CRYSTALS.

The simplest modification of form in crystals, consists in a simple variation in length or breadth, without a disparity in similar secondary planes. The distortion, however, extends very generally to the secondary planes, especially when the elongation of a crystal takes place in the direction of a diagonal, instead of the crystal-lographic axes. In many instances, one or more secondary planes are *obliterated* by the enlargement of others, proving a source of much perplexity to the young student. The interfacial angles remain constant, unaffected by these variations in form.

As most of the difficulties in the study of crystals arises from these distortions, this subject is one of great importance to the student.


Monometric System.—A cube, (f. 1), lengthened or shortened along one axis, becomes a right square prism, (f. 2), and if varied in the direction of two axes is changed to a rectangular prism, (f. 3). Cubes of pyrites, galena, fluor spar, &c., are generally thus distorted. It is very unusual to find a cubic crystal that is a true symmetrical cube. In some species the cube or octahedron, (or other monometric form), is lengthened into a capillary crystal or needle, as happens in Red Copper and Pyrites. Crystals of acicular pyrites occur at the Middletown (Ct.) lead mine.


An octahedron flattened parallel to a face is reduced to a tabular crystal, (f. 173). If lengthened in the same direction, it takes the form in f. 174; or if still farther lengthened to the obliteration of A', it becomes an acute rhombohedron, (same figure).




When an octahedron is extended in the direction of a line between two opposite edges, it has the general form of a rectangular octahedron; and still farther extended, as in f. 175, it is changed to a rhombic prism with dihedral summits. The figure represents this prism lying on its acute edge, (spinel, fluor, magnetite).

The dodecahedron lengthened along a diagonal between the ob-









time solid angles, becomes a six-sided prism with three sided summits, as in f. 176; and shortened in the same direction, is a short prism of the same kind, (f. 178). Both resemble secondaries to a rhombohedron, and are common in garnet and zinc blende. When lengthened in the direction of one of the crystallographic axes, it becomes a square prism with pyramidal summits, (f. 177), and shortened along the same axis it is reduced to a square octahedron,

with truncated basal angles, (f. 179).

The trapezohedron is still more disguised by its distortions.

When elongated in the line of an octahedral axis, it assumes the form in f. 180; and still farther lengthened, to the obliteration of some of the planes, becomes a scalene dodecahedron, (f. 181). This has been observed in fluor spar. If the elongation takes place along a crystallographic axis, it changes to a double eight-sided








pyramid with four-sided summits, (f. 182); or if these summit planes are obliterated by a farther extension, it becomes a complete eight-sided double pyramid, (f. 183).


Still more complex forms are of occasional occurrence among monometric crystals, especially when modified by secondary planes. Fig. 184 represents a garnet from Monzoniberg; it is a combination of the dodecahedron and trapezohedron; but the crystal is so altered by distortion, that only four dodecahedral faces (e) remain, and sixteen of the trapezohedral, (a'); and the latter are of very

nnequal size. Fig. 185 is a distorted twin of diamond. It is shortened in the direction of a diagonal, so that only two octahedral planes (a) remain, and 12 out of 48 planes o'—the six around each



a, (f. 51). Fig. 186 represents a crystal of Galena from Rossie. It is a shortened cube; the lateral faces are very irregularly curved, and consist of the primary faces of the cube and the planes truncating the lateral edges. Some of the terminal edges are also truncated. The crystal is surmounted by a low pyramid, consisting of four planes on each of the angles and edges, which, owing to the distortion, do not occur elsewhere on the crystal. The cleavages of the crystal easily explain the relations of the several planes to the primary.


The scalene dodecahedron of calcite is shown distorted in f. 187,



Figures 339, 340, under Quartz, are other crystals less distorted. The inclination of R on a or a" is the same


in all the various distorted forms; and by measuring the angles, and also by observing the similar surfaces of like planes, the homologous parts may be distinguished, however much disguised. The angle a on a around the prism is 120°; and consequently by a

measurement these planes may be detected. It is also a help to note that like planes are alike in surface.



The prismatic planes of quartz may be usually distinguished from the other faces, by their horizontal striæ.

Fig. 190 of apatite is the same form that is represented in f. 191, but greatly distorted. The planes e', e, e'', between P and the right 11, are enlarged, while the corresponding planes below are in part obliterated. By observing that similar planes are lettered alike,





the two figures may be compared throughout. Fig. 192 represents hexagonal prism of beryl distorted so as to resemble a rhombic prism with the acute lateral edges truncated, two opposite planes being nearly obliterated by the extension of the other four.

Curved Crystals.—Curves in imbedded crystals are of frequent occurrence; and in implanted crystals they are not very uncommon. The annexed figure of quartz (f. 193) illustrates this kind of distortion; the same is described by Beck as occurring in the apatite of St. Lawrence Co., N. Y. Six-sided prisms of calcite are occasionally curved in the same manner.

In many species, the crystals appear as if they had been broken transversely into many pieces, a slight displacement of which has given a curved form to the prism. This is common in tourmaline

and beryl. The beryls of Monroe, Conn., often present these interrupted curvatures, as represented in f. 194.





Singular curvatures occur in crystalline plates of ice adhering to stems of plants. These plants are commonly implanted longi-



tudinally either on one side or opposite sides of the stem, and many curve so far around as nearly to encircle it. They have a fibrous look, like some varieties of gypsum. They are often observed (as at New Haven, Ct.) in temperate latitudes in the cold season. instance of the same on a stone wall recently built, has been observed by Professor Rigaud. The plates of ice were attached to the edges of the stones and curved away from the mortar.* Similar crystallizations of gypsum from the mam-moth cave of Kentucky, have been described by Dr. Locke of Cincinnati. (Am. Jour. of Science, xlii.) "Alabaster rosettes" are common there a foot in diame-

ter, consisting of a disk surrounded by circles of leaves rolled elegantly outward; and tortuous vines with tendrils, and curled leaves, are beautifully imitated.

^{*} See also a paper by Prof. J. Le Conte, on this subject, Proc. Amer. Assoc. iii, 1850, p. 20.

III. INTERNAL IMPERFECTIONS AND IMPURITIES.

The transparency of crystals is often destroyed by disturbed crystallization, or by impurities taken up from the solution during the process of crystallization. Oxyd of iron, chlorite, pyrites, silica, and alumina, are among the most common of these impurities. Any mineral, indeed, that may be dissolved or mechanically suspended in the menstruum with the crystallizing mineral, may be thus entangled and forced into the constitution of crystals.

The impurities often take a symmetrical arrangement. In general, foreign matters collect most abundantly about the centre and along the diagonals, and also in planes between the centre and edges of the crystal. The latter taking place in the cube, produces an arrangement similar in form to the cavernous cubes above de-

cribed.

In chiastolite, the foreign matter is arranged about the central axis, and in planes running from this axis to the edges, and also about the lateral edges and exterior surface of the crystal, (see figures under Andalusite). Dr. Jackson has observed the same in staurotide. Tremolite has also been observed, according to Naumann, with an interior tesselated structure, like chiastolite. It had crystallized in contact with pulverulent carbonate of lime and magnesia. Fluor spar, common salt, and numerous other species, sometimes present similar appearances. The zircons of St. Lawrence County, New York, often have a tesselated structure. Some crysals are grayish-white with the exception of the angles, which are bright chestnut-brown, either of a uniform color, or in parallel tripes about the plane 33. In one crystal from this region, Prolesor Beck found a nucleus of carbonate of lime, and it is probable, as he suggests, that the white coloring matter thus symmetrically arranged, is carbonate of lime.

Crystals of quartz from Southington, Ct., have an asteriated structure within, arising from the meeting at centre of six whitish planes, corresponding to the six lateral edges of the crystals; the

aterior of the prism is also whitish.

In many instances, the foreign matter lies in layers parallel with ome of the exterior planes. This is often noticed in crystals of quartz, in which there are layers of different colors parallel with the faces of the terminal pyramids, owing usually to intermissions in the process of their formation. In this way transparent crystals meetimes have an exterior coating of an opaque white color, or ontain a crystal within of different color, &c. Tabular crystals theavy spar are often banded parallel with the lateral faces.

The mica from Jones's creek near Baltimore, contains opaque mes or bands in concentric hexagonal figures, which arise from the same cause. In one specimen the meeting of two hexagonal

figures indicated a compound structure, or twin crystallization, a fact not apparent from any peculiarity on the surface of the mica. A mica from New Hampshire has similar markings, and in one transparent specimen in the cabinet of Dr. Jackson of Boston, there are broad bands of a deep black color meeting at angles of 120° and 60°, the angles of the crystal.

Among the most remarkable impurities are the drops of liquids that occur in many crystals. In some cases they appear to be simply water or a solution of the mineral itself, and when exposed by fracture, crystallization takes place on evaporation. In other instances, they are resinous fluids of different kinds, as first detected by Sir David Brewster in topaz, quartz, and other minerals.

The same author has discovered in topaz innumerable microscopic crystals arranged more or less in extensive layers, though sometimes in concentric arches or radiations, among which were many different forms, as the tetrahedron, the cube and its secondaries, rhombohedron, hexagonal plates, prisms with plane and pyramidal summits, flat octahedron more or less modified, rectangular plates. Some of the tesseral crystals melt easily and others not at all; and others are infusible: so that at least five different substances were indicated.* Two different fluids have been recognized by Brewster in some topazes. In one crystal a cavity 0.18 in. long was partly filled with a fluid of still different character, besides different crystals. Fluor spar, Calcite, and Heavy spar are other species that have been found to contain fluids.

A microscopic examination of iridescent feldspar has brought to light that in some cases it contains minute crystals of specular iron disseminated through it, to which the peculiar iridescence is

owing. The same is true of some red Cancrinite.

IV. VARIATIONS IN THE ANGLES OF CRYSTALS.

The greater part of the distortions described occasion no change in the interfacial angles of crystals. But those imperfections that produce convex, curved, or striated faces, necessarily cause variations, as explained on pp. 111, 113. The surfaces of larger crystals often have a composite character, as a magnifying glass will show, if not visible to the naked eye; they appear as if there had been a tendency to the formation of smaller crystals, while the crystal was enlarging. The polygonal markings on quartz crystals are of this character. Octahedrons of fluor sometimes have the faces made up of little cubes. Such a cause produces more or less irregularity in the planes and their inclinations. Sometimes while

^{*} See further on this subject, Trans. Roy. Soc. of Edinburg, for 1823 and 1826; and Trans. Royal. Soc. London, 1847, xvi, 11; Phil. Mag. [4], v. 235, 1853; also Amer. Jour. Science, xii, 214, 1827, and [2] v, 420, 1848.

enlargement is in progress and far advanced, portions of a crystal become more or less independent in their crystallization, and thus quite large variations from symmetry result, exhibited either in the unnatural protuberance or breadth of certain parts, or a subdi-

vision into distinct crystals.

Besides imperfections from these sources, there are others derived from the presence of impurities, entangled in the crystallizing mineral. Such impurities, although in many instances symmetrically arranged, still influence unfavorably the form of the crystal; the foreign particles are guided in an imperfect degree by the forces of the crystallizing molecules, and have not the powers of arrangement in themselves which can carry each to its place; and hence impure crystals, as macles, commonly differ much in their angles. When these foreign ingredients are not thus symmetrically arranged, their injurious effect on the form is even more striking; and there are few cases of crystals of large size, in which such impurities do not exist.

Even the presence of foreign ingredients in solution, when the crystallization is going on, seems often to affect the angles; and such ingredients may be included in the species without its being at all

apparent except by analysis.

According to the measurements of calc spar by A. Baudrimont, the rhombs of this mineral seldom have the three angles at sum-

mit perfectly identical.

The variations of angles just alluded to, are of no constant chancter, and are therefore imperfections. They often amount to 30' even in crystals that appear regular, and sometimes to two or three degrees. A cube under some circumstances may have the angles of a rhombic prism; but the identity of the similar faces, and the teseral character in the modifications of the crystal, will still be apparent; the six bounding planes will be alike in lustre, cleavage, hardness, and striæ, however much the angles may vary, and this sever the case with any but equilateral solids. The distribution of modifying planes will prove in like manner the perfect similarity of the edges and angles. So in a form resembling a rhombohedron, if the angles at the lateral edges differed fundamentally from one another, the edges would be unlike, and the modifications would be monoclinic, (or those of an oblique rhombic prism), instead of rhombohedral. Thus by means of the modifications and physical characters, as already illustrated, we may distinguish without difficulty between accidental variations and those of a fundamental character. Without such modifications some cubical crystals, as of salt, might be taken for rhombohedrons of 92°

The angles of crystals are varied also by temperature. But this kind of variation depends on the nature of matter or its relation to

heat, and is not properly noticed in this place.

V. DETERMINATION AND MEASUREMENT OF CRYSTALS.

Owing to the irregular variations of form in crystals, it is evident that the shape alone is seldom sufficient to determine the system of crystallization. The indications giving important aid, may be

briefly reviewed.

a. Cleavage.-Cleavage being alike parallel to like faces, and unlike parallel to unlike faces, if a cube affords three equal rectangular cleavages, (equal in ease and alike in lustre), the form must be monometric; if two equal rectangular cleavages, it is dimetric; if three unequal, it is trimetric. Again, if the angle between the cleavage planes is oblique, this gives further evidence as to the system, as the principles already explained sufficiently elucidate.

b. Lustre, Hardness, Color, Character of Surfaces.—Like planes are alike in lustre, hardness, striæ, whatever may be the variations in size. Hence, if a cube has like striæ on all its six sides, the form is plainly monometric; but if the surface of one of its opposite sides differs from that of the others, the form belongs to some other system. So hardness and color often differ, and lustre almost uniformly, for unlike planes. (See beyond, under Color).

c. Refraction, Polarization.—As explained on a following page, the system of crystallization has generally a direct relation to the polarizing properties of the crystal. When we have but fragments

of a mineral, this mode is highly important.
d. Heat, Elasticity.—The properties of crystals as regards the conduction of heat, and their elasticity, have a direct dependence on their crystalline form; but the means of making observations on these points are not yet easily obtained, and require much skill

in their application.

e. Character of the modifications of crystals.—The position of planes upon crystals is an unerring guide to the system of crystallization, when the crystal is much modified, (except in some of the grosser distortions), and may serve to correct deductions from measurements. If a cube is found to have slightly oblique angles on measurement, and still the edges are all modified alike, and the angles also alike, there is good evidence that the crystal is monometric, for only like parts of a crystal are alike in their modifications. If the crystal were rhombohedral, as the apparently oblique angle might be thought to imply, there would be two kinds of edges to the rhombohedron, and two kinds of solid angles, to be modified differently. If a cubical crystal has different planes in number or inclination on a set of lateral edges from what it has on the basal, the form must be dimetric. The same principle is easily applied to other cases. In such examinations, the characters mentioned in the following table should be noted:-

1. All edges modified alike.
2. Angles trunc. or repl. by
3 or 6 similar planes.

MONOMETRIC
System.

Number of similar planes at extremities \ HEXAGONAL of crystal 8 or some multiple of 8. The superior Two adjacent, or two approximate sim. pl. impossible. System. basal modifications in front not similar to the corresponding Two adjacent, or) Monocliinferior in front two approximate or superior besim. pl. possible. System. N.B. The Right Rhomboidal Prism on its 1. All edges not modified alike. Rhomboidal base may be distinguished from the other right prism by the dissimilar modifications Number of sim-1 Two or none of its lateral and basal edges and angles. of the angles ilar planes at extremities of crystrunc. or repl. 1. Similar planes tal, neither 8 nor by 3 or 6 simiat each base either DIMETRIC r planes. a multiple of 8. 4 or 8 in number. The superior 2. All lat. edges System. basal modifica-(if modified) simil. tions in front trunc. or beveled. similar to the corresponding 1. Similar planes inferior in front at each base either or superior be-2 or 4 in number. Trinet-2. All lat. edges hind. (if modified) not System. simil. truncated or beveled.

The following are important laws for determining dissimilarity of planes, and their application will often prove a similarity where, from the great dissimilarity in the size of the planes, it was not supposed to exist.

Planes equally inclined to the same plane, are similar.
 Planes equally inclined to similar planes, are similar.

b. Measurement of Angles.—The importance of this means of ascertaining the system of crystallization is obvious. As has been implied, it may lead to erroneous deductions; but in most cases it enables us to correct conclusions drawn from other sources. It generally gives essential aid in carrying out the mode of discrimination last laid down.

The occurrence of the angle 120° should always suggest the possibility (not the certainty) that the form may be hexagonal or monometric; or of 109° 28′, or 70° 32′, that the form may be the regular octahedron; or of 135°, that one of the planes giving the angle truncates a rectangular edge.


these statements may be generally applicable both to prisms and octahedrons.

The rhombohedron is the only solid included in this division, any of whose angles admit of a truncation or replacement by three or six planes.
 The terminal edges of the octahedrons are here termed lateral, in order that

USE OF GONIOMETERS.

The angles of crystals are measured by means of instruments called Goniometers.

a. Common Goniometer, called also, Hauy's Goniometer.—The simplest of these instruments, called the Common Goniometer, is here represented. It consists, 1, of a semicircular arc graduated to half degrees, and, consequently, measuring 180°; 2, two arms, one of which, ab, is stationary, or admits only of a sliding motion back-



ward and forward, by means of slits, gh, ik. The other arm turns on o, the centre of the arc, as an axis; there is also a slit, np, in this arm. By means of these slits, the parts of the arms below o, that is, ao, co, may be shortened, which is found necessary for the measurement of small crystals. The faces, whose inclination is to be measured, are applied between the arms ao, co, which are opened till they just admit the crystal, and are seen to be closely applied to the surface of the same. This should be determined by close examination, holding it at the same time up to the light and observing that no light passes between the arm and the plane of the crystal. The number of degrees on the arc, between k and the left edge of d, (this edge being in the line of the centre o of the arc), is the required angle.

For measuring crystals partially imbedded, the arc is usually jointed at f, so that the part, af, may be folded back on the other quadrant. When the angle has been measured, the arms are secured in their place by the screw at o, and the arc restored to its former position, and there fastened by the bar, mo. The angle may now be read off. The arms sometimes admit of being separated from the arc, in order to obtain more conveniently the required angle. They may then be adjusted to the arc in a very simple manner, which will be understood by the observer without expla-

nation, and the angle read off as above.

When a goniometer is not at hand, approximate results may be obtained by means of an extemporaneous pair of arms, made carefully of mica, or even of Bristol board. After taking the angles with them in the manner explained, place them on a sheet of paper, and with a pencil and ruler lay off the angle by drawing lines parallel with, or in the direction of, each arm of the forceps. This angle may then be measured by means of a graduated arc, or a scale of cords or tangents.

The results obtained with a common goniometer are seldom within a quarter of a degree of the truth. For polished crystals, we have a much superior instrument in the Reflective Goniometer

of Wollaston.

b. The Reflective Goniometer of Wollaston.—The reflective goniometer is represented in the annexed figure. The principle on which this instrument is constructed may be understood by reference to the following figure, which represents a crystal, whose an-


gle, abc, is required.

The eye at P, looking at the face of the crystal, k, observes a reflected image of m, in the direction of Pn. The crystal may now be so changed in its position, that the same image is seen reflected by the next face, and in the same direction, Pa. To effect this, the crystal must be turned ~

around, until abd has the present direction of bc. The angle dbc, nessures, therefore, the number of degrees through which the avstal must be turned. But dbc, subtracted from 180°, equals the required angle of the crystal, abc. The crystal is, therefore, passed in its revolution through a number of degrees, which subtracted from 180° give the required angle. This angle evidently might be measured by attaching the crystal to a graduated circle, which should turn with the crystal.

This object is convenientby accomplished by the ingenious and simple contrivance of Wollaston.

AB is the circle, graduated to half degrees. By means of the vernier, v, minutes are measured. The wheel m is attached to the main axis, and moves the graduated circle, together with the adjusted crystal. The wheel n is connected with an axis that passes through the main axis, (which is hollow for the purpose), and moves merely



the parts to which the crystal is attached, in order to aid in its adjustment. The contrivances for the adjustment of the crystal are at p, q, r. To use the instrument, it must be placed on a small stand or table, and so elevated as to allow the observer to rest his elbows on the table. The whole, thus firmly arranged, is to be placed in front of a window, distant from the same from six to twelve feet, with the axis of the instrument parallel to it. Before operation, a dark line should be drawn below the window near the floor, parallel to the bars of the window; or, what is still better, on a slate or board, placed before the observer on the table.

The crystal is attached to the movable plate q, by a piece of wax, and so arranged, that the edge of intersection of the two planes, including the required angle, shall be in a line with the axis of the instrument. This is done by varying its situation on the plate q, or the situation of the plate itself, or by means of the adjacent

joints and wheel, r, s, p.

When apparently adjusted, the eye should be brought close to the crystal, nearly in contact with it, and on looking into a face, part of the window will be seen reflected, one bar of which must be selected, or a cord stretched across the window, for the experiment. If the crystal is correctly adjusted, the bar or cord will appear horizontal, and on turning the wheel, n, till this bar, reflected, is observed to approach the dark line below, seen in a direct view, it will be found to be parallel to this dark line, and ultimately to coincide with it. If there is not a perfect coincidence, the adjustment must be altered until this coincidence is obtained. Continue then the revolution of the wheel, n, till the bar or cord is seen by reflection in the next face, and if here there is also a coincidence of the reflected bar or cord with the dark line seen direct, the adjustment is complete; if not, alterations must be made, and the first face again tried. A few successive trials of the two faces, will enable the observer to obtain a perfect adjustment.

After adjustment, 180° on the arc should be brought opposite 0 on the vernier. The coincidence of the bar and dark line is then to be obtained, by turning the wheel n. As soon as obtained, the wheel m should be turned until the same coincidence is observed, by means of the next face of the crystal. If a line on the graduated circle now corresponds with 0 on the vernier, the angle is immediately determined by the number of degrees marked by this line. If no line corresponds with 0, we must observe which line on the vernier coincides with a line on the circle. If it is the 18th on the vernier, and the line on the circle next below 0 on the vernier, marks 125°, the required angle is 125° 18'; if this line

marks 125° 30', the required angle is 125° 48'.

Some goniometers are furnished with a small polished reflector attached to the foot of the instrument, below the part s q, and placed at an oblique angle so as to reflect a bar of the window. This is an important improvement, as the reflected bar answers the purpose of the line drawn below the window, and is more conveniently used. This reflector may be easily added to the common instruments, placing it at an angle of about 45°, or such as will reflect the bar to the eye when looking towards the crystal while observing.

Mitscherlich's Goniometer has a small lens mounted in a tube for sighting the crystal; but the lens diminishes so much the light reflected by the crystal to the eye, that it is not generally of much value. This instrument is furnished also with a micrometer screw for aid in turning the graduated circle, and certain valuable

contrivances for adjusting the crystal.

Mohs's Goniometer differs from Wollaston's mainly in having

the circle horizontal.

Babinet's Goniometer has a horizontal graduated circle. The crystal is placed at centre on the axis, with the edge vertical. There are two glasses mounted horizontally, with tubes and cross threads, for sighting the crystal: both are attached to the graduated arc, one moveable, the other fixed. The crystal is so placed that one face, (of the two including the required angle), on being viewed through the movable glass reflects the sight-threads of the other glass; it is then turned around till the other glass gives the ame reflection. The arc through which the crystal is revolved, is then read off on the graduated circle.

Adelman's Goniometer is an ingenious contrivance, made at Paris, combining a common and a reflecting Coniometer. It is

much less costly than Wollaston's.

In goniometrical measurements, a knowledge of the simple nathematical principles stated on page 61 are of great importance.

For accurate measurements of the angles of crystals, the temperature of the crystals should be noted; the angles often change somewhat with a change of temperature, as stated in the remarks on Heat.

VI. COMPOUND CRYSTALLINE STRUCTURE.

The compound crystalline structure of minerals is exhibited either in distinct crystals having a composite character, or in aggregated crystallizations. The former are called *Compound* or *Trin Crystals*; they have regular facets and the same perfection of outline and angle as simple crystals.

Compound crystals may be compared to monsters in the animal kingdom. They may be composed of two united crystals, or of

everal

Compound Crystals, composed of two individuals, or Twin Crystals.—Representations of some of these compound forms are

given in the following figures, and in connection with the descriptions of many species through the succeeding pages of this work. Their structure may be imitated by cutting a model of a crystal in two halves, inverting one of the halves, (or revolving it 180°), and



then applying it thus inverted to the other half. Fig. 199 is an octahedron, which is represented as cut in two in the plane abcd. If we revolve one half 60° or 180°, and reapply it to the other, it produces the form in f. 200.

In compound crystals, composition may take place parallel to different secondary planes, but generally it occurs parallel to some face of the fundamental prism, or to the diagonal planes, that is, parallel to planes I, ii, 1i, or 1. Composition parallel to other faces is occasionally met with.

There are two modes in which composition may take place. They may be explained by reference to the method of imitating them, as follows. On dividing a crystal into halves, and holding the plane of division vertical,—

(1). One of the halves may be inverted, as if by revolution 180°, on a horizontal axis at right angles to the plane of section, and the two again united by the surfaces that were separated.

(2). One of the halves may be turned around, through 180°, as if by revolution on a horizontal axis parallel to the plane of section, and the face opposite and parallel to that of the plane of section may then be applied to the other half.




Fig. 201 represents an oblique prism, bisected vertically along the plane a c. The back planes may be considered as lettered like those in front with the addition of an accent. The first of these two modes of composition is illustrated in f. 202; p m t is inverted so that the back plane m' is in front, in

place of m, and p is at top in place of p'. In the second mode, t' would be the outer plane instead of t, the latter being the plane of union with P M T; and p' would be at top as before, but m would remain in front. In the junction of the two parts, by this second mode, an obtuse plane angle of one of them comes against an acute of the other, so that the two parts do not fit into a symmetrical solid, unless the acute edges of the prism (the opposite edges a and e) be truncated, which is usually the fact in species in which this mode of composition occurs, viz. Feldspar and Albite.

The first of these modes of composition may occur in each of the systems of crystallization, though not always apparent in all, in the external form. Examples of it are sometimes distinguished by internal arrangements of color, or by optical characters, when not otherwise recognizable. The second mode is of rare occurrence.


In the monometric system there may be composition in three directions, (1), parallel to an octahedral face or a plane truncating the angle of a cube; (2), parallel to a dodecahedral face, or a plane truncating the edge of a cube; (3), parallel to a face of the cube. The first kind produces forms with reëntering angles; and the second and third also when occurring in hemihedral forms. The third kind and the second, except in the case mentioned, are not distinguishable by the form, as the inversion of the halves of a cube parallel to a cubic face, or parallel to an edge, produces only a cube still, and no change of the apparent form. Such twins in bolohedral forms cannot therefore be recognized by the external form when they occur.

Fig. 200 represents a twin of the first of these kinds; it occurs in spinel, Magnetite, &c. When the form is shortened parallel to the pane of union, it becomes tabular, and is sometimes quite thin

tabular.

Fig. 203 exhibits the same kind of composition in a dodeca-

bedron. One half, as in the case of the ceahedron, is revolved 60°, (or the result sequivalent to this). In a cube it protess a solid made up of two cubes united their angles, parallel to an octahedral time. In a form like f. 34, the result is smilar in kind, but sometimes the six faces tout one solid angle, and the six about the diagonally opposite, form together twin having the form of a low double maded pyramid, resembling somewhat 180, as in Native Copper, the interme-




In the parts being absent. Fig. 185 is an example in the Diamond. In the 273 of Blende, a revolution of 60° produces the solid in f.


In the dimetric system twins may occur parallel to (1) the basal time (O) of a prism; (2) a lateral plane, ii; (3) a vertical diagral plane I; (4) a plane replacing a basal edge of the prism ii, and we plane 1i; (5) a plane replacing an angle, usually plane 1. The last two kinds are marked by reëntering angles in holo-blad forms, or are recognizable except it be by optical characters, while all may be distinguished in hemihedral forms.

The annexed fig. 204 represents a square prism terminating in a manid, divided by a diagonal section; and f. 205 shows the form ling from revolving one of the halves thus formed 180°. It is

amon in tin ore, (Cassiterite).

The square octahedron 1i or 1 gives rise to twins by composition parallel to one of its faces, similar to f. 200, but of less symmetrical





205

character, a process that may be instructively followed through by cutting out models. A form of this kind is represented in f. 295; composition is parallel to 1i. Tabular forms may result with this kind of composition; and thin tables thus formed are sometimes

aggregated, or, as it were, piled up, together.

In the trimetric system composition may occur in the same directions as in the dimetric; and as the lateral axes are unequal, twins formed by composition parallel to these axes, (as to planes 17 or 17), are different in kind. Composition parallel to the axial sections, as in or in, does not produce twins recognizable as such by external form; but when it takes place parallel to the plane I, (f. 4, 22, 24), as these planes form a rhombic prism, there are reëntering angles, as shown in Aragonite, (q. v.) An example of composition par-

allel to plane 1% is given in f. 332, under Manganite.

In the oblique systems, twins parallel to the axial sections may have reëntering planes, or planes in abnormal positions, as a result of the composition, as well as those formed by composition in other directions. Fig. 357 (Augite) represents an example of composition parallel to ii, the simple form of which is shown in f. 350. Fig. 362 is another in Hornblende; f. 361 is the simple form. Fig. 415, 416 (Albite) are examples of composition parallel to ii; the former, by an inversion of the first kind, and the other of the second kind, described on page 128. Fig. 424, 425, are twins of Orthoclase, compounded parallel to ii, similar to the last mentioned of Albite. In f. 428 composition is parallel to 2i. Gypsum and several other species afford additional examples.

In the hexagonal system, twins of rhombohedral forms occur compounded (1) parallel to the terminal plane O(0R); (2) the prismatic planes I or i2; the rhombohedral faces (R); (4) planes truncating the terminal edges, or $-\frac{1}{2}R$; (5) rarely parallel to the

face of the pyramid 1-2 and the rhombohedron -2R.

When composition is parallel to O, the twin appears as if made


by a revolution through 60° of one half of the simple crystal, the axis of revolution being the vertical axis of the prism. Several figures under Calcite (q. v.) are forms of this kind. A similar mode of composition produces the form in f. 300 A, (Pyrargyrite); the hexagonal prism of the simple crystal has its alternate edges truncated; and in the compound form (produced through a revolution of one half 60°) this truncation appears on half of each edge alternately above and below. Composition parallel to I is represented in one of the forms of Calcite, (q. v.) Composition parallel to R occurs in Calcite, Chabazite, Quartz, &c. Composition parallel to $\frac{1}{2}R$ is met with in Calcite and Pyrargyrite; see f. 300. Composition parallel to -2R is exemplified under Calcite, (q. v.) Composition parallel to the pyramid 1-2, or an edge of the common pyramid of Quartz, sometimes occurs, (f. 342).

In the compound forms which have been described, the crystal is generally as complete and well finished as the simple form, and it is obvious that the formation of the twin commenced with the nucleal molecule, which itself possessed the compound character, it consisted essentially of two molecules. Such twins are properly paragenic; and they are distinct from another kind, metaguic, in which the composition took place subsequently to the commencement of the crystal.

In metagenic twins, the two parts of the twin are not united long a diagonal section, but by parts more or less distant from the proper centre of either. Such are the forms represented in

1345, 346, (Quartz).


A mode of metagenic composition is observed in doubly geniculated crystals, as tose of Rutile, annexed figure. The geniculations take place at equal distances either one of the centre of the crystal, and are ridently the result of some cause acting ther the crystal had begun to form. The reniculation is usually parallel to a plane common occurrence, either, one of those of the fundamental form, or its simplest modifications. This geniculation often is frequently repeated in the same crystal, and thus the ends of a crystal are, by successive reniculations, bent around together or into me another, as happens in Rutile.



In the monometric system, in which the axes are all equal, the monometric system, in which the axes are all equal, the map occurring along one octahedral section may occur reallel to all such sections alike; and hence comes a compound form of pyrites, (f. 282 A), made up of pentagonal dodecahedrons. It corresponds to an interpenetration of two pentagonal dodecahedrons.

drons, a right and a left, (+ and —). In a similar manner there results the compound form represented in f. 306, which becomes very complex when the crystals are highly modified. Fig. 272 A, represents a crystal of Galena of this kind, distorted by being shortened in the direction of an octahedral axis.

In tetrahedral forms, composition parallel to the cubic faces produces the form in f. 207, which may be viewed as made of two interpenetrating tetrahedrons. By this method is formed the twin



of Diamond represented in f. 267 A. With the composition parallel to an octahedral face, the form in f. 208 is produced, also made of two interpenetrating tetrahedrons. It illustrates the origin of the twin of Gray Copper in f. 303 A.

In the dimetric system, the eight octahedral sections are similar to one another, as in the monometric, and hence there may be composition simultaneously parallel to all. Very complicated forms are thus produced in Copper Pyrites and Tin Ore. Fig. 295 A, represents one of the occurring forms of Copper Pyrites.

represents one of the occurring forms of Copper Pyrites.

In the trimetric system, cruciform



In the trimetric system, cruciform and stellate crystals are common. Fig. 209 represents a form in chrysoberyl. Other varieties are shown in f. 233, 234, 236, beyond; others under Staurotide, Aragonite, Cerusite, and Harmotome. In the stellate forms, the compound crystals consist of three or six rays, when the angle of the prism is near 120°, or one-third of 360°, and five rays when about one-fifth of 360°, as in Marcasite.

In rhombohedral species, as Pyrargyrite, Chabazite, Levyne, and Cinnabar, compound crystals occur, which in the simplest form resemble f. 306 of Fluor spar. They may be viewed as formed by the interpenetration of two rhombohedrons a + and a —, with the vertical axis as the axis of composition, or by a composition of six crystals united parallel to the prismatic planes I. In Ilmenite, anal-



ogous forms occur; by composition, upon the form in f. 314, compound crystals nearly similar in their faces to f. 313, are produced.

Stellate forms also occur in the rhombohedral system, as represented in the accompanying figure of a crystal of snow, (f. 210). Another form of compound crystal in this system is represented in f. 300, under Pyrargyrite. It consists of four crystals, united parallel to the faces—½R. Crystals are often grouped in linear series, as in Native Copper and Silver, and thus constitute long threads or reticulations. In clustered crystals, it is generally a fact that adjoining crystals are parallel in position, and united by a plane parallel to one of the principal sections or planes of common occurrence. Senarmont mentions the union in Galena parallel to the octahedral faces as common; and he also describes an instance where the union was

parallel to the plane 3-3.

The positions of crystals on the supporting rock seem at first to be without any regularity. By closer inspection we detect even here the same law of harmony that governs the formation of the simple and compound crystal. The various positions assumed correspond generally with the more common kinds of composition in twin crystals. Brooke observes with respect to certain artificial crystallizations of nitrate of lead, that some of the octahedrons "had their axes perpendicular to the surfaces on which they rested"—"others rested on one of their planes, and others were attached by an edge to the bottom of the vessel;" thus exemplifying three kinds of composition. This regularity is not always manifest on account of the unevenness of the surface on which they rest. In general, however, on glancing the eye over a surface covered with crystals, a reflection from one face will be accompanied with reflections from the corresponding face in each of the other crystals, showing that the crystals are similar throughout in their positions.

This tendency to parallelism in the positions of associated cystals seven apparent in crystalline aggregates. In granite, for example, which is composed of feldspar, quartz, and mica, the feldspar crystallizations have usually a common position; that is, the corresponding extremities lie in the same direction, or nearly so. On this account granite is cleavable in one direction more easily than in others, and this direction is that of the perfect cleavage plane of the feldspar. The parallel positions of the mica in gneiss causes

the fissile character of that rock.

In some cases also, crystals of different minerals associated together take a parallel or continuous position. Thus crystals of albite and Feldspar, and of Staurotide and Kyanite, at times have this relation; and Breithaupt has observed the same between crystals of Rutile and Specular iron, the crystals of Rutile in this case having the vertical axis in the direction of a lateral axis of the Specular iron. Haidinger has observed Pyroxene and Hornblende crystals associated in parallel positions.

A prism of Calcite terminating in the planes $-\frac{1}{2}$, has been observed, in which each plane $-\frac{1}{2}$ was covered with small crystals of quartz all lying symmetrically, with their pyramids pointing

towards the summit.

The subject of twin crystals will receive further illustration in the chapter on Crystallogeny.

VII. CRYSTALLINE AGGREGATES AND AMORPHOUS VARIETIES.

The greater part of the specimens or masses of minerals that occur on our globe, may be described as aggregations of imperfect crystals. Even those whose structure appears the most purely impalpable, and the most destitute internally of anything like crystallization, are probably composed of crystalline grains. We, consequently, include under the above head, all the remaining varieties of structure in the mineral kingdom. The only certain exceptions are liquids and gases, which require so few remarks, that a separate caption for them is unnecessary.

The individuals composing imperfectly crystallized individuals,

nay be.

1. Columns, or fibres, in which case the structure is columnar.

Thin laminæ, producing a lamellar structure.
 Grains, constituting a granular structure.

1. Columnar Structure.

A mineral possesses a columnar structure, when it is made up of slender columns or fibres. There are the following varieties of the columnar structure:—

Fibrous: when the columns or fibres are parallel. Ex. gypsum,

asbestus. Fibrous minerals have often a silky lustre.

Reticulated: when the fibres or columns cross in various directions, and produce an appearance having some resemblance to a net.

Stellated or stellular: when they radiate from a centre in all directions, and produce star-like forms. Ex. stilbite, wavellite.

Radiated, divergent; when the crystals radiate from a centre, without producing stellar forms. Ex. quartz, gray antimony.

2. Lamellar Structure.

The structure of a mineral is lamellar, when it consists of plates or leaves. The laminæ may be curved or straight, and thus give rise to the curved lamellar, and straight lamellar structure. Ex. tabular spar, some varieties of gypsum, talc, &c. When the laminæ are thin and easily separable, the structure is said to be foliaceous. Mica is a striking example, and the term micaceous is often used to describe this kind of structure.

3. Granular Structure.

The particles in a granular structure differ much in size. When coarse, the mineral is described as coarsely granular: when fine, finely granular; and if not distinguishable by the naked eye, the structure is termed impalpable. Examples of the first may be

observed in granular carbonate of lime; of the second, in some varieties of specular iron; of the last, in chalcedony, opal, and

other species.

The above terms are indefinite, but from necessity, as there is every degree of fineness of structure in the mineral species, from perfectly impalpable, through all possible shades, to the coarsest granular. The term *phanero-crystalline* has been used for varieties in which the grains are distinct, and *crypto-crystalline*, for those in which they are not discernible. Granular minerals, when easily crumbled in the fingers, are said to be *friable*.

4. Imitative Shapes.

Reniform: kidney shape. The structure may be radiating or concentric.

Botryoidal: consisting of a group of rounded prominences. The name is derived from the Greek corgus, a bunch of grapes. Ex. limonite, chalcedony.

Mammillary: resembling the botryoidal, but composed of larger

prominences.

Globular: spherical or nearly so; the globules may consist of radiating fibres or concentric coats. When attached, as they usually are, to the surface of a rock, they are described as implanted globules.

Nodular: in tuberose forms, or having irregular protuberances

over the surface.

Amygdaloidal: almond-shaped, applied usually to a greenstone containing almond-shaped or sub-globular nodules.

Coralloidal: like coral, or consisting of interlaced flexuous

branchings of a white color, as in some arragonite.

Dendritic: branching tree-like.

Mossy: like moss in form or appearance.

Filiform or Capillary: very slender and long like a thread or

Acicular: slender and rigid like a needle.

Reticulated: net-like.

Drusy: closely covered with minute implanted crystals.

Stalactitic: when the mineral occurs in pendant columns, cylin-

ders, or elongated cones.

Stalactites are produced by the percolation of water, holding mineral matter in solution, through the rocky roofs of caverns. The evaporation of the water produces a deposit of the mineral matter, and gradually forms a long pendant cylinder or cone. The internal structure may be imperfectly crystalline and granular, or may consist of fibres radiating from the central column, or may have a broad cross-cleavage.

Common stalactites consist of carbonate of lime. Chalcedony,

gibbsite, brown iron ore, and many other species, also present sta-

Amorphous: having no regular structure or form either crystalline or imitative. The word is from a, privitive, and μορφη, shape.

VIII. PSEUDOMORPHOUS CRYSTALS.

A pseudomorphous crystal possesses a form that is foreign to the

species to which the substance belongs.

Crystals sometimes undergo a change of composition from aqueous agency or some other cause, without losing their form: for example, octahedrons of spinel change to steatite, still retaining the octahedral form; cubes of pyrites are altered to red or brown iron ore; anhydrite becomes gypsum by the addition of water: or crystals are sometimes removed entirely, and another mineral is substituted; as, for example, cubes of fluor spar may be transformed to quartz, without a change of form.

In these and other ways, many minerals appear under a form of crystallization which does not belong to the species. The discussion of the origin and chemical relations of pseudomorphs will be more properly considered in the chapter on Chemical Mineralogy.

Pseudomorphous crystals are distinguished, generally, by their rounded angles, dull surfaces, and often granular composition. They either have no cleavage, or the cleavage is wholly different in direction from that of the mineral imitated. Their surfaces are frequently drusy, or covered with minute crystals. Occasionally the resemblance to real crystals is so perfect, that they are distinguished with difficulty.

SECTION II.

CRYSTALLOGENY.

Crystallogeny, or the formation of crystals, may be discussed either from a practical point of view, by treating of the processes of crystallization and attendant circumstances; or theoretically, by considering the nature of molecular attraction in crystallization, and the laws under which it acts. Under the former head, only a few of the causes that determine the modifications of form in crystall are here mentioned, as a full discussion of the methods of crystallizing minerals by art belongs rather to chemical science.

I. PRACTICAL CRYSTALLOGENY.

Crystallization may take place—from a solution of a crystallizable material; from a state of fusion by heat; from a state of capor, another condition dependent on temperature; from a solid state without fusion, under a continued elevation of temperature. The crystallization of sugar or alum is a common example of the first mode; the formation of ice, of the second; the production of snow from vapor, of the third; and the usual mode of hardening steel, (since it depends on varying the size or system of crystallization of the crystalline grains), is an example of the fourth. All solidification of inorganic matter is probably crystallization, and the solid condition is arrived at in one or the other of these methods. Frequently, however, the solid is formed immediately upon the sombination of the elements that constitute it, or upon the liberation of the substance from some other state of combination.

The formation of distinct crystals usually requires a freedom from disturbing causes, a slow rate of progress in the process, and a large apply of material, or else a gradual supply from some constant source. In many instances a crystal that has been long out of a

solution, may be restored and further enlarged.

Crystallization without a change from the solid state, is well llustrated by facts mentioned to the author by Mr. N. P. Ames. If a bar of tempered steel, bent in the form of a semicircle, be heated on the inner side, when the heat has reached a certain point, the bar may easily be bent around and made to curve in the oppote direction. He states that until the moment when the requisite temperature is acquired, the bar does not yield; but at this moment, a change takes place which is distinctly felt in the hands, and the bar at once bends. He carefully measured the inner and outer curves of the bar, after thus bending it, and found them of the same length as before. This shows that there had been no compression of the particles on the inner side, which would have portened that side, and therefore, also, that there was actually a freedom of motion among the particles on either side. He oberves, moreover, that the elasticity of the inner and outer sides was the same, which would not have been the case were the former empressed. By the old method of restoring a warped sword-blade was rendered unequally elastic, and would spring more easily on me side than the other; but by the means here explained, the elasfifty is perfectly equal on both sides. Here, then, there is a ange in the position of the particles throughout the bar, proriment was often repeated, and he found that, at every time he at the steel, the temperature required was a little above that at which it bent the preceding time. The change resulting from fricbined action of the heat thus excited, and the vibration that takes place. Mr. Ames states instances in which a large bar of iron, used as an axle through a heavy wheel of cast iron, broke square off in the middle, after use for a few months; and in one case, there were two other fractures on either side of the centre. In these instances, the bar was rendered coarsely crystalline, and was wholly unlike the original iron.

Causes of secondary planes.—Beudant, in his treatise on Mineralogy, in which this subject has received some attention, states as the principal cause of secondary planes, the nature of the solvent,

and of the substances it holds in solution.

He remarks, that when the solvent contains, mechanically suspended, minute particles of foreign matter, the crystals formed contain more or less of these foreign particles regularly arranged, either in concentric layers with the laminæ of the crystal, or in the direction of a diagonal, or occasionally intermingled without regular order; and that the crystals thus impure, are more simple and regular than those obtained from a clear liquid. Crystals of quartz are seldom perfectly regular bipyramidal prisms, except when they contain large portions of chlorite or oxyd of iron. But if the solvent contains other substances in solution, either solid, liquid, or gaseous, secondary forms are usually produced. "Common salt, crystallizing from pure water, presents, almost invariably, a cubic form. But in a solution of boracic acid, it always occurs with truncated angles," (f. 15). The Rev. E. Craig, in an interesting article on Microscopic Chemistry, in the Lond. and Ed. Phil. Mag. and Jour. of Science, July, 1836, p. 13, states the following remarkable transformations in crystals of carbonate of copper, produced by a change in the nature of the solvent: "If sulphuric acid be added to carbonate of copper, crystals speedily appear presenting the form of six-sided tabular prisms. Add a little ammonia, the form is changed entirely to a long rectangular prism, with the angles replaced. Add a little more ammonia, and the form changes to several varieties of the rhombic octahedron: a little nitric acid restores again the form of the rectangular prism. In all these successive changes, it is not that a few crystals of another form have been superadded, but each time the metamorphosis is seen to take place in the whole mass."

There are many evidences that the same cause has operated in nature to produce the peculiar secondary planes a crystal presents. Aragonite, in iron mines, crystallizes in very acute pyramidal crystals; but in the gypsum clays, accompanying the saliferous deposits, it always appears in prismatic crystals, grouped so as to form hexagonal prisms. Other similar instances might be added; but this will suffice to establish the fact, that secondary planes often

arise from the peculiar nature of the solvent.

Another cause may be the electrical state of the rock support-

ing the crystal, and also its nature. M. Planiava has observed that, in some instances, in which the form of the *floating* crystal was the primary, it assumed secondary planes as soon as it attached itself to the sides of the vessel.*

In some instances, secondary planes proceed from some permanent peculiarity in the molecule; for, without this supposition, we cannot account for the invariableness in the occurrence of a particular secondary form of some minerals; for example, the pris-

matic form in quartz, whose primary is a rhombohedron.

The influence of magnetism or electricity on crystallization has received some attention, especially from Mr. Robert Hunt. By placing the poles of a horse-shoe magnet against a glass vessel or a plate of glass, in or on which crystallization was in progress, he has found the crystals to be guided in their positions by the poles of a magnet. The facts he has developed have a bearing upon the miformity of position in crystallizations over large areas. But other causes have aided in directing the crystalline structure of rocks, and among them the pressure to which the material was subjected during crystallization may be the most important.

M. Lavalle has shown, (L'Institut, 1853, 90), among his results, that when a crystal of alum lies on one of its sides, as it enlarges, the under surface and the opposite, if there is one similar, enlarge more than the rest; and if an angle be cut off and it be laid on this face thus made, a similar plane forms on the opposite angle, but not on the others; and if all the edges are removed by solution, the crys-

tal will complete again every edge and angle.

Brewster has made some very remarkable investigations on the optical figures which reflected light exhibits upon the surfaces of crystals acted on by solvents, showing the points or directions of weakest cohesion. Phil. Mag. 1853, [4], v, 16.

II. THEORETICAL CRYSTALLOGENY.

THEORIES OF VARIOUS AUTHORS.

Speculations on the nature of molecules have displayed the ingenuity of men of science in various ages of the world. The Grecian philosophers, to account for the various phenomena in nature, imagined the ultimate particles of matter to be at different times "round, oval, lenticular, flat, gibbous, oblong, conical, smooth, bugh, quadrilateral,"‡, and, to afford these atoms the means of miting in the production of compounds, provided them with hooks.

; Epicurus,

^{*} Kastner's Archiv. X, 42; cited in Ferussac's Bulletin. † See remarks on this subject by the author in Amer. Jour. Sci, [2], iii, 393, 394, there there are references to writers on this point.

The investigations of modern times have not, indeed, answered the inquiry, what is this plastic power in nature; but philosophers have been led to satisfy themselves with calling it by the general term, attraction, a term rather expressing the fact, that particles com-

bine, than explaining the nature of this power.

This subject lay uninvestigated, from the times of the ancient philosophers till the 13th century.* From the 13th to the 17th century, appeared Albertus Magnus, + Agricola, + Cæsalpinus, S Boetius de Boot, Baptista von Helmont, Christian Huygens,** Boyle, †† and many others, who advanced various hypotheses as to the seeds of crystals, their generation, &c. But, excepting Huygens, who in a very recondite treatise first developed the doubly refracting nature of Iceland spar, and inferred that its elementary particles were spheroids, to account for this peculiar refraction, none made any real improvements on the speculations of their predecessors.

With Nicolaus Steno, towards the latter part of the 17th century, commences a new era. This author examined minutely the different forms of several minerals, and first deduced the important principle afterwards rediscovered, that, although the faces of crystals are subject to frequent variations of form, their inclinations remain constant. ‡‡ In the commencement of the 18th century, Gulielmini published on the crystallizations of the salts, and advanced another principle equally fundamental, that cleavage in crystals of the same substance yields constantly the same forms. Gulielmini was led, by his observations, to the same conclusions as

^{*} Many of the following facts have been cited from a valuable work on the History of Crystallography, by Dr. C. M. Marx, entitled Geschichte der Crystallkunde; 314 pp. 8vo. Carlsuhe und Baden, 1825.

† De Mineralibus et Rebus Metallicis, 12mo. Colon. 1619.

De Ortu et Causis subterraneorum. Basiliæ, fol. 1657. De Metallicis Libri Tres: Noribergæ, 1602. In Book II, 19, he says: "Relin-S De Metallicis Libri Tres: Noribergæ, 1602. In Book II, 19, he says; "Reinquitur igitur ut sola hexagona fiat, sola enim perfecta est, quia fit ex triplici divisione superficiei ad angulos acutos, sex triangulis in unum veluti centrum cocuntibus, ut omnes anguli externi majores sint recto, ideo ad circuli naturam prope accedunt."

[Genumarum et Lapidum Historia, quam olim edidit Anselmus Boctius de Boot, postea Andr. Tollius. Lugd. Bat., 1647.

[In a work published in German at Sulzbach, in 1683, he subscribes to the opin-

ion, that the different crystals, like plants and animals, proceed each from its own peculiar seeds.

^{**} Christ. Huygeni Op. Vol. I, Amst. 1728, 4to Tractatus de lumine.

†† R. Boyle, Specimen de Gemmarum Origine et Virtutibus. Colon. Allobr. 1680,
4to. P. 6, we find, "Reperiebam in solida lapidis massa cavitates, quarum latera undique circumdederant concretiones, que cum essent pellucide instar crystalli et elegantisime figuratæ, videbantur fuisse succus lapidescens purior, qui tandem percolatione quadam per substantiam crassioris lapidis penetraverat in illas cavitates,
et postquam evaporassent superflue et aqueæ partes, aut imbibitæ fuissent a vicino
lapide, poterant concurrere in pura illa crystalla."

†# Nic. Stenonis, Dissertationis Prodromus de Solido intra Solidum naturaliter
contento. Pistorii, 1763—(first published at Florence, 1669, also, in the Collect.
Academ. de Dijon, Partie etrang. T. IV, p. 383).

the Abbé Haüy, namely, that the elementary corpuscles of bodies possess those simple forms which may be obtained from crystals by cleavage.* He neglected, however, to extend his investigations en this subject, and left to Romé de Lisle and Hauy the honor of founding the science of Crystallography.

Several writers on these subjects appeared during the half centary following Gulielmini; but they made no essential additions to facts.—The theory of tetrahedral atoms was proposed by Ludwig

J. Woodward makes quartz crystal the source of all crystallizations, concerning which he thus expresses himself in his treatise on his collection of "English Fossils," p. 146: "There is in all spar more or less crystal, which renders it more or less diaphanous," &c. Again, p. 220: "Crystal, pure and without mixture of other matter, concretes even into an hexagonal figure, pyramidal or columnar, terminating in an apex or point. Mineral or metallic matter concreting with it, frequently determines it to other figures peculiar to the disposition of each kind of that matter. Iron concreting with crystal, determines it to a rhomboidal figure; tin, to a quadrilateral pyramid; lead, to a cubic."

Somewhat similar was the opinion of Linnæus, who supposed that all crystals contained a salt, and to this owed their crystallization.§ This theory obtained considerable credit at that time. We find it clearly expressed in the Philosophical Transactions for 1749, p. 250, by W. Borlase: "Tis by the force of salts that liquid bodies are thrown into all the geometrical planes, angles, and more compounded shapes, the variety of which is no less surprising, than the constancy and uniformity of each particular species." The discoveries in chemistry soon dissipated these views, and at last established philosophers on this settled ground, that the power of crystallization is naturally and independently inherent in all inorganic matter.

Immediately preceding the commencement of the Abbé Haüy's very successful scientific career, appeared Bergman, Werner, and Romé de Lisle. Bergman has the honor of discovering the fundamental forms of crystals, and Romé de Lisle that of first measuring

^{*} De Salibus Dissertatio epistolaris physico-medico-mechanica conscripta a Dominico Gulielmini; Lugd. Bat. 1707, 8vo. P. 2: "Determinatam figuram non ab unirersali aut particulari architectonico spiritu, non a propria innominata forma, sed a primarum particularum schemate unice derivandam." P. 10: "Corpuscula insectilia, terminata planis superficiebus ita ad invicem inclinatis, ut simplicem aliquam includent figuram." P. 19: "Figuris non omnibus, quæ possibiles sunt, utitur natura, med certis quibusdam tantum, quarum determinatio non est a cerebro eximenda, aut priori probanda, sed ab experimentis et observationibus desumenda."

† L. Bourquet, Lettres philosophiques sur la formation de sels et de cristaux;

Amsterd. 1729, 8vo.

[†] An attempt towards a natural history of the fossils of England, in a Catalogue of the English Fossils in the collection of J. Woodward; 2 vols. London, 1728-9.

§ Systema Nature, ed. VI, p. 160: "Crystallus lapidea sal non est, sed continet sal, cujus figuram gerit, omnis enim crystallizatio ex sale," &c.

their angles, and thus rendering crystallography subservient to the

purposes of the mineralogist.

Haüy seems to have entered on his studies with an entire ignorance of the results of Bergman and Gulielmini, and in all his observations was an original investigator. A mere accident, the dropping of a crystal from his hands and its fracture in consequence, exhibited to him the rhombohedral particles of carbonate of lime. He was thus led to commence his investigations, and with his philosophic mind soon arrived at general conclusions with regard to the primary forms.—An obvious theory as to their structure, that already proposed by Gulielmini, was the next result of his investigations. The primary cube he imagined to be constituted of cubic molecules, for cubes, and cubes only, can be obtained by mechanical division. Similarly, the rhombohedron was formed of rhombohedral molecules.

Investigations, with respect to the situation of secondary planes, and the laws which govern their formation, gave Haüy what appeared to be additional proof of the correctness of his theory. He discovered that the secondary planes on the edges of crystals might be exactly imitated by composing a primary of its molecules, and dropping one row (or, in his phraseology, by a decrement of one



row) of particles in height and breadth, (f. 211), or, two rows in one direction, and one in the other, (f. 212), and so in some simple ratio for all planes. These splendid results proved that the

science of Crystallography was founded on a mathematical basis, and they seemed to establish the truth of Haüy's views, on the same sure foundation.


It appeared, however, to be a difficulty, that cleavage was obtained, in some instances parallel to two primaries at the same time. The rhombic prism, besides its rhombic cleavage, admitted of cleavage parallel to a diagonal, thus dividing it into two three-sided prisms. Again, octahedrons could not be composed of octahedral molecules, except by leaving large spaces, to fill which, tetrahedrons were necessary. Haüy surmounted the first difficulty, by supposing the molecules to be composed of still simpler solids, which he called *integrant* molecules. These are the tetrahedron, the three-sided prism, and the parallelopiped. The second difficulty, however, remained, and could only be avoided by the improbable hypothesis of two nucleal solids, an octahedron, and a tetrahedron.

The difficulties lay unremoved, when Dr. Wollaston brought forward his ingenious views on the *spherical* forms of the molecules of bodies, in the Philosophical Transactions for 1813. It is easily conceived, that many of the primary solids in crystallog-

raphy may be formed by the regular aggregation of spheres. Two four-sided pyramids of shot, (similar to those frequently seen in arsenals), placed base to base, form the regular octahedron, (f.

213). If, to the octahedron, two three-sided pyramids are added, tetrahedrons, one to each of two opposite faces, a rhombohedron is formed, (f. 214). A rhombohedron of this kind is easily obtained in the cleaving of fluor spar; it is reduced to the octahedron by separating two tetrahedrons.

Rhombohedrons, however, occur of various angles. To obtain these, it is



only necessary to suppose the particles of other rhombohedrons to be spheroids, instead of spheres; spheroids are also his molecules of the prisms. The formation of the cube is illustrated by Dr. Wollaston, as follows: "Let a mass of matter be supposed to consist of spherical particles, all of the same size, but of two different kinds in equal numbers, represented by black and white balls; and let it be required that, in their perfect intermixture, every black ball shall be equally distant from all surrounding white balls, and that all adjacent balls of the same denomination shall also be equidistant from each other. I say, then, that these conditions will be fulfilled, if the arrangement be cubical, and that the particles will be in equilibrio." He had previously stated, that "a cube may evidently be put together of spherical particles, arranged four and four above each other; but this is not the form which simple spheres are naturally disposed to assume, and, consequently, this hypothesis alone is not adequate to its explanation."

This theory is in some respects far more simple than that of

This theory is in some respects far more simple than that of Hauy. Yet it is manifest that it received but sparingly the attention of the philosophic mind of Dr. Wollaston. The cube and rhombohedron are similar solids, differing merely in that the latter is oblique. It is surely improbable, that their atomic arrangements should be as different as Wollaston's theory supposes; or with reference to the cube alone, that its formation, or even the

explanation of it, should require two kinds of particles.

Other theories have been proposed, but only one seems to demand a notice in this place, before entering upon that which appears to afford the best explanation of the phenomena. I refer to the *Chemical* theory, as it may be called, since chemical facts are usually explained by a reference to its principles. According to this theory, the atoms of the elements are either spheres or spheroids, and the molecules of compounds result from a juxtaposition of the elementary atoms. These elementary atoms, moreover, are so arranged, that the compound molecule has the shape of the *primary form* of the compound.

It will be remembered that crystals are solids of definite dimensions, and constant angles, exhibiting a perfect symmetry in their several parts, and an exact regularity in the occurrence of secondary planes. In order, therefore, that the similar parts of a crystal should be similarly modified, there should be a corresponding similarity in the different parts of a molecule. The molecule of the cube, besides having the form of a cube, should present a uniformity of character on its six opposite parts, corresponding to the faces of the cube. Such molecules, it is evident, cannot be formed by the juxtaposition of the elementary atoms. An atom of sulphur, the fundamental form of which is a rhombic octahedron, united to an atom of lead, whose primary is the regular octahedron, could not in any way be made to receive the cubic form of galena. Nor were the molecules equal spheres, would it be a less difficult task; and if the form were possible, still the compound molecule would not contain similar atoms in its similar parts, and could not possess that symmetrical character necessary to account for the regularity in the ocurrence of secondary planes. Such examples might be multiplied indefinitely.

The chemical theory is equally unsatisfactory, in all attempts to account for crystallographic phenomena. Indeed, it may be considered as formed merely for illustrating combinations in a lecture room. In the explanations of optical phenomena, it has been rejected by the principal theorists, who, in accounting for the double refraction of crystals, suppose the molecules to have spherical and

ellipsoidal forms, and a homogeneous structure.

Without further introduction, I proceed to explain what is conceived to be the most probable view of the nature of molecules and molecular action in the formation of crystals.

ON CRYSTALLINE MOLECULES.*

By crystalline molecule is understood, the molecule in the state peculiar to it, when about to enter into the constitution of a crystal, or when a constituent part of a crystal. Evidently, some important change takes place in molecules, at the time of crystallization. The moment before, when in the liquid state, they are in close connection, but move freely among themselves; in the act of crystallization, they unite, almost instantaneously, and are firmly compacted in the hard, unyielding crystal.

Forms of Molecules.—Adopting the idea of spherical and spheroidal molecules, we suppose the molecule of each primary to

The following views on crystallogeny were first published by the author in the American Journal of Science, 1836, xxx, 275, in an article on the formation of Compound or Twin Crystals.

be that spheroidal body or ellipsoid,* which, described within the prism, touches the centres of its faces. These molecules, by their aggregation, will build up the same forms that proceed from the aggregation of Hauy's polyhedral molecules; for they have the same proportional height, breadth, and thickness, and therefore, by combination, must produce a solid of the same dimensions.+ Such molecules are potentially correct representatives of the forces of attraction indicated by the forms and structure of crystals, whether actualities or not.

Crystallogenic Attraction.—Crystallogenic attraction, and the attraction exerted in solidification, appear to be one and the same: and consequently the subject before us is that of solidification in

Attraction acting in every direction from the centre of a particle, will cause an addition of particles in no fixed direction, and

* The following remarks are made in explanation of the solids, termed ellipsoids ar solid eclipses, and their conjugate axes and diameters.

AA' BB' is a plane ellipse. AB, A'B', two lines crossing a right angles, are termed its conjugate axes; a'b', ab, are signate diameters. The relative situation of the conjugate axes is such, that if a line be drawn, touching the

present as such, that if a line be drawn, touching the spee at a, the extremity of one diameter, ab, it will be pralled to the other a'b'. When ab and a'b' are equal, by are termed the equal conjugate diameters; when they missed at right angles, they are conjugate axes.

The revolution of a plane semi-cllipse, AB'B, around one air, describes the surface of a solid, which is denominated a clipsoid of revolution. The cllipsoid of revolution has a sections in one direction, circles. If these sections are dispose, the solid is still an ellipsoid, but not one of revolutions as the simple revolution of a plane cllipse will not as the simple revolution of a plane ellipse will not

lescribe it.

The axes of ellipsoids are three, and intersect at right angles. The three conjugate imeters are any lines so drawn that a plane touching the ellipsoid at the ex-Isch face of a prism, which touches the ellipsoid at the extremity of one crystallomic axis, is necessarily parallel to the plane in which the other two axes are

posite faces) are always the conjugate diameters of the ellipsoid, and, if they interest at right angles, they are the conjugate axes.


The above approaches the view of Brewster, deduced from the study of the fraction of crystallized and other substances, and published in 1830; but this inscribed within a primary, but another substances, and published in 1830; but this billosopher considers the form of the molecule not that of the spheroid which may inscribed within a primary, but another spheroid of such dimensions that the case of form superinduced upon it by the forces of aggregation determines the tast form of the combination. The form of the ultimate molecules of crystals making separately, are regarded as determining only within certain limits the primare form to which they belong; while the precise form of the crystal and its bably refracting structure are produced by the action of the forces of aggregation. The theory is suggested by the fact that compression will give a doubly refracting return to glass and other substances not otherwise possessing it. The progress ience will probably soon clear up these doubtful points. See Brewster on bable Refraction, Transactions Royal Society for 1830, and American Journal of thee, xxi, 296; also an article by the author, American Journal of Science, [2], must invariably produce a spherical solid. Proof of this fact is observed in every drop of water, or globule of mercury, whose sphericity results from this condition of attraction. To form solids, bounded by a definite number of surfaces, there must be a definite number of directions for the exertion of attraction. If attraction is exerted in but one direction, the particles will unite only in this direction, and by their union will form only a single line of spheres; exertion in two directions will, in a similar manner, produce a figure of two dimensions only, that is, a plane; in three directions, a figure of three dimensions, or a solid bounded by six faces, as the cube. For the construction of prisms, it is therefore necessary that the mutual attraction of the particles be strongest in three directions in each molecule.

These directions may be denominated axes, and their extremities, poles; the two, relatively, positive and negative, or north and south. This polar character is a fundamental law of molecular force. In each instance, the axes connect the centres of the faces or opposite edges of the prism; action in these directions

will produce solids like the prisms.

The attraction within a molecule is not supposed to be confined to the extremities of the axes. On the contrary, every portion of the surface exerts attraction. But the attraction is strongest at the poles, and weakest at an intermediate point between them.

The crystallogenic axes of the cube are three equal lines intersecting each other at right angles, and hence the molecule is a sphere, with three equal conjugate axes, as axes of attraction, (f. 215). Influenced by these axes, the spheres will combine, as in f. 216, and a cube will be formed in the same manner as by the aggregation of an equal number of cubes. The square prism has its breadth and width equal, but a varying length; and the mole-



cule, consequently, is an ellipsoid of revolution, (f. 217), with rectangular axes. The rectangular prism has three unequal dimensions, and therefore the ellipsoidal molecule is not an ellipsoid of revolution. Fig. 218 is a transverse section of the prism and ellipsoid. The axes are rectangular, as in the preceding forms. The right rhombic prism has a similar molecule to that of the rectangular prism, but its lateral crystallogenic axes, which connect the centres of opposite faces, are obliquely inclined to one another; and being equal, are the equal conjugate diameters, instead of con-

jugate axes, (f. 219). The vertical axis, as in the preceding prisms, is still one of the conjugate axes. The same is the fact with the right rhomboidal prism; but its lateral axes are unequal, and may be any unequal conjugate diameters of the ellipsoid, at right angles with the

vertical axis. In the preceding, we suppose that both the rhombic and rectangular prisms may be crystallogenically primary prisms. In the oblique prisms, the vertical axis is inclined, and is not

therefore one of the conjugate axes, but a conjugate diameter to each of the lateral axes, which are also conjugate diameters. The lateral conjugate diameters are equal in the rhombic, but unequal in the rhomboidal prism. In the rhombohedron, the lines connect-







ing the centres of opposite faces are equal, and consequently the ellipsoid is one of revolution, and the three crystallogenic axes, its equal conjugate diameters, (f. 221 and 222).*

A comprehensive view of the molecules and their axes is given in the following table:

Prisms, all of whose cryst. axes intersect at axes equal—Cube.

right angles, and are therefore conjugate two only equal—Rt. Square Prism.

the three unequal—Rt. Rectang. Prism.

Prisms whose lat. axes are oblique- (lat. axes equal conj. diam.—Rt. Rhombic Prism, ly incl. and are therefore conj. (lat. axes unequal conj. diam.—Rt. Rhomboidiam. (not axes) of the molecule (dal Prism.

Prisms, all of whose axes intersect at oblique angles, and are therefore conj. diam. (not the three axes, equal conj. diam. — Rhombohedron. two lat. axes, eq. conj. diam. — Ob. Rhombic Prism. the three axes, uneq. conj. diam. — Ob. Rbdl. Prism.

From this table it is apparent, that all possible positions of these dismeters occur in the forms of crystals, from an equality and rectingularity in the cube, through different variations in length and ituation, to a general inequality in length, and a like inequality in their mutual inclinations, as in the oblique rhomboidal prism.

Moreover, we perceive that all the prismatic primaries may pro-

The rhombohedron thus formed differs materially from that proposed by Wollasa, (£ 135). The molecule influenced by these axes will take an arrangement ular to that in the cube and other prisms.

three poles of one molecule on three opposite of the other, and consequently the composition is parallel to a plane on an angle.


An example of the second kind of twins is given in f. 357, under Pyroxene, which represents a crystal compounded parallel to the edge *ii*. Figures of crystals of Feldspar represent other forms resulting by this method: the *similar* poles of the vertical axes lie in opposite directions.

The third kind of twins is exemplified in figures of Calcite, and

in other species.

Compound crystals composed of more than two individuals, arise from the occurrence of the above species of composition parallel to two or more faces, edges, or angles, simultaneously. Examples of which are represented in figures beyond.

Fig. 231 represents a horizontal section of a crystal of Cerusite, four of whose lateral angles equal 117° 14′, the obtuse angle of the primary rhombic prism, and two equal 125° 32′, twice the acute



angle of the same. In this instance, composition of the first kind


has taken place parallel to two faces of the molecule A.

Fig. 232 is a horizontal section of f. 233, (another crystal of the same mineral). Composition has here taken place between A and B, and subsequently, though almost consentaneously, C was added by the attractions between the poles represented in contact. In the preceding prism, (f. 231), the union of B and C with A, was effected at the same instant, but here the addition of C was subsequent to the union of A and B, and from this has arisen the equal inclination of C to the other molecules.

In compound crystals thus formed, each face of the prism is a primary plane. The same form may result from the union of A and B merely, without the addition of C, provided the prism A and B have one of their acute lateral edges—the distant ones—truncated; for the two upper edges in f. 232 are parallel to the shorter diagonals of A and B, and therefore are also parallel to the truncating plane just referred to. The second figure under the

species Aragonite is an instance of this mode of formation; two of the lateral planes of the prism are the planes ii, and four are primary planes, I, and the crystal is composed of two individuals, the planes with the letters accented below, belonging to one, and those without the accent, belonging to the other.


A horizontal section of f. 234, a crystal of Witherite, is exhibited in the outer lines of f. 235. This prism differs from the preceding in the disposition of its primary angles, which are lettered a, b, c, d. The angles m and n, each equal twice the acute angle.



To form the nucleus, A, B, and C, D, were first united, and then the compound nuclei AB, CD, were joined by the action of the axes, which are here represented as nearly in contact. Fig. 236 is also based on this mode of structure.

In f. 237, a compound nucleus is represented, in which composi-

tion has been effected parrallel to all the lateral faces of the molecule A. The truncation of the lateral edges of the four crystals, B, C, D, E, would give rise only to a cruciform crystal. But the action of the central molecule A, in conjunction, will cause an addition of particles parallel to A, and thus produce the other two rays. This is a horizontal section of a stellate crystal of cerusite, (see under that species,) and possibly, also of the similar stellate forms of snow.



Stellate or hexagonal twins, like those of f. 234 to 237 appear to be impossible in oblique crystals. There are monoclinic species which are near 120° in the vertical prism—Orthoclase is an example; but although in trimetric species of the same angle such

compound forms are very common, they are not known in Orthoclase and species of similar form. From the nature of the aggregation it is evident that the attraction above and below the middle plane must be perfectly symmetrical, or else such symmetrical aggregations of molecules about a centre could not take place. It is true that three oblique prisms of 120° might be placed with their backs together so as to make a triple crystal with a symmetrical pyramid at one extremity, and a corresponding concavity below. But in the molecules of such prisms, the lateral axes will have the front poles n (or s), and the back poles the reverse; so that in such an aggregation, all the molecules in the nucleus would be united by poles of the same name, which is an impossibility. If the prisms were joined by the acute angle, the summit would be a cluster of projections. We have sufficient reason, therefore, for concluding that in monoclinic forms such twins are not possible. Moreover, trimetric forms, when hemihedral, as in Datholite, do not become stellately compounded, since they are potentially monoclinic.

The second mode of composition, mentioned on page 128, does not come under the explanations thus far presented. This kind of twin cannot occur except under certain conditions. If two molecules are united by an axis, n to s, an inversion like that referred to would bring n against n, or s against s, and would be impossible. But if two molecules were united by a middle point between an n and an s, then an inversion might take place, and the right half of the compound form might have the plane of section in or out, and constitute a twin in one case of the first mode, and in the other of the second mode. Thus it appears to be, in Feldspar and Albite.

An important conclusion hence follows. The lateral crystallogenic axes in these species are not at right angles with one another, like the crystallographic; they intersect at an angle corresponding with the angle of the fundamental prism, or to lines connecting the centres of opposite lateral faces. The crystallographic axes are a mathematical convenience simply, and are not necessarily the crystallogenic; the latter may intersect at oblique angles as well as right angles, as has been assumed in the preceding pages. The same conclusion follows from the relations of the trimetric species near 90° in angle to monometric forms. For very many of them approach the regular octahedron, not in the rhombic octahedron that is formed on the edges of the rhombic prism, but in the rectangular octahedron formed on the angles of this prism, and consisting of planes 17 and 17. The axial lines connecting the lateral solid angles of such an octahedron are homologous with those of the regular octahedron; but they cross at an oblique angle, corresponding to the angle of the rhombic prism.

Metagenic Compound Crystals.—Metagenic crystals have been

described as either-

1. Doubly geniculated crystals, that is, those which have been apparently bent subsequently to their formation; or—


2. Those which are composed of two distinct crystals, united by

their similar parts.

Compound crystals of the former kind result from a reversion of the original polarity in the molecules of the crystal, after the crystal has attained some size. The causes of this reversion are, probably, agents that are not unknown to us. Heat will have this effect on crystals of tourmaline and other minerals, their polarity varying with the temperature. Electricity is equally an efficient

agent in producing similar results.

Let AB (f. 238) represent a line of molecules in a crystal in the act of formation, with its poles situated as there seen, the marked poles being north. The particle C is supposed to be on the point of obeying its axes of attraction, by uniting the pole n with m. At this moment there is a sudden reversion of the polarity of the crystal, as represented in A'B'. The molecule C now finds a repellant pole opposing it—since m and n are both north—and is immediately drawn around by the attraction between o, the nearest south, and m, and the union exhibited in A'B'C takes place, pro-



ducing a geniculation in the crystal. The process, going on simultaneously at the other extremity of the crystal, causes another geniculation of the same. Fig. 239 is a section of a crystal, in which there is seen both a paragenic and metagenic composition. The latter was effected as above described. Geniculation, parallel to a plane on an edge, (or plane 1i), may be illustrated by means of f. 240; AB is again the crystal, C the next particle to be added. The molecules are those of a right square prism, which form is peculiarly subject to these accidents. In the figure, these molecules lie on one of their sides, and only one lateral axis is seen; the other directing its north pole, s, towards the observer. The union of m and n is again prevented by a reversion of the polarity; m therefore attracts the nearest north pole, which is s. A revolution of 90° must hence take place. But during this time, the unlike poles t and u, (the vertical of the prism), are acting on one another, and tending towards a union; consequently, the molecule will as

sume the intermediate position seen in A"B"C, in which, contact has taken place at the point of equilibrium between two poles. Fig. 206 represents a crystal of Rutile geniculated, either by this or the next method.

A similar composition could not occur in the right rectangular prism; for s could not be united to m, since they belong to unlike axes, and consequently, there must be a revolution of 180° , to bring r into union with m. We hence see why the right square prism is particularly subject to this kind of geniculation.

An explanation of metagenic geniculation, parallel to an octahedral plane 1, flows readily from the above. Fig. 316, under Cassiterite, may be an example of this kind of geniculation.

The remaining kind of compound crystal is represented in f. 346, of the species Quartz. It is perfectly analogous to the ordinary union of two molecules; for the crystals are united by their similar faces. They were, probably, brought originally into this parallel situation, by a process analogous to electrical induction, or the mutual action of their attracting influences.

FORMATION OF SECONDARY PLANES, AND ORIGIN OF CLEAVAGE.*

It has been abundantly explained that the same substance may crystallize under a variety of forms, all being modifications of one type. A species may occur under the form of a cube, or a cube with truncated edges, or with bevelled edges, or with variously modified angles. If, then, a certain state of the attraction in a molecule will produce the primary cube, some variation from this state is necessary to produce another form, and a different variation for every different secondary form.

In view of the fixed simple ratios of mathematical exactness, governing secondary planes, it is obvious that the variations which the attraction undergoes, are in some fixed ratio. And as similar parts of crystals are similarly modified, and similar parts are those similarly situated as regards like axes, the homologous parts of molecules experience the variation similarly and simultaneously.

The only exceptions to this last principle are the cases of hemihedrism, in which half the similar parts are modified alike; and hence it follows that in some cases the parts of a molecule on two opposite sides of a pole may undergo a different amount of variation of attraction; but this takes place symmetrically, with reference to all the poles.


In the formation of a cube with truncated edges, the cube is not finished out on the edges. There is, therefore, when secondary planes are formed, a diminution of the force of attraction in the

[#] See an article by the author in the American Journal of Science, [2], iv. 364

line of the primary axes, since these axes fail of completing the primary solid; and this diminution, as above shown, is in some

simple ratio.


In an enlarging cube, the molecules are added in planes of increasing breadth, as in this way only would the form continue to be a cube. If we consider the case, we find that the central molecule attracts a molecule by each of its poles, and also simultaneously the added molecules act by their lateral axes to complete the plane. We observe in the sectional view (through the centre) in f. 241, when A by its axes unites with four B's, the B's, simultaneously, while in the act of union, unite with



B', B', B', B'; and thus the square form is retained. This is a sim-


ple statement of the process.

If now when the B's are uniting, their lateral axes do not act at the same time, then the forming cube will have the edges truncated as in f. 17. To understand this we must study the steps in the process. Fig. 242 presents the same secondary planes as in f. 17, without the primary faces. It is obvious that in the enlargement of such a secondary, when the summit molecule is annexed, its lateral axes do not act as they do when the cube is formed: but when another molecule is added beyond, then they act laterally. This may perhaps be more clearly seen in the transverse section in f. 243. When A attracts B, B does not act laterally as in f. 241; it does not so act until B attracts C, when a C is added either side of B. So C acts laterally when a D is added to C, and not before.




Again, in f. 244 we have a section of another figure, (the same secondary as in f. 32), showing the arrangement of molecules in a solid, presenting such a section. Examining it, we perceive that when G is added to the extremity of the central axis, two molecules, G, G, are added on either side of F, and none laterally to G.

This figure represents the formation of the secondary plane, having the ratio 1:2, as is evident from inspection, and f. 242 or 243, another with the ratio 1:1.



If the period of time occupied by the union of a molecule be represented by p, then when the lateral axes act only after the period of time p, and then add a single row of molecules, the secondary plane is the truncating plane 1:1. For the plane having the ratio 1:2, in which two are added laterally to one terminally, or what is equivalent, one laterally for every half one terminally, the time would be $\frac{1}{2}p$; for the plane 1:3, the time would be $\frac{1}{4}p$.



To understand the origin of planes on an angle, we must again consider the actual circumstances. Fig. 245 (the same secondary as in f. 15) will aid the mind in conceiving of it. Here, when the summit particle unites itself, it adds nothing laterally, as was the case also in f. 243; when another unites beyond, then four particles

are united, one by each lateral pole; but these four add nothing, until still another particle is added to the summit. In this case there is an interval of time p, between the action of the terminal and lateral axes, and another interval p, between the adding of the four molecules and the action by their lateral axes. And this is the difference between the plane truncating an angle, (f. 15), and another truncating an edge of a cube, (f. 17). This plane truncating an angle has the ratio 1:1:1. For a plane 1:2:2, the times will be each $\frac{1}{2}p$, and for any plane 1:m:n, the times will be $\frac{1}{m}p$ and $\frac{1}{n}p$.

It appears that the lateral axes act less speedily therefore for the truncating plane of an angle, than for that of an edge: the centre of the former in a cube is 54° 44′ from the centre of the face of the cube, and the centre of the latter from the same is 45°.

We have before observed, that the production of secondary forms depends on the fact, that the force of attraction in the axes of the molecules, when secondaries are produced, is less than that which is exerted when the primary prism or cube is formed. But we cannot suppose the whole force of attraction in a molecule to be different in different circumstances. No facts nor reasoning would sustain this conclusion. We may admit that the attraction may be more concentrated in the primary axes, in some cases than

in others. It is well known that the polar condition in bodies does not imply an addition of force, but simply an axial action or concentration of the force. This concentration or excited action may be induced by the condition of neighboring bodies or influences; and different bodies should differ widely in their susceptibility to it, as is evidently the fact. Now if the attraction is less concentrated in the primary axes, when a secondary plane forms, the interval of time above alluded to as characterizing the formation of different secondaries, will be longer or shorter according to the state of concentration in the primary axes. The more or less diffused state of the attraction is connected with the kind

of secondary produced.

But when we observe in a complex crystal the evenness of the faces, the neat regularity of the edges, and the perfection throughout, even when many secondary planes are combined, it appears clear that such forms could not result from simply a generally diffused state of the attraction, any more than a primary could be so produced. In each case there must be as many distinct poles as there are planes. When therefore the principal axes lose their concentration, this loss consists in a distribution of the force into subordinate axes intermediate between the primary axes. For a truncation of the edges of a cube, the intermediate axes would have their poles just at the middle point between every two poles of the primary axes; for a truncation of the angles, the poles would be at the middle point between every three poles. We have remarked on the symmetrical arrangement of secondary planes in general, and this would follow from the necessary symmetrical arrangement of such axes. Moreover, the length of time p, will be greater the farther the secondary pole is situated from the primary poles. And this is true in fact. The pole for the octahedron is the most distant, being at the central point between three primary poles. The number of combined secondary forms may still seem mysterious. But a crystal, in its capacity as a unit, would necessarily have a corresponding character in its different parts to that of the molecules of which it consists, and consequently the attraction exerted by the molecules in these different parts would correspond, occasioning thus the secondary planes. The relative extent of the several different kinds of planes will depend primarily on the relative force of action in the different sets of axes.

These considerations lead us to conclude, that the diminution of attracting force in the primary axes, on which the formation of a secondary depends, consists in the partial action of this force along intermediate axes, symmetrically situated with reference to the primary axes; and the greater or less amount of diminution,

determines the kind of distribution."

^{*} In the case of substances that very seldom crystallize or never, we have evidence that the polar forces are weak.

The relation of the planes in Humite (see page 59, and this species beyond) have an important bearing on this subject. The planes, or the numbers expressing their axial proportions, are parts of infinite series, which are different in the three crystals. Such mathematical series point out definitely a mutual dependence in the planes of each form; they suggest that the modifications of the attraction upon which they depend, are connected with the different conditions of the attraction that may be represented by

curves to which such infinite series lead.

The same crystalline form may have different cleavage. For example, cubes of Galena have a cubical cleavage, while cubes of fluor spar have an octahedral cleavage, or yield octahedrons when cleaved. These different circumstances would result, provided that in one case (for Galena) the three primary axes of the molecule were dominant, and in the other, the eight intermediate or octahedral axes. The arrangement of the molecules in each case would depend on the dominant axes, and so also would the direction of the cleavage. Hence, the direction of cleavays may sometimes indicate in any species of matter which set of axes is dominant, the primary or a secondary set.

In the preceding paragraphs, after explaining the general polar action of crystallogenic or cohesive attraction, we have pointed out the modifications of condition this attraction undergoes, the simple ratios presented by these modifications, and their dependence on the formation of intermediate axes. Cohesive attraction, instead of being a constant force, as might be inferred from the ordinary definitions, appears therefore to be complex in its actions, yet simple in the general laws by which this complexity is produced.

Owing to some intrinsic or extrinsic influence, (the presence and condition of matter near by or commingled with the crystallizing material), the primary axes may be sustained in an excited state. But if there is nothing to sustain or excite this concentration, and the action is quiet, or if bodies around induce it, owing to their own condition, the attraction becomes more diffused, and secondary axes multiply. All the crystals of a locality or region have usually the same form.

The constancy of certain forms in some species is evidence of the peculiar susceptibilities of the molecules of these substances. Thus the calc spar in the limestone of Lockport has the dog-tooth shape, the scalene dodecahedron; that of Boonville, N. Y., occurs in short six-sided prisms. That of the Rossie lead region in complex combinations of different secondary planes with the primary.

These facts indicate, that the variations of attraction, producing secondary forms, depend often on surrounding bodies favoring the concentration or diffusion of the attracting force; and the causes often act in nature simultaneously over wide areas.

Cleavage.—The peculiarities of cleavage give us information on

another point, respecting cohesive or crystallogenic attraction. The facility of cleavage in prisms differs in the direction of unlike axes. Topaz cleaves easily parallel to the base of the prism, and hardly at all in other directions. This difference does not depend upon the relative strength of attraction in the unequal axes; for it is often the reverse of this. Again, while some of the hardest substances have perfect cleavage, other soft species have none.

If then this quality has no relation to the strength of the attraction which unites molecule to molecule, it must depend on some peculiarity in the manner in which this force acts. This force may act in two ways ;—either continuously or intermittedly ; and the latter mode only, could produce the result in view. The action of force in nature appears to be generally intermittent. Alternate action and comparative inaction, with corresponding results, are everywhere exemplified in organic growth; and it is therefore no anomaly that it should be exemplified in the inorganic kingdom.*

When, therefore, cleavage is produced in crystallization, the union of layers of molecules takes place by an intermitted action; that is, with regular successive variations or pulses in the intensity of the force of attraction. This intermitted action, when reduced to the adding simply of single layers in succession, becomes continuous. On these principles there might be every variety of this quality in nature, and there should be no necessary connection between cleavage and strength of attraction. We therefore inferthat the action of cohesive attraction is often intermittent, producing seriate results, (as exemplified in the cleavage of crystals), and the specific rate of intermittent action is different for unequal

The attraction of cohesion is shown by cleavage to be intermittent in intensity;

we do not learn from it that there is any actual intermission of time in the exertion

of the force, or a variation in rate of pulsation.

^{*} The successive layers in wood, the periodical reproduction of leaves or flowers, and of young in animals, and the seriate arrangement of parts in many plants and mimals, all illustrate intermittent growth. In some zoophytes the buds form in mocessive series of two, four, or six, or some other fixed number; in other cases opposite sides alternate in budding, or when there are several rows, the rows bud and these are avanuers of intermittent serior. a succession; and these are examples of intermittent action.

The spiral arrangement of leaves in vegetation, is another illustration of intermittent growth; for here the different sides of the growing plant bud successively, for the simple reason, of universal application, that reproduction produces temperary exhaustion, or, that force is exerted intermittedly.

The pulsation of molecular force is also an example of intermitted action, and must lie at the basis of the universal principle on this subject to which we have alluded. The reality of this pulsation we cannot doubt. The undulatory theory of light must be received as fully demonstrated; and if it is an ether that pulsates, it is molecular force which makes it pulsate, and this implies pulsating action in molecular force itself.

[†] Many crystals, as remarked on page 110, have parallel striations, which consist of alternations of two or more sets of planes. Thus cubes of pyrites very generally have their faces marked with strike which are oscillations between a plane replacing the edge, and either a face of the primary cube, or another plane of the same

In aggregated crystallizations, there is a mass of material entering the solid state together, and no opportunity exists for single crystals to perfect themselves. While a liquid mass is cooling, whenever the temperature of solidification is reached, at numberless points throughout the mass, crystallization will begin: and together, an aggregation of crowded crystals or grains is produced, with no external regularity of form; in other words, the granular structure. The same will happen in a crystallizing solution, if the process goes on rapidly.

When a solution is spread thinly over a large surface, minute crystalline points incrust the whole; and if the solution be gradually supplied as crystallization goes on, it is obvious that the minute points may elongate into crowded prisms or fibres, producing a fibrous structure. Such a structure is common in narrow seams in rocks, and the fibres are usually elongated across the seam.

The concentric structure is another result depending on the rate of solidification connected often with the rate of chemical combination. In the first place, the nucleus is always a cluster of molecules, instead of a single one, as in a simple crystal. The structure sometimes commences around some foreign body as a centre, though the aggregation is often without any proper nucleus except that of the cluster of molecules that first solidified. The second principle, on which the concentric structure depends, is the tendency of a body to communicate its own condition to other bodies within its influence. This law—the law of equilibrium, and contact or catalysis in chemistry-is one of the universal laws of existence. According to it, either a collection of molecules entering the solid state, or any foreign body already solid, will tend to bring adjacent bodies into the same or an intermediate condition. If susceptible to this influence, the particles adjoining become assimilated, and unite to the nucleus; these again act upon others adjoining, and thus a spherical form is produced, as a result of successive development.*

The influence of foreign substances associated with a crystallizing mineral is known to cause, not only secondary planes, but also considerable variations in the angles of crystals, even when they are chemically inert. This has been attributed to an intervention simply of the foreign particles among the others. But M. Nickles

secondary. Some octahedrons of fluor spar have faces which consist of minute cubes. These facts, and they are common and well known, show a frequent intermittent mode of action in the different axes of molecules, (or a seeming strife between different sets); and such examples are well called an "oscillatory combination" of planes. Crystals of snow often well illustrate intermittent action.

planes. Crystals of snow often well illustrate intermittent action.

The concentric structure here explained is analogous in many respects to the circular and spherical forms in vegetation. The growing lichen extends itself circularly, owing to progressive assimilation or development. This proves no similarity of nature between the organic forces and cohesive attraction; it only shows that different forces act under a common law.

regards it as due to a change in the axial molecular attractions of the crystallizing material, and by way of illustration he alludes to the influence upon a planetary system from the sudden appearance in it of a new body: the attractions of the foreign particles modify more or less the molecules of the associated material. This chemist states that bimalate of ammonia was thus changed a degree or more in angle in his experiments.* It has long been known that a change in refraction or polarization is produced by this cause: but Senarmont has quite recently rendered certain salts (as nitrate of strontian) pleochroic by the same process—that is, by the introduction of foreign substances through crystallization, which were afterwards removed by recrystallizations in pure water. †

We have thus reviewed some of the various facts presented by matter, as it exists around us. Observation has proved more profitable than closet speculation in animal and vegetable Physiology; and thus it will be with regard to the organizing force of the so-called inorganic kingdom. The fact that the attraction of molecules is liable to modifications of condition, and especially the simple yet fixed relations between these modifications, nothing but a crystal could make known to us. Yet the principle is as wide as the universe in its application; for we live in a universe of molecules, and all the grandeur of physical nature is the result of molecular

From the late rapid progress in science, we may be encouraged to hope that ere long this entrance to one of the innermost recesses of the works of nature will be thrown open, and that the qualities of atoms or molecules, their forms and peculiarities, will soon be fully understood. Its connection with the science of chemistry, and other physical sciences, renders it deserving of very minute experimental research. Beautifully and truly was it long since observed by Gulielmini, in his work on Crystallization—an author who, though afterwards forgotton, had a clearer insight into the nature of crystallization, than any of his contemporaries, and many of his successors—p. 144: "Crystallizatio geometrizantis naturee opus quoddam est, et sane mirabilissimum; dignum ideo ut totis ingenii viribus totâque mentis contentione exquiratur, non quod spectet tantam amœnitatem et voluptatem, quæ mirabilium zcientiam consequitur, verum etiam ob maximam in re physica utilitatem; videtur quippe Natura hic se prodere, et omni exutâ velamine non qualis esse potest, sed qualis actu est sese præbere conspiciendam."

^{*} Compt. Rend. de l' Acad. Sci., 1848, xxvii, 270. Compt. Rend. de Laurent, etc., 1850; Ann. de Ch. et de Phys. 1853. Compt. Rend. de l' Acad. Sci. 1854.

PART II.

PHYSICAL PROPERTIES OF MINERALS.

I. CHARACTERS DEPENDING ON LIGHT.

LIGHT may be either reflected, transmitted, or emitted. The qualities of minerals thus produced are of six kinds:-

1. Lustre; depending on the power and manner of reflecting

light.

- 2. Color; depending on the kind of light reflected or trans-
 - 3. DIAPHANEITY; depending on the power of transmitting light. 4. Refraction; depending on the manner of transmitting light.

5. Polarization; depending on the manner of transmitting or reflecting light, and due to the polar nature of force.

6. Phosphorescence; depending on the power of emitting

I. LUSTRE.

The lustre of minerals varies with the nature of their surfaces. A variation in the quantity of light reflected, produces different degrees of intensity of lustre; a variation in the nature of the reflecting surface, produces different kinds of lustre.

a. The kinds of lustre recognized are six.

1. Metallic: the lustre of metals. Imperfect metallic lustre is

expressed by the term sub-metallic.

2. Vitreous: the lustre of broken glass. An imperfectly vitreous lustre is termed sub-vitreous. The vitreous and sub-vitreous lustres are the most common in the mineral kingdom. Quartz possesses the former in an eminent degree; calcareous spar, often the latter. This lustre, in each case, approaches the lustre of broken glass of the color of the mineral.

3. Resinous: lustre of the yellow resins. Ex. Opal, and some

yellow varieties of Blende.

4. Pearly: like pearl. Ex. Talc, Brucite, Stilbite, &c. When united with sub-metallic, as in Hypersthene, the term metallicpearly is used.

5. Silky: like silk; it is the result of a fibrous structure. Ex.

fibrous Calcite, fibrous Gypsum.

163 COLOR.

6. Adamantine: the lustre of the diamond. When also submetallic, it is termed metallic-adamantine. Ex. Cerusite, Pyrargy-

b. The degrees of intensity are denominated as follows:—

1. Splendent: reflecting with brilliancy, and giving well defined images. Ex. Specular Iron, Cassiterite.

2. Shining: producing an image by reflection, but not one well defined. Ex. Celestine.

3. Glistening: affording a general reflection from the surface, but no image. Ex. Talc, Copper Pyrites.

4. Glimmering: affording imperfect reflection, and apparently

from points over the surface. Ex. Flint, Chalcedony.

A mineral is said to be dull when there is a total absence of lus-

Ex. Chalk, the Ochres, Kaolin.

These different degrees and kinds of lustre are often exhibited differently by unlike faces of the same crystal, but always similarly by like faces. The lateral faces of a right square prism may thus differ from a terminal, and in the right rectangular prism the lateral faces also may differ from one another. The surface of a cleavage plane in foliated minerals, very commonly differs in lustre from the sides, and in some cases the latter are vitreous, while the former is pearly. As shown by Haidinger, only the vitreous, adamantime and metallic lustres belong to faces perfectly smooth and pure. In the first, the index of refraction of the mineral is 1.3—1.8; in the second, 1.9-2.5; in the third, about 2.5. The pearly lustre is a result of reflection from numberless lamellæ or lines within a translucent mineral, as long since observed by Breithaupt.

II. COLOR.

The external color of minerals often differs from the color of the powder, or that of a scratched surface. The latter, called the Streak, is the most constant character, since it seldom varies in the same species. The mineral species are liable to so many accidental mixtures of foreign substances, that, in general, little reliance can be placed on the external color. The metals and the metallic oxyds are among those species which are least subject to variation.

The following eight colors have been selected as fundamental, to facilitate the employment of this character in the description of minerals: White, Gray, Black, Blue, Green, Yellow, Red, and

Brown.

a. Metallic Colors.

1. Copper-red: native copper.—2. Bronze-yellow: magnetic pyrites. 3. Brass-yellow: copper pyrites. 4. Gold-yellow. 5. Silver-white: native silver, less distinct in arsenical pyrites.—6.

Tin-white: Mercury, Cobaltine. - 7. Lead-gray: Galena, Molybdenite .- 8. Steel-gray: nearly the color of fine grained steel on a recent fracture; native platinum, and palladium.

b. Non-metallic Colors.

A. White. 1. Snow-white: carrara marble.—2. Reddish-white: some varieties of calcite and quartz.—3. Yellowish-white: some varieties of calcite and quartz.—4. Grayish-white: some varieties of calcite and quartz .- 5. Greenish-white: Talc .- 6. Milk-white:

white, slightly bluish; some Chalcedony.

B. Gray. 1. Bluish-gray: gray, inclining to a dirty blue color. -2. Pearl-gray: gray, mixed with red and blue; Horn silver .-3. Smoke-gray: gray, with some brown; flint. 4. Greenish-gray: gray, with some green; Cat's eye, some varieties of Talc .- 5. Yellowish-gray: some varieties of compact limestone. -6. Ash-gray: the purest gray color; Zoisite.

C. Black. 1. Grayish-black: black, mixed with gray, (without any green, brown, or blue tints); basalt, Lydian stone.—2. Velvet-black: pure black; Obsidian, black Tourmaline.—3. Greenish-black: Pyroxene.—4. Brownish-black: bituminous coal.—5. Blu-

ish-black: Black Cobalt.

D. Blue. 1. Blackish-blue: dark varieties of blue Malachite. 2. Azure-blue: a clear shade of bright blue; pale varieties of blue Malachite, bright varieties of Lapis lazuli. -3. Violet-blue: blue, mixed with red; Amethyst, fluor spar .- 4. Lavender-blue: blue with some red and much gray.—5. Prussian-blue, or Berlin blue: pure blue; Sapphire, Kyanite.—6. Smalt-blue: some varieties of gypsum.-7. Indigo-blue: blue with black and green; blue Tourmaline.—8. Sky-blue: pale blue with a little green; it is called moun-

tain blue by painters.

E. Green. 1. Verdigris-green: green inclining to blue; some feldspar .- 2. Celandine-green: green with blue and gray; some varieties of Talc and Beryl. It is the color of the leaves of the celandine, (Chelidonium majus) .- 3. Mountain-green: green with much blue; Beryl .- 4. Leek-green; green with some brown; the color of leaves of garlic; distinctly seen in prase, a variety of quartz.—5. Emerald-green: pure deep green; Emerald.—6. Applegreen: light green with some yellow; Chrysoprase.-7. Grassgreen: bright green with more yellow; green Diallage.—8. Pistachio-green: yellowish green with some brown; Epidote. -9. Asparagus-green: pale green with much yellow; Asparagus stone.-10. Blackish-green: Serpentine.—11. Olive-green: dark green with much brown and yellow; Olivine .- 12. Oil-green: the color of olive oil; Beryl, Pitchstone.—13. Siskin-green: light green, much inclining to yellow; Uranite.

F. Yellow. 1. Sulphur-yellow: Sulphur.—2. Straw-yellow:

COLOR. 165

pale yellow; Topaz.—3. Wax-yellow: grayish yellow with some brown; Blende, Opal.—4. Honey-yellow: yellow with some red and brown; Calcite.—5. Lemon-yellow: Sulphur, Orpiment.—6. Ochre-yellow: yellow with brown; Yellow Ochre.—7. Wine-yellow: Topaz and Fluor.—8. Cream-yellow: some varieties of lith-

omarge. -9. Orange-yellow: Orpiment.

G. Red. 1. Aurora-red: red with much yellow; some Realgar.—2. Hyacinth-red: red with yellow and some brown; Hyacinth Garnet.—3. Brick-red: Polyhalite, some Jasper.—4. Searlet-red: bright red with a tinge of yellow; Cinnabar.—5. Blood-red: dark red with some yellow; Pyrope.—6. Flesh-red: Feldspar.—7. Carmine-red: pure red; Ruby Sapphire.—8. Rose-red: Rose Quartz.—9. Crimson-red: Ruby.—10. Peach-blossom-red: red with white and gray; Lepidolite.—11. Columbine-red: deep red with some blue; Garnet.—12. Cherry-red: dark red with some blue and brown; Spinel, some Jasper.—13. Brownish-red: Jasper, Limonite.

H. Brown. 1. Reddish-Brown: Garnet, Zircon.—2. Clove-brown: brown with red and some blue; Axinite.—3. Hair-brown: wood Opal.—4. Broccoli-brown: brown, with blue, red, and gray; Zircon.—5. Chestnut-brown: pure brown.—6. Yellowish-brown: Jasper.—7. Pinchbeck-brown: yellowish-brown, with a metallic or metallic-pearly lustre; several varieties of Talc, Bronzite.—8. Wood-brown: color of old wood nearly rotten; some specimens of Asbestus.—9. Liver-brown: brown, with some gray and green; Jasper.—10. Blackish-brown: Bituminous coal, brown coal.

c. Peculiarities in the Arrangement of Colors.

Play of Colors.—An appearance of several prismatic colors in rapid succession on turning the mineral. This property belongs in perfection to the diamond; it is also observed in precious opal, and is most brilliant by candle light.

Change of Colors.—Each particular color appears to pervade a larger space than in the play of colors, and the succession produced

by turning the mineral is less rapid; Ex. Labradorite.

Opalescence.—A milky or pearly reflection from the interior of a specimen. Observed in some Opal, and in Cat's eye.

Iridescence.—Presenting prismatic colors in the interior of a

crystal.

Tarnish.—A metallic surface is tarnished, when its color differs from that obtained by fracture; Ex. Erubescite. A surface possesses the steel tarnish, when it presents the superficial blue color of tempered steel; Ex. Columbite. The tarnish is irised, when it exhibits fixed prismatic colors; Ex. specular iron of Elba.

The tarnish and iris colors of minerals are owing to a thin sur-

face film, proceeding from different sources, either from a change in the surface of the mineral, or foreign incrustation. Hausmann states that hydrated oxyd of iron (usually formed from pyrites) is one of the most common sources of it, and produces the colors on anthracite and specular iron. Arsenic becomes irised through the action of hydrogen from the atmosphere: arsenical cobalt, nickel, and iron, by oxydation: galena probably, from the formation of sulphate of lead at the surface: magnetic iron and some ferruginous silicates from a change in the oxyd of iron to a hydrate: pyrites, and probably also copper pyrites and variegated pyrites, from the formation of a hydrate of iron: antimony glance and other antimony ores from the formation of antimony ochre; Gray Copper and other arsenical ores probably from the oxydation of the arsenic.

The irised colors may also proceed from a disengagement of carbonic acid or water, as in Spathic iron and Diallogite. Heat some-

times favors it, as in the case of steel.

Dichroism, Pleochroism.—Some crystals, viewed by transmitted light, present different colors in different directions. This property is termed pleochroism, (from the Greek πλεος, full, and χροα, color), or dichroism, (from δίς, two-fold, and χροα), when the colors are different in two directions only. This property is exhibited by crystals which have at least two kinds of axes; the colors are the same in the direction of like axes, and different in the direction of unlike axes. Iolite owes its name (dichroite) to this property. Mica is nearly opaque in one direction, while it is transparent and of a different color in another. Monometric crystals are sometimes pleochroic, the color differing in the direction of unlike diagonals.



An instrument called a dichroscope has been contrived by Haidinger for examining this peculiarity of crystals. An oblong rhombohedron of Iceland spar has cemented to each extremity a glass prism of 18°. It is placed in a metallic cylindrical case, as in the figure, having a convex lens at one end, and a square hole at the other. On looking through it, the square hole appears double; and when a pleochroic crystal is examined with it, by transmitted light, on revolving it, the two angles, at inter-

vals in the revolution, have different colors, the colors being those which the transmitted light affords. Andalusite, Tourmaline, Corundum, Topaz, Idocrase, Euclase, Mica, show well the property, and any colored crystals not monometric that are sufficiently transparent. Dichroism is thus detected by looking in but one direction, and the two colors are brought into direct contrast, and made thereby obvious when not otherwise perceived.

III. DIAPHANEITY.

The diaphaneity of a mineral is its capacity of transmitting light. The following terms are adopted to express the different degrees of this property.

Transparent: when the outline of an object seen through the

mineral is perfectly distinct. Gypsum, Quartz.

Subtransparent, or semi-transparent: when objects are seen, but outlines are not distinct.

Translucent: when light is transmitted, but objects are not seen.

Carrara marble.

Subtranslucent: when merely the edges transmit light, or are translucent.

When no light is transmitted, the mineral is said to be opaque. This property occurs in the mineral kingdom, in every degree from a perfect opacity to a perfect transparency, and most minerals present, in their numerous varieties, nearly all the different shades. Few minerals, except the metals, are perfectly opaque. It is always similar in the direction of like axes of a crystal, and often dissimilar in the direction of unlike axes.

IV. REFRACTION, POLARIZATION.

A full account of the refraction and polarization of light belongs more especially to a treatise on optics, where the student will find the subject discussed at length. The remarks in this place are

necessarily confined to a few simple explanations.

a. Simple Refraction.—If we look into a cup obliqely, at such an angle that an object at its bottom is just concealed from view by its sides, on filling the cup with water, this object will become visible. This is owing to a bending or refracting of the rays of light, by the water. This effect is termed refraction, and is produced by all transparent bodies, whether solid, liquid, or gaseous.

The part of the ray AED, within the water, is nearer the perpendicular BC, than if it had proceeded in its original direction AE; or, if we consider the ray as passing from the water into the air, the part AE, is farther from the same perpendicular than if it had proceeded in the original direction DE. We have therefore this important

B

principle: Light, in passing from a rarer to a denser medium, is refracted TOWARDS the perpendicular; if from a denser to a rarer, it is refracted FROM the perpendicular.

It has been proved by experiment, that at whatever angle we

look at the surface of the water, there will be a constant ratio between AB and CD, provided the eye and the object are at the same distance, A and D, from E. That is, if AB is twice the length of CD, viewing it at one angle, it will be twice at every other angle, until the eye is perpendicular over the object D, when there is no refraction. But AB is the *sine* of the angle AEB, which is the *angle of incidence*, and CD is the sine of the angle CED, which is the *angle of refraction*. This principle may therefore be thus stated:

The sine of the angle of incidence bears a constant ratio to the

sine of the angle of refraction.

This ratio is termed the index of refraction. In water, the ratio is as 1.335 to 1. 1.335 is therefore the index of refraction of water.

The following are the indices of refraction for the substances enumerated:

Tabasheer,		1.211	Witherite,	1.700
Ice,		1.308	Boracite,	1-701
Water,		1.835	Chrysoberyl,	1.760
Cryolite,	2 .	1.349	Feldspar (Adularia),	1.764
Fluor Spar,		1.486	Corundum-white,	1768
Alum,		1.457	" red,	1.779
Borax,		1.475	" blue,	1:794
Gypsum,		1.525	Garnet,	1.815
Chalcedony,		1.553	Zircon,	1.961
Rock Salt,		1.557	Cerusite,	2.084
Quartz,		1.548	Sulphur,	2.115
Euclase,		1.642	Blende,	2.260
Calcite		1.654	Diamond,	2.439-2.755
Aragonite,		1.698	Crocoisite,	2.500-2.974

There is some variation often in the same species, and it fre-

quently corresponds to a change of color.

Double Refraction.—Many crystalline substances give two images instead of one, owing to double refraction. If a line be viewed through a transparent crystal of calc spar, it will appear double in every direction but one—that of the vertical axis of the rhombohedron. One image is seen by the ordinary refraction of light; the other, by an extraordinary refraction. If the same crystal is placed over a point, and turned around, one image will appear to revolve around the other. The direction in which there is no refraction is called the axis of double refraction, or neutral line, since in its direction the ordinary and extraordinary rays coincide. Double refraction increases in passing from this direction to one at right angles with it.

In some instances the extraordinary ray is situated between the ordinary ray and a perpendicular to the surface of the crystal; and in others it is exterior to this ray. The former possess a greater index of refraction for the extraordinary than for the ordinary ray, and the axis is called a *positive* axis of double refraction. In the latter, the reverse is the case, and the axis is a *negative* axis. Calcite has a negative axis, quartz, a positive. The following are

the indices for a few substances:

	Ordinary ray.	Extraordinary ray.
Calcite (neg.)	1.654	1.483
Aragonite (neg.)	1.693	1.535
Quartz (pos.)	1.548	1.558
Euclase (pos.)	1.643	1.663
Topaz (pos.)	1.632	1.640

Zircon, tin ore, rutile, apophyllite, göthite, brucite, tungsten, and ice are examples of a *positive* axis; and idocrase, scapolite, meionite, tourmaline, corundum, emerald, apatite, nepheline, dioptase, alum, pyromorphite, arsenate and molybdate of lead, cinnabar,

anatase, of a negative axis.

When there are two axes of double refraction, both rays, as shown by Fresnel, are due to extraordinary refraction. The two axes are in a vertical plane in right prisms, but not necessarily so in oblique prisms. The apparent angle between these axes has been determined for many minerals, and has served to distinguish species. The following are some examples:


Cerusite,	5° 15'	Celestine,	500
Strontianite,	6° 56'	Comptonite,	560 64
Mica-different kinds, 1	o to 20° 50',	Topaz (Scotland),	- 56°
	60° to 78°	Gypsum,	600
Tale,	70 24'	Iolite,	62° 50'
Aragonite,	18° 19′	Adularia,	680
Chrysoberyl,	270 51'	Topaz (Aberdeenshire).	650
Anhydrite,	280.71	Axinite,	730
Epsomite,	37° 24'	Kyanite,	81° 48'
Barvtes,	870 42'	Epidote,	840 19'
Stilbite,	410 42'	Andalusite,	870 33'
Zinc Vitriol,	490 42'	Chrysolite,	879 56'
Topaz (Brazilian),	49-50°	Copperas,	900

Monometric solids which have the three axes equal to one another have no double refraction. But all other forms exhibit this property; and if the horizontal diameters are equal, as in the dimetric and hexagonal systems, there is but one axis; if unequal,

two axes, as in the trimetric and oblique systems.

Polarization.—The polarization of light is intimately connected with double refraction, this polarity being exhibited by the extraordinary ray, which is said to be a polarized ray. When such a ray is viewed by means of another doubly refracting crystal or crystalline plate, (called from this use of it, an analyzing plate), the ray of light becomes alternately visible and invisible, as the latter plate is revolved. If the polarized light be made to pass through a doubly refracting crystal, then on viewing it in the manner stated, rings of prismatic colors are developed, and on revolving the analyzing plate, the colored rings and intervening dark rings gradually change places. If crystalline plates having one axis of double refraction be viewed in the direction of the axis, the rings are circles, and they are crossed by a dark or light cross.

Fig. 249 shows the position of the colored rings and cross in calc spar, and f. 250 the same at intervals of 90° in the revolution of the plate. With a crystal having two axes of double refraction,



there are two series of elliptical rings, as in f. 251 and 252, the latter alternating with the former in the revolution of the plate.

Light is polarized also by other means. If a ray of light be reflected from a plate of glass at a certain angle it is polarized; and so each reflecting substance has its own angle for polarizing light. In glass the angle between the ray and a perpendicular to the glass, is 56° 45′, or between the ray and the glass, 35° 15′, but varying somewhat for the kind of glass. In fluor spar the latter angle is 34° 51′, in quartz 33° 2′, calc spar 31° 9′, diamond 21° 59′. Again, if light be made to pass through a series of thin transparent plates of glass or mineral substance it is polarized, the angle of polarization differing as the number of plates is varied.

The angle of polarization or double refraction, varies widely in the same species, it varying with small differences of composition or the presence of impurities, and also the condition of crystals. Senarmont even refers all the micas to a single form, notwith-standing the wide difference in the angles. In common mica (species *muscovite*) the angle is acknowledged to vary between 45° and 78°. Phlogopite ranges in the angle between 3° and 20°.

Plates of transparent tourmaline, cut parallel to the vertical axis, are conveniently used both for the polarizer and analyzer; and it is necessary only to put the mineral between two such tourmaline plates and look through, revolving one of them, to see the rings and their changes. In mica they are well shown; but it is often necessary to look very obliquely to distinguish both of the poles in the biaxial micas, and the plate of mica must not be too thin. As the light from certain parts of the sky in a clear day is polarized, a single tourmaline is often sufficient to show the rings to the observer looking towards the sky.

The angle between the two poles is easily measured, when the crystals are not too minute, or the angle not too large. A convenient method, of sufficient accuracy for the mineralogist, is to

take a graduated horizontal circle, having an arm moving over it, attached at the centre. The mica being put between the polarizer and analyzer, place it vertically (by means of some contrivance for the purpose) upon the movable arm, precisely at the centre of the circle. Look through until the middle of the system of rings is seen in the direction of a cord stretched vertically across a window; then move the arm until the centre of the other system of rings is seen in the same direction; the angle over which the arm has passed, will be read off on the graduated circle.

By a very simple arrangement, easily inferred from the above, a common Wollaston's goniometer may be employed. A contrivance for this purpose has been planned by Mr. W. P. Blake, and an instrument of the kind has been recently constructed which gives very accurate results, by Soleil of Paris. It is adapted with a small telescope for observing very small plates. Other instruments have been devised expressly for this purpose, but it is not neces-

sary to speak of them in this place.

Polarization has the same relation to crystalline form as double refraction. Some monometric crystals give the rings of colors due to polarization; but the rings have a symmetrical arrangement like the faces of the crystals, and have been shown by Biot to be due not to the molecular character of the crystal, but to its cleavage or lamellar structure, the lamellæ polarizing as a series of thin plates, in the manner just mentioned. A peculiar polarizing structure in apophyllite, not according with the general law for dimetric crystals, is explained by him in this manner. Compression will give a doubly-refracting crystal to many monometric crystals.

Besides ordinary or plane polarization, there is also what is called circular polarization. Quartz crystals have been described sometimes right-handed and sometimes left-handed in their modifications. The circles of colors, when plates of crystals cut transverse to the axis are examined, have a spiral character, and on revolving the analyzer, the spiral is found to turn to the right

in right-handed crystals, and to the left in left-handed.

V. PHOSPHORESCENCE.

Phosphorescence, or the emission of light by minerals, may be produced in different ways: by friction, by heat, or by exposure

to light

By friction. Light is readily evolved from quartz or white sngar, by the friction of one piece against another, and merely the rapid motion of a feather will elicit it from some specimens of sulphuret of zinc. Friction, however, evolves light from a few only of the mineral species.

By heat. Fluor spar is highly phosphorescent at the temperature

of 300° F. Different varieties give off light of different colors; the *chlorophane* variety, an emerald green light; others purple, blue, and reddish tints. This phosphorescence may be observed in a dark place, by subjecting the pulverized mineral to a heat below redness. Some varieties of white limestone or marble emit a yellow light.

By the application of heat, minerals lose their phosphorescent properties. But on passing electricity through the calcined mineral, a more or less vivid light is produced at the time of the discharge, and subsequently the specimen when heated will often emit light as before. The light is usually of the same color as previous to calcination, but occasionally is quite different.

The light induced by electricity is in general less intense than that of the unaltered mineral, but is much increased by a repetition of the electric discharges, and in some varieties of fluor it may be nearly or quite restored to its former brilliancy. It has also been found that some varieties of fluor, and some specimens of diamond, calc spar, and apatite, which are not naturally phosphorescent, may be rendered so by means of electricity. A dozen discharges through a non-phosphorescing statuary marble in powder, caused it to emit a yellow light when subsequently heated. Electricity will also increase the natural intensity of the phosphorescent light.

Acquired phosphorescence is not, however, equally permanent with the natural. On 21 days of exposure to the light, according to Mr. Pearsall, many specimens lost partially, and some entirely, this property; in others, the color of the light was changed; and generally to purple and orange tints. If laid away in a dark room, they retained this property for a much longer period of time.

Mr. Pearsall states that some colored fluors that had been rendered white by calcination, received a bluish or reddish tint, by means of repeated electrical discharges.*

Light of the sun. The only substance in which an exposure to the light of the sun produces very apparent phosphorescence, is the diamond, and some specimens seem to be destitute of this power. This property is most striking after exposure to the blue rays of the spectrum, while in the red rays it rapidly loses its

phosphorescence.

^{*} Jour. Roy. Institution, i, 77, 267.

II. ELECTRICITY—MAGNETISM.

The electric and magnetic characters of crystals bear but slightly upon the Science of Mineralogy, although of high interest

to the student of physics.

Frictional Electricity.—The development of electricity by friction, is a familiar fact. There is no line of distinction among minerals, dividing them into positively electric and negatively electric; for both kinds of electricity may be presented by different varieties of the same species, and by the same variety in different states. The gems are positively electric only when polished; the diamond alone among them exhibits positive electricity, whether polished or not. The time of retaining electric excitement is widely different in different species, and topaz is remarkable for continuing excited many hours.

Pyro-electricity.—On heating crystals of some minerals, they become electric with opposite polarity in opposite parts. This property is called pyro-electricity. Tourmaline, calamine, and boracite, are among the species thus affected. They are peculiar in having the opposite parts dissimilarly modified, and in these opposite parts are the opposite poles. The polarity continues as long as the temperature is increasing, and becomes reversed when it commences to decline; and when the heat is stationary it disappears. This subject has been investigated by the Abbé Haüy, Canton, Becquerel, Brewster, Erman, Köhler, Hankel, Riess, and


Rose

Rose and Riess* name one of the poles the analogue electric pole, and the other the antilogue electric pole. The former becomes positive while the crystal is heating and negative while cooling; and the latter the reverse, being negative while heating and positive while cooling. Becquerel says of the tourmaline: † "At 30° C., electrical polarity was sensible; it continued unchanged to 150°, as long as the temperature continued to rise; if stationary an instant, the polarity disappeared, but shortly manifested itself reversed, when the temperature commenced to decline. If but one end of the crystal was heated, the crystal was unpolarized, and when two sides were unequally heated, each acquired an electrical state independent of the other" In tourmaline, the extremities of the prism are dissimilarly modified, and that end which presents

^{*} Uber die Pyro-electricität der Mineralien, von P. Riess und G. Rose, Akad. Wissench. zu Berlin. 1843.—Also, Ueber den Zusammenhang zwischen der Form und der electrischen Polarität der Krystalle, von G. Rose; Ibid. for 1836.

† Ann. de Chem., xxxvii, 1, 1828.—Brewster's Edinb. Jour. x, 50, 1829.

the greatest number of planes is the antilogue pole; or if the number of planes is the same, the secondary rhombohedrons of the antilogue pole have (one or more of them) longer vertical axes than those of the analogue pole. In f. 456, under tourmaline, the upper extremity is the antilogue pole, (positive under increasing heat), and the other is the analogue pole. The pyramid of the analogue end is more flattened by its facets than that of the antilogue end.



The figures here given represent the extremities of a crystal from Gouverneur, N. Y., as drawn by Rose. On the antilogue end we find the rhombohedral faces, 4r, 5r', while on the other the longest rhombohedron is 2r', thus conforming to the statement just made.

Pyro-electric polarity has been observed in the following substances; the names of those who first observed it, are annexed.

lances, the names	or mose who h	ist observed it, are a	milexeu.
Tourmaline,	Lemery.	Prehnite,	Haüy.
Topaz,	Canton.	Electric Calamine,	Hawy.
Axinite,	Brard.	Sphene,	Hauy.
Boracite,	Hairy.	Rhodizite,	Rose.
Scolecite,	Haüy.	Heavy Spar,	Brewster.
The state of the s	D 1 C +1	D	

Rock Crystal, Brewster.

Riess and Rose have confirmed the observations with regard to the above mineral species. Brewster has added Calcite, yellow Beryl, Celestine, Cerusite, red and blue Fluor spar, Diamond, Orpiment, Analcime, Amethyst, Idocrase, Mellite?, Sulphur, Garnet, and Iolite. But the more recent investigations of Riess and Rose have failed to detect this property in any but the species first enumerated.

Pyro-electricity is of two kinds: "—either terminally polar, or centrally polar. In the former, the extremities are opposite poles. In the latter, two sides of a prism are of the same name, and the opposite pole to each is intermediate between the two.

^{*} Riess and Rose.

The examples of the first kind are Tourmaline, Calamine, and Scolecite, uniavial; Axinite, biavial; Boracite and Rhodizite,

with four axes.

Calamine, like tourmaline, has the sharper extremity the antilogue end, and the more flattened the analogue. Compound crystals from Altenberg have both ends analogue, and the middle, between the twins, antilogue electric. As in tourmaline, the pyro-electric axis corresponds with the vertical axis of the prism.

Boracite, which crystallizes in cubes with the opposite solid angles differently modified, has four pyro-electric axes, corresponding to the four octahedral axes. In f. 53 of this species, the plane 1 is the antilogue pole, and the unmodified angle the analogue pole; and, generally, the antilogue pole is most largely modified by secondary planes, or has larger facets. Rhodizite resembles


boracite in its pyro-electricity.

The species in which pyro-electricity of the second kind has been observed, are prehnite and topaz. If f. 255 represent a tabular crystal of prehnite, the poles will be situated as marked, the analogue being central, and the antilogue at either extremity of the shorter diagonal of the rhombic prism. Topaz has in a similar manner a central analogue pole and an antilogue at either extremity of the shorter diagonal. In some instances there is a separate set of

similar poles near one or the other angle, as in the following figure; this has arisen probably from the com-

pound nature of the crystal.

The particular character of the axes in Sphene, Barytes, and rock crystal has not been made out. Two specimens of Barytes were heated to 180° R, and positive electricity was observed, but not negative, and it was hence inferred that the



255 Ant.

Anal.

pyro-electricity was centrally polar, as in topaz. Quartz was found to be pyro-electric in a single small crystal six lines long and two thick, after failing in six others, five of which were an inch in length and one half an inch thick. Great caution is required in the trial with this mineral, as the crystals are so readily rendered electric by friction.

Magnetism.—Substances have been divided into magnetic and diamagnetic. The magnetic take a longitudinal position between the poles of a strong magnet, the diamagnetic a transverse position. In the former division are iron, nickel, cobalt, manganese, cerium, osmium; among the latter, bismuth, antimony, tin, mercury,

gold, arsenic, zinc, lead.

Magnetism is most strongly exhibited by iron and its compounds.

and specimens of magnetic iron often have polarity. Ilmenite and specular iron ore are also at times magnetipolar. The ordinary mode of testing whether a mineral is magnetic or not, is to bring it near a pole of a delicately suspended magnetic needle, and observe whether it causes it to vibrate; and another mode is to apply a strong magnet to the mineral in powder. These are sufficient for the mineralogist, without all the delicacy required for the purposes of physical science. Delesse has experimented extensively upon the magnetic force of minerals, and has determined the relative amount for numerous species. Calling this force for Styrian steel 100·000, the following are some of his results:—

Native platinum,	2.173-3.047
Magnetic iron ore,	15.00-65.00
Franklinite from the United States,	1.033
Chromic iron,	0.136-0.065
Spinel, (pleonaste), from Monzoni, Tyrol,	0.078
Titanic iron, (rhombohedral), often magnetipolar,	5-764
Specular iron—sometimes magnetipolar,	0.14 - 2.35
Graphite,	0.015-0.040
Spathic iron—(spherosiderite, the highest),	0.092-0.287
Iron pyrites,	0.039-0.057
Vivianite,	0.027-0.075
Columbite of Bodenmais and Haddam,	0.151
Pyrochlore,	0.010
QuartzIt is diamagnetic, but many varieties are	
magnetic. For chrysoprase was found	0.004
Feldspar-not magnetic, or feebly so.	1000
Labradorite of an antique green pophyry,	0.077
	0.012-0.057
Hornblende,	0.012-0.001

Crystallo-magnetic action.—The magnetic polarity thus far alluded to, belongs to the mass, and has no relation to crystalline form. There is also a kind of polarity directly related to the crystalline or optical axes of minerals, as has been recently developed by Faraday and Plücker. Plücker observes that a crystal of kyanite, suspended horizontally, points very well to the north, by the magnetic power of the earth only, and is a true compass needle, from which even the declination may be obtained; and the line of direction is the line of the optical axes. Other crystals, which are called negative, take a transverse or equatorial position. The latter are diamagnetic crystals, according to Knoblauch. A bare allusion to the subject is all that is proper in this place.

III. HEAT.

There are two sets of phenomena observed with crystals under the action of heat, in addition to phosphorescence and pyroelectric qualities.

(a.) Crystals expand unequally in the direction of unequal axes, and alike in the direction of like axes. The monometric solids change equally in all directions; but those of other systems have HEAT. 177

directions of least and greatest dilatation; and these correspond with axial lines in the crystals. Any dimetric or hexagonal crystal dilates alike in corresponding parts about the vertical axis; for the lateral axes of the crystal are equal. But the trimetric and clinometric forms have three unequal axes, and dilate unequally along these axes. Crystals are not only enlarged; their interfacial angles are also varied. This change in the angles takes place in all crystalline forms, excepting those of the monometric system. Mitscherlich found that in calc spar there was a diminution of 8' 37" in the angle of the rhombohedron, on passing from 32° to 212° F., the form thus approaching that of a cube, as the temperature increased. Dolomite, in the same range of temperature, diminishes 4' 46"; and in aragonite, between 63° and 212° F., the angle of the prism diminishes 2' 46", and 1i: 1i increases 5' 30"; Nitratine is increased about 27'; in gypsum I: ii is increased 5' 24", I: 1, 4' 12", and 1i: ii is diminished 7' 24". In some rhombohedrons, as of calc spar, the vertical axis is lengthened, (and the lateral shortened), while in others, like quartz, the reverse is true. The variation is such either way that the double refraction is diminished with the increase of heat; for calc spar possesses negative double refraction, and quartz, positive. According to Fresnel, the same is true of gypsum. The dilatation for calc spar, according to experiment, is 0.001961. In nitre, an increase of temperature of 180° changes the angle 1i:1i,44', but scarcely at all the angle I:I.

Dr. Kopp has shown that in the carbonates of lime, magnesia, iron, manganese, and zinc, which are nearly the same in their crystals, the vertical axis (axis a) is shorter the greater the atomic volume. And since heat diminishes the density, and therefore necessarily increases the volume, the axis a should be lengthened by an increase of temperature, as is actually the case. He has determined by calculation, that the change of angle for 180° F. (from 32° to 212°) should be 7′ 37″, which is but 57″ less than Mitscherlich's observations—a near coincidence, when we consider the difficulties of measuring exactly the dilatation and change of

angles.

(b.) Crystals conduct heat according to a similar law to that of their expansion. This subject has lately been investigated by Senarmont. This author states that, from a point in a tesseral or monometric crystal, heat is conducted equally in all directions, so that the isothermal surfaces are spherical surfaces, concentric about the point. In crystals of the dimetric and hexagonal systems, (whose molecules are ellipsoids of revolution), the isothermal surfaces are the surfaces of concentric ellipsoids of revolution. In the other systems, (in which the molecules are ellipsoids not of revolution), the isothermal surfaces are surfaces of concentric ellipsoids not of revolution.

The correspondence with the phenomena of light is striking.

Yet there are some points of difference. Quartz and calc spar differ, in the former being optically attractive, and the latter optically repulsive. Yet both have a prolate thermic ellipsoid. Oblate thermic ellipsoids have, however, been found in idocrase, specular iron, and corundum; and the most prolate occur in attractive crystals. The heat rays appear thence to correspond to light rays which lie beyond the extreme red. In calc spar, the proportion of the axes of the ellipsoid is 1·12; in quartz, 1·312; in beryl, 1·11; in idocrase, 1·13; in rutile, 1·27. In aragonite, the proportion of the horizontal axes is 1·22; in bournonite, for a perpendicular ellipse, parallel with the longer diagonal, 1·31, and parallel with the shorter diagonal, 1·29. In feldspar, augite, and gypsum, for the three principal elliptical sections,—1, vertical to the axis of symmetry, (a thermal axis), and 2 and 3, parallel to the axis of symmetry and one of the other two thermal axes:

	Feldspar,	Augite.	Gypsum,
1	1.23	1.24	
2	1.02	1.28	2.24
3	1.27	1.10	1.50

Senarmont's experiments were made by cutting thin slices of crystals in different directions, covering them with a thin coat of wax, and heating them at a point, by placing them on the fine point of a heated silver wire, (or some other means). The melting of the wax took place in circular or elliptical areas, according to the material, with great precision and uniformity for the same plate.

A correspondence to the phenomena of light and heat in the unequal elasticity of crystals along unequal axes, was first observed

by Savart.*

M. Wiedemann,† moreover, has investigated the figures produced on different faces of crystals, by electricity acting on a light powder, or some kinds of oil; and he finds the same general correspondence between circular and elliptical areas and the axes, as was distinguished for heat by Senarmont.

Recherches sur l'élasticité du cristal de roche, etc., Ann. Ch. Phys. [1], xl, 118.
 Poggendorff's Annalen, lxxvi, 1849.

IV. SPECIFIC GRAVITY.

The specific gravity of a mineral is its weight compared with that of another substance of equal volume, whose gravity is taken at unity. If a cubic inch of any mineral weighs twice as much as a cubic inch of water, (water being the unit), its specific gravity is 2, if three times as much, its specific gravity is 3, &c. In the case of solids or liquids, this comparison is usually made with water; but for gases, atmospheric air is assumed as the unit.

It results from the nature of a fluid, that the weight lost by a solid immersed in water, is equal to the weight of an equal volume of water. The determination of specific gravity is, therefore, a very simple process. We ascertain the weight out of water, by weighing it in the usual manner; we then determine the weight in water; and the loss by immersion, or the difference of the two weights, is the weight of an equal volume of water: that is, if a mineral weighs 120 grains out of water, but 90 on emersion, it has lost 30 grains, which is the weight of a volume of water equal to that of the mineral. The mineral, consequently, weighs in this instance 4 times as much as the water; for 4×30 grains equals 120 grains, which is the weight of the mineral. The rule for the process is, therefore,—Divide the weight out of water by the difference of weights obtained out and in water.

The water employed for this purpose should be distilled, to free

The water employed for this purpose should be distilled, to free it from all foreign substances. Since the density of water varies with its temperature, a particular temperature has been selected for these experiments, in order to obtain uniform results: 60° F. is the most convenient, and has been generally adopted. But the temperature of the maximum density of water, 39.5° F., has been

recommended as preferable.

If a pair of scales is used for obtaining the weight, they should be exceedingly delicate, when perfect accuracy is required. For original investigations they should turn with the 1000th of a grain. The weights must be selected with care, and should vary from the wentieth of a grain to 120 grains. To weigh the mineral immersed in water, it may be attached to the scales by a single fibre of raw silk or a fine hair, and thus let down into a jar of water, care being taken that the scales be kept perfectly dry. The attachment of the fibre of silk to the scales may be made by means of a small hook attached to the lower part of one scale. For the ordinary investigations of the mineralogist, in the determination of pecies, it will be found most convenient, if the scales are not provided with this hook, to make a small hole through the centre of one scale, and through it attach a horse hair permanently to the scale. By tying a slipping knot in the horse hair, the minerals under investigation may be attached and detached without difficalty, owing to the elasticity of the hair.

To insure accuracy, those specimens should be selected which are perfectly free from foreign substances, and contain no vacuities, even under a magnifying glass. If vacuities exist, they may usually be removed by coarsely pulverizing the mineral. An impalpable powder is apt to swim on the surface, although heavier than water.

A better and more simple process than the above, and one available for porous as well as compact minerals, is performed with a light glass bottle, capable of holding exactly a thousand grains (or any known weight) of distilled water. Pour out a few drops of water from the bottle after filling it and then weight it. Then add the powdered mineral till the water is again to the brim, and reweigh it. The difference in the two weights, divided by the loss of the water poured out, is the specific gravity sought. The weight of the glass bottle itself is here supposed to be balanced by an equivalent weight in the other scale.

Rose has recently observed that fine pulverization of a mineral, and even of a metal, gives uniformly a higher specific gravity than is obtained from the solid mass, and he considers the result therefore as involving a slight error.

The mineralogist is so seldom required to take the specific gravity of liquids or gases, that an explanation of the different methods employed is unnecessary.

V. CHARACTERS DEPENDING ON COHESION.

These characters are of three kinds:—1. Hardness; 2. Tenacity; 3. Fracture.

I. HARDNESS.

A harder body is distinguished from a softer, either by attempting to scratch the one with the other, or by trying each with a file. Each of these methods is used by the mineralogist in determining the hardness of the species, though the latter is in most cases to be preferred. Both methods should be employed when practicable. Certain varieties of some minerals give a low hardness under the file, owing either to impurities or imperfect aggregation of the particles, whilst they scratch a harder species,—showing that the particles are hard, although loosely aggregated. Chiastolite, spinel, and sapphire are common examples of this fact. When the mineral is too hard to be impressed by a file, the peculiarity of the grating sound will suffice to the practised ear.

To give a definite character to the results obtained with respect to the hardness of minerals, the distinguished German mineralogist Mous introduced a scale of hardness. Mohe's scale consists of ten minerals, which gradually increase in hardness from 1 to 10. The intervals between 2 and 3, and 5 and 6, are larger than the others. Breithaupt has therefore introduced another degree of hardness between each of the above, and thus his scale consists of twelve minerals.

Mohs's scale is as follows:

- 1. Tale; common laminated light green variety.
- 2. Gypsum; a crystallized variety. Calcite; transparent variety.
 Fluor Spar; crystalline variety. Apatite; transparent variety.
 Scapolite; crystalline variety.
- 6. Feldspar (orthoclase); white cleavable variety.
- 7. Quartz; transparent.
 8. Topaz; transparent.
 9. Sapphire; cleavable varieties.

10. Diamond.

If the file abrades the mineral under trial with the same ease as No. 4, and produces an equal depth of abrasion with the same force, its hardness is said to be 4. If with more facility than 4, but less than 5, the hardness may be $4\frac{1}{4}$ or $4\frac{1}{2}$, written in decimals 4.25, 4.5. Several successive trials should be made to obtain certain results.

The use of the file is acquired with very little experience; usually a single trial is sufficient. Care must be taken to apply the file to edges of equal obtuseness. That part, also, of the specimen should be selected which has not been altered by exposure, and has the highest degree of transparency and compactness of structure. The pressure for determination should be rather heavy, and the file should be passed three or four times over the specimen.

Rock salt is usually given in the scale of hardness for No. 2;

but crystals are nearer 3.

Many specimens present different degrees of hardness on dissimilar faces; as an example of which, we mention kyanite and mica. This is confined to the inequilateral primary forms, and like the similar difference of color, lustre, &c., finds a ready explanation in the theory of their formation; unlike faces are the result of

the action of unlike axes.

This difference in faces parallel to unlike axes may be perceived in nearly all cases, when the methods of trial are exceedingly delicate. Huygens long since observed that the cleavage face of a crystal of calc spar differed in hardness from the other faces; and even in a monometric crystal it has been found that the faces of the cube and octahedron are not exactly alike in this respect.*

^{*} This subject has been examined by Frankenheim, (De crystallorum cohesione, 1829, and Baumgartner's Zeitschrift für Physik, ix, 94 and 194), Seebeck (Hartmann's Jahrbücher der Min. u. Geol. i. 123) and Franz, (Pogg. Ann. lxxx, 1850, 37).

II. TENACITY.

Solid minerals may be either brittle, sectile, malleable, flexible, or elastic. Fluids are either gaseous or liquid.

1. Brittle; when parts of a mineral separate in powder or grains

on attempting to cut it; kerolite, calc spar.

2. Sectile; when pieces may be cut off with a knife without falling to powder, but still the mineral pulverizes under a hammer. This character is intermediate between brittle and malleable; gypsum.

3. Malleable; when slices may be cut off, and these slices flatten

out under a hammer; native gold, native silver.

4. Flexible; when the mineral will bend, and remain bent after the bending force is removed; talc.

5. Elastic; when after being bent, it will spring back to its orig-

inal position; mica.

A liquid is said to be viscous, when, on pouring it, the drops

lengthen and appear ropy; petroleum.

The unequal elasticity of unlike faces of crystals has been shown by Savart in his Acoustic investigations, and he thus distinguishes the rhombohedral from the other faces in the pyramid of quartz crystal.

III. FRACTURE.

The natural fracture of crystalline minerals has already been noticed under cleavage. The fracture of amorphous minerals varies in the form and kind of surface produced.

1. Conchoidal; when a mineral breaks with curved concavities, more or less deep. It is so called from the resemblance of the concavity to the valve of a shell, from concha, a shell; flint.

2. Even; when the surface of fracture is rough, with numerous

small elevations and depressions.

4. Hackly; when the elevations are sharp or jagged; broken

VI. TASTE.

Taste belongs only to soluble minerals. The different kinds of taste adopted for reference are as follows:

1. Astringent; the taste of vitriol. 2. Sweetish astringent; taste of alum.

3. Saline; taste of common salt.

Alkaline; taste of soda.
 Cooling; taste of saltpeter.
 Bitter; taste of epsom salts.
 Sour; taste of sulphuric acid.

VII. ODOR.

Excepting a few gaseous and soluble species, minerals in the dry unchanged state do not give off odor. By friction, moistening with the breath, and the elimination of some volatile ingredient by heat or acids, odors are sometimes obtained which are thus designated:

1. Alliaceous; the odor of garlic. Friction of arsenical iron elicits this odor; it may also be obtained from any of the arsenical

ores or salts, by means of heat.

2. Horse-radish odor; the odor of decaying horseradish. This odor is strongly perceived when the ores of selenium are heated.

3. Sulphureous; friction will elicit this odor from pyrites and

heat from many sulphurets.

Bituminous; the odor of bitumen.

 Fetid; the odor of sulphuretted hydrogen or rotten eggs. It is elicited by friction from some varieties of quartz and limestone.

6. Argillaceous; the odor of moistened clay. It is obtained from serpentine and some allied minerals, after moistening them with the breath; others, as pyrargillite, afford it when heated.

PART III.

CHEMICAL MINERALOGY.

I. COMPOSITION OF MINERALS.

1. General Remarks on the Constitution of Minerals.

The mineral species are either the uncombined elements in a native state, or compounds of the elements with one another. The number of elements, as at present recognized, is sixty, forty-seven

of which are metals.

The following table contains the names of the elements, with the abbreviations by which they are represented, and their atomic weights. In the catalogue here given, the more common compounds of the elements with oxygen and sulphur are also included, together with their atomic weights; and following these, the percentage proportion of oxygen and sulphur in each. The dots indicate atoms of oxygen; and the dashed letter, a double atom of the substance so expressed; thus Fe means 2 of Iron to 3 of Oxygen.

ALUMIN	TAKE STATE		141.00		10	10-	. n.	200.05	
Alexan	TUM, Al,		171.25	0 100)		(Cuprun		396.25	(0 11-90)
Ainn	nina, Al,		642.5 (1285.0	0, 46-7)	Oxyd	of Coppe	ar Ču		(0, 11.20) (0, 20.15)
	3 31		1927.5	100	DIDYMI		or, ou,	600	(0,2010)
	4 1		2570.0		ERBIUM,			10000	
	5 X 1		3212.5			(Fe) see	Iron.		
	6 X 1		3855-0		FLUORIN			237.5	
	NY (Stibit		1612.5	200		ofluorie A			(F.95)
	Antim., S		2212.5 (8	3, 27.12)		M(Beryll	ium),Be		
	TUM (Ag),	see Silve				na, Be,	D.	158.75	(O, 63)
ARSENIC	o, As,	4	937.5	70.40		Glucinum		88.125	(0 00)
Arsei	nie Acid,	AS,	1437.5 (0, 34.8)		Glucina,		476.25	(0, 63)
	huret of A		1991.9	(S, 39·0)	Hyppan (2	Aurum), A	In) son	1231.25 Quickeil	ner
BARYUN	(Au), see	Crosca	856.25			EN, (H),	18) 800	12.5	007.
	ta, Ba,		956-25 (0	0. 10.45)	Wate				(O, 88·89)
	2 Ba		1912.5	,	7	2 H		225.0	
	3 Ba		2868.75			3 H		837.5	
	4 Ba		3825.0		100	4 H		450.0	
	IUM (Be),	see Glu			1	5 H		562.5	
BISMUT		× 10.	2600		4000	6 H		675.0	
	of Bismi	ath, Bi,		0 10.35)		7 连		787.5	
Boron,		15	136-2	100,000		9 H	-	900.0	
	eie Acid,	Ъ,), 68-78)	Tonres			1012·5 1587·5	
BROMIN			1000		Indine,			1237.5	
CALCIUM			250			errum), F		350	
Lime	. Ča.), 28.57)	Proto	xvd of In	on. Fe.		(0, 22-22)
2211110	2 Ca		700.0	, 2001)	Perox	xyd of Ir	on. Fe.	1000	(0, 30)
	3 Ča		1050.0		KALIUM	(K), see	Potassi	um.	4-1-1
	4 Ca		1400.0			NUM, La,		587.5	
CARBON	, C,		75		Proto	oxyd of L	a., La,	687.5	(0, 14.55)
	onic Acid	l, C,	275		Peroz	cyd of La	., Ба,		(0, 20.34)
CERIUM	, Ce,		587.5		LEAD (1	fumbum) of Lend,	, Pb,	1294.6	10 mans
	oxyd of (), 14.55)	Oxyd	of Lend,	Pb,	1394.6	(0, 7.17)
	xyd of C,	ee,	1475 (0), 20.34)		ee Calciu	m.	01.00	
CHLORE		17 500			LITHIUM			81.66	(0, 55-05)
	eachler /	Loid HC							
Hydr		Acid, HC			Lithi				(0,0000)
Нуф Спвомі	UM, Cr,		333 75	0. 81-01)	MAGNES	HUM, Mg,		150	
Нуф Сивоми Ожуб	um, Cr,	me, Er,	888.75 967.5 (C		MAGNES	esin, Mg,			(0, 40-0)
Hydr Chromi Oxyd Chro Cobalt	of Chronic Acid	me, ër, , ër,	333 75		MAGNES	esia, Mg, 2 Mg		150 250	
Hydr Chromi Oxyd Chro Cobalt Oxyd	um, Cr, l of Chromic Acid , Co, l of Coba	me, ër, , Čr,	383.75 967.5 (6 633.75 (6 368.65 468.65 (6	0,47.84)	MAGNES	ium, Mg, lesin, Mg, 2 Mg 3 Mg 4 Mg		150 250 500	
Hydr Chro Chro Chro Cobalt Oxyd Columb	om, Cr, l of Chromic Acid , Co, l of Coba	me, ër, , Ör, lt, Čo, alum)Ta	883.75 967.5 (C 633.75 (C 368.65 468.65 (C ,2300.0	0,47.84)	Magnes Magn	sium, Mg, lesin, Mg 2 Mg 3 Mg 4 Mg 5 Mg	11	150 250 500 750 1000 1250	
Hydr Chro Chro Chro Cobalt Oxyd Columb	um, Cr, l of Chromic Acid , Co, l of Coba	me, ër, , Ör, lt, Čo, alum)Ta	883.75 967.5 (C 633.75 (C 368.65 468.65 (C ,2300.0	0,47.84)	Magnes Magn	ium, Mg, lesin, Mg, 2 Mg 3 Mg 4 Mg	11	150 250 500 750 1000	
Hydr Chro Chro Chro Cobalt Oxyd Columb	om, Cr, l of Chromic Acid , Co, l of Coba	me, ër, , Ör, lt, Čo, alum)Ta	883.75 967.5 (C 633.75 (C 368.65 468.65 (C ,2300.0	0,47.84) 0,21.84) 0,11.54)	Magnes Magn	arum, Mg, lesia, Mg 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg		150 250 500 750 1000 1250 1500	(0, 40-0)
Hydr Chromi Oxyd Chro Conalt Oxyd Column Column	tum, Cr, 1 of Chron mic Acid , Co, 1 of Coba num(Tant mbic Acid	me, ër, , Ör, ilt, Čo, alum)Ta i, Ta,	883.75 967.5 (6 633.75 (6 368.65 468.65 (6 ,2300.0 2600.0 (6	0,47·84) 0,21·84) 0,11·54) 4	Magnes Magn	aum, Mg, lesia, Mg, 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg	7	150 250 500 750 1000 1250 1500	(0, 40-0)
Hydr Chromi Oxyd Chro Conalt Oxyd Column Colum	um, Cr, l of Chromic Acid , Co, l of Coba uum(Tant mbic Acid	me, ër, , Ör, alt, Čo, alum)Ta l, Ta,	383.75 967.5 (6 633.75 (6 368.65 468.65 (6 ,2300.0 (6 2600.0 (6	0,47·34) 0,21·34) 0,11·54) 4 1·868	Magnes Magn	arum, Mg, esin, Mg, 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg 6	7 3-269	150 250 500 750 1000 1250 1500 8 3-736	9 4·203
Hydr Chromi Oxyd Chro Columb Columb Columb	tum, Cr, 1 of Chromic Acid , Co, 1 of Coba num(Tant mbic Acid 1 0.467	me, ër, , ër, alt, čo, alum)Ta 1, Ta, 2 0-934 0-696	383.75 967.5 (6 633.75 (6 368.65 468.65 (6,2300.0 2600.0 (6 3 1.401 1.044	0,47·34) 0,21·34) 0,11·54) 4 1·868 1·392	5 2-335 1-740	aum, Mg, esin, Mg, 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg 6 2.802 2.088	7 3·269 2·436	150 250 500 750 1000 1250 1500 8 3.736 2.784	9 4·203 3·132
Hydr Chromi Oxyd Chro Columb Columb Columb Al	orm, Cr, of Chroi mic Acid, , Co, of Coba orm (Tant mbic Acid 1 0-467 0-348 0-1045	me, ër, , ër, alt, čo, alum)Ta i, Ta, 2 0.696 0.2090	383.75 967.5 (6 633.75 (6 368.65 (6 ,2300.0 2600.0 (6 3 1.401 1.044 0.3135	0,47·34) 0,21·34) 0,11·54) 4 1·868 1·392 0·4180	5 2.335 1.740 0.5225	6 2:802 2:088 0:6270	7 3·269 2·436 0·7315	150 250 500 750 1000 1250 1500 8 3.736 2.784 0.8360	9 4·203 3·132 0 0·9405
Hydr Chromi Oxyd Chro Cobalt Oxyd Columb Columb Columb As Ba Be	orm, Cr, of Chroimie Acid , Co, of Coba orm (Tant mbie Acid 0.467 0.348 0.1045 0.63	me, ër, , ër, lt, čo, alum)Ta 1, Ta, 2 0.934 0.696 0.2090 1.26	383.75 967.5 (C 633.75 (C 633.75 (C 368.65 (C ,2300.0 2600.0 (C 3 1.401 1.044 0.3135 1.89	0,47·34) 0,21·34) 0,11·54) 4 1·868 1·392 0·4180 2·52	5 2.335 1.740 0.5225 3.15	6 2.802 2.088 0.6270 3.78	7 3-269 2-436 0-7315 4-41	150 250 500 750 1000 1250 1500 8 3.736 2.784 0.836(5.04	9 4·203 3·132 0·9405 5·67
Hydr Chromi Oxyd Chro Columb Columb Columb As Ba Be Ca	1 0-467 0-348 0-1045 0-63 0-2857	me, ër, , ër, , ër, alum)Ta 1, Ta, 2 0-934 0-696 0-2090 1-26 0-5714	383.75 967.5 (C 633.75 (C 633.75 (C 2300.0 2600.0 (C 3 1.401 1.044 0.3135 1.89 0.8571	0,47·34) 0,21·34) 0,11·54) 4 1·868 1·392 0·4180 2·52 1·1428	5 2·335 1·740 0·5225 3·15 1·4285	arum, Mg, essia, Mg, 2 Mg 3 Mg 3 Mg 5 Mg 6 Mg 6 Mg 6 2-802 2-088 0-6270 3-78 1-7142	7 3·269 2·436 0·7315 4·41 1·9999	150 250 500 750 1000 1250 1500 8 3-736 2-784 0-8360 5-04 2-2856	9 4·203 3·132 0·9405 5·67 1·2·5713
Hydr Chromi Oxyd Chro Columb Columb Columb As Ba Be Ca	1 0-467 0-348 0-1045 0-63 0-2857 0-7273	me, ër, , ër, lt, čo, alum)Ta 1, Ta, 2 0-934 0-696 0-2090 1-26 0-5714 1-4546	383.75 967.5 (6 683.75 (6 368.65 468.65 (6 2600.0 (6 3 1.401 1.044 0.8135 1.89 0.8571 2.1819	0,47:34) 0,21:34) 0,11:54) 4 1:868 1:392 0:4180 2:52 1:1428 2:9092	5 2·335 1·740 0·5225 3·15 1·4285 3·6365	esia, Mg, esia, Mg 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg 6 2 802 2 088 0 6270 3 78 1 7142 4 3638	7 3-269 2-436 0-7315 4-41 1-9999 5-0911	150 250 500 750 1000 1250 1500 8 3-736 2-784 0-8360 5-04 2-2856 5-8184	9 4·203 3·132 0·9405 5·67 12·5713 6·5457
Hydr Chromi Oxyd Chro Columb Columb Columb As Ba Be Ca O	1 0-467 0-348 0-1045 0-63 0-2857 0-7273 0-31	me, ër, , ër, , ër, , it, čo, alum)Ta l, Ta, 2 0-934 0-696 0-2090 1-26 0-5714 1-4546 0-62	383.75 967.5 (6 683.75 (6 368.65 468.65 (6 2600.0 (6 3 1.401 1.044 0.8135 1.89 0.8571 2.1819 0.93	0,47·34) 0,11·34) 4 1·868 1·392 0·4180 2·52 1·1428 2·9092 1·24	5 2·335 1·740 0·5225 3·15 1·4285 3·6365 1·55	esia, Mg, esia, Mg 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg 6 2 802 2 088 0 6270 3 78 1 7142 4 3638 1 86	7 3·269 2·436 0·7315 4·41 1·9999 5·0911 2·17	150 250 500 750 1000 1250 1500 8 3-736 2-784 0-8360 5-04 2-2856 5-8184 2-48	9 4·203 3·132 0·9405 5·67 6·26713 6·5457 2·79
Hydr Chromi Oxyd Chro Columb Columb Columb As Ba Be Ca O	1 0.467 0.348 0.1045 0.63 0.2857 0.31 0.4734	me, ër, , ër, lt, čo, alum)Ta l, Ta, 2 0-934 0-696 0-2090 1-26 0-5714 1-4546 0-62 0-9468	383.75 967.5 (6 683.75 (6 368.65 468.65 (6 2600.0 (6 3 1.401 1.044 0.8135 1.89 0.8571 2.1819 0.93 1.4202	0,47·34) 0,11·34) 4 1·868 1·392 0·4180 2·52 1·1428 2·9092 1·24 1·8936	5 2·335 1·740 0·5225 3·15 1·4285 3·6365 1·55 2·3670	6 2 802 2 088 0 6270 3 78 1 7142 4 3638 1 86 2 8404	7 3-269 2-436 0-7315 4-41 1-9999 5-0911 2-17 3-3138	150 250 500 750 1000 1250 1500 8 3.736 2.784 0.8360 5.04 2.2856 5.8184 2.48 3.7873	9 4·203 3·132 0·9405 5·67 6·25713 6·5457 2·79 2·4·2606
Hydr Chromi Oxyd Chro Columb Columb Columb Columb As Ba Ba Be Ca Ca Ca Ca Ca	1 0-467 0-348 0-1045 0-63 0-2857 0-7273 0-31 0-4734 0-2134	me, ër, , ër, lt, čo, alum)Ta l, Ta, 2 0-934 0-696 0-2090 1-26 0-5714 1-4546 0-62 0-9468 0-4268	383.75 967.5 (6 683.75 (6 368.65 468.65 (6 2600.0 (6 3 1.401 1.044 0.8135 1.89 0.8571 2.1819 0.93 1.4202 0.6402	0,47·34) 0,11·54) 4 1·868 1·392 0·4180 2·52 1·1428 2·9092 1·24 1·8936 0·8536	5 2·335 1·740 0·5225 3·15 1·4285 3·6365 1·55 2·3670 1·0670	esia, Mg, esia, Mg 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg 6 2 802 2 088 0 6270 3 78 1 7142 4 3638 1 86 2 8404 1 2804	7 3-269 2-436 0-7315 4-41 1-9999 5-0911 2-17 3-3138 1-4938	150 250 500 750 1000 1250 1500 8 3.736 2.784 0.8360 5.04 2.2856 5.8184 2.48 3.7873 1.7072	9 4·203 3·132 0·9405 5·67 6·2·5713 6·5457 2·79 2·4·2606 1·9206
Hydronia Columbia Col	1 0-467 0-348 0-1045 0-63 0-2857 0-7273 0-31 0-4734 0-112	me, ër, , ër, lt, čo, alum)Ta l, Ta, 2 0-934 0-696 0-2090 1-26 0-5714 1-4546 0-62 0-9468 0-4268 0-224	383.75 967.5 (6 683.75 (6 368.65 468.65 (6 2600.0 (6 3 1.401 1.044 0.8135 1.89 0.8571 2.1819 0.93 1.4202 0.6402 0.336	0,47·34) 0,11·54) 4 1·868 1·392 0·4180 2·52 1·1428 2·9092 1·24 1·8936 0·8536 0·448	5 2·335 1·740 0·5225 3·15 1·4285 3·6365 1·55 2·3670 1·0670 0·560	6 2 802 2 088 0 6270 3 78 1 7142 4 3638 1 86 2 8404 1 2804 0 672	7 3·269 2·436 0·7315 4·41 1·9999 5·0911 2·17 3·3138 1·4938 0·784	150 250 500 750 1000 1250 1500 8 3.736 2.784 0.8360 5.04 2.2856 5.8184 2.48 3.7872 1.7072 0.896	9 4·203 3·132 0·9405 5·67 6·26713 6·5457 2·79 2·4·2606 1·9206 1·908
Hydr Chromi Oxyd Chro Columb Columb Columb Columb As Ba Ba Be Ca Ca Ca Ca Ca	1 0-467 0-348 0-1045 0-63 0-2857 0-7273 0-31 0-4734 0-2134	me, ër, , ër, lt, čo, alum)Ta l, Ta, 2 0-934 0-696 0-2090 1-26 0-5714 1-4546 0-62 0-9468 0-4268	383.75 967.5 (6 683.75 (6 368.65 468.65 (6 2600.0 (6 3 1.401 1.044 0.8135 1.89 0.8571 2.1819 0.93 1.4202 0.6402	0,47·34) 0,11·54) 4 1·868 1·392 0·4180 2·52 1·1428 2·9092 1·24 1·8936 0·8536	5 2·335 1·740 0·5225 3·15 1·4285 3·6365 1·55 2·3670 1·0670	esia, Mg, esia, Mg 2 Mg 3 Mg 4 Mg 5 Mg 6 Mg 6 2 802 2 088 0 6270 3 78 1 7142 4 3638 1 86 2 8404 1 2804	7 3-269 2-436 0-7315 4-41 1-9999 5-0911 2-17 3-3138 1-4938	150 250 500 750 1000 1250 1500 8 3.736 2.784 0.8360 5.04 2.2856 5.8184 2.48 3.7873 1.7072	9 4·203 3·132 0·9405 5·67 6·25713 6·5457 2·79 2·4·2606 1·9206 1·908 0·1·8135

```
Mangamese, Mn,
                                                                           266-25
                                                Silicium, S
  Protoxyd of M., Mn,
2 Mn,
3 Mn,
4 Mn,
                            4447 (0, 22.45)
                                                  Silica,
                                                                           566.25 (O, 52.98)
                            8894
                                                                          1182.50
                           1884-1
                                                        8
                                                                          1698-75
                           17788
                                                                          2265-00
         5 Kn
                           2222·K
                                                                          2881-25
                           2668-2
                                                                          3897.50
     squoxyd of M., An.
                           989.4 (O, 80.82)
                                                                          8968-75
        9 2n
8 2n
                           1978-8
                                                                          4580-00
                          2968-2
                                                                          5096-25
         4 2n
                                                SILVER (Argentum), Ag, 1850
                           2957-A
                                                                          287.5
MERCURY (Hg), see Quickeilver.
                                                Sodium (Natrium), Na,
Molybonsum, Mo,
Molybolic Acid, Mo.
                                                  Soda, Na,
2 Na
8 Na
                            575
                                                                           887 5 (O, 25 80)
                            875
                                    (0, 84.8)
                                                                           7750
NATERUM (Na), see Sodium.
NECHEL, Ni, 869-38
Protoxyd of Nickel, Ni 469-88 (O, 21-8)
                                                                          1162.5
                                               STANNUM (Sn.), see Tin.
STIBIUM (Sb.), see Antimony
STRONTIUM, Sr., 54
Niosrum, (Columbium, Cb.)
                                                                           547·6
                                                                           647-5 (0, 15-44)
NITEOGER, N.
                            175 •
                                                  Strontia, Sr,
  Nitrie Acid, Ñ,
2 Ñ
3 Ñ
4 Ñ
                            675
                                     (0,74)
                                               SULPHUR, S,
                                                                           200
                           1850
                                                  Sulphuric scid, B,
                                                                           500
                                                                                     (0, 60)
                                               Tantalum, Ta,
Tantalic seid, Ta,
                                                                          2800
                           2025
                                                                                 (0, 11.54)
                           2700
                                                                          2600
                                                TELLURIUM, Te,
NOMIUM.
                                                                          801-8
                                               TERBIUM, Tb,
THORIUM, Th,
OSMIUM, OS,
                          1248.6
                                                                         748-86
OXYGEN, O,
                            100
Palladium, Pd
                            665.48
                                                  Thoria, Th,
                                                                         848-9
                                                                                 (0, 11.84)
                                               Tin, (Stannum), Sn,
Oxyd of Tin, Sn,
PROSPHORUS, P.
                            887.5
                                                                         725
  Phosphoric Acid, P,
                            887.5 (0, 56.84)
                                                                                 (O, 21·62)
                                                                          925
                                                Titanium, Ti, 812
Oxyd of Titanium, Ti, 925
         2 P
8 P
                           1775
                                                                          812.5
                                                                                  (O, 82·42)
                           2662.5
                                                Titanic Acid, Ti, 512.5
Tungsten (Wolfr'um), W 1150
                           8550
                                                                                 (O, 89-02)
         5
                           4487.5
PLATINUM, Pt
                           1237.5
                                                  Tungstie Acid, W,
                                                                           1450
                                                                                  (O, 20-69)
PLUMBUM (Pb), see Lead.
                                                URANIUM, U,
                                                                            750
Ротавагим (Kalium), K, 488 86

Ротавае K, 588 86

2 K 1177 72
                                                Protoxyd of U., U,
Peroxyd of U., U,
Vanadium, V,
                                                                            850
                                                                                  (0, 1176)
                            588-86 (O, 16-98)
                                                                           1800
                                                                                 (0, 16.66)
                           1177 72
                                                                           856.9
                                                WOLFRAMIUM (W), see Tungsten.
         8 Ķ
                           1766.58
         4 K
                           2855.44
                                                YTTRIUM, Y,
                                                                           402.5
 QUECESILVER (Hydrargy
                                                  Yttria, Ż,
                                                                           502.5 (O, 19.90)
                                                Zinc, Zn,
     rum), Hg,
                           1250
                                                                           406.6
                                                  Oxyd ofZine, Zn,
REODIUM,
                            651.96
                                                                           506-6 (O, 19-74)
RUTHERIUM, Ru.
                                                ZIRCONIUM, Zr,
                                                                           419-73
                            652
                                                  Zirconia, Zr.
                            49375
SELENTUM, Se.
                                                                           1189.5
                                                                                   (O, 26·3)
Ĥ
         0.8889
                  17778
                                                          5.8834
                                                                   6.2228
                                                                            7.1112
                              2.6867
                                       8.5556
                                                 4.4445
                              0.5094
Ŕ
         0.1698
                   0.3396
                                       0.6799
                                                 0.8490
                                                          1.0188
                                                                   1.1886
                                                                            1.8584
ti
         0.5505
                                       2.2020
                                                27525
                                                          8.8080
                                                                   8.8585
                                                                            4.4040
                                                                                      4.9545
                  1.1010
                              1.6515
Eg
                                                                    2.80
                                                                             8-20
         0.40
                   0.80
                              1.20
                                                 2.00
                                                          2.40
                                       1.60
Ĺ
         0-2247
                   0.4494
                              0.6741
                                       0.8988
                                                 1.1285
                                                          1.8482
                                                                   1.5729
                                                                            17976
                                                                                      2-0992
         0.3032
                   0.6064
                              0.9096
                                       1.2128
                                                 1.2160
                                                          1.8192
                                                                   2.1224
                                                                             2-4256
                                                                                      2-7988
         0.74
                   1.48
                              2.22
                                       2-96
                                                 870
                                                          4.44
                                                                    5.18
                                                                             5-92
                                                                                       6.66
         0-258
                   0.516
                              0-774
                                       1.032
                                                 1.290
                                                          1.548
                                                                    1.806
                                                                             2064
                                                                                       2.822
İ
                                                 2-8170
                                                          8.8804
                                                                   8-9488
•
         0.5684
                   1.1268
                              1.6902
                                       2-2586
                                                          0.4802
                                                                   0.5019
Pb
         0-717
                   0.1484
                              0.2151
                                       0.2868
                                                 0.3585
                                                                             0.5786
                                                                                      0.6453
Ŀ
                   1.0596
                                       2.1192
                                               2.6490
                                                         8.1788
                                                                  8-7086
                                                                            4-2884
                                                                                      47682
         0-5298
                              1 5894
                              04682 06176 07720 09264
                   0.3088
                                                                  1-0808 1-2259 1-2896
         0.1544
                                              24
```

As the use of the table in deducing formulas involves the frequent multiplication of the oxygen per-centage, the multiples by the digits 1 to 9 are given, for the compounds of most common occurrence, at the foot of the two preceding pages.*

The modes of combination and uses of chemical language are explained in chemical treatises, to which reference should be made by the student. A few brief illustrations are here added:

By atomic weights is understood the combining proportions of the elements. For example, when iron and oxygen combine, they unite in the proportion of 350 parts by weight of iron to 100 of oxygen, or in some simple multiple of this ratio. The protoxyd contains one part or atom of each, and has therefore the atomic weight 450; the peroxyd (more precisely sesquoxyd) contains 2 of iron (2×350 = 700) to 3 of oxygen, (3×100=300), and therefore has the atomic weight 1000, (700+300=1000). To ascertain the per-centage of oxygen in this oxyd, we have 300 of oxygen in 1000 parts; hence the ratio, 1000 are to 300 as 100 to the number of parts in 100; therefore dividing 300×100 by 1000 gives the oxygen per-centage. Hence too if we multiply the per-centage of oxygen by the atomic weight of the oxyd, we obtain as a result, after dividing by 100, the oxygen amount in the compound. For alumina, 46.7×642.5 +100=300, the amount of oxygen; and in this way the correctness of the oxygen per-centage may be verified.

The mode of deducing chemical formulas may be illustrated

by two or three examples.

1. We have an analysis of Red Silver Ore as follows: Silver 59.02, antimony 23.49, and sulphur 17.49 per cent.

It is desired to ascertain the relative number of atoms of each element in the compound. This number must depend on the weights of the atoms, as compared with the quantity of each, for the less the weight, the greater the number of atoms. The rule consequently is,—Divide the per-centage of each element by the atomic weight of the same; as, 59.02 by 1350, the atomic weight of silver, and so on. (See preceding table). This process gives the relation,

0.0437:0.0146:0.0875,

and dividing each by the smallest, to simplify it, it becomes 3:1:6,

which is therefore the number of atoms of each, silver, antimony, and sulphur. The formula 3Ag+1Sb+6S, or Ag'Sb S', expresses this relation.

^{*} Since the printing of the first half of the preceding table, (and a portion also of the second volume of this work), an article has appeared in the L. E. and D. Philosophical Magazine, noting the fact that Rose's Niobium is properly Hatchett's Columbium, and that consequently the name Columbium should be given it. The true Tantalum of Berzelius is another metal. Hence, after Columbium, p. 184, the Symbol Cb should be written; and for Columbia acid Cb. The atomic weight of Columbium is yet undetermined, though near that of Tantalum.

As chemistry makes known a sulphuret of silver consisting of 1 of sulphur to 1 of silver, and also a sulphuret of antimony containing 3 of sulphur to 1 of antimony, the ingredients are regarded as thus combined in the compound. The 3Ag take 3S, making 3AgS, and leave 3S for the 1Sb to form 1(SbS³); so that Red Silver Ore is supposed to be represented by the formula

3AgS+SbS2; or Ag2Sb,

if the mark (1) be used, as is common, for Sulphur.

2. An analysis of Feldspar gives in 100 parts,

Silica 64.78, Alumina 18.38, Potash 16.84.

Now if we ascertain the proportion of oxygen in these constituents we learn the ratio of the constituents, since we know that silica contains 3 of oxygen, alumina 3, and potash 1. From the above table we find that 100 of silica contain 52.98 of oxygen; consequently if 100 give 52.98, the amount in 64.78 parts will be found by multiplying 52.98 by 64.78, and dividing by 100; or what is equivalent, multiplying 0.52.98 by 64.78. So in 100 parts of alumina the oxygen is 46.7; hence the oxygen in 18.38 parts of alumina will equal 18.38×46.7÷100. In this way we ascertain that

64-78 of silica contain 34-32 oxygen, 18-38 of alumina " 8.58 " or, dividing each by the smallest, 1 1

Hence the amount of oxygen in the potash, alumina, and silica, is as 1:3:12. Now as each atom of silica contains 3 of oxygen, 12 atoms of oxygen correspond to 4 of silica: so also 3 of oxygen for the alumina correspond for a like reason to 1 of alumina; and 1 of oxygen for the potash to 1 atom of potash. The compound therefore contains 4 parts of silica to 1 of alumina and 1 of potash.

The next step in the usual method, is to determine how these constituents are combined; how much of the silica with the potash, and how much with the alumina. Reference is made to the possibility or probability of certain compounds, which Chemistry alone can teach; but aid is found in the principle, that the number of atoms of oxygen in each acid and base is usually some simple multiple, the one of the other. If in the above compound, 1 of silica be united with 1 of potash, the ratio alluded to is 1 to 3; and if the alumina be combined with the remaining 3 atoms of silica, the same ratio holds. This is the mode of combination commonly adopted; it is expressed in the following formula, the dots as explained, indicating the oxygen:

KSi+XISi".

The index 3 expresses the number of atoms of silica; had the 3 been written as a prefix, thus, 3x15i, it would have meant 3 atoms of a compound of silica and alumina.

The formula might also be written with equal precision, and without dividing the silica between the bases, as follows:

(於十基1) Bi4.

In a similar manner, an analysis of Garnet affords the ratio of ingredients as follows:

3 of lime (3Ca), 1 of alumina (1Al), 2 of silica (2Si),

corresponding to the oxygen ratio 3:3:6 or 1:1:2. Apportioning the silica to the bases, we have the formula

CaBi+AlBi,

in which the oxygen ratio for each member is 1:1. Idocrase

and Meionite afford other simple examples.

3. In Feldspar, above cited, the protoxyd portion is often not potash alone, but part sods or lime. Again, in Garnet, the protoxyds, instead of being alllime, may be part magnesia, protoxyd of iron, &c. In each case, however, all the protoxyds added together, make up the same specific number of atoms as if there were but one alone. So the peroxyd portion may not be all of it alumina, but part peroxyd of iron, the amount of this peroxyd of iron being just equivalent to the deficiency in the alumina; that is, an equivalent not in actual weight, but in atomic weight. In Garnet, as stated above, the oxygen ratio is 1:1:2; and whatever the peroxyds or protoxyds, the ratio still holds. Suppose an analysis of Garnet affords the per-centage, Silica 39.6, alumina 22.5, lime 32.6, protoxyd of iron 5.3: we ascertain the oxygen in each constituent in the manner explained, (in the Silica, by multiplying 0.5298 by 39.6,—in the alumina, by multiplying 0.467 by 22.5,—in the lime by multiplying 0.2857 by 32.6,—in the protoxyd of iron by multiplying 0.2222 by 5.3); then on adding the oxygen of the protoxyd of iron to that of the lime, the amount just equals that of the alumina, as the oxygen ratio requires. Moreover the oxygen of all the protoxyds and peroxyds together equals the oxygen of the silica.

As different protoxyds may thus replace one another, and as different peroxyds likewise admit of mutual replacement, it is common to write k as a general symbol for the protoxyds of a compound, and ### for the peroxyds. It is also common to write the special symbols of the protoxyds which replace one another, in parentheses, with a comma between them. Thus in the Garnet referred to, in which lime and protoxyd of iron replace one another, the gen-

eral formula may be either

R'Si+AlSi; or (Ca, Fe)'Si+AlSi.

The proportions of the lime and protoxyd of iron are not here stated, but may be; if 1:2, the formula becomes

(100+11°)Si+XISi.

Is (On 15) signifies that the compound is a

carbonate of lime and magnesia, in definite or indefinite proportions; (\$\delta \delta + \delta \text{Mg} \delta \delta \delta \text{that the proportion is 1:1; (\$\frac{2}{3} \delta + \frac{2}{3} \text{Mg} \delta

4. The formula for Garnet, Rosi+Alsi, may also be written with

equal precision as follows:

(1 Rº+1 X1)Si,

the ratio 1:1:2 being still retained, and the fact being also presented to the eye that the oxygen of all the oxyds is to that of the silica as 1:1. In Gehlenite, another silicate of alumina and lime, the oxygen ratio is 3:3:4, which gives 6:4 or 3:2 for the ratio of the oxyds and silica, (that is, the oxygen of the silica is two thirds that of all the oxyds), while that of the protoxyds and peroxyds is 1:1. The formula may hence be

R.Si#+RSi#; or (1R.+1R)Si#.

In the first of these formulas each of the two members has the same oxygen ratio 3:2; in the second this ratio is also retained, and is more briefly expressed, without the hypothetical idea that the silica in the compound is divided off between the protoxyd

and peroxyd bases.

5. To deduce the per-centage atomic relations from a formula, the process above described is reversed. For example: for feld-par we have 4 of silica, 1 of alumina, 1 of potash. In the preceding table the atomic weight of silica is 566.25, and four times this is 2265. Setting this down and the atomic weights of alumina and potash below it, and adding, we have

4 of Silien,	40)	100	10565	-	min	11	5.34	2265
1 of Alumina, 1 of Potash,	010	160	tuo:	Sar	411	160	100	642.5 588.86
I of Potash,			1					900.00

Total atomic weight of the feldspar, 349

3496.36

Now if this amount (3496·36) of feldspar contains 2265 of silica, what will 100 parts contain? Hence, to obtain the per-centage, we divide the atomic weight of each constituent in succession by the sum of the whole, and this gives the per-centage relation for each; viz. Silica 64·78, alumina 18·38, potash 16·84.

2. Relations of Minerals, as exhibited in the Principles of Isomorphism or Homomorphism, and Dimorphism.

The principle has now been long established that analogous elements, bases, or acids, may replace one another in compounds, without an essential change in the crystalline form of the species. Mutual replacement of protoxyd of iron, protoxyd of manganese, ime, and magnesia, in garnet, has already been alluded to. Simularly arsenic and phosphoric acids may replace one another, and

The formula might also be written with equal precision, and without dividing the silica between the bases, as follows:

(K+XI) Si*.

In a similar manner, an analysis of Garnet affords the ratio of ingredients as follows:

3 of lime (3Ca), 1 of alumina (1X1), 2 of silica (2Si),

corresponding to the oxygen ratio 3:3:6 or 1:1:2. Apportioning the silica to the bases, we have the formula

Ča*Ši+XIŠi,

in which the oxygen ratio for each member is 1:1. Idocrase

and Meionite afford other simple examples.

3. In Feldspar, above cited, the protoxyd portion is often not potash alone, but part soda or lime. Again, in Garnet, the protoxyds, instead of being alllime, may be part magnesia, protoxyd of iron, &c. In each case, however, all the protoxyds added together, make up the same specific number of atoms as if there were but one alone. So the peroxyd portion may not be all of it alumina, but part peroxyd of iron, the amount of this peroxyd of iron being just equivalent to the deficiency in the alumina; that is, an equivalent not in actual weight, but in atomic weight. In Garnet, as stated above, the oxygen ratio is 1:1:2; and what-ever the peroxyds or protoxyds, the ratio still holds. Suppose an analysis of Garnet affords the per-centage, Silica 39.6, alumina 22:5, lime 32:6, protoxyd of iron 5:3: we ascertain the oxygen in each constituent in the manner explained, (in the Silica, by multiplying 0.5298 by 39.6,—in the alumina, by multiplying 0.467 by 22.5,—in the lime by multiplying 0.2857 by 32.6,—in the protoxyd of iron by multiplying 0.2222 by 5.3); then on adding the oxygen of the protoxyd of iron to that of the lime, the amount just equals that of the alumina, as the oxygen ratio requires. Moreover the oxygen of all the protoxyds and peroxyds together equals the oxygen of the silica.

As different protoxyds may thus replace one another, and as different peroxyds likewise admit of mutual replacement, it is common to write R as a general symbol for the protoxyds of a compound, and H for the peroxyds. It is also common to write the special symbols of the protoxyds which replace one another, in parentheses, with a comma between them. Thus in the Garnet referred to, in which lime and protoxyd of iron replace one another, the gen-

eral formula may be either

R'Si+AlSi; or (Ca, Fe)'Si+AlSi.

The proportions of the lime and protoxyd of iron are not here stated, but may be; if 1: 2, the formula becomes

(†Ca+iFe)*Si+AlSi.

Again, the formula (Ca, Mg)C, signifies that the compound is a

carbonate of lime and magnesia, in definite or indefinite proportions; (4Ca+1Mg)O that the proportion is 1:1; (3Ca+3Mg)O that the proportion is 2:3, \frac{2}{5} and \frac{3}{5} having this ratio, and together equaling a unit. RO is a general expression for a carbonate of any protoxyd.

4. The formula for Garnet, R'Si+XISi, may also be written with

equal precision as follows:

(+R+++X1)Si,

the ratio 1:1:2 being still retained, and the fact being also presented to the eye that the oxygen of all the oxyds is to that of the silica as 1:1. In Gehlenite, another silicate of alumina and lime, the oxygen ratio is 3:3:4, which gives 6:4 or 3:2 for the ratio of the oxyds and silica, (that is, the oxygen of the silica is two thirds that of all the oxyds), while that of the protoxyds and peroxyds is 1:1. The formula may hence be

ذSi*+#Si*; or (½Ř°+½R)Si*.

In the first of these formulas each of the two members has the same oxygen ratio 3:2; in the second this ratio is also retained, and is more briefly expressed, without the hypothetical idea that the silica in the compound is divided off between the protoxyd

and peroxyd bases.

5. To deduce the per-centage atomic relations from a formula, the process above described is reversed. For example: for feld-spar we have 4 of silica, 1 of alumina, 1 of potash. In the preceding table the atomic weight of silica is 566.25, and four times this is 2265. Setting this down and the atomic weights of alumina and potash below it, and adding, we have

4 of Silica,	*				1	r.			nke.				1		2265
1 of Alumina, 1 of Potash,		N/	13	h	b	(0)	M	11		'n		8	1	1	642.5 588.86
	О.		-				2				ů		1		000 00

Total atomic weight of the feldspar, 3496.36

Now if this amount (3496:36) of feldspar contains 2265 of silica, what will 100 parts contain? Hence, to obtain the per-centage, we divide the atomic weight of each constituent in succession by the sum of the whole, and this gives the per-centage relation for each; viz. Silica 64:78, alumina 18:38, potash 16:84.

2. Relations of Minerals, as exhibited in the Principles of Isomorphism or Homeomorphism, and Dimorphism.

The principle has now been long established that analogous elements, bases, or acids, may replace one another in compounds, without an essential change in the crystalline form of the species. Mutual replacement of protoxyd of iron, protoxyd of manganese, lime, and magnesia, in garnet, has already been alluded to. Similarly arsenic and phosphoric acids may replace one another, and

The formula might also be written with equal precision, and without dividing the silica between the bases, as follows:

(水+米I) Si*.

In a similar manner, an analysis of Garnet affords the ratio of ingredients as follows:

3 of lime (3Ĉa), 1 of alumina (1\frac{X}{1}), 2 of silica (2\frac{X}{2}i),

corresponding to the oxygen ratio 3:3:6 or 1:1:2. Apportioning the silica to the bases, we have the formula

Ca Si+XISi,

in which the oxygen ratio for each member is 1:1. Idocrase

and Meionite afford other simple examples.

3. In Feldspar, above cited, the protoxyd portion is often not potash alone, but part soda or lime. Again, in Garnet, the protoxyds, instead of being alllime, may be part magnesia, protoxyd of iron, &c. In each case, however, all the protoxyds added together, make up the same specific number of atoms as if there were but one alone. So the peroxyd portion may not be all of it alumina, but part peroxyd of iron, the amount of this peroxyd of iron being just equivalent to the deficiency in the alumina; that is, an equivalent not in actual weight, but in atomic weight. In Garnet, as stated above, the oxygen ratio is 1:1:2; and whatever the peroxyds or protoxyds, the ratio still holds. Suppose an analysis of Garnet affords the per-centage, Silica 39.6, alumina 22.5, lime 32.6, protoxyd of iron 5.3: we ascertain the oxygen in each constituent in the manner explained, (in the Silica, by multiplying 0.5298 by 39.6,—in the alumina, by multiplying 0.467 by 22.5,—in the lime by multiplying 0.2857 by 32.6,—in the protoxyd of iron by multiplying 0.2222 by 5.3); then on adding the oxygen of the protoxyd of iron to that of the lime, the amount just equals that of the alumina, as the oxygen ratio requires. Moreover the oxygen of all the protoxyds and peroxyds together equals the oxygen of the silica.

As different protoxyds may thus replace one another, and as different peroxyds likewise admit of mutual replacement, it is common to write R as a general symbol for the protoxyds of a compound, and H for the peroxyds. It is also common to write the special symbols of the protoxyds which replace one another, in parentheses, with a comma between them. Thus in the Garnet referred to, in which lime and protoxyd of iron replace one another, the gen-

eral formula may be either

R'Si+AlSi; or (Ca, Fe)'Si+AlSi.

The proportions of the lime and protoxyd of iron are not here stated, but may be; if 1: 2, the formula becomes

(lCa+iFe)Si+AlSi.

Again, the formula (Ca, Mg)C, signifies that the compound is a

carbonate of lime and magnesia, in definite or indefinite proportions; (\$\darkalla_n + \darkalla_n \da

4. The formula for Garnet, R'Si+HiSi, may also be written with

equal precision as follows:

(1R3+1X1)Si,

the ratio 1:1:2 being still retained, and the fact being also presented to the eye that the oxygen of all the oxyds is to that of the silica as 1:1. In Gehlenite, another silicate of alumina and lime, the oxygen ratio is 3:3:4, which gives 6:4 or 3:2 for the ratio of the oxyds and silica, (that is, the oxygen of the silica is two thirds that of all the oxyds), while that of the protoxyds and peroxyds is 1:1. The formula may hence be

Ř*Si*+#Si*; or (1R*+1H)Si*.

In the first of these formulas each of the two members has the same oxygen ratio 3:2; in the second this ratio is also retained, and is more briefly expressed, without the hypothetical idea that the silica in the compound is divided off between the protoxyd

and peroxyd bases.

5. To deduce the per-centage atomic relations from a formula, the process above described is reversed. For example: for feld-spar we have 4 of silica, 1 of alumina, 1 of potash. In the preceding table the atomic weight of silica is 566.25, and four times this is 2265. Setting this down and the atomic weights of alumina and potash below it, and adding, we have

4 of Silica, 1 of Alumina, 1 of Potash,	orl .	one light	(8)	AND I	n'm	00	-117	2265 642.5 588.86
								2000

Total atomic weight of the feldspar,

3496.36

Now if this amount (3496·36) of feldspar contains 2265 of silica, what will 100 parts contain? Hence, to obtain the per-centage, we divide the atomic weight of each constituent in succession by the sum of the whole, and this gives the per-centage relation for each; viz. Silica 64·78, alumina 18·38, potash 16·84.

Relations of Minerals, as exhibited in the Principles of Isomorphism or Homocomorphism, and Dimorphism.

The principle has now been long established that analogous elements, bases, or acids, may replace one another in compounds, without an essential change in the crystalline form of the species. Mutual replacement of protoxyd of iron, protoxyd of manganese, lime, and magnesia, in garnet, has already been alluded to. Similarly arsenic and phosphoric acids may replace one another, and

The formula might also be written with equal precision, and without dividing the silica between the bases, as follows:

(於十五1) Si*.

In a similar manner, an analysis of Garnet affords the ratio of ingredients as follows:

3 of lime (3Ca), 1 of alumina (1XI), 2 of silica (2Si),

corresponding to the oxygen ratio 3:3:6 or 1:1:2. Apportioning the silica to the bases, we have the formula

Ca3Si+AlSi,

in which the oxygen ratio for each member is 1:1. Idocrase

and Meionite afford other simple examples.

3. In Feldspar, above cited, the protoxyd portion is often not potash alone, but part soda or lime. Again, in Garnet, the protoxyds, instead of being alllime, may be part magnesia, protoxyd of iron, &c. In each case, however, all the protoxyds added together, make up the same specific number of atoms as if there were but one alone. So the peroxyd portion may not be all of it alumina, but part peroxyd of iron, the amount of this peroxyd of iron being just equivalent to the deficiency in the alumina; that is, an equivalent not in actual weight, but in atomic weight. In Garnet, as stated above, the oxygen ratio is 1:1:2; and whatever the peroxyds or protoxyds, the ratio still holds. Suppose an analysis of Garnet affords the per-centage, Silica 39.6, alumina 22.5, lime 32.6, protoxyd of iron 5.3: we ascertain the oxygen in each constituent in the manner explained, (in the Silica, by multiplying 0.5298 by 39.6,—in the alumina, by multiplying 0.467 by 22.5,—in the lime by multiplying 0.2857 by 32.6,—in the protoxyd of iron by multiplying 0.2222 by 5.3); then on adding the oxygen of the protoxyd of iron to that of the lime, the amount just equals that of the alumina, as the oxygen ratio requires. Moreover the oxygen of all the protoxyds and peroxyds together equals the oxygen of the silica.

As different protoxyds may thus replace one another, and as different peroxyds likewise admit of mutual replacement, it is common to write R as a general symbol for the protoxyds of a compound, and R for the peroxyds. It is also common to write the special symbols of the protoxyds which replace one another, in parentheses, with a comma between them. Thus in the Garnet referred to, in which lime and protoxyd of iron replace one another, the gen-

eral formula may be either

R'Si+AlSi; or (Ca, Fe) Si+AlSi.

The proportions of the lime and protoxyd of iron are not here stated, but may be; if 1:2, the formula becomes

(†Ca+†Fe)*Si+XISi

Again, the formula (Ca, Mg)C, signifies that the compound is a

carbonate of lime and magnesia, in definite or indefinite proportions; (40a+1mg)0 that the proportion is 1:1; (30a+3mg)0 that the proportion is 2:3, 3 and 3 having this ratio, and together equaling a unit. RC is a general expression for a carbonate of any protoxyd.

4. The formula for Garnet, R'Si+XISi, may also be written with

equal precision as follows:

(+R°++X1)Si,

the ratio 1:1:2 being still retained, and the fact being also presented to the eye that the oxygen of all the oxyds is to that of the silica as 1:1. In Gehlenite, another silicate of alumina and lime, the oxygen ratio is 3:3:4, which gives 6:4 or 3:2 for the ratio of the oxyds and silica, (that is, the oxygen of the silica is two thirds that of all the oxyds), while that of the protoxyds and peroxyds is 1:1. The formula may hence be

Ř*Si*+#Si*; or (1R*+1#)Si*.

In the first of these formulas each of the two members has the same oxygen ratio 3:2; in the second this ratio is also retained, and is more briefly expressed, without the hypothetical idea that the silica in the compound is divided off between the protoxyd

and peroxyd bases.

5. To deduce the per-centage atomic relations from a formula, the process above described is reversed. For example: for feld-spar we have 4 of silica, 1 of alumina, 1 of potash. In the preceding table the atomic weight of silica is 566.25, and four times this is 2265. Setting this down and the atomic weights of alumina and potash below it, and adding, we have

4 of Silica,		JOHN	050	-	200	Lan		2265
1 of Alumina,	wit.	don	140	10 10	1 .	die	-	. 642.5 588.86
1 of Potash,				*				969.90

Total atomic weight of the feldspar,

Now if this amount (3496.36) of feldspar contains 2265 of silica, what will 100 parts contain? Hence, to obtain the per-centage, we divide the atomic weight of each constituent in succession by the sum of the whole, and this gives the per-centage relation for each; viz. Silica 64.78, alumina 18.38, potash 16.84.

2. Relations of Minerals, as exhibited in the Principles of Isomorphism or Homomorphism, and Dimorphism.

The principle has now been long established that analogous elements, bases, or acids, may replace one another in compounds, without an essential change in the crystalline form of the species. Mutual replacement of protoxyd of iron, protoxyd of manganese, lime, and magnesia, in garnet, has already been alluded to. Similarly arsenic and phosphoric acids may replace one another, and

the crystallization remain unchanged, or with but a slight variation of angle. This capability of mutual replacement without change of form has been traced to a similarity of form in the replacing substances, and such substances are said to be isomorphous, (from юсь, equal, and морфи, form), or homeomorphous, (from вмоюсь,

similar, and μορφη).

Absolute identity of form between related species occurs only when the crystallization is monometric. In this system very wide variations in composition take place, through isomorphous substitutions, without the slightest change of angle. There is a balance of forces in these equiaxial forms which is not overcome even when the substitutions are such as would make a difference of two or three degrees in a rhombohedral form. Thus in Garnet, magnesium and calcium take one another's places with no change in the angle of the form, while the same substitution in a rhombohedral carbonate makes a difference of nearly two and a half degrees.

The term Isomorphism is hence strictly applicable only to monometric species, while Homeomorphism is of general application.

The more important isomorphous groups of elements, bases, and acids, as regards the constitution of minerals, are the following:

1. Oxygen, Fluorine.

 Chlorine, Bromine, Iodine.
 Sulphur, Selenium; Sulphuric and Selenic Acids, with also in part Tantalic, Columbic, Molybdic, and Tungstic Acids.

4. Chromic and Vanadic Acids.

5. Arsenic, Phosphorus, Antimony, Bismuth; Arsenic and Phosphoric Acids.

6. Titanium, Tin; Deutoxyd of Tin, and of Titanium.

7. The metals of the Hydrogen Group, (see beyond); their protoxyds; their sesquoxyds. In the Sulphurets, eu or 2Cu replaces 1Pb, 1Fe, &c.

Homœomorphism, as Laurent has observed, is not confined to forms of the same system alone. Thus Orthoclase and Albite, one monoclinic and the other triclinic, are in fact homoeomorphous; so also Natrolite and Scolecite; Epistilbite and Heulandite. The approximation of form between Idocrase and the monometric octahedron may be regarded as homeomorphism, as stated by Laurent; and still as the monometric species undergo the various isomorphous substitutions without a change of angle, it is a less satisfactory case than the others mentioned.

The same element may crystallize in different systems, so that the two forms are unrelated. Carbon is an example, the diamond being one form, (monoclinic), and graphite another, (hexagonal). In physical characters, the two are different; both as to hardness, specific gravity, color, optical characters, and also chemical reactions to some extent. This property of presenting two independent forms is called dimorphism, from os, twice, and poppy, form.

In some cases, the same substance has three independent forms. Thus carbonate of lime is sometimes rhombohedral, as in Calcite; sometimes trimetric, as in Aragonite; sometimes monoclinic, as in Barytocalcite. This is an example of trimorphism. Rutile, Brookite, and Anatase, are three forms of Titanic Acid. Garnet, Allanite, in part, and Biotite, are three forms of the same silicate. Carbon is regarded as actually trimorphous, the diamond and graphite, as just stated, being two forms or conditions, and charcoal the third condition.

Two substances may be both homeomorphous and correspondingly dimorphous; and they are then described as *isodimorphous*. Thus both Titanic Acid and Oxyd of Tin are dimorphous, and they are homeomorphous severally in each of the two forms. This is an example of *isodimorphism*.

There are also cases of isotrimorphism. Thus there are the following related groups; the angle of the rhombohedral forms here

given is R:R; of the trimetric and monoclinic, I:I:

Rhombohedral.

BČ Calcite, 105° 5'. Aragonite, 116° 10'. Barytocalcite, 95° 8'.

RŠ Dreelite, 93°-94°. Anglesite, 103° 38'. Glauberite, 83°-83° 20'.

BŠ+nŘČ Susannite, 94°. Leadhillite, 103°16'. Lanarkite, 84°.

Calcite, Aragonite, and Barytocalcite, are an undoubted case of trimorphism, the same compound (RO) occurring under these three forms. Dreelite, Anglesite, and Glauberite, constitute another like series, and moreover it is closely parallel in angle with the former. The difference between the angle R:R of Calcite and Dreelite is near that between I:I of Anglesite and Aragonite, and also that between I:I of Glauberite and Barytocalcite. In the third line we have the sulphato-carbonate Susannite near Dreelite in angle, Leadhillite (identical with Susannite in composition) near Anglesite, and Lanarkite, another Sulphato-carbonate, near Glauberite, forming thus a third parallel line. The sulphuric acid in these sulphato-carbonates dominates over the carbonic acid, and gives the form of the sulphates enumerated in the second line of the table.

The known cases of dimorphism among the elements are the following:

1. The two forms monometric and hexagonal (R: R=82°-88°).—Arsenic, Antimony, Phosphorus, Bismuth, Palladium, Iridium, Iron (?), Copper, Carbon.

2. The two forms monometric and dimetric.-Tin.

3. The two forms trimetric and monoclinic.—Sulphur, Selenium.

The homœomorphous groups among minerals are numerous, and in many of them species very various in composition are included.

Before giving a list of them, the methods of comparison and evidence of true affinity or homology may be briefly reviewed.

Monometric System .- In this system, as the dimensions are unvarying, the species fall into a single group, unless cleavage and hemihedrism are important distinctions. Cleavage is often of little importance. The two species Gray Copper and Tennantite, analogous in composition, have one, an octahedral, the other, a dodecahedral cleavage. Sylvine (chlorid of potassium) has a cubic cleavage, while the related compound, chlorid of ammonium, has an octahedral. Hemihedrism is often of value in marking off species. It is a remarkable fact that while the protoxyd of zinc is rhombohedral, like the peroxyd of iron and aluminium, and unlike other protoxyds, the sulphuret of zinc is tetrahedral, unlike most related protosulphurets. Again, the borates, Boracite and Rhodizite, are hemihedral; and so also are all minerals containing boracic acid, that crystallize in other systems, excepting those that are oblique in crystallization. On the other hand, the related compounds, FeS' (pyrites), Co (S,As)2, and Co As2 differ, the first two being hemihedral, while the last is not so-indicating apparently that the sulphur here determines the hemihedral character.

Dimetric and Trimetric Systems.—In the dimetric system, there are two square prisms to each form, one diagonal to the other, and the axial dimensions of a species will vary according as we assume one or the other to be the fundamental prism. This uncertainty is one to be set aside by the best means we may have, and to be admitted where analogies still leave it unremoved. The length of the vertical axis also varies directly according as one octahedral plane or another in a series is referred to the unit octahedron. There is often a number of planes, between which we may choose, one of which will give a vertical axis two or three times as long as another. Here is a second source of doubt. The planes assumed as those of the unit octahedron by crystallographers, are ordinarily so assumed because they afford a simple view of the relations of the planes; and with no better evidence of correctness than this, they may lead to error, when we have in view a comparison of form be-

tween different species.

Cleavage affords the best criterion with regard to the vertical prism, the cleavage prism being usually the true fundamental prism. But in some cases there are no vertical cleavages, and only basal or octahedral. An octahedral cleavage affords important evidence

as to the fundamental octahedron, whenever it occurs.

Frequency of occurrence of planes is another criterion, and one of some value in determining the true fundamental prism and the unit octahedron; yet it is often a false guide. A striking example of its want of value in another system, is seen in Calcite, the fundamental rhombohedron of which is of rare occurrence; also in Fluor, which is oftenest in cubes, although its cleavage is octahedral;—so also in Quartz, Tourmaline and other species, in which the fun-

damental form is far less common than some of the secondary

forms, if ever observed.

Twin-composition parallel to an octahedron plane, is good evidence as to which is the true unit-octahedron, since twins are formed, with rare exceptions, parallel to planes of unit or primary value In the monometric system they occur only parallel to the three primary sections—that is, parallel to a cubic face, an octahedral and a dodecahedral; and they are almost always parallel to corresponding sections in the dimetric system. Still the doubt may remain whether the plane of composition, if a unit plane, belongs to the fundamental or diagonal series; and it is possible that it may be some other than a unit plane.

There is hence no criterion which is an unfailing reliance. All the several characteristics must be reviewed, and also the analogies with other species, in order to arrive at a satisfactory conclusion.

In very many cases, we may make out a relation in the angles of the series of octahedral planes occurring in dimetric species, when it is impossible to decide with certainty which plane in the series belongs to the unit-octahedron for the species. This serial relation is of the highest importance, and is independent of all the doubts above alluded to. It indicates a fundamental analogy between the species so related. Thus the table beyond shows that the octahedron regarded as 1 in zircon and rutile, is identical nearly in angle with that considered 1 in Nagyagite; and if these two planes have this relation, then the plane 2 of the former and 1 of the latter will be likewise related; so that there is a serial relation between the forms of the species. Again, 1 in zircon is nearly identical in angle with the intermediate octahedron 2i of Scapolite and Mellilite. There is no valid reason for making this octahedron of scapolite one of the diagonal series; and none also for assuming it as 2i rather than 1i or 4i, excepting the frequency of occurrence of the plane. This example and the further application of the same principle apparent in the table will suffice to illustrate what we mean by the serial relation of forms.

In Trimetric forms, doubts are still more varied. It is first necessary to decide which is the true vertical axis, as either of the three axes may be made the vertical. The best evidence on this point, is that afforded by cleavage, the prism of most perfect cleav-

age being almost always parallel to the true vertical axis.

The next point is to determine the unit vertical prism from which we may ascertain the relation of the lateral axes (b:c). This may be the cleavage prism just alluded to. Yet in some cases two species evidently closely related in form, have cleavage parallel to different prisms. In Augite, in the monoclinic system, cleavage is parallel to a prism of 87° 6', and in hornblende, closely homeomorphous with augite, it is parallel to a prism of 124° 30'; the last has twice the breadth of the other,—a simple mathematical relation which proves an actual analogy of form

in the two species; and this is sustained by finding that all the planes of one may be very simply deduced from the type of the

Another criterion is afforded by twin composition, on the principle already explained. Although as stated above, it is not always sure evidence, it is in very many cases of high authority.

Similarity in modes of composition always suggests, if it does not prove, that species are related in form, and that the planes of composition are homologous. Thus we have evidence in the twins parallel to a prism near 120° in angle, of the relation which exists between Aragonite, Cerusite, Chrysoberyl, Copper Glance, etc.; and at the same time, of the wide discrepancy between Aragonite and Bournonite, and between Chrysolite and Chrysoberyl. The prism of Bournonite (115° 58'), near the fundamental prism of Aragonite, is only a secondary prism (i2); the twins of Bournonite are formed parallel to the true fundamental prism of the species, that of 93° 40'. Chrysolite also affords no stellate twins like those of Chrysoberyl; the angle of its vertical prism is 94° 3', and it belongs to a different zone from that of Chrysoberyl. Chrysoberyl and Aragonite, on the contrary, are closely related; they have similar twins, and the former has a brachydome of 108° 26', the latter of 109° 39'.

Additional assistance, but of less certain value, may be had by reference to the frequency of occurrence of planes, or superior lustre or smoothness, and also by noting the resemblance in habit to

species that are already well determined.

After determining the true vertical axis and unit vertical prism, a unit dome or octahedron must next be ascertained, in order to fix the length of the vertical axis. Here twin composition, the frequency of occurrence of planes, and rarely cleavage, come in to afford help, yet only to afford presumptive, not demonstrative, evidence. Analogies with other species chemically related, afford

very essential aid, and should never be overlooked.

Notwithstanding the doubts that may remain, we may, as in the dimetric system, discover a serial relation in the angles, and this is sure evidence of a true mathematical relation between forms. If we cannot decide whether the form which crystallographers have made the unit octahedron is in fact the true unit octahedron, we may discover that the angles of the forms \frac{1}{2}, 1, \frac{3}{2} or 2, are similar to a series in another species, and prove thus a true fundamental resemblance.

Clinohedral Systems. In the Monoclinic System the same difficulties exist. Of the three axes the vertical must lie in the clinodiagonal section, but it may have any position in this section. A crystal in this system is hence like a wheel, any spoke of which may be made the vertical one. When there is distinct cleavage parallel to a prism, the axis parallel to the faces of this cleavage prism may be regarded as the true vertical axis. But the top plane of this prism is yet to be assumed or ascertained: either by taking a plane of cleavage, when there is one; or one of twin-composition; or one of most frequent occurrence; or one suggested by analogies with other species. The criterion appealed to by the crystallographer is usually, simplicity in calculation—one of some importance, but often misrepresenting the true relations of species.

portance, but often misrepresenting the true relations of species.

Rhombohedral System. The remarks on the Dimetric System apply in principle here. In this system, there are two hexagonal prisms to each species, one diagonal to the other, (one lettered I, the other i2); also two series of pyramids, one corresponding to each prism, (one lettered 1, 2, 3, &c., the other 12, 22, 32, &c.) Either series may be the fundamental series: and in a series of pyramids, there may be a choice between two or three of them as to the unit pyramid. Hence the angle of pyramid 1 in one species, may be near that assumed by the crystallographer as 2 in another, and which might as correctly be made 1. In the table beyond, such relations are seen in numerous cases. The serial relations in angle exhibited are devoid of hypothesis on this point.

After the above explanations, the following tables are presented.

In the Dimetric and Rhombohedral Systems, the accepted values of the planes are given, without conforming them to one or more types. In the Trimetric System, the related species for the different groups are reduced to a common type, and the values of the planes as adopted by the best authors, when not the same as taken in the table, are mentioned in parentheses.

1. Monometric System.

1. Holohedral Forms.*

		Cleav.		•	Cleav.
Amalgam,	AgHg ^a RS	D.	Red Copper,	C uO	О.
Galena,	RS	H!	Melaconite,	CuO	
Cuproplumbite,	4	H!	Spinel,	R₽	H,O,tr.
Erubescite.	4	Ο.	Magnetite,	46	• •
Manganblende,	44	D.	Franklinite,	44	
Silver glance,	••	H, D, tr.	Chromic Iron,	44	
Naumannite,	RSe	HI!	Arsenolite,	AsO ²	0.
Clausthalite,	**	H.	Senarmontite,	SbO ⁸	0.
Altaite,	RTe	H.	Fluor Spar,	CaF	01
Linnzite,	Co ² S ⁴	H.	Salt,	RCI	H.
Skutterudite,	CoAs ³	H.	Sylvine,	"	н.
Smaltine,	RAs ³	D, tr.	Sal Ammoniac,	44	Q.
Chloanthite,	"	**	Horn Silver,	"	
Ullmannite,	R(S, Sb, As)2	H!	Bromic Silver,		
Dufrenoysite,	RS++1As*S*.		Embolite,	R(Cl, Br)	H.
Periclase,	RO	н.	Perofskite,	CaTi	H.

^{*} In this table H stands for Hexahedral or cubic; O for Octahedral; D for Dodecahedral.

Section.	market a land of	Cleav.		Cleav.
Pyrochlore,	ŘºTa²?		Ittnerite,	(化十五)513+211.
Alum,	(R+H)S+241	T O.	Sodalite,	" + NuCl.
Garnet,	(Ra,H)Si	D.	Hauyne,	" ++CaS.
Leucite,	(R+H)Sis	D.	Nosean,	" + 18 NaS.
Analcime,	" +2H	H.	and the later water	orthogen of tendency

2. Tetrahedral.

<u>ta</u>

Blende, Gray Copper.
Helvin, Tennantite.
Tritomite, Eulytine.
Boracite, Pharmacosiderite.
Rhodizite,

3. Pyritohedral.

Pyrites, FeS². Cobaltine, Co(S, As)². Hauerite, MnS². Gersdorffite, Ni(S, As)³.

2. DIMETRIC AND HEXAGONAL SYSTEMS.

In the Dimetric System, there are two grand groups, the first (Rutile Group) consisting of Sections I, II, III, and IV; and the second (Idocrase Group) of V and VI. The simple relation as to the vertical axis in the sections of each of these groups is obvious without further remark. In the first of these groups, the basal angle of the fundamental octahedron is near 90° (4° to 7° above it), and in the second near 109° 28′; or taking 1i of Idocrase as 1, the basal angle is also near 90°, but 1° to 6° less than 90°.

In the hexagonal system, there are also several Sections, if we take the values of the vertical axis as usually deduced. But the second section becomes united to the first if we take the plane $\frac{2}{3}$ as 1; and the IV, also, if we take $\frac{1}{3}$ as 1, the ratios of the axes for the sections being of this simple kind. In Section V, an intermediaet pyramid is very near in angle a pyramid in each of the other sections. The basal angle of pyramid 1 in this section is near 90°, and hence R:R in Calcite, &c., is near 105°, and to this angle many species approximate. In Section IV, the angle R:R is near 90°, but 1 to 6 degrees less than 90°. In Section III, the angle R:R is also near 90°, but 2 to 5 degrees above it.

There are close correspondences in angle between Hexagonal and Dimetric species, as the two tables exhibit to the eye; and they indicate a kind of Homcomorphism; for a like inclination of the base on a pyramidal plane is truer evidence of analogy or identity than equality in the calculated axes; it is a correct measure of the relations in the ellipsoidal molecules of the two forms. With equal axes in a Dimetric and Hexagonal form, the inclination of O on 12 in the former will equal O on 12 of the latter; but O on 1 in the two will diverge widely, because in one the lateral axes cross at 90° and in the other at 60°; hence the unsatisfactory character of comparisons between the forms of the two systems made from the calculated axes.

Dimetric System.*

	_	. •			
I.	0:1	0:2			0:3
Tin,	151° 24′	18 2° 81′	•••••		121° 26′
II.	0:3			0:1	0:2
Zircon,	148° 52'			1870 507	118° 54'
Rutile,				1870 401	118° 46'
Cassiterite				186° 26'	1170 48'
Œrstedite,				1380 2/	
Edingtonite,	•••••	•••••		186° 20′	•••••
m.				O : 2i	0 : 4i
Scapolite,				188° 38′	119° 36'
Sercolite,				188° 25'	119° 24′
Meionite,				138° 48′	119° 40'
Mellilite,				187° 48′	1180 48'
				20, 20	110 10
IV.	0: 1			0:1	0:1
Apophyllite,	149° 30'	l l		138° 82′	119° 80′
Nagyagite,				187° 80′	118° 87'
Uranite,				1870 27	1189 354
Anatase,				188° 28′	1190 221
Matlockite,				188° 87′	1190 84'
Calomel,	•••••			188° 56'	119° 51′
Hausmannite,				140° 17′	1210 8
Faujasite,	•••••				118° 16′
v.		0 : 1i	0:1		
Romeine,		1840 17/	1240 351		
Cerasine,	•••••	182° 40′	123° 06′		
Chiolite,			1280 171		
Braunite		1	125° 40'		
Idocrase,		::::::	(2) 123° 27′		•••••
Copper Pyrites,		135° 25′	1250 40'		
Tin Pyrites,		100 20	120 10		•••••
Mellite,		(1)1880 27	1280 16'		
Gismondine,		(1) 188° 45'			
G Editor and S, 11111111	•••••	(1)100 10	l	••••	•••••
VI.		0:1	0:1i		
Scheelite,		188° 38′			
Schooletine		1820 5'	122° 83′		
Wulfenite,			122° 26′ 124° 20′		

The angles given in the Dimetric System, are the inclinations of the basal plane O on the octahedral planes specified; and in the Hexagonal System, those of O en different pyramids specified, (or rhombohedrons). The isomorphous groups of species presented in this and the following tables, have to a large extent been made out by other authors. Von Kobell as early as 1831 showed the relations of a large part of the dimetric species in principle as above presented. The alumina group first indicated by Mitscherlich, was extended by Prof. G. Rose, who added the rhombohedral metals and Red Zinc Ore. Frankenheim and others have abored extensively in this department. The relations of the groups to one another in these several tables were first presented as here given by the author in the Jour. Lyeeum Nat. Hist. N. Y. 1854, vi, 37, and Am. J. Sci. [2], xvii, 480, xviii, 35, and many additions to the groups were made by him at the same time, and to some extent in earlier papers.

Hexagonal System.

I.	0:1	0:2	0:3	0:12	0:2-2	0:4-2				
Coquimbite,	1510 00'		1 5000	Market I	1100000					
Beryl,	150° 3'	130° 57'	120° 3'	153° 29'	135° 4	1160 37'				
Pyrosmalite,	148° 30'	129° 13'	118° 33'	1520 8'	133° 18					
Eudialyte (R)	11480 38'	1290 21	118° 40'	1520 10'	133° 27					
Dioptase (R),	148° 38′	129° 21'	118° 40′	152° 10′	133° 27	115° 20′				
11	0.2	0.4	0.0		0.40	Section 1				
II.	0:3	0:4	0:2	177711	0:4-2	April 19				
Apatite,	150° 851	131° 35'	120° 36'	****	135° 41					
Levyne (R),	1500 43	131 43	120° 44′		135° 50					
Mimetene,	1500	180° 58′	1200	****	1350 0	100 100 100 100 100 100 100 100 100 100				
Pyromorphite,	1500 27	131° 26′	120° 28′	****	135° 32	1222				
III.	0:1	0:1	0:3	0:1-2	0:1-2	0:2-2				
1 7 1 1 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2		128° 13'	1170 42'	151° 12'	1820 17	A STATE OF STREET				
Quartz (R), Chabazite (R),	1400 99	1290 15'	1180 35'	152° 5'	133° 20'					
Dreelite (R),	1470	120 10	4444	The second second	100 20	110 10				
Susannite (R),	1470 98	128° 03'		151° 3′	1320 7	1140 19'				
Cinnabar (R),	1460 897	1270 06'	****	150° 13'	131° 8					
		126° 57'	****	11000		****				
CHR. THE PARTY OF			113333	The same	The same of	The same of the sa				
IV.	0:1	0:3	0:1	0:1-2	0:2-2	0:42				
Corundum (R),	1520 19'	1330 37'	1220 26'	155° 84'	1370 44'					
Specular Iron (R),			1220 30'	155° 374	1370 49	118° 58'				
Ilmenite (R),	****	*****	1220 30'	1550 374	1370 49'	118° 53'				
Willemite (R),			122° 18′	155° 27'	137° 35′	1180 411				
Phenacite (R),			123° 16'	156° 15′	138° 39′	1190 86'				
Bismuth, (R),	****	****	123° 36′	156° 31′	1390 1	119° 55'				
Arsenie (R),	****	****	1220 9'	155° 20'	1370 26'	118° 34'				
Antimony (R),	****	****	123° 32′ 122° 24′	156° 28′ 155° 38′	188° 56′	1190 51'				
Tellurium (R),		****	1210 33'	The same of the sa	137° 42′	118° 48′				
Iridosmine (R), Tetradymite (R),	****	****	118° 38'	****	****	****				
Red Zine Ore,	****		1230 5'	156° 5'	1380 27	1190 26'				
Copper Mica (R),.			1240 9							
Alunite (R),	****	11925/04/01				****				
Brucite (R),	****		1190		****	****				
	100000	40.0	Don't a		1000	V 3 10 1				
V.	0:3.2	0:4.2	0:2.2	$0:\frac{1}{2}$	0.1	0:2				
Pyrrhotine,	149° 53'		119° 53'	153° 20'	134° 52′					
Greenockite,	****	****	****	154° 32′	186° 28′	100000000000000000000000000000000000000				
Breithauptite,	2772	****	****	153° 38′	135° 15′	116° 46′				
Copper Nickel,		****	****	1540 41'	1360 35'	1170 51'				
Iodid of Silver,		****	****	1540 49'	186° 46′ 186°	1180				
Nepheline,			****	154° 134′ 154° 7′	1850 52	1170 221				
Cancrinite,		****	****	194 4	(1) 136° 53'					
Parisite, Tourmaline (R),	1499 107		****	1520 40'	1340 8	1150 49				
Calcite (R)	1500 207	****		1530 45'	1850 28	116° 58'				
Dolomite (R),			1000	1540 20'	136° 8'	1170 28				
Magnesite (R),	****	****		154° 57'	136° 56'	1180 9'				
Spathic Iron (R),.		2775		1540 43'	136° 37′					
Smithsonite (R), .	****	****		155° 2'	187° 8′					
Diallogite(R),	****	1000		1540 37	1360 311	1170 48'				
Pyrargyrite (R), .	****	****	4000	155° 32'	137° 42′ 137° 9′	118° 47′ 118° 19′				
Proustite (R),	****				137° 9′ 136° 1′					
Millerite (R)	****	****	****	****	1420 44'	10000				
The state of the state of			****	****	190 30					

3. Trimetric System.

The species of this system fall naturally into three or four great groups, differing in the angle of the unit vertical prism, (angle I: I), as follows:

Angle I: I from 90½° to 95°.
 Angle I: I near 102°, or from 98° to 105°.
 Angle I: I near 110°.

4. Angle I: I near 120°.

The species of the third group, by changing the position of the crystal, fall into the second group, and this may be their true place, although cleavage seems to indicate that the prism of 110° is the true vertical prism. The species are inserted in the second group, and also stand as Table III by themselves.

The angles mentioned in the Tables are the obtuse angle of the prism I: I, (column 1), and the angle at top of the unit macro-

dome and brachydome (12 and 14).

Angle of Vertical Prism I near 90°.

	Vert Prism. <i>I</i> : <i>I</i>	Macrodome. 1f: 1f	Brachydeme. 1¥:1¥	Axes. a:b:c
L				
Thomsonite	90° 40′	108° 18′	1080 56	072253:1:1-0117
Mesotype,	910	(21)108° 46'	(21)109° 42'	0-71644:1:1-0176
Harmotome,	91° 46′	108° 48′	110° 26'	071626:1:10812
Wöhlerite,	90° 54′	108° 2′	108° 56'	07261 : 1:1-01588
Polymignyte,	91° 44′	108° 6′	109° 46′	0.7252 : 1 : 1.0808
Æschynite,	90° 34′		112° 28′	0.675 : 1 : 1.01
Pyrolusite,	980 40/	104° 22′	(11)107° 54'	0776 : 1:1-0661
Andalusite,	900 44/		109° 50′	071198:1:10129
Lievrite,	(1) 91° 82′	111° 14′		0.68429:1:1.0271
Staurotide,	(1) 98° 8'	(11)108° 12'	111° 10′	0.72388 : 1 : 1.05617
Wavellite,	(1) 90° 34'	(21)106° 14'	106° 46′	0.75047:1:1.0099
Olivenite,	92° 80′			072084:1:10446
Libethenite,	92° 20′			0.7811 : 1:1.0416
Caledonite,	95°	(11)105° 8'	({}1)109° 54′	0.76568:1:1.0918 0.74176:1:1.0805
Chondrodite,	94° 26′	(11)106° 52'	(11)111° 4'	0.74176:1:1.0805
Antimony Glance,	90° 45′	(11)109° 26'	({{11})110° 8′	0.6901 : 1 : 1.0182
Do . do	90 45	(11) 880	(11) 880 47	1 0 0 5 2 : 1 : 1 0 1 3 2
Polycrase,	95°	(11) 88° 80′	(11) 98° 58'	1.02655: 1:1.0918
П.				
Epsomite,	900 84	1200 4	1200 88	0.57647:1:1:01
Zine Vitriol,	90° 42	1200 20		0.5785 : 1 : 1.0128
Diaspore,	930 52			0.68398:1:1.0699
Göthite,		118° 6		0.66068:1:1.0888
Polianite,		115° 26	1180	0.6817 : 1:1-0518
Euchroite,		117° 20	119° 18′	0.6088 : 1 : 1.088
Topaz,	(4)98° 8	(4x)115° 22	(11)118° 10	0.68258 : 1 : 1.0561
Chrysolite,	94° 8	(+t)115° 86	(1)119° 12	0.6297 : 1:1.0783
Triphyline,		(11)118° 27	(11)121° 55	0.59549:1:1.0724
Bournonite,		(11)115°	(#1)118° 14	
Do	. "	(11) 92° 84	(11) 96° 12	
! Warwickite,		1		
! Lanthanite,		4	1	

Table II. $\textit{Angle of Vertical Prism I near } 102^{\circ}.$

	Prism I	Dome 17.	Dome 1%	Axes a:b:c.
I.				
Valentinite,	(4) 103° 30	58° 17	700 32	17934:1:1-2688
Barytes,	101° 40	680 40		1:6107:1:1:2276
Anglesite,	103° 38		1.4	1.6415:1:1.2716
Leadhillite,	108° 16		,	17205:1:1.2639
Celestine,				1.6432:1:1.2807
Anhydrite,	0.500		10.00	1.6836:1:1.2557
Tentelite		(21) 64° 7'		1.5967:1:1.2247
Tantalite,	104° 59	590 31		1.749 : 1 : 1.8
Glaserite,	1030 26			
Thenardite,	1000 20			1.6905:1:1.267
Descloizite,	100° 28			1.494 : 1 : 1.2059
Mascagnine,				1.5437 : 1 : 1.3680
Atacamite,				1.4919:1:1.1310
Marcasite,				1.5049 : 1 : 1.1847
Sulphur,				1.5606:1:1.2345
*		(11) 46° 16'	(11) 55° 36'	2.3408:1:1.2349
II.				Section of the second
Orpiment,	100° 40	780	880 80	1.3511 : 1 : 1.2059
Dimorphine (I),	980 6	hen to		1.2876 : 1 : 1.1526
" (II),	100° 89		00 40	1.8262 : 1 : 1.203
Missiskal	990 59	C. C. C. C. C. C. C. C. C. C. C. C. C. C	04 44	1.3520:1:1203
Mispickel,			02 40	1.3797 : 1 : 1.2234
Aurotellurite,			880 6'	
Epistilbite,	(4) 1000 08	730	(41) 81, 30,	1.4063 : 1 : 1.2121
Childrenite,	104° 14	10	870 14	1.3514 ; 1 : 1.2858
III.	1.623	100 000 00		1
Prehnite,	990 56	(21) 89° 45	990 41/	1.0044 : 1 : 1.1904
Columbite,			970 98/	1 0584 : 1 : 1 2059
Wolfram,		88° 6'	000 19/	1.0837 : 1 : 1.2149
Mengite,	. 100° 28	87° 24	970 54	1.0463 : 1 : 1.2071
Brookité,	100°	83° 14'		1-1260 : 1 : 1-1918
Scorodite,	980	840 40		1.0977 : 1 : 1.115
Hopeite,	1010	86° 38'		1.0607 : 1 : 1.213
Struvite,*	101° 45	850 4		1.0900:1:1.2283
"		(3i) 62° 54	(3x) 500 50	1.6950 . 1 . 1.9900
		(20)02 01	(31) 780 50	1.6350 : 1 : 1.2283
IV.		11 - 53	100	Lower Drove
Manganite,	990 40			0.6455 : 1 : 1.184
Calamine,	1080 54			0.6170:1:1.2776
Haidingerite,	100°	118° 32		0.5945 : 1 : 1.1918
Brochantite,	104° 10	(21)114° 29'		0.6434 : 1 : 1.2838
Cotunnite,	990 46	1180 28	126° 44'	0.5953:1:1:1868
Mendipite,	1020 36		1000	x :1:12485
Jamesonite,	1010 20	1		x :1:1-2202

[•] Taking \$1 as 11, then the dimensions of Struvite are near those of Barytes.

TABLE III.

Angle of Vertical Prism, near 109° 28'.

	Prist I.	n.	1	Dome 14-			Dome	•			a :	Xee D:	o,	
I. Marcasite,	106°	5′		64°	52′		80°	20'	1.5	787	: 1	:	1.8	3287
Mispickel,	11110	807	ļ	59°				- 1						798
Aurotellurite,	110°	18′	(2i)	58°	52'	(2 %)	78°	84'	17	728	: 1	l :	1.4	1496

Table IV.

Angle of Vertical Prism, near 120° (1151°-120°).

	Prism I.	Dome 1 f	Dome 11.	Axes a:b:o,		
I. Sternbergite,	119° 80′	69° 88′	100° 2′	1·4879 : 1 : 1 <i>7</i> 147		
П.		220 404		1.1763 . 1 . 1 . 0		
Aragonite,	116° 10′			1.1571:1:1.6055		
Cerusite,				1.1852:1:1.6388		
Witherite,				1.2460:1:1.6808		
Bromlite,	118° 50′			1.2504:1:1.6920		
Stephanite,	115° 89′			1.0897:1:1.5844		
Nitre,	118° 50′	80° 16′		1.1861:1:1.692		
Chrysoberyl,	119° 46′	(32) 78° 54′	(3%) 109° 38′	1.2152:1:1.4239		
Discrasite,	119° 59'	81° 22′	1120 127	1.1633:1:17815		
Copper Glance,	119° 85′	(11) 83° 56′	114° 10′	1-1117:1:1-7176		
III.						
Herderite,	115° 58′	111° 42′	185° 58′	0·6783 : 1 : 1·59 71		
IV.						
Iolite,	119° 10′ 119°-120°	94°	121° 88′	0 9325 : 1 : 1 7038		

In Table I, of the Trimetric System, there are two sections; 1, having the domes near 109° 28', the angle of the regular octahedron; 2, having the domes near 120°, the angle of a dodecahedron.

In the first, the axes have approximately the ratio $1:\sqrt{2}:\sqrt{2}$; in the second, the ratio $1:\sqrt{3}:\sqrt{3}$. The former is almost exactly true of Andalusite, and the latter of Epsomite and Zinc Vitriol, (Goslarite).

For many of the species, the domes 27 and 28 might with as good reason be made the unit domes; and in that case, the summit angle would be near 70° 32′, (the supp.ement of 109° 28′)

which is the angle over the apex, in the regular octahedron. It is important to observe that the regular octahedron is represented by these united domes or the rectangular octahedron, and not by the rhombic octahedron of these trimetric species, and hence the axes of this rectangular octahedron (and not those of the rhombic, or the crystallographic axes) are homologous with those of the regular octahedron. Antimony Glance is an exception to this remark, and probably also Bournonite and Polycrase.

The relation of Topaz to Andalusite in form and formula, indicates the homœomorphism of oxygen and fluorine. At the same time the divergence in the angle of the domes shows the distinctive influence of fluorine; and the same is seen in the relations of Chondrodite and Chrysolite, or in the unlike angles of the three

types of Chondrodite alone.

In Table II, section I has the macrodome near 60° and the brachydome near 70° 32', both monometric angles, and these angles necessarily require that the vertical prism should be near 101° 34' in angle; and hence the frequency of angles near this. In Valentinite the brachydome has exactly the angle 70° 32', and the axes have nearly the typical value 1: $\sqrt{3}$: $\sqrt{2}$. Section II has the macrodome of 70° to 75° or near the brachydome of section I. Section III has the macrodome of 83° to 90°, or near the brachydome of section II, and 90° is nearly a mean between the macrodome and brachydome. In section IV, the macrodome is between 114° and 120° in angle, and 120° is nearly a mean between the two domes. The vertical axis in section III is two-thirds that of section I; and taking \$\frac{1}{2}\tilde{i}\$ as \$1\tilde{i}\$, the two groups would coalesce.

We hence perceive that in the change that takes place in a case

of dimorphism from the monometric to these trimetric forms, the characteristics of the monometric system are still to a consid-

erable extent retained.

In Table IV, Section I has the angle of the macrodome near 70° 32′; II, brachydome near 109° 28″; III, macrodome near 109° 28′; IV, brachydome near 120°.

By a change of position, making one or the other of the lateral axes the vertical axis, many of the species might be referred to Table IV. Although the cleavage is opposed to this change, it is of interest to view the species in this way, in order to apprehend more fully all the relations of the forms. Hausmann has thus compared the anhydrous sulphates and carbonates. The following Table (IV A) contains the species of the Tables I to III, which admit of this change; and in the first column, the particular dome is mentioned which is here made the vertical prism.

In the following and preceding tables, the only changes from the fundamental forms adopted by other authors,* are such as de-

^{*} The fundamental forms adopted through the Descriptive part of this work, are made to correspond with these tables, when there was no doubt as to the propriety of it; in other cases they stand as given by the best authors.

pend on the simple ratios 1:2 and 2:3. The general principle is everywhere illustrated, that species may be homeomorphous and still vary by the simple ratios 1:2 or 2:3; a fact which has been illustrated by reference to augite and hornblende, and is also exemplified in the case of Andalusite, Topaz and Staurotide, and in other species.*

TABLE IV. A.

		Prism I	Dome 11	Dome 1%
From Table I.				
Chrysolite,	11	115° 86′	60° 48′	850 57'
Do	īř	1190 12'	64° 24'	940 8
Triphyline,	lŧ	118° 27'	58° 5'	860
Do	11	1210 55'	61° 88'	940
Epeomite,	11	1200 4'	59° 27'	890 261
Do. '	11	120° 83′	59° 56'	90° 84′
Disspore,	11	115° 16′	61° 18′	860 8
Do	11	118° 42′	64° 44'	980 281
Göthite,	11	113° 6′	62° 80'	850 8/
Do	11	117° 30′	66° 54'	940 52/
Polianite,	11	115° 26′	62°	870 87
Do	11	118°	64° 84′	920 52
Euchroite,	17	117° 20′	60° 47′	870 52'
Do	11	119° 18′	62° 40′	920 8'
Topaz,	11	(1) 115° 22'	61° 50′	860 521
_ Do	11	(1) 118° 10'	64° 38′	980 8/
Bournonite,	16	(1) 115°	61° 46′	86° 20′
Do	11	(1) 118° 14'	65°	98° 40'
From Table II.				
Valentinite,	11	120° 56'	770 24	109° 28′
Barytes,	11	116° 20′	78° 20'	1050 24'
Anglesite,	11	1170 18'	760 22'	1040 81'
Leadhillite,	11	119° 40′	76° 44′ ~	107 26
Celestine,	11	1170 21'	75° 58′	1040 8'
Anhydrite,	11	118° 85′	770 4'	1070 22'
Tantalite,	11	115° 58′	78° 28′	105° 2'
Mascagnine,	11	1140 8'	72° 20′	960 52'
Sulphur,	18	(1) 114° 42'	78° 2′	108° 20'
Manganite,	11	114° 19'	57° 10′	80° 20'
Calamine,	1₹	116° 89'	51° 84'	660 6'
Haidingerite,	11	1180 82'	580 2'	80°
Brochantite,	11	114° 29′	58° 19′	75° 50′
Cotunnite,	11	118° 28′	58° 16′	80° 14'
From Table III.				
Marcasite,	11	1150 8	780 55	990 40
Mispickel,	18	1200 45'	68° 7′	990 2'
Ausotellurite	11	1210 8	69° 12′	1010 26'

The angle of Andalusite is 90° 44'; of Staurotide 129° 20'; while Topas gives two prisms, one of 86° 52' and 93° 8', and one of 124° 19'. The relation of the forms of Andalusite and Staurotide is as 1:2, (for the axes b, e); while the two prisms in Topas have the same relation, and either, with almost equal reason, might be made the fundamental prism. The prism 6' of Staurotide is 93° 8' in angle, as

4. Monoclinic System.—Triclinic System.

Among the minerals of the Monoclinic system, several prominent homeomorphous groups may be pointed out.

1. Pyroxene Group.-I: I=85° to 88°.

Borax,	Ña B³+10Ĥ.	Hornblende,	R'Si'=R'Si'.
Glauber Salt,	Na S+10H.	Aemite,	(Ř+Ħ)Ši°=(ذ, Ħ)Ši°. (ذ, Ħ)Ši°+2Ĥ.
Hydromagnesite,	Mg ⁴ C ² +4H. R ⁸ Si ² .	Laumontite,	
Pyroxene,	R Si2.	Leonhardite ? se	
Rhodonite,	Mnº Siº.	Pectolite,	(R³, ₩)Si 4+Aq.
Wollastonite,	Ca ³ Si ² .	Caporcianite !	
Spodumene,	(R3, 11) Si2.	Okenite i see vo	l. ii, p. 306.

2. Monazite Group.-I: I=91-9510

Monazite, Crocoisite,	R.P. Pb Ör.	Lazulite. Wagnerite.	- 10
	3. Euclase Group.	-I: I=nearly 115	0,
Euclase, Sphene, Zoisite.	(茶l, ∄e) Ši [‡] . (Ča+Ti)Ši [‡] =(雅)Ši [‡]	Datholite, Barytocalcite,	(ذ, Ħ, ذ) Ší*. Ř Č.

4. Heulandite Group.

Heulandite,	(R+\(\frac{1}{4}\)Si*+5H.	Stilbite,	(R+Al)Si*+6H Ca S+2H.
Brewsterite.	100 - 100	f Gypsum,	Oa 5+211.

Other groups are mentioned in the Descriptive part of this work. In the Triclinic System, the feldspars (exclusive of orthoclase) make a natural group, having I:I' nearly 120°, and characterized by a basal and clinodiagonal cleavage. Orthoclase is properly of the same homeomorphous group, although Monoclinic (or more probably Diclinic.)

In the discovery of the first facts in Isomorphism, the grand principle was announced by Mitscherlich, that analogous compounds of related elements were alike in crystallization, and the converse proposition was deduced, that similarity of form was evidence of similar or analogous composition. Dr. H. Kopp, in pursuing this subject, observed that such homeomorphous compounds were closely similar in atomic volume, and he obtained the following results for the carbonates:

in Table I, and this although not an observed prism, may be made the fundamental prism, as the mere frequency of occurrence of a form (that having the angle 129° 20' in Staurotide) is not necessarily proof of its being the fundamental form. But the plains of twin composition have complex expressions with either of these fundamental forms, and become simple (1, and 1s) only when the larger lateral axis is made two-thirds the usual length, in which case the prism is 109° 20'.

	Atomic volume.	Axis a.	Angle,
Carbonate of zinc,	175.88	0.807	107° 40′
Carbonate of magnesia,	181.25	0.812	107° 25'
Mesitine,	186.26	0.815	107° 14'
Carbonate of iron,	188.50	0.819	107°
Carbonate of manganese,	202:29	0.822	106° 51'
Dolomite,	202.36	0.833	106° 15'
Calcite,	231.20	0.854	105° 05'

This table, which contains also the length of the vertical axis, (axis a), and the angle of the rhombohedron of each of these minerals, illustrates the interesting principle which he next deduces, that the axis increases, in this series, or the angle diminishes, as

the atomic volume increases.

Subsequent investigation showed that there may be resemblances of form among unrelated compounds. A simple multiple relation in the atomic volume was to some extent detected in such species, and this fact was regarded as the true explanation of the identity of forms. The author obtained simpler results by reducing the aggregate atomic volume of the compounds to a unit value by dividing by the number of atoms in the compound.* The following are examples of the atomic volumes thus obtained.

Borax 46:38, Pyroxene 46:1—48:8, Glauber Salt 49:6, Spodumene 43:44, Horn-blende 48:2—48:6, Acmite 48:33.

- Scapolite 51-6, Meionite 55-65, Dipyre 55-21.
 Epidote 45-28, Orthite of the Urul 48-025, Orthite of Hitteroe 48-43.
 Calcite 46-24, Dolomite 40-47, Spathic iron 37-70, Carbonate of zinc 35-07,
- Chrysoberyl, 37:15. 5. Quartz 54, Chabazite 51 5.
- Andalusite 41.94, Topaz 42.6.
 Feldspar family:—1. Monoclinic: Orthoclase 60.4; 2, Triclinic: Albite 55.67,
 Andesite 55, Labradorite 53.0, Oligoclase 54.64, Anorthite 52.85; 3. Monometric: Leucite 63'08.

The serial relation of the rhombohedral and trimetric carbonates

was pointed out in the same paper, as follows:

The upper range of figures pertain to the rhombohedral species, and the lower to the trimetric. Calcite is the only one certainly known to be dimorphous.

2n0 107° 40'	MgÖ 107° 25′	FeÖ 107° 0'	MnÖ 106° 51'	ČaČ 105° 15'	Рьё	ŠrÖ	BaÖ
35.07	36.25	87-70	40.46	46.24 48 116° 10′	50.6 117° 13′	50·54 117° 19'	57·3 118° 30′

These, in each series, are acknowledged isomorphs, according to

the old principle. Yet the range of numbers is wide.

From the tables on the preceding pages the subject of Isomorphism has a still wider extension. Some modification of earlier views are required, as was long since urged by von Kobell (1832.) It is still true that similarity or analogy of composition may be exhibited in similarity of crystallization; and when forms are similar and composition is analogous, homeomorphism is evidence of a homeomorphism in the constituents of the compound. Thus the similarity of form between Tantalite and Heavy spar is evidence that tantalic and sulphuric acids are homeomorphous.

But it is also evident that similarity of form may be independent of relations in composition, and result from a certain mathematical dependence of the prismatic forms on the monometric. The elements are mostly monometric in one state or another; and as the prismatic forms are derived from these elements, and often have a monometric form as one of their dimorphous states, the retained impress of the monometric forms, found in the angles of the domes, determines the prismatic angles, and leads often to identity of form when there is no analogy either in the nature of the ele-

ments or their proportions in the compound.

Among the striking cases of homeomorphism with unlike constitution, are the following: one group includes Sulphur, the Anhydrous sulphates RS, Marcasite Fe S², Descloizite Pb²v. Another includes Childrenite a phosphate, Epistilbite a silicate, Orpiment As² S², Mispickel Fe (S, As)², Aurotellurite (Ag, Au) Te². Another contains Tourmaline a silicate, Nitratine a nitrate, Pyrargyrite a sulphuret, the Anhydrous Carbonates, Iodic silver. Again, along with arsenic and some other metals, there are protoxyds, as protoxyd of zinc, many peroxyds, (as of iron, &c.) and Willemite, a silicate of zinc. The tables are made up of similar examples.

In many cases of homocomorphous compounds which are apparently dissimilar in composition, a resemblance may hereafter be detected when the true relations of the constituents are better

understood.

Hermann has discussed the varying composition of Scapolite, Epidote, Tourmaline, and other species, and explains it by supposing the mineral to include two silicates which are mutually replaceable. Thus for the Scapolite group, these silicates or "heteromerous molecules" are

a, R'Si+2RSi,-b, RSi+RSi,

Meionite=a; Edingtonite, which he refers to the group,=a+12 it; Wernerite, one variety a+b; another variety a+2b; a third a+6b; a fourth, a+12b; a fifth,=b. This mode of explaining the facts is but partial in its bearing, and tends to give increased complexity to the subject, by multiplying points demanding explanation.

Scheerer endeavors to explain the relations of various magnesian species, hydrous and anhydrous, on the hypothesis that three parts or atoms of water may replace one of magnesia, and that three of alumina may replace two of silica. He thus reduces Tale, Steatite, and certain other magnesian silicates, to the hornblende type; and another set of related species to the augite type; and still a third group to the type RSi. But the so-called species referred to are for the most part uncrystallized, and therefore not well

adapted to settle questions in this department.

Others have met some of the difficulties by the view that protoxyds and peroxyds may replace one another, in the proportion of the oxygen they contain. It is found in Epidote and Idocrase, that while the protoxyds and peroxyds vary in their oxygen proportions, the ratio of the sum of the two to the silica is constant. Now a fact that is thus a constant one for a species is a fundamental fact of the profoundest signification; and there is hence the best reason to accept of the oxygen ratio between the oxygen of all the bases (protoxyds and peroxyds) and the silica as the essential characteristic of the species. The oxygen ratio of the protoxyds and peroxyds may still be in general a simple ratio, and this is probably true for the species mentioned, the two prevalent ratios being 1:2 and 3:2.*

This relation may be expressed in the formula in the manner already explained, (p. 189), making 3R replace R; thus the general formula (1), and two special formulas (2), (3), of idocrase, are,-

(1.) (R³, H) Si, (2.) (1R³+1R) Si, (3.) (3R3+3R) Si.

In Tourmaline, as Rammelsberg has shown, there are five varieties, differing widely in the oxygen ratios of the protoxyds, peroxyds, boracic acid, and silica, and varying nearly indefinitely for the boracic acid,—the ratios for the protoxyds, peroxyds and boracic acid lying between 1:3:1 and 1:14:3. Yet there is the constant ratio 4:3 between the oxygen of all the oxyds, including the boracic acid, and that of the silica. This ratio of 4: 3 is consequently the characteristic of the species. Disregarding this fact, and making the boracic acid replace silica, we obtain no common type of formula for the species; Rammelsberg's formulas being

(1.) R°Si°+3ESi, (2.) R°Si°+4ESi, (3.) R°Si°+6ESi, (4.) RSi+3ESi, (5.) RSi+4RSi.

But recognizing the true bearing of this ratio, we are compelled to place the boracic acid with the bases, and make it, on the principle stated, replace the other oxyds. The general formula is then

(R1, H, B) Sit,

in which R. H. B vary between 1:3:1 and 1:14:3.

Thus the mode of making the oxyds replace one another in the proportion of the oxygen they contain appears to exhibit the true simplicity of nature.

^{*}The whole oxygen ratio for R, R, Si in Idocrase, is 1:1:2, for one variety, and 1: \(\frac{1}{2} : 1\) (or 3:2:5) for the other. Adding the first two terms, we have 1:1 for the ratio of the oxygen of the bases and silica in each. \(\frac{1}{2} \) See further under Tourmaline, vol. ii, p. 271.

The correctness of this application of the principle alluded to, is proved by the remarkable isodimorphism of Tourmaline and Calcite. R:R in these species is respectively 103° and 105°. Now Calcite and Barytocalcite are dimorphous, and related carbonates. Moreover Barytocalcite and Euclase are quite nearly related in form.* Therefore Tourmaline and Euclase are dimorphous. Moreover, since the accepted formula of Euclase is (#) Sit, Tourmaline and Euclase have on the ground taken, and no other, analogous formulas.

Another example illustrating the fact that R³ and R replace one another, is afforded by Spodumene and Augite. The crystallization of these species is the same, and the resemblance is so close, that G. Rose, in his recent classification, places them together, although this does not correspond with the principles of his system. The augite oxygen ratio for the protoxyds and silica is 1:2. Spodumene contains peroxyds, with the oxygen ratio 1:4:10. Adding the 1 and 4, we have 1+4:10 or 1:2, the true augite ratio, and thus the species are reduced to the common type. The formulas of the two species are therefore

Augite, R'Si'; Spodumene, (R',R')Si', or exactly (\$\frac{1}{5}R' + \frac{1}{5}R')Si', the oxygen ratio of the oxyds in Spodumene being 1: 4.

Again, this principle brings together the homosomorphous species Zircon and Meionite, in which the ratio is 1:1; so also Willemite and Phenacite, which, with the same ratio 1:1, are nearly alike in rhombohedral form and angle; so also Danburite and Ax-

inite, both of which are triclinic.

The fact that the protoxyds and peroxyds are thus mutually replaceable is further shown by the crystallization of the oxyds themselves. The protoxyd of zinc is well known to be isomorphous, in many species with the protoxyd bases; yet it crystallizes in hexagonal forms, with the angles of alumina and other peroxyds. And hence it should also be capable of replacing peroxyds, and not only should this be true of protoxyd of zinc, but also of the other protoxyds by which zinc is replaceable. The protoxyds may exist apparently in two states, in one of which they replace protoxyds, in the other peroxyds. The peroxyd of iron is also supposed to crystallize in octahedrons in martite, and if this be sustained, the argument is double-headed; for we then not only have protoxyds with the hexagonal form of peroxyds, but peroxyds with the monometric form of protoxyds. The principle is sustained again by another well-known fact, that the peroxyds and protoxyds combine together and form monometric species, as in magnetite, spinel, etc.+

^{*} See paper by the author, Am. J. Sei. [2], xvii, p. 216.

† There are many examples showing that the rhombohedron of 84° to 88°, and a monometric form are related as the two forms of a dimorph, and that there is thus a mutual dependence. Arsenic, Antimony, Palladium, present both forms, proving

Many deductions bearing on the principles of Chemistry might be deduced from the facts that have been presented,* and large citations might be made from various authors. But the discussion has proceeded far enough to exhibit the bearing of the subject on the classification of minerals. The arrangement which is explained beyond, is a systematic view of the homeomorphous groups of species under the several grand divisions; and the parallel groups in the same division, which are analogous in composition, are examples of dimorphism-or, to use the more general term, of pleo-

morphism.

Cause of Dimorphism.—The occurrence of one of two forms of a dimorphous substance rather than the other, has been shown by Mitscherlich, Rose, and others, to result in many instances from the different temperatures attending crystallization. When a right rhombic prism of sulphate of zinc is heated to 126° F., certain points in its surface become opaque, and from these points bunches of crystals shoot forth, in the interior of the specimen; and in a short time the whole is converted into an aggregate of these crystals diverging from several centres on the surface of the original crystal. The small crystals, thus formed at 126° F., are oblique rhombic prisms; and the same form may be obtained by evaporating a solution, at this temperature, or above it. Sulphur crystallizes from fusion in oblique rhombic prisms, while the common form obtained by evaporation is a rhombic octahedron. Rose has obtained crystals of aragonite by evaporating a solution of carbonate of lime to dryness by means of a water bath, and crystals of calc spar by permitting the solution to evaporate in an open vessel at the ordinary temperature. The crystals of aragonite were minute six-sided prisms and double six-sided pyramids. They change to rhombohedrons of calc spar if left moist; but if washed and dried at once, they remain permanent. By exposing aragonite to a low temperature, the crystal falls to pieces, in consequence of the change to calc spar which takes place; or if the prisms hold together, they consist, after the change, of an aggregate of minute particles of calc spar.† Artificial aragonite has been observed in the interior of a copper boiler used to supply hot water for household purposes at Port Eliot, Cornwall. The crystals were minute six-sided prisms, and were at-

this correlation. The oxyds come under this system, the peroxyds presenting usually this rhombohedron, but sometimes its correlate; the protoxyds usually the monometric form, but sometimes the rhombohedral.

^{*} We call attention to one point, the close homeomorphous relations of Sulphur, prismatic sulphuret of iron, (Marcasite Fe S'), and the anhydrous sulphates, table 2, p. 200; and of Orpiment As' S', and mispickel Fe, (S, As). In the former group, the sway of the Sulphur is seen; in the latter, that of the Arsenic. The same dominant sulphur influence is seen in the Sulphato-carbonates, Susannite having the form of Dreelite, (a sulphate), and Leadhillite the form nearly of Anglesite.

† Rose, Lond. and Ed. Phil. Mag. [3], xii, 465.

tached at base to the surface supporting them.* Breithaupt has described a carbonate of lime from a greenstone rock near Zwickau, which consists of alternations of layers of aragonite and calc spar; and he suggests that one may be a winter, the other a

summer deposit.+

Temperature appears to be a prominent cause. Yet it is probable that the nature of the solvent, or the presence of some accidental ingredient in the solution, may have some effect in changing the molecules; but in general the only effect of these causes is to produce secondary planes. Rose did not succeed in obtaining aragonite crystals by mixing a strontian salt with the solution of lime, and shows that the strontia in arragonite does not alone produce the rhombic form.

The presence of one base in place of another isomorphous with it, often decides the form, as with the soda in albite and potash in orthoclase, the latter causing a monoclinic form, the former

a triclinic in a compound otherwise identically the same.

II. CHEMICAL EXAMINATION OF MINERALS.

The chemical properties of minerals are ascertained (1) by the action of acids and other re-agents; 2, by heat, concentrated by means of the blowpipe, assisted by various chemical re-agents; 3, by chemical analysis. This subject, especially the last division of it, falls into the department of chemistry. Only the more ordinary chemical and blowpipe tests are here mentioned.

I. CHEMICAL TESTS.

The simplest use of acids consists in the detection of a volatile ingredient expelled by them. A carbonate is thus distinguished. The acids ordinarily employed are the sulphuric, muriatic, and nitric, and they are commonly diluted with one-half water. Carbonate of lime, when dropped into either of these acids diluted, gives off bubbles of gas, an effect called effervescence. Some carbonates require the addition of heat. Before making this trial it should be observed that the mineral is quite pure, as a carbonate in seams or fissures might give a fallacious result. Another gas of a pungent odor is obtained when common salt is subjected to the action of sulphuric acid; and another of acrid character when copper and some other metals are acted on by nitric acid.

In such examinations with acids it is important to observe the odor of the escaping gas—whether very suffocating and disagreea-

† Pogg. li, 506, 1840.

^{*} Lond. and Ed. Phil. Mag. [3], xii, 330, 1841.

ble, or merely pungent; also, its color, and the color of the solution. In many instances, solution is obtained without effervescence; and often a mineral is but partly soluble, and the insoluble part is thrown down in the state of a powder; frequently, it may be insoluble in cold, but soluble in hot acid. The fumes given off will sometimes redden paper tinged blue with litmus or cabbage liquor, owing to their acid character; others will blacken paper that is charged with acetate of lead, because of the sulphur they contain. Others, again, will discharge the color of brazilwood in paper, a property of hydrofluoric acid, which acid, when driven off from a mineral by strong sulphuric acid, will also corrode glass placed over it.

Another effect of the action of acids is the formation of a jelly. To accomplish this, the finely pulverized mineral is thrown into a strong acid, and a gentle heat applied. After a short time, as the solution cools, it gelatinizes; or in other cases, partial evaporation is necessary before the jelly appears. In a few instances, a jelly may be formed with cold acid. By heating the mineral, this property is often destroyed; but occasionally it takes place, with equal facility, before and after heating, and sometimes not at all until after heating. The minerals that gelatinize in this manner are silicates; it arises from the separation of the silica in a gelatin-

The following are some of the more common chemical re-actions: a. Carbonates. - Effervesce with dilute muriatic acid, yielding a colorless inodorous gas, which gives a white precipitate when passed into lime water. The fumes slightly redden moist littuus paper and heat restores the blue color.

b. Sulphates.-No effervescence with acids. When in solution, they give with barytic water a white precipitate not soluble in

water, or the muriatic, nitric, or sulphuric acids.

c. Nitrates.—With strong sulphuric acid give white corrosive vapors of nitric acid. With heated muriatic acid yield an acid

that dissolves gold, becoming at the same time yellow.

d. Phosphates.—Well dried and heated in a glass tube with potassium, give a phosphuret, which in water produces phosphuretted hydrogen, a gas which inflames on coming into the atmosphere, and has a garlic odor. The phosphates generally dissolve unchanged in muriatic and nitric acids. In sulphuric acid they are for the most part decomposed-forming double salts. nitrate of silver the soluble phosphates, or neutral nitric solutions of the insoluble, produce a characteristic yellow precipitate of phosphate of silver. When molybdate of ammonia is added to a solution of any phosphate, and then muriatic or nitric acid in excess, a yellow color soon appears, and after a while a yellow precipitate is thrown down.

e. Fluorids .- If a pulverized fluorid be subjected to the action of strong sulphuric acid, in a platinum crucible, and heat be applied, fumes will be given off which will corrode a plate of glass placed over the crucible.

f. Chlorids.—In solution afford with nitrate or silver a white curdy precipitate, which darkens and becomes violet on exposure, is not soluble in water, hardly so in acids, and wholly in ammonia. Any chlorid heated in sulphuric acid yields muriatic acid, which acts as just stated with nitrate of silver; or heated with oxyd of

manganese, affords chlorine.

g. Silicates.—Fuse in a silver crucible with three or four times their weight of caustic potassa or soda, yielding a silicate soluble in water, which gives with an acid a precipitate (silica) that dries to a white, insoluble powder, harsh to the touch. Many silicates gelatinize with acids, as already stated. They dissolve with effervescence in strong fluohydric acid.

h. Borates.—If a borate in powder is heated with sulphuric acid, and alcohol is then added, the flame will have a green color,

especially on the edges.

i. Salts of Lime.—In solution, even if dilute, give with oxalic acid or oxalate of ammonia a white precipitate insoluble in water or acetic acid, but very soluble in either of the stronger acids.

k. Compounds of Iron.

Precipitate with potash greenish white, becoming green or soda,

Precipitate with ferrocy anid of potassium,

Precipitate with nutgalls or tannic acid,

Protoxyd Salts.

Peroxyd Compounds of Manganese.—The oxyds heated with muriatic acid give chlorine. Heated with potash or its nitrate, the salts give manganate of potassa, which affords a green color with water, and a rose tint with dilute acids that is destroyed by sulphurous acid or organic matters.

m. Compounds of Copper.—Mostly soluble in nitric acid. Metallic iron in the solution becomes coated with metallic copper; potash or soda produces a blue precipitate, which becomes black on boiling; ammonia a green, which is soluble in an excess of am-

monia and becomes fine blue.

n. Compounds of Zinc.—The sulphate gives a white precipitate with potash, soluble in an excess of this re-agent; no precipitate with sulphuretted hydrogen. Acetate of zinc affords an abundant

white precipitate with sulphuretted hydrogen.

o. Compounds of Lead.—Dissolved in nitric acid, give with sulphuretted hydrogen a black precipitate, insoluble in excess; with iodid of potassium, or chromate of potash, a yellow precipitate. The acetate yields with metallic zinc, metallic lead in shining plates or scales. With a slip of zinc neutral solutions of lead precipitate metallic lead.

p. Compounds of Tin.—Dissolved in muriatic acid, form a chlorid, which with chlorid of gold give a purple color, or if strong,

a brown precipitate.

q. Compounds of Mercury.—The protosalts in solution give with potash a black precipitate insoluble in excess; with sulphuretted hydrogen a black insoluble precipitate; with metallic copper, they yield metallic mercury, which is dissipated by heat. With muriatic acid afford a white precipitate or calomel.

r. Compounds of Silver.—Dissolved in nitric acid, a chlorid or muriatic acid throws down a dense, white, curdy chlorid of silver, which blackens on exposure, and is soluble in ammonia. With

metallic copper it affords metallic silver.

s. Gold.—Dissolves in nitromuriatic acid, (aqua regia), but not in either of the acids unmixed. The solution gives, with protochlorid of tin, a purple precipitate, and with protoculphate of iron,

metallic gold.

t. Plainum.—Dissolves in nitromuriatic acid, and not in either of the acids unmixed; the solution gives with muriate of ammonia a yellow precipitate, which heated in a platinum crucible gives metallic platinum in powder.


II. ACTION WITH THE BLOWPIPE.

The first of the following figures represents the simplest kind of blowpipe. It is merely a bent, tapering tube of brass, from seven to ten inches long, with a minute aperture at its smaller end. It is used to concentrate to a point the flame of a lamp or candle; and this is done by blowing through it while the smaller end is just within the flame.

After blowing awhile, the moisture of the breath often condenses in the tube; and to receive this moisture, and prevent its passing

out at the beak, the chamber at o (see f. 258, 259) is usually added. The airchamber in f. 259 is a cylinder, into which the tube abc is screwed at c, and the smaller piece, def, at d. The point of, screws off, and is made of platinum in order that it may be cleaned when necessary, by immersion in an acid.

When the blowpipe is made of brass, it is usual to have an ivory mouthpiece, as it is more agreeable in the mouth. Silver is the best material; and the point, at all events, should be of platinum. Wollaston contrived a convenient pocket instrument on the plan of a common pencil case. The instrument represented in f. 259 has a screw



at b. On unscrewing it, the part bc may be inserted at a into the part ab, and the two screwed together again. In this way it is as portable as Wollaston's, and has the advantage of being more easily made tight with the screw, and is less liable to get out of order.

Operations with the blowpipe often require an unintermitted heat for a considerable length of time, and always longer than a single breath of the operator. It is therefore requisite that breathing and blowing should go on together. This may be difficult at first, but the necessary skill or tact is soon acquired. Let the learner attempt first to breathe through his nostrils with his cheeks inflated and mouth closed. This accomplished, if the blowpipe is now put to the mouth, he will find no difficulty in continuing his respirations while the muscles of the inflated cheeks are throwing their contained air through the blowpipe. When the air is nearly exhausted, the mouth may again be filled through the nose without intermitting the process of blowing. The chamber at o has been recently made of india rubber, with valves, which does away with all the difficulty.

The blowpipe flame consists of two cones: an inner of a blue color, and an outer, yellow. The heat is most intense just beyond the extremity of the blue flame. The inner flame is called the reduction flame, and the outer the oxydation flame. A mineral reduced to the metallic state by the inner, may often be oxydized, or combined with oxygen, in the outer flame, where it is in contact with the atmosphere. For oxydation, the beak of the blowpipe should have a large aperture, and the wick of the lamp should also be large: the heat may be that of incipient redness.

The best flame is that of a lamp with a large wick, fed by olive oil. A common candle with a large wick will answer for most of the purposes of the mineralogist, and is most conveniently carried about. When used, the wick should be bent in the direction of the flame.

To support the mineral in the flame, either charcoal or platinum forceps or wire may be used. The charcoal should be well burnt but firm; that from pine wood is the best, as it burns with least ashes. The reaction of the carbon of the coal aids in reducing or decomposing many mineral species.

A convenient kind of forceps is represented in the annexed figure.



It is made of steel, with platinum points, ab, and pins at p, p, for opening the forceps. The mineral kyanite, and also mica, are sometimes used for a support when more convenient means are not at hand.

To test the presence of water or a volatile ingredient, the mineral may be supported near one end of a test tube, which may be three or four inches long, and the bore little larger than a quill. The flame is concentrated on the exterior of the tube beneath the assay, and the volatilized substance usually condenses in the upper part of the tube. By inserting into the upper end of the tube a strip of litmus or other test paper, it is ascertained whether the fumes are acid or not, the color of the paper, if so, changing to red.

The specimen to be subjected to the flame of the blowpipe should be a very small thin fragment, especially when the mineral is not very fusible; for fusion is often thus obtained, when impossible with a fragment without thin edges. A fragment as large as a pea might afford a score of pieces, large enough for a blow-

pipe trial.

Many minerals remain unaltered before the blowpipe, unless some substance be added to aid in the fusion or reduction. These substances are called fluxes. Those in common use are borax, carbonate of soda, and salt of phosphorus or microcosmic salt.* Care should be taken to obtain the fluxes pure, and for this purpose it is well to dissolve and recrystallize the borax; and the soda should be tested for sulphuric acid, as any adulteration with this acid will give the glass obtained with silica, a brown or reddish color. These fluxes should be powdered and added to the mineral, and the whole assay should not exceed the size of a small pea. One fourth this size is better than larger. The soda should be added in small successive doses; this flux is often absorbed by the charcoal, but generally reappears when the heat is sufficiently raised.

Besides the fluxes mentioned, other tests are sometimes used, of

which the following are the most important.

a. Nitrate of cobalt in solution, for distinguishing alumina and magnesia. This solution should be pure, free from alkali and slightly concentrated. Berzelius recommends having a bit of platinum wire in the cork stopper, in order to take out a drop upon it when required for use.

b. Boracic acid and iron wire, used in testing for phosphoric

acid.

c. Tin-foil, for using with certain peroxyds of metals to reduce them to protoxyds. The assay, previously heated in the reducing flame, should be touched with the end of the tin-foil; a very minute quantity of a metallic oxyd is often thus detected.

d. Gypsum and fluor, used as tests of one another. When two parts of the former rendered anhydrous by heating, and one of the

This salt, a phosphate of soda and ammonia, may be made by dissolving sixteen parts of sal-ammoniac in a small quantity of boiling water, and afterwards adding 100 parts of crystallized phosphate of soda, boiling gently the whole, and then setting it away to cool. The salt of phosphorus is deposited in small crystals. If the heat be too great during ebullition, decomposition takes place.

latter, are mingled and heated, they fuse to a clear glass, which is a milk-white enamel on cooling. The globule from fluor and heavy spar is transparent when cold; and that with sulphate of

strontian is more or less frothy.

c. Saltpetre is employed in discovering manganese, bringing out the characteristic amethystine color when the quantity of this metal is too small to color glass without this reagent. The heated globule is touched with the point of a crystal, just at the moment of suspending the blast. The melted mass swells, foams, and either becomes immediately colored, or is so soon, upon cooling.

f. Anhydrous bisulphate of potash, used for detecting lithia. It is kept in a coarse powder in a phial well secured from moist-

ure.

g. Oxalate of nickel, or nitrate of nickel, used to detect potash. The nickel must be quite free from cobalt; it may be tested by treating it with borax, with which it should give a brown, not a blue head.

h. Nitroprussid of sodium,* for detecting sulphur.

The effects of the blowpipe are various. Some minerals are volatilized wholly or in part, others fuse at a low temperature; while others melt only on the edges, (then called subfusible), or are wholly infusible. Kobell has proposed the following scale for denoting in figures the degree of fusibility: 1. Gray antimony.—2. Natrolite.—3. Cinnamon Stone, (var. of garnet).—4. Black Hornblende.—5. Feldspar.—6. Chondrodite. The fusibility, when equal to that of natrolite, is designated by 2; or if like hornblende, by 4, and so on.

The fluxes are also often required in obtaining the pure metals from the metallic ores.

The following are some of the reactions with the fluxes:

1. Silica, Silicates.—Silica dissolves with effervescence in soda. The silicates are decomposed by salt of phosphorus, and the silica is set free, often remaining as a silica skeleton in the globule. Columbic acid, on the contrary, forms a clear glass with salt of phosphorus.

2. Potassa, Soda, Lithia.—Soda gives an intensely yellow color to the flame, even when in combination: yet this color may be otherwise produced. Potash salts often give a violet tinge, and a lithia salt a red color to the flame; but the presence of soda vi-

It is readily obtained by treating two parts of the powdered ferrocyanid of sodium with five parts of common nitric acid previously diluted with its own volume of water. The solution when the escape of gas has ceased, is heated in a water bath, until a salt of the protoxyd of iron gives a slate colored (and no longer a blue) precipitate. It is then cooled, when a precipitate forms; the liquid is next filtered and neutralized with carbonate of soda, when a green or brown precipitate goes flown leaving it ruby colored; this liquid is poured off and evaporated, a crystallization takes place of nitrate of potash and soda, together with the new salt, the last in crystals of a splendid ruby-red color.

tiates the test by communicating its own color. A glass of borax containing potash becomes blue when a little oxalate of nickel is carefully added, and one of soda, brown; and this holds good for the potash salt, although soda be present. A lithia salt fused on platinum foil, if soda be present, produces a yellow stain; but this stain is produced also by other reagents. If a lithia mineral be mixed with one part of fluor finely pulverized, and one and a half parts of bisulphate of potash, the flame is red; if no lithia is present, it is faint violet.

3. Lime.—Lime and lime salts give a brilliant white light. They sometimes tinge the flame reddish, but more faint than car-

bonate of strontia.

4. Magnesia.—Magnesia and many magnesian silicates afford a clear rose-red color with cobalt solution, after a long heat. A fragment after heating, should be moistened with the solution, and then heated again; the color deepens on cooling. Magnesia is

not acted on by soda.

5. Alumina.—If a fragment of alumina, or if an aluminous silicate, after heating to redness, be moistened by cobalt solution and again heated, but not to fusion, it assumes a fine blue color. The harder species should be finely pulverized. The test is sure except when oxyds of certain metals are present; and also when saltpeter is present, since it gives a blue color with silica and zirconia, and in some other cases.

6. Arsenic and Arsenical Compounds.—Give off usually arsenical fumes having an alliaceous odor when heated on charcoal or with soda. With many of the compounds heated in a tube, white arsenic or orpiment is condensed; and with charcoal metallic

arsenic is obtained on the tube in crystals.

7. Selenium and Seleniurets.—Give a horse-radish odor in the outer flame on charcoal; yield in a tube a sublimate in the form

of a dark red powder.

8. Sulphurets.—A glass made of soda and silica becomes red or orange yellow when sulphur is present. Heated on charcoal with soda and then adding a drop of water, the sulphurets yield sulphuretted hydrogen, which blackens silver foil or test paper containing acetate of lead. Heated in a glass tube closed below, with litmus paper above, they redden the paper and yield often a

sulphureous odor.

A more delicate test for sulphur is the nitroprussid of sodium, as published by Prof. J. W. Bailey. Heat by blowpipe any sulphuret or sulphate (or anything containing sulphur) upon charcoal with carbonate of soda, put the fused mass into a watch glass with a drop of water, and add a particle not larger than a pin's head of the nitroprussid of soda; there will be a magnificent purple at once. If this test for sulphur is tried upon parings of nails, hair, albumen, &c., the carbonate of soda should be mixed with a little starch, which appears to prevent the loss of any of

the sulphur by oxydation. On winding up a piece of hair four inches long by coiling it around one point of a platinum support, moistening it and dipping it into the mixture of carbonate of soda with starch, and then heating by the blowpipe, the fused mass will give with the nitroprussid an unmistakable action indicative of sulphur. By careful management perfectly satisfactory results may be obtained from a piece of hair less than an inch long.

9. Tellurium and Tellurets.—Give fumes but no odor. Heated on charcoal, the oxyd covers the charcoal with a brownish yellow coating, and the inner flame directed upon this coating is tinged bright green. In a tube the fumes rise and coat the glass, and when heated the coating melts into drops, which are but slowly

driven off by the continued heat.

10. Chromium.—Oxyd of chromium with borax gives an emerald green color; but on platinum wire in the outer flame the color nearly disappears. Chromic iron gives the same color, and it is

brightened on the addition of tin-foil.

11. Antimony.—The ores of antimony afford fumes usually white on charcoal, which are inodorous. The oxyds form with soda on the platinum wire, a clear colorless bead, which becomes white on cooling; on charcoal they are reduced. In an open tube, antimony gives white fumes, which coat the glass, and vaporize easily on a new application of the heat, without fusion to globules.

12. Bismuth.—Fuses and gives off inodorous fumes. On charcoal it becomes surrounded with a dark brown oxyd, which is pale yellow on cooling; the flame directed on the coating is not tinged;

ultimately the metal is wholly vaporized.

13. Titanium.—Titanic acid with borax yields a colorless glass, which becomes milk-white on flaming, if not without. In the inner flame the glass with little of the assay is first yellow and afterwards amethystine and transparent. With more assay on charcoal in the inner flame becomes dark blue or nearly black on cooling; but it is pale blue afterwards on flaming. With salt of phosphorus, it forms in the outer flame a clear colorless glass; in the inner flame, a red or violet-blue glass, when cold, especially if tin be added. When iron is present the color after heating in the inner flame is deep red on cooling. Siliceous titanic minerals, as sphene, do not give the reaction with borax, except after long heating in the inner flame with salt of phosphorus, and it is apparent only on cooling.

14. Tin.—Oxyd of tin is slowly dissolved by borax to a transparent glass, which is transparent on cooling. With soda or cyanid of potassium on charcoal it is easily reduced; and if borax also be added, a very minute quantity of tin may be detected

when present in other minerals.

15. Cerium.—Oxyd of cerium affords with borax and salt of phosphorus, a fine red or dark yellow glass in the outer flame, which becomes white on flaming. The protoxyd changes to

peroxyd, and the latter is not changed in the inner flame. In the compounds with silica, cerium is not distinguishable from iron by the blowpipe.

16. Lead.—Minium is black while hot, but at a low red heat changes to a yellow oxyd. The ores of lead on charcoal, with or without soda, are reduced; unlike tin, they often give a coating of

oxyd on the charcoal, when heated in the outer flame.

17. Zinc.—Oxyd of zinc with borax gives a clear glass, which is milk-white on flaming; or with more assay, is enamel-white on cooling. In the inner flame on charcoal, fumes are given off, and a white coating surrounds the assay. With soda on charcoal, the ores, even when containing little zinc, afford the peculiar bluish flame of burning zine, and the oxyd is deposited on the coal. With cobalt solution, a green color, while tin gives a bluish green.

18. Cadmium.—Oxyd of cadmium, even when in small proportions in other minerals, when heated on charcoal deposits a reddish brown powder; it forms from cadmiferous blende before the

zinc begins to incrust the charcoal.

19. Copper.—Oxyd of copper gives a fine green glass with borax, which becomes cinnabar-red on cooling. The ores are reduced on charcoal with soda, and a malleable copper-colored globule obtained; when the copper is combined with oxyds that are reduced together with it, borax and tin should be used. If iron be present, the copper and iron are obtained separately.

20. Manganese.—Oxyd of manganese gives with borax in the outer flame an amethystine globule, (very deep, with much manganese), which becomes colorless in the inner flame. With soda on platinum the oxyd gives a green color which is bluish green on cooling. When other metals are present, soda should be added, and then the bluish green color is obtained, even with less than one per cent. of manganese.

21. Iron.—With borax in the outer flame, oxyd of iron gives a dark red glass, which becomes yellowish or colorless on cooling. In the inner flame it affords a bottle green color, or a bluish green in a more perfect reduction. With tin the green color is hastened. The peroxyd becomes magnetic when heated in the inner flame.

22. Cobalt.—Oxyd of cobalt gives a clear blue bead with borax, which does not become opaque on flaming. As in other metallic species, the sulphurets should be roasted before testing for the

23. Nickel.—Oxyd of nickel forms a dark yellow or reddish glass with borax, which is nearly colorless on cooling; but with more of the oxyd, the glass is dark brown, while hot, and becomes red on cooling; and with saltpetre in the outer flame the color is changed to a blue or deep purple, distinguishing it from oxyd of

Silver.—The ores on charcoal, with, if not without, a flux, are reduced to the metallic state. But when other metals are present, lead is to be mixed with the assay, with the borax, and thus an alloy of lead and silver formed, from which the silver may be obtained by cupellation.

25. Chlorids.—A dull green pearl, made by dissolving a little oxyd of copper in salt of phosphorus, becomes surrounded by a fine blue or purple flame if a chlorid be added, which continues

till the chlorine is expelled.

26. Fluorids.—When fluorids are heated with salt of phosphorus previously melted in an open glass tube, the glass is coroded, and Brazil paper, placed within the tube, is turned yellow. The salt of phosphorus for this experiment should be free from all chlorids. If the fluorine is present only in small quantity the assay may be heated in the same way without the salt of phosphorus.

27. Sulphates.—Like the sulphurets, in their reaction with a

glass of borax and silica.

28. Nitrates.—Deflagrate on burning coals, and also give off a red gas when heated in a matrass with a drop of sulphuric

acid.

29. Phosphates.—If a phosphate be fused with boracic acid, and the extremity of a small iron wire be inserted into the melted globule, and the whole be heated in the reduction flame, the globule formed at the extremity of the wire will prove to be more or less brittle, when struck with a hammer on an anvil. As the bead cools, a flash of light is usually seen. Before this trial it should be ascertained that no sulphuric or arsenic acid is present, which also may form a globule with the iron; nor any metallic oxyd reducible by the iron.

30. Borates.—When a borate is melted with three parts of the

30. Borates.—When a borate is melted with three parts of the flux called Turner's reagent, (a mixture of two parts of fluor spar and one of bisulphate of potash), the flame at the instant of fusion is brightly tinged with green. This trial should be made in a

dark place.

For a more complete account of the blowpipe and of its use in chemical analysis, I would refer to the Treatise by Berzelius

(Whitney's translation) and also that of Plattner.

In addition to the instruments already described, the following are important: 1. A small hammer, with a slightly rounded face and a transverse sharp edge at the other extremity. 2. An anvil, or piece of steel 3 inches long, 1 broad, and \$\frac{1}{16}\$ thick—to be used for pulverizing minerals, for which purpose the specimen should be first wrapped in a piece of paper. 3. Platinum foil, for enveloping minerals that decrepitate. 4. Fine Platinum wire, bent at one end into a circle one or two lines in diameter; it very conveniently holds the assay in fusion. 5. Cutting pliers, for separating small fragments of a mineral for assay.

Oupellation.—Cupellation is a process by which one metal in an alloy is oxydized and absorbed by a porous material, and the other left pure. It is used for separating silver and gold from

lead. It is performed before the blowpipe by making a small rounded cavity in charcoal, about as deep as broad, (say ‡ inch), putting in fine bone ashes a little moistened, and made smooth by pressure, and upon this, after drying slowly, the assay; then heating in the outer flame. When the alloy of silver and lead is thus treated, the lead becomes an oxyd and is absorbed by the bone ashes, and the silver, though extremely minute in quantity, re-

mains as a brilliant globule in the cavity.*

The ordinary process of cupellation is as follows: The assay is heated in a small cup (called a cupel) made of bone ashes, (or in a cavity containing bone ashes), while the atmosphere has free access. The heated metal is oxydated by the air passing over it, and the oxyd formed sinks into the porous cup, leaving the precious metal behind. In order to fuse the alloy and still have the atmosphere circulating over it, the cupel is placed in a small oven-shaped vessel, called a muffle, (f. 261); it is of infusible stoneware, and has a number of oblong holes

ware, and has a number of oblong holes through which to admit the flame from the fire, and give exit to the atmosphere which passes into it. The muffle is inserted in a hole fitting it in the side of a vertical furnace, with the open mouth outward



and even nearly with the exterior surface of the furnace. The fire is made within the furnace, below, around, and above; and after heating up, the cupel is put in the muffle with the assay in its shallow cup-shaped cavity. It thus has the heat of the furnace to fuse the assay, and the air at the same time is drawn in over it through the large opening of the muffle. The oxygen of the atmosphere unites with the lead of the assay, and produces an oxyd, which oxyd sinks into the cupel, leaving the silver or gold behind. The completion of the process is at once known by the change of the assay suddenly to a bright shining globule.

In the cupellation of gold containing copper, lead is melted with the assay. The lead on being fused in a draft of air oxydizes, and also promotes the oxydation of the copper, and both oxyds disappear in the pores of the cupel, leaving the gold behind, and the silver alloyed with it. In this process the gold is melted with three times its weight of silver, (a quartation, as it is termed, the gold being one part out of the four of the alloy), in order by diffusion to effect a more complete removal of the silver as well as the contained copper. The cupel is placed in the heated furnace, and the gold, silver, and lead on the cupel; the heat is sustained until the surface of the metal is quiet and bright, when the cupellation is finished; the metal then is slowly cooled and removed.

A table by Prof. W. W. Mather, is contained in the American Journal of Science, [2]. iii. 414, which gives the ascertained weight of globules of silver, of given diameters. Similar tables are given in different Treatises on chemical analysis.

The button obtained, after annealing it by bringing it to a red heat, is rolled out into a thin plate and boiled in strong nitric acid. This process is repeated two or three times with a change of the acid each time, and the silver is thus finally removed. At the United States mint, half a gramme of gold is submitted to assay. The assay-gold and quartation-silver are wrapped in a sheet of lead weighing about ten times as much as the gold under assay. After cupellation, the plate of gold and silver, loosely rolled into a coil, is boiled for 20 minutes in 1½ oz. of nitric acid, of 20 to 22° Beaumé; the acid is then poured off and another portion of stronger acid is added, about half the former quantity, and boiled ten minutes; then the same again. The gold thus purified is washed and exposed to a red heat, for the purpose of drying and annealing it, and then weighed.

III. PSEUDOMORPHS AND METAMORPHIC CHANGES IN MINERALS.

Pseudomorphs were formerly viewed as singular freaks of nature, of occasional or rare occurrence. As science advanced, their numbers were found to be large, collections of them began to be made, and chemistry was variously taxed for their individual explanation. At the present time they are looked upon as types and evidences of vast metamorphic changes and processes of decay or reformation in inorganic nature, which have modified extended rock strata, and altered the structure of the earth's surface.

The earliest systematic treatment of the subject was made by Haidinger in Brewster's Edinb. Jour., vols. ix, x. In 1843 appeared the extended work of Blum, which has been followed by two supplements. Since then, the wide range of metamorphic action as illustrated by pseudomorphs has been discussed with ability, and many new developments by Bischof, in his Chemical and Physical Geology. The work of Volger on the history of minerals, issued the year past, follows up the same subject in some of its departments with critical care, and some original views. Various memoirs by other authors have also appeared, illustrating this important topic. Mineralogy is thereby becoming a living science, and the active germ from which the science of Geology in some of its departments is to have its true development. Moreover, it is receiving a purification itself, by the thorough study of the liabilities of species to change, thus making known the causes of variations in analyses, and bringing to light the true types of the original species. A high importance is given moreover to these variations; for each marks out principles that have operated extensively in the earth's history. Even the smaller differences in the varieties of species are proving to have an influential bearing on the alterations of these or other species; and they have also become essential data towards discussing the origin and peculiarities of associated species and the genesis of the beds of rock in which they occur. Every analysis has therefore a high interest, a special as well as a general value, and they cannot be too much multiplied, nor too fully presented in a Mineralogical Treatise. The formulas commonly given have their value, if they are right, which is not always sure. But the details of the analyses have a higher and wider importance, geological as well as mineralogical.

Pseudomorphs have been classed under four grand heads:

1. Pseudomorphs by alteration: those formed by a gradual change of composition in a species; e.g., change of Augite to

Steatite.

2. Pseudomorphs by substitution: those formed by the replacement of a mineral which has been removed, or is gradually under-

going removal; e. g., petrifaction of wood.

3. Pseudomorphs by incrustation: those formed through the incrustation of a crystal which may be subsequently dissolved away; often the cavity is afterwards filled by infiltration; e.g., change of Fluor to Quartz.

4. Pseudomorphs by paramorphism: those formed when a mineral passes from one dimorphous state to another; e.g., change of

Aragonite to Calcite.

These different kinds of change are not always distinguishable without special study. In some cases a change may take place through alteration of the surface, and then, this process ceasing, the interior may be dissolved out, leaving a pseudomorph like one of incrustation; or a pseudomorph that appears to be a result of alteration, explicable on chemical grounds, may be wholly due to

substitution simply.

Again, changes of some Scapolites to a feldspar, and of Augite to Uralite, (hornblende), have been considered by Scheerer examples of paramorphism; Scapolite being considered dimorphous with some feldspar, and Augite with Hornblende. But while such paramorphic changes undoubtedly take place with Aragonite, their occurrence in these silicates—which are common associates in the same rock, and must have been formed under like circumstances—is hardly probable.

The following table contains a list of the known varieties of pseudomorphs that have thus far been observed:

1. ELEMENTS.

Pseudomorph. Native Copper, Native Antimony, Graphite,

Forms Imitated. Red Copper, Aragonite. Valentinite. Pyrites.

Pseudomorph.
Pyrites,

Leucopyrite,
Marcasite,
Erubescite,
Copper Glance,
Chalcopyrite,
Gray Copper,
Silver Glance,
Galena,
Blende,
Stephanite,
Covelline,

Horn Silver, Common Salt, Fluor,

Magnetite, Hematite, (Fe),

Göthite,

Limonite,

Minium,
Pyrolusite,
Hausmannite,
Braunite.
Wad, Psilomelane,
Manganite,
Black Copper,
Tin Ore,
Bismuth Ochre,
Antimony Ochre,
Antimony Blende,
Valentinite,
Arsenolite,
Quartz,

Hornblende, Mica,

2. Sulphurets, Arseniurets.

Forms Imitated.

Mispickel, Pyrrhotine, Stephanite, Red Silver Ore, Polybasite, Marcasite, Galena, Specular Iron, Barytes, Calcite, Quartz, Anhydrite.

Stephanite.
Stephanite, Calcite.
Copper Glance.
Chalcopyrite.
Copper Glance, Gray Copper.
Galens.
Pyrargyrite, Native Silver.
Pyromorphite, Calcite.
Calcite.
Polybasite.
Copper Pyrites.

3. Chlorids, Fluorids. Silver, Red Silver Ore. Dolomite. Calcite.

4. OXYDS.

Spathic Iron, Specular Iron, Actinolite, Mica.
Pyrites, Magnetite, Limonite, Göthite, Spathic Iron, Pharmacosiderite, Dolomite, Calcite, Barytes, Fluor, Quartz, Garnet.
Pyrites, Dolomite, Smithsonite, Barytes, Calcite, Calamine, Vivianite.
Specular Iron, Pyrites, Leucopyrite, Marcasite, Beryl, Ankerite, Spathic Iron, Scorodite, Cube Ore, Spherosiderite, Blende, Galena, Pyromorphite, Cerusite, Barytes, Fluor, Calcite, Dolomite, Comptonite, Jeffersonite, Pyroxene, Red Copper, Beryl, Quartz. Cerusite, Pyromorphite, Galena, Calcite.
Manganite, Polianite (1), Dolomite, Calcite.
Manganite, Calcite.
Manganite, Pyroxene, Fluor, Pharmacosiderite.
Calcite.
Copper Glance.
Feldspar.
Needle Ore.
Gray Antimony.
Gray Antimony.
Gray Antimony.
Gray Antimony.
Realgar.
Barytes, Fluor, Gypsum, Calcite, Smithsonite, Calamine, Diallogite, Barytocalcite, Dolomite, Scheelite. Cerusite. Augite. Corundum Garnet. Stilbite.

Realgar.
Barytes, Fluor, Gypsum, Calcite, Smithsonite, Calamine, Diallogite, Barytocalcite, Dolomite, Scheelite, Cerusite, Augite, Corundum, Garnet, Stilbite, Heulandite, Natrolite, Datholite, Scapolite, Wolfram, Galena, Pyrites, Spathic Iron; as Prase, Calcite; as Chalcedony, Barytes, Fluor, Calcite, Dolomite, Datholite, Pyromorphite; as Carnelian, Calcite; as Hornstone, Fluor, Calcite, Mica, Spathic Iron; as Jasper, Hornblende; as Semiopal, Calcite.

5. AMBYDROUS SILICATES.

Augite.
Pinite, Iolite, Feldspar, Andalusite, Wernerite, Tourmaline, Hornblende, Elecolite, Beryl, Idocrase,
Augite, Epidote, Albite.

Pseudomorph. Orthoclase,

Chlorite,

Forms Imitated

Calcite, Laumontite, Prehnite, Analcime, Leucite. Leucite.

Ice Spar, Albite, Orthoclase, Wernerite.

Scapolite, Epidote. Kyanite, Sandstone, clay, Andalusite. Common Salt.

6. Magnesian Hydrous Silicates.

Talc.

Kyanite, Feldspar, Pyrope, Chiastolite, Couseranite, Actinolite, Magnetite. Dolomite, Spinel, Quartz, Chiastolite, Topas, Feldspar, Mica, Scapolite, Tourmaline, Andalusite, Staurotide, Steatite,

Kyanite, Garnet, Idocrase, Hornblende, Pyroxene, Gehlenite.

Pyroxene, Hornblende, Chrysolite, Spinel, Schiller Spar, Diallage, Mica, Garnet, Chondrodite. Garnet, Hornblende, Feldspar, Tourmaline, Magnet-ite (†) Limonite (†) Calcite, Fluor. Serpentine,

Rensselacrite, Pyroxene.

Pyroxene, Prehnite, Chabazite. Calcite. Green Earth, Meerschaum,

7. Non-Magnesian Hydrous Silicates.

Feldspar, Porcelain Spar, Scapolite, Leucite, Beryl, Sodalite, Kaolin,

Volknerite, Spinel. Lithomarge, Topaz, Feldspar, Fluor. Cimolite, Pyroxene.

Pinite, Labradorite, Hornblende. Fahlunite, etc.,

Iolite, (see page 214, vol. ii).
Analcime, Leonhardite, Laumontite, Natrolite. Prehnite,

Gieseckite, Nepheline.

Natrolite, Nepheline, (Elseolite).

Thomsonite, Nepheline,

Carpholite. Wolfram.

Chrysocolla, Copper Mica, Red Copper, Asurite, Chalcopyrite,

Cerusite.

8. SULPHATES, MOLYBDATES, TUNGSTATES.

Celestine, Strontianite.

Barytes, Anhydrite, Witherite, Barytocalcite, Calcite. Common Salt.

Anhydrite, Calcite, Common Salt. Common Salt.

Gypsum, Polyhalite, Copperas, Anglesite, Wulfenite, Pyrites. Galena. Galena.

Behoelite, Wolfram. Wolfram, Scheelite.

9. PHOSPHATES.

Triphyline. Smaltine. Pseudotriplite, etc., Cobalt Bloom, Pyromorphite,

Calcite,

Galena, Cerusite.

10. CARBONATES.

Gay-Lussite, Gypsum, Anhydrite, Fluor, Feldspar, Pyrope, Garnet, Pyroxene, Barytes, Pyromorphile, Manganite.

Pseudomorph. Dolomite,

Brown Spar, Strontisnite,

Spathic Iron, Smithsonite,

Cernsite,

Diallogite, Malachite, Azurite,

Forms Imitated.

Calcite. Cerusite.

Gypsum. Calcite, Dolomite, Barytes.

Calcite, Fluor. Galena, Anglesite, Leadhillite, Linarite, Barytes,

Fluor. Galena.

Red Copper, Chalcopyrite, Gray Copper, Azurite, Calcite, Cerusite.

Gray Copper, Red Copper.

These examples of pseudomorphism should be understood as cases not simply of alteration of crystals, but in many instances of changes in beds of rock. Thus all serpentine, whether in mountain masses or the simple crystal, has been formed through a process of pseudomorphism, or in more general language, of metamorphism. The same is true of other magnesian rocks, as stetatitic, talcose, and chloritic slates. The crystalline rocks often offer examples of a change similar in nature. The Graphite of these rocks may be but a pseudomorph (or metamorph) after some vegetable product, and as truly so as the petrified wood of more recent times. Thus the subject of metamorphism, as it bears on all crystalline rocks, and that of pseudomorphism, are but branches of one system of phenomena; the chemistry is the same for both.

The common change of pyrites, forming the main ingredient of the upper part of metallic lodes, to earthy red or brown iron ore, thus producing the gossan of miners, is an example of these processes now in progress. In a similar manner, lodes containing copper pyrites are sometimes changed above to red or black copper ore, or impure chrysocolla, or malachite, mixed with which are the results of alteration of other minerals, (as iron pyrites, arsenical pyrites, and other sulphurets and arseniurets), that were associated with the copper ores; and often the gossan contains disseminated silver or gold derived from the decomposed ores. These are cases of pseudomorphism, as truly as when a simple crystal of iron pyrites becomes limonite; the mode of change and its laws are the same. In like manner, the erubescite of the upper part of a copper lode is a comparatively modern product, arising from the alteration of vitreous copper; or copper pyrites and vitreous copper may have each proceeded from the yellow copper pyrites; for the erubescite and then the vitreous copper usually disappear as the lode is more deeply explored. So, when Spathic Iron is the veinstone of a lode, it is often extensively changed to earthy brown iron ore, more or less impure from mixed ingredients. Again, phosphates and arsenates of copper, lead, &c., as well as carbonates and sulphates, are among the surface species, or those that occupy the upper part of metallic lodes; they are the results of alteration within those depths to which atmospheric agencies penetrate.

Causes of Change.*

The causes of change are the simplest and most universal operations about us. (1), The solvent power of ordinary waters, cold or hot, or of steam; (2), the reactions, according to chemical principles, of the ingredients dissolved in these waters, or in mineral or sea waters, heated or at the ordinary temperature; (3), the process of gradual oxydation to which some substances are liable, and the reaction of substances thus formed on the ingredients at hand, aided or promoted by electrical currents or heat; (4), the action of exhaling gases from the earth, with or without volcanic action.

Ordinary waters hold in solution, as is well known, more or less of mineral matter. The Professors Rogers subjected a large number of minerals in powder on filters to the action of water containing carbonic acid; there were among them, different feldspars, tourmaline, mica, leucite, hornblende, pyroxene, epidote, axinite, garnet, prehnite, zeolites, steatite, serpentine, chlorite; and in all cases the water that passed the filter gave evidence of the presence of an alkali, or lime, or magnesia, and some even gave the tests with the first drops. *Pure* water gave with many of them a similar result, but more slowly. By digesting for forty-eight hours in carbonated water, hornblende, actinolite, epidote, chlorite, serpentine, feldspar, mesotype, &c., they procured a quantity of lime, magnesia, oxyd of iron, alumina, silica, and alkali, and the dissolved ingredients of these minerals severally amounted to from 04 to 1 per cent. of the whole mass. The lime, magnesia, and alkalies were in the condition of carbonates, and the iron passed from the state of carbonate to that of peroxyd during evaporation. Thus forty grains of hornblende digested for forty-eight hours in carbonated water at 60° F., with repeated agitation yielded silica 0.08, oxyd of iron 0.05, lime 0.13, magnesia 0.095, manganese, a trace. The silicates of magnesia, lime, and manganese, were especially ready in yielding to this action.

These facts illustrate two important points:

1. That ordinary waters upon and through the earth's surface, are constantly active in dissolving and decomposing minerals and rocks; and that even species reputed indestructible are thus acted upon.

2. That the waters are thus furnishing themselves with chemical

agents for effecting other changes.

These waters penetrate all rocks, as well as percolate through soils, or run in streams over the earth's surface. Hence the action is a universal one, everywhere going on; and the results are universal. Bones, shells, corals, and animal remains generally are also sources of carbonate of lime, phosphates, and fluorids; and plants may contribute also potash and soda, and sometimes silica.

^{*} The following observations are derived mainly from Bischof's extensive work.

Carbonic acid is a constant ingredient of the atmosphere, and is dissolved by the rains as they descend; and hence this active decomposing agent is present in ordinary waters. It is also a result of different mineral changes. Sulphate of iron along with vegetable matters gives oxygen to the carbon of the vegetable matter, and thus produces carbonic acid and pyrites or sulphuret of iron, and the large quantities of pyrites in coal beds shows on how grand a scale this process has acted. Sulphate of zinc in a similar manner produces carbonic acid and blende or sulphuret of zinc. Bischof observes that the carbonic acid which has thus been eliminated, must have been sufficient in quantity to make if together an atmosphere of carbonic acid equal in height to our present atmosphere. Again, decomposition of sulphurets produces sulphuretted hydrogen; this by oxydation by means of the atmosphere forms sulphuric acid, and the sulphuric acid acting on limestone produces gypsum, it may be in extensive beds, and liberates carbonic acid. Sulphurous acid also forms about volcanoes, which becomes sulphuric acid, with the same result. Moreover silica in waters accompanied by heat will decompose limestone and liberate carbonic acid. Hence it is that this gas is exceedingly common in exhalations from mineral springs, and occurs more or less in all waters.

The dissolving and decomposing action of carbonated waters is therefore general. The sea and all other sources partake of this character, and unite in carrying on the changes to which the pro-

cess leads.

The chemical agents with which ordinary waters are generally

supplied, are the following:

Carbonic acid; carbonate of potash, of soda, bicarbonate of magnesia, of lime, of protoxyd of iron; chlorids of sodium, of magnesium, of calcium; sulphate of soda, of lime, of magnesia; silica or silicate of soda, of magnesia, of lime; phosphate of lime; with rarer ingredients, as fluorine, in some of its compounds, nitrates, salts of lithia.

Mineral waters contain the same ingredients only in larger quantities; also, boracic acid and borates, sometimes traces of arsenic, copper, and other metals, bromids, iodids, sulphuretted

hydrogen.

The sea differs rather in the proportion of the salts than in their kinds. Chlorid of sodium or common salt is most abundant; next chlorid and sulphate of magnesium; then chlorid of potassium, of magnesium, sulphate and bicarbonate of lime, some silicate, (probably, according to Bischof, a silicate of magnesia), bromids, iodids, fluorids, boracic acid, and hydrosulphurets. The carbonic acid in sea water, most abundant about shores where animal life may contribute it by respiration, enables it to dissolve shells and corals, and form bicarbonate of lime.*

^{*} See on this subject, Bischof, Vol. I, p. 966, and elsewhere.

The following are the constituents of different natural waters in

10,000 parts:

I, Sea water from near coast of France, Vogel; II, ib. near Havre, Riegel; III, Mediterranean, Laurent; IV, Geysers, Dr. Sandberger; V, Rhine, Müller; VI, Thames, near Twickenham, Clarke; VII, Artesian well, near Vienna, Rageky (containing also free carbonic acid, 4:44 cub. in. in 26 Prussian ounces); VIII, Salt Springs of Wiesbaden, Fresenius, (to the analysis add, chlorid of lithium 0:0018, chlor. ammonium 0:17, iodid of magnesium trace, bromid of magnesium 0:04, silicate of alumina 0:0051, arsenic acid 0:0015, traces of carbonate of baryta, strontia, oxyd of copper, and 32:2 cub. cent. nitrogen); IX, Marienbad, temp. 11:85° C. Kersten,—add Carb. lithia 0:06, carb. strontia 0:02, phosphate of alumina 0:07.

	I.	II.	III.	IV.	v.	VI.	VII.	VIII.	IX.
	Bea.	Sea.	Sec.	Geys.	Rhine.	Thames.	Art.well.	Wiesbaden.	Marienbad
Chlorid Sodium,	2510	246.82	272-2	25.21	0.07			68.86	14.54
" Potassium,		8-07	0.1					1 ·46	
" Calcium,		4.89				0.250	0.18	471	
" Magnesium	, 850	25.64	61.4				2.02	2.04	
Carb. Lime,		176	0.1		0.85	1.828	8.65	4.18	6-04
" Magnesia,			1.9		0.48	0.147	0.90	0.10	4.64
Sulph. Lime,	1.2	10.97	1.5		0.88	0.064	2.58		
" Magnesia,	57 ·8	21.46	70-2	0.04	0.26				
Free Carb. Acid,	2.8			5.57		51.84	4.44	5229·0*	19.48
Phosphate Lime,								0.004	0.02
Silica,				50.97	0.16	0.088	0.17	0.60	0.88
Sulphuret Sodium	,								
Carb. Soda,				19.89					11.54
" Ammonia,				0.88					
Sulph. Soda,				10.70		0.286			47.22
" Potash,				475		0.095			0.65
Carb. Manganese,					0.04			0.006	0.02
" Iron,					0.08		0.01	0.08	0.45
Organie,						0.497	0.19		
Nitrate Magnesia,						—ь	1.20		
" Soda,							1.27		
	a In cubic centimeters.				ъ	b Add 0·195 alumina.			

The amount of solid matter in solution in the Rhine, which passes Emmerich in a day, according to Muller, amounts to 44,240 cubic meters, of which 4,604 is sulphate of lime, 4,580 sulphate of magnesia, 11,523 carbonate of lime, 5,770 carbonate of magnesia, 940 carbonate of Iron and manganese, 930 chlorid of sodium, 1,930 silica, 2,730 alumina, 11,333 organic ingredients; and the amount for the year is 16,147,600 cubic meters of these ingredients.

For an analysis of the waters of the Dead Sea, see Vol. II, p. 91, and for others of sulphuric acid waters, p. 143. For American waters, Am. J. Sci. [2], ii, 218; iv, 385; ix, 123: xi, 174

The following are the rates of solubility in water of some mineral substances, as given by Bischof:

Silica in its gelatinous condition, Silicate of Potash (K°Si°, Wasserglas),	1 part in	1,000 4 to 5	of water.					
Carbonate of Lime,	44	16,000-24,000	"					
" with carbonic seid,	. 44	1,000	• •					
Carbonate of Magnesia, " "	"	749	**					
Carbonate of Baryta, " "	46	4.300	**					
Sulphate of Lime, 32° F.,	•6 •	462	44					
"" " 912° F.	44	462	44					
Sulphate of Magnesia, 82° F.,	44	4	44					
Sulphate of Banyta,	46	210,000	41					
Silicate of Baryta,	"	20,000	**					
Silicate of Strontis,	46	1,262	••					
Bilicate of Lime, (Wollastonite),	**	5,3886,882	44					
Silicate of Magnesia,	44	82,000-90,600	66					
Silicate of Alumina, (formed by action of alkaline								
silicate on a hot solution of alum),		179,000-884,600						

Very many of the ingredients in solution are, when pure, active agents in producing chemical changes: and their power is not altogether lost by diffusion in water. An alteration or decomposition may go on at slow pace, but it is all sure progress, and in process of time it will make itself apparent; with past geological ages to work in, the results may be measured only by the extent of the earth's surface itself. Heat may occasion greater activity in these changes; and the wide prevalence of thermal springs, and volcanic regions, extinct and active, and the foldings, elevations, and crystallization of rock strata, show that this aid has been extensively given.

The saline and other ingredients of waters are derived from various mineral species.

Line.—From Calcite, and related species, Gypsum, Apatite, much Pyroxene (some giving 20 p. c.), Hornblende (12 p. c.), Wollastonite (46 p. c.), Scapolite (20 p. c.) and related species, Oligoclase (3 p. c.), Labradorite (11 p. c.), Anorthite (15 p. c.), Andesite (5 p. c.), Epidote (21 p. c.), Allanite (10 p. c.), Idocrase (33 p. c.), Garnet (some 30 p. c.), Axinite (20 p. c.), Margarite (10 p. c.); also from shells, Bones, etc.

Potask.—From Orthoclase (12 p. c.), less abundantly from the other feldspars; Muscovite (9 p. c.), Biotite (8 p. c.), Lepidolite (4—10 p. c.), Phlogopite (6—10 p. c.), Nepheline (5 p. c.), Leucite (21 p. c.), some Tourmaline, Scapolite. Hence Potash is abundant in granitic and most feldspathic rocks.

Sods.—From Albite (10 p. c.), Oligoclase (8 p. c.), other feldspars less abundantly. Nepheline or Elsolite (16 p. c.), some Scapolite (5 p. c.), Aemite (10 p. c.), some Tourmaline, some Mica, Analcime, and many Zeolites. Soda is therefore largely distributed in Granites, Syenites, and various igneous rocks, besides being so abundant in Seawater.

Magnesia.—From Tale or Steatite (38 p. c.), and Talcose rocks, Serpentines (40 p. c.), and related minerals, Chlorite (88 p. c.), and Chlorite rocks, Pyroxene (some 20 to 25 p. c.), Hornblende (some 20—30 p. c.), Chrysolite (50 p. c.), Chondrodite (55 p. c.), Iolite (10 p. c.), Biotite (18 p. c.), Phlogopite (26 p. c.), Spinel (20 p. c.) Sparingly in Garnet, Idocrase, Epidote, &c.

Lithia.—From Petalite (2.6 p. c.), Spodumene, (5 p. c.), Triphyline (5 p. c.) Lepidolite (sometimes 4 p. c.)

Silica.—From Quartz and all silicates. The Silicates contain Silica either in its soluble or its insoluble state, the former in those species which gelatinize with acids, and these are most readily decomposable and most soluble.

- risa.—From Fluor Spar (48 p. c.), Cryolite (54 p. c.), Apatite (1.25 p. c.), Chondrodite (8.5 p. c.), some Mica (sometimes 10 p. c.), Topaz (15 p. c.), Fluocerite, Yttrocerite; also traces in Hornblende, Pyrochlore, Leucophane, Fahlunite, Apophyllite, Carpholite and Pyromorphite, and several other phosphates; also in corals, shells, and animal remains.
- Chlorine .- From Common Salt and other Chlorids; also Sodalite, Pyrosmalite; traces in Apatite and some other Phosphates, some Micas, Elscolite, Nosean, Hauyne, &c.
- Boracie Acid-From Boracite (69 5 p. c.), Danburite (27 p. c.), Tourmaline (4 to 12 p. c.), Axinite (5 p. c.), Datholite (21 p. c.), Warwickite (50 p. c. !)
- Sulphur and Sulphuric Acid.—From Sulphate of Lime and other Sulphates, Iron Pyrites and other Sulphurets; also Nosean, Hauyne, Helvin, Lazulite, Skolop-
- Phosphoric Acid.—From Apatite and other phosphates; also sparingly disseminated in Basaltic and other rocks; also from bones, shells, corals, and all animal remains, and soil which contains the results of their decomposition.

The following are some of the modes in which the ingredients in waters act, and the results of the operations. Governing the whole, is the general principle in chemistry, that in decompositions the resulting compound is less soluble than the compound attacked.

Carbonic soid (O) in solution

a Dissolves calcite (CaO), and thus aids in forming pseudomorphs by substitution after calcite, the new mineral present, as carbonate of iron or carbonate of man-

- ganese, taking its place. Hence Spathic Iron, Diallogite, etc., after Calcite.

 Acts on Scapolite; combines with the lime and forms carbonate of lime (CaC);
 and when the lime is removed C if it continues to act, removes alkalies, as alkaline carbonates
- a Acts on Labradorite and the lime feldspars; combines with the lime, making carbonate of lime, (Calcite). Hence part of the Calcite in amygdaloids. If too little 0 to take up all the lime, the rest separates as silicate of lime. Hence may come Wollastonite; and with hydrous silicate of alumina, the seolites containing lime; with alumina and silicate of soda from the soda of a feldspar, come the zeolites containing soda, and with infiltrating waters holding baryta
 - in solution, those containing baryta. In the above process, part of the silica is set free as soluble silica; hence may come silica in the form of rock crystal, agets, chalcedony, opal, common in amygdaloids. Also with the feldspars, stmospheric waters, in which there is little C, carry off part of the alkalies, and the rest separates as alkaline silicates, in solution, and leave *Kaolin*, (<u>Als Bis As</u>), containing some disseminated silica, that is set free by the process.
- d. Acts on pyrozens, hornblends, trap or basalt, (usually composed of labradorite and augite,) and amygdaloid: if solution is saturated with C, lime is removed as carbonate of lime, also the magnesia as carbonate of magnesia; and thus by the removal of the bases may come Cimolite. With less C, the magnesia is not acted upon until the lime is mostly removed, and if O is exhausted, the magnesia separates as silicate of magnesia; hence may come Saponite; and if iron is present, chlorite, both of which are common in amygdaloids.

a. Acting on olivine, removes the protoxyd of iron and some magnesis, as carbonate, hence serpentine after olivine. Carbonate of magnesia is a common associate of serpentine.

f. Dissolves gelatinous silica, and the silica crystallizes as quartz on heating slowly to 200 or 800 C. (Senarmont).

. Alkaline Carbonate in Solution, (KC or NaO with water).

s. Decomposes CaF (fluor spar), especially if heated, making carbonate of lime (Ca

O); hence the pseudomorph Calcite after Fluor.
b. Acts on heavy spar, (BaS), heated to 80° F., affords Witherite, and alkaline sulphates, (BaC), hence Witherite after Heavy Spar. Temperature much below 80°, the sulphate is restored. Hence Heavy Spar after Witherite.

c. Acts on Celestine, (Sr S) heated to 80° F., affords Strontianite (Sr Č), and alkaline sulphates; hence Strontianite after Celestine. Similarly on Pb St.

d. Acts on Silicate of lime, decomposing it, forming Carbonate of Lime.

s. Acts on pyroxene, the lime of pyroxene takes the C, and the alkalies take the place of the lime; hence Green Earth after Augite. The same on Scapolite; hence Mica after Scapolite; and also, Algerite after Scapolite; in a similar man-ner other altered alkaline forms.

f. Acts on an aluminous hornblende, the alkalies are left, and Ca removed; hence Mica after Hornblende. Or Fe and Mg removed and Chabazite is formed, (oxy-

gen ratio of which for bases and silica is 1: 2, as in hornblende).

g. Acts on phosphate, of lime (apatite), producing carbonate of lime and alkaline phosphate; hence Calcite after Apatite.

- h. Dissolves alumina, and may remove part of the alumina from aluminous minerals.
 i. Acting on Sulphate of Copper, forms carbonate of copper or Green Malachite, (Rose).
 k. Bicarbonate of Soda acts on Sulphate of lime and forms Calcite if the solution is very weak, (2° Beaumé); or Aragonite, if stronger, (5° or 6°); and hence araginate in the solution of the solution of the solution is the solution. gonite in gypseous and saliferous deposits; the same acting on sulphate of magnesia heated forms Carbonate of Magnesia; on sulphate of iron forms Carbonate of Iron, etc.; on sulpho-arsenite of silver, forms Light red silver, Senarmont. Potash in solution acting on gypsum forms calcite, the carbonic acid in this case coming from the atmosphere.
- 3. Alkaline Silicate in solution, (derived largely from decomposition of feldspars. a. Acts on sulphate or chlorid of lime, produces Silicate of lime, and sulphate of alkali; hence Wollastonite.

b. Acts on sulphate of magnesia, if heated, produces Silicate of magnesia and sulphate of alkali.

c. Acts on BaS or SrS, no decomposition.

d. Acts on Mg Cl, produces Silicate of magnesia and chlorid of alkali.

e. Acts on bicarbonate of lime, heated, a partial decomposition, complete only after a long trial; forms alkaline carbonate, carbonate of lime, and free silica; hence quartz, &c., (in part) in amygdaloid; and Quartz after Calcite.

f. Acts on bicarbonate of iron, similar result.

Acts on Magnesia Alba, similar result.

h. Acts on carbonate of iron (FeC), and carbonate of magnesia, (MgC), together produces augite !.

i. Acts on aluminous hornblende, gives alkali removing lime, and forms mica; hence Mica after Hornblende

k. Acts on ferruginous grains, and forms Glauconite, (green grains of cretaceous formation containing alkalies).

1. Decomposed when organic matter and an alkaline carbonate, which give rise to ammonia, are present, and silica separates, as opal, quartz, chalcedony; a common process

With phosphate of lime (Ca'P) or phosphate of alumina no action, even when heated; and hence these compounds may coexist with alkaline silicates. n. Potash silicate acted on by solution of common salt, more or less changed to

soda silicate.

 Decomposed by carbonic acid, if the silicate contains no more than 1K to 165;
 and hence alkaline silicates and carbonates of alkali coexist; so also silicate of soda and bicarbonate of lime, as in Cancrinite. p. Silicate of baryta in solution is changed by sulphate of magnesia, lime or soda

to sulphate of baryta.

Silica in solution is often distributed through other minerals, and may thus give them an unnatural hardness. The hydrous magnesian silicates and zeolites appear especially to be at times affected by this cause.

4. Sulphate of Soda in Solution.

a. Acts on chlorid of calcium, forms gypsum.

b. Acts on chlorid of magnesium, forms sulphate of magnesia.

c. Acts on BaC forms sulphate of baryta, (Heavy Spar).

5. Carbonate of Lime in Solution, as Bicarbonate.

a. Acts on alkaline silicates, producing Silicate of Lime, Alkaline Carbonates, and free Silica; hence Quartz, &c., in rocks.

b. Acts on sulphate or chlorid of copper, and affords Sulphate of Lime and

Carbonate of Copper.

c. Dissolves fluor spar; hence infiltrating waters in limestone dissolve out fluorids, (as Fluor Spar), and carry them to open spaces where they may crystallize. Perhaps the same with Apatite.

d. Acts on sulphuret of iron and forms Sulphate of Lime and Carbonate of Iron, or Limonite by oxydation of iron.

2. Acts on blende and forms Carbonate of Zinc, (Smithsonite).

3. Acts on Sulphate of Magnesia, if heated, and forms Dolomite (von Morlot) and Gypsum, which minerals are often associated.

6. Sulphate of Lime (CaS) in Solution.
4 Acts on Witherite (BaC) at ordinary temperature, producing Heavy Spar (BaS), hence Heavy Spar after Witherite.
b. Acts on Barytocalcite similarly; hence Heavy Spar after Barytocalcite.
c. Acts on Strontianite (SrC); hence Celestine after Strontianite.

- d Acts on Carbonate of Magnesia, producing Sulphate of Magnesia and Calcite.
- Acts on Silicate of Strontia, yielding silicate of lime, and Sulphate of Strontia, (Celestine).

Acts on an alkaline silicate, affording Silicate of Lime.

5. Acts on an alkaline silicate, affording Silicate of Lime.

5. Dissolves Apatite, (CaP).

6. Acted on by organic matter, yields carbonic acid by deoxydation of sulphuric acid and lime, and forms sulphuret of calcium and water.

L Decomposed by steam, sulphuretted hydrogen produced.

7. Carbonate of Magnesia in solution as bicarbonate. 4. Acts on CaC and produces a double carbonate of lime and magnesia, or Dolomite; hence Dolomite after Calcite.

Acts on sulphate of lime, and produces Dolomite; hence Dolomite after Gypsum. Acts on silicate of lime, forming silicate of magnesia; hence steatitic compounds.

d Acts on pyroxene, the carbonic acid taking off lime and leaving magnesia; hence
Hornblende after Augite, Pyrallolite after Augite, Bronzite and Hypersthene
after Augite. Further action, removing all the bases but magnesia, and adding magnesia in place of the lime, and water taken up; hence Serpentine, Steatite, Tale, after Pyroxene.

8. Sulphate of Magnesia in solution.

a Acts on carbonate of baryta, (BaC), produces Heavy Spar, (BaS), and carbonate of magnesia, (MgC); and similarly with carbonate of strontia; hence Heavy Spar after Witherite, Celestine after Strontianite.

Silicate of Magnesia in solution

a. With carbonate of magnesia, (MgC), produces the siliceous variety of magnesite.

b. Acts on MgC, produces Steatite; hence Steatite after Magnesite.

c. Acts on Spinel, produces Steatite; hence Steatite after Spinel; similarly for Chiastolite, Feldspar, Augite, and many other steatitic pseudomorphs.

10. Sulphate of Iron in solution.

a Acts on phosphate of lime in solution, (from animal remains), and produces phosphate of iron; hence Vivianite; similarly from sulphate of copper in solution, Phosphate of Copper or Pyromorphite.
b. Acts on carbonate of lime, and produces carbonate of iron and sulphate of lime; hence Spathic Iron after Calcite. Similarly sulphate of zine produces carbonate of zine; and hence Smithsonite, (ZnÖ), after Calcite.

11. Carbonate of Iron, (FeC), in solution, as bicarbonate.
a. Acts on phosphate of lime, and produces Vivianite or phosphate of iron, (probably

the common process).

- b. Acts on silicate of lime, and forms silicate of protoxyd of iron, Hisingerite, Pingerite, Chlorophæite, Silicates of Iron, resulting from decomposition of basalt, and minerals containing iron.
- 12. Sulphuretted Hydrogen or Hydrosulphurets in solution, (produced by oxydation of sulphurets, or by deoxydation of sulphates in water, through the intervention of organic matter with water).
- a Acted on by organic matter, a deposit of Sulphur, as in some sulphur water.

b. Acted on by sulphurous acid, a deposit of Sulphur, as about volcanoes, (2HS+ SO2=2HO+3S)

SO²=2HO+3S).
Changed by oxydation through oxygen of atmosphere, to sulphuric acid and water, and some sulphur deposited; and sulphuric acid, with chalk, or calcite, then forms gypsum, and gives rise to other sulphates; hence Gypsum after Calcite and Gaylussite. Hence gypsum beds and the sulphur they contain.
d. The sulphur acid acts on augite, feldspar, &c., in volcanic regions especially, and produces complete decomposition, separating silica as Hyalite, Quartz, siliceous incrustations, Sinter, forming also Cimolite, Pholerite, Lenzinite, Scarbroite, &c. Lithomarge after Feldspar and Topaz.
Acts on sulphate of zinc, and reduces it to sulphuret of zinc.

e. Acts on sulphate of zinc, and reduces it to sulphuret of zinc.

f. Acts on carbonate or phosphate of lead, and changes it to Sulphuret of Lead or Galena; on Native Silver, and changes it to Sulphuret.

g. Acts on chlorids of the metals, and forms sulphurets; thus Blende, Pyrites, Galena, Copper Glance, Silver Glance, Bismuth Glance, Antimony Glance, Tetrahedrite (Durocher).

14. Oxydation.

a. The protoxyd of iron is especially liable to peroxydation, when moisture is present; and compounds containing it, whether silicates or carbonates, often undergo alteration by this means. The protoxyd of iron usually passes to the state of a hydrous sesquoxyd (Fe² H²) and then to anhydrous sesquoxyd (Fe). Spathic iron (Fe C) often goes through these changes, becoming brown, black, and when finally anhydrous, red, unless it passes to the crystalline state. Pyroxene, augite and augitic rocks, mica, garnet, often show commencing decom-position in the peroxydation of the iron; if carbonic acid exists in the moist-

position in the peroxydation of the fron; if carbonic acid exists in the moisture, the iron may pass into the state of carbonate; but then in many cases it passes soon to a hydrous oxyd.

b. The protoxyd of manganese is still more liable to oxydation, and it may pass to two states of oxydation, with or without water. This liability is so strong that some species, as the phosphates of protoxyd of manganese, are seldom found in an unaltered state. The silicates become black, and several species have been made from analyses of the altered varieties.

have been made from analyses of the altered varieties.

c. Sulphurets, arseniurets. Many sulphurets (RS² or RS) change readily to hydrous sulphates, by an oxydation of the sulphur and metal (air and moisture being present) often developing nitrogen if the oxygen is derived from the air; or sulphuretted hydrogen if partly from the water; and frequently some sulphur is set free. The sulphates may then promote other changes.

By means of organic matter, sesquoxyd of iron (Fe) may be reduced to protoxyd (Fe); and thus a carbonate of iron may be formed if carbonic acid is present or

is formed in the process. Hence spherosiderite.

is formed in the process. Hence spherosiderite.

Sulphate of lime, of iron, of zinc, by the same means, may be reduced to sulphurets, sulphuretted hydrogen and carbonic acid often being given out at the time, the carbonic acid forming from the oxygen removed by the carbon of the organic matter; thus come Pyrites, Blende, etc., by the wet way; when a sulphate, oxyd of iron and organic matter are together, pyrites may be formed; thus sulphurets may have been produced in fossil plants, as in Fuci.

16. Other reactions and results.
a. Alkaline phosphates act on a magnesian salt and form phosphate of magnesia: also upon lime in Scapolite and form phosphate of lime.
b. Sulphate of baryta is rarely decomposed, like sulphate of lime, by organic matter. Sulphate of copper in solution, in contact with porous limestone forms Brochantite.

c. The decomposition of species containing iron, (as some augites, hornblende, &c.), gives rise in many cases to silicates of iron, as Hisingerite, pinguite, chloro-

d. Alkaline fluorids, acting on pargasite, may form Chrondodite (!); with wollastonite, they are decomposed into alkaline silicate and fluor spar (CaF).

Moisture, acting on anhydrite, water is absorbed and the species is changed to gypsum. Hence Gypsum after Anhydrite. Acting on other minerals it is more or less absorbed, and promotes their decomposition. Added to Labradorite, it may form Mesolite.

f. The degree of solubility of silicates of strontian and barytes accounts for their

non-occurrence as species among minerals.

g. In pseudomorphs of oxyds of iron after calcite, it is probable, as Volger urges, that the calcite first passes to the condition of spathic iron; then to a hydrous sesquoxyd (Fe'H', Fe H', or Fe H); then to an anhydrous sesquoxyd (at 160° to 180°. C. Senarmont); then it may be by deoxydation to Magnetite (Fe Fe), or to Fe; and then to FeC or carbonate of iron again, if carbonic acid is present.

a. Carbonated waters dissolve silicate of zine without decomposing it.

i. Organic matter with heat to 150° to 250° C., reduces salts of copper or lead.

be Steam, acting for a period of time, will dissolve away or decompose many silicates; alter some suphyerate promoting their covadation; at a high temperature.

cates; alter some sulphurets promoting their oxydation; at a high temperature acting on Galena, it will carry off the sulphur as sulphurous acid and sulphuretted hydrogen and leave metallic lead; acting on chlorid of iron, deposits Specular Iron, regarded by Gay Lussac and Mitscherlich the origin of specular iron of volcanoes; acting on chlorid or fluorid of tin, forms oxyd of tin or Cassiterite; on the same of titanium, forms brookite, anatase, or rutile; on the same of silicon, forms quartz: Daubrée, (Compt. Rend. 1849, 227, 229), who observes that these minerals just mentioned (rutile, quartz and specular iron) are associates in the Alps; acting on the furnace product Ti Cy+3Ti³N, produces crystals of Anatase.

4 Carbonate of lime is decomposed by silica at the temperature of boiling water, and carbonic acid expelled; hence carbonic acid given out by many waters.

It is thus seen that in the decomposition of a silicate, there may not only be a removal of the alkalies and earths, but in other cases, a large addition of alkalies. It is also obvious, that no mineral can withstand the agencies to which it may be exposed, and even when apparently unaltered, changes may have already been begun. Bischof regards the feldspar called Andesine as Oligoclase from which some silica has been removed by the methods explained, and scapolites are considered as mostly altered, the Meionite oxygen ratio being taken as the true ratio of the unaltered species. Although these particular cases may be doubted, it is altogether probable that different feldspars and scapolite are liable to a loss of silica or other ingredients from this means.

In several of the processes of alteration, silica is set free. This silica takes on the form of opal or quartz, according as it is soluble or insoluble silica, these being two isomerous states of the same

Delesse has experimented on the loss of silica produced by the action of a potash solution, heated to boiling, on different igneous rocks in powder. He found no action on granite: but on porphyry a loss of 5.35 per cent., Basalt 7.60, Black lava 4.50, Obsidian 18.39, Retinite 9.50 to 12.23, Trachyte 17.06 to 36.00. There was also a removal of some alumina, the porphyry losing a trace, the Basalt 2.85 per cent., Black lava 2.60, Obsidian 3.78, Retinite 1.16 to 1.25, Trachyte trace to 2.39. The partially altered rocks were much the most easily acted upon, and those containing quartz the The Retinite, Perlite, Trachyte which contain the silica partly in the soluble condition or in easily attacked glassy silicates are most readily acted upon. The loss of alumina was greatest in the glassy rocks, and in those that contain augite.

The various recent papers on pseudomorphs by Haidinger should

have attentive study in this connection.

Various applications of the principles that have been presented will be found throughout the Descriptive part of this work. On these principles and others of like nature which science may develop, the changes and origin of minerals and rocks are to be studied. Bischof, in all his discussions, has direct reference to Geology, and arrives at a Neptunian theory—making nearly all rocks by the "wet" way—in which few will follow him. The subject needs a much more extended investigation from the opposite point of view before the exact limits of the two agencies fire and water shall be appreciated. We have aimed in the preceding pages at a brief review of the elements of the subject, such as is appropriate to a treatise on Minerals; a fuller discussion pertains rather to Chemical Geology.

As an appendix to the above, some further results of Chemistry in the formation of minerals, and the artificial products of furnaces, may be mentioned, although several of the processes appear not to be the out-door processes of nature. The following are among the mineral species that have been made and crystallized artificially.

Grayish white Pyroxene, by mixing the constituents and exposing to a high temperature: Berthier, Ann. de Ch. xxiv, 376.

Idocrase, Garnet: Mitscherlich, Ann. de Ch. et de Phys. lvii, 219.

Spinel, colorless and of red, blue, and black colors, Chrysoberyl, Chromic Iron, Emerald, Chrysolite, Corundum: EBELMEN, Ann. Ch. Phys. [3], xxii, 211, 1848, by employing the dissolving action of boracic acid or borax; spinel was formed by mixing alumina and magnesia, with boracic acid, and exposing to a high heat, adding a little oxyd of chrome to form red spinel, oxyd of iron for the black, oxyd of cobalt for blue; the Chrysoberyl was formed in a similar way from 6 of alumina, 1.62 of Glucina, and 5.0 of boracic acid; crystallized corundum from four parts of borax and one of alumina.

Periclase, Perofskite, Tantalate of lime, (resembling Pyrochlore), Tantalate of iron: EBELMEN, Ann. Ch. Phys. [3], xxxiii, 34, 1851; by making lime to act on borate of magnesia at a high temperature, the magnesia (Periclase) separates in cubo-octahedra; similarly lime acting on a silicate of titanium, perofskite (titanate of

lime) is produced, &c.

Oxyd of Copper, Sulphuret of Silver, of Copper, of Tin, of Lead, of Mercury, of Iron, Kermes, Iodids, &c.: Beequerel, Ann. Ch. Phys. xli, and xlii, 225, using weak electrical currents; the sulphuret of silver from solutions of nitrate of silver and hydrosulphate of potash, &c.

Native Copper, and other native metals, by electric decomposition through weak currents: Bird, Phil. Mag. x, 376.

Sulphurets, Arseniurets, &c.; DUROCHER, Compt. Rend. xxxii,

823-see p. 334.

Crocoisite and Melanochroite: Drevermann, Ann. Ch. u. Pharm.

lxxxvii, 120.

Diamond: Despretz, Compt. Rend., 1853, by the action of galvanic heat on charcoal in a glass globe, the vapor of carbon thus

formed condensing in minute octahedrons on the glass.

Carbonate of Magnesia (Magnesite), of Iron (Spathic Iron) of manganese (Diallogite), of zinc (Smithsonite), &c.; also Sulphurets of Iron, Manganese, Cobalt, Nickel, Zinc, etc: Senarmont, Ann. Ch. Phys., [3], xxx, 129. This important paper contains many new processes, for carbonates, sulphurets, and other species.

Cassiterite, (Tin Ore), Brookite, Quartz, Apatite, Wagnerite, Topaz: Daubree, Compt. Rend. xxvii, 1849, 227, xxxii, 625, 1851, —see p. 335; Topaz by the action of fluorid of silicon on alumina at a high temperature; apatite by means of chlorid or fluorid of

phosphorus acting on lime,

Dolomite: Durocher, by action of vapors of anhydrous chlorid of magnesium in a gun barrel on porous carbonate of lime: for von Morlor's process, see p. 333: Bromeis, by reaction of chlorid of magnesium in solution on carbonate of lime, Ann. Ch. Pharm. lxxxi, 129.

Heavy Spar, Celestine, Anhydrite, Pyromorphite, Wolfram, Tungsten, Scheeletine, Wulfenite, Crocoisite, Anglesite: N. S. Mannoss, Inaug. Dissert. Götting., and Am. J. Sci., [2], xii, 186.

The following are observed Crystallized furnace products.

1. Elements.—Graphite, in six-sided tables at Dillenberg; Sil-

ver; Lead; Copper; Iron; Bismuth.

2. Silicates.—Chrysolite, (Silicate of iron), having the form of crystals and angles of native chrysolite, from Iron and Copper Furnaces, at Fahlun, Oldbury in England, etc. Pyroxene at Garpenberg; also in an iron furnace near Hacheburg, and a copper furnace near Dillenberg; Iron Augite at Fahlun and Oldbury;—Hornblende in crystals, giving for the angle I: I, 123° 55′, yet with the composition of pyroxene;—a fibrous amianthus-like substance, at Westphalia;—Mica, at Garpenberg, having nearly the composition of a magnesia mica;—Idocrase, in square prisms, from hot-blast furnaces of Dudley, England, and Marchienne, Belgium;—Gehlenite (or near) in thin square prisms, white, and transparent when very thin, from a hot-blast furnace at Oldbury, England;—Humboldtilite (!) in long yellow square prisms, with perpendicular cleavage;—Feldspar in crystals at Sangerhausen;—Hexagonal crystals, resembling Nepheline, from Rauthenthal in the Hartz.

Also the following compounds unknown in nature;—Chytophyllite, Hausmann, a gray subfoliated species, resembling kyanite a little, H.=55, G.=2.940, and having the formula (fe, ča) (Si, XI); analysis, Silica 54.897, alumina 5.078, protoxyd of iron 20.794, lime 20.346.—Tabular Crystals, yellow or leek green, G.=2.89, H.=6.5; composition, Silica 48.20, alumina 8.41, lime 37.67, protoxyd of iron 0.97, of manganese 2.23, magnesia 0.74, with 1.78 of sulphuret of calcium, alkalies, water and loss (Schnabel); see further for analyses of doubtful compounds, Percy and Miller's paper, referred to below.

3. Oxyds.—Magnetite in octahedrons at different places; Specular Iron, usually in tabular crystals; Oxyd of Zine, in many furnaces; Red Copper, in crystals; Peroxyd of Chromium, in brilliant black tabular crystals, like those of Specular iron.

4. Sulphurets, &c.—Galena, in cleavable tubes at Holzappel, Ems, &c.; Blende, in modified octahedrons and other forms in the Hartz, &c.; Copper Pyrites, in square octahedrons; Magnetic Pyrites; Antimonial Nickel, in long hexagonal needles, at Ems. The cyanid, TiCy+3TiN in cubes, at Bodenstein, Lahnstein, and Cornwall, (formerly called native titanium.)

5. Sulphates, Arsenates, &c.—Anglesite; Arsenate of Copper; Arsenate of Nickel; an antimonite of copper 3Cu*O+SbO*, (not observed in nature), in copper-red or yellow hexagonal tables at Dillenburg.*

The subject also of the association of minerals in rocks has an intimate bearing on the question of their origin. Associated minerals may obviously have been either cotemporaneously or successively formed. If the former, the species were alike in the general phenomena attending their origin; if the latter, there may still have been many circumstances in common, arising from their condition in the same rocks, or their dependence on the same system of causes, or from the earlier contributing more or less to the material in the latter; or again, they may have no relation except that of relative position. The chemistry of the formation of species is therefore to be learned from a thorough study of all these conditions, as well as from the principles of chemical science itself. This subject properly pertains to geological science: and we only pass in rapid review in this place some of the more frequent associations of mineral species.

A full investigation of the subject, with reference to its geological bearings, would require that each species of mineral should

The more important papers on furnace products are the following:—Mitscherlich, Ann. de Ch. xxiv, 355, Pogg. 1826, 630; Kersten, Pogg. xxxiii, and Ann. de Ch. lvii, 219; Percy and Miller, Rep. Brit. Assoc. for 1846, 351, (Am. J. Sci. [2], v, 127.) giving several analyses; Hausmann, Beit. z. Met. Krystallkunde, Göttingen, 1850 and 1852, valuable papers from the Transactions of the Royal Academy of Science at Göttingen; Sandberger, Pogg. lxxxiii, 596, and Jahrb. d. Nassauisch. Ver. f. Nat., 1851, 131; Schnabel, Pogg. lxxxiv, 158, lxxxv, 462.

be taken up by itself, its associates in its various localities noted, and also the relative connection or relative position of a species and its associates, whether one is imbedded in the other, implanted upon it, or the two are only in juxtaposition, besides other peculiarities of condition. Breithaupt in his work on the "Paragenesis of Minerals," Bischof in his Chemical and Physical Geology, and Delesse, Durocher, and others, in various memoirs, have treated of these subjects. Very much remains yet to be done.

The following are some of the most prominent groups of associated species:

1. Beryl, apatite, columbite, tantalite, eschynite, uranium ores, orthoclase, albite or oligoclase; often together in coarse-grained granite; with sometimes chrysoberyl, garnet, automolite, zircon. At the columbite locality, near Middletown, the columbite occurs imbedded in each mica, feldspar, apatite, and beryl.

Topaz, tourmaline, mica, beryl, euclase, phenacite, apatite, fluor, tin, often lithomarge with topaz; with quartz and tourmaline makes topaz rock.

Spodumene, lepidolite, triphyline, blue and red tourmaline, petalite, (all containing lithia), in granite; also with garnet, staurotide, magnetite, scapolite, sphene,

4. Scapolite, hornblende, (often gray, white, or brown), pyroxene, asbestus, sphene, zircon, feldspar, graphite, yellow or other varieties of garnet, brown tourmaline, idocrase, apatite, chondrodite, mica, sphene, allanite, warwickite, perofskite, fluor, phlogopite, biotite, serpentine, corundum, spinel, rutile, clintonite, graphite, specular iron, in granular limestone; corundum is associated often with margarite, euphyllite, chloritoid, diaspore, tourmaline, chlorite, specular iron, &c.

5. Tale, actinolite, nephrite, dolomite, brown spar, magnesite, tourmaline. 6. Tabular spar, green pyroxene, coccolite, colophonite, sphene, in granular lime-

7. Nepheline (elæolite), apatite, brookite, leucophane, schorlomite, zircon, mica,

pyrochlore, cancrinite; in granite, syenite.

8. Nepheline, glassy feldspar, ilmenite, hornblende; in phonolite.

9. Garnet, hornblende, kyanite, corundum, staurotide; in mica slate or gneiss; with often anthophyllite, tourmaline, graphite.

10. Labradorite, ilmenite, magnetite, hypersthene; constituting a labradorite

granite-like rock.

11. Oligoclase, albite, danburite, sphene; oligoclase, tantalite, and other tanta-

lates, allanite.

- 12. Serpentine, diallage, hornblende, pyroxene, (var. sahlite and diopside common). pyroselerite, chromic iron, brucite, hydromagnesite, aragonite, dolomite, emerald nickel, pyrope.

 13. Quartz, and the various zeolites, with pectolite, wollastonite, prehnite, datholite, chlorite, chlorophæite, and sometimes spathic iron; in amygdaloid; the prehnite or datholite lowest when occurring with the zeolites; and next analcime; quartz either below or above."
- 14. Olivine, augite; magnetite or ilmenite, labradorite, with sometimes leucite and sodalite; in basalt, or augitic lava.

 15. Andalusite; in clay slate.

Manganesian epidote, greenovite, heteroclin.
 Chlorite, sphene, hornblende, chlorospinel, garnet, epidote, rutile, magnetite,

- specular iron, quartz.

 18. Tin ore, the tungsten ores wolfram and scheelite, molybdenite, magnetic pyrites, tourmaline, fluor, beryl, topaz, apatite, pyrochlore, lepidolite, native bis-muth; in granite or gneiss; lodes less common in mica slate, hornblende slate, or clay
- 19. Native gold, tetradymite, pyrites, bismuth needle ore, copper pyrites, galena, blende, rutile, magnetite, ilmenite, specular iron, in quartz veins intersecting talcose

^{*} See on this subject, a paper by the author, in the Am. J. Sci., xlix, 49, 1845.

and chloritic rocks or slates, or in these rocks near the veins; kyanite, brookite, monazite, garnet, platinum, iridium ores, and diamond, often in the same regions.

20. Specular iron, spathic iron, sulphuret of nickel, (millerite).

21. Specular iron, or magnetite, hornblende, epidote, black or dark red garnets, spatite, sphene, in gneiss or granite, &c.

22. Franklinite, red zinc ore, willemite, magnetite, hornblende, brown garnet, ealcite, &c.

23. Cobaltine and other cobalt and nickel ores, mispickel, magnetic pyrites, axinite, glaucodot; also with copper pyrites, linnæite.

24. Magnetite, bitter spar, dolomite; disseminated in crystals through talcose and chlorite slates.

25. Galena, blende, salts of lead, often copper pyrites, as a large constituent of the vein of galena; calcite, sometimes heavy spar, spathic iron, quartz or fluor as

gangue; with pyrites, &c., the blende having a black color when associated with pyrites, (Breit.); also tetrahedrite, &c.

26. Tetrahedrite, antimonial lead ores, galena, spathic iron, copper pyrites.

27. Red silver ore, silver glance, native silver, freialebenite, stephanite, spathic iron, argentiferous galena, antimonial lead ores, native arsenic, bournonite, calcite; in veins in gueiss, metamorphic slates, &c., the chlorid and bromid of silver usually in upper part of bed or vein, and in Chili near junction of stratified and igneous rocks; also often ores of nickel, cobalt, uranium, bismuth.

28. Limonite, wad, pyrolusite, red copper, phosphates of iron, kaolin; sometimes malachite, azurite, copper pyrites, gibbsite.

29. Copper glance, erubescite, native copper, malachite and other salts of copper, red copper, pyritous copper, (below in the lode), pyrites, often galena, &c.; the red copper, malachites, and native copper in upper part of lode.

30. Calamine, smithsonite, usually with galena and blende, and most commonly in statified limestone.

in stratified limestone.

81. Gypsum, sulphur, anhydrite, boracite, selenite, calcite, sometimes with fluor.

PART IV.

TAXONOMY.

I. MINERALOGICAL SPECIES.

It has already been remarked, that the power of crystallization in the inorganic kingdom is, in a certain sense, analogous to that of vitality in the other kingdoms of nature. As in these kingdoms, therefore, the existence of species and their peculiarities depend on the action of this vitality, so in the organic kingdom the existence and individuality of species are determined by the power of crystallization. It must be understood that the term crystallization, as here used, includes not merely the action of the attraction that aggregates the molecules in the formation of a crystal, but also the power that fixes the form and condition of the molecule.

Regularly crystallized minerals alone, therefore, are properly perfect individuals in the mineral department; imperfect crystallizations, like the monsters among organic bodies, have arisen from a suspension of the regular plan of nature by some extraneous influence. It would, hence, be theoretically correct, and in accordance with the practice in the sciences of Botany and Zoology, to confine the term species to perfectly crystallized individuals, and in the descriptions, to give their characters alone, reserving for subsequent remark, the imperfect crystallizations or mineral monsters. But inorganic nature differs from organic, in this essential particular, that while in the latter, exceptions to this regular organizing action are but seldom observed, in the former, they are far the most numerous, perfect individuals being of comparatively rare occurrence.

A mineral species, therefore, is any natural inorganic substance, composed of particles capable in favorable circumstances of combining by means of their mutual attractions so as to constitute a crystalline solid.

We thus include among mineral species the liquids found in nature, for they require only a proper temperature, or favorable circumstances of pressure, and a freedom from disturbing causes, to enable them to assume a regular crystalline form. The conditions of liquidity, gaseity, and solidity, are only different physical.

states of substances, and are never admitted as specific distinctions; much less can they separate one division of inorganic species from another, and thus be made a criterion for limiting the mineral department. We also include all natural inorganic products, in which a tendency to crystallization can be detected, although they have never been observed in regular crystals. We exclude all mechanical aggregates, which, as they are composed of heterogeneous particles, can never assume, from any innate powers, the forms of a crystalline solid.

This definition implies that the substance in the case of each species is a definite chemical compound, as such only are of homogeneous composition. But chemical analysis is not therefore always an available test of the homogeneity of a crystal; crystallization is quite as generally important as a test of chemical com-

bination, and is often referred to for this purpose.

The question still arises, what is distinctively a mineral species? By some authors, every separate chemical compound among minerals has been arranged as a separate species, howeverlike others in crystallization or physical characters. But since it has been found that, in accordance with the principles of isomorphism, there are elements which may replace one another indefinitely and still the form of the crystals remain the same, crystallization has been assumed as the only authoritative test of identity or distinction of species: and this idea has been the means of greatly simplifying the science. The species garnet would make, according to the old chemical view, a dozen or more species. The species hornblende includes a still greater variety of different chemical compounds. Indeed, as magnesia, lime, protoxyd of iron, and protoxyd of manganese, are substitutes for one another in all proportions, the species based on composition alone would be without number. Isomorphism has thus come to the aid of the science, and removed much perplexity. In some instances, however, this principle has seemed inadequate, and while those regarding the crystallographic criterion as paramount have retained together the varieties of like crystallization, others insisting upon a seeming incompatibility of chemical formula have widely distributed them. The species Epidote and Tourmaline are examples. But research may yet discover a principle (if not already accomplished) which will embrace these seemingly anomalous cases, and establish the canon that individuals of analogous constitution which are one in crystallization, constitute a single species; they are at least so far identical as to pertain naturally to a common group, whether we call it a genus, family, or species, or by any other name. The canon must be allowed some flexibility in the present state of science.

Minerals are so seldom in distinct crystals, that it becomes necessary to weigh well what importance should be attached to

other characters.

After crystallographic characters, chemical composition takes the highest place, or rather both are on the same level. The physical characters differ much in value.

 Lustre.—The distinction of metallic lustre from non-metallic, is of the first importance; but all the different kinds of non-metal-

lic lustre are sometimes presented by the same species.

2. Streak .- A highly important character, seldom varying with

the color of the mineral.

- 3. Hardness.—The liability of some minerals to decomposition, their accidental impurities, and the mechanical states they may present, render this in certain instances a character of some uncertainty. An allowance of 0.5 at least, should usually be made for variation.
- 4. Specific Gravity.—Subject to variation, like hardness, especially through variations in composition arising from impurities and substitution of isomorphous substances in the composition of species.

5. Color.—Subject to but little variation in those species that have a metallic lustre, and not without some value in the discrim-

ination of non-metallic minerals.

6. Diaphaneity.—Subject to wide variations in the same species.
7. State of Aggregation.—More especially useful among the metallic minerals, and occasionally among the non-metallic species.

8. Taste.—Useful only among the soluble minerals.

9. Fracture.—Seldom of much value except in distinguishing

varieties.

10. Refraction, Polarization.—Of great value in determining the character of crystallized substances, whose form is not distinct. By these means, species have been distinguished when the mineral was invisible unless magnified. The properties of elasticity and conductility of heat afford analogous results.

11. Phosphorescence, Electricity, Magnetism, and Odor, are

each of limited importance.

In the determination of minerals, and especially the institution of new species, the value of the above characters should be well weighed. With distinct crystals, identity or non-identity may be fully ascertained. And with two or more concordant chemical analyses, when the species is crystalline and homogeneous, the determination may be as satisfactory. But when not obviously crystalline, and especially if earthy and opaque, analysis is often unsatisfactory, as there may be reasonable doubts of the homogeneity of the substance. Physical characters, without chemistry or crystallography, seldom afford a proper basis for the institution of a species.

Haste in making species is the bane of the Science; and every bad species, introduced through carelessness or a worse reason, cannot fail to prove a millstone to the reputation of its author.

II. CLASSIFICATION OF MINERALS.

In the classification of minerals it must be fully understood that we are dealing with but a small part of the third department of nature—the Inorganic Kingdom. The term Mineral Kingdom, so often used, is fundamentally erroneous, although all natural products not organic may be embraced under it. The distinction between natural and artificial inorganic products is convenient for the student, but is contrary to strict science; for nothing authorizes the wide separation usually admitted but the necessities of the school-room, or the fact that mineral information is the A B C of another science, and the basis of certain arts. Any classification therefore that can claim to be perfect, must take into consideration the whole range of inorganic compounds; and each species should have its place fixed on the broadest principles of the science of inorganic nature. The fullest development of the science of Chemistry is required to give the classification its highest perfection.

While considering the relations of Species, it should also be observed that some minerals are only the result of the decay or alteration of others. Every species has its perfect state, and also its changes from the influence of various disorganizing causes, which, like disease in organic beings, result in modifications of the type, and it may be in the total destruction of the original mineral. We cannot therefore give the history of a species without embracing these results of alteration, and we shall naturally cluster about the original species, others that originate in their decay, especially such of these results of alteration as are uncrystallized. As usually presented in full title among the other species, they are a burden to the Science. The Science will thus take on a consistent aspect and prove a more efficient handmaid to Geology.

With this restriction, the classification of Minerals must flow directly from the principles of Chemistry.

The true basis for the classification of compounds is found in the relations of the elements. These relations are indicated in a general way in the following classification of them. The elements exhibit their resemblances in their crystallization or isomorphous relations; and in their entering into like compounds with the same or analogous elements. Thus Iron, Chromium, Manganese, form both protoxyds and sesquoxyds, RO and R²O³; Sulphur and Selenium form acids RO³; Arsenic and Phosphorus, Acids R²O³; Tin and Titanium compounds RO³. The affiliations are seen to be most intimate when the stable compounds, or those of most common occurrence, are alike. Iron may exist in the compound RO³ like Tin, but still the metals are rather remotely related, as RO² is the stable and common compound of the latter, while it is not at all so of the

The principles of isomorphism, as well as other considerations, remove Carbonic Acid far from Titanic Acid, although each contains 2 of oxygen.

The arrangement of the elements is as follows:—

- 1. HYDROGEN GROUP. Either RO, R'O', or RO', the most stable and common states of oxydation.
 - 1. HYDROGEN SECTION.—Hydrogen.
 - 2. IRON SECTION.—RO or ROO, the most common or stable state of oxydation. Crystallization mostly monometric, sometimes dimorphous, and then both monometric and hexagonal.—Gold; Platinum, Palladium, Rhothenium, Iridium; Mercury, Silver, Copper, Uranium, Lead; Zinc, Nickel, Cobalt, Manganese, Chromium, Iron, Aluminium, Beryllium, Thorium, Cerium, Lanthanum, Didymium, Yttrium, Erbium, Terbium, Magnesium, Calcium, Strontium, Baryum; Sodium, Lithium, Potassium.
 - 2. Tim Smorion. RO2 the most common and stable state of oxydation; crystallization dimetric.—Tin, Titanium.
- 2. ARSENIC GROUP. Oxyds include the compounds RO³ or R.O., these the most stable or common states of oxydation, and acting as acids.
- 1. Arsenic Section. R²O⁵⁺ a common state of oxydation; crystallization usually hexagonal, sometimes monometric; or dimorphous, and both hexagonal and monometric.—Nitrogen; Phosphorus, Arsenic, Antimony, Bismuth, Osmium,
- 2. SULPHUR SECTION. ROs the most stable state of oxydation; crystallization, (in part), trimetric or monoclinic.—Sulphur, Selenium; Tantalum, Columbium, Tungsten, Molybdenum, Vanadium.
- 3. CARBON GROUP.
- 1. Boron Section. The common oxyd RO3, either a base or acid.—Boron.
- 2. Carbon Section. The common oxyd RO2, always an acid.—Carbon.
- 2. Silicon Section. The common oxyd RO3, always an acid.—Silicon.
- 4. CHLORINE GROUP. Chlorine, Bromine, Iodine.
- 5. OXYGEN GROUP. Oxygen, Fluorine (?).

The Hydrogen Group passes into the Sulphur Section of the Arsenic Group through Chromium, which forms an acid RO's analogous to the Vanadic; also through Iridium and Palladium, which are in part rhombohedral in crystallization. The Arsenic and Sulphur Sections are united through Tellurium, which is most analogous in its characters to the Arsenic Section, but is not known to afford the oxyd R'O'. The Carbon Group is most nearly related to the Hydrogen Group through Boron, whose oxyd BO' may replace the peroxyd bases of Aluminium, Iron, &c.+

^{*} Equivalent to RO if the double atom of the element be taken as adopted in

the table of atomic weights, pp. 184, 185.

† The relations of the elements may be viewed as follows, adopting Laurent's theory with regard to the oxyds. The oxyds RO, R²O, RO², RO², are equivalent to RO, R²O, RiO, RiO; in which 1 of oxygen is combined with a metal in different

The classification of the elements establishes the fundamental points in the classification of compounds or minerals.

The elements of the Hydrogen Group enter as electro-positives,

(1) Into compounds with elements of the Arsenic Group; (2) Into compounds with elements of the Chlorine Group; (3) Into compounds with elements of the Oxygen Group.

The elements of the Arsenic and following Groups also enter into combination with Oxygen.

There are hence the classes-

(1) Sulphurets, Arseniurets, etc.;

(2) Chlorids, Bromids, etc.;

(3) Oxyds.

In each of these divisions there may be Binary Compounds and Double Binary Compounds, the latter consisting of an acid in combination with bases, as the salts; the former being bases alone, either singly or united together, as the ordinary sulphurets, oxyds, &c.

The Binary Oxygen Compounds are either (1) Oxyds of Elements

of the Hydrogen Group; (2) Oxyds of Elements of the Arsenic Group; or (3) Oxyds of Elements of the Carbon Group. The Double Binary Oxygen Compounds or Salts, may be Salts (1) of Acids RO³; (2) of Acids R³O³; (3) of Acids RO³; (4) of

Such are the main points in the classification followed in this work. In general principle it is like that of Berzelius, and therefore closely related to the systems adopted by various authors in mineralogy. The details of the system will be gathered from the synopsis given beyond.

Analogous composition requires that species should be grouped together in the same division; and species that are related in

form constitute a natural group in such a division.

From the facts already stated, it appears that boracic acid should be regarded as a base in all silicates. Datholite is related to Euclase as well as Sphene in both form and formula, if the boracic acid is thus regarded; and Axinite has also the simple oxygen ratio 1:1.

Again, titanic acid in the so-called silico-titanates, acts as a base, this acid RO united with RO being equivalent to R'O', and replacing thus an ordinary peroxyd. See under Sphene, ii, 269.* The true relations of the anhydrous Silicates are made out by

states, virtually equivalents, as they saturate equal quantities of oxygen. These states are R, Rt, Rt, Rt. The metals of the Hydrogen Section in the state expressed by R appear to be monometric and mutually replaceable; in the state of Rt dimetric, as in Tin, Titanium. Chromium in the states H and Rt is related to Iron; in the state Rt it should be classed with Vanadium, as exemplified in the relations of the Chromates and Vanadates. Iron the state of Ri (as in the deutoxyd) is related to Tin and Titanium. The dimor-phone forms of a metal may depend on these different states or conditions. * Also a paper by the Author, in the Am. J. Sci. [2], xvii, p. 218.

taking, as the basis, the oxygen ratio between all the oxyds and the silica, as explained on p. 207. They may for the most part be grouped into four grand sections.

1. Oxygen ratio for the bases and silica 1:3. 2. Oxygen ratio for the bases and silica 1:2.

3. Oxygen ratio for the bases and silica 1:1.

4. Oxygen ratio for the bases and silica 1 to less than 1.

The first group includes one or two doubtful species, Edelforsite a silicate of lime, Mancinite a silicate of zinc. The second includes Augite, Spodumene, Rhodonite, Beryl, &c., and is the Augite The third includes Garnet, Chrysolite, Zircon, Meionite, Idoorase, Epidote, &c., and is the Garnet Section. The fourth includes Andalusite, Topaz, Staurotide, Kyanite, Sillimanite, Sphene, Euclase, Tourmaline, &c., constituting the Andalusite Section.

Besides these, there may be another group, characterized by the ratio 1:1½, represented in Eulytine, (Bismuth Blende), and Leucophane. The composition of Eulytine is however still in doubt.

There are in some cases accessory ingredients, or an excess of base or silica, which cause divergences from these ratios, and indicate another principle which should be recognized alongside of

the prominent central one.

Thus Hornblende and Augite are related in form and so closely in composition that they graduate into one another, and a mineral with the form of one may have the composition of the other. Yet the oxygen ratio of Augite is 1:2, and of Hornblende $1:2\frac{1}{2}$. In Hornblende there is an addition therefore of one eighth to the silica, without removing the species from the Augite type.

Meionite has the oxygen ratio for the bases and silica of the Garnet Section 1:1, and Bischof and Rose regard this as the true ratio of all Scapolite. The analyses of Scapolite give mostly the ratio 1:15, and taking this (as is probably correct) as the Scapolite ratio, there is here an addition of one third to the silica, which does not interfere with close homeomorphism with Meionite.

Again, Sodalite, Haüyne, and Nosean have a like trapezohedral form and also a common composition, except that one contains a portion of chlorid of sodium, another of sulphate of lime, another of sulphate of soda; and the accessory ingredients do not interfere with the fundamental resemblance of the species. In Ittnerite there is the same form and composition, with water as the accessory ingredient. Nepheline and Cancrinite are closely allied to one another both in form and composition, except that the latter includes a portion of carbonate of lime and soda; this addition in Cancrinite causes scarcely any divergence from the angles of Nepheline.

In Staurotide, the oxygen ratio for the peroxyds and silica is mostly 1: 1; yet some good analyses afford the ratio 1: 2; and moreover there is a difference in specific gravity, corresponding with the difference of composition, the ratio 1: \(\frac{1}{2} \) being connected with the highest. In Andalusite the ratio is 1: \(\frac{2}{3} \); yet a chemist analyzing Andalusite and associated Kyanite finds this ratio for the latter, and 1: \(\frac{2}{3} \) for the former, in which last several analysts agree with him. The analyses of Sillimanite afford the oxygen ratios 1: \(\frac{2}{3} \), 1: \(\frac{2}{3} \), and perhaps also 1: 1. The facts therefore go to show that there may be an addition to the amount of silica without altering the type of the species.

In the Feldspars, Anorthite, a well characterized species, has the oxygen ratio for the bases and silica 1:1, as in Meionite. Oligoclase, Andesine, Labradorite, and Albite, are all Triclinic and closely homeomorphous with Anorthite. Yet these species differ from Anorthite in having an increased proportion of silica, and this silica is therefore added without changing the type. 1:1 is therefore the type ratio of the Feldspars, while $1:1, 1:\frac{4}{3}, 1:2$, $1:\frac{4}{3}, 1:3$, are the occurring ratios.

The Micas illustrate the same principle; the type ratio is 1:1, as with the feldspars. The Hydrous Silicates are also in many cases examples of the same, the water often not affecting the type, and the species, if the water is excluded, having an analogy in

form and composition to anhydrous species.

In characterizing the sections of silicates laid down, it is therefore necessary to recognize not only the type ratios for the group, but also the variations on this type that occur. It appears also preferable to make distinct sections of the Micas and Feldspars, as these species form natural groups by themselves. The Feldspar section is characterized by a ratio of 1:3 for the oxygen of the protoxyds and peroxyds, which ratio does not occur in the other sections of anhydrous Silicates.

With respect to the Sulphurets and Arseniurets, an important fact is established by the homeomorphism of the species, as recognized by Frankenheim, viz: that Arseniurets and Sulphurets are related in form, and also in formula, if the halved atomic weight of arsenic be adopted. Thus Fe S', Fe (As, S)', Fe As', are

related compounds.

In the following synopsis, it will be observed, that the species of the first on are associated on the ground of their analogy in the first and divided into groups, according to their crystalline forms. These groups are therefore in many cases mutually dimorphism, in rather pleomorphous. The many cases of pleomorphism and their exact relations, are therefore exhibited in the arrangement.*

The second preasurement published by Professor Gustaf Rose in his Krystallo-

The elementarion which is here adopted, both in its Berzelian features, and its grouped spaces of like crystallization together, is similar to that published in the motion of this work. There are however many modifications introduced, especial; a the arrangement of the Silicates; and greater precision has been given to all of the transactions.

General Review of the Classification of Minerals.

I. NATIVE ELEMENTS.

- I. HYDROGEN GROUP.
- 1. Iron Section.
- 1 Tin Section.
 - II. ARSENIC GROUP.
- 1. Arsenic Section.
- 2. Sulphur Section.
 - III. CARBON GROUP.

II. SULPHURETS, ARSENIURETS, ETC.

L BINARY COMPOUNDS.

- 1. Compounds of Elements of the Arsenic Group with one another, (p. 30).
- Realgar Group. Composition RS. Monoclinic.—Realgar.
 Orpiment Gr. Composition R² S³. Trimetric.—Orpiment, Bismuthine, Stibnite.
- 2. Compounds of Elements of the Arsenic Group with those of the Hydrogen Group.
 - 1. DISCRASITE DIVISION. Composition R² A,* (p. 35).
- 1. Discrasite Gr. Trimetric.—Discrasite.
 - 2. GALENA DIVISION. Composition R.A. (p. 37).
- Galena Gr. Monometric.—Silver Glance, Erubescite, Galena, Cuproplumbite, Manganblende, Syepoorite, Scheererite, Clausthalite, Tilkerodite, Naumannite, Altaita
- 2. Blende Gr. Monometric, Tetrahedral.—Blende.
- Stromeyerite Gr. Trimetric.—Copper Glance, Stromeyerite.
 Pyrrhotine Gr. Hexagonal.—Cinnabar, Millerite, Pyrrhotine, Greenockite, Copper Nickel, Breithauptite.
 - 3. Pyrites Division. Composition R A', (p. 54).
- Pyrites Gr. Monometric.—Pyrites, Hauerite, Smaltine, Chloanthite, Cobaltine, Gersdorffite. Ullmannite.
 Marcasite Gr. Trimetric.—Marcasite, Rammelsbergite, Leucopyrite, Mispickel,
- Glaucodot, Sylvanite.
- Nagyagite Gr. Dimetric.—Nagyagite.
 Covelline Group. Hexagonal.—Covelline.
- 4. SKUTTERUDITE DIVISION. Composition R A³. Monometric, (p. 67.) Skutterudite.

Chemische Mineral-System (1858) has many points in common with the above. Yet in the adaptation of Crystallography to the Berzelian System, the author's method is his own and of earlier date; moreover the peculiarities are many and of a fundamental character. The author however takes pleasure in acknowledging his indebtedness to Prof. Rose's able work, for many invaluable facts and opinions

therein contained.

• A stands for Arsenic, Sulphur, or any element of the Arsenic Group. The halved Atomic Weight of Arsenic is adopted in these formulas.

II. DOUBLE BINARY COMPOUNDS.

- 1. The Persulphuret a Sulphuret of Iron, Cobalt, or Nickel, (metals of the Hydrogen Group), (p. 67).
- Linnæite Gr. Monometric.—Linnæite.
 Chalcopyrite Gr. Dimetric.—Chalcopyrite, Tin Pyrites.
 Sternbergite Gr. Trimetric.—Sternbergite.
- - 2. The Persulphuret a Sulphuret of an element of the Arsenic Section, (p. 72).
- Persulphuret of the form R² S³.—Wolfsbergite, Berthierite, Zinkenite, Miargy-rite, Plagionite, Jamesonite, Heteromorphite, Brongniardite, Chiviatite, Dufre-noysite, Freislebenite, Pyrargyrite, Proustite, Bournonite, Boulangerite, Aikin-ite, Wolchite, Kobellite, Tetrahedrite, Tennantite, Geocronite, Stephanite,
- 2. Persulphuret of the form R2 St.-Enargite, Xanthocone, Fireblende.

III. FLUORIDS, CHLORIDS, BROMIDS, IODIDS.

I. BINARY COMPOUNDS.

- 1. CALOMEL DIVISION. Composition R3(Cl, I, Br), (p. 89).
- 1. Calomel Gr. Dimetric.-Calomel.
 - 2. ROCK SALT DIVISION. Composition R (Cl, I, Br) or RF.
- 1. Rock Salt. Gr. Monometric. Sylvine, Rock Salt, Sal Ammoniac, Kerargyrite, Embolite, Bromyrite; Fluor Spar, Yttrocerite.
 2. Iodyrite Gr. Hexagonal.—Iodyrite, Fluocerite.
- 3. Cotunnite Gr. Trimetric.-Cotunnite.

II. DOUBLE BINARY COMPOUNDS.

Cryolite, Chiolite.

IV. OXYGEN COMPOUNDS.

I. BINARY COMPOUNDS.

I. OXYDS OF ELEMENTS OF THE HYDROGEN GROUP.

a. Anhydrous.

- 1. MONOMETRIC OXYDS, (p. 101).

- Perielase Gr. Composition R O.—Perielase, Red Copper.
 Martite Gr. Composition R² O².—Martite.
 Spinel Gr. Composition R O+R² O³.—Iserine, Irite, Spinel, Automolite, Magnetite, Franklinite, Chromic Irou, Pitchblende.
 Melaconite Gr. Composition R O².—Melaconite (I).
- - 2. HEXAGONAL OXYDS, (p. 110).
- Zincite Gr. Composition R O.—Zincite, Water (?).
 Corundum Gr. Composition R'O'.—Corundum, Specular Iron, Ilmenite.
 Tenorite Gr. Composition R O'.—Tenorite.
- - 3. DIMETRIC OXVDS, (p.-117).
- 1. Rutile Gr. Composition R O'.-Cassiterite, Rutile, Anatase; Braunite, Hausmannite (1).
 - 4. TRIMETRIC OXYDS, (p. 122).
- 1. Chalcotrichite Gr. Composition R O .- Chalcotrichite.

- 2. Chrysoberyl Gr. Composition R² O³.—Chrysoberyl.
- 3. Brookite Gr. Composition R O'.—Brookite, Pyrolusite (1).
- 5. Combination of Oxyds and Chlorids or Sulphurets, (p. 127). Matlockite, Mendipite, Voltzite.

b. Hydrous Oxyds. (p. 128).

- Disspore Gr. Ratio of oxygen of oxyd and water 8: 1. Trimetric.—Disspore, Göthite, Manganite, (!) Polianite (!).
 Limonite Gr. Ratio of oxygen of oxyd and water 2: 1.—Limonite.
 Brucite Gr. Ratio of oxygen of oxyd and water 1: 1. Hexagonal.—Brucite,
- Gibbsite.
- Appendiz. Völknerite, Psilomelane, Wad. Combination of oxyds and chlorids.—Atacamite.

IL OXYDS OF ELEMENTS OF THE ARSENIC GROUP.

- 1. Arsenic Division, (p. 139).
- Arsenolite Gr. Composition R O³. Monometric.—Arsenolite, Senarmontite.
 Valentinite Gr. Composition R O³. Trimetric.—Valentinite, Bismuth Ochre(!).
 Kermesite Gr. Composition R (O, S)³. Monoclinic.—Kermesite.
 Composition, R O⁴.—Cervantite.
- - 2. Sulphur Division, (p. 143.)

- Sulphurous Acid Gr. Composition R O³.—Sulphurous Acid.
 Sulphuric Acid Gr. Composition R O³.—Sulphuric Acid.
 Wolframine Gr. Composition R O³.—Wolframine, Molybdine.

III. OXYDS OF CARBON, BORON, SILICON.

Carbonic Acid, (p. 144). Sessolin, (p. 144). Quartz, Opal, (p. 145).

IL DOUBLE BINARY COMPOUNDS, OR SALTS.

1. Acid of the Form RO3.

I. SILICATES.

- a. Anhydrous Silicates.
- 1. Edelforsite Section. Oxygen ratio of bases and silica, 1:3, (p. 155). Edelforsite, Mancinite.
 - 2. Augite Section. Oxygen ratio 1: 2—varying to 1: 21, (p. 156).
- Augite Gr. Monoclinic.—Wollastonite, Pyroxene, Rhodonite, Spodumene, Hornblende, Acmite, Wichtyne, Sordawalite.
- 2 Babingtonite Gr. Triclinic .- Babingtonite.
- 1. Beryl Gr. Hexagonal.—Beryl, Eudialyte.
- 3. Eulytine Section. Oxygen ratio 1: $1\frac{1}{2}$, (p. 181). Eulytine (!). Leucophane.
- 4. GARNET SECTION. Oxygen ratio 1:1; -varying to 1:4 in Chondrodite, and 1: 4 in Scapolite.
- 1. Chrysolite Gr. Trimetric, (p. 184) .- Chrysolite, Fayalite, Tephroite, Chondrodite.
- 2. Phenacite Gr. Hexagonal, (p. 189).—Willemite, Phenacite.

- 3. Garnet Gr. Monometric, (p. 190).-Garnet, Pyrope, Helvin.
- Scapolite Gr. Dimetric, (p. 195).—Zircon, Idocrase, Sarcolite, Meionite, Scapolite, Melilite, Dipyre (f).
 Epidote Gr. Monoclinic, (p. 206).—Epidote, Allanite, Zoisite, Gadolinite.
 Axinite Gr. Triclinic, (p. 212).—Danburite, Axinite.
 Iolite Gr. (p. 214).—(Perhaps more related to mica section). Iolite.

- 5. MICA SECTION. Oxygen ratio for type 1:1,-varying to 1:13. Structure micaceous, (p. 217).

Muscovite, Phlogopite, Biotite, Lepidolite, Lepidomelane.

- 6. Feldspar Section. Oxygen ratio for type 1:1,-varying to 1:3; oxy en ratio between protoxyds and peroxyds 1:3.
- 1. Leucite Gr. Monometric, (p. 229) .- Sodalite, Lapis-lazuli, Hauyne, Nosean, Leu-
- Nepheline Gr. Hexagonal, (p. 232).—Nepheline, Cancrinite.
 Feldspar Gr. Triclinic or Monoclinic, (p. 234).—Anorthite, Andesine, Labradorite, Oligoclase, Albite, Orthoclase.
- 4. Petalite Gr. Petalite.
 - 7. Andalusite Section. Oxygen ratio 1 to less than 1.
- Gehlenite Gr. Dimetric, (p. 256).—Gehlenite.
 Andalusite Gr. Trimetric, (p. 257).—Andalusite, Topaz, Staurotide, Lievrite (f).
 Kyanite Gr. Triclinic, (p. 263).—Kyanite, Sillimanite.
 Euclase Gr. Monoclinic, (p. 267).—Euclase, Sphene.
 Tourmaline Gr. Hexagonal, (p. 270).—Tourmaline.

b. Hydrous Silicates.

A. MAGNESIAN HYDROUS SILICATES.

- 1. Tale Section. Oxygen ratio for bases and silica (water excluded) 1:3 to 1: 21, (p. 275).
- Tale, Meerschaum, Neolite, Spadaite, Chlorophæite, Crocidolite (1).
- Serpentine Section. Oxygen ratio 1: 2 to 1: 11, (p. 279).
- Pierophyll, Kerolite, Monradite, Aphrodite, Pierosmina Antigorite, Saponite, Serpentine, Deweylite, Hydrophite.
 - 3. Chlorite Section. Oxygen ratio 1:1 to 1:1, (p. 289).

- Oxygen ratio 1: 1.—Hisingerite, Thuringite, Euphyllite, Pyrosclerite (A).
 Oxygen ratio 1: 2.—Pyrosclerite (B), Clinochlore, Chlorite, Delessite.
 Oxygen ratio 1: 2.—Ripidolite, Aphrosiderite, Clintonite, Chloritoid (A).
 Oxygen ratio 1: 2.—Chloritoid (B), Cronstedite, Sideroschisolite, Margarite.

B. NON-MAGNESIAN HYDROUS SILICATES.

- 1. Pyrophyllite Section. Oxygen ratio between bases and silica, water excluded, 1:3 to 1:21, p. 303. (Related to Edelforsite Section of Anhydrous Silicates.)
- Pyrophyllite, Anthosiderite.
- 2. Pectolite Section. Oxygen ratio 1:2 to 1:24, p. 304. (Related to Augite Section of Anhydrous Silicates).
- 1. Apophyllite Gr. Apophyllite (1).
 2. Laumontite Gr. Monoclinic and Augitoid.—Pectolite, Okenite, Laumontite,
- Catapleiite (f).

 2. Dioptase Gr. Hexagonal and Berylloid.—Dioptase, Pyrosmalite.

- 3. CALAMINE Section. Oxygen ratio 1:1, p. 311. (Related to Garnet Section of Anhydrous Silicates).

- Tritomite Gr. Monometric and Garnetoid.—Tritomite.
 Thorite Gr. Thorite, Cerite.
 Calamine Gr. Trimetric.—Calamine, Prehnite. Appendix. Chlorastrolite, Savite, Schneiderite, Carpholite.
- 4. ZEOLITE SECTION. Oxygen ratio of protoxyds and peroxyds 1: 3, p. 317, (as in Feldspar Section of Anhydrous Silicates).

- Analeime Gr. Monometric and Leucitoid, (p. 818).—Analcime, Ittnerite.
 Chabazite Gr. Hexagonal, (p. 819).—Chabazite, Gmelinite, Levyne.
 Gismondine Gr. Dimetric, (p. 322).—Gismondine, Edingtonite, Faujasite.
 Thomsonite Gr. Trimetric. I: I=90°-92°; rarely monoclinic, and when so, still homeomorphous with the trimetric species. No perfect pearly cleavage. (p. 323).—Harmotome, Phillipsite, Thomsonite, Natrolite, Scolecite, Sloanite.
 Stilbite Gr. Monoclinic or trimetric; a perfect pearly cleavage, (p. 380).—Epistilbite, Heulandite, Brewsterite, Stilbite, Caporcianite.
- 5. Datholite Section. Oxygen ratio 1 to less than 1. (Related to Andalusite Section of Anhydrous Silicates), p. 334.

Datholite; Allophane, Schrötterite. Appendix to Hydrous Silicates, (p. 887).

c. Unarranged Silicates containing Titanic Acid, (p. 341).

Keilhauite, Tscheffkinite, Schorlomite, Mosandrite, Wöhlerite.

- IL TANTALATES, COLUMBATES, (TITANATES), TUNGSTATES, MOLYBDATES, VANADATES, CHROMATES, (p. 344).
- Monometric.—Oxygen ratio 1: 2.—Perofskite, Pyrochlore, 1. Pyrochlore Gr.
- Pyrrhite (1).

 Scheelite Gr. Dimetric.—Oxygen ratio of bases and acid 1: 3.—Scheelite, Schee-

- letine, Wulfenite, Azorite (?).

 1. Fergusonite Gr. Dimetric. Oxygen ratio 2: 1.—Fergusonite.

 1. Image: I. I=100°-102°.—Tantalite, Wolfram, Columbite, Tantalite Gr. Trimetric; I. = 100°-102°.—Tantalite, Wolfram, Columbite, Samarskite, Mengite.
 Polymignyte Gr. Trimetric; I: I=901°-95°.—Polymignyte, Polycrase, Es-
- chynite, Euxenite, Rutherfordite.

 6. Yttrotantalite Gr. Oxygen ratio 1: 1.—Yttrotantalite.

7. Vanadates, Chromates. Crocoisite, Melanochroite, Dechenite, Descloizite, Vanadinite, Volborthite, Aræoxene.

III. SULPHATES—SELENATES.

- 1. ANHYDROUS, (p. 364).
- 1. Celestine Gr. Trimetric.—Glaserite, Thenardite, Barytes, Celestine, Anhydrite, Anglesite, Almagrerite, Leadhillite,

 1 Dreelite Gr. Rhombohedral.—Dreelite, Susannite.
- & Glauberite Gr. Monoclinic.—Glauberite, Lanarkite. Appendix. Connellite, Selenate of Lead, Reussin.
 - 2. Hydrous, (p. 376).
- Misenite; Polyhalite; Gypsum, Astrakanite; Mascagnine; Coquimbite; Cyanosite; Alunogen; Alum; Epsomite, Goslarite; Copperas, Bieberite, Pyromeline, Johannite; Glauber Salt; Botryogene; Copiapite; Apatelite; Alunite, Jarosite; Websterite; Pissophane; Linarite; Brochantite; Letteomite; Medjidite, (p. 876-896).

IV. BORATES.

Boracite, Rhodizite; Hydroboracite; Hayesine; Borax; Lagonite; Larderellite; Warwickite, (p. 892-895).

2. Acid of the Form R'O'.

V. PHOSPHATES, ARSENATES, ANTIMONATES, NITRATES.

- 1. Annydrous Phosphates, Arsenates, Antimonates.
- Apatite Gr. Hexagonal.—Oxygen ratio of bases and acids, (exclusive of fluorid or chlorid), 3: 5, (p. 396).—Apatite, Osteolite, Cryptolite, Zwieselite, Pyromorphite, Mimetene.

- Xenotime Gr. Dimetric. Oxygen ratio 3: 5, (p. 401).—Xenotime.
 Monazite Gr. Monoclinic. Oxygen ratio 3: 5 to 4: 5, (p. 402).—Monazite, Wagnerite, Kühnite, (f) Lazulite.
- 4 Triplite Gr. Trimetric. Oxygen ratio 3: 5 to 4: 5, (p. 406).—Triphyline, Triplite.
- 5. Fischerite Gr.* Trimetric. Oxygen ratio 6: 5, (p. 408).—Fischerite, Peganite.
 6. Romeine Gr. (p. 410). Romeine. Appendix. Hopeite, Amblygonite, Herderite, Carminite.
 - 2. Hydrous Phosphates, Arsenates.
- Thrombolite; Stercorite; Struvite; Haidingerite; Pharmacolite, Vivianite, Erythrine, Nickel Green, Köttigite, Symplesite, Scorodite; Libethenite, Olivenite; Euchroite; Arseniosiderite; Pharmacosiderite; Beudantite; Wavellite, Cacoxene; Childrenite, Erinite; Cornwallite; Phosphochalcite; Tyrolite; Delvauxene; Dufrenite; Aphanesite; Chalcophyllite; Liroconite; Uranite, Chalcolite; Carphosiderite; Plumboresinite; Castelnaudite, (p. 412-432). Sulphato-phosphates: Pitticite; Diadochite, (p. 482).
 - 3. NITRATES.

Nitre: Nitratine; Nitrocalcite, (p. 433, 434.)

3. Acid of the Form RO.

VI. CARBONATES.

- 1. ANHYDROUS CARBONATES.
- Calcite Gr. Rhombohedral. R:R=105°-108°, (p. 485).—Calcite, Magnesite, Dolomite, Breunnerite, Mesitine, Chalybite, Diallogite, Smithsonite.
 Aragonite Gr. Trimetric. I: I=116°-119°, (p. 448).—Aragonite, Witherite, Strontianite, Bromlite, Manganocalcite, Cerusite.
- 8. Barytocalcite Gr. Monoclinic, (p. 458).—Barytocalcite.
 - 2. Hydrous Carbonates.

Carbonate of Ammonia; Trona; Thermonatrite; Natron; Gaylussite; Lanthanite; Hydromagnesite; Malachite; Azurite; Aurichalcite; Zinc Bloom; Emerald Nickel; Remingtonite; Liebigite; Bismutite, (p. 454-457).

4. Acid of the Form R'O'.

VII. OXALATES.

Whewellite; Oxalite; Conistonite, (p. 464, 465).

[•] This group (p. 408) should be transferred to the section of Hydrous Phosphates, &c.

V. RESINS-ORGANIC COMPOUNDS.

Amber; Copaline; Middletonite; Retinite; Scleretinite; Guyaquillite; Piauzite; Walchowite; Bitumen; Idrialine; Pyropissite; Brewstoline; Elaterite; Scheererite; Könlite; Fichtelite; Könleinite; Hartite; Hartine; Ixolyte; Hatchettine; Ozocerite; Chrismatine; Depplerite; Dinite; Mellite.

III. NOMENCLATURE.

A systematic nomenclature like that for botany and zoology, is out of place in this science, except it be based upon relations among the whole range of inorganic products. Moreover, it is not necessary nor desirable.* The number of minerals known is less than seven hundred, and the double names of Natural History, therefore, can well be dispensed with. The addition of the termination ite or lite, (originally from $\lambda i \theta o \epsilon$, stone), answers sufficiently well the purposes of science.

The best names allude to some prominent characteristic of the species; others are given in honor of those who have labored in the science, or in reference to a prominent locality of a species. It should be remembered that the use of names of persons eminent in other sciences, or of such as are ignorant of all science, is wholly at variance with good usage and propriety; moreover; an attempted flattery of the politically distinguished is degrading to science, and cannot be too strongly discountenanced. It is important that the names when taken from a locality, or the name of a person, should retain their original orthography; and also when not thus derived, that they should be of Greek derivation.

† Von Kobell has published a valuable work on Mineralogical Nomenclature, entitled, "Die Mineral-Namen," etc. München, 1853.

The author has here departed widely from principles deemed important in the first two editions of this treatise. The arrangement of Mohs, followed in the main in those editions, cannot stand the test of the developments of science. Even on its assumed ground of being a natural system, it is in many parts singularly artificial; being little better in some of its groupings than an ancient classification of plants which arranged the hard wood species in one group, the herbaceous in another, or collected together flowers of a color. For it is on no better ground that the diamond is placed alongside of topaz and sapphire; spathic iron near heavy spar, (instead of near calcite); graphite near psilomelane; allophane with green malachite; mics in the same order with cronstedite, spodumene with prehnite; iolite with quartz and chrysolite: and so on. Yet in justice to this Mineralogist of merited celebrity, it should be said, that very many natural groupings were embraced in his classification—far more, indeed, than in any of the chemical systems of that time, for the latter refusing almost all reference to physical characters, and considering only the elements present, instead of the mutual relations of the constituent elements, broke up species into fragments and strewed them about into most heterogeneous assemblages.

PART V.

DETERMINATIVE MINERALOGY.

In the following Tables for the Determination of Minerals, the student is supposed to have the requisite means for determining the blowpipe and ordinary chemical characters of minerals, so far at least as to be able to test-*

1. The effervescence or non-effervescence with the three mineral acids.

2. The solubility, more or less perfect, in these acids, cold or hot, or the insolubility of a mineral in the same reagents.

3. The presence of water by subjecting the mineral in a matrass or tube closed below, to the blowpipe heat.

4. The character of the water or fumes given off with the acids or heat, whether containing fluoric or other acids, or alkaline.

5. The blowpipe reactions for sulphur, phosphorus, boracic acid, and other cases of this kind.

6. The presence of arsenic, and each of the volatile metals; also of copper, lead, &c.

The student is advised to study well the use of the blowpipe, and the various effects of the fluxes; and for this purpose Whitney's translation of Berzelius on the Blowpipe, (published at Boston), will be found the best guide in the English language.†

Two tables are here given, one in which the general divisions are based on lustre, streak, and blowpipe and chemical characters; and another, in which the species are arranged under the several systems of crystallization.

large and full work on the subject, giving the most recent facts, and including also reactions with acids and other chemical reagents.

[·] It is obvious that for correct results, the testing should be carefully performed. It is obvious that for correct results, the testing should be carefully performed. It is not sufficient in trying for carbonic acid, to put a drop of dilute acid on the specimen; for carbonate of lime may be present as an impurity, and give rise to effervescence: a fragment should be tested in a test tube and its complete solution and effervescence to the end ascertained. To ascertain whether a mineral yields a malleable globule before the blowpipe with the fluxes, sods should be tried, if not successful with borsz, and in some cases expellation is necessary.

† Plattner's "Die Probirkunst mit dem Löthrohre" (8d edit., Leipzig, 1858) is a large and full work on the subject, giving the most recent facts, and including also

Before presenting the Tables for determining species, a few facts upon some prominent minerals may be stated, that may aid the

student in naming the specimens of his Cabinet.

1. Quartz.—No mineral is more common, or more varying in its colors, than quartz. It is the most abundant ingredient of gravel beds, of the pebbles of the fields, and of the sands of shores, as well as a characteristic ingredient of granite and many rocks. It will therefore be everywhere encountered by the student. He will hardly err in pronouncing a specimen to be quartz, whatever the color, if on trial he finds it equal to 7 in hardness, and therefore scratching glass with facility and not attacked by a file—not at all cleavable—infusible before the blowpipe—not acted upon by acids hot or cold—easily dissolved to a bead before the blowpipe with carbonate of soda—specific gravity not over 2.84. After a little experience, the hardness and absence of cleavage will suffice to determine it in almost all its varieties.

Calcite.—The mineral next in abundance to quartz, and as varied in its aspects, is limestone or calcite. Here—a knife-point easily scratches the surface—a drop of dilute muriatic acid causes an immediate effervescence—the blowpipe does not produce fusion, but gives an intense light, and the mineral after heating is alkaline, (being reduced to quicklime)—the specific gravity is not over 2.8—and when not compact massive, there is a very perfect cleavage.

Zeolites.—The hydrous silicates of alumina and some alkali or earth (potash, soda, or lime) are often called zeolites. They are most commonly found associated together in cavities or seams in amygdaloidal rocks, though occurring also in other rocks, as granite, &c. On page 317, Vol. II, several groups are mentioned. The Stilbite group is distinguished by its pearly cleavage; the forms are often laminato-radiate, and a drusy surface of a crystalline mass is made up of narrow oblong projections.

In Group IV, there is no perfect pearly cleavage; the forms are often acicular, and radiated masses consist of slender fibres, with the exterior often made of the squarish blunt or acute extremities of crystals. The other groups do not present fibrous forms; the species occur mostly in short and stout glassy crystals, analcime showing usually faces of the trapezohedron (f. 39) and characteristics.

bazite often in rhombohedrons which are nearly cubes.

Hornblende, Pyroxene, Epidote.—These minerals fall among anhydrous species that are fusible before the blowpipe and have an uncolored streak. Epidote has commonly a characteristic yellowish-green color, and this variety is unlike any pyroxene or hornblende; it shades into brown, gray, and grayish-white, and may sometimes be red. Hornblende and Pyroxene vary from white to black through grass-green and olive-green shades. Hornblende and Pyroxene are distinctly cleavable, and prisms when broken longitudinally often show a cleavage plane or splintery look; Epidote has no very distinct cleavage, and the crystals

and columnar forms have a more solid aspect, with a smoother surface, without any splintery appearance in the fracture or a tendency to further subdivision of the columns. In this last it resembles columnar Tourmaline, which is also distinct from Hornblende in its more compact look, with no vertical lines of cleavage in the several fibres or columns.

Hornblende and Pyroxene are often distinguished with difficulty when not in crystals, except by the aid of chemical analysis. The crystals of Hornblende are often six-sided prisms, with angles approaching 120° (two angles of 1241° and four of about 118°) or rhombic prisms of 124½°; while Pyroxene crystals are as commonly four-sided prisms near 90° in angles, (87° 6′ and 92° 54′), or eight-

sided prisms near 135° in each angle of the prism.

Feldspars.—The feldspars are 6 to 7 in hardness, and occur either in tabular crystals or cleavable massive; never fibrous columnar and rarely granular; the lustre is vitreous, sometimes inclined to pearly, and the colors are white to flesh-red common; but sometimes bluish, greenish, and brown. There is one perfect cleavage, giving a smooth surface; another less perfect, at right angles, nearly or quite, with the former: if at right angles the species is Orthoclase; if varying three or four degrees from ninety, it is triclinic and therefore some other feldspar.

Spodumene is a whitish, grayish, or pale greenish mineral, resembling a feldspar; but it has two very distinct cleavages

making between them an angle nearly of 135°.

Micaceous Minerals.-The following are the names of the only unmetallic minerals that are properly micaceous in any of their varieties-that is, which consist of very thin, easily separable

 Muscovite, Phlogopite, Biolite, Lepidolite.—Closely related, with laminæ elastic, unless they have undergone alterationaffording no water, or only a trace in a tube-B.B. fusing only on the edges; with acids, little or no action; with cobalt solution sometimes a clear blue, but usually dull. G.=2.75-3.2; H.=1.5

—2. See further, pp. 221 to 227.

2. Pyrophyllite, Margarite, Euphyllite.—Laminæ, (excepting in Pyrophyllite), rather brittle, colors white or pale, affording water in a tube; B.B. fusing on thin edges; Pyrophyllite swells out. With acids, little or no action; a blue color with cobalt solution. G = 2.7 -3·1; H.=3·5-4·5, (1·5 in Pyrophyllite.) See pp. 291, 300, 303.

3. Chlorite, Ripidolite, Clinochlore, Pyrosclerite.—Laminæ not elastic, flexible, affording water in a tube-feel often a little greasy-B.B. fusing on the edges, more easily than the preceding; in cobalt solution no blue color. Somewhat attacked by acids; colors mostly dark green, except pyrosclerite, which is often reddish. See further, pp. 291-296.

4. Talc.—Like the last in most of the characters, but laminæ

more greasy, much softer, and less thin, and color mostly very

pale green; B.B. infusible, and with acids not dissolved; with cobalt solution, with some difficulty, a reddish color.

5. Brucite.—Somewhat like talc, whitish or greenish in color; B.B. infusible, heated in a tube affords water; in the acids entirely

soluble without effervescence. See further, p. 133.
6. Diallage, Hypersthene, Bronzite, Clintonite, Chloritoid.— Often nearly micaceous, though more properly foliated. The laminæ are brittle, and do not separate easily. The same is true of Marmolite, which has some resemblance to talc, and differs from the species just enumerated in having a greasy feel.

7. Gypsum.—A crystallized variety: it is very soft, laminæ separable, hardly flexible without breaking, often transparent, and generally colorless. B.B. whitens and crumbles, but fuses only

with difficulty.

8. Uranite, (p. 430), Red Zinc Ore, (p. 110), Copper Mica, (p. 428).—Uranite is bright green, or yellow; Red Zinc Ore is bright or deep red; Copper Mica is deep green. Crystals of Uranite are square tables, and those of Copper Mica hexagonal. Copper Mica gives a copper reaction; Red Zinc Ore is oxyd of zinc. Erythrine (Cobalt Bloom) is peach-blossom red in color, with often a bluish tinge. Pharmacolite and Vivianite have also a very perfect cleavage in one direction.

The classification in the body of the work may be conveniently used in determining species. A specimen, for example, may be easily ascertained to be a sulphate, and next a hydrous sulphate, if such; and then by turning to the section containing hydrous sulphates, a few further trials will enable the student to ascertain which of the species described he has in hand. To facilitate the use of the work in this way, a few remarks on certain compounds, in addition to those to be derived from the chapter on chemical tests and blowpipe analysis, are here offered, and also an index to some of the prominent classes of species.

Sulphurets, Sulphates.—Sulphurets may have a metallic lustre, or an unmetallic lustre with a colored streak. Only Blende (sulphuret of zinc) and Voltzite (an oxysulphuret of zinc) have an unmetallic lustre and an uncolored streak. Consequently, with these exceptions, any unmetallic species with an uncolored streak which contains freely of sulphur, must be a sulphate. The sulphates are all unmetallic in lustre, and they are often colorless. Helvin,

Hanyne, and Nosean are silicates containing a very little sul-

Phosphates.—All the phosphates have an unmetallic lustre. The streak may be colored or uncolored. None of them are soluble in water, or have taste, excepting a single phosphate of ammonia; and the pure phosphates give no odor in any way before the blowpipe. Besides the direct test for phosphorus, the tests for carbonic acid, boracic acid, sulphur, separate them from the carbonates, borates, and sulphates; the test for fluorine from fluorids, although traces of fluorine often occur in phosphates; the complete solubility (without gelatinizing) in muriatic acid, hot or cold, distinguishes them from the silicates. There are the following exceptions to this last character: viz., Xenotime, Childrenite, Monazite, Turquois, Lazulite, which are also B.B. infusible.

Molybdates, Tungstates. - The Molybdates and Tungstates are unmetallic in lustre. The streak is colored, (yellow or yellowish, rarely red from chrome,) excepting in Scheelite, which is often white.

Specific gravity never under 6.

Columbates, Tantalates.—Mostly submetallic in lustre, with an iron-black, velvet-black, or brownish black color. But Wöhlerite and Pyrochlore are yellow to brown, and Yttrocolumbite yellow to black; streak yellowish to nearly colorless.

See in the second volume for description of species of-

Sulphurets, not containing Arsenic, Bismuth, Selenium, or Antimony, pp. 37 to 56, 60, 66 to 71, 127.

Arseniurets, or Sulphurets containing Arsenic, Antimony, Bismuth, pp. 31—36, 41, 44, 52—63, 67, 73—88, 141.

Arsenic and Antimony Oxyds, pp. 139—142, 410.

Seleniurets, pp. 42, 43, 52.

Tellurets, pp. 21, 44, 64, 65.
Fluorids, Chlorids, Bromids, Iodids, pp. 89—98, 127, 128, 138, 463.
Sulphates, Anhydrous, p. 364; Hydrous, p. 376; Selenates, p. 375.
Arsenates, Phosphates, Anhydrous, p. 396; Hydrous, p. 411.
Borates, p. 392. See also Silicates containing Boracic Acid, Danburite, Axinite, Tourmaline, Datholite.

Tourmaline, Datholite.

Nitrates, p. 433.
Carbonates, Anhydrous, p. 434; Hydrous, p. 454.
Vanadates, Chromates, pp. 359—364.
Columbates, Tantalates, Tungstates, Molybdates, pp. 345—358.
Ores of Silver, Sulphurets, pp. 37, 48; Sulpho-arseniurets, Arseniurets or Antimoniurets, pp. 35, 75—88; Seleniurets, p. 43; Tellurets, pp. 44, 64; Chlorid, Bromid, Iodid, pp. 92, 93, 95.
Ores of Quicksilver, Sulphurets, pp. 48; Seleniuret, p. 52; Chlorid, Iodid, p. 89, 96.
Ores of Copper, Sulphurets, pp. 38, 46, 65, 68; Arsenical or Antimonial, pp. 36, 73, 77, 82, 84—88; Seleniurets, pp. 43; Oxyds, pp. 101, 109, 117, 122; Oxychlorid, p. 138; Silicate, p. 309; Chromates, p. 360; Sulphates, pp. 375, 389, 391; Phosphates, Arsenates, pp. 412, 419—421, 425, 426, 428, 429; Carbonates, 458.
Ores of Lead, Sulphurets, pp. 39, 41; Seleniurets, p. 42; Tellurets, pp. 44, 65; Antimonial Sulphurets, pp. 74—88; Chlorid, p. 97; Oxyds, pp. 109, 117, 126; Oxychlorid, p. 127; Tungstate, p. 348; Molybdate, p. 349; Chromate, Vanadate, pp. 259—362; Sulphata, 370—374, 390; Selenate, p. 375; Phosphate, pp. 400, 431; Arsenate, p. 401; Carbonate, 462.
Ores of Cobalt and Nickel, Sulphurets, pp. 41, 42, 49, 67; Bismuth, p. 45; Antimonial or Arsenical, pp. 52, 53, 56—59, 61, 63, 67; Sulphate, p. 385; Arsenate, pp.

soonial or Arsenical, pp. 52, 53, 56-59, 61, 63, 67; Sulphate, p. 385; Arsenate, pp. 416, 418; Carbonate, 461.

Ores of Iron, Sulphurets, pp. 50, 54, 60, 68; Arsenical or Antimonial, pp. 61, 62, 78; Oxyds, pp. 102-106, 113-116, 129, 131; Sulphate, pp. 380, 383, 385, 387, 289; Borate, pp. 395,; Phosphate, pp. 399, 406-408, 415, 424, 427, 431; Arsenate, 444.

Ores of Zine and Cadmium, Sulphuret, pp. 45, 51; Oxyd, p. 110; Oxysulphuret, 127; Silicate, pp. 156, 189, 313; Sulphate, p. 384; Phosphate, p. 409; Arsenate, p. 445; Carbouate, 447, 460.

Gree of Biamuth, Sulphurets, pp. 33, 73, 77, 88, 82; Telluric, 21; Silicate, 181;

Count, 141; Carbonate, 462.

Lease of Antissony, Sulphurets, p. 38; Oxyds, pp. 140-142, 410.

Lease of Assenie, Sulphurets, pp. 31, 32; Oxyds, p. 139.

Ores of Manganese, Arsenical, p. 53; Sulphuret, p. 41, 56; Oxyda, pp. 118, 125, 130, 135, 136; Silicate, p. 167, 186; Phosphate, pp. 397, 406—408; Carbonate, 146, 452

Ores of Molybdenum, Tungsten, Sulphuret, p. 66; Oxyd, pp. 148, 144.
Ores of Tin, Sulphuret, p. 70; Oxyd, p. 118.
Ores of Uranium, Oxyds, p. 107; Sulphate, pp. 888, 892; Phosphate, pp. 480;
Carbonate, 461, 462.

Ores of Titanium, Oxyd, pp. 120-123; other ores, 115, 268, 845, etc.

The following are the Tables for the determination of Species. By Infusible, or nearly so, is meant either wholly infusible or fusing only with great difficulty on the thinnest edges. The abbreviations employed are explained beyond, (p. 264).

TABLE I.

- I. SOLUBLE MINERALS: MINERALS SOLUBLE IN WATER AND HAVING TASTE.
 - I. Carbonates: effervescing with muriatic acid; fumes inodorous.
 - II. NITRATES: deflagrating more or less on burning coals; effervescing with sulphuric acid and not with nitric or mu-
 - III. Chlorids: effervescing and giving off suffocating fumes with sulphuric acid, and not with muriatic.
 - IV. Sulphates and Phosphates: no effervescence with either of the acids; B.B. a sulphur or phosphorus reaction.
 - 1. Little or no metallic reaction.
 - 2. Reaction of iron, manganese, cobalt, zinc, or copper.
 - V. Borates or Boracic Acid: not effervescing with the acids; B.B. boracic acid reaction.
 - VI. Arsenous Acid: B.B. on charcoal alliaceous fumes.

II. INSOLUBLE MINERALS.

I. LUSTRE UNMETALLIC.

A. STREAK UNCOLORED.

- 4. B.B. NO ODOROUS OR VISIBLE FUMES ON CHARCOAL, WITH OR WITH-OUT FLUXES; GLOBULE OBTAINED BY REDUCTION NOT MALLEABLE,
 - 1. When pulverized, wholly soluble to a liquid state in one or more of the acids, (cold or hot); none gelatinizing.
 - * B.B. infusible or nearly so, (p. 267).

- † Carbonates: when pulverized, effervescing more or less in acids; fumes inodorous, reddening litmus paper.
 †† Sulphates, Phosphates, Oxyds: no effervescence with acids.
 ††† Fluorids, Borates, Oxalates.
- ** B.B. fusible, (p. 269).
 - † Carbonates: when pulverized, effervescing as above. † Phosphates, Sulphates: no effervescence with acids; B.B. a sulphur or phosphorus reaction.

††† Fluorids: a fluorine reaction, and none of phosphorus. †††† Borates: no effervescence; B.B. reaction of boracic acid.

- 2. Soluble in acids; the silica gelatinizing: Silicates.
 - * B.B. infusible or nearly so, (p. 271).

** B.B. fusible, (p. 271).

+ Hydrous. + Anhydrous.

- 3. Insoluble in acids, or partly soluble without gelatinizing.
 - B.B. infusible, (p. 274).

† B.B. reaction of sulphur, phosphorus or fluorine. †† Hydrous: B.B. no phosphorus reaction; Hydrous silicates of magnesia, alumina, or oxyd of iron, with opul and hydrates of alumina. ††† Anhydrous, (p. 277).

** B.B. fusible; (includes no phosphates), (p. 280).

† Sulphates: sulphur reaction.
† Hydrous; B.B. no sulphur reaction; G below 3.8.
† Anhydrous: B.B. no sulphur reaction, (Helvin excepted), (p. 282).

- b. B.B. EITHER FUMES, OR A MALLEABLE GLOBULE, (p. 286).
 - B.B. globule of lead with the fluxes on charcoal if not without, and lead oxyd on charcoal; no fumes of Arsenic, Selenium, or Antimony.

** B.B. inodorous fumes of Zinc, Bismuth, Antimony, Tellurium.

*** B.B. odorous fumes of Arsenic or Selenium.

**** B.B. wholly vaporizable, with fumes of Quicksilver and Chlorine.

B. STREAK COLORED.

- a. B.B. NO FUMES WITHOUT OR WITH THE FLUXES; GLOBULE NOT MALLEABLE.
 - * B.B. infusible or nearly so, (p. 288).

† Gelatinize with acids. †† Not gelatinizing with acids.

- ** B.B. fusible, (p. 291).
 - † Gelatinize with acids.
 † Not gelatinizing with acids; B.B. phosphorus reaction.
 †† Not gelatinizing with acids; B.B. no phosphorus reaction.
- B.B. NO FUMES, EXCEPT SOMETIMES OF LEAD; A MALLEABLE METALLIC GLOBULE, (p. 294).
 - B.B. infusible; a globule of tin or copper with soda.
 - ** B.B. fusible; a globule of lead, copper, or silver; no fumes of Arsenic, Sulphur, Selenium, or Antimony.
 - † Gravity below 4.5; Ores of Copper. †† Gravity above 4.5; Ores of Lead, Copper, or Silver.
- c. B.B. vaporizing wholly and easily in fumes, leaving no metallic globule, (unless antimony or bismuth), (p. 296).
- d. B.B. fumes of arsenic, sulphue, antimony or chlorine; leaving a globule which is not malleable, (p. 297.)
 - * B.B. fumes arsenical.
 - ** B.B. fumes not arsenical.
- e. B.B. fumes of sulphur, arsenic, antimony, chlorine, bromine, or iodine; a malleable globule of copper or silver, (p. 298).
 - * B.B. fumes of Arsenic, Sulphur or Antimony.
 - ** B.B. fumes of Chlorine, Bromine, Iodine or Muriatic Acid.

II. LUSTRE METALLIC.

A. STREAK UNMETALLIC.

- a. B.B. no fumes, (p. 300).
 - * B.B. infusible, or nearly so; colors steel-gray to black.
 - † With muriatic acid fumes of Chlorine; contain manganese.

 †↑ No fumes of Chlorine with muriatic acid; (no hydrous species).
 - ** B.B. fusible.
- b. B.B. giving off fumes, (p. 302).
 - * B.B. fumes of Arsenic associated sometimes with Sulphur; globule brittle; color whitish with sometimes a reddish or yellowish tinge, excepting Tennantite, which is black.
 - ** B.B. fumes sulphurous or antimonial, not arsenical; globule brittle; colors rather pale, excepting Manganblende, which is black.
 - *** B.B. a malleable globule, or mineral wholly vaporizable, (p. 304).
 - † B.B. A globule of lead, silver or gold. †† B.B. A globule of copper or tin.

B. STREAK METALLIC.

a. Not malleable, (p. 306).

- * B.B. no fumes; infusible.
- ** B.B. fumes; globule not malleable.
- *** B.B. fumes; malleable globule, or mineral wholly vaporiza-

 - † B.B. wholly and easily vaporizable, (ores of lead not included). † B.B. a malleable globule; fumes odorous. ‡ B.B. a globule of lead or silver, without copper or any copper reac-
 - ‡‡ B.B. a globule of copper, or of silver or lead along with copper; a copper reaction.

 ††† B.B. a malleable globule; fumes inodorous.

b. Malleable, (p. 309).

The following are the abbreviations used in the following pages.

Antim.	Antimony.	Mur.	Muriatic acid.
Arsen.	Arsenical.	Nit.	Nitrie acid.
B, bh.	Blue, bluish,	Op.	Opaque.
BB	Before the Blowpipe.	Phos.	Salt of phosphorus.
Bn, bnh.	Brown, brownish.	P'ly.	Pearly.
Bk, bkh.	Black, blackish.	Pms.	Prisms.
Bor.	Borax.	R, rdh.	Red, reddish.
Cleav.	Cleavage, Cleavable.	Rad.	Radiated.
Cryst.	Crystals, Crystalline.	Ren.	Reniform.
Decrep.	Decrepitate.	Soda,	Carbonate of soda.
Dif.	Difficult, difficulty.	Sol.	Soluble, solution.
Efflor.	Effloresce.	Stalact.	Stalactitic.
Exfol.	Exfoliate.	Stel.	Stellate.
Fib.	Fibrous.	Strl.	Translucent on edges only.
Fol	Foliated.	Strp.	Semitransparent.
Fus.	Fusible, Fusion.	Sulph.	Sulphureous.
Gelat.	Gelatinize.	Submet.	Submetallic.
Gn, gnh.	Green, greenish.	Sul.	Sulphurie acid.
Gran.	Granular.	Trl.	Translucent.
Gy, gyh.	Gray, grayish.	Trp.	Transparent.
Insol.	Insoluble.	Vit.	Vitreous.
Intum.	Intumesce.	W, wh.	White, whitish.
Met.	Metallic.	Yw, ywh.	Yellow, yellowish.

The constituents of the species are in all cases stated, and they are an indication of the blowpipe reactions, both as to whether a mineral affords water in a matrass or not, and the effects of the metallic oxyds and other ingredients present. The page on which the species is described at length is added, that the student may resolve his final doubts by a reference to the full descriptions.

The Roman numerals indicate the system of crystallization, in the order: I, Monometric; II, Dimetric; III, Trimetric; IV, Monoclinic; V, Triclinic; VI, Hexagonal.

After each subdivision in the following Table, there is a catalogue of the species of the subdivision that occur foliated or fibrous in some or all varieties, also a list of the species arranged according to their specific gravities. As species often vary much, they sometimes fall into more than one of the sections in the following Table.

I. SOLUBLE MINERALS, HAVING TASTE.

I. CARBONATES: effervescing with muriatic acid; fumes inodorous.

B.B. either fuse, liquefy, or vaporize.

Carb. Ammonia, Hardness. Whitish crusts. Odor of Ammonia. 454.

Natron, 1—1.5 Crusts: G 1.428; w, gyh; taste alkaline; efflor; Ña, Õ, Aq, 455. Trona has G 2.11, 454. Thermonatrite has G 1.5-1.6, 455.

Gay Lussite, 2—3 IV; cryst; G 1-9—2; ywh-w; vit; taste weak; B.B. decrep, opaque, like calcite. Na, Ca, C, Aq, 455.

II. NITEATES: deflagrating on burning coals; effervescing with sulphuric acid, but not with nitric or muriatic.

Nitrocalcite, Silken tufts, effior; vit; taste sharp, bitter; very deliq;
BB slight deflagration, fuses and dries; Ös, Ñ, Aq, 434.

Nitratine, 1.5-2 VI; rhombohedral; efflor; mas; G 2-2.3; w, bnh, ywh; vit; trp; taste cooling; BB yw flame; Na, Ñ, 483.

Nitre, 2 III; 120°; in crusts; acic cryst; G 1'937; w; wit; strp; taste saline cooling; BB flame not yw; K, Ñ, 433.

III. CHLORIDS: effervescing with suffocating fumes with sulphuric acid, and not with muriatic.

Sal Ammoniac, 1—1.5 Whitish, ywh, gyh; crusts; pungent saline taste; odor of ammonia with soda, 92.

Sylvine, 2 I; mas; w; vit; taste saline; BB flame not yellow; K, Cl, 90.

Common Salt, 2.5 I; eryst; mas; w, ywh, rdh, bh; trp; taste saline; BB flame yellow; Na, Cl, 90.

IV. Sulphates and Phosphates: no effervescence with either of the acids. B.B. sulphur or phosphorus reaction.

1. B.B. little or no metallic reaction. (All but Thenardite, Glauberite, Reussin and Glaserite, contain water.)

Mascagnine, In ywh crusts. Odor of ammonia with soda, 879.

Glauber Salt, 1.5—2 IV; efflor crusts; G 1.48; w, wh; taste cool saline, bitter; BB fuses, flame yw; Na, S, Aq, 386.

Alum, 2—2.5 I; fibrous; crusts; efflor; G 1.75—2; w, ywh, rdh; taste astringent; very soluble; BB intum, spongy; Al, S, Aq, with K, Na, Mg, Fe, Mn or Am, 382.

Epsomite, 2—2.5 III; mas; cryst; G 1.751; w; vit; taste bitter saline;

BB deliq; flame not yw; Mg, S, Aq, 384. Astrakanite, Mg, Na, S, Aq, 379.

Polyhalite, 2—8 III; massive; subfibrous; G 2.7—2.8; rdh; trl, op; taste bitter astringent, very weak; BB fus!!; K, Mg, Ca, S, Aq, 877.

	Hardnes	8.
Thenardite,	2-2.5	III; cryst; G 273; w; vit; trl; effloresces; BB yw flame; Na, S, 365.
Glauberite,	23	IV; cryst; G 27-29; ywh, gyh; vit; taste weak saline; BB decrep; trp glass; Ña, Ĉa, Š, 374.
Reussin,		Prisms; acic; efflor; w; taste saline, bitter; Mg, Na, B, 875.
Alunogen,	2—8	fib; massive; crusts; w, ywh, rdh; vit; silky; taste like alum; BB intum; fus! very sol; \(\frac{\pi}{2}\)l, \(\frac{\pi}{2}\)
Glaserite,	2—8	III; massive; crusts; G 17-175; w, bh; gnh; trl; taste saline, bitter; BB fus; no intum; K, S, 365. Misenite is a sulphate of potash containing water, p. 365.
2. B.B. reaction o	f Iron (ir	Copperas, Botryogen, Iron alum), Manganese (in Mangan-
ese alum). Zir	ne (in Go	oslarite), Copper (in Cyanosite), Cobalt (in Bieberite).
		in Johannite), and Nickel (in Pyromeline.)
Copperas,	2	Crusts; massive; vit; gn, gnh-w; w on exposure; trp,
Copiapite,		trl; taste sweetish-astringent, met; BB magnetic; Fe,
Coquimbite,		8, Aq, 385. Copiapite is yellow; 387; Coquimbite,
Apatelite,		wh, ywh, bnh, 380.
Iron Alum, Voltaite,	2.5	I; crust; G 2; ywh, gnh; taste met-astringent, or chaly- beate; BB iron reaction; Fe, 五l, 5, Aq, 383. Volta- ite is sometimes black, 383.
Manganese Alum,	2.2	I; crusts; fibrous; G 2; ywh, rdh; taste met-astringent; BB manganese reaction; Mn, Al, S, Aq, 882.
Goslarite,	2-2.2	III; incrustations, massive; w; vit; trp, trl; BB intum; taste astringent, met; Zn, S, Aq, 384.
Cyanosite,	2.2	V; massive, earthy; G 2.213; bright blue; strp, trl; taste metallic, nauseous; BB on charcoal copper; Cu, S, Aq, 380.
Bieberite,		IV; stalact; crusts; fesh and rose-red; trp, trl; taste astringent; BB on charcoal sulph; with bor blue; Co, S, Aq. 385.
Johannite.	2-2.5	IV; cryst, massive; G 8.19; vit; emerald green, gnh;
•		streak paler; trp, trl, op; taste bitter; solution bn precip with infusion of nutgalls; Û, Š, Aq, 386.
Pyromeline,		Capill cryst; also as a gnh-w efflorescence; taste met-as- tringent; contains nickel, Ni, S, Aq, 886.
Botryogen,	2-2.2	IV; deep hyacinth-red, ywh; streak ochre yw; trl; taste slightly astringent. BB iron reaction; Fe, S, A, 387.

- V. Borates, or Boracic Acid: not effervescing with the acids; B.B. boracic acid reaction.
- Massive or in scales; G 1'48; w, ywh; p'ly; feel smooth; acidulous; BB fus!! flame gn; B, Aq, 144.
- Hydroborseite, 2 Fibrous and fol like gypsum; G 1-9; w; trl, op; BB fus! trp glass, flame gnh; slightly sol in water; in mur easily sol; Ca, Mg, B, Aq, 898.

Hardness.

Boraz,

3-2.5 IV; G 1.716; w, gyh, bh, gnh; vit; trl, op; taste feebly sweetish-alkaline; BB puffs up, then fuses to a glass; Ña, B, Aq, 394.

VI. Arsenous Acid: B.B. alliaceous fumes on charcoal.

Arsenolite, 1.5 IV; capillary; botryoidal, stalactitic; G 3.7; vit, silky; w, ywh, rdh; trp, op; taste astringent, aweetish, 139.

II. INSOLUBLE MINERALS, OR WITHOUT TASTE.

I. LUSTRE UNMETALLIC.

A. STREAK UNCOLORED.

- **6.** B.B. NO ODOROUS OR VISIBLE FUMES ON CHARCOAL, WITH OR WITHOUT THE FLUXES; GLOBULE OBTAINED BY REDUCTION NOT MALLEABLE.
- 1. When pulverized, wholly soluble in one or more acids (cold or hot) without gelatinizing—Carbonates, Sulphates, Phosphates, Fluorids, Borates, Oxyds.

** Infusible or nearly so.

† Carbonates: when pulverized, effervescing more or less in acids; fumes inodorous.

Obs.—The species are all anhydrous excepting Hydromagnesite, Lanthanite, and Parisite; the last contains also fluorine. All but Lanthanite, Diallogite, and Spathic Iron give an alkaline reaction after strongly heating B.B.

Hydromagnesite, 2-8.5 Fibrous. subfol, earthy, crust; w; in mur efferv; Mg, C, Aq, 456.

Lanthanite, 2.5—8 III; thin plates; earthy; gyh-w, ywh; dull, p'ly; La, Ö, Ĥ, 456.

Calcite,

1-8.5 VI; clear rhombohed; cryst, fibrous, massive; G 2.5-2.78; w, ywh, rdh, bn, bk; vit, subvit, earthy; trp, op; BB intense light, caustic; in mur easy efferv; columns of fibrous var, have an oblique cross cleavage, and in this unlike Aragonite, Ča, Č, 435.

Aragonite, 8:5—4 III; cryst, mas, fib; G 2:9—3; w, gyh, ywh; trp, trl; BB falls to powder; Ča, Č, 448.

Dolomite, 3.5—4 VI; 106° 15'; cleav; rhombohed, cryst, gran, mas; G 2.85—3.1; w, ywh, rdh, bn, bk; vit; strp, op; in mur slow efferv; Ča, Mg, Č, with sometimes Fe, and then bn on exposure, 441.

Barytocalcite, 4 IV; 106° 55'; cleav; G 3.6—3.7; w, gyh, gnh, ywh; trp, trl; BB with bor trp glass; Ba, Ča, Č, 453; Bromlite is same compound trimetric, 451.

H	•	_	•-	-	

Diallogite, 3.5-4.5 VI; el R; clear massive; botryoid, fib; G 3.4-3.6; vit, p'ly; rose-rd; bu on exposure; trl, strl; BB bu, infus, decrep; in hot mur efferv; Mn, C, 446. Manganocalcite (p. 452) is the same compound in rhombic prisms.

Magnesite, 4-5 VI; clear R; cryst, fibrous, massive; G 2.8-3; w, ywh, rdh, bn; trp, op; in mur slow efferv; Mg, Ca, 414.

Spathic Iron, 3.5—4.5 VI; R cleav, massive, foliated; G 3.7—3.85, vit, pl'y; gyh-w, bnh, gnh-gy; bnh-r; trl, op; BB bk, magnetic; in mur sol dif; Fe, Ö, often with Mn, Mg, Ca, 444.

Breunnerite is similar; G 3—363; w, ywh; bn on exposure Mg, Fe, Č, 443.

Parisite, 4.5 VI; cleavage basal! G 4.35; bnh-yw; streak wh, w; vit;

BB bnh; with bor trp glass; in mur slow sol and
efferv; Če, Ča, Č, F, Aq, 463.

Smithsonite, 5 VI; mas botryoid; p'ly, vit; wh, gyh, gnh, bnh; BB fumes of zinc; Zn, C, 447.

a. Very distinctly foliated or fibrous in some varieties.

Hardness,
Hydromagnesite,
2.5 Fol, fib.
Calcite,
Magnesite,
3-3.5 Fol, fib.
Diallogite,
3.5-4.5 Fib.
Spathic Iron, 3.5-4.5 Fol, fib.

B. Species arranged according to their specific gravity.

0.1.01.1.1A. W.	Sp. Gravity.	Distribute -	Sp. Gravity.
Calc Sinter (Ca C)		Diallogite,	3.5-3.6.
Hydromagnesite,	2.1-2.2.	Barytocalcite	3.6-3.7.
Calcite.	2.5-2.78.	Bromlite,	37-372
Magnesite,	2.8-3.	Spathie Iron,	3.7-3.82
Dolomite,	2.85-3.1.	Lanthanite	
Aragonite,	2.9-3.	Parisite,	4:35.
Resummenite	9_2.69	Total Control of the	

†† Phosphates, (Childrenite, Cryptolite, Fischerite); Sulphates, (Alunite); Ozyds, Periclase; or Hydrated Ozyds, (Brucite, Völknerite); no effervescence with acids.

Brueite, 1.5 VI; tables; foliated! laminæ flexible; also fine fibrous;
G 2.35; w, gyh; p'ly! trl, strl; in nit sol, no efferv;
BB op, friable, alkaline; Mg, Aq, 133.

Völknerite, VI; cleav! foliated, massive; G 2.04; w; p'ly; feel greasy; BB exfol; with bor intum, trp glass; in acids sol; Mg, ₹1, Aq, 134.

Apatite, 4.5-5 VI; hexag prisms; also massive; G 3-3.3; green, bh, w, gnh, gyh, rh, bnh; vit, subres, brittle; BB fus diff!! in mur in powder sol; Ca, P, F, 396.

Childrenite, 4.5-5 III; only in cryst; yw, ywh, bnh; vit-res; trl; in mur sol after long ignition; Al, Fe, Mn, P, H, 424.

Alumits, 5 VI; clear basal; massive gran; G 2:5—2:8; w.gyh.

Jarosite, rdh; vit, p'ly; trp—strl; BB decrep; in sul powder

sol; Kl, K, S, Aq, 388. Pissophane is green, Al, Fe, S,

Ĥ, 390.

	LUSTRE	UNIMETALLIO—STREAK UNCOLORED. 269
	Hardnes	•
Cryptolite, Fischerite,	5—5.5	Minute acic hexag pms; G 4.6—4.8; ywh or colorless. BB fus dif!! flame gnh; in sul sol; Ĉe, P, 399. III; erystals; massive; dull gn trl; G 2.46; BB much
Variscite,		water; Al, P, H, 408. Variscite is apple-green, 408.
Periclase,	5—6	I; only in cubes or oct; clear cub; G 8.674; gnh, gn; trp, trl; in hot nit sol, no efferv; Mg, 101.
•	. Very di	stinctly foliated or fibrous in some varieties.
Brucite,		Fol!, fib. Völknerite, Fol.
††† Fluorids, (Yttrocerit	te, Fluocerite),—Borates, (Warwickite),—Oxalates, (Whewellite).
clude a small per	r-centage.	onate containing fluorine, and many phosphates also in- Topaz, Chondrodite, and some micas are infusible sili- Danburite, Tourmaline, Axinite are silicates containing
Yttrocerite,	45	III f; massive, earthy, G 3.4-3.5, violet, gyh, wh, rdh- bn, vit, p'ly; BB with bor glass yw in outer flame while hot; in mur in powder sol yw; Ce, Y, Ca, F, 95.
Pluocerite,	45	VI; hexag pms and plates; massive; G 47, tile-rd, ywh; streak w, ywh; strl—op; BB darkens; Ce, Y, F, 96.
Warwickite,	8-4	Prismatic cryst, imbedded; G 3.188; submet, p'ly, often dull; bn, bkh, gyh, 395.
Whewellite,	2.5—3	IV; cryst and opaline incrust; lustre subadamantine, vitreous; in mur sol; oxalate of line, 464, 465. Conistonite is similar, but trimetric, 465.
** Fusible.	(Apatit	e fuses with great difficulty, and is placed above.)
† Carbonates	: when p	oulverized, effervescing more or less; fumes inodorous.
Witherite, Strontianite,	3—8·75 8·5—4	 III; cryst; massive, subfib; G 4.8; w, ywh, gnh; vit—res; strp, trl; BB fus! in mur efferv; Ba, Ö, 449. III; cryst, massive, fibrous; G 3.6—3.72; gnh; w, gyh,
ononmanive,	00-4	ywh; trp, trl; BB fus dif, rdh flame; Šr, Č, 450.
†† Phosphates of phorus reaction		ates: no effervescence with acids; BB sulphur or phos- ly all the anhydrous species contain also some fluorine.
‡ Websterite,	Hydrous. 1—2	(Altered Tryphyline falls here, see p. 407). Massive, reniform; G 1.66; w; earthy; adheres to tongue; BB fuses dif; in acids sol, no efferv; 基1, 克, Aq, 389.
Pissophane,	1—2	Massive, stalact; G 1-9-2; gn, gnh; trp, fragile; BB fus dif; in mursol; BB bk; Al, Fe, S, Aq, 390.
Struvite,		III; in crystals; wh, yh, bnh; vit; BB water and ammonia, a colorless glass; in acids sol; Am, Mg, P, 418.
Hopeite,	2·5—3	III; cleav!; massive; G 276—29; vit; p'ly; gyh-w; bn; trp, trl; sectile; BB fus, flame gn; with soda fumes of zinc; in mur sol; Zn, P, Aq, 409.

	Hardness.	
Wavellite,	8-4	III; stellate fibrous, hemispheres; G 23-24; w, ywh, gnh, bnh, bk; vit—res; trl: BB w, intum; in hot sul sol; often fluorine; \(\frac{\pi}{4}\), \(\frac{\pi}{p}\), F, Aq, 423.
Cacoxene,	3-4	III; stellate fibrous; G 3.88; ywh, bnh, bn on exposure; resinous; trl; like wavellite; Fe, Æl, P, Aq, 424.
		‡ Anhydrous.
Pyromorphite,	8.5-4	VI; hexag; ren, bot, fib, gran; G 6-5-7-1; bn, bright gn; orange; strp, strl; brittle; BB on charcoal fus, glob, cryst; in hot sit sol; Pb, P, Cl, F, 400.
Triphyline, Triplite,	45.2	III; often cleavable; massive; G 3.5—3.8; subres; bh, bn, dull b, bkh-bn; streak gyh; trl, strl; BB fus! magnetic; in acids sol, no efferv; Fe, Mn, Li, P, 406, 408.—Often altered and hydrous.
Herderite,	5	III; clear imperf; G 298; ywh, gnh-w; vit, subres; trl; very brittle; BB fus dif w enamel; in hot sour sol; \(\frac{\frac{\pi}}{4}\), \(\true{C}_a\), \(\true{P}\), F! 410.
Zwieselite,	5	Hexag i cleav; G 3.97; bn; streak gyh-w; BB decrep, fus bh-bk glass, magnetic; Fe, Mn, P, F, 399.
Wagnerite,	5-5.4	IV; massive; G 3; ywh, gyh; vit; trl; BB fus dif, gnh glass, with bor trp; in heated sit or dilute sul sol, no efferv; Mg. P, F, 403.
Amblygonite,	6	IIII cryst; clear brilliant; G 3-3:11; pale gn; vit, p'ly; strp-trl; BB fus! intum, w; in sul in powder sol; H, P, L, F, 409.
a. 81	ecies veri	distinctly foliated or fibrous in some varieties.

a. Species very distinctly foliated or fibrous in some varieties.

Wavellite,	Fib!	Pyromorphite,	Fibrous.
Cacoxene.	Fib!	•	

B. Species arranged according to their specific gravities.

	Sp. Gravity.		Sp. Gravity.
Websterite, 389.	1.66.	Wagnerite, 403.	8.
Pissophane, 890.	1 92.	Amblygonite, 409.	88·11.
Wavellite, 428.	2·3—2·4.	Cacoxene, 424.	8 ·3 8.
Hopeite, 409.	276-29.	Triphyline, 406, 408.	3.5-3.8.
Hederite, 410.	2 -98 .	Pyromorphite, 400.	6.5-7.1.

††† Fluorids: a fluorine reaction, and none of phosphorus.

Cryolite, 2.5 III; massive, clear rectang; G 2.9—3.1; w; vit, subp'ly; strp—trl; brittle; BB fus!!!; in sul soluble, fumes of fluorine; Na, Al, F, 97. Chiolite is very similar, 98.

Fluellite, 8 III; cryst; w; vit; trp; Al, F, 98.

Fluor Spar, 4 I; cryst; clear oct!; massive granular; G 3·1-3·2; w, yw, gn, rdh, bh, purple; vit; trp, trl; brittle; BB phosphoresces fus dif, enamel; Ca, F, 94.

†††† Borates: no effervescence with acids. B.B. reaction of boracic acid.

Mydroboracite, 2 Foliated and fibrous like gypsum; G 19-2; wh; BB fus, clear glass; Ca, Mg, H, B, 393.

		GELATINIZING SILICATES.	271
	Hardness		
Hayesine,		Masses made of interwoven fibres; w; Ča, Other hydrous borates, p. 394.	B, Aq, 393.
Boracite, Rhodizite,	7—8	I; small cubes, &c., hemihed; massive; G gyh, ywh, gnh; vit; strp, trl; BB intum, is w when cold; in mur sol; Mg, B, 398.	The second second
2. Soluble in		the silica gelatinizing either before or eral has been heated; Silicates.	after the
		B.B. infusible or nearly so.	
Collyrite,	1—2	Like clay; feel greasy; adheres to the ton 2.2; BB infus; in nit gelat; Al, Si, Aq, 339	
Nontronite,	2—3	Massive; feel unctuous; ywh, gnh; op, st BB infus, bh, bn; in mur gelat; Fe, Si, Ac	* '
Allophane, Schrötterite,	3—3.5	Mas, or in hyaline crusts, and reniform; G guh, bh, ywh, w; BB flame commonly gre fus! glass; Al, Si, Aq, 336, 337.	
Calamine,	4.5—5	III; mammillary, botryoid, massive; G 3:35 bh, gnh, ywh, bnh; trp, trl; BB fus dif! glass; with soda, fumes of zinc dif; in m Zn, Si, Aq, 313.	1; with bor
Willemite,	5.2	VI; in hexag pms and massive; G 3.9-4: yw, gyh, bnh; trp, op; BB decrep, infus in powder in mur gelat; Zn, Si, 189.	
Geblenite,	δ·5—6	II; in small glassy cryst; G 2.9-3.1; gnh BB fus dif!! in mur gelat, 256.	, gyh, bnh;
Cerite,	5.5	VI; in hexag pms, mas, gran; G 4 912; dull resinous; clove-bn, cherry-r, gyh; str infus; powder in dilute mur gelat easily Aq, 312.	l, op; BB
Chrysolite,	6.5—7	III; glassy grains and crystals disseminated; green; trp—trl; BB with bor fus, iron be insol; sul gelat; Mg, Fe, Si, 184.	
Chondrodite,	6-6.5	III; opaque ywh or bn grains or masses diss limestone; also in cryst at Vesuvius; G: mur gelat; fluorine reaction, 186.	
		** B.B. fusible.	
+ Hvd	rous. (A	pophyllite and Analcime imperfectly gelatiniz	(4)

† Hydrous. (Apophyllite and Analcime imperfectly gelatinize.)

Spadaite, Metachlorite,	2.5	Mas; rdh; p'ly; BB glassy enamel; in mur sol, imperf gelat; Mg, Si, Aq, 278. Metachlorite is dull leek-gn, in mur gelat; BB fus dif! 297.
Caporcianite,	2.5	IV; like Heulandite; also laminato-radiate; G 2.47; flesh-red; p'ly; BB no intum, w, enamel; in acide gelat!; Ca, Al, Si, Aq, 334.

9000		The state of the s
	Hardness.	
Schneiderite,	3	Laminato-radiate; w; opaque; BB fus, intum; in acids gelat! Al, Ca, Mg, Si, Aq, 316.
Leonhardite,	3—3.5	IV; cryst, cleav; G 2.25; p'ly, vit, w, ywh, bnh; usually whitens and crumbles on exposure like Laumontite; BB exfol, intum, fus!; Ca, Al, Si, Aq; 308.
Sphærostilbite,	3.5	Glob, diverg, laminato-radiate; G 2·05—2·21; p'ly, vit; w, ywh, gyh; trl, strl; brittle; BB intum, fus; Al, Ca, Si, Aq; Zeolite, 333.
Laumontite,	3.5—4	IV; cryst, cleav; G 2·26—2·36; vit, p'ly; w, ywh, gyh; trp, trl; usually opaque and falls to powder on exposure; BB intum, fus; in nit or mur gelat; Al, Ca, Si, Aq, 307.
Mesole,	3.5—4	Globe, diverg, flat columnar; G 2:3-2:4; silky, p'ly; wh, ywh, rdh; trl; BB fus; in mur gelat!; Al, Ca, Na, Si, Aq; Zeolite, 328.
Gismondine,	4.5	II; in octahedrons and mammillated forms, surface drusy; bh-w, gyh, rdh; splendent; trp, trl; BB in- tum, fus; Al, Ca, K, Si, Aq, 322.
Phillipsite,	4-4-5	III; in glassy cryst, often cruciform; cleav imperf; G 2-2·2; vit; w, rdh; trl, op; BB intum, fus; in mur in powder gelat!; Al, Ca, Si, Aq; Zeolite, 324.
Pectolite, Okenite,	4—5	IV; fibrous, acicular, radiate; G 2.25—274; w, gyh; subvit, p'ly; strl; op; tough; BB fus! enamel; in mur gelat after heating, (okenite before heating); Ca,
Gmelinite,	4.5	Na, Si, Aq, 305; Okenite, Ca, Si, Aq, 306. VI; in small glassy hexag crystals, w, or colorless; G 2.05—2.1; BB intum, fus; in mur gelat; Al, Ca, Na, Si, Aq; Zeolite, 321.
Apophyllite,	4.5—5	II; acute octahedrons and prisms, cleavage basal! also subfoliated; massive; G 2—2.4; w, gyh, gnh, ywh, rdh; trp, op; brittle; BB exfol, fus; in nit imperf gelat; Ca, K, Si, Aq, 304.
Thomsonite,	55.5	III; in glassy or somewhat p'ly cryst; also columnar diverg; G 2.3—2.4; vit, p'ly; w, bnh; trp, trl; brittle; BB intum, fus dif! in mur in powder gelat; Al, Ca, Na, Si, Aq; Zeolite, 325.
Analcime,	55.5	I; usual in glassy or whitish trapezohedrons; G 2.05—2.3; vit; sometimes gnh, ywh, rdh; trp, op; brittle; BB fus, no intum; in mur gelat; Al, Na, Si, Aq, 318; Ittnerite is similar in form, also massive; G 2.8—2.4; bh-gy, ash-gy; BB some sulphur; Na, Ca, Al, Si, S, Aq, 319.
Hatrolite,	5-5.5	III; in acicular cryst; also diverg fibrous; G 2·1—2·25; vit, subp'ly; w, gyh, ywh; trp, trl; brittle; BB fus quietly; in mur gelat!; Al, Na, Si, Aq; Zeolite, 327.
Scolesite,	5-5.5	III; in acicular cryst, also diverg, fibrous; G 2-2-2-8; vit, p'ly; w, gyh, ywh; trp, trl; BB curls up like

Hardness.

a worm, fus; in mur gelat!; Al, Ca, Aq; Zeolite, 328. Like Natrolite, but lustre more p'ly. Sloanite fuses without intumescence, 329.

Datholite,

5-5.5 IV; small glassy cryst; mas; G 2.9-3; w, gyh, gnh, ywh, purplish; trp, trl; BB intum, vit glob, flame gn; in nit gelat; Ca, Si, B, Aq, 334.

a. Species distinctly foliated or fibrous in some varieties.

Caporcianite, 334.	H.=2·5	Col.	Okenite, 806. H=4.5-5 F	ib.
Schneiderite, 816.	8	Fib.	Apophyllite, 304. 4.5-5 F	ol.
Sphærostilbite, 388.	8.2	Fib.	Thomsonite, 325. 5-5.5 F	ίb.
Laumontite, 807.	8.5-4	Col.	Scolecite, 328. 5-5.5 F	ib.
Mesole, 328.	8.5-4	Fib.	Natrolite, 327. 5-5.5 F	'nλ.
Pectolite 805.	45	Fib.	•	

B. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Collyrite, 838.	2-2.2.	Scolecite, 328.	2.2-2.28.
Spadaite, 297.		Laumontite, 307.	2.26-2.36.
Phillipsite, 324.	22.2.	Mesole, 328.	2.3-2.4.
Gmelinite, 321.	2.05-2.11.	Thomsonite, 325.	2·8—2·4.
Sphærostilbite, 388.	2.05-2.21.	Ittnerite, 319.	2.37-2.4.
Analcime, 318.	2.05-2.3.	Datholite, 334.	2·9—3.
Apophyllite, 304.	2—2·4.	Gehlenite, 256.	2.9-3.1.
Pectolite, 805.	2 - 2.74.	Chondrodite, 186.	3·13·2.
Natrolite, 827.	2·15—2·25.	Willemite, 189.	4-4.2.
Okenite, 806.	2.28-2.38.	·	

		†† Anhydrous.
Wollastonite, Edelforsite,	4.55	IV; cleav, mas, sublamellar, subfib; G 2.75-2.9; w, gyh; ywh, rdh, bnh; strp, trl; subvit, p'ly; BB on charcoal fus, colorless bead; mur gelat; Ca, Si, 155, 156.
Kellilite,	5	II in small pms; G 2.9—3.15; vit; bnh, yw, gnh, rdh; trl, op; BB fus dif; in acids gelat; Al, Ca, Mg, Na, Fe, Si, 205.
Lapis Lazuli,	5.2	I; massive; dodec; G 2.8-2.5; vit; b; trl, op; BB fus; in mur gelat, 229.
Sodalite, Hauyne, Nosean,	5·5 —6	I; dodec; G 2.2—2.4; vit; bn, gy, b, gn; trp, strl; BB fus dif; in nit or mur gelat; Al, Na, Si, Cl or S, 229, 230. Skolopsite (231) is similar.
Cancrinite,	5·5—6	VI; hexag, like Nepheline; massive; G 2·42—2·62; subvit, subp'ly; w. gy, yw, gnh, b, rdh; trl; BB fus! intum; in mur efferv, gelat after heating; Al, Na, Ca, Si, Č, 233.
Nepheline,	5 ·5 6	VI; hexag pms; massive; G 2.5—2.65; vit, greasy; w, gyh, gnh, rdh, bnh; trp, strl; BB fus; in acids gelat; Al, Na, K, Si, 232.
Barsowite,	5.5—6	Mas, gran; G 27-276; subp'ly; w; strl; BB fus dif; in acids gelat; Al, Ca, Si, 236.

	Hardner	ss.
Allanite, Orthite,	5·5—β	IV; broad or acic cryst, mas; G 3:3-4:2; pitch-black, bn, ywh; strl, op; brittle; streak gyh; BB intum, fus; in acids gelat; Al, Fe, Ce, Ca, Si, 208.
Sarcolite,	5.2—6	II; in small glassy cryst; G 2.545; flesh-r, rdh-w; trp, strp; brittle. BB fus w enamel; Ca, Al, Si, 200.
Indianite,	6	V; mas, gran; G 2.668; w, gyh; trl, strl; BB fus dif; acids gelat!; Al, Ca, Si, 235.
Eudialyte,	6	VI, R, clear basal!; mas; G 2.89—2.91; vit; bnh-r; op, strl; BB fus gyh-gn scoria or op glass; in powder acids gelat; Zr, Fe, Ca, Na, Si, 181.
Tephroite,	6	Mas, gran; G 4—4·12; ash-gy; streak gyh; bn or bk on exposure; BB fus! bk scoria; in mur gelat!, not evolving chlorine; Mn, Si, 186.
Idocrase,	6.2	II; often in square prisms; clear indist; mas; G 3.34—4.0; vit, res, often lustrous; bn, gn; yw, b; strp, strl; BB fus! intum; in acids after heating, soluble and gelat; Al, Ca, Fe, Si, 197.
Epidote, (in part),	6-7	1V; cryst; massive, subcolumn; G 3.25—3.5; vit, res; pistachio-gn. bn, gy; strp, op; BB fus; in mur after strong ignition sol and gelat; Al, Ca, Fe, Si, Mg, Ce, 206.
Chrysolite,	6:5—7	III; glassy grains, massive, resinous; G 3·1-3·6; green to black; Mg, Fe, Si, 184.

a Species distinctly fibrous in some varieties.

Edelforsite, 155. H=5.5 Fib. Wollastonite, 156. H=4.5-5.

β. Species arranged according to their specific gravity.

	Sp. gravity.		Sp. gravity.
Sodalite, 229.	2.2-2.4.	Barsowite, 236.	27-276.
Nosean, 230.	2.25-2.3.	Wollastonite, 156.	27-2.9.
Lapis Lazuli, 229.	2·3-2·5.	Eudialyte, 181.	2.9
Hauyne, 230.	2.4-2.5.	Mellilite, 205.	2.9-3.15.
Cancrinite, 233.	2.42-2.62	Epidote, 206.	3·25—3·5.
Nepheline, 232.	2.5-2.65.	Chrysolite, 185,	3—3 ·6.
Skolopsite, 231.	2.53.	Allanite, 208.	3 · 3 - 4 · 2.
Sercolite, 200.	2·545.	Idocrase, 197.	3.34-4.0
Edelforsite, 155.	2.58.	Tephroite, 186.	4-4.12.
Indianite, 235.	2.668.	•	

3. Insoluble in acids, or partly soluble, without gelatinizing.

Obs.—The only species in this subdivision in which G is above 4.8, are Scheelite, Plumboresinite, Cassiterite, and Yttrotantalite. See pp. 347, 359, and 431.

• Infusible, or nearly so.

† B.B. reaction of sulphur, phosphorus, or fluorine, (fluorine only in fluorerite).

Blende,

3.5—4 I; perfect cleavage dodec; massive; G 3.9—4.2; resinyw, bn, bk, rdh, gnh; brittle. BB infus or fus dif!!; in mur sol, sulphur separating; Zn, S, 45.

	not gr	LATINIZING WITH ACIDS—INFUSIBLE. 275
	Hardness	.
Xenotime,	45	II; small octahed cryst; G 4.4—4.6; ywh-bn; streak pale; res; op; BB with bor uncolglob; in acids insol; Y, P, 401.
Fluocerite,	45	VI; in hexag pms; G 47; rdh, yw; streak w, ywh; strl, op; BB darkens; with bor sol, red in outer flame; Ce, F, Aq, 96.
Turquois,	6	Massive, stalact, reniform, no cleavage; G 2.6—2.85; bhgn; waxy; strl, op; BB decrep, bn, gn flame; with bor fus; in mur insol; Al, P, Aq, 405.
Lazulite,	5—6	IV; cryst, massive; G 3—3·15; blue, gnh; vit, strl, op; BB blebby appearance; with bor trp glob; after heatsol in acids; Mg, Xl, P, Aq, 404.
No species in which is sometim		odivision is either fibrous or foliated, excepting Blende, rectly fibrous.
† Hydrous'; no		orus reaction. (Hydrous silicates of magnesia, alumina, or iron, with opal and hydrates of alumina.)
Margarodite, Ma give the reaction and Opal someti pyroxene; and o	of mag mes cont f similar as Pyra	a blue color with cobalt solution are Pholerite, Halloysite, &c. Pyrophyllite, Gibbsite, Diaspore; 2, the remaining species nesia or iron, excepting Erstedite, Opal, and Malacone; ains oxyd of iron when impure. Schiller Spar is altered nature are other hydrous substances, which if good species llolite, &c., (see p. 165). Zircon and Kyanite are also some-95, 265).
Pholerite,	0.5—1	Soft pearly scales, w; massive; G 2:3—2:6; in dilute nit not sol; Al, Si, Aq, 251.
Halloysite, &c. Kaolin, Dillnite, Collyrite,	1	Clay-like, mass; G 1.5—2.1; w, bh; waxy; feel greasy; adheres to the tongue; strl, more trp in water; in acids decomp; Al, Si, Aq, 251, also 340. Kaolin differs in its harsh feel, 249. Dillnite, 338.
Pyrophyllite,	1	Foliated like talc, radiated; G 2.7—2.8; p'ly; gn, gnh, w, ywh; strp, trl; laminæ flexible; BB swells up!!, with soda fus; in sul partly sol; Al, Si, Aq, 303.
Vermiculite,	11.5	Scaly massive; scales foliated; G 2756; olive gn, gnh;

p'ly; strl; BB fus dif, swells out, worm-like!! in mur decomp; Mg, Al, Fe, Si, Aq, 292.

Massive; soft; G 2.26; w, ywh, bh, rdh; greasy; BB Seponite, bkns, fus dif!!; in sul soluble; Mg, Al, Si, Aq, 282.

Fib, stel, mas; G 2.77; gn; silky or earthy; BB an iron Neolite, reaction; Mg, Fe, Al, Si, Aq, 278.

Ripidolite, VI; hexag; foliated!; mas, gran; G 2.65-2.96; gn, 1-2 olive-gn; p'ly; trl, strp; lam flexible, inelast; BB fus Chlorite, often dif!!; Mg, Fe, Al, Si, Aq, 293-296. Clinochlore,

III i foliated!!; also compact massive; G 2.55-2.85; Talc, 1-1.2 gnh, gn, w; p'ly; feels greasy; laminæ flexible, ine-Margarodite, lastic; BB with bor intum, glass; acids no action; Talc Mg, Si, 275. Margarodite (223) is more like Mica, and gives a dull blue color with cobalt solution.

	Hardness,	
Steatite,		Is a massive tale; w, gyh, gnh, 275. Meerschaum is similar, gyh-w, earthy texture; H 2—2·5, 277. Aphro- dite is allied, 276.
Kerolite,	2-2.5	Massive, reniform, foliated; G 2-2.4; vit, res; w, gnh, gn; trp-trl; feel greasy; BB bkns; Mg, Si, Aq, 280.
Chloropal, Pinguite,	2-3	Gives an iron reaction; color ywh-gn, gnh-yw; BB bkns; Fe, Si, Aq, 337.
Antigorite,	2.5	III; mas, fol!; G 2.622; bnh-gn, leek-gn; trp, trl; feel smooth, not greasy; BB fus dif!!; in mur decomp dif; Mg, Fe, Si, Aq, 281.
Groppite,	2.5	Mas, foliated; G 2.73; rose rd; trl; BB wns, fus dif!!; with bor sol, intum; Al, Fe, Mg, Si, Aq, 287.
Epichlorite,	2—2.5	Fib; G 276; dull leek-gn; greasy; strl; BB fus dif!!; Mg, Al, Fe, Si, Aq, 288.
Pierosmine, Pierophyll,	2.5—3	III; cleavable massive, fibrous; G 2:59-2:75; gnh-w, gn, gy; p'ly, vit; strl, op; odor argil if moist; BB intum; Mg, Si, Aq, 281, 280.
Serpentine,	2-4	Massive, foliated, or fibrous; green, ywh, bk, wh, bnh, bkh; subres; feel somewhat greasy; BB fus dif!! bor sol! mur sol; Mg, Si, Aq, 282. Retinalite, (283), and Deweylite, (285), have a pale resin-like look. Chrysotile or fibrous Serpentine is soft. Metaxite is related, 285. Xylite or Xylotile is wood-brown, 285.
Margarite,	8-4	Micaceous like Mica, but laminæ rather brittle; p'ly; G 2.9—3, 300. Euphyllite is similar, (291); BB fus dif.
Gibbsite,	8-4	VI; hexag tables with basal cleav; commonly stalactitic, surface smooth; G 2·3-2·4; gyh, gnh, w; p'ly, waxy; trl; tough; Al, Aq, 134.
Schiller Spar.	3.5—4	Foliated; G 2.5—2.8; gn, pinchbeck-bn; met-p'ly; lam brittle; BB fus dif!!; sul decomp; Mg, Fe, Si, Aq, 165.
Clintonite,	4-5	Foliated! massive; G 3-098; rdh-bn; copper-r; submet- p'ly; strl; laminæ brittle; BB wtns; with bor sol; in acids in powder some action; Al, Mg, Ca, Fe, Si, Aq, 297.
Bowenite,	8	Massive like nephrite; G 2:59-2:8; apple-gn; faint vit; trl; splintery, tough; BB unalt; in hot mur decomp, 283.
Monradite,	5—6	Mas, fol; G 3-2-3-3; ywh, w, rdh; vit; Mg, Fe, Si, Aq, 280.
Chloritoid, Sismondine,	5.5—6	Coarse fol or micaceous; G 3.4-3.56; gy, gyh-gn, gnh- bk; weak-p'ly; BB darkens, magnetic; with bor fus iron glass; in acids not sol; Al, Fe, Si, Aq, 298.
Opal,	5.2—6.2	Mas; G 1.9-2.3; w, yw, r, b, gn, gy, bn; vit, res, p'ly; BB yields some water, sometimes rdns when impure; with soda fus! Si, Aq. 151.

Diaspore,

6—7 III; thin or acic cryst; foliated mas; G 3·3—3·5; gyh, gnh, bnh; p'ly, vit; trl, strl; brittle; BB decrep; with soda unalt; in sul no action; \(\frac{\mathbf{X}}{4} \), Aq, 128.

a. Species distinctly foliated or fibrous in some varieties.

Pyrophyllite, 808.	H=1,	Fol!	Picrosmine, 281. H.	=2.5-8	Fib.
Talc, 275.	1-1.5	Fol!	Picrophyll, 280.		Fib.
Vermiculite, 292.	1-2	Fol.	Gibbeite, 134.	3-4	Fol.
Neolite, 278.	1-2	Fib.	Margarite, 300.	3-4	Fol
Ripidolite, 293.	1-2	Fol.	Euphyllite, 291.	3.5-4	Fol
Chlorite, 296.		Fol.	Schiller Spar, 165.	3·5—4	Fol.
Xylite, 285.		Fib.	Clintonite, 297.	45	Fol.
Metaxite, 285.		Fib.	Monradite, 280.	56	Subfol.
Serpeutine, 282.	2-4	Fol, Fib.	Chloritoid, 298.	5.5-6	Subfol.
Kerolite, 280.	2-2.5	Fol.	Diaspore, 128.	66-5	Fol.

β. Species arranged according to their specific gravities.

_	Sp. gravity.		Sp. gravity.
Halloysite, 251.	1.5-2.1.	Picrophyll, 280.	2.75.
Kerolite, 280.	2.0-2.2.	Pyrophyllite, 303.	2.7—2.8.
Opal, 151.	1.9-2.3	Antigorite, 281.	2.622.
Seponite, 282.	2.26	Groppite, 287.	2.73.
Gibbsite, 134.	2.3-2.4	Epichlorite, 288.	276.
Pholerite, 251.	2·3-2·6.	Vermiculite, 292.	2.76.
Retinalite, 283.	2·4 93.	Clintonite, 297.	3.098.
Tale, 275.	2.55-2.65.	Monradite, 280.	3·2 —3·8.
Picrosmine, 281.	2.59-2.68.	Diaspore, 128.	3 ·3—8·5.
Bowenite, 282.	2.59-2.8.	Chloritoid, 298.	3·4 —8·6.
Steatite, 275.	2.65-2.8.		

††† Anhydrous.

Obs.—Andalusite, Chiastolite, Kyanite, Sillimanite, Rubellite, Topaz, Chrysoberyl, Sapphire, and sometimes Leucite and Spinel, give a fine blue color with cobalt solution; Mica and Phenacite less clearly so. Chondrodite, Topaz and some Mica give a fluorine reaction.

Hardness.

Mica,	2-2.5	Micaceous; laminæ thin flexible, elastic; G 2.75-3.1;
•		w, gy, gnh, ywh, bnh, bk; trp, trl, opaque. BB whi-
		tens, fuses on the edges; K, Mg, Al, Si; 217.

Chiastolite, 3—6.5 III; in stout prisms, nearly square, tesselated with gyhw; dull, subvit; G 2.8—3.3; BB infus, with bor fus, dif!! Al, Fe, Si, 257.

Azorite,

4-4.5 II, like zircon; only in minute cryst; vit; colorless, ywh, gnh; trl, op; BB with bor sol dif!, with more bor op, on flaming; with phos slow solution; Ca, Ta (!) 850.

Knebelite,
 5-6? Mas; G 3.71; glistening; gy, r, bn, gn; BB alone unaltered, with bor fus dark olive-gn pearl; Mn, Si, 186.
 Boltonite.
 5.5 Disseminated grains, somewhat cleavable; G 2.8-3;

dark gyh-bn, ywh-gy; ywh on exposure; vit; trl; BB bleached; with bor trp glass; Mg, Fe, Al, Si, 167.

Pyrochlore, 5-5.5 Only seen in small octahedral cryst; yw, bn; subres; G 3.8-4.35. BB fus dif!! with bor rdh, yw, 345.

Perofskite, 5.5 I; in cubes, hemihed; G 4.017; met-adamantine; gyh, iron-bk; strl, op; BB with bor glass, titanium reaction; Ca, Ti, 345.

Leucite.

Kyanite,

Sillimanite,

lardness.			

5.5-6 I; in trapezohedrons; cl imperf; G'2.45-2.5; vit, not lustrous; w, gyh-w; trl, op; BB with bor fus dif; in acids decomp, silica pulv; Al, K, Si, 231.

Opal, 5.5—6.5 Never cryst, massive, crust, often opalescent; G 1.9—
(in part), 2.3; sometimes hyaline, also trl, strl; nearly opaque;
BB with soda fus! 151.

Brookite, 123, 5·5-6·5 G 3·85-4·25; met-ad; bn, bh, gnh, black; BB unalt; Ti.

Anatase, 121,

Rutile, 120,

Rutile in square prisms often geniculated, often acicular, G 4·18-4·25, H=6·5; Anatase in brown or dark bluish acute octahedrons, G 3·85-8·95, H=5·5.

Chondrodite, 6—6.5 III; disseminated in granular limestone; G 3.1—3.2:
subvit, res; yw, wh, bnh; gnh, bkh; trl—sbtrl; very
brittle; BB with bor ywh-gn; reaction of fluorine,
Mg, Fe, F, Si, 186.

Chrysolite, 6—7 III; in green glassy grains and masses; G 3·3—3·6; rarely white; trp, trl; Fe, Mg, Si, 184.

Cassiterite, 6—7 II; cryst, mas, grains; G 6:3—7:1; ad, subvit, subres; bn, bk, rdh, gy, ywh; st gyh; strp—op; BB char reduced; acids insol; Sn, 118.

6-7.25 V; in slender bladed cryst, common; bh, wh, deepest blue along the middle; rbc pms, bnh; gyh; also fib mas; G 8.5-3.7, Kyanite; 3.1-3.6 Sillimanite; vit, sbp'ly; trp-sbtrl; BB unalt; bor fus dif; Al, Si, 263, 265.

Andalusite, 6-7.5 III; prisms stout, nearly square, often tesselated; G 3.1
-3.3; vit, weak; gyh, rdh, gnh; strl-op; tough;
BB unalt, with bor fus dif!; Al, Si, 257.

Quartz, 7 VI; cryst, mas; G 2:6-2.7; w, yw, r, bn, gn, b, bk; trp-op; vit, subres; BB with soda fus! Si 145.

Staurotide, 7-7.5 III; 129° 20'; always in crystals, prisms stout, often cruciform; G 3.5-3.75; subvit, vit; bnh, rdh, bn, bk, gy; trl, op; BB darkens, with bor fus dif gn glass; Al, Fe, Si, 261.

Chrome Garnet, 7.5 I; dodec; G 8:4184; vit; emerald-green; BB infus; bor chrome-gn glass; Cr, Al, Ba, Si, 190.

Zireon, 7.5 II; always in crystals; G 4.5—4.75; vit-adamantine; bn, r, yw, gy, w, often bright; trp, strl; BB loses color; with phos and soda infus; in acids no action, or dif! Zr, Si, 195.

Rubellite, 7.5 VI; three or six-sided prisms; red, bh, wh; G=3-3.8; BB infus; Al B, Si, 270.

Sapphirine, 7—8 Small grains, or gran mas; 3.4—3.5; vit; pale b, gn; trp, trl; BB infus, with bor infus, unaltered; Mg, Al, Si, 266.

Beryl, 7.5—8 VI; in hexag pms; G 2.65—2.75; vit, subres; green, emerald-gn; ywh, bh, bhh; trp, strl; BB with bor clear glass; Be, Al, Si, 178.

	Hardness	•
Phenacite,	8	VI; in crystals, clear R; G 2.9—3; vit; colorless, wine- yw; rdh; trp, op; BB with bor fus dif, trp glass; with soda w enamel; cobalt solution dull blue; Be, Si, 189.
Topes,	8	III; usual in crystals; clear basal!; sometimes massive, sub-fibrous; G 3.4—3.65; vit; yw, w, gnh, bh; trp, trl; BB with bor clear glass; Al, Si, F, 259.
Spinel,	8	I; usual in octahedrons; G 3.5—4.8; vit; r, gn, b, gy,
Automolite,		bk, sometimes bright; trp, op; BB with bor fus dif;
Kreittonite, d	ia.,	Mg, Al; Zn, Al; Mg, Fe, Al; Zn, Mn, Al, Fe; Zn, Fe, 103.
Chrysoberyl,	8•5	III; cryst; G 3.5-8.8; vit; bright green, ywh; rdh; trp, trl; BB unaltered, soda infus; bor fus dif!; Be, Al, 122.
Sapphire,	9	VI; in hexag crystals; mas; G 3.9—4.2; vit, p'ly; blue; r, yw, bn, gy, wh; trp, op; tough; BB soda unaltered; in acids no action; Xl, 111.
Diamond,	10	I; in crystals, rarely massive; G 3.4-3.6; w, b, r, gn, bn, gy, bk; adamantine; trp, strl, 24.

a. Species distinctly foliated or fibrous in some varieties.

Mica, 217.	H=2-3	Fol!!	Sillimanite, 265.	77.5	Fib.
Kyanite, 268.	6-675	Fib.			

B. Species observed always or mostly in distinct crystals.

Perofakite, L. Chiastolite, III.	Anatase, II. Rutile, II.	Zircon, II. Beryl, VI.
Azorite, IL	Andalusite, III.	Phenacite, VI.
Leucite, L	Staurotide, III.	Spinel, I.
Brookite, III.	Chrome Garnet, I.	Diamond, L

y. Species arranged according to their specific gravities.

Opal, 151. Leucite, 231. Quartz, 145. Beryl, 178. Boltonite, 167.	Sp. gravity. 1·9—2·3. 2·4—2·5. 2·6—2·7. 2·65—2·75. 2·8—3.	Kyanite, 263. Staurotide, 261. Spinel, 108. Topaz, 259. Knebelite, 186.	8p. gravity. 3·5—3·7. 3·5—3·75. 3·5—4·8. 3·4—3·85. 8·71.
Andalusite, 257. Phenacite, 189.	2·8—3·3. 2·969.	Brookite, 123. Anatase, 121.	3·8—4·18. 3·85—3·95.
Rubellite, 270.	3-8.3	Pyrochlore, 845.	3.8-4.4.
Chondrodite, 186.	3 ·1—3·2.	Sapphire, 111.	8.9-4.2.
Sillimanite, 265.	3 ·1—3·5.	Perofskite, 845	4.017.
Chrysolite, 184.	3·33·6.	Rutile, 120.	4·184·25.
Chrome Garnet, 190.	3.418.	Azorite, 350.	
Sapphirine, 266.	3.4-3.5.	Zircon, 195.	4.3-4.75.
Diamond, 24.	8·43·6.	Cassiterite, 118.	6.3-7.1.

** Fusible. (Includes no Phosphates).

† Sulphates: Sulphur reaction. Anhydrous (excepting Gypsum).

Hardness,

Gypsum, 1.5—2 IV; 111° 14'; cleav crystals; foliated!! massive fibrous!

G 2.26—2.36; w, gy; ywh, bn, bh, bk; trp, op; BB
exfol, whitens, crumbles; fus dif!; Ĉa, S, Aq, 378.

Heavy Spar, 2.5—3.5 III; tabular eryst; also prismatic; also tabular and fibrous massive to compact; G 4.3—4.5; w, ywh, gyh, bnh; rdh; trp, rtl, op; BB fus dif; Ba, S, 366.

Anhydrite, 3-3.5 III; rectang cleavages, lamellar; fib, massive; G 2.85

-3; w, gyh, bh, rdh; vit-p'ly; trp, trl; BB not exfol,
fus dif! Ca, S, 369.

Celestine, 3-3.5 III; prismatic cryst; also massive, fibrous; G 3.9-4; w, bh; vit, p'ly; trp; strl; brittle; BB decrep, fus; \$r, \$, 368.

Dreelite, 8.5 VI; rhombohedral; G 3.2—3.4; w; p'ly, splendent; Ca, Ba, S, 373.

Species distinctly foliated or fibrous in some varieties.

Gypsum, 378. H=1.5—2 Fol! fib! Anhydrite, 369. H=3—3.5 Fol, fib. Heavy Spar, 366. 2.5—3.5 Subfol, fib. Celestine, 368. 3—3.5 Fib.

†† Hydrous; B.B. no sulphur or phosphorus reaction; G. below 8.8, (excepting Plumboresinite).

Obs.—Of the included species, the magnesian are Chlorite, Spadaite, Pyrosclerite, Xylite; the carthy aluminous Halloysite and allied; the crystallized aluminous or sectites, Stilbite, Heulandite, Epistilbite, Chabazite, Harmotome, Edingtonite, Apophyllite, Brewsterite, Faujasite, to which Savite, Chlorastolite, Apophyllite, and Prehnite are related; Croeddolite is asbestiform; Palagonite a tufa product; Ottrelite and Chloritoid more or less foliaceous, and of gray to green and black colors.

Halloysite,

(in part),

Mas; earthy; G 1.6—2.1; w, bh; adheres to the tongue;

waxy; strl, more trp in water, and increase in weight;

acids decomp; Al, Si, Aq, 250. The Halloysites and
allied species are generally infusble.

Chlorite, 1—2 Micaceous or massive; lam inelastic, p'ly; olive-gn, bu, Ripidolite, Clinochlore, wh; BB fus dif!—298—296. Chlorophæite fuses easily (Chlorophæite, 278; aphrosiderite is a ferruginous ripidolite, 297.

Valuation, 2—3 Often in coarse hexag prisms, basal cleavage and sometigantolite, times foliated; G 2·7—2·9; gyh-gn,gnh bnh; sub-p'ly; sbtrl; BB fus dif; bor iron glass; soda insol; in acids insol; Al, Fe, Si, Aq, 216.

Mas; rdh; p'ly; BB glassy enamel; in mur sol; imperf gelat; Mg, Si, Aq, 278.

MyAssive, fibrous; G 2:4—2:65, dark gn; BB bkns, becomes magnetic, fus bk glob, Mg, Fe, Si, Aq, 286.

Scaly massive, scales foliated, G 2792; yw, ywh; p'ly; trl, scales trp; BB wns, fus dif!, with bor sol; in mur insol, in sul sol; Al, K, Si, Aq, 228.

	Hardness.
Pyrosclerite,	III?; foliated!; mas, gran; G 2.74—2.76; gn, gyh, wh, rdh; weak p'ly; trl; feel somewhat greasy; BB fus dif!; in mur decomp; Mg, Si, Aq, 291.
Margarite, Euphyllite,	8.5—4.5 Thin micaceous; G 2.9—8.032; pale gyh, wh, ywh; trl, strl; rather brittle; BB intum, fus dif; Al, Ca, Si, Aq, 300, 291. Ephesite is related, 301.
Plumboresinite,	4-4.5 Reniform, glob; fib, massive; G 4.9-6.4; res; ywh, rdh-bn, ywh-w; like gum arabic; Pb, Al, P (?) Aq, 431.
Savite,	8 II, Acicular pms; G 2'45; colorless; trp; BB fus dif; in acids soluble; Mg, Na, Al, Si, Aq, 316.
Liebenerite,	8.5 VI; hexag pms; clear indistinct: G 2.814; greasy; gnh- gy; BB intum, fus dif no globule: Al, K Si, Aq, 216.
Stilbite,	8.5 IV; cryst, a pearly cleavage; diverg. columnar, laminato-radiate: G 2.15-2.21: ['ly, vit; w, ywh, gyh, rdh; strp. strl; brittle; BB intum, fus; in acids slimy; Al, Ca, Si, Aq, 332.
Heulandite,	8.5—4 IV; a pearly cleavage; cryst; sometimes glob; G 2.19—2.25; w, rdh, gyh, bnh; trp, strl; brittle; BB intum, fus; in mur sol; Al, Ca, Si, Aq; Zeolite, 330. Epistibile is similar, but is trimetric, 330.
Crosidolite,	4 Fibrous like asbestus, fibres easily separable; lavender- blue. BB fus! shining slag; Fe, Si, Aq, 279.
Chabazite,	4-4.5 VI; in R and hexag forms; G 2.05-2.2; w. gyh, rdh; vit; trp, trl; brittle; BB intum, fus; in mur in powder sol; Al, Ca, Si, Aq, 319.
Harmotome,	4—45 III; in glassy cryst, often cruciform, clear imperf; G 285—25; w, ywh, rdh, bnh trp, trl; BB fus, no intum; in acids not sol without heat; Al, Ba, Si, Aq, 323.
Edingtonite,	4—4.5 II; in cryst, hemihed; G 2.7—2.8; vit; w, gyh; trl; BB w, opaque, fus dif; Al, Ca, Na, Si, Aq: Zeolite, 323.
Palagonite,	4-5 Massive, part of volcanic tufas, G 2·43; yw, ywh-bn; trl; resinous subvit; BB fus!; in mur sol; Al, Fe, Ca, Mg, Si, Aq, 166.
Apophyllite, Gyrolite,	4.5—5 II; in acute octahedrons and prisms, a pearly basal cleavage; also subfoliated massive; G 2—2.4, w, gyh, gnh, ywh, rdh; trp. op; brittle; BB exfol, fus; in nit flaky, imperf gelat; Ca, K, Si, Aq, 814.
Brewsterite,	4.5-5 IV; cryst; a pearly cleavage; G 2.1-2.44; vit, p'ly; w, ywh, gyh; trp, trl; BB froths, fus; in mur sol; Al, Ba, Sr, Si, Aq, 332.
Faujasite,	5 II; in octahedrons; G 1.923; w, bnh; vit; trp, trl; BB intum, fus; in mur sol; Al, Ca, Na, Si, Aq, 823.
Ottrelite,	Scales, micaceous, brittle disseminated through a slaty rock; G 4.4; bkh-gy, gnh-gy; BB fus dif, glob, bk. magnetic; Al. Fe, Mn, Si, Aq, 287.

H				

Carpholite,	5-5.5	The state of the s
		very brittle; BB intum, fus dif, bn, op; in acids hard-
		ly attacked; Al, Mn, Si, Aq, 316.
Allanite,	5.5	In slender cryst and massive; pitch-black, bnh-bk, dark
(in part),		ywh-brown, 208. Erdmannite, (p. 340) may belong here.
Chlorastrolite.	5.5-6	Massive radiated fibrous or subfibrous stell : p'ly : on

strolite, 5.5—6 Massive, radiated fibrous or subfibrous, stell; p'ly; gn,
pale bh-gn; BB fus! intum; in mur sol; Al, Ca, Fe,
Si, Aq, 315.

Chloritoid, 5—6 Coarse foliated; G 3.4—3.5; gy, gyh-gn, gnh-bk; weak (Masonite), p'ly; BB mag; fus dif, dark gn; Al, Fe, Si, Aq,

Prehnite, 6-6.5 III; botryoid, or thick and hard incrust, surface crystalline; G 2.8-3; vit, sbp'ly; gnh, wh; strp, trl; BB intum, fus; in mur sol slowly; Al, Ca, Si, Aq, 314.

a. Species foliated or fibrous in some varieties.

	Hardness	8.		Hardness.	
Ripidolite, 293.	1-2	Fol!	Margarite, 300.	3.5-4.5	Fol!
Chlorite, 295.	1.5-2	Fol!	Euphyllite, 291,	4-5	Fol!
Fahlunite, 216.	2-3	Fol.	Apophyllite, 304.	4.5-5	Subfol.
Iberite, 216.	2.5	Subfol.	Ottrelite, 287.	5	Fol.
Pyrosclerite, 291.	3	Fol.	Carpholite, 316.	55.5	Fib.
Stilbite, 332,	3.5	Fol!	Chlorastrolite, 315.	5.5-6	Subfib.
Heulandite, 330.	3.5-4	Fol!	Chloritoid, 298.	5.5-6	Subfol.

B Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Halloysite, 250.	1.6-2.1.	Fahlunite, 216.	2.7-2.9.
Faujasite, 323.	1.928.	Pyroselerite, 291.	2.74-2.76.
Stilbite, 332.	2:0-2:21.	Vermiculite, 291.	2.756.
Chabazite, 319.	2.0-2.21.	Prehnite, 314.	2.8-3.
Apophyllite, 304.	2.0-2.4.	Iberite, 216.	2.89.
Heulandite, 830.	2.19-2.2.	Carpholite, 816.	2.9-2.95.
Brewsterite, 332.	2.1-2.44.	Margarite, 300.	3-3:1.
Harmotome, 323.	2.35-2.5.	Euphyllite, 291.	2.9-3.1.
Palagonite, 166.	2.4-2.7.	Chlorastrolite, 315.	3.18.
Spadaite, 278		Chloritoid, 298.	8.4-3.5.
Chlorite, 293-296.	2.6-3.	Ottrelite, 287.	44.
Edingtonite, 323.	2.7-2.8.		

+++ Anhydrous; no Sulphur reaction, (excepting in Helvin.)

Obs.—Of the following species, the only micaceous one is Mica; Diallage and Hypersthene are thin foliated; the only delicately fibrous, with separable flexible fibres, are included under Asbestus; the other fine fibrous, with brittle fibres or columns, are either Pyroxene or Hornblende; Epidote and Tourmaline are sometimes columnar, and rarely Idocrase. The only Tetrahedral species is Helvin. Danburite gives a strong boracic acid reaction, and Tourmaline and Axinite one less decided. Obsidian or black volcanic glass would fall in this division were it a simple mineral. (See p. 248.)

Hardness.

Asbestus,

Fib, sometimes like cotton, fibres separable or not; BB fus dif; in acids imperf soluble; same compound as pyroxene or hornblende, 158, 170.

Hardness.

Mica, Muscovite,	* 22·5	Thin micaceous, lamine very thin, flexible, clastic, easily
Phlogopite, Biotite, Lepidolite,		separable; G 2.75—3.1; w, gy, gnh, ywh, bnh, bk, rdh, purplish; trp—trl; BB whitens, sometimes fluorine reaction, fus dif; Al, K, Fe, Si; Al, Mg, Fe, Si; Al, Li, K, Si, F, 217-227.
Leucophane,	8-54	III; mas, columnar, cleavable; G 2-974; vit; dirty gn, wine yw; trp—trl; BB fus, violet glass; fluorine re- action; with bor amethystine glass; Be, Ca, Na, Si, F, 182.
Sphene,	56-5	IV; usual in thin acute-edged crystals; also massive; G 8:4—3:6; adamant, res; brown and black common; also gy, yw, gn; trp—op; BB fus dif intum, enam; with metallic tin a violet color; with bor clear glass; in mur heated, imperf solution; Ca, Ti, Si, 268.
Melinophane,	5	Massive, cleav; G 3.0; vit; yw; brittle; optically uni- axal, 183.
Wohlerite,	5.5	Tabular cryst, massive; G 3.4; yw, bnh, gyh; BB ywh, glass; in mur sol; Zr, Na, Ca, Si, 343.
Babingtonite,	5.5—6	V; G 3.3—3.5; vit; gnh-bk; strl, op; BB fus! bead magnetic; Ca, Fe, Mn, Si, 178.
Glaucophane, Violan,	5.5	Prisms massive; G 3:108; vit, p'ly; b, lavender-b, bh-bk, gyh; streak gyh-b; trl—op; powder slightly magnetic; BB fus! gn glass; acids partly sol; Al, Fe, Mg, Na, Si, 177.
Scapolite, Meionite, Dipyre,	5—6	II; in square pms, large or small; massive; G 25—275; vit-p'ly, vit; w, gy, bh, gnh, rdh; trl, strl, op; BB fus intum; in acids decomp; Ca, Na, Al, Si, 200, 201, 205.
Pyroxene, Hornblende, Acmite,	5—6	IV; prisms, hornblende 124° 32'; acmite and pyroxene 87° 6'; massive, fib, gran, foliated; G 2.9—34; vit, p'ly; gn, w, bk; BB fus dif or easy; Ca, Si; Mg, Si; Fe, Si; Mn, Si, 158, 170, 176. Prismatic crystals of hornblende often hexagonal, with angles approaching 120°, while those of pyroxene are often 8-sided, with angles near 135°. Diallage and hypersthene are thin foliated and fus dif!!
Wichtyne,	5.5—6	Mas; G 3-08; dull; bk; BB fus bk, mag; acide not attacked; Al, Fe, Ca, Mg, Na, Si, 177.
Sanssurite,	5·5—6	V! mas, cleav; G 32—37; p'ly, vit; w, gnh, gyh; strl; tough! BB fus dif; in acids insol; Al, Fe, Ca, Na, Si, 254.
Allanite, Orthite,	5·56	IV; cryst often tabular, prismatic or acic; mas; G 3.8—42; pitch-black or bn, ywh; strl, op; brittle; streak

^{*} These micas often contain some water. Margarodite, Margarite and Euphyllite are hydrous species, yet the amount of water is very small, being but 4 or 5 per cent. B.B. fus. often easily.

gyh; intum easily, fus; in acids sol or insol; Al, Fe, Ce, Ca, Si, 208, 210. Erdmannite, (p. 340), may be near orthite.

Latrobite.

5.5—6.5 V: mas; G 2.7—2.8; vit; rose-r, pink; strl, op; BB fus dif!; Al, Mn, Mg, Ca, K, Si, 285.

Rhodonite.

5.5—6.5 IV; like Augite; massive, cleavable or granular; G 3.4
—3.75; vit; light rd; gnh, ywh, when impure; bk on
exposure; BB bn, rdh-bn glob; in mur partly sol; Mn,
Si, 167.

Orthoclase,

IV; in crystals; cleavable, massive; G 2.4—2.6; vit, subp'ly; w, rdh, gyh, gnh; trp—sbtrl; BB fus dif; in soids insol; Al, K, Si, 242.

Andesine,
Labradorite,
Voegite,
Bytownite,
Cyclopite.

Petalite,

V; massive feldsp cleav; G 2.6—2.8; subvit, p'ly; gy, bu, gnh, often a play of colors; trl, strl; BB fus dif; Labradorite in mur heated sol! Andesine attacked by acids; Bytownite is granular massive, gnh-w, trl; Al, Ca. Na. Si. 286, 237, 254.

Mas; subcleav; subfeldsp; G 2.4—2.45; vit, glist, a little p'ly or greasy; w, gy, rdh, gnh; trl; BB fus dif! w enamel. reaction of lithia; in acids insol; Al, Na. Li, Si, 253.

Albite,
Oligoclase,

6-6.5 V; feldsp; G 2.6-2.69; vit, subp'ly; ywh, gyh, w; trp, strl; BB fus quietly, flame ywh; in acids insol; Al, Na, Ca, Si, 239, 240. Oligoclase is a little more pearly or greasy in look usually than albite. The hardness of albite is sometimes 7. Albite and other triclinic feldspars differ from Orthoclase in having the stwo most perfect cleavages, (or planes O and it), not quite at right angles with one another, (85° to 87°.)

Anorthite,

6-7 V: in crystals; G 2-65-2-78; w, gyh, rdh; trp, trl; BB fus dif; with soda an enamel; in acids sol; Al, Ca, Si, 234.

Couzeranite.

6—6.5 III G 2.69; vit; gy, gnh-gy, bk; BB fus w enamel; in acids insol; Al, Ca, K, Na, Si, 206.

Pollux,

6—6.5 Mas, like quartz; G 2.88; vit; colorless; trp; BB fus, flame orange; with bor glass easily; in acids decomp; Al, K, Li, Na, Si, 255.

Helvin.

6-6.5 I; tetrahed; G 3:1-3:3; vit; subres; wax-yw, bnh, gnh; strl; BB fus, intum, yw globule op; with bor manganese reaction; Be, Mn, Si, S, 194.

Fayalite,

6.5 Black, gnh, bnh, massive, glassy; G 4.1. BB fus 1 with acids easily attacked; Fe, Mg, Si, 185.

Leopyre,

6.5 Massive no cleav; G 2-9-3; glassy black, gyh; op, strl; brittle; BB fua in acids decomp, dif; Al, Ca, Fe, Si, 255.

Mephrite,

6-7 Mas, subgran; G 2'9-3'1; subvit; wh, gnh; tough; BB fus dif!!; Mg, Ca, Si, 175.

	Hardness	l .
Weissigite,	6.2	IV, in small indistinct crystals, cleav; G 2·5—2·6; w, pale rose-red; BB fus, w blebby enamel, outer flame weak red, yw at point; Al, Na, Li, Si, 254.
Idocrase,	6.2	II; often in four or eight-sided prisme; clear indist; mas; G 3·3—4; vit, res, often brilliant; bn, gn; yw, b; strp—strl; BB fus! intum; in hot acids sol; Al, Ca, Fe, Si, 197.
Epidote, Zoisite,	67	IV; cryst; massive, subcolumn, hardly cleavable; G 3-2 —3-5; vit—res; pistachio-gn, bn, gy; strp—op; BB fus; in mur more or less sol; Al, Ca, Fe, Si, sometimes with Mn, Ce, 206.
Spodumene,	6-57	IV; Massive, cleav; G 8·1—8·2; subp'ly; gyh—gyh-gu; trl, strl; BB fus, intum; Al, Li, Si, 169.
Axinite,	6·5—7	V; crystals with sharp thin edges; G 3.2-3.8; vit; bn, bh, gyh; trp, trl; BB fusl; Ca, Al, Fe, Si, B, 218.
Garnet,	6·5—7	I; dodecahedrons; trapezohedrons; mas; in grains; G 3·5-4·3; vit, res; r, bn, ywh-bn, yw, w, gn, bk; trp-strl; BB fus; in acids more or less sol; Ca, Al, Si; Fe, Al, Si; Al, Mn, Si; Ca, Fe, Si, 190. Pyrope, G 3·69-3·8; in rounded grains; BB fus dif; bor emerald-green glob, 194.
Muromontite,	6—7	Grains; G 4.263; bk, gnh-bk; streak gyh-w; strl, op; BB fus dif, glows, flame yellow, 211.
Ioli te ,		III; six and twelve-sided pms; also massive; G 2.55—2.68; glassy and dark blue; trp, trl; BB fus alow; b glass; in acids attack dif!; Al, Mg, Fe, Si, 214.
Denburite,		Disseminated cryst, sub-cleav mas; G 2.8—3; pale ywh, wh; vit; trl, strl; very brittle; BB fus, strong reaction of boracic acid; Ca, B, Si, 212.
Tourmaline,	77·5	VI; usual in three or six-sided pms; mas; G 3—3:3; black common; also b, gn, rd, w, bn; vit, res; trp, op; BB fus or infus; Al, Si, B, with often Fe, Ca, K, 270.
Eucl ase ,	7.5	IV; in cryst, also one perfect diag cleav; G 8-3·1; vit; pale gn, bh; trp. strp; very brittle; BB intum; fus dif; w enamel; with bor a clear glass; electric by friction!; Be, Al, Si, 267.
	9 0	

β Species arranged according to their specific gravities.

Sp. gravity.		Sp. gravity,
2:39-3:45.	Dipyre, 205.	2 646.
$2 \cdot 4 - 2 \cdot 6$.	Andesine, 286.	2.65-274
2.5 - 2.74	Anorthite, 234.	2.652.78.
2.5-2.6.	Labradorite, 236.	2.682.76.
2.55 - 2.7.	Couzeranite, 206.	2.69
2.59-2.65.	Vosgite, 287.	27-2.8.
2.6-2.62.	Latrobite, 285.	27-2.8.
2.6 - 2.7.	Mica, 217-227.	2.75-8.1.
2.6-2.75.	Danburite, 212.	2.8—8.
2.63-2.69.	Pollux, 255.	2.88.
	2·4 — 2·6. 2·5 — 2·74. 2·5 — 2·6. 2·55 — 2·7. 2·59 — 2·62. 2·6 — 2·7. 2·6 — 2·75.	2:39—3:45. Dipyre, 205. Andesine, 236. 2:5 - 2:74. Anorthite, 234. Labradorite, 236. 2:55 - 2:7. Couzeranite, 206. Vosgite, 237. Latrobite, 236. 2:6 - 2:75. Danburite, 212.

24.3. 36.00	Sp. gravity.	The second second	Sp. gravity.
Isopyre, 255.	2.9-3.	Pyroxene, 158.	3.23-3.5.
Nephrite, 175.	2.9-3.1.	Epidote, 206.	3.25-3.5.
Euclase, 267.	2.9-31.	Allanite, 208.	3.3-3.42.
Leucophane, 182.	2.973.	Idocrase, 197.	3.34-4.
Hornblende, 170.	2.9-3.3.	Wohlerite.	
Tourmaline, 270.	3-3.2.	Babingtouite, 178.	3.3-3.5.
Wichtyne, 177.	3.04.	Sphene, 268.	3.4-3.6.
Melinophane, 183.	3.0.	Rhodonite, 167.	3.43.7.
Glaucophane, 177.	3.108.	Garnet, 190.	3.5-3.8.
Helvin, 194.	3.1-3.3.	Pyrochlore, 345.	3.8-4.85.
Spodumene, 169.	3.15-3.2.	Fayalite, 185.	4.1.
Axinite, 213.	3.2-3.3.	Muromontite, 211.	4.263.
Saussurite, 254.	3'2-3'4.	Microlite, 397.	5.4.
Acmite 176	8-2-8-55		100

[Norm.—The ores of lead, having an uncolored streak, as they yield a metallic malleable globule before the blowpipe, fall into the next subdivision.]

b. B.B. EITHER FUMES, OR A MALLEABLE GLOBULE, OR BOTH.

Obs.—There are no sulphurets here included. Blende and Voltzite do not give off the sulphur as fumes. Other sulphurets without a metallic lustre have a colored streak. Specific gravity of the included species above 4.8.

* Globule of lead or silver, with, or without, the fluxes; the lead passes off in fumes, and discolors the charcoal around the assay: no fumes of Arsenic, Selenium or Antimony.

	Hardness,	
Cotunnite,	1-2	III; acie cryst; adamantine, silky; w; BB fus! flame b; on charcoal w vapors, with soda lead; Pb, Cl, 97.
Kerargyrite,	1-1.5	I; like wax; sectile; G 5'8-5'6; pearl-gy, ywh, bnh; streak shining; trl-op; BB on charcoal fumes of chlorine, and silver glob; Ag, Cl, 92. Embolite, (p. 98), contains also bromine.
Matlockite,	2.5-3	II; tabular crystals; G 5:4-7:2; clear ywh, guh; adamantine, or little p'ly; trp, trl; Pb, Cl, O, 127.
Cerasine,	2.5-3	II; G 6-6-3; adamantine; w, gyh, ywh; trp, trl; BB on charcoal fumes lead; nit efferv; Pb, Cl,C, 463.
Anglesite, Leadhillite,	2.5—3	III; cryst; mas; G 6·2-6·3; adamantine, vit, res; w, ywh, gyh, gnh; trp, op; brittle; BB fus!, on charcoal with soda lead; Pb, S, 370; for Leadhillite Pb, S, C, 371. Susannite is the same, but rhombohedral, 373. Lanarkite is related, 374. Caledonite has a deep bluish green color and greenish streak.
Wulfenite,	2.5—3	II; square tables and octahedrons; also massive; G 6.3 —6.9; res, adamantine; ywh, orange yw; strp, strl, brittle; BB decrep, fus dif; on charcoal with soda lead; in mur or nit in powder decomp; Pb, Mo, 349.
Lanarkite,	2-2.5	IV; clear basal!; G 63-7; p'ly, adamantine; res; gnh-w, ywh, gyh; trp, trl; BB fus, w cold; on char- coal lead; in nit sol little efferv; Pb, S, Q, 374.

	Hardson,	•
Vanadinite,	2-5-8	VI; hexag prisms; glob incrust; G 6.6-7.3; res; pale bnb-yw, straw-yw, rdb bn; strl, op; brittle; BB fus; on charcoal glob lead; in mur sol gn, in nit yw; Pb, Cl, V, 862.
Mendipite,	2.5—8	III; columnar. rad; cleav!; G 7—7:1; p'ly; w, ywh, rdh; sbtrl, op; BB fus!, on charcoal w, fumes; with soda lead; Pb, Cl, O, 128.
Scheeletine,	2.58	II; cryst; G 7.8-8.12; res, subadamantine; gn, gy, bn, rdh; trl, strl: BB fus; on charcoal vapors of lead; in sit sol, yw; Pb, W, 348.
Cerusite,		III; cryst; mas; G 6 4—6 5; earthy, 5 4; ad, vit, res; w. gyh, bh; sometimes bkh externally; trp, strl; brittle; BB fus! on charcoal lead; in nit efferv: Pb. C, 452.
e. No foliated	species in	this division; Mendipite is sometimes fibrous.

β. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Cotunnite, 97.		Lanarkite, 874.	6·8—7.
Kerargyrite, 92.	5.8 - 5.6.	Caledonite, 872.	6.4.
Matlockite, 127.	5.4-7.2.	Cerusite, 452.	6·4 — 6 ·5.
Cerasine, 468.	6-6-1.	Susannite, 373.	6.55.
Leadhillite, 371.	6-6.5.	Vanadinite, 362.	6.67.8.
Anglesite, 870.	6.2-6.3.	Mendipite, 128.	7-7·1.
Wulfenite, 349.	6.8—6.9.	Scheeletine, 348.	7·9—8· 2 .

•• B.B. Inodorous Fumes of Zinc, Bismuth, Antimony, Tellurium.

		•
Bismuth Ochre,		Mass, earthy, pulv. somewhat fol; G 4:36; gnh-yw, straw-yw; gyh-w; ad, earthy; BB char met, then fumes; Bi, O, 141.
Zine Bloom,	2-2.5	Earthy; G 3.5-3.6; dull; w, gyh, ywh; op; BB on charcoal fumes of zinc; in mur sol; Zn, C, Aq, 460.
White Antimony Senarmontite,		III; lam; mas, columnar, gran; G 5.2-5.7; adamantine, p'ly; w, gyh, rdh; trl, strp; BB fus!!!, volat, w fumes; Sb, O, 140. Senarmontite is octahedral, 140.
Eulytine,		I; hemihed, glob, columnar, lamellar, granular; G 5-9—6-1; res, adamantine; bn, ywh-gy, straw-yw; strp, op; BB fus; fumes inodorous, on charcoal ywh-bn areola; Bi, Si, 181.
Cervantite, Bleinierite, Volgerite,	4	Massive, earthy, incrust; G 3.9—4.8; res, dull; gy, bnh, ywh; st gyh, ywh, op; BB char fumes antim, sometimes arsen; glob lead; Pb, Sb, O, Aq, 141, 142.
Bismutite,	3·5 1 ·5	Acic, incrust; massive; G 7-77; vit, earthy; w, gnh, ywh; strl, op; BB decrep, fus! on charcoal met, fumes; Bi, C, Aq, 462.
dmithsonite,	5	VI; clear rbdrl; mas; earthy; G 4—4.5; vit, p'ly; w, gyh, gnh, bnh; strp, trl; BB infus, zinc fumes; in nit efferv; Žn, Č, 447.

a. No foliated species in this subdivision, excepting white antimony, which may be lamellar; this species and eulytine may occur columnar.

*** BB. odorous fumes of Arsenic or Selenium.

Hardness.

- Haidingerite, 1.5—2.5 III; cleav!!; minute cryst, crusts, botryoid; G 2.848; w; vit; trp, trl; laminæ flexible; BB on charcoal arsenic; in nit sol, 418.
- Pharmacolite, 2-2.5 IV; cleav!/ fibrous, acic, stellate; massive; G 2.64-2.75; w, gyh; vit; p'ly; trl, op; laminæ flexible; BB fus w; on charcoal arsenic; in acids sol!; Ca, As, H, 414.
- Pitticite, 2-3 Reniform, massive; G 2.2-2.5; vit, greasy; ywh, rdh-bn, rd, w; trl. op; BB char arsen; Fe. As, S, Aq, 432.
- Mimetene, 8:5 VI; in hexag prisms; G 5:4-7:8; resinous; pale-yw, bnh, orange-yw; strp. trl; BB fus, bnh-yw; on charcoal arsen; in nit sol; Pb As, 401.
- Selenate of Lead, 3-4 Botryoidal, glob; vit, greasy; sulphur yw; brittle; BB fus! bh slag; on charcoal selen; Pb, Se, 375.
- Scorodite,, 3.5-4 III; cryst; G 3.1-3.3; vit, subadamantine; pale gn, bn;
 BB arsen, fus scoria, magnetic; in mur sol; Fe, As,
 Aq. 419.
- Kühnite, 5—6 Massive, one cleavage; G 2:52; wh, ywh; waxy; BB on charcoal arsenic; in nit sol; Ca, Mg, As, 404.
- a. No foliated species in this group, but Pharmacolite and Haidingerite have a very perfect cleavage; Pharmacolite occurs fibrous.
 - **** B.B. wholly vaporizable with fumes of quicksilver and chlorine.
- Calomel, 1-2 II; massive incrust; G 6.482; adamantine; ywh-gy, gy, wh; trl; strl; sectile; BB volat; Hg, Cl, 89.

B. STREAK COLORED.

- a. B.B. no fumes without or with the fluxes; globule not malleable.
 - ** B.B. infusible, or nearly so.
 - † Gelatinize with acida.
- Obs.-Dioptase affords with soda a kernel of copper, but with difficulty.
- Wolchonskoite, 2—8 Massive, compact; G 2—23; dull gn; trl, op; Chrysocolls: BB reaction of chrome; in mur gelat; Cr, Si, etc., 339.
- Montronite, 2:5-8 Massive; G 2:1-2:2; nearly dull; gn, gnh, streak paler; BB fus; with bor iron; in mur gelat; Fe, Si, Aq, 837.

	a rd nass	

Dioptase,	5	VI; in emerald-gn cryst; G 3.278; vit; streak gn; brit- tle; BB decrep, gn flame; with bor gn glob, copper; in mur gelat; Cu, Si, Aq, 309.
Tritomite,	8.2	Brown tetrahedrons; G 4·1—4·7; vit, submet; dark bn; streak ywh-bn; BB whitens; with bor a glass; in mur gelat; Ce, La, Ca, Si, Aq, 311.
Cerite,	5 ·5	VI; hexag pms; bn, cherry-red; G 4.9; streak grayish- white; brittle; Ca, Si, Aq, 312.
Thorite,		Massive, compact; G 4:6-5:4; vit to res; bnh-yw, bk, bn; streak dark-bn; BB bnh-r, infus; with bor fus! glass colored by iron; in mur gelat; Th, Fe, Mn, Si,

a. No foliated or fibrous species in this subdivision.

Aq, 312.

†† Not gelatinizing with acids.

Obs.—Fluorids include, Fluocarine, Fluocarite; Phosphates, Xenotime, Monazite; Osalates, Oxalite; Tantalates, Pyrochlore, Yttrotantalite, Fergusonite; Carbonates, Zippeite, Liebigite, Emerald Nickel, Parisite; Oxyds, Wad, Chrome Ochre, Red Iron Ore, Red Zinc, Limonite, Pitchblende, Brookite, Rutile; Silicates, Chloropal, Malacone; Borate, Warwickite. Remingtonite a carbonate of cobalt (p. 461) may belong in this section.

Wad,	0.5-3.5	Mas; earthy; G 3-37; bkh, dull bh, bnh; often soils; BB infus (or subfus); in mur fumes of chlorine; Mn, O, Aq; often with Co, or Cu, 186.
Oxalite,	2	Capillary, botryoid, earthy; yw; streak ywh; BB blackens and becomes magnetic; in acids sol; oxalate of iron, 464.
Chrome Ochre,		Mas; bh-gn, grass-gn; a chrome reaction with the fluxes, 339. <i>Miloschin</i> is indigo-blue to celandine-gn, 339.
Zippeite,		Earthy powder; sulphur yw, bnh, rdh; BB orange; BB in inner flame gn, infus; 🖰, H, Č, 461. Voglite contains Ca, Cu, Č, Aq, 462.
Wolframine,		Bright yw powder, crust; BB infus; W, 143; occurs with ores of tungsten, I43.
Liebigite,	22:5	Mamillary cleav; apple-gn; vit; trp; BB bkns; with bor yw in outer fl, gn glass in inner; in acids efferv, yw sol; U, Ca, Aq, 461.
Red Iron Ore,		Massive; lentic, earthy, &c. G 4-5; often earthy, dull or bright red; streak the same; BB bor gn or yw glass; in hot mur sol; Fe ⁵ O ⁵ , 113.
Chloropal,	2·5—3	Massive; G 1.7—2.2; nearly dull; gn, gnh; streak lighter; BB infus, bk, bn; with bor iron reaction; in mur partly sol; Fe. Si, Aq, 337. Pimelite is apple-gn, amorphous, and contains nickel; G 2.2—2.8; feel greasy; does not adhere to the tongue, 339.
Emerald Nickel,	3—3·5	Massive, crust; G 2.5-2.7; emerald-gn; streak gnh; Ni, C, Aq, 461.

	Hardness,	
Warwickite,	3-4	Oblong prisms, often slender, imbedded; G 3·188; submet-p'ly, subvit; bn, bkh, gyh; streak bh-bk; BB infus, reaction of boracic acid, 395.
Xenotime,	4-5	II; in small octahedrons; G 4.4—4.6; ywh-bn, streak pale; resinous; BB with bor uncolored glob; in acids insol; Y. P. 401.
Red Zine,	4-4.5	VI; foliated; G 54-56; subadamantine; deep-red; ywh; streak orange; trl, strl; brittle; BB with bor trp glass; Zn, O, 110.
Fluocerine, Fluocerite,	4.5—5	I; usually massive; yw, rdh, bnh; streak yw, bnh; strl, op; vit, res; BB bkns; with bor slow sol, red in outer flame; in sul sol, yw; Ce, F, Aq, 96.
Parisite,	4.2	VI; cleav basall; G 4:35; bnh-yw; streak ywh-w; vit; BB bnh; with bor trp glass, yw hot; in mur slow sol, efferv; Če, Ča, Č, F, 463.
Limonite,	3—5	Massive, stalactitic, incrust; G 3.5—4; earthy, silky; bn, yw, ochreous; streak ywh-bn; BB bkns, becomes magnetic; with bor iron; in hot nitro-mur sol; Fe, O,
Pyrochlore,	5—5.2	Aq. 131. In small bn or yw octahedral cryst; streak bn, ywh; BB fus dif!! Ce, Th, Ca, Ta, Ti, 345. Pyrrhite is also in small octahedral cryst; H=6; orange yw, 345.
Monazite,	55.5	IV; in small crystals, basal cleav perfect; rdh-bn, sub- resinous; G 49-53; BB with bor fus; in mur de- composed; Ce, La, P, 402.
Yttrotantalite,	5.5	G 5:395; submet; iron-bk; streak gy; op; BB with soda intum, fus; with bor sol; Y, Ca, Fe, Ta, W, U, 359.
Pitchblende,	5.5	I; massive, in grains; G 6.4—7.1; submet or dull; gyhbk, bnh-bk, velvet-bk; op; streak bk, gnh; BB flame usually gn; with bor fus yw glass, gnh in inner fl; in nit pulv sol dif; U, O, 107. Eliasite is dull rdh-bn; G 4—4.25, 108.
Brookite,	5:5-6	III; cryst; G 3.8-4.18; met-adamantine, submet; bu, ywh, rdh, bk; streak gyh, ywh; BB like Rutile; Ti, 123.
Fergusonite,	5.5—6	II; hemihed, clear traces; G 5.8—5.85; vit, submet; bnh-bk, bn, ywh-bn; streak pale-bn; strl, op; BB loses color, with bor fus dif; with soda a slag; Y, Ce. Zr.
Rutile,	66.5	Ta, 350. Rutherfordits is similar; G 5-5.5; 358. II; cryst, often acic; mas; G 4.18-4.25; met-ad, subvit; rdh-bn, rd, ywh, bk; streak pale-bn; strp, op; BB unalt; bor red in outer flame; Ti, 120.
Malacone,	6.5	II; cryst, like Zircon; G 4047; vit, subres; bnh, rdh; bh-w within; streak bn; BB yields water; with bor sol dif; in powder in acids boiling sol dif; Zr. Si, Aq. 196.

a. There are no fibrous species in this subdivision, excepting Limonite, which is sometimes imperfectly so; and Red Zinc Ore is the only species that occurs distinctly foliated.

B. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Chrome Ochre, 889.	 !	Red Iron Ore, 118.	45.
Zippeite, 462.		Malacone, 196.	4.047.
Wolframine, 143.	1	Rutile, 120.	4.18-4.25.
Liebigite, 461.	1	Eliasite,	42.5.
Fluocerine, 96.	?	Parisite, 468.	4.85.
Chloropal, 387.	2·1—2·2.	Xenotime, 401.	4.4-4.6.
Emerald Nickel, 461.	2.5-2.7.	Monazite, 402.	4.9-5.3.
Wad, 186.	3—87.	Rutherfordite,	55.5.
Warwickite, 395.	3·188.	Yttrotantalite, 359.	5.395.
Limonite, 131.	8·5—4.	Red Zinc Ore, 110.	5.45.6.
Brookite, 123.	3·8 4 ·3.	Fergusonite, 856.	5·85·9.
Pyrochlore, 845.	8 ·8 4 · 4 .	Pitchblende, 107.	6·47·1 .

** Fusible.

1 Gelatinize with acids-(Silicates.)

Hardness.

Hisingerite,	1.5—2	Massive, cleav; G 3.045; bk; streak gnh-gy, bnh-yw;
		fracture earthy; sectile; BB fus bk magnetic slag; in
		acide sol, subgelat; Fe, Si, Aq, 290.

Thuringite, 2-2.5 Mas, cleav; G 3.1-3.2; p'ly; olive-gn; streak gnh; BB with bor iron; in mur gelat; Fe, Si, Aq, 290.

Sideroschisolite. 2.5 Crystals minute; G 3—3.4; velvet-bk, gnh-gy; streak leek-gn, gnh-gy; op; BB fus! magnetic; in mur sol, gelat; Fe, Si, Aq, 299.

Cronstedtite,

2.5 VI; hexag pms; also ren, mas; cleav basal!; G 3.348; vit!; bhn-bk, bh; streak dark leek-gn; thin laminæ elast; BB intum, froths; in mur in powder gelat; Fe, Mn, Si, Aq, 299.

Lievrite, 5.5-6 III; prisms, massive; G 3.8-4.2; submet, bh, gyh-bk; streak bk, gnh, bnh; brittle; BB fus, bk glob; with bor iron glass; in mur gelat; Fe, Ca, Si, 262.

Gadolinite, 6.5—7 V; massive, G 4—4.5; vit-pitchy; bk, gnh-bk; streak gnh-gy; strl, op: BB decrep, swells up, usually glows; in mur gelat; Y, Ce, Fe, Si, 211. Tscheffkinite is similar; streak dark-bn; G 4.5—4.6; BB intum; fus dif! bh glass; in mur gelat! 211.

a. No species in this subdivision are properly foliated or fibrous.

†† Not gelatinizing with acids; B.B. phosphorus reaction.

Obs.—All but Triplite and Zwieselite are hydrous species. Vivianite, Alluaudite, Dufrenite, Carphosiderite, Zweiselite, Triplite, afford B.B. a magnetic bead.

Vivianite,

1.5—2 IV; cryst, cleav! radiated fibrous, incrust, earthy; G2.66; p'ly, vit; b, gn, dirty-gn; streak bh-w, b, bn;
trp, trl; BB bn or bk scoria, magnetic; in acids sol;
Fe, P, Aq, 415.

	Hardness.	The same of the sa
Uranite,	2-2.5	II; micaceons; G 3-8.6; bright yw (Uranite), bright gn
Chalcolite,		(Chalcolite), streak similar; p'ly, ad; lam, brittle; BB fus bkh mas; in nit yw, sol; U, Ca, Cu, P, 430.
Dufrenite,	2-3	Fibrous, radiated; G 3.2-3.4; weak, silky; dull leek-gn,
		yw, bnh on exposure; etreak gn; strl; BB fus! slag magnetic; in acids sol; Fe, P, Mn, Aq, 427. Delvaux- ene is ywh-bn, bnh-bk, rdh; G 1.85; Fe, P, Aq, 427.
Carphosiderite,	4-4.5	Reniform; G 2.5; res; straw-yw; streak ywh; feel greasy; BB magnetic bead; Fe or Fe, P, Aq, 431.
Alluaudite,	4.51	Massive, sometimes cleav; dull clove-bn, rdh-yw; streak
Hureaulite,		ywh, strl, op; BB glob, bk, magnetie; in mur sol; Fe, Mn, P, Aq, 407.
Zwieselite,	5	VII cryst, massive; G 3.97; greasy; clove-bn; streak gyh-w; BB decrep, bh-bk glass, magnetic; Fe, Mn, P, F, 399.
Triplite,	55.5	III; cryst, massive; G 3.4—3.8; resinous, adamantine; bn, bkh-bn; streak ywh-gy; strl, op; BB fus! bk seoria; in nit sol; Mn, Fe, P, 408.

a. Species distinctly foliaceous or fibrous in some varieties.

Vivianite, 415.	H=1.5-2	Fib, fol.	Chalcolite, 430.	H=2-2.5	Fol!
Uranite, 430.	2-2.5	Fol!	Dufrenite, 427.	2-3	Fib.

B. Species arranged according to their specific gravities.

THE PERSON NAMED IN	Sp. gravity.		Sp. gravity.
Delvauxene, 427.	1.85.	Dufrenite, 427.	3.2-3.4.
Hureaulite, 407.	2.27.	Allunudite, 407.	3.468.
Carphosiderite, 431.	2.5.	Triplite, 408.	3.4-3.8.
Viviante, 415.	2.66	Chalcolite, 430.	3.5-3.6.
Uranite, 430.	3-3.2.	Zwieselite, 399.	3.97.

††† Not gelatinizing with acids; B.B. no phosphorus reaction.

Obs.—Lepidomelane, Stilpnomelane, Limonite, Göthite, Crocidolite, Anthosiderite, afford B.B. a magnetic globule.

Tree, mileta bibi	m rombuor	and Browner.
Molybdine,	1	Yw, powder or crust; BB on charcoal slag; in mur sol; Mo; occurs with Molybdenite, 144.
Chlorophæite,	1.5—2	Massive, or foliated granular; G 2.02; dark-gn, bkh; BB fus; Fe, Si, Mg, Aq, 278.
Sordawalite	2.5	Pitch-bk, gyh-bk, massive; G 2·5—2·6; streak liver-bn; BB fus dif; in mur partly sol; Al, Fe, Si, H, 177.
Lepidomelane,	*8	VI; in small micaceous black scales or aggregations of scales; G 3; ad, vit; atreak mountain-gn; op, strl: not flex; BB fus, bk, op, magnetic; with bor bottle-gn glass; Fe, Al, K, Si, 227.
Stilpnomelane,	3	Foliated, rad, mas; G 3-34; vit, p'ly; bk, gnh-bk;

Fe, Si, Al, Aq, 287.

	Hardness,			
Limonite,	85.5	Massive, botry	oid, stalact, incrust,	earthy; G 8.6-4;
		silky, dull;	bn, ochreous; streak	ywh-bn; BB bkns,
		magnetic; f	us dif!; with bor iron	; Fe, O, Aq, 131.
Mosandrite,	4		so fibrous, cleav; G 2	
			; streak gyh-bn; BB f	
a			anganese ; Ti, Ce, Mn,	
Crocidolite,	4		8.2—3.8; silky; bh, g	_
0-41.4		•	ast; CB fus! magnetic;	
Göthite,	55.2		il, fibrous, reniform, m bnh-yw; BB bkns ma	
		bor iron; Fe	·-	gn; ide diri; with
Pyrochlore,	55-5		ral crystals; G 3.8—4	85: vit. ros. vwh
- ,			; streak ywh, bnh; s	
			yw trp, on flaming o	
			Ce, Th, Ca, Ta, Ti, 845.	
Glaucophane,	5.2		e; G 3·108; vit, p'ly;	
		bk, gyh; str	eak gyh-b; trl, op; po	wder slightly mag-
			as! gn glass; in acids	partly sol; Al, Fe,
		Mg, Na, Si,		
Catapleiite,	6		pasal!; G 2.8; nearly o	
			lla-yw; opaque; BB	•
Wöhlerite.	5.5		ly; Na, Zr, Si, Aq, 308 pms, massive; G 3·4; l	
wonterive,	0.0		w; vit, res; trp—strl;	
•		•	Ca, Na, Si, 843.	DD ywn giass, in
Keilhauite.	6∙5		7; G 3.69; vit, res;	bnh-bk: bnh-r in
,			treak gyh-bn; BB fus	
			, Y, Si, Ti, 341.	. 0,
Anthosiderite,	6.2	Tufts, fibrous i	n structure ; G 3·6 ; ocl	re-yw, bnh ; streak
		same; tough	; BB rdh-bn, fus dif, b	lack magnetic slag;
		•	Fe, Si, Aq, 304.	
Schorlomite,	7—7.5		av; black, sometimes	
			1; vitreous; streak gy	
			mass; in mur partly	soluble; Ti, Ca, Fe,
	<i>a</i> .	Si, 842.		
	-		us in some of their vari	
Stilpnomelane, 2 Lepidomelane, 2		H=3 Fol. 3 Fol.	Limonite, 181. Crocidolite, 279.	II=3-3.5, Subfib. 4 Fib!
Mosandrite, 342.		4 Subfol, fib.	Anthosiderite, 304.	6.5 Fib!
a,	Species o	ırranged accordi	ng to their specific grav	rities.
Molybdine, 144.		Sp. gravity.	Crocidolite, 279.	Sp. gravity. 3·2—3·3.
Chlorophæite, 27		2.02	Wöhlerite, 848.	3·4.
Sordawalite, 177		2.5-2.6.	Anthosiderite, 804.	3.1.
Catapleiite, 308. Mosandrite, 842.		2·8. 2·9—3.	Limonite, 131. Keilhauite, 341.	8·6 4 . 3· 69.
Lepidomelane, 2	27.	3	Schorlomite, 342.	3.7-3.81
Stilpnomelane, 2		8-8·4. 3·108.	Pyrochlore, 845.	3·8—5·4. 4—4·4.
Glaucophane, 17		9 100.	Göthite, 129.	1 - 1 4.

c. B.B. no fumes, (except sometimes of lead); globule malleable.

* Infusible.

Chrysocolla,

Hardness.

Chrysocolla,

Massive, and in seams; G 2—2'3; bh-gn; trl, op; BB
with bor gn globule, and a grain of copper; in mur
decomposed, silica deposited; Cu, Si, Aq, often with
some C, 309.

Cassiterite,

6—7 H; cryst, massive; adamantine; subvit, subres; bn,
bk; streak gyh, bnh; BB with soda tin, 118.

Dioptase,

5 VI; Emerald gn cryst; G 3'2—3'4; vit; trp, strl; BB
bk; with bor gn globule, and finally copper; in mur
gelat; Cu, Si, Aq, 309.

** B.B. fusible; a globule of Lead, Copper, or Silver, with the fluxes, if not without. No fumes of Arsenic, Sulphur, Selenium, or Antimony.

+ Gravity below 4.5; ores of Copper.

Obs.—Aurichalcite, Chalcolite, Thrombolite, Malachite, Azurite, Libethenite, and Phosphochalcite, are hydrous species; Aurichalcite, Malachite, and Azurite, are carbonates.

Aurichalcite, 2 Acicular, drusy; granular, lamellar; p'ly; verdigris-ga; trl; BB darker, slag; with soda and bor copper and zinc; in mur sol, efferv; Zn, Ču, Č, Aq, 460. Buratile is similar.

Chalcolite, 2-2.5 II; micaceous; G 3.5-3.6; emerald-gn; apple-gn; streak gnh; BB fus bk, flame bh-gn; in nit ywh-gn sol; U, Cu, P, H, 430.

Volborthite, 3-3.5 VI; mas; earthy; G 3.4-3.9; p'ly, vit; gn, gy; streak ywh, bnh-yw, bn, gy; strl; BB fus! no intum, slag; with bor chrome-gn glass; Ču, Ča, and Vanadic Acid, 362.

Thrombolite, 3—4 Amorphous; G 3.38—3.4; vit; emerald, dark-gn; op; BB flame b, gn; on charcoal fus! copper; Cu, P, Aq,

Malachite, 3.5—4 IV; mas, earthy, tuberose, incrust, compact fib; G 3.7
—4.1; silky, adamantine, dull; gn; streak paler; trl,
op; BB on charcoal fus! copper, flame gn; acids
efferv; Cu, C, Aq. 458.

Azurite, 3.5—4.5 IV; mas, earthy; G 3.5—3.9; vit; adamantine; bright deep-b; streak paler; trp, strl; brittle; BB on charcoal fus, copper, flame gn; in acids effery; Ču, Č, Aq. 459.

Libethenite, 4 III; G 3.5-3.8; resinous; olive-gn, dark; streak same; strl; BB fus bnh globule† on charcoal copper; Cu, P, Aq, 420.

Hardness

Phosphochaloite, 4.5-5 IV; mas; G 3.8-1.4; ad, vit; emerald, dark-gn, verdigris; streak paler; trl, strl; BB fus! on charcoal copper; in nit sol; Cu, P, Aq, 425.

a. Species foliated or fibrous in some of their varieties.

Aurichalcite, 460. H=2 Lam, fib. • Malachite, 458. 3.5—4 Fib. Chalcolite, 480. H=2-2.5 Fol!

B. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Aurichalcite, 460.	8·2—8·4.	Azurite, 459.	8.5—3.9.
Buratite,	8·83·4.	Libethenite, 420.	8·5—8·9.
Thrombolite. 412.	8·83·4.	Malachite, 458.	87-4.1.
Volborthite, 362.	8·48·9.	Phosphochalcite, 425.	3.8-4.4.
Chalcolite, 480.	3.5-8.6.	•	

Gravity above 4.5; ores of Lead, Copper, or Silver; colors various.

Minium, Massive, earthy; G 4.6; bright red; BB fus; on charcoal lead; Pb, O, 126. Mas, scaly cryst; G 8; yw, ywh; BB fus! Pb, O, 109. Mumbic Ochre. 2-8 Melaconite. I; mas; earthy; G 5:1-5:4; bk; streak bk; BB on charcoal no fumes; glob copper; Cu, O, 109. IV; clear! G 5.2-5.5; vit, ad; azure-b; streak paler; Linarite, 2.5-3 trl; BB fus; Pb, Cu, S, Aq, 890. Vauquelinite. 2.5-3 IV; reniform, botryoidal, gran; G 5.5-5.8; adamantine, res; dark-gn; bkh-gn; streak siskin gn, bnh; trl, op; BB fus, on charcoal gray, submet; some points of lead; in nit partly sol; Pb, Cu, Cr, 360. 2.5-8 IV; cryst; massive; G 5.9-6.1; adamantine, vit; Crocoisite. bright hyacinth-red; streak orange; trl; BB fus, on charcoal with soda lead; in mur sol, gn; Pb, Cr, 359. Caledonite, 2.5-3 III; G 6.4; resinous; verdigris-gn, bh-gn; streak gnhw; trl; BB on charcoal lead; Pb, Cu, S, C, 372. III; mas; G 575; res, ad; bright red; lemon-yw on Melanochroite, 3-35 exposure; streak brick-r; strl, op; BB fus! on charcoal lead; Pb, Cr. 361. Cryst, massive; 5.8-7.2; color ywh, rdh-bn, dull red, Vanadate of Lead, 3.5—4 (Dechenite and Vanadinite); bn, bk, wh, (Descloizite); deep red, (Aræoxene); BB fus easily; with soda lead, 361-364. I; octahedral, massive; earthy; G 5.85-6.15; adaman-Red Copper.

sed Copper.

3.6—4 1; octahedral, massive; earthy; G 5.85—6.15; adamantine, earthy; red, often bnh; streak bnh-r; strp-op;
BB on charcoal copper; Cu, O, 101. Chalcotrichite is similar but capillary and trimetric, 122.

• No species in this subdivision fibrous or foliated.

B. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Minium, 126.	4.6.	Red Copper, 101, 126.	5.85-6.15.
Melaconite, 109.	5.1-5.4.	Vanadate Lead, 361, 3	
Linarite, 390.	5.2-5.5.	Crocoisite, 359.	5.9-6.1.
Vauquelinite, 360.	5.5-5.8.	Caledonite, 372.	6.4.
Melanochroite, 361.	5.75.	Plumbic Ochre, 109.	8.

c. B.B. WHOLLY AND EASILY VAPORIZABLE IN FUMES, LEAVING NO METALLIC GLOBULE, (UNLESS ANTIMONY OR BISMUTH).

	Hardness	
Coccinite,		Earthy particles, rdh-bn; BB violet; Hg, I, 96.
Sulphur,	1.5—2.5	III; crystals, massive; G 2-21; yw; trp, trl; BB sulph fumes, 22.
Selensulphur,	1.5-2.5	Massive; G 2·1-2·5; orange or bnh; on char sulph and selen fumes, 24.
Selenium,		Incrust; G 4·3—4·8; gyh, bnh; red in splinters; powder red; selen fumes, 23.
Ammiolite,		Red powder consisting of antimonous acid and quick- silver, 142.
Orpiment,	1.5-2	III; cleav !, submicaceous, laminæ flexible, inelastic ; G
Dimorphine,		3.4-3.5; p'ly; lemon-yw; streak ywh; strp, strl; BB
	-	fus, burns b flame, fumes alliaceous; As, S, 32. Dimorphine no cleav, 32.
Realgar,	1:5-2	IV; cleav; massive; G 3.4—3.6; res; bright-rd; streak ywh—rdh; trp—trl; sectile; BB fus! burns b flame, fumes alliaceous; As, S, 31.
Kermesite,	1-1-4	IV; capillary cryst in tufts; 4.4—4.6; adamantine; cherry-rd; streak bnh-r; trl, strl; sectile; BB on charcoal fus, vol, sulph fumes; Sb, O, S, 141.
Cinnabar,	2-2.5	VI; mas; earthy; G 8.5—9; adamantine, in crystals, submet; also dull earthy; cochineal-r, bnh-r; streak scarlet; strp, op; BB volat, sulph; in a matrass with soda, quicksilver; Hg, S, 49.
Bismutite,	4-4.5	Acic, incrust; vit; earthy; w, gnh, ywh; streak gnh-gy; strl-op; BB decrep, fus! on charcoal met, fumes; Bi, Ö, Aq, 462.
Cervantite,	5.5	Mas; G 5.28; greasy; ywh; streak ywh, shining; trp; BB on charcoal fumes inod; Sb, O, H, 141.

. Species foliated or fibrous in some of their varieties.

Orpiment, 32.

Fol!

B. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Coccinite, 96,		Selenium, 23.	4.3-4.8.
Ammiolite, 142.	-1	Kermesite, 141.	4.4-4.6.
Sulphur, 22.	2-2-1.	Cervantite, 141.	5.28.
Selensulphur, 24.	2.1-2.5.	Bismutite, 462.	6.8-7.7.
Orpiment, 32.	3.4-3.5.	Cinnabar, 49.	8-9-1.
Realgar, 31.	3.4-3.6.	f	-

d. B.B. funces of Aesenic, sulphur, antimony, or chlorine; a GLOBULE WHICH IS NOT MALLEABLE.

• B.B. fumes arsenical. Species all contain water.

Hardness

Annabergite, IV; capil; mas; fine apple-gn; streak gnh-w; BB on charcoal arsenie; Ni, As, Aq, 418.

Pitticite, Reniform, mas; G 20-2.5; vit, greasy; ywh, rdh-bn, r, w; streak yw; trl, op; BB on charcoal arsenic; Fe, Disdochite, **As, B, Aq, 482, 483.**

Arseniosiderite. 1-2 Fib; diverg; G 3.5-3.9; yw, golden; streak ochreous; fibres separable!; BB fus bk; with soda arsen; in hot nit or mur, sol; Fe, Ca, As, Aq, 422.

1.5-2.5 IV; cleav!! laminæ flexible; earthy; G 2.948; p'ly, Erythrine, earthy; peach-r, crimson; gyh; streak paler lavenderblue; trp, strl; BB on charcoal arsenic; in acids sol; Co, As, Aq, 416.

2.5 IV; cleav!; G 2.957; p'ly, vit; indigo, gn; streak bh-Symplesite, w; strp-trl; BB on charcoal arsen; bk, without melting, magnetic; Fe or Fe, As, Aq, 418.

I; cubes, etc; G 2.9-3; adamantine; olive-gn, ywh, Pharmacosiderite, 2.5 bnh, rdh, gn; streak gn, bn, yw; strl; BB on charcoal Beudantite, arsen, magnetic; Fe, Ās, Aq, 422.

Köttigite. 2.5-3 IV; cleav /; crusts; G 3.1; silky; light rd; streak rdhw; trl, sbtrl; BB on charcoal fus, arsen; in acids sol!; Zn, Co, As, Aq, 418.

a. Species foliated or fibrous in some of their varieties.

Arseniosiderite, 422.

Fib.

Erythrine, 416.

Fol.

** Fumes of Chlorine, Sulphur or Antimony.

Greenockite. 3-3.5 VI; hexag cryst; G 4.5-5; adamantine; honey-yw, orange; streak yw rdh; strp, trl; BB on charcoal ywh ring; in mur sol; Cd, S, 51.

Hauerite, I; G 8:463; met-adamantine; rdh-bh, bnk-bk; streak bnh-r; BB on charcoal sulphur; Mn, S, 56.

Pyrosmalite. 4-4.5 VI; hexag; cleav basal; mas; G 3-3.1; p'ly, vit; pale liver-bn, gy, gnh; gnh-yw within; BB on charcoal fumes of chlorine, fus slag, magnetic; in nit perfectly sol; Fe, Man, Cl, Si, Aq, 310.

Voltzite. Implanted glob; G 3.66; vit, p'ly; rdh, ywh, bnh; op, 4.5 strl; BB on charcoal zinc fumes; in mur sulph hyd; Zn, S, O, 127.

II; octahed; hyacinth or honey-yw; BB fus bkh slag; Romaine. in acids insol; Ca, Sb, O, 410.

. None of the species of this subdivision are foliated or fibrous.

$oldsymbol{eta}$. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Romeine, 410.		Voltzite, 127.	3.66.
Pyrosmalite, 310. Hauerite, 56.	8— 3·1.	Greenockite, 51.	4.85.
Hauerite, 56.	8.463.	·	

e. B.B. fumes of sulphur, arsenic, antimony, chlorine, bromine or iodine; a malleable globule of silver or copper.

OR IODI	NE, A	RALLEADLE GLODULE OF SILVER OR COPPER.
	* A	rsenical, Sulphur, or Antimony fumes.
	Hardness	•
Tyrolite,	1.5—2	III; reniform, mas; drusy; p'ly, vit; G 3-3:1; pale apple-gn, bh; streak paler; trl, strl; laminæ flexible; BB on charcoal fus, arsen; Ču, Ås, Aq, 426.
Covelline,	1.5—2	VI; incrust; mas; G 3.7-8.9; res, faint; indigo-b; streak lead gray, shining; BB on charcoal fus, sulphur, copper; Cu, S, 65.
Lettsomite,		Drusy, velvety crusts; clear smalt blue; p'ly; BB on charcoal copper; Cu, Al, S, Aq, 892.
Chalcophyllite,	2	VI; cleav basal!!, foliated!; G 2.4—27; p'ly, vit; emerald, grass gn; streak paler; BB decrep, on charcoal arsen, fus; with soda copper; in acids sol; Cu, As, Aq, 428.
Kanthocone,	2	VI; reniform, massive, cryst structure within; G 5-5-2; dull-rd, clove-bn; streak yw; sbtrl, edges orange; BB on charcoal sulph, arsen, silver; Ag, S, As, 87.
Fireblende,	2	IV; G 4.2—4.3; p'ly adamantine; hyacinth-r; trl; sec- tile and somewhat flexible; Ag, S, Sb, 88.
Liroconite,	2-2.5	III; rarely gran; G 2.8—3; vit, res; sky-b, verdigris; streak same; BB on charcoal areen, bk scoria; with bor gn, partially reduced; in nit sol; Cu, Xl, As, Aq, 429.
Miargyrite,	2—2.2	IV; cleav imperf; G 5.2-5.4: submet-adamantine; iron- bk; streak dark cherry-red; thin splinters red; sectile; BB on charcoal antim, sulph, silver; Ag, S, Sb, 74.
Proustite,	2—25	VI; crystals and massive; 5.4—5.5; adamantine; cochineal-r; streak bright red; strp, trl; BB on charcoal sulphur, arsen, silver; Ag, As, S, 78.
Pyrargyrite,	2—2.5	tine; bk, rdh; streak cochineal-r; trl, op; sectile; BB on charcoal sulphur, antim, silver; Ag, S, Sb, 77.
Aphanesite,	2.5—3	IV; massive, rad hemispher; G 4:19—4:86; p'ly; dark verdigris; streak same; strl; BB on charcoal fus, deflag, arsen; Cu, As, Aq, 428.
Olivenite,		III; glob, reniform, fibrous; massive; G 8-9-4-4; ad, vit, p'ly; olive-gn, leek-gn; wood-bn; streak gn, bn; strp, op; BB on charcoal fus, deflag!, arsen: in mit sol; Am Ta Ac Aco.

	Hardness.	
Carminite,	2.5	In clusters of fine needles; carmine to tile-red; BB ca charcoal arsenic; with soda lead; Pb, Ās, Fe† 410.
Brochantite,	8.5—4	III; G 3.8-3.9; vit; emerald, bkh-gn; streak paler; trp; BB on charcoal fus, copper; Ču, S, Aq, 391.
Euchroite,	8·5 4	III; G 3:389; vit; bright emerald, leek-gn; streak paler; trp, trl; BB on chercoal fus, deflag, copper, arsen; Cu, As, Aq, 421.
Erinite,	4:5—5	Mammillary, massive; G 4043; dull, res; fine emerald-green, streak paler; strl, op; BB arsen, copper; Cu, As, Aq, 425.
Conichaleite,	4.2	Massive, reniform; G 4·123; pistachio-gn; streak same, Ču, Ča, Ās, P, H, 421.

a. Species foliated or fibrous in some of their varieties.

Chalcophyllite, 428. Lettsomite, 392.	H=2	Fol!	Aphanesite, 428.	H=2·5-8	Fib.
Lettsomite 392.		Drusy fib.	Olivenite, 420.	8	Fib.

β. Species arranged according to their specific gravities.

Letteomite, 892.	Sp. gravity.	Erinite, 425.	5p. gravity. 44)48.
Chalcophyllite, 428.	2.4-2.7.	Conichalcite, 421.	4.128.
Liroconite, 429.	2.8—3.	Aphanesite, 428.	4-19-4-16
Tyrolite, 426.	8 - 8.1.	Fireblende, 88.	4.2-48.
Euchroite, 421.	8.389.	Xanthocone, 87.	55-2.
Brochantite, 391.	8.7-8.9.	Miargyrite, 75.	5-284.
Covelline, 65.	8.8—8.9.	Proustite, 78.	5.4-5.6.
Olivenite, 420.	8.9-4.4.	Pyrargyrite, 77.	5-75-8
Carminite, 410.	• • • • • •	- J	

** Fumes of Chlorine, Bromine, Iodine, or Muriatic Acid.

Iodyrite,		VI; thin plates, lam; G 5:504; resinous; pale citron- yw, ywh-gn; trl; streak submet; plates flexible; BB fus!!, on charcoal fumes of iodine, violet flame, silver; Ag, I, 95.
Kerargyrite,	1—1.5	I; like wax; G 5-56; pearl-gy, gnh; bn on exposure; streak shining; sectile; BB fumes of muriatic acid; on charcoal silver; Ag, Cl, 92.
Bromyrite,	1—2	I; concretions; G 5.8—6; splendent; often gn without, yw within; BB fus; fumes of bromine; silver glob; Ag, Br, 93.
Percylite,	1	I; in cubes; sky-blue; BB emerald-gn easily! b on cooling; flame gn, fue!, on charcoal fumes; Pb, Cu, Cl, O, see Appendix.
Embolite,	2	I; oct; mas; G 5.85.8; yw, gn; adamantine; fracture hackly; BB fus! fumes of bromine and chlorine; silver glob; Ag, Br, Cl, 98.
Connellite,	•	VI; vit; fine blue; trl; BB on chercoal fumes; glob copper; Cu, S, Cl, 375.

Hardness.

Atacamite,

8-8.5 III; mas; G 3.7-4.3; adamantine, vit; olive-gn, bright gn; streak paler; trl, strl; BB gn or b flame, fumes of muriatic acid; on eharcoal copper; Cu, Cl, O, Aq, 188

a. None of the species in this subdivision are properly foliated or fibrous.

II. LUSTRE METALLIC OR SUBMETALLIC.

A. STREAK UNMETALLIC.

a. B.B. no fumes.

- B.B. Infusible, or nearly so. Colors steel-gray to black.
- † With muriatic acid, fumes of chlorine: contain manganese.

Obs.—Wad, Psilomelane and Manganite, are the only hydrous species included.

Wad,

0.5-8.5 Mas; earthy; incrust; G 8-8.7; submet, dull; bk, bh
or bnh; BB infus or subfus; Mn, O, H; sometimes
Mn, Cu, O, H, or Mn, Co, Ni, O, H, 186.

Pyrolusite,
Polianite,
Bk, gyh; streak bk; brittle; BB infus; Mn, O, 122,
131.

Manganite,

4 III; prismatic, columnar, radiated; gran; G 4.2-4.4;

submet; steel-gy, bk; streak rdh-bn, nearly bk; BB infus; Mn, O, H, 130.

Hausmannite, 5-5.5 II; G 4.722; submet; bnh-bk; streak bn; BB infus; Mn, O, 118.

Psilomelane, 6-6 Mas, bot; G 4-4'; submet; iron-bk, gy; streak bnh-bk, shining; BB infus; Mn, O, H, 135.

Braunite, 6-6.5 II; massive and in crystals; G 4.7-4.9; submet; bnh bk; streak dark bnh-bk; brittle; BB infus; Mn, O, 117. Heteroclin (p. 127) and Crednerite (p. 126) are other manganese ores, with black streak. H=4.5-5.

†† No fumes of chlorine with muriatic acid.

Pitchblende, 5.5 I; massive; in grains; submet or dull; G 6.4—8; velCoracite, vet-bk, bnh; streak bk; BB flame usually gn; with
bor fus yw glass, gnh in inner flame; in sit in powder
slowly soluble; U, O, 107. Coracite contains water,

Limonite, 4-5.5 Massive, stalact, botryoid; G 3.6-4; submet; bk, bn; streak bn; BB bkns, magnetic; Fe, O, Aq, 131.

	Hardness.	
Chromie Iron,	5.5	I; oct, massive; G 4.8—4.5; iron bk, gyh-bk; streak bn; brittle; sometimes magnetic; BB infus; with bor fus dif, beautiful gn glob; Fe, Cr, O, 106.
Yttrotantalite,	5.2	G 5:895; submet; iron-bk; streak gy; Y, Ca, Fe, Ta, W, 359.
Columbite, Mengite,	5—6	III; mas, uncleav; G 54-80; bk; submet; often a steel tarnish; streak bk, to bnh-red; brittle; BB infus, with bor fus slow, bkh-gn glass; Fe, Mn, Cb, 358. Mengite contains Zr, Fe, Ti, 356.
Tantalite,	5—6	III; eryst, mas; G 7·1—8; bk; streak rdh-bn; brittle; BB like Columbite; Fe, Mn, Ta, 351.
Fergusonite,	5·5—6	II; hemihed; cleav traces; G 5.8-6; submet, vit; bnh- bk, bnh; streak bnh; strl, op; BB infus; with bor fus dif; Y, C, Ta, 350.
Specular Iron, Ilmenite, Martite, Iserine,	5·5—6·5	VI; cryst, massive; and Specular Iron is sometimes micaceous, &c. Martite and Iserine, I, oct.; G 4·5—5·8; steel-gy, often splendent; BB infus; bor gn or yw glass; in hot mur sol; streak of Spec. Iron red; of Ilmenite black or nearly so, or submet; 113, 115: Martite is the same as Specular Iron, except it is octahedral, 102. Iserine is similar to Martite, 102.
Franklinite,	5·56·5	5 I; oct, massive, gran; G 5-5·1; bk; streak dk rdh-bn; slightly magn; BB infus; on charcoal oxyd zine at high heat; with bor manganese reaction; Fe, Mn, Zn, O, 106.
Exenite, Polymignyte, Eschynite,	6.2	III; massive without cleav; G 4.6—4.9; submet, vit; bnh-bk, rdh-bn! streak rdh-bn; BB infus; with bor fus; Y, U, Ce, Ti, 358, 356. Polycrase similar; G 5.1; in sul sol, 357. Æschynite BB intum on thin edges, but infus, 357.
Irite,		Octahedral; G 6.506; contains Iridium and Osmium, with Iron and Chromium, 103.

a. Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Wad, 136.	3-87	Polymignyte, 356.	4 77-4 85.
Limonite, 131.	3·6—4.	Polianite, 131.	4.8-4.9.
Pulomelane, 135.	44.4.	Æschynite, 357.	4.9-5.14.
Manganite, 130.	4.2-4.4.	Franklinite, 106.	5—5·1.
Chromic Iron, 106.	4.8-4.5.	Polycrase, 357.	5 ·1.
Hausmannite, 118.	4-722.	Yttrotantalite, 359.	5·395.
Ilmenite, 115.	4.5-5.	Columbite, 853.	5.4-6.4.
Pyrolusite, 122.	4.8—5.	Mengite, 856.	5.48.
Specular Iron, 113.	4.5-5.3.	Fergusonite, 350.	5.8—6.
Martite, 102.	3.8 - 5.3.	Tantalite, 351.	7-8.
Euxenite, 858.	4.6-4.9.	Pitchblende, 107.	6.4—8.
learing, 102.	4.8—5.1.	Irite, 108.	6.507.

** Fusible. Colors steel-gray to black.

Obs.—Tenorite and Melaconite afford a globule of copper; Magnetite fuses with difficulty; Crednerite contains manganese. No species fibrous.

	Hardness,	
Tenorite,		VI; scales; dark steel-gy; streak bk; BB on charcoal no fumes, copper globule; Cu, O, 117.
Melaconite,	3— 6	I; mas; G 5:1-54; earthy; bk; streak bk; BB on charcoal no fumes, copper glob; Cu, O, 109.
Crednerite,	4.5	IV; cleav; G 4.9-5; met; iron-bk, gy; streak bk, bnh; BB fus dif! Mn, Cu, O, 126.
Wolfram,	5 5·5	III; cryst; mas; uncleav; G 7·1—7·6; submet; gyh-bk, bnh-bk; streak dark rdh-bn; BB fus dif, magnetic globule; with bor gn bead; Fe, Mn, W, 351.
Samarskite,	5.2	III; in grains; G 4-57; bk; streak dark rdh-bn; BB burns like Gadolinite, fus dif! to a steel-gy mass; with bor fus! Fe, U, Y, Cb, 355.
Lievrite,	5.5—6	III; rbc prism; massive; G 3.8—4.2; submet; bk, bnh; brittle; BB fus bk glob; in mur sol, gelat; Fe, Ca, Si, 262.
Magnetite,	5·5—6·5	I; octahedrons, &c. massive, gran; G 4.9—5.2; bk; streak bk: magnetic: BB fus dif! loses magnetism:

b. B.B. giving off fumes.

in hot mur sol; Fe, O, 105.

B.B. fumes of Arsenic, and sometimes also of Sulphur; globule brittle.
 Color whitish, with sometimes a reddish or yellowish tinge, excepting
 Tennantite, which is black. No species fibrous.

Obs.—Tennantite, Leucopyrite, and Mispickel alone afford B.B. a magnetic globule; of the other species, Kaneite gives a manganese reaction, and the rest a reaction of Cobalt or Nickel.

Tennantite,	3.5—4	I; G 4.8-4.5; bkh lead-gy, iron-bk; streak dark rdh-gy; BB burns b flame, arsen, bk scoria magnetic; Cu, Fe, S, As, 84.
Leucopyrite,	5-5.2	III; cryst, mas; G 7.0—7.4; tin-w, gyh; streak gyh-bk; BB on charcoal fumes of arsenic, mag glob; Fe, As, 61.
Copper Nickel,	5-5-5	VI; massive; G 7:3-7.7; copper-r, gyh or bkh tarnish; streak pale bnh-bk; brittle; BB on charcoal arsen; fus w glob; in nit gn coating; Ni, As, 52.
Kaneite,	above 5	Massive, botryoidal; fol or gran; gyh-w, bkh tarnish; BB b flame, on charcoal arsen; nit-mur sol wholly; Mn, As, 53.
Gersdorffite,	5.2	I; cleav cubic; massive; G 5.6-6.9; silver-w, gyh;

arsen; Ni, As, S, Fe, 58.

tarnish gy, gyh-bk; streak gyh-bk; BB on charcoal

	Hardness.	
Smaltine, Chloanthite,	5-5	I; in crystals; massive; G 646—7-2; tin-w, gyh; streak - gyh-bk; brittle; BB on charcoal arsen, w glob; Co, Ni, As, Fe, 56. Rammelsbergite is similar, but trimetric, 61.
Cobaltine,	5-5	I; hemihed; massive; G 6-6-8; silver-w, rdh; streak gyh-bk; brittle; BB on charcoal arsen, bk mag glob; Co, As, S, Fe, 57.
Mispickel, Glaucodot,	5—6	III; crystals; usually massive; G 60—64; silver w, gyh; streak dark gyh-bk; BB on charcoal arsen fumes; mag glob; Fe, As, Co, S, 62, 68.
Skutterudite,	6	I; clear cubic; G 6-7-6-9; gyh tin-w; BB on charcoal arsen; Co, As, 67.

Species arranged according to their specific gravities.

Tennantite, 84.	Sp. gravity. 4'8—4'5.	Skutterudite, 67.	5p. gravity. 67—6-9.
Gersdorffite, 58.	5.6-6.9.	Smaltine, 56.	6.4-7.2.
Glaucodot, 68.	5·9—6·1.	Chloanthite, 56,	6.47.2.
Cobaltine, 57.	663.	Leucopyrite, 61.	7.0-7.4
Mispickel, 62.	6.06.4.	Copper Nickel	7.8-77.
Ulimannite, 59.	6.2-6.5.	Kaneite, 58.	

** Fumes sulphurous or antimonial, not arsenical; globlule brittle. Colors rather pale, (excepting Manganblende, which is black).

Obs.—Berthierite, Pyrrhotine, Pyrites, and Marcasite afford B.B. a magnetic globule; Manganblende, a manganese reaction; the others reactions of Cobalt or Nickel. Breithauptite contains Antimony. Erubescite, Cuban, and Chalcopyrite, also afford BB a magnetic globule, but with borax or soda they yield a globule of copper, and they are consequently not included in this subdivision.

Syepoorite,		Massive; G 5.45; steel-gy, ywh; Co, S, 41.
Berthierite,	28	Long prisms or massive plumose; G 4—4-3; dark steel- gy; pinchbeck-bn; BB fus! antim fumes, bk magnetic slag; Fe, S, Sb, 73.
Millerite,	83-5	VI; capillary; G 4.61—5.65; brass-yw, tarnish gy, irid; brittle; streak bright; BB fus, brittle glob; warm nit gyh or pale-gn sol; open tube sulph; Ni, S, 49.
Manganblende,	8·54	I; clear cubic; mas; G 3 9-4:1; submet; iron-bk, bn on exposure; streak gn; BB on charcoal fus dif!; in mur sul-hyd; Mn, S, 41.
Pyrrhotine,	3.2—4.2	VI; hexag, mas; G 44-47; bronze yw, rdh; streak dark gyh-bk; magnetic; BB nearly like Pyrites; Fe, S, 450.
Gränsuite,	4.2	I; clear octahed; G 5:18; pale steel-gy, silver-w; tar- nish ywh, gyh; brittle; streak dark-gy; BB on cher- coal sulph, coal ywh; Ni, Bi, Fe, S, 44.
Ullmannite,	5—5.5	I; clear cubic; mass; G 64—655; wh steel-gy; brittle; BB on charcoal fumes antim, sulph; Ni, Sb, S, 59.
Linnæite,	5.5	I; clear cubic; G 4.8-50; pale steel-gy, copper-r tarnish; streak bkh-gy; BB on charcoal sulphur; Co, S, 67.

RAL
orz.

LUSTEE METALLIO-STREAK UNMETALLIO.

•	Hardness.	
Breithauptite,	5.2	VI, thin plates; arborescent; G 7.5—7.6; light copper rd, violet; streak rdh-bn; brittle; BB on charcoal antim; Ni, Sb, 58.
Pyrites,	6-6-5	I; cubes, &c. also massive; pale brass-yw; streak dark bnh-bk; G 4·5—5·1; BB on charcoal fumes sulph; mag glob; nit sol; Fe, S, 54.
Marcasite,	66-5	 III; in thin crystals, often crested; also massive; G 4-65 4-85; pale ywh-bronze, ywh, gyh; streak gyh-bk; BB like Pyrites; Fe, S, 60.

Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Manganblende, 41.	8·9—4·1.	Grünauite, 44.	5.13.
Berthierite, 78.	4-4.3.	Sycpoorite, 41.	5.45.
Pyrrhotine, 50.	4.4-4.7.	Millerite, 49.	4.6-5.65.
Marcasite, 60.	4.6-4.9.	Ullmannite, 59.	6.4—6.6.
Pyrites, 54.	4.8 - 5.1.	Breithauptite, 58.	7.5-7.6.
Linnseite, 67.	4.8-5.0		

B.B. with the fluxes, if not without, a malleable globule, or mineral wholly vaporizable.

† Globule of Lead, Silver or Gold. (Aikinits and Cuproplumbite, afford a globule of lead containing copper.)

Obs.—Sulphur fumes, Cuproplumbite; Antimony or bismuth fumes, often with sulphur, Heteromorphite. Miargyrite, Pyrargyrite, Kobellite, Aikinite, Tannenite; Selenium fumes, Clausthalite.

Heteromorphite,	1—8	Capillary, plumose; massive, gran; G 5.6—5.9; dark lead-gy, steel-gy; BB fus!!, on charcoal antim, sulph; Pb, S, Sb, 76. For other antimonial ores of lead, see p. 72, etc.
Miargyrite,	2-2.5	IV; clear imperf; G 5.234; submet ad; iron-bk; streak dark cherry-red; op, thin splinters red; sectile; BB on charcoal antim, sulph, silver; Ag, S, Sb, 74.
Pyrargyrite,	2-2.5	VI; massive; G 5.7—59; met-adamantine; bk, rdh; streak cochineal-red; trl, op; sectile; BB on charcoal sulph, antim, silver; Ag, S, Sb, 77.
Kobellite,	soft	Like Stibnite; radiated columnar; G 6:29-6:32; bkh lead-gy to steel-gy; streak bk; BB fus, charcoal yel-

low, w glob; Pb, S, Bi, Sb, little Fe, 82.

Aikinite,

2-2.5 III; acicular cryst; mas; G 6.1-6.8; bkh-lead-gy, pale
rdh tarnish; BB on charcoal fumes sulph; Bi, Pb, Cu,

rdh tarnish; BB on charcoal fumes sulph; Bi, Pb, Cu S, 81.

Tannenite. Thin prisms; bright metallic; gyh to tin white; BB sulphur, on charcoal with soda copper, fumes of bismuth;
Ch. Ri. S. 72

Cuproplumbite, 2.5 I; clear cubic!; mas; G 64—645; bkh-lead-gy; streak bk; BB on charcoal lead, sulph; Pb, Cu, S, 41.

Hardness

Dufrénoyaite,

I; dodec; G 5.55; steel-gy; streak rdh-bn; brittle;

BB on charcoal arsen, sulph, lead; in acide sol; Pb, S,

Clausthalite, 2.5 I; granular mas; G 7—8.8; lead-gy, bh; streak dark gy; BB on charcoal selen, lead; Pb, S, with sometimes Co, Ag, Cu, 42.

†† Globule of copper or tin with sods.

Obs.—Sulphur fumes alone, Erubescite, Chalcopyrite, and Tin Pyrites; Antimony or bismuth fumes, Wölchite, Wolfsbergite, Wittichite; Arsenical fumes Domeykite, Tennantite, Enargite.

Erubescite,	3	I; cryst mas; G 5-5·1; pinchbeck bn, tarnishes reddish and bluish; lustre bright; streak pale gyh-bk; brittle; BB on charcoal sulph; nit partly sol; Cu, S, 38. Barnhardtite: see Appendix.
Wölchite,	8	IIII cryst, and mas; G 57-58; bkh lead-gy; brittle; BB on charcoal antim, sulph; Pb, Cu, S, Sb, 82.
Domeykite,	33.2	Massive, reniform; G 45; tin-w, ywh tarnish; BB fus arsen; in mur partly sol; Cu, As, 36.
Wolfsbergite,	8-4	III; G 4.748; lead-gy, iron-gy; streak bk; BB decrep, fus!, on charcoal antim, copper; Cu, S, Sb, 73.
Wittichite,	8.5	III; acic, columnar; G 5; steel-gy, tin-w, tarnish lead-gy; streak bk; BB fus! sulph fumes; Bi, Cu, S, 88.
Eaargite,	8	III; massive, gran or fib; G 4·3—4·5; iron-bk; streak same; BB on charcoal, arsen, sulphur, with bor copper; Cu, As, S, 87.
Tennantite,	8.5—4	Tetrahed; G 4.37—4.5; bkh-lead-gy, iron bk; streak dark rdh-gy; BB decrep, burns with b flame, arsen fumes, magnetic globule; Cu, Fe, S, As, 84.
Chalcopyrite, Cuban,	3·5 4	II; tetrahed; mas; G 4·1—4·3; steel-gy, brass-yw; streak gnh-bk; BB on charcoal sulph; fus mag glob;
Tin Pyrites,	5	in nit partly sol; Cu, Fe, S, 68. Cuban is cubic, 68. II; massive; G 4.3—4.52; steel-gy, bkh, ywh; streak bk; BB on charcoal sulph, scor glob bk; nit-mur sol, 70.

Species arranged according to their specific gravities.

	Sp. Gravity.		Sp. Gravity.
Cuban, 68.	41)-4.2.	Miargyrite, 74.	5.234.
Chalcopyrite, 68.	4·1—4·3.	Dufrénoysite, 77.	5.55.
Tin Pyrites, 70.	4.3-4.52.	Heteromorphite, 76.	5.6-5.9.
Tennanite, 84.	4.3-4.5.	Pyrargyrite, 77.	5·7—5·9.
Enargite, 87.	4:3-4:5.	Wölchite, 82.	5·7 —5 ·9.
Domeykite, 36.	4.5.	Aikinite, 81.	6 1—6.8.
Wolfsbergite, 73.	4 75.	Cuproplumbite, 41.	6.4-6.5.
Wittichite, 88.	5.	Kobellite, 82.	6.29 - 6.32.
Erubescite, 38.	55.1.	Clausthalite, 42.	78.8.

B. STREAK METALLIC.

a. NOT MALLEABLE.

* B.B. no fumes with fluxes, or without; infusible.

Hardness,

Graphite, 1.0-20 VI; foliated!, mas, gran; G 2-2.1; steel gy, bkh; sectile; soils; nit no action; BB infus, 29.

** B.B. fumes; globule not malleable.

Molybdenite, 1-1.5 VI; fol!, G 4.44-4.8; lead-gy; laminæ flexible; inelast; sectile; a trace on paper; BB on charcoal sulph; in nit sol; Mo, S, 66.

Irite, Grains or scales; G 6.506; black; magnetic; BB with nitre reaction of osmium; Ir, Os, Cr, Fe, 103.

Iridosmine, VI; also I; scales; G 19—22; tin-w; light-steel gy; BB infusible, with nitre odor of osmium, 19.

Berthierite, 2—3 Prism, mas, cleav; plumose; gran; G 4—4°3; dark steel-gy, tarnishes; BB fus! fumes antim sulph; mwr sol; Sb, Fe, S, 78.

Millerite, 3.5 VI; Acicular crystals; 4.6—5.7; nearly brass-yellow, tarnish gyh: brittle; BB fus, magnetic glob; Ni, S, 49.

••• B.B. fumes; a malleable globule, or wholly vaporizable.

† Easily and wholly vaporizable, (ores of lead not included).

Stibnite,

2 III; in prisms; cleav; also fib, massive; G 4.5—4.65; lead-gy; streak lead-gy; tarnish dark; sectile; BB fus!; on charcoal, fumes, sulph; in mur sol; Sb, S, S. S.

Tellurium, 2-2.5 VI; cleav hexag; gran; G 6:1-6:3; tin-w; streak tinw; brittle; on charcoal fus! gnh-flame; w vapors, 20.

Tetradymite, 2 VI; clear basal!! mas, fol, gran; G 7.2—8.5; pale steel-gy; lamins elastic; soils paper; G fus!! flame b on charcoal wh or ywh, fumes; Bi, Te, with often 8 or Se, 21.

Bismuthine, 2-2.5 III; acicular cryst; cleav; also mas, fol, fib; G 6.4-6.6; lead-gy-tin-w, ywh or iridescent tarnish; sectile; BB fus!, on charcoal vol, yw areola; sulph fumes; in hot mit sol; Bi, S, 33.

Bismuth, 2-2.5 VI; R, cleav! mas; G 9.7-9.8; rdh-silver-w, tarnishes; sectile; brittle; BB fus; on charcoal yellow areols,

Antimony, 3-8.5 VI; cleav!; massive, lamellar; G 6.6-6.72; tin-w rather brittle; BB fus! w fumes, inod, 21.

Bardness.

Native Arsenic, 3.5 VI; massive, reniform gran; G 5.8—6; tin-w, gy; streak the same; BB volat; w fumes, alliaceous; As,

Arsen. Antimony, 8.5
Allemontite,

VI; reniform massive; G 6·1—6·21; tin-w, rdh, gyh; tarnished bnh-bk; BB fus, fumes arsen, antim; Sb, As. 22.

Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity
Stibnite, 33.	4.5-4.65.	Bismuthine, 88.	6.4-6.6.
Arsenic, 22.	5.8-6.	Antimony, 21.	6.6—7.2.
Allemontite, 22.	6.1-6.21.	Tetradymite, 21.	7 ·2 — 8 · 5.
Tellurium, 20.	6·1—6·3.	Bismuth, 20.	9 <i>-</i> 7—9·8.

†† B.B. a malleable globule; fumes odorous.

1 A globule of lead or silver, without copper or a copper reaction.

‡ A glol	oule of le	ad or silver, without copper or a copper reaction.
Nagyagite,	1—1:5	II, foliated! laminæ flexible; also granular; G 6:85—7:2; bkh lead gy; BB on charcoal tellurium, flame b, sometimes sulphur fumes; Pb, Au, Te, S, 65.
Bismuth Silver,		Acic; massive; tin-w, gyh, tarnishes; sectile; BB fus! on charcoal lead, bismuth, silver; sectile; Ag, Bi, Pb, S, 16.
Sylvanite,	1.5—2	III, massive; often like writing characters; G 5 7—8·3; steel-gy, silver-w, or ywh; streak same; very sectile; BB fus; flame gnh-b, malleable globule; sit sol; Au, Ag, Te, 64.
Silver Glance,	2-2.5	I; no cleav; G 7:19-7:37; streak and color bkh lead gy; streak shining; bkh tarnish; sectile!!; Ag, S, 37.
Stephanite,	2-2.5	III: massive; G 6.269; iron-bk; streak same; sectile; BB on charcoal antim, sulph; with soda silver; Ag, S, Sb; some As, 86.
Preislebenite,	2-2:5	IV; cleav; G 6-6.4; steel-gray; wh; dark gyh; streak same as color; BB on charcoal antim, sulph, lead, silver; Ag, Pb, S, Sb. 79.
Sternbergite,		III; cleav basal !!!; foliated; pinchbeck-bn; G 4.215; streak bk; thin lam flexible like tinfoil; traces on paper; BB on charcoal sulphur, b flame, silver, Ag, Fe, S, 71.
Plagionite,	2—5	IV; tabular crystals; massive; G 5.4; bkh-lead-gy; streak same; brittle; BB fus!!; sulphur, antim, lead; Pb, S, Sb, 75.
Naumannite,	2.5	I; cleav cubic; massive; iron bk, splendent; G 80; streak iron-bk; BB on charcoal fus!, selen; with soda silver; Ag, Se, 43. Riolite: see Appendix.
Geocronite,	2-3	III; cryst; massive; G 6.4-6.6; light lead-gy, bh;

streak same; Ph, S, Sb, As, 85.

Boulangerite, 2:5—3 Plumose, columnar; gran; G 5:7—6, bh-lead-gy; BB on

Jamesonite,

Charcoal sulph, antim; Pb, S, Sb, \$1. Jamesonite has

Heteromorphite,

a basal cleavage! p. 75.

Galena, 2.6—3 I; cleav! cubic; massive granular; G 7.2—7.7; lead-Steinmannite, gy; brittle; BB on charcoal sulph, lead; Pb, S, 39. Steinmannite gives antim fumes, 41.

Zinkenite, 3-8.5 III; hexag; G 5.3-5.4; steel-gy; streak same; BB decrep, fus!!; on charcoal antim, lead; Pb, S, Sb, 74.

Brongniardite, above 3 Massive, no cleav; G 5.95; steel-gy; streak gyh-bk; BB on charcoal decrep, fus!, sulphur, w fumes, silver; Pb. Ag. S. Sb. 76.

Chiviatite, Cleav massive; G 6-92; lead-gy; BB sulph, Bi, trace of copper; Pb, Bi, S, 77.

Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Sternbergite, 71.	4.215.	Geocronite, 85.	6.46.6.
Zinkenite, 74.	5.3—5.4.	Chiviatite, 77.	6.92.
Plagionite, 75.	5·4.	Steinmannite, 41.	6.833.
Jamesonite, 75.	5.5-5.8.	Nagyagite, 65.	6.8-7.2
Heteromorphite, 76.	5.6-5.9.	Sylvanite, 64.	5 7 8 3.
Boulangerite, 81.	57—6.	Silver Glance, 37.	7.19-7.4.
Brongniardite, 76.	5.95.	Galena, 39.	7.2—77.
Freislebenite, 79.	66.4.	Naumannite, 43.	8.0.
Stephanite, 86.	6.269.	Bismuth Silver, 16.	

‡‡ Globule of Copper, or of Silver or Lead along with Copper; BB a Copper reaction.

Obs.—Polybasite, Bournonite, and Stromeyerite afford a copper reaction, and on cupellation a globule of silver; Tetrahedrite is sometimes argentiferous.

Berzelianite, Dendritic crusts; silver w; BB selen; fus gy bead; with soda copper; Cu, Se, 43.

Eucairite, 2-2.5 Mas; films; silver-w, lead-gy; streak shining; sectile; BB on charcoal fus! selen!; Cu, Ag, Se, 43.

Polybasite, 2—3 VI; tabular; massive; G 6.214; iron-bk; streak same; BB fus!; on charcoal sulph, antim; with soda arean; Ag, Cu, Sb, S, As, 85.

Copper Glance, 2.5—8 III; in crystals, and massive; G 5.5—5.8; bkh lead-gy; streak same; BB on charcoal sulph, flame bh; copper; hot nit a gn solution; Cu, S, 46.

Bournonite, 2.5—3 III; cruciform and wheel-shaped cryst; massive; G 5.7

-5.0; steel-gy, bkh; streak same; brittle; BB decrep,
fus!; on charcoal antim, sulph; lead fumes on char;
Pb, Cu, S, Sb, 80.

Stromeyerite, 2.5—3 III; massive; G 6.2—6.3; dark steel-gy; streak shining; sectile; BB fus!; glob little malleable; on charcoal sulph; with lead, silver; Ag. Cu, S. 48.

Tetrahedrite, 8-4 I; tetrahed; massive; G 45-52; steel gy, bkh; streak same as color, or bnh; BB autim; on charcoal copper; in powder sol nit bnh-gn; Cu, S, Sb, sometimes with Ag or Hg, 82.

Species arranged according to their specific gravities.

		Sp. gravity.		Sp. gravity.
Berzelianite, 48.			Bournonite, 80.	57-59
Eucairite, 48.			Polybasite, 85.	6.214.
Tetrahedrite, 82	•	4:55:8.	Stromeyerite, 48.	6.2-6.8.
Copper Glance,		5.5-5.8.		
	††† B.	B. a malleable glob	oule; fumes inodorous.	
	Hardness	•		
Nagyagite,	1—1.5	bkh lead-gy; l	ible, foliated!; also gran BB on <i>charcoal</i> tellur, i sulphur); Pb, Au, Te, 6	lame b, (some-
Amalgam, Arquerite,	3-8.2		s; massive; silver-w; br er fumes, silver globule;	
Hessite,	2-3.5		re; G 8·3—8·9; lead-gy ble; Ag, Te, 44.	and steel-gy;
Altaite,	8	I; clear cubic, r Te, 44.	nassive; G 8.16; tin-v	r, sectile; Pb,
Discrasite,	8.5—4		-10; silver-w, tin-w; ta ob not malleable; on c	•
Gold Amalgam,		-	asily crumbling; BB fun of gold left; Hg, Au, 15.	nes of mercury,

Species arranged according to their specific gravities.

	Sp. gravity.		Sp. gravity.
Nagyagite, 65. Altaite, 44.	6.8—7.2.	Amalgam, 15.	10.5—14
Altaite, 44.	8·16.	Arquerite, 15.	
Hessite, 44.	8·38·9.	Gold Amalgam, 15.	
Disamonita 95	9.4—10	0 ,	

b. malleable.

Obs.—Palladium, Platinum, and Iridosmine are infusible. Native Bismuth, Bismuth Silver, and Silver Glance, not here included, are somewhat malleable. Iridosmine is imperfectly malleable.

	Sp. gravity	7.
Tin,	7-285	II; gyh-w; BB fus!, 19.
Iron,	7.8—7.8	I; iron-gy; H 4-5; BB fus dif, no fumes; magnetic, 17.
Lead,	11:445	I; lead-gy; BB fus!!, fumes, 17.
Copper,	8·59	I; copper-rd; ductile, malleable; H 2.5—3; BB fus, flame gn; in nit sol, and solution with ammonia blue, 17.
Silver,	10-11-1	I; H 2.5-3; silver-w; BB fus, no fumes; nit sol, 15.
Palladium,	11.512.5	I also VI; scales; H 4.5—5; wh steel-gy; ductile; malleable; BB infus, 14.
Gold,	15.6—19.5	I; massive, grains, leaves; H 2:5—3; gold-yw, sometimes wh; BB fus; in nit insol; in nit-mur sol, 7.
Quicksilver,	13.6	Liquid down to - 39° F.; tin-white, 14.
Platinum,	1619	I; massive; grains; no cleav; H 4—45; whitish steel- gy; ductile; BB infus; in nit insol; in hot nit-mur sol, 12.

Sp. gravity.

Iridosmine,

19-21.5 I, also VI; scales; H 6-7; tin-w; steel-gy; imperfectly malleable; BB infus; with nitre odor of osmium; in nit insol; in hot nit-mur sol, 19.

TABLE II.

MINERALS ARRANGED ACCORDING TO THEIR CRYSTALLIZATION.*

I. CRYSTALLIZATION MONOMETRIC.

I. LUSTRE UNMETALLIC.

	Hardness.	
Kerargyrite,	11.2	Cl none; wax-gy, etc.; G 5:3-5:6, 92.
Bromyrite,	12	Cl none; gn, yw; G 5.8—6, 93.
Arsenolite,	1.5	Whitish; G 8.698. 139.
Sal Ammoniac,	1.5-2	Cl oct; G 1.528; taste saline, pungent, 92.
Sylvine,	2	Cl cubic; G 1.9-2; taste saline, 90.
Embolite,	2	Cl cubic, traces; yw, gnh; G 575-585, 93.
Senarmontite,	2-2.2	Oct; w; G 5·2-5·3, 140.
Common Salt,	2.9	Cl cubic!; G 2.257; taste saline, 90.
Pharmacosiderit	e, 2·5	Cl cubic; G 2-9-8; gn, bn, rdh, 422.
Alum,	2-8	Oct; cl oct perf; taste alum, iron varieties inky, 382.
Percylite,		Cubes; sky-blue.
Manganblende,	3.5-4	Cl cubic!; bk, bn; submetallic; G 8.9-4.1, 41.
Blende,	8.5-4	Tetrahed; cl dodec!; yw, bn, bk, etc; res; G 4-4.2, 45.
Red Copper,	8.5—4	Cl oct; red; G 5.8—6.15, 101.
Fluor,	4	Cl oct perf!; G 8:14-8:18; vit, 94.
Hauerite,	4	Pyritohed; cl cubic; G 8:468; bn, rdh, bk, 56.
Eulytine,	1.5	Hemihed; cl dodec; bn, ywh, gy, yw; G 5-9-6-1, 181.
Analcime,	55∙ŏ	Trapezohed; cubic; cl indistinct; G 2-2.3, 318.
Hadyne,	55.2	Dodec; cl usually indist; b, gnh; G 24-2.5, 230.
Pyrochlore,	5— 5·5	Oct; cl imperf; yw, bnh; G 3.8-5, 345.
Nosean,	5.2	Dodee; gyh, bh, bnh; G 2·2-2·3, 230. Skolopsite similar; G 2-2·3, 231.
Sodalite,	5.26	Cl dodec; gy, bn, b, gn; G 2·2—2·4, 229.
Lapis Lazuli,	5.2	Dodec; b; G 2-3-2-5, 229.

[•] In this table the angles of a pyramid given are first the pyramidal angles, and then the basal; the angle of a dome mentioned is that over O, unless otherwise mentioned. In the dimetric and following systems, the figure 1 preceding the angles stands for the octahedron 1, (P in Naumann's system); and so on.

Hardness Ittnerite. Dodec; cl dodec: gy, bh; G 2:85-2:4, 819. 5.5 Perofskite, 5.2 Cubes; cl cubic imperf; G 4 017; gyh-bk, 845. Tetrahedral; dull-brown; G 4.1-47, 811. Tritomite. Leucite. Trapezohedrons; w, gyh-w; G 2.4-2.5, 231. 5:5-6 Periclase. 6 Cl cubic; G 8.674; gyh, gn, 101. Pyrrhite, 6 Oct; cl not observed; color orange-yw, 346. Tetrahed; cl oct traces; G 3.1-3.8, 194. Helvin, 6--6.2 Garnet, 6.5-7.5 Dodec; trapezohed, etc.; cl dodec; G 8.5-4.8, 190. Boracite, Tetrahed; cl oct dif!; G 2.9-3, 398. Rhodizite, Tetrahed; cl oct dif1; G 3.3-3.5, 398. Spinel, Oct; cl indistinct; G 3.5-4.9, 103. Diamond, 10 Cl oct, perf; G 8.5-8.6, 24.

II. LUSTRE METALLIC.

Dufrévnosite. Cl indistinct; G 5.549; gy, 77. 2 Silver Glance. 2-2.5 Cl dodec imperf; gy; G 7:15-7:4, 87. Cl cubic!; bkh gy; G 6.4-6.45, 41. Caproplumbite, 2.5 Steinmannite, 2.2 Cl cubic; G 6.888; gy, 41. Galena, 2.5-8 Cl cubic!!; lead-gy; G 7.25-77, 89. Clausthalite, 2.5-3 Cl cubic; gy, bh; G 7-8.8, 42. Naumannite, 2.2 Cl cub; bk; G 80, 43. Copper, 2.5-3 Oct; r; G 8-9, 17. Silver. 2.5-8 Cl none; w; G 10-11, 15. Gold, 2.5-3 Cl none; yw; G 19.5-20, 7. Erubescite, Cl dif!; rdh or bronze yw, tarnishes; G4.4-5.1, 88. ñ Altaite, Я Cl cubic; w; G 8.159, 44. 3--3.2 Amalgam, Cl dodec, imperf; G 10-14; w, 15. Tetrahedrite, 8-4 Tetrahed; cl oct imperf; gray; G 4.5, 82. Tennantite, 3.5-4 Cl dodec, imperf; bkh-gy; G 4.3-4.5, 84. Melaconite, 8--6 Cub; bk; G 5.1-5.2, 109. Cubes; G 4-4:17; rdh bronze, bk, 68. Cuban. 4 Platinum. 4-4.5 White, gyh; malleable; G 16-19, 12. Grunauite. Cl oct; w, gyh; G 5.18, 44. 4.2 Iron, 4.5 Iron-gray; G 7:8-7:8, 17. Palladium, 4.5-5 Gyh-w; G 11-12.5, 14. Ullmannite, 5-5.5 Cl cubic!; G 6.4-6.51; gyh, w, 59. Perofskite. 5.2 Cubes; bk, gyh; G 4.017, 345. Chromic Iron. 5.2 Oct; cl oct; gyh-bk; G 4.3-4.5, 106. Gersdorffite. 5.2 Pyritohed; cl cubic; G 5.6-6.9; w, gyh, 58. Cobaltine, 5.5 Pyritohed; cl cubic!; G 6-6.8; w, rdh, 57. Linnæite, 5.2 Cl cubic; gyh-w; G 6.3-6.4, 67. Smaltine. 5.5-6 Cl oct imperf; w, gyh; G 6.4-7.2, 56. Pitchblende. 5.5 Oct; cl none; G 6.4-8; bk; submetallic, 107 Chloanthite. 5.2--6 W, gyh; G 6.4-6.8, 56.

Hardness.

Magnetite, 5.5—6.5 Oct, dodec, &a.; cl oct; gyh-bk; G 4.9—5.2, 105. Martite is similar; G 8.8—4.82, 102.

Franklinite, 5.5—6.5 Oct, cl oct; gyh-bk; G 5—5.1, 106.

Skutterudite, 6 Cl cubic; w, gyh; G 6.7—6.9, 67.

Iserine, 6—6.5 Oct; cl none; G 4.7—5.1; gyh-bk, 102.

Pyrites, 6—6.5 Pyritohed: ywh: G 4.8—5.1, 54.

Pyrites, 6—6.5 Pyritohed; ywh; G 4.8—5.1, 54.

Iridosmine, 6—7 W, gyh; G 19—22, 19.

Platiniridium, 6—7 W; G 22.6—28, 18.

Irite, Octahedrons; black, 108.

II. CRYSTALLIZATION DIMETRIC.

I. LUSTRE UNMETALLIC.

```
O:1\ 119^{\circ}\ 51',\ O:1i\ 129^{\circ}\ 4';\ cl\ I;\ G\ 6.4-6.5,\ 89.
Calomel.
Uranite.
                  2-2.5
                           O: 1i 128° 35'; cl basal!!; G 3-36; gn, yw, 430.
Cerasine,
                           O: 1 123° 61'; cl I; G 6-6'3; w, gy, yw, 468.
                  2.5-3
Wulfenite,
                  2·5—8
                          1 99° 40′, 131° 35′; cl oct; G 6·8—6·9; yw, gn, wh, 849.
Matlockite,
                  2.5-8
                           O: 2i 111° 50', O: 1 119° 34'; vw; G 7.21, 127.
Scheeletine,
                  2.5-3 1 99° 44′, 131° 25′; 2 92° 40′, 154° 36′; cl basal imperf;
                             gn, gy, bn, r; G 7.9-8.2, 848.
                           Acic pms; colorless; G 2.45, 316.
Savite.
                  8
Chiolite,
                           Snow white; G 27-2-9, 98.
                          Hemihed; pms 92° 41', 129° 8'; cl I perf; G 2-7-28.
Edingtonite,
                  4-4.2
                             828.
Xenotime,
                  4--5
                           1 124° 26′, 82° 30′; cl I; G 4·4-4·6, 401.
Gismondine.
                  4.2
                           1 118° 30' and 92° 30'; bh-w, gyh, rdh; G 2-265, 322.
Azorite,
                  45
                           1 128° 15'; nearly colorless; cl none, 850.
                          1 104° 2', 121°; cl basal!!; G 2·2-2·4, 304.
Apophyllite,
                 4.5-5
Scheelite,
                 4.5-5 1 100° 40′, 129° 2′; 1i 108° 12′, 112° 2′; cl oct,i mperf;
                             G 6-6.1, 847.
                           1i 134° 48′, 65° 80′; cl basal; G 2.9—3.1, 205.
Mellilite,
                  5
                           1i 111° 80′, 105° 30′; bn, w, G 1.923, 323.
Faujasite,
                 5
Gehlenite,
                 5--5-5
                           CI basal, hardly distinct; G 2.9-3.1, 256.
                 5--5.5
                           Like Scapolite; G 2.646, 205.
Dipyre.
Scapolite,
                 5--6
                           1 136° 7', 68° 48'; cl ii and I; G 2.6-2.75, 201.
                          1 (basal) 111°; yw, rdh; G 4.6-4.72, 410.
Romeine.
                 5---6
                 5.5
                          1 136° 11' and 63° 40'; w; G 2.5-2.74, 200.
Meionite,
                          1 123° 161'; G 8.629, 197.
                 5.2
Erstedite,
                 5.5-6 1 97° 55', 186° 80; cl 1 and O perf; G 3.8-4, 389.
Anatase,
Sercolite,
                           O: 1i 156° 5'. O: 2 128° 83'; w, rdh; G 2.545, 200.
Rutile,
                 6-6.5
                          1 123° 8′, 84° 40′; 1i 184° 58′, 65° 85′; cl lat; G 4 1—
Idocrase.
                           1 129° 29', 74° 14'; cl imperf; G 3.3-8.5, 197.
                 6.2
                 6---7
Cassiterite,
                           1 121° 40′, 87° 7′; 1i 182° 31′, 67° 50′; cl imperf; G
                            6.5-7, 118.
                          1 128° 19', 84° 20'; cl imperf; gy, bn, r, etc; G 40-
                 7.5
Zircon,
                             4.8, 195.
```

II. LUSTRE METALLIC.

	Hardnes	.
Nagyagite,	1-1.2	2i (bas) 137° 52'; cl basal!!; bkh-gy; G 6.8-7.2, 65.
Chalcopyrite,	8.5—4	Tetrahed; 1, 109° 53′, 108° 40′; cl imperf; yw; G 4·1 —4·3, 69.
Tin Pyrites,	4	Steel-gray, ywh, bkh, 70.
Hausmannite,	5.5—6	O: 1 121° 3′, O: 1i 130° 25′; bnh-bk; G 47—4·8, 118.
Fergusonite,	5.2—6	1 100° 54', 128° 28'; cl basal imperf; G 5.8-5.9, 350. Submetallic.
Braunite,	66.5	1 109° 53′, 108° 89′; bnh bk; G 47-4·9, 117.

III. CRYSTALLIZATION TRIMETRIC.*

I. LUSTRE UNMETALLIC.

Thermonatrite,	1-1.5 107° 50', 83° 50'; cl brachyd imperf; G 1.5-1.6, 455.
Tyrolite,	1-1.5 Gn, bh: G 5-8.1, 426.
Orpiment,	1.5—2 I, 100° 40'; 11 83° 30'; fol!; yw, 32.
Sulphur,	1.5-2.5 cloct; I 101° 46'; Oct 1 106° 25', 85° 07', 148° 28';
•	G 2 072, 23.
Haidingerite,	1.5-25 I 100°; 11 126° 58'; cl brachyd perf!; G2.8-2.9, 413.
Conistonite,	2 I 97° 5', 17 86° 30'; colorless; G 2°0; 465.
Struvite,	2 I 101° 42′, 12 68° 8′, 11 96° 50′; ywh, bnh; G 1 6—1 7,
	413.
Nitre,	2 I 118° 50'; G 1.9-2; taste saline, cooling, 433.
Mascagnine,	2-2.5 I 107° 40'; cl brachyd; taste pungent, 379.
Epsomite,	2-2.5 I 90° 34'; hemihed; G 1.75, 384.
Goslarite,	2-2.5 I 90° 42'; cl brachyd!; w; G 2-2.1, 384.
Thenardite,	2-2.5 cl O; taste alkaline; G 2.73, 365.
Mica,	2-2.5 I 120°; cleav basal, micaceous! lam elastic; G 2.7-8.1,
	221. Phlogopite, and Lepidolite similar, 224, 226.
Clinochlore,	2-2.5 I 120°; cleav basal, micaceous! lam flex, inelast; G 2.7
•	-2.8; green, 293.
Liroconite,	2-2.5 I 119° 20'; 1ī 72° 22'; b, bh-gn; G 2.8-3, 429.
Glaserite,	2-3 cl macrod; taste saline, bitter, 365.
Bromlite,	2.5 I 118° 50'; cl imperf; G 3.7—3.72, 451.
Leadhillite,	2.5 I 103° 16'; cl it perf!; G 6.2—6.5; w, ywh, gnh, 871.
Polyhalite,	2.5-3 I 115°; cl imperf; taste bitter, weak; G 2.78, 377.
Picrosmine,	2.5-3 I 126° 52'; 17 (bas) 62° 11'; G 2.55-27, 281.
Hopeite,	2.5-3 I 101°; cl brachyd!; gyh-w, bnh, 409. Fischerite, G
	2.46, 408.
Lanthanite,	2.5-3 I 93°-94°; gyh, ywh, 456.
Valentinite,	2·5—3 I 136° 58'; 11 70° 32'; w, G 5—5·6, 140.

[•] In this system, Mica, Margarite, Clinochlore, Chondrodite, Datholite, Phosphocalcite, are hemihedral and have a Monoclinic form.

```
Hardness.
                 2.5-3 I 103° 38', 17 (bas) 104° 31'; w, gyh; G 6.2-6.8, 370.
Anglesite,
                 2.5-3 I 102° 36'; cl II; w, ywh; G 7-7.1, 128.
Mendipite,
Heavy Spar,
                 2.5-3.5 / 101° 40'; 11(bas) 105° 24'; G 4.3-4.8, 366.
Caledonite,
                 2.5-3 I 95°; cleav indistinct; gn, bh; G 6.4, 372.
Fluellite.
                         I 105°; w; trp, 98.
                         I 92° 30', 17 110° 50'; cl imperf; G 4·1-4·4, 420.
Olivenite.
                 3
Stilbite,
                 3.5
                         194° 15'; in rectang pms; cl brachyd!! p'ly: G 2-2.2,
                           339.
                 3-3'5 I 102° 56'; cl O perf! it perf, it less so; w, bh, gyh;
Anhydrite,
                           G 2.9-3, 369.
Celestine.
                 3-3.5 I 104°-104½°; 11 (bas) 104° 8'; G 3.9-4, 368.
Witherite,
                 3-3.75 I 118° 30'; cl I, imperf; w, gnh; G 4.3, 449.
                 3-3.5 I 117° 13'; cl I imperf; w, gyh; G 6.4-6.5, 452.
Cerusite,
                 3-3.5 /112° 20', 11 105° 40'; green, bkh; G 4-4.3, 138.
Atacamite.
Descloizite.
                         I 100° 28', occurring prisms 122° 6', 116° 25'; bk, olive,
                           yw, bnh; G 5.839, 362.
                 3-4 Angles of Chrysolite (pseudomorphs?); G 2.2-2.6, 282.
Serpentine,
                        199° 46', i 118° 38'; w; G 5.24, 97.
Cotunnite,
Wavellite.
                 3-4 I 126° 25', 11 106° 46'; cl I imperf; G 2.3-2.4, 423.
                 3.5-4 I 116° 10'; 11 (bas) 108° 26'; G 2.9-3.0, 448.
Aragonite,
                 3.5-4 I 98° 2', iv, 120° 10'; gn, bn; G 3.1-3.3, 419. Dufre-
Scorodite,
                           nite, leek-gn, 427.
Euchroite.
                 3.5-4 I 92° 8', 1t 117° 20'; cl I, 1t imperf; gn; G 3.384, 421.
                 3.5-4 I 117° 19'; cl I; G 3.6-3.75, 450.
Strontianite,
                 3.5-4 /104° 10', 21 114° 29'; 11 151° 52'; cl it /; gn; G 37
Brochantite,
Margarite,
                  3.5-4.5 / 120°; Micaceous; lam, rather brittle; w; G 3, 300.
Libethenite,
                         I 92° 20', 17 109° 52'; cl imperf; dark gn; G 3.6-3.8.
                            420.
Epistilbite.
                         I 135° 10'; cl brachyd! w; bh, ywh; G 2.2-2.3, 330.
Harmotome,
                 4-4.5 1 121° 6', 119° 4', 89° 52'; 11 110° 26'; cl imperf; G
                            2.35-2.5, 323. Phillipsite, similar; G 2.2, 324.
                4.5-5 Hemihed, monoclinic; gn; G 4-4.4, 425.
Phosphocalcite,
Manganocalcite, 4-4.5 I near Aragonite, 452.
                        I 105°; white; G 2:441, 329.
Sloanite,
                 4.5
Childrenite.
                 4.5-5 I 111° 54', 21 75° 46'; cl imperf; G 3:1-3:3, 424.
                 4.5-5 I 103° 54'; cl I!; w, gyh, gnh; G 3.3-39, 313.
Calamine,
Triphyline,
                 5
                        194°, 12 130°; gnh, gy, bh; G 3.45-3.65, 406.
Göthite,
                         194° 52', ig 130° 40'; bn; G 4-44, 129.
                  5
Portite.
                        I 120°; white; G 2.4, 311.
                 5
Herderite,
                         I 115° 53'; cl imperf; G 29-3, 410.
                 5-5.5 I 91°; w; gyh; G 2.1-2.27, 327. Scolecite is similar,
Natrolite,
                           328.
Thomsonite.
                 5-5.5 I 90° 40'; w; bnh; G 2.3-2.4, 325.
Triplite,
                 5-5.5 bn, bkh-bn; G 3.4-3.8, 408,
Datholite,
                 5-5.5 I1150 26'; i2 760 44'; cl indistinct; w; G 2-9-3, 334.
Æschynite,
                 5-6 190° 34'; ig 127° 19'; el imperf; G 4.9-5.2, 357.
```

```
Hardness.
Wöhlerite.
                  5.2
                          190° 54', O: 11144° 1'; cleav; yw, bnh, gyh; G 841,
Lievrite,
                  5.5-6 I 111° 12'; 1 188° 26', 117° 84', 77° 50'; gyh-bk; G
                            8-8-4-2, 262.
Brookite.
                 5.5-6 I 100°; bn, bk; cl indistinct; G 3.8-4.2, 123.
                          I 106° 10'; cl I perf; 3—8·15, 409.
Amblygonite,
Chondrodite,
                  6-6.5 I 94° 26', hemihed; yw, bn; G 8.1-8.25, 186.
Keilhauite.
                          I 122° 30'; bnh-bk, 841.
                  6.2
Prehnite,
                  6-6.5 I 99° 56'; cl basal; gnh, w, ywh; G 2.8-8, 314.
Diaspore,
                  6—7
                          I 98° 52', i2 129° 54'; cl brachyd!! G 8.8—8.5, 128.
Chrysolite,
                  6---7
                          194° 8', i \(\bar{2}\) 180° 2'; green, glassy; G 3.8—3.5, 184.
Iolite.
                  7-7.5 I 119° 10'; cl indistinct; G 2.5-2.67, 214.
Staurotide.
                  7-7.5 1 129° 20'; cl brachyd, imperf; G 8.5-3.375, 261.
Andalusite.
                  7.5
                          I 90° 44'; cl I; G 3·1-8·8, 257.
Topaz,
                          1124° 19'; i 398° 8'; cl basal!; yw, bnh, bh, gnh, w;
                  8
                            G 3.4, 259.
Chrysoberyl,
                  8.2
                          I 119° 46', 8% 70° 40'; cl brachyd, imperf; G 8.5-8-8,
                            122.
```

II. LUSTRE METALLIC.

```
Sternbergite,
                 1-1.5 I 119° 30'; cl basal!!; bnh bronze; 4.2-4.8, 71.
Sylvanite,
                 1.5-2 /110° 48', 11 78° 34'; gy; G 5.7-8.5, 64.
Stibnite,
                         I 90° 45'; cl brachyd!; G 4.5-4.7, 33.
                 2-2.5 I 98° 40'; cl I, ii; G 4.8-5, 125.
Pyrolusite,
Jamesonite.
                 2-2.5 I 101° 20'; cl basal!; gy; G 5.5-5.8, 75.
Aikinite,
                 2-2.5 I 110°; long acic, cryst; gy; G 6.1-6.8, 81.
Bismuthine..
                 2-2.5 I 91° 30'; cl it!; lead-gy; 6.4-6.6, 38.
Stephanite,
                 2-2.5 I 115° 39'; 21 72° 12'; cl 21, it; bk; G 6.2-6.8, 86.
Geocronite.
                        I 119° 44'; cl one perf; gy; G 6.4—6.6, 85.
                 2.5-3 I 119° 35'; 21 125° 28'; cl I dif! gy; G 5.5-5.8, 46.
Copper Glance,
                 2.5-3 198° 40'; 1196° 12'; gy, dark; G 5.7-5.8, 80.
Bournonite,
Stromeyerite,
                 2.5-3 I119° 35'; gy; G 6.2-6.3, 48.
Enargite,
                         I 98° 11'; bk; G 4.4-4.6, 87.
Wolchite,
                         dark-gy; G 5.7-5.8, 82.
                 8-8.5 I 120° 39', Rose; G 5.3-5.4, 74.
Zinkenite,
                         I 101°, i2 138° 12'; gy; G 4748, 73.
Wolfsbergite,
Manganite,
                 8.5-4 I 99° 40'; cl brachyd!; gyh-bk; G 4.3-4.4, 180.
Discrasite,
                 3.5-4 I119° 59'; often in hexag twins; w; G 9.4--10.0, 35.
Glaucodot,
                         I 112° 36'; cl basal!; G 5.9-6.1; gyh-w, 68.
                 6
                 5-5.5 I 111° 80', (122° 26'); cleav; w; G 7.0-7.4, 61.
Leucopyrite,
                 5-5.5 I 101° 5'; 11 99° 12'; bk, 851.
Wolfram,
Columbite,
                         I 100° 40'; cl ii, it imperf; bk; G 5.4-6.4, 853. Men-
                 5--6
                           gite similar, 356.
                         I 101° 82'; occurring prism 122° 54'; cl imperf; bk;
Tantalite,
                 5--6
                           G 7:1--8, 351,
```

Hardness.

Samarskite, 5.5 I 101°, i 3 135° to 136°; cl imperf; G 5.3—5.7; submetallic, 355.

Mispickel, 5.5-6 I 111° 53'; 11 80° 8'; cl I; G 5.9-6.2, 62.

Rammelsbergite, 5.5-6 I 123° to 124°; w; G 7-7.2, 61.

Marcasite, 6-6.5 I 106° 5′, 11 80° 20′; ywh; G 4·6-4·9, 60. Euxenite, 6·5 I 120°; cl none; G 4·6-4·8; submetallic, 358.

Polymignyte, 6.5 I 91° 44'; 11 109° 46', 21 70° 30'; cl imperf; G 4'7—4'9, 356. Polycrase is related, 357.

Polianite, 6.5-7 192° 52', O: 11 147° 43'; bkh; G 4.8-4.9, 131.

IV. CRYSTALLIZATION MONOCLINIC.

I. LUSTRE UNMETALLIC.

Hexag tables; I120° nearly; angle between the optical Tale, 1.0 axes 7° 24'; cl basal!!; G 2.55-2.85, 275. Natron, 1-1.5 I 76° 28'; taste alkaline, 455. Kermesite, 1-1.5 cl basal; r; G 4.4-4.6, 141. Glauber Salt, 1.5-2 I 86° 31'; cl clinod perf, 386. Gypsum, 1.5-2 prisms 111° 42', 143° 42'; cl ii perf!!; G 2.3-2.35, 1.5-2 /111° 12', 771° 25'; 1 119° 10'; bh; G 2.66, 415. Vivianite. 1.5-2 174° 26'; i2 113° 6'; r, rdh-yw; G 3.4-3.6, 31. Realgar, I 82° 21'; gn, w; G 1.8-1.9; taste inky, 385. Copperas, Fireblende. I 139° 12'; hyacinth-red; G 4-2-4-3; 88. Borax, 2-2.5 I 87°; taste sweetish, alkaline, feeble; G 1.716, 394. Botryogen, 2-2.5 I 119° 56'; in 98° 16'; bn; G 2-2.1, 387. 2-2.5 I 111° 6'; 1 117° 24'; cl clined perf!!; G 2.6-2.75. Pharmacolite, 414. Bieberite, Like Copperas; rdh, 385. Erythrine, 2-2.5 I 111° 16', C 70° 54'; el clinod!!; rdh; G 2.9-3.1, 416. Lanarkite, 2-2.5 One perf cleav; O: 1i 120° 45'; G 6.3-7; gyh-w. ywh, gyh, 374. 2-5.5 I 69°; C 85° 40'; cl I; G 3.19; gn, 386. Johannite, Miargyrite, 2-2.5 139° 38', i3 90° 30'; bk; G 5.2-54; submetallic, 74. 2-8 I 68° 50', C 78° 27'; cl I; ywh-w; G 1'9-2, 455. Gay-Lussite, Vauquelinite, 2.5-3 bkh-gn, dark-gn; G 5.5-5.8, 360. 2.5-3 / 100° 36'; cl O; w, 464. Whewellite, 2.5-3 C 103° 15'; taste alkaline; G 1.9-2, 454. Trona, Glauberite, 2.5-3 I 83° 20'; el O perf, G 2.6-2.9, 874. Köttigite, 2.5-8 Like Cobalt Bloom; G 3.1; rdh, 418. 2.5-3 I 61°; cl ii perf!; azure b; G 5.2--5.5, 390. Linarite, 2.5-3 I 93° 44'; rd; G 5.9-6.1, 359. Crocoisite. Aphanesite, 2.5-3 156°; gn, b; G 4.15-44, 428. Hydromagnesite 3.5 187° 52'; w; G 2:14-2:18, 456. Heulandite. 3.5-4 / 136° 4'; el elinod/ 1 p'ly; G 2.15-2.2, 330.

```
8.5-4 I 86° 16', cl ii!!; G 2.25-2.4, 307. Leonhardite re-
Laumontite,
                            sembles Laumontite, 308.
Stilbite,
                  8.5-4 I 94° 16', cleav clinod! p'ly w, rdh, yw; G 2-2-2, 882.
                  8.5-4 I 99° 82'; b; G 8.5-8.9, 459.
Azurite.
Malachite,
                  8.5-4 I 108° 42'; of basal!; gn; G 8.7-4.1, 458.
Barytocalcite,
                          I 106° 54'; C78° 52'; G 86-87, 458.
Turnerite,
                  above 4 I 96° 10; O: I 90° 40'; el diagonals, one perf.
Brewsterite,
                  4.5-5 I 186°; O: ii 98° 40'; el elinod p'ly; G 2.1-2.5, 882.
                  4.5-5 I 87° 28', 2i 95° 86'; cleav; G 2.75-8, 156.
Wollastonite.
Pectolite,
                          near Augite in form; w; G 2.6-2.8, 805.
Monazite,
                          I 98° 10', C 108° 46'; cl basal!; G 4.8-5.25, 402.
Scolecite,
                  5-5.5 Monoclinic, according to Rose; / 910-910 35'; G 2.1-
                            2-25, 828.
                  5-5.5 I 95° 25'; O71° 53'; cl imperf; G 3.068, 408.
Wagnerite,
Sphene,
                  5-5.5 Angles of dif prisms, 186° 4', (or 186° 48'); 188° 48'.
                            (or 183° 56'); d imperf; G 8.4-3.6, 268.
 Rhodonite,
                  5.5--6.5 I 87° 6', like Augite; cl I; rdh; G 8.4-8.7, 167.
 Hornblende,
                          I 124° 80'; cl I, perf; colors various, w to gn to bk;
                  5---6
                            G 2.8-8.2, 272,
 Lazulite.
                  5--6
                          I 91° 80'; C 88° 15'; cl I indist; G 8-8-15, 404.
                           I 87° 6'; cl I, and diags; also O sometimes; G 3-2-
 Pyroxene,
                  5-6
                            3.5, 158.
                  5.5--6 12 70° 51'; O: ii 114° 55'; G 8.8-4.2; bk, gnh, bnh,
 Allanite,
                            gyh, 208.
 Orthoclase,
                           I118° 48'; cl O perf, it nearly perf; w, rdh, bh; G 2.4--
                            3.6, 242.
 Petalite.
                  6--6.5
                          Cleav 142°; w, gyh; G 2.4-2.45, 258.
 Acmite,
                 6-6-5
                          I 86° 56'; G 8.2-8.6, 176.
                          I 68° 8'; 1 70° 33', 11 70° 9' O: ii 115° 24'; cl imperf;
 Epidote,
                 6-7
                            G 8.2-8.5, 206.
 Zoisite,
                 6-6.5 I 116° 16'; gy, bnh, 211.
 Weissigite,
                 6.2
                          White, rdh; G 2.5-2.6, 254, (perhaps Orthoclase).
 Spodumene,
                 6.5—7
                          I 87°; cl I and ii perf; G 3.1-3.2, 169.
 Gadolinite.
                          I 115°; cl imperf; G 4-4.5, 211.
                 6.2—7
                          I 115°; cl clinod!; G 3-8.1, 267.
 Euclase.
                 7.5
                             II. LUSTRE METALLIC.
                  2-2.5 I 119° 12', 11 132° 16'; gy, wh; G 6-6.4, 79.
 Freislebenite,
 Miargyrite,
                  2-2.2
                          I 89° 88', 11 88° 18'; cl imperf; bk; lustre submet; G
                            5.2-5.4, 75.
 Plagionite.
                 2.5
                          2 120° 49'; O: 2 188° 52'; cl 2 perf; gy; G 5.4. 75.
 Crednerite,
                          Cl basal perf!; bk, gyh; G 4.9-5.1, 126. Heteroclin is
                 4.2
                            similar, 127.
```

Wolfram (in part) 5-5.5 I 101°, C 91° 59', according to Descloizeaux.

5.5-6 See above; sometimes submetallic.

Allanite,

V. CRYSTALLIZATION TRICLINIC.

	Hardness.	
Sassolin,	1	I: I 118° 30', O: I 95° 3'; cleav basal!, 144.
Cyanosite,	2.5	109° 32′, 127° 40′, 123° 10′; cleav imperf; b; G 2·2—2·3, 380.
Babingtonite,	5.2	Different prism, angles 89° 20′, 92° 34′, 112° 30′; 88° between cleavages; one cl perfect; G 3·4—3·5, 178.
Latrobite,	5.5—6.5	93° 30′, 91° 9′, 98° 30′; cleav 3 unequal; G 2·7—2·8, 235.
Albite,	6	I: I' 122° 15'; O: it 93° 36'; G 2.55-2.65, 240.
Oligoclase,	6	I: I' 120°; O: it 93° 15'; G 2.6-2.7, 239.
Labradorite,	6	I: ñ 119° 16'; O: ñ 86° 32'; G 2.65—2.8, 237.
Andesine,	6	Like Albite; but cl less perfect; G 2.65-2.74, 236.
Anorthite,	6-7	I: I' 120° 30'; O: it 85° 48'; G 2.65-2.78, 234.
Kyanite,	6-7.5	O: ii 100° 50', ii: ii 106° 15'; I: I' 97° 4'; cl macrod; G 3·1—3·7, 263.
Axinite,	6.5-7	134° 40', 115° 17', 135° 10'; bn, gyh, bk; G 3.271, 213.
Sillimanite,	6.5-7.5	I: I' 98° varying to 110°; cl macrod!; G 3.2-3.6, 265.
Danburite,	7	110°, 54°, 93°; cl dist; ywh, pale; G 2.9—3, 212.

VI. CRYSTALLIZATION HEXAGONAL.

I. LUSTRE UNMETALLIC.

Iodyrite,		Hexag pms, O: 1 136° 46'; yw, 95.
Ripidolite,	1-2	Hexag; cl basal!!; lam flex; G 27-3, 296.
Brucite,	1.2	Hexag tables; cl basal!!; G 2.35, 133.
Nitratine,	1.5-2	R 106° 33'; cl R perf; G 2-2.3; taste cooling, 433.
Chlorite,	1.5-2	Tab; cl basal!!; lam flex; G 2.6-2.9, 294.
Chalcophyllite,	2	R 69° 48'; cl basal!!; gn; G 2.4-2.7, 428.
Xanthocone,	2	R 71° 84', O: R 110° 30'; rd, bn; G 5-5.2, 87.
Coquimbite,	2-2.5	Hexag; 0:1 151°; w, bh; taste copperas; G 2-2-1.
1		380.
Proustite,	2-2.5	R 107° 48'; cl R; rd; G 5.4-5.6, 78.
Pyrargyrite,	2-2.5	R 108° 42'; & R 137° 58'; el R; bk, rdh; G 57-5-9,
		77.
Cinnabar,	2-2.5	R 92° 46'; 2 R 71° 48'; cl I; r; G 8-81, 48.
Cronstedtite,	2.5	Hexag; cl basal!; bnh-bk; G 3.3-3.4, 299.
Susannite,	2.5	2 R 72° 30'; cl O easy; w, gn, ywh, bnh; G 6.55, 378.
Pyrosclerite,		Cl basal!!; lam flex; G 2.6-2.8, 291.
Biotite (Mica),	2.5-3	Hexag; cl basal!!; G 2.8-3.1, 225.
Calcite,	8	R 105° 5'; cl R perf; G 2.5—2.8, 435.
Volborthite,	3-3.5	Hexag; cl one perf; yw, ywh-gn; G 3-4-3-9, 362.
Greenockite,	3-3.5	Hexag pms; honey yw, 51.
Vanadinite,		Hexag; yw, bn; G 6.6-7.3, 362.
Gibbsite,	3-4	Hexag; cl basal; G 2.3—2.4, 134.

```
Hardness.
                           R 107° 29'; cl R perf; G 2.8—8, 441.
Magnesite,
                  8-4
                           R 98° to 94°; cl R traces; w; G 3.2—3.4, 378.
Dreelite,
                  8.2
Mimetene.
                  8.5
                           Hexag; O: 1 139° 6'; yw, rdh; G 7:1-7:25, 401.
Dolomite.
                  8.5-4
                           R 106° 15'; cl R perf; G 2.8-8.1, 441.
                           R 89° 10'; cl bas!; w; gyh, rdh; G 2.5-2.8, 388.
Alunite.
                  8.5-4
Jarosite.
                           R 88° 58'; cl bas; ywh; G 3.2-3.3, 389.
Pyromorphite,
                   8.5-4 Hexag; O: 1 139° 38'; cl imperf; gn, yw; G 6.9-7.1,
                             400.
                  3.5-4.5 R 106° 51', (107° 20'); cl R!; rdh, bnh; G 3.4-3.6,
 Diallogite,
                             446.
 Chalybite,
                  8.5-4.5 R 107°; cl R !; gnh, bnh; G 8.7-8.9, 444.
 Connelite,
                           Hexag; b; trl, 375.
 Chabazite,
                  4-4.5 R 94° 46'; cl R, also hexag; w, rdh; G 2-2.2, 819.
                  4-4.5 Hexag; O: 1 148° 30'; cl basal!; bn, gy, gn; G 3-3.1,
 Pyrosmalite.
                             310.
                  4-4.5
                           R 107° 23'; cl R perf; G 3-3.68, 443.
 Breunnerite.
 Parisite,
                           Hexag; 1 120° 34', 164° 58; cl basal! bnh-yw; G 4.85,
                  4.2
 Clintonite,
                  4---5
                           Hexag tables; cl basal!!; lam brittle; G 3-3-1, 297.
 Muocerite,
                   4--5
                           G 47; ywh-bn, 96.
                           Hexag; cl basal!!; rd, G 5.4-5.6, 110.
                           O: 1 189° 47'; O: 22 124° 30'; cl indistinct; G 3-8.3,
 Apatite,
                   5
                             397. Cryptolite in acic hexag pms; G 4.6, 399.
 Dioptase,
                   5
                           R 126° 24'; 2 R 95° 58'; cl R!; gn; G 3.2-3.4, 809.
 Smithsonite,
                   5
                           R 107° 40'; cl R; w, gyh, gnh; G 4-4.5, 447.
 Willemite,
                  5.2
                           R 115^{\circ}; \frac{4}{3}R 128^{\circ} 30'; \frac{1}{3}R 142^{\circ} 52'; cl basal and lat-
                              eral; G 3.9-4.2, 189.
 Cerite.
                   5.2
                           Hexag; bn, r; G 4.912, 312.
 Cancrinite,
                  5.5-6 Hexag; O: \(\frac{1}{4}\) 154° 7'; cl I imperf; G 2.4-2.65, 283.
 Nepheline.
                   5.5-5.6 Hexag; O: 1186° 2', O: 1154° 15'; cl I, O; G 2.5-
                              2.65, 232.
 Eudialyte,
                           R 126° 25', 4 R 73° 30'; cl basal! R imperf; G 2.85-
                              3, 181.
 Quartz,
                           R 94° 15'; hexag; cl indistinct; colors various; G 2.6
                              --27, 145.
 Tourmaline,
                  7-7.5 2 R 133°; cl imperfect; bk, bn, b, gn, rd; G 3-8.3, 270.
 Beryl,
                           Hexag; O: 1 150° 3'; cl basal not very distinct; G 2.6
                              -27, 178.
 Phenacite,
                           R 116° 40'; cl R; G 2.9-3, 189.
 Corundum,
                           R 86° 4'; cl basal; G 3.0-4.2, 111.
                              II. LUSTRE METALLIC.
```

Molybdenite,	1-1.5	Hexag tables; cl basal!!; G 4.1-4.8, 66.
Graphite,	1-2	Hexag tables; cl basal!!; G 2.0891, 29.
Covelline,	1.5 - 2	Hexag; dark b; G 3.8-3.9, 65.
Tetradymite,	2	2 R 66° 40'; R 81° 2'; cl basal!; gyh; G 7-84, 21.

```
Hardness.
Tellurium,
                 2-2.5 R 86° 57'; G 6·1-6·3; tin-w, 20.
Bismuth,
                 2-2.5 R 87° 40'; G 9727; tin-w, rdh, 20.
Tenorite.
                          Scales; G 5-5.5; lead-gy, 117.
Polybasite,
                 2-8
                          Hexag, O: 1 121° 30', tabular; cl indist; bk; G 6.214,
                            85.
                 3-3.5 ' R 144° 8'; cl R; yw; G 5.2-5.7,49.
Millerite,
                 3-8.5 Rhombohedral; cl basal!; w; G 6.1-6.2; arsenical
Allemontite,
                            antimony, 22.
Antimony,
                 8---8.5
                          R 87° 85'; \(\frac{1}{4}R\) 117° 7'; cl basal!; \(\mathbf{w}\); \(\mathbf{G}\) 6.6—6.8, 21.
Arsenic,
                 3.2
                          R 85° 41; w, gy; G 5.6-6, 22.
Pyrrhotine,
                 4-4.5 Hexag pms; cl basal; bronze; G 4.4-4.7, 50.
Copper Nickel,
                 5-55 Hexag; cl imperf; rdh; G 7.3-7.7, 52.
                          R 85° 40'-86° 10'; cl imperf; gyh-bk; G 4.5-5.1, 115.
Ilmenite,
                  5-6
                            Orichtonite 5 R 61° 29', 115.
Breithauptite,
                 5.2
                         Hexag; rdh; G 7 541, 58.
Hematite,
                 5.5-6.5 R 86° 10; cl imperf; gyh-bk; G 4.8-5.3, 113.
Iridosmine.
                 6--7
                          R 84° 52'; w, gyh; G 19-22, 19.
```

SYSTEM

OF

MINERALOGY,

COMPRISING THE

MOST RECENT DISCOVERIES:

INCLUDING

PULL DESCRIPTIONS OF SPECIES AND THEIR LOCALITIES, CHEMICAL ANALYSES
AND FORMULAS, TABLES FOR THE DETERMINATION OF MINERALS,
WITH A TREATISE ON MATHEMATICAL CRYSTALLOGRAPHY
AND THE DRAWING OF FIGURES OF CRYSTALS.

ILLUSTRATED BY NUMEROUS WOOD CUTS.

BY JAMES D. DANA, A. M.

Member of the Soc. Cæs. Nat. Cur. of Moscow, the Soc. Philomathique of Paris, the Geological Soc. of London, the American Academy of Arts and Sciences at Boston, etc. Silliman Professor of Natural History, Yale College.

"Hæc studia nobiscum peregrinantur, rusticantur."

FOURTH EDITION, REWRITTEN, REARRANGED, AND ENLARGED,

VOLUME II.

NEW YORK AND LONDON:
PUBLISHED BY GEORGE P. PUTNAM & CO.

1854.

THOMAS J. STAFFORD, PRINTER,
MEW HAVEN, CONN.


INTRODUCTORY REMARKS.

In the Descriptions of Species, the characteristics are mentioned in the following order:—1, Structure; 2, Hardness, Specific gravity, Lustre, Color, Diaphaneity, etc.; 3, Chemical Composition and reactions, etc.; 4, Geological position; 5, Localities and Mineral associates, etc.; 6, Altered Forms.

Under Structure are included, the system of crystallization, axial dimensions, occurring forms and angles, cleavage, modes of composition, and semi-crystalline aggregations.

To avoid any ambiguity in the angles and prisms referred to in the following pages, and render the subject intelligible to those who may not be familiar with crystallographic language, a few explanations are here given in recapitulation of some of the principles more fully elucidated in the chapters on Crystallography. The annexed figure represents a rectangular prism with

replaced edges and angles. O is the basal plane of the prism; $i\bar{i}$ the larger lateral plane, parallel to the longer lateral axis; $i\bar{i}$ the smaller lateral plane, parallel to the shorter lateral axis. a, b, c, are the axes, of which a is the vertical, b the shorter lateral or brachydiagonal, c the longer lateral or macrodiagonal. I are planes on the edges of the rectangular prism, which when extended would form a vertical rhombic prism, having its axes b and c in the ratio of 1b:1c. It is therefore the unit or fundamental vertical prism. It are planes parallel to the longer lateral axis, and having for the axes a, b, the ratio 1a:1b; extended upwards they form a dome, (so named



from domus, a house), which is called the macrodome. The planes $1\bar{\imath}$ in a similar manner form what is called a brachydome, they being parallel to the shorter lateral axis; its axes a, c, have the ratio 1a:1c, that is, the two diagonals of this horizontal prism have this ratio. These two domes are there-

fore the *unit domes*. The planes 1 on the eight angles are planes of an octahedron, having for the axes a, b, c, the ratio 1a:1b:1c. It is therefore the unit or fundamental octahedron, (1). Its pyramidal edges, if the octahedron were completed, as in f. 13, would be of two kinds, two at each extremity opposite to the axis c, the longer lateral axis, and two opposite to b, the shorter lateral axis. The former is the macrodiagonal edge, the latter the brachydiagonal.

By doubling the length of the vertical axis, the lateral being fixed, we form the octahedron 2; by trebling it the octahedron 3; by halving it the octahedron $\frac{1}{2}$; and so for the domes, doubling the vertical axis we have the dome 2i or 2i; by halving the same, the dome $\frac{1}{2}i$ or $\frac{1}{2}i$, and so on. The letter i stands for infinity, and means that the plane is parallel to one of the axes; i, that it is parallel to the longer lateral axis; i, that it is parallel to the shorter lateral axis: i or I alone, or as the initial letter in a symbol, signifies that the plane is parallel to the vertical axis. A plane ii is parallel both to the vertical and longer lateral; ii, both to the vertical and shorter lateral.

The octahedrons alluded to above have for the axes b, c, the ratio 1b:1c, and belong to what is called the *fundamental* series. But others may exist with different ratios for b and c, and any value for a. If the ratio for b, c, is 1b:2c, then as b is the shorter lateral axis, if the vertical axis is 1a, the octahedron is $1\bar{2}$; or if the vertical axis is 3a the plane is $3\bar{2}$, or if $\frac{1}{2}a$, it is $\frac{1}{2}\bar{2}$. So for the ratio 3b:1c; if the vertical axis is 1a, the octahedron is $1\bar{3}$, or if 2a, it is $2\bar{3}$; and if the vertical axis is infinite, the plane is parallel to the vertical axis, and the symbol is $i\bar{3}$. The first figure or letter in these symbols always refers to the vertical axis, and the second to one of the lateral axes.

The planes may thus be viewed as lying in vertical zones, a different zone for every ratio of the lateral axes b:c. Each series, or zone, terminates above in the basal plane of the prism, for which a=0, and below in a vertical prism, for which a is infinite.

The small tables inserted in connection with the crystalline forms of many of the species consist of the vertical zones of occurring planes. The planes of a vertical zone have mutual horizontal intersections in the crystal. Consequently in a crystal not oblique the inclination of the basal plane, O, on any plane in a zone, subtracted from 270°, gives the inclination of the prismatic plane of the same zone on that plane, and the tangents of the supplemental angles of O on the planes of a zone vary as the coefficient of the vertical axis for each plane. Thus, suppose there are the planes 1i, 2i, 3i, take the supplement of O:1i, (which, if O:1i is 124° , equals $180^\circ-124^\circ=56^\circ$); then the tangent of this angle, doubled, will be the tangent of the supple-

ment of $O: 2\overline{i}$, and trebled, of the supplement of the angle of $O: 3\overline{i}$. The same for the planes 1, 2, 3, or 12, 22, 32; and so on.

In these tables, the column of the fundamental series of octahedrons is distinguished from the other columns by being enclosed by heavier lines. Reading across the tables, planes with the vertical axis equal, (that is, with the initial figure of the symbol the same), are in the same horizontal line; and the planes in any one of these transverse lines between the fundamental column and the right-hand column have their mutual intersections parallel; and so also with planes between it and the left. The horizontal line made up of the symbols of the vertical prisms is also enclosed by heavier lines. For further elucidation of these tables, see page 58, etc., under Crystallography.

In the Dimetric System, the lateral axes are equal, and there is no distinction of longer and shorter axis. The symbols 1i, 2i, apply to planes about the base of a square prism parallel to either lateral axis, as in figure 83, p. 40.

In the Monoclinic System, the planes above the middle horizontal section in front differ from those below, on account of the obliquity of the crystal, and those of one set are +, and the other -..

In the Rhombohedral section of the Hexagonal System, the planes 1, 2, 3, $\frac{1}{2}$, etc. are planes of rhombohedrons, having for the vertical axis, 1a, 2a, 3a, $\frac{1}{2}a$, etc., 1a being the value of the axis in the fundamental rhombohedron, (R). The angle of a Rhombohedron mentioned, is always that over a terminal edge, as that between the upper planes R of figure 26, p. 30. On gradually shortening the rhombohedron in figure 26, it may become $\frac{1}{2}R$, $\frac{1}{4}R$, and so on, till the length becomes 0, and the rhombohedron is reduced to a flat plane. Hence starting from this plane, (which corresponds to the basal plane of the rhombohedron or hexagonal prism), the rhombohedron as it elongates reaches the form of figure 26; and continuing the elongation, the vertical axis doubles,—trebles,—and so on, till finally, it becomes infinite and the rhombohedron is then a six-sided prism. If a diminution in length n ow commences by planes inclined to the opposite extremities of the vertical axis, these planes correspond to another series of rhombohedrons which are distinguished by a minus (—). The planes,

$$0 \ldots \frac{1}{4} \ldots 1 \ldots 2 \ldots I \text{ (or } \infty) \ldots -2 \ldots -1 \ldots -\frac{1}{2} \ldots 0,$$

lie in a single vertical zone; and the same relation exists for the tangents of the supplemental angles of the inclination on O, as is mentioned above.

In the Hexagonal prism, the tables include one sixth of either extremity of the prism, commencing with the fundamental series or zone, m ... I, and continuing around 30 degrees to the intermediate series m2 ... i2; the prism i2 truncates the lateral edges of prism I, as shown in figure 121.

The above explanations may suffice to give a general idea of the system of notation used in this work and the principles on which it is based; and they will subserve completely their end if they tempt the reader to study carefully the chapters on Crystallography, the difficulties in which with most persons are more imaginary than real.

The angles of the domes mentioned (in the descriptions of species) are the angles at top, unless otherwise stated. Those of the octahedral forms, are the angle at the macrodiagonal edge, as the angle 1:1 in the preceding figure over 1i, (indicated by the syllable mac.); that at the brachydiagonal edge, or 1:1 over 1i, (brach.); that at the basal edge or 1:1 over the base, (bas.) Those of the vertical prism, may similarly be either the macrodiagonal (over ii) or brachydiagonal, (over ii).

The angles of Monometric forms are mentioned in a table on pages 70, 71. The dimensions of the axes given in the following pages are those that correspond to the values of the angles mentioned in the same line of the text. But in very many species, these angles admit of variations from change of temperature, and often still wider variations from other causes. They are therefore to be regarded only as approximations, or the best mean results that have been arrived at.

In the classification of the mineral species here adopted, the grand subdivisions are as follows:

- I. NATIVE ELEMENTS.
- IL COMBINATIONS WITH ELEMENTS OF THE SULPHUR AND ARSENIC SECTIONS.
 - 1. Binary Compounds.
 - 2. Double Binary Compounds.
- III. FLUORIDS, CHLORIDS, BROMIDS, IODIDS.
 - 1. Binary Compounds.
 - 2. Double Binary Compounds.
- IV. OXYGEN COMPOUNDS.
 - 1. Binary Compounds.
 - 2. Double Binary Compounds.
- V. ORGANIC COMPOUNDS, as Resins, etc.

Under the second subdivision of the Oxygen Compounds, fall the Silicates, Titanates, Columbates, Tungstates, Sulphates, Phosphates, Carbonates, and other related groups of Salts.

PART VI.

DESCRIPTIVE MINERALOGY.

I. NATIVE ELEMENTS.

- I. Hydrogen Group.—Oxyds either RO, R²O³, or RO².
 - 1. Iron Section.—Monometric; sometimes dimorphous, and both monometric and hexagonal.
 - 2. Tin Section.—Dimetric.
- II. Arsenic Group.—Oxyds include the compounds RO3 or R2O5.
 - 1. Arsenic Section.—Mostly hexagonal.
 - 2. Sulphur Section.—Trimetric or monoclinic.
 - III. CARBON GROUP.-
 - 1. DIAMOND SECTION.—Monometric.
 - 2. Graphite Section.—Hexagonal.

I. HYDROGEN GROUP.


- 1. IRON SECTION: Gold, Platinum, Palladium, Platin-iridium, Quicksilver, Silver, Amalgam, Copper, Lead, Iron, Nickel; and to this section also belong the elements Chromium, Manganese, Cobalt, Calcium, &c.
- 2. Tin Section: Native Tin.

GOLD. Gediegen Gold, W. Or Natif, H. Sol, Alchym. Rex Metallorum.

Monometric. Observed planes, O, I, 1, 33, 42, i2. Fig. 1, 11, 14, 15 to 19, 32, 33, 40, 45, and the following. Edges of crystals often salient. Cleavage none. Twins, composition as in f. 200. Com-

mon in filiform, reticulated, and arborescent shapes; also in thin laminæ; often in flattened grains or scales, and in rolled masses in gravel or sand detritus.





II.=2·5—3. G.=15·6—19·5: 19·30—19·34, when quite pure, G. Rose. Lustre metallic. Color and streak various shades of gold-yellow, sometimes inclining to silver-white. Opaque. Very ductile and malleable.

Composition.—Gold with silver in different proportions. The ratio 6: 1 contains 84.6 of gold; 8: 1, 88 of gold; 12: 1, 91.6; 18: 1, 94.2 of gold. The proportion of silver in the electrum of Klaproth, is gold 64, and silver 36, or two of gold to one of silver.

silver.

The following are analyses by G. Rose, (Pogg. xxiii, 161); Boussingault, (Ann. Ch. Phys. xxxiv, 408); Awdejew, (Pogg. liii, 153); Rivot, (Ann. d. Mines, [4], xiv, 67); T. M. Henry, (Phil. Mag. xxxiv, 205, 1849); Hoffmann, (Ann. d. Ch. u. Pharm. lxx, 255); E. T. Teschemacher, (Quart. J. Chem. Soc. ii, 193); F. Oswald, (Pogg. lxxvii, 96); T. S. Hunt, (Logan's Rep. Geol. Canada, and Amer. Jour. Sci. [2], xv, 448); A. Levol, (Ann. Ch. Phys. [2], xxvii, 310); A. D. Thomas, (Phil. Mag. [4], i, 261); Kerl, (B. u. H. Ztg. 1853, No. 3):

		Gold.	Silver.	Proportion.
1.	Linarowski, Altai,		39:38, Cu 0:33=98:79, Rose.	2:1
	Vöröspatak, Transylvania,		38:74=99:23, Rose.	-,-
	Santa Rosa,		35:07=100, Boussingault.	**
	Transylvania,	64.52		+6
	Katharinenburg, G.=15:627,		28:30, Cu, Fe, loss 0:84, Awd.	24:1
	Marmato, G.=12:666,	73.45		3:1
	Titiribi, Columbia,		26:00=100, Bouss.	٠. ٠
	Guamo,		26:32=100, Bouss.	••
	Titiribi, Columbia,		26 00=100, Bouss.	
	Katharinenburg, G .= 16-03,		19:47, Cu, Fe and loss 0:84, Aw	·.3
	Trinidad.		17:60=100. Bouss.	5:1
	Ojas Anchas,		15:50=100, Bouss.	6:1
	Senegal,		15:30, Cu, 0:20=100, A. Levol	
	Nischne Tagilsk,		16:15=100 Rose.	•
	Santa Barbara, Transylvania,		14.68, Cu 0.04, Fe 0.13=99.65,	Rose
	Goruschka, near N. Tagilsk,		12·12, Cu 0·08=99·51, Rose.	8:1
	Petropawlowski,		13·19, Cu 0·3, Fe 0·24, Rose.	٠
	Near Minsk,		12:07, Cu 0:09=99:56, Rose.	
	Chaudière, Canada,		18·27=100, Hunt,	
	Senegal.		11:30, Cu 0:90=100, A. Levol.	
	California, G.=15:63,		12:33, Cu 0:29, iron 0:54=99:7	
	Senegal, Africa,	86.97		o,
	Rio Sucio, near Mariquita.		12:06=100, Bouss.	
	Chaudière, G.=17:60,		12:23=100, T. S. Hunt.	
	Baia, near l'amplona,		11.85=100, Bouss.	
	,			

GOLD. 9

```
Gold. Silver.
                                                                               Proportion.
26. Malpaso, near Mariquita,
                                       88.24
                                              1176=100, Bouss.
                                                                                    8:1
                                      88.54
27. Llana, near Vega de Supia,
                                              11.42=99.96, Bouss.
                                             10.65=100, Rose.
10.76=100, T. S. Hunt.
8.7, Fe, XI, Ca. 1.7, Si, ign.loss 2.0=100, O.
28. Near Miask,
                                       89.35
29. Chaudière, fine scales, G.=16.57, 89.24
80. California, G.=17.4,
                                       87.6
31. California, G.=14.6, fused, 17.48, 90.70
                                              8.80, Fe 0.38=99.88, Rivot.
32. California, G.=15.96,
                                      90.01
                                              9.01, Cu with Fe trace 0.86=99.88. Hen.
33. California,
                                       89.61
                                              10 05, Cu and Fe undet .= 99 66, Hofmann.

 Boruschka, near N. Tagilsk,

                                       90.76
                                              9.02=99.78, Rose.
35. Beresof,
                                       91.88
                                             8 03, Cu 0 02, Rose,
                                                                                   12:1
36. Katharinenburg, G. 17-74-18-35,91-21
                                              8.03, Cu, Fe and loss 0.76, Awd.
                                             8.00=100, Bouss.
7.00=99, Teschemacher.
37.
   Bogota,
                                       92.00
38. California, G.=16.33,
                                       92.00
39.
   California,
                                       92.70
                                             6.90, Cu 0.40=100, A. Levol.
40. Perroe-Pawlowsk, near Kath.,
                                      92.60
                                             7·08=99·78, Rose.
   Czarewo-Nikolajewsk,
41.
                                       92.17
                                             7.27=99.74, Rose.
42. Katharinenburg, G. 18·11—18·4.92·23
                                             6.17, Cu, Fe and loss 1.6, Awd.
43.
                                      92.80
                                             7 02, Fe 0 08, Rose.
                                             6·28, Cu 0·06, Fe 0·32=99·94, Rose.
6·47=100, A. D. Thomas.
44.
                                       93.34
411. California,
                                       98.53
45. Katharinenberg,
                                       93.75
                                             6.01, Cu, Fe and loss 0.24, Awd.
46.
                                       94.09
                                             5.55,
                                                                    0.86, Awd.
47. Brazil.
                                       94.00
                                             5.85=99.85, Darcet.
                                                                                   18:1
   Senegal, irregular grains,
48.
                                       94:00
                                             5.85, Platinum, 0.15=100, A. Levol.
49. Boruschka,
                                             5.23, Cu, 0.89, Fe 0.04=100.07, Rose.
                                       94.41
50. Katharinenburg, G. 18-77-18-89, 95-5
                                              4.0, Cu, Fe and loss 0.5, Awd.
51. Australia,
                                       95.48
                                             3.59, Quartz 0.10=99.17, Kerl
52. Katharinenburg, G. 1879,
                                       95.81
                                             3.58 Cu, Fe and loss 0.61, Awd.
53. California,
                                       96.42
                                             8.58=100, A D. Thomas.
   Schabrowski, near
    Katharinenburg, G.=19.099 $ 98-96 0.16=99.12, Rose.
```

The Californian gold averages 875 to 885 thousandths in gold, and the Australian 960 to 966 thousandths.

The Chilian gold afforded Domeyko 84 to 96 per cent. of gold and 15 to 8 per

cent. of silver, (Ann. d. Mines, [4], vi).

Copper is occasionally alloyed with gold, and also palladium and rhodium. A Brazilian specimen of Palladium gold (Porpezite) from a place called Porpez, afforded Berzelius, Gold 85 98, palladium 95 8, silver 4 ·17. Gold amalgam has been reported from California expecially near Marinove. reported from California, especially near Mariposa.

Rhodium gold has the specific gravity 15.5-16.8. It is brittle, and contains, according to Del Rio, 34 to 43 per cent. of rhodium. The mineral nagyagite con-

tains 8 to 9 per cent. of gold.

Native gold is largely obtained from alluvial washings. It is also found disseminated in certain rocks, especially the quartz veins that intersect talcose, mica, and argillaceous schists. It is sometimes found also in gneiss, granite, and porphyry. It is often contained in pyrites, constituting the auriferous pyrites. The detritus af-

fording gold dust has proceeded from some gold-bearing-rocks.

Gold is widely distributed over the globe. It occurs in Brazil, (where formerly a greater part of that used was obtained), along the chain of mountains which runs nearly parallel with the coast, especially near Villa Rica, and in the province of Minas Geraes; in New Grenada at Antioquia, Choco, and Giron; in Chili; sparingly in Peru; in Mexico; in New Mexico, near Santa Fe, Cerillos, Avo; in Guatemala, and near Panama; in the Rocky Mountains, near the Great Salt Lake; in California, between the Sierra Nevada and the Sacramento and San Joaquim; in the southern of the United States. In Europe it is most abundant in Hungary at Konigsberg, Schemnitz, and Felsobanya, and in Transylvania at Kapnik, Vörospatak, and Offenhanya; it occurs also in the sands of the Rhine, the Reuss, and the Aar; on the southern slope of the Pennine Alps from the Simplon and Monte Rosa to the valley of Aosta; in Piedmont; in Spain, formerly worked in Asturias; in many of the streams of Cornwall; near Dolgelly and other parts of North Wales; in Scotland, in considerable amount, near Leadhills, and in Glen Coich and other parts of Perthshire; in the county of Wicklow, Ireland; in Sweden, at Edelfors.

In the Urals are valuable mines at Beresof, and other places on the eastern or Asiatic flank of this range, and the comparatively level portions of Siberia; also in the Altai mountains. Also in the Cailas mountains in Little Thibet.

There are mines in Africa, at Kordofan, between Darfour and Abyssinia; also south of Sahara in the western part of Africa, from the Senegal to Cape Palmas; also in the interior on the Somat, a day's journey from Cassen; also along the coast opposite Madagascar, between 22 and 35 degrees south latitude, supposed to have been the Ophir of the time of Solomon. Other regions are China, Japan, Formosa, Ceylon, Java, Sumatra, western coast of Borneo, and the Philippines.

The gold of commerce comes mostly from Asiatic Russia, Australia, Brazil, Bohemia, Transylvania, Africa, the East India Islands, California, and the southeastern

parts of the United States

The Russian mines, until the discovery of the mines of California and Australia, were the most productive in the world. They are principally alluvial washings, and these washings seldom yield less than 65 grains of gold for 4000 pounds of soil; never more than 120 grains. The alluvium is generally most productive where the loose material is most ferruginous. The mines of Katherinenburg are in the parent rock—a quartz constituting grains in a half decomposed granite called "beresite," which is connected with talcose and chloritic schists. The shafts are sunk vertically in the beresite, seldom below 25 feet, and from them lateral galleries are run to the veins. These mines afforded between the years 1725 and 1841, 679 poods of gold, or about 30,000 pounds troy. The whole of the Russian mines yielded in 1842, 970 poods of gold, or 42,000 pounds troy, half of which was from Siberia, east of the Urals. In 1843, the yield was nearly 60,000 pounds troy, or about \$13,000,000; in 1845, it amounted to \$13,250,000; and in 1846, to 1722-746 poods, equal to 75,358 troy pounds, and \$16,500,000; in 1851, \$15,000,000. Fig. 263 is by G. Rose from a

At the Transylvania mines of Vöröspatak, the gold is obtained by mining, and

these mines have been worked since the time of the Romans.

The annual yield of Europe, exclusive of Russia, is not above \$1,000,000. Austria afforded in 1844, 6785 marks. The sands of the Rhone, Rhine, and Danube, contain gold in small quantities. The Rhine has been most productive between Bâle and Manheim; but at present only \$9000 are extracted annually. The sands of the richest quality contain only about 56 parts of gold in a hundred millions; sands containing less than half this proportion are worked. The whole amount of gold in the auriferous sands of the Rhine is estimated at \$30,000,000, but it is mostly covered by soil under cultivation.

Africa yields annually at least 4500 pounds troy, (\$850,000), and Southern Africa,

1250 pounds, (\$235,000).

The mines of South America and Mexico were estimated by Humboldt to yield annually about \$11,500,000; but the amount has much diminished. Brazil of late has furnished about 17,500 pounds troy. It is estimated that between 1790 and 1830, Mexico produced \$31,250,000 in gold, Chili \$13,450,000, and Buenos Ayres \$19,500, 000, making an average annual yield of \$16,050,000.

The mines of Australia yield 60 or 80 millions of dollars a year. They are situ-

ated mostly in southeastern Australia, especially about Mt. Alexander, in lat. 87° S., long. 144° 20′ E; the valleys of Forest Creek and Fryer's Creek are most productive.

The mines of the Southern United States have produced till recently about a million of dollars a year. They are mostly confined to the States of Virginia, North and South Carolina, and Georgia, or along a line from the Rappahannock to the Coosa in Alabama. But the region may be said to extend north to Canada; for gold has been found at Albion and Madrid in Maine, Canaan, N. H., Bridgewater, Vermont, Dedham, Mass., and on the Chaudière river, and elsewhere in Canada. Traces occur also in Franconia township, Montgomery Co., Pennsylvania.

In Virginia, the principal deposits are in Spotsylvania county, on the Rappahan nock, at the United States mines, and at other places to the southwest; in Stafford county, at the Rappahannock gold mines, ten miles from Falmouth, in the Culpepper county, at Culpepper mines, on Rapidan river; in Orange county, at the Orange Grove gold mine, and at the Greenwood gold mines; in Goochland county, at Moss and Busby's mines; in Louisa county, at Walton's gold mine; in Buckingham county, at Eldridge's mine. In North Carolina, the gold region is mostly confined to the three ranges of counties between Frederick and Charlotte, which are situated about in a line running northeast and southwest, parallel nearly with the coast. GOLD. 11

The mines of Mecklenburg are principally vein deposits; those of Burke, Lincoln, and Rutherford, are mostly in alluvial soil. The Davidson county silver mine had afforded \$7000 of gold in 1844. In Georgia, the Shelton gold mines in Habersham county have long been famous; and many other places have been opened in Rabun and Hall counties, and the Cherokee country. In South Carolina, the principal gold regions are the Fairforest in Union district, and the Lynch's creek and Catawba regions, chiefly in Lancaster and Chesterfield districts; also in Picken's county, adjoining Georgia. There is gold also in eastern Tennessee. In Canada, it occurs at St. Francois Beauce, Aubert, Gallion, Sherbrooke, Melbourne, etc., with some platinum and iridosmine.

Viewing the gold region of the Eastern United States as a whole, it is perceived that it ranges along the Appalachians, particularly the castern slope, from Maine to Alabama, having nearly a northeast and southwest course.

Gold also occurs in Arkansas, Texas, and the Rocky Mountains.

The California mines are mostly alluvial. They yield 50 millions of dollars annually. The gold is found in the gravel and sand of the valleys, and beds of streams leading from the Sierra Nevada into the adjoining valley of the Sacramento and San Joachim. Pebbles of quartz abound over the region, and magnetic iron sand is also abundant. All the tributaries of these rivers have their auriferous sands, and the dry valleys and gorges, (runs of water only in the wet season), also yield it abundantly. In the higher country, or along the dry ravines, the gold is in larger pieces, or grains, and occasionally cavities in the surface of the subjacent rocks, (called pockets), are laid open, which afford large quantities of the metal. Lower down the streams, the gold is in finer grains, usually flattened scales, a form which partly results from the condition in lamine in the original rock, and partly from the trituration the grains are subjected to among the gravel under the action of running water; for as in other regions of alluvial gold, the auriferous earth, or gravel, has resulted from the wear of auriferous rocks, and water has been some way concerned in producing, transporting, and distributing it. The gold being specifically four or five times heavier than ordinary pebbles, it settles high up the streams, and only the small particles are carried far below. The scales have been observed by Mr. J. E. Teschemacher to be sometimes hexagonal plates. Zircons have been observed in the auriferous sands, and also platinum; diamonds have been reported. Fig. 262 represents a crystal of gold of natural size, as published by F. Alger. C. U. Shepard describes another crystal from California which is a pentagonal dodecahedron two fifths of an inch in diameter. The color of the grains varies from a pale to a deep yellow, the shade depending mainly on the proportion of silver present; there is generally great uniformity in the appearance of the grains of the same locality,

The gold rock of the United States is to a great extent a micaceous or talcose schist, with veins or beds of quartz. The gold is mostly confined to these veins, though also found to some extent in the rock either side. The schist is often half decomposed or rusted. The quartz is usually more or less cellular, or wanting in perfect compactness, and sometimes tabular; yet it is at times quite solid. Iron pyrites is frequently present, and by decomposition it stains the rock with iron rust. Other minerals often associated with the gold, are copper pyrites, blende, galena, anglesite, zircons, sulphur, (in minute crystals, proceeding from the decomposition of pyrites). Heavy spar is sometimes a large constituent of the vein, and fluor spar is now and then present. The peculiar appearance of the quartz, somewhat cellular, more or less rusted, and its position in veins, through an imperfect shale, and generally not firmly attached to the enclosing walls, afford the best indications of the presence of gold, though the absence of all these conditions is not evidence that no gold is to be found. The grains of gold may sometimes be seen in evidence that no gold is to be found. The grains of gold may sometimes be seen in the cavities of the quartz, or it sparkles on a surface of fracture. But very commonly a mass of quartz that shows nothing to the eye, yields gold on trial.

The same kinds of rock and veins of quartz were observed by the author in 1842 near the Umpqua river, Southern Oregon, and pebbles from similar rocks were met with along the Sacramento; and the resemblance to other gold districts was remarked at the time; but there was no opportunity for exploring the country where

gold has since been found.

Masses of gold of considerable size have been found in North Carolina. The largest was discovered in Cabarras Co.; it weighed twenty-eight pounds avoirdu-pois, ("steel-yard weight," equals 37 lbs. troy), and was 8 or 9 inches long by 4 or

5 broad, and about an inch thick. The largest mass yet reported from California weighed 20 pounds. In Paraguay, pieces from 1 to 50 pounds weight were taken from a mass of rock which fell from one of the highest mountains. Several specimens weighing 16 pounds have been found in the Ural, and one of 27 pounds; and in the valley of Taschku Targanka, in 1842, a mass was detached, weighing very nearly 100 pounds troy. This mass is now in the Museum of Mining Engineers at St. Petersburgh. A mass found recently in Australia had the enormous weight of 134 lbs. 7 oz., and afforded 109 lbs. 11 oz. of fine gold; it sold for £5,532. Another of 27 lbs. 6 oz. 15 dwts. was obtained at Forest Creek, South Australia.

An examination of a gold rock for gold is a simple process. The rock is first An examination of a gold rock for gold is a simple process. The rock is first pounded up fine and sifted; a certain quantity of the sand thus obtained is washed in a shallow iron pan, and as the gold sinks, the material above is allowed to pass off into some receptacle. The largest part of the gold is thus left in the angle of the pan; by another similar process a further portion is obtained; and when the bulk of sand is thus reduced to a manageable quantity, the gold is amalgamated with clean mercury; the amalgam is next strained to separate any excess of mercury, and finally is heated and the mercury expelled, leaving the gold. In this way, by specessive trials with the rock the proportion of gold is quite accurately assert. by successive trials with the rock, the proportion of gold is quite accurately ascertained. It is the same process used with the larger washings, though on a small scale. Mercury unites readily with gold, and thus separates it from any associated rock or sand; and it is employed in all extensive gold washings, though much gold may be often obtained by simple washing without amalgamation.

The operation of hand washing is called in Virginia panning. With a small iron

pan, they wash the earth in a tub or in some brook, and thus extract much gold from the gravel or soil, which is said to pan well or pan poorly, according to the result. Masses of quartz, with no external indication of gold, examined in the above way at a Virginia mine, afforded an average of more than eight dollars to the

bushel of gold rock.

When gold is alloyed with copper or silver, the mode of assay for separating the copper depends on the process of capellation; and that for separating the silver, on the power of nitric acid to dissolve silver without acting on gold. (See chapter

on chemical reactions).

The uses of gold are well known; and also that it owes a great part of its value to its extreme malleability, and the fact of its not tarnishing on exposure. Although a costly metal, it is one of the cheapest means of ornament, on account of the things of the leaves into which it may be bester. A grain of the metal may be ness of the leaves into which it may be beaten. A grain of the metal may be made to cover 564 square inches of surface, and the thinnest leaf is but 1,280,000th of an inch thick.

Perfectly pure gold is denominated gold of 24 carats, or fine gold. If it contains 22 parts of pure gold to 2 of silver, or 1 of copper and 1 of silver, it is said to be 22 carats fine; so also for 20 carats fine, it contains 20 parts of pure gold. The carat is divided into 1, 1, 16, 1 parts, for a more minute specification of the quantity of gold.

The standard of gold of the United States consists of 900 parts of gold to 100 of an alloy of copper and silver. The eagle (10 dollars) contains 232 grains of fine

PLATINUM. Gediegen Platina, W. and L. Polyxen, Haus. Platine Natif. H.

Monometric. Rarely in cubes, usually in grains, and occasion-

ally in irregular lumps. Cleavage none.

H.=4-4.5. G.=16-19, 17.862, 17.759, two masses, G. Rose, 17.200, a smaller; 17.108, small grains, Breit.; 17.608, a mass, Breit.; 17.60, large mass from Nischne Tagilsk, Sokoloff. Lustre metallic. Color and streak whitish steel-gray; shining. Opaque. Ductile. Fracture hackly.

Composition .- Platinum combined with iron, iridium, and other metals. Analysis: 1-4, Berzelius, (K. V. Ac. H. 1828, 113); 5, 6, Osann, (Pogg. viii, 505, xi, 411, xiii, 283, xiv, 329, xv, 158); 7, 8, Svanberg, (Jahresb. xxiii, 273):

13

```
Plat. Fe Irid, Rhod. Pal. Os Cu
84°30 5°31 1°46 3°46 1°06 1°03 0°74, quartz 0°6, Ča 0°12=98.08, Berz.
1. Columbia,
2 Goroblago't, 86.50 8.32 — 1.15 1.10 — 0.45, Îr. Os 1.40=98.92.* Berzelius.

3. N. Tagilak, 78.94 11.04 4.97 0.86 0.28 — 0.70, " 1.96=98.75.* Berzelius.
                                                                            1.96=98.75,* Berzelius.
2.30=97.86,* Berzelius.
& N. Tagilsk,
                                                                       "
                    73.58 12.98 2.35 1.15 0.30 --- 5.20,
                   83·07 10·79 1·91 0·59 0·26 —— 1·30,
80·87 10·92 0·06 4·44 1·30 —— 2·30,
                                                                       "
                                                                             1.80=99.72, Osann.
6. Ural.
                                                                            0.11=100,, Osann.
                                                                       "
                    86.16 8.03 1.09 2.16 0.35 0.97 0.40,
                                                                             1.91, Mn 0.10=101.17, Sv.
7. Choco,
                    84.84 7.52 2.52 3.13 1.66 0.19 trace,
                                                                            1.56, " 0.31=101.23, Sv.
8. Pinto i
                                        · Loss partly osmium.
```

Syanberg makes the Platinum of Nos. 2, 7, 8=Fe Pt3; of No. 1, (Barbaçoa, Columbia), Fe Pt⁴; of 8, 4, 5=Fe Pt². The last is called Iron Platinum (Eisenplatin) G.=14-6—15-8, H.=6.

B.B. infusible. Soluble only in heated nitro-muriatic acid. Acts slightly on the

magnet; but this property depends on the amount of iron it contains.

Platinum was first found in pebbles and small grains, associated with iridium, rhodium, osmium, palladium, gold, copper, and chrome, in the alluvial deposits of Brazil, Choco, and Barbaçoa, in South America, where it received its name, platina, from plata, silver, of which word platina is a diminutive. Occurs at Nischne Tagilsk, and Goroblagodat, in the Ural, here, (as elsewhere), in alluvial or drift material; the gravel has been traced to a great extent up Mount La Martiane, which consists of crystalline rocks. It has been formed into coins of eleven and twenty-two rubles each, by the Russians, which are not a legal tender, but pass conventionally, and principally in the southern provinces of the empire. Russia affords annually about 800 cwt. of platinum, which is nearly ten times the amount from Brazil, Columbia, St. Domingo, and Borneo. The amount coined from 1826 to 1844, equaled 24 millions of dollars. Platinum is also found on Borneo; in the sands of the Rhine; at St. Aray, val du Drac; county of Wicklow, Ireland; on the river Jocky, St. Domingo; in the California gold region; in traces with gold in Rutherford Co., North Carolina; at St. Francois Beauce, etc., Canada East. Borneo affords 600 to 800 pounds per year.

Although platinum generally occurs in quite small grains, masses are sometimes found of considerable magnitude. A mass, weighing 1088 grains, was brought by Humboldt from South America, and deposited in the Berlin museum; specific gravity 18-94. In 1822 a mass from Condoto was deposited in the Madrid museum, measuring two inches and four lines in diameter, and weighing 11,641 grains. A specimen was found in the year 1827, in the Ural, not far from the Demidoff mines, which weighed 10 16 Russian pounds, or 11:57 pounds troy, and similar masses are not uncommon; the largest yet seen weighed 21 pounds troy, and is in the Demidoff cabinet.

The infusibility of this metal, and its property of resisting the action of the air and moisture, and nearly all chemical agents, render it highly valuable for the construction of philosophical and chemical apparatus; for vessels for the concentration of sulphuric acid; for crucibles and capsules in chemical analysis; for covering other metals, and for painting on porcelain. It may be drawn into wire of extreme tenuity; Dr. Wollaston succeeded in obtaining a wire not exceeding the two thousandth of an inch in diameter.

The metal platinum was first discovered by Ulloa, a Spanish traveler in America, in the year 1735.

This metal fuses readily before the "compound blowpipe;" and Dr. Hare succeeded in 1837 in melting twenty-eight ounces into one mass. The metal was almost as malleable and as good for working as that obtained by the other process; it had a specific gravity of 19.8. He afterwards succeeded in obtaining from the ore masses which were 90 per cent. platinum, and as malleable as the metal in ordinary use, though somewhat more liable to tarnish, owing to some of its impurities.

PLATINIRIDIUM, Svanberg. Native Iridium.

In small grains with Platinum; sometimes in cubes with truncated angles, (f. 15). H = 6 - 7; $G = 22 \cdot 6 - 23$. Color white.

Composition.—Platinum and iridium in different proportions. Analyses by Svanberg, (Jahresb. xv, 205):

	lrid.	Plat.	Pallad.	Rhod.	Fe	Cu	Os
1. N. Tagilsk,	76.80	19.64	0.89			1.78	——=99.11.
9. Brazil	27.79	55:44	0.49	6.86	4.14	3.30	trace==98.02

Prinsep, in a specimen from Ava in India, found 60 of iridium and 20 of platinum. If platinum and iridium are isomorphous, it is probable that the proportions of these metals are indefinite. Dr. Genth, after some trials, considers some grains occurring with the California gold to be Platiniridium. Am. J. Sci. [2], xv, 246.

PALLADIUM.

Monometric. In minute octahedrons, Haid. Mostly in grains sometimes composed of diverging fibres.

II.=4.5—5. G.=11.8, Wollaston; 12.14, Lowry. Lustre metallic. Color whitish steel-gray. Opaque. Ductile and malleable.

Composition.—Palladium, alloyed with a little platinum and iridium. Infusible alone before the blowpipe, but fuses readily with sulphur. By continuing the heat, the sulphur is driven off and a globula of pelladium obtained

the sulphur is driven off, and a globule of palladium obtained.

Palladium occurs with platinum, in Brazil. Quite large masses of the metal are brought from that country. It is extracted from the auriferous sands by first fusing it with silver, and consequently forming a quaternary alloy of gold, palladium, silver, and copper, which is granulated by projecting it into water. By means of nitric acid all but the gold is dissolved; and from the solution, the silver is first precipitated by common salt as an insoluble chlorid, and then, after separating the chlorid, the palladium and copper are precipitated by plates of zinc. This precipitate is redissolved in nitric acid, an excess of ammonia added, and then hydrochloric acid sufficient to saturate; a double chlorid of palladium and ammonium is deposited as a crystalline yellow powder, which on calcination produces spongy palladium. The metal is malleable and when polished has a splendid steel-like lustre, which does not tarnish. A cup weighing 3½ pounds was made by M. Breant for the mint of Paris, and is now in the garde-meuble of the French government. One part fused with six of gold forms a white alloy; and this compound was employed at the suggestion of Dr. Wollaston, for the graduated part of the mural circle, constructed by Troughton for the Royal Observatory at Greenwich. It has been employed for balances and mathematical and surgical instruments.

A brown ochreous substance associated with the Palladium Gold of Brazil, has

A brown ochroous substance associated with the Palladium Gold of Brazil, has been considered a Palladium Ochroor oxyd. It is soluble in muriatic acid. Detected by Johnson and Lampadius, (J. f. pr. Chem. xi, 309).

Hexagonal Palladium.—The native palladium also occurs in small hexagonal ta-

HEXAGONAL PALLADIUM.—The native palladium also occurs in small hexagonal tables, with perfect lateral cleavage: Color pale steel-gray; lustre bright. Occurs at Tilkerode. It is the Sclenpalladite of Zinken.

QUICKSILVER. Native Mercury. Gediegen Quecksilber. Mercure Natif, II. Hydrargyrum. Argentum Vivum. Spuna argenti. Liquor Æternalis, Pliny. Mercurius of the Alchemists.

Monometric. Occurs in small fluid globules scattered through its gangue.

G.=13.568. Lustre metallic. Color tin-white. Opaque.

Composition.—Pure mercury, (Hg); with sometimes a little silver.

Entirely volatile before the blowpipe, vaporizing at 662° F.: becomes solid at
—39° F., and may be crystallized in octahedrons. Dissolves readily in nitric acid.
Mercury in the metallic state is a rare mineral; the quicksilver of commerce is
mostly obtained from cinnabar, one of its ores. Its most important mines are those
of Idria in Carniola, and Almaden in Spain. At Idria it occurs interspersed through
a kind of clay slate, from which it is obtained by washing. It is found in small
quantities at Wölfstein and Mörsfeld, in the Palatinate, in Carinthia, Hungary, Peru,
and other countries; also at Peyrat le Chateau, in the department of the Haute
Vienne, in a disintegrated granite, unaccompanied by cinnabar; in California.


AMALGAM. Mercure argentif, H. Naturlich Amalgam, W.

Monometric. Observed planes, as in the annexed figure, with also plane 2. Figure 14 common; also 17, 18, 19, 37, 43, 44. Cleavage: dodecahedral, in traces. Also massive.

H.=3-3.5. G.=10.5-14; 13.755,

H.=3—3.5. G.=10.5—14; 13.755, Haid. Color and streak silver-white. Opaque. Fracture conchoidal, uneven. Brittle, and giving a grating noise when cut with a knife.

Composition.—Both Ag Hg³ (Silver 34.8, quicksilver 65.2), and Ag Hg³ (Silver 26.25, and quicksilver 73.75), are here included as afforded by the following analyses: 1, Klaproth, (Beit, 182); 2, Cordier, (Jour. d. Mines, xii, 1, and Phil. Mag. xix, 41); 3, Heyer, (Crell's Annal. ii, 90):



			Silver.	Mercury.
1.	Ag Hg ³ ,	Moschellandsberg	36	64 =100, Klaproth.
		Allemont ?	27.5	72:5=100, Cordier.
Q	°°°'	Moschallandshara	95.0	73.3-08.3 Haver

B.B. the mercury volatilizes and silver is left. Dissolves in nitric acid. Rubbed on copper it gives a silvery lustre.

From the Palatinate at Moschellandsberg, in fine crytals, and said to occur where the veins of mercury and silver intersect one another. Also reported from Rosenau in Hungary, Sala in Sweden, Allemont in Dauphine, Almaden in Spain, and in crystals in Chili

ARQUERITE, Berthier.—The arquerite is a silver amalgam from the mines of Arqueros near Coquimbo. Occurs crystallized. According to Domeyko, (Compt. Rend. nr, 567), it has the formula Age Hg—Silver 86:49, mercury 13:51=100.

GOLD AMALGAM, H. Schneider, J. f. pr. Chem. xliii, 317.

In small white grains as large as a pea, easily crumbling.

Composition. - (Au, Ag)2 Hgs. Analysis by Schneider,

Mercury 57:40, Gold 38:39, Silver 5:0.

From the platinum region of Columbia, along with platinum. Reported from California, especially near Mariposa.

SILVER. Gediegen Silber, W. Argent Natif, H.

Monometric. Observed planes O, 1, I, i2, i4, 33. Figs. 1, 11, 15, 16, 33, 40. Cleavage none. Compound crystals, f. 200. Usually coarse and fine filiform, reticulated or arborescent; also in plates, and in superficial coatings.; also in masses.

H.=2.5—3. G.=10.1—11.1, when pure 10.5. Lustre metallic. Color and streak silver-white; subject to tarnish, by which the color becomes grayish-black. Ductile.

Composition.—Silver, with some copper, gold, platinum, antimony, and other metals. Berthier found in a specimen from Curcy, near Caen, (Ann. d. Mines, xi, 72), silver 90, copper 10. Fordyee found in an alloy, silver 72, gold 28; and Klaproth, silver 36, gold 64; and under gold, many other combinations of these metals are given. John detected 1 per cent. of antimony in silver from Johanngeorgenstadt, basides traces of copper and arsenic. A bismuth-silver from Copiapo, S. A., con-

- Programme (特別) - Programme (大学) - Programme (大学)

De ma comes a mens of comes of the comes of

the control of the cornship in the control of the control of the control of the control of the control of the cornship in the control of the cornship in the corns of the cornship in the corns of the cornship in the corns of the cornship in the cornship i

the first of the most particular conferes in silver. In Mexter of the most consequence of the obtained 400 pounds; the first of the lateral accorded when obtained 400 pounds; the first of consequence of Hountaya), weighed over 8 cwt. During the first of the first outerly, more than 8,180,000 marks of silver

the control of the control of the coper of Michigan, the coper of Michigan, the coper of the coper of Michigan, the coper of the coper of Michigan, the coper of the coper of Michigan, the coper of the coper of Michigan, the coper of the coper of Michigan, the coper of the coper of Michigan, the coper of

1. C. C. and C. and C. and A. C. and A. T. at the Bridgewater copper

the control of the control of the control of the site of silver glance. The control of the contr

And the second of the second o

and the second s

•

.

17 TRON.

COPPER. Gediegen Kupfer. Cuivre Natif, H. Venus, Alchem.

Monometric. Observed forms O, 1, I, i2, $i\frac{5}{2}$, 33. Fig. 1, 11, 14, 15, 16, 17, 18, 32, 33, and others. Cleavage none. Twins, composition-face octahedral. Usually massive and also arborescent, filiform, or in films.

H.=2.5—3. G.=8.94, when pure. Lustre metallic. Color copper-red. Streak metallic shining. Ductile and malleable. Lustre metallic. Color

Fracture hackly.

Composition.—Pure Copper; but often containing native silver disseminated through it. B.B. fuses readily; on cooling, it is covered with a coating of black oxyd. Dissolves readily in nitric acid, with the extrication of the red fumes of nitrous acid, and produces a blue solution with ammonia.

Copper occurs in beds and veins accompanying its various ores, and sometimes

associated with iron. It is frequently found in loose masses imbedded in the soil.

In Siberia, and the island of Nalsoe, in Farce, it is associated with mesotype, in amygdaloid, and though mostly disseminated in minute particles, sometimes branches through the rock with extreme beauty. Common in Cornwall, at many of the mines near Redruth; and also in considerable quantities at the Consolidated mines, Wheal Buller, and others. Brazil, Chili, and Peru afford native copper; a mass now in the museum at Lisbon, supposed to be from a valley near Bahia, weighs 2816 pounds. weighs 2616 pounds.

This metal has been found native throughout the red sandstone region of the eastern United States, particularly in Massachusetts, Connecticut, and more abundantly in New Jersey, where it has been met with sometimes in fine crystalline masses, especially at Brunswick, Somerville, Schuyler's mines, and Flemington. One mass from near Somerville, on the premises of J. C. Van Dyke, Esq., of Brunswick, weighed 78 pounds, and is said originally to have weighed 128. Near Brunswick a vein or sheet of copper, a line or so thick, has been traced for several rods. Near Haven Comp. a mass was formerly found weighing 90 pounds.

New Haven, Conn., a mass was formerly found weighing 90 pounds.

No known locality exceeds in the abundance of native copper, the Lake Superior copper region, near Kewenaw Point, where it exists in veins that intersect the trap and sandstone. Masses of great size were observed in this district near the Ontanagon river, by Mr. Schoolcraft, in 1821. A large mass was thrown down in the Lake Superior region, July 8th, 1853, at the North American mine; it was about 40 feet long, and its estimated weight was 200 tons. This copper contains intimately mixed with it about $\frac{3}{10}$ per cent. of silver; often this metal is in visible grains, lumps, or strings, and occasionally a mass of copper when polished, appears sprinkled with large silver spots, resembling, as Dr. Jackson observes, a porphyry with its feldspar crystals. The copper occurs in trap or sandstone, near the junction of these two rocks, and has probably been produced through the reduction of copper ores. Strings of copper often reticulate through crystals of analcime and prehnite.

The copper of Chili also contains silver, and sometimes 7 to 8 per cent.

The copper of Chili also contains silver, and sometimes 7 to 8 per cent.

NATIVE LEAD. Plomb Natif, H. Gediegen Blei, W.

Monometric. Found in thin plates and small globules.

H.=1.5. G.=11.445, when pure. Lustre metallic. Color lead-Malleable and Ductile. gray.

Composition .- Pure lead. Fuses easily, covering the charcoal with a yellow

Oxyd. This species is reported as occurring in globules in galena at Alstonmoor; in lava in Madeira, Rathke; at the mines near Carthagena in Spain; in carboniferous limestone near Bristol, and at Kenmare, Ireland; recently, according to R. P. Greg, Jr., in thin sheets in red oxyd of lead near a basaltic dyke in Ireland.

IRON. Gediegen Eisen, W. and L. Fer Natif, H. Mars, Alchem.

Monometric. Cleavage octahedral.

H=40 G=70—76; rardy a liv as the meeting; 7:318 a partially captibed fragment of a crystal of meteoric iron from Griffied Coll N. C. Listre metallick Colle iron-gray. Streak shiring Fragmentarily. Duralle, Are so ugly to the magnet

Number will supposed to be of terrestrial origin has been observed at Canasa, Green and John the milities and fill or mode where or a said to have been found in a year or place two modes think articled to a mass of modesiate mode. It contames grapaire is the bessi lamine mi. which is was invited, and it had no obyealine exterme nor was any developed by eaching with nitric acid, as in Make the end and

However the mode.

From the for mode are also represent to have been found. Orasine describes one weighing from possible obtained in the mine of Harkenberg. It is said to have been showed in this laming in an iron store congluments in Frank and in laws in Assential and it has been stored as in the k-treet in Thomasia in an ampliance is sanistone, containing fiscally. It all of click that a trace of middle 0 miles. Forge interval, 1888, 148, where where a country are ment to click.

The procedure of metallic iron is grains in baselite rocks from Plant's Causeway, each may been announced by To Andrews. After polynoming the rock and separating by means of a magnet the grains that were attracted by it, he subjected the sential trace are not as a self-subject. The baselite is the process in the process of a mile of a self-subject.

remains by measure of a length of the grains that were attracted by its he subjected the grains to the active of an acid solution of subjects of organism the field of a minerage which sait when there is a trace of part into present gives a deposit of express and in his trials there were consistent deposits of organism in expectations.

Meteorie into usually evoluine I to at per cent of nickel besides a small per cent-

Meters from usually contains 1 to 17 per cent of nickel besides a small per centage of the metals as obtait marganese, tin, sorrer, chromium; also phosphorus extinute as a phosphorus sulphure is sulphured, latter in a me instances, chrome Pro a review of paters of meters, iven see Rammelsberg's Handworterbuch of Chemical Mineralogy, 422 and Surplements if, so line Solve 181, v. 11; v. 1; especially the law which is a general account of the subject with full citations of analyses; also Respect Mineralogisther. Fore burger for 1844-1845, title and 1850-1841, p. 117; also Presentation on Meteoric Irone by W. S. Clarke, Lieb, m. W. Annierze, 167 reviewed in Am. J. Sol. 15, xv. 1 warm to papers in Am. J. Sol. by C. U. Shepavil especially, in [2] v. law [3], v. xv. 1 warm to paper in Am. J. Sol. by C. U. Shepavil especially, in [2] v. law [3], v. xv. 2 warm to paper in Am. J. Sol. by C. U. Shepavil especially, in [2] v. law [3], v. xv. 2 warm to paper in Am. J. Sol. by C. U. Shepavil especially, in [2] v. law [3], v. xv. 3 and 3 recent paper by J. Lawrence which in vol. xvii. The following area for analyses: 1. Remedius, K. V. Ac. H. 1814, Prog. xxxiii. 1220; 3. Pergermann, Prog. lxxviii. 4 a. (3), W. S. Clarke, (loc. etc. 4 v. H. liger. Baumg. Zeits ix, 526, and Prog. xxviii. 118.

	1	2	5	4
	Sileria.	Zatatecas, Mexico	Lesses	Brit marriera
Iroz.	55142	\$3.5 %	y : s	20.70
Ni kel.	10.752	ر د ن	6 333	5-12
Coluit.	455	0.47	3.2	0.39
Manganes	e. 171 52		0.145	0.46
Copper. (0.066	0.4(8)	شؤندن	Be 0/12
Magzesim	n, únişti	0.13	0.552	$A_s \sim 82$
Carton.	0143	C. Fe @88		Carrell
Sulphar.	tr	0.54	0.445	
Fe. Ni. P	•	1 %5	1-224	
Chromiro	n,	1.48		
Gangue.	0.460			1:34
	100 000	100-88	99-228	95:16

One of the most extraordinary of these iron meteorites, preserved in any collection, is now in the Yale College cabinet. It weight 1635 lbs.; length three feet inches; breadth two feet four inches; bright one foot four inches. It has been gred by C. U. Shepard, (Am. Jour. Sci. xvi, 217, also by R. Silliman, Jr., and

⁻restrial native iron of Schooley's mountain referred to in this nothing but a furnace slag.

found to contain Iron 90 02 to 92 912, nickel 8 80 to 9 674. The crystalline structure of this iron is very remarkable as developed by nitric acid on a polished surface. Silliman has observed that the nickel is segregated along the lines of erystallization, and that it is not uniformly alloyed with the iron, as had been previously supposed, (communicated to the author). It was brought from Red river. Still more remarkable masses exist in South America; one was discovered by Don Rubin de Celis in the district of Chaco-Gualamba, whose weight was estimated at \$0,000 lbs., and another was found at Bahia in Brazil, whose solid contents are at least twenty-eight cubic feet, and weight 14,000 lbs. The Siberian meteorite, discovered by Pallas, weighed originally 1600 lbs. and contained imbedded crystals of chrysolite. Smaller masses are quite common. Meteoric iron is perfectly malleable, and may be readily worked into cutting instruments, and put to the same uses as manufactured iron.

M. Bahr has observed grains of native iron in a fragment of petrified wood. The iron was mixed with limonite and organic matter, and is supposed to have been produced by the deoxydation of a salt of iron by the organic matter of the wood.

He calls the iron Sideroferrite.

NATIVE TIN.

1:1 (over basal edge)=57° 13′, over pyramidal =140° 25′, 1i:1i (over basal edge)=42° 11′, over pyramidal=150° 31'; a=0.38566. Reported as occurring in small grayish-white metallic grains along with the Siberian gold.

Composition.—Tin with some lead. Hermann, J. f. pr. Ch. xxxiii, 300. The above angles are from artificial crystals galvanically deposited, measured by

ARSENIC GROUP.

1. Arsenic Section: Hexagonal or rhombohedral. Iridosmine, including Newjanskite, (Ir, Rh) Os, and Sisserskite, Ir Os'; Tellurium, Te; Bismuth, Bi; Tetradymite, (Te, Bi); Antimony, Sb; Arsenic, As; Arsenical Antimony, (Sb, As.)

2 SULPHUR SECTION: Trimetric or monoclinic. Sulphur, S; Selenium, Se.

IRIDOSMINE. Native Iridium. Osmium-Iridium. Irid-osmium. Newjanskite, Haid. Sisserskite, Haid.

Hexagonal. Rarely in hexagonal prisms with replaced basal edges; pyramidal angle, 127° 36', basal, 124°. Commonly in irregular flattened grains.

H.=6-7. G.=19·3-21·12. Lustre metallic. Color tin-white, and light steel-gray. Opaque. Malleable with difficulty.

Composition.—Analyses:

1.—Iridium 46 77, osmium 49 85, iron 0 74, rhodium 3 15, Berzelius, (Pogg. xxxii), **Orresponding to Ir Os [=Iridium 49.78, osmium 50.22=100]. This variety occurs in flat scales. H.=7. G.=19.386—19.471. Color tin-white. From Katharinen-

2.—Iridium 25, osmium 75=100, corresponding to Ir Os² [=Iridium 24.83, osmium 75.17=100]. In flat scales, often six-sided. This compound may be a

8.—Ir Os Iridium 19.86, osmium 80.14=100. In six-sided scales. Color steelgray. H .= 7. G .= 21.118, Rose. From Nischne-Tagilsk.

4-Iridium 72.9, osmium 24.5, Fe 5.6=100, Thomson. From Brazil. Color steelgray. G.=19.5.

No. 1 is Haidinger's Newjanskite, and 2 and 3 his Sisserskite, names derived from the names of localities.

At a high temperature the Sisserskite gives out osmium, but undergoes no further change. The Newjanskite is not decomposed and does not give an osmium odor. With nitre, the characteristic odor of osmium is soon perceived, and a mass obtained soluble in water, from which a green precipitate is thrown down by nitrie acid.

It occurs with platinum in the province of Choco in South America, and in the Ural mountains. It was first distinguished by Dr. Wollaston, who discovered that the specimens were an alloy of iridium and osmium. It is rather abundant with the alluvial gold of California, occurring in small bright lead-colored scales, some-times six-sided. Also found in the gold-washings on the rivers du Loup and des Plantes, Canada.

TELLURIUM. Gediegen Sylvan, W. Gediegen Tellur, Haus. and L. Tellure Natif Auro-ferrifère, H.

Hexagonal $R: R=86^{\circ}$ 57', G. Rose; $O: R=123^{\circ}$ 4', a=1.3302. Observed planes, R, -R, I, O; R: -R (over base) =113° 52′. In six-sided prisms, with basal edges replaced. Cleavage: lateral perfect, basal imperfect. Commonly massive and granular.

H.=2-2.5. G.=6.1-6.3. Lustre metallic. Color and streak

tin-white. Brittle.

Composition .- According to Klaproth, (Beit. iii, 2), Tellurium 92.55, iron 7.2, and gold 0.25. A specimen from Nagyag afforded Petz, (Pogg. lvii, 1842, 447), Tellurium 97-215, and gold 2.785, with a trace of iron and sulphur. It fuses readily on charcoal, burning with a greenish flame, and volatilizes almost entirely in white vapors, forming a white areola on the charcoal, red at the border.

Native tellurium occurs at the mine of Maria Loretto, near Zalathna, in Transyl-

vania, in sandstone, accompanying quartz, iron pyrites, and gold. About forty years since it was found in considerable abundance, and was melted to extract the

small quantity of gold it contains.

BISMUTH. Gediegen Wismuth, W. Bisemutum, Agricola. Plumbum Cinereum.
Tectum Argenti. Antimonium Femininum.

R: R=87° 40′, G. Rose; O: R=123° 36′; a= Hexagonal. 1.3035. Observed planes, R, -R, O, 2, and -2; 2: $2=69^{\circ}$ 28′. Cleavage: basal, perfect, 2, -2, less so. Also in reticulated and ar-

borescent shapes; foliated and granular.

H.=2-2.5. G.=9.727. Lustre metallic. Streak and color silver-white, with a reddish hue; subject to tarnish. Opaque. Fracture not observable. Sectile. Brittle when cold, but when

heated somewhat malleable.

Composition .- Pure Bismuth, excepting occasionally a slight admixture of arsenic Fuses readily; fusing temperature 476° F. B.B. evaporates, and leaves a yellow coating on the charcoal. Dissolves in nitric acid; subsequent dilution causes

white precipitate. Crystallizes readily from fusion.

Bismuth occurs in veins in gneiss and clay slate accompanying various ores of silver, cobalt, lead, and zinc. It is most abundant at the silver and cobalt mines of Saxony and Bohemia, Schneeberg, Altenberg, Joachimstahl, Johanngeorgenstadt, &c. It has also been found at Modum in Norway, and Fahlun in Sweden, At Schneeberg it forms aborescent delineations in brown jasper. At Huel Sparner, near Redruth, and elsewhere in Cornwall, and at Carrack Fell in Cumberland, it is

associated with ores of cobalt; formerly from near Alva in Stirlingshire.

At Lane's mine in Monroe, Conn., it is associated in small quantities with wolfram, tangstate of lime, galena, blende, &c., in quartz; also at Brewer's mine, Chesterfield district, South Carolina.

TETRADYMITE. Telluric Bismuth. Tellurwismuth. Bornite.

Rhombohedral. $O: R=118^{\circ}$ 38', $R: R=81^{\circ}$ 2'; a=1.5865. $-2: -2=66^{\circ}$ 40', $O: -2=105^{\circ}$ 16'. Crystals often tabular. Cleavage: basal, very perfect. Also massive, foliated or granular. H.=1.5-2. G.=7.2-8.44. Lustre metallic splendent. Color pale steel-gray. Not very sectile. Laminæ elastic. Soils paper.

Composition.—Bi and Te in different proportions according to G. Rose, the two being isomorphous, and the other ingredients unessential. Hausmann sustains the

Analyses: 1, Wehrle, (Schw. J. lix, 482); 2, Berzelius, (K. V. Ac. H. 1823, 183); 3, Wehrle, (Baumg. Zeit. ix, 144; 4-5, C. Fisher, Jr., (Am. J. Sci. [2], vii, 282); 6, C. T. Jackson, (This. Min. 3d edit..., p. 712); 7, F. A. Genth, (Am. Jour. Sci. [2], xvi, 81); 8-9, Damour, (Ann. Ch. Phys. [3], xiii, 372).

1. Schubkau, Te 34.6 S 4.8 Se trace Bi 60.00=99.4, Werhle. 58.30, gangue 0.75=99.42, Berzelius. 86.05 4.82 & Deutsch-Pilsen, 61·15, Ag 2·07=95·29, Werhle. 51·65, Fe 1·25, Si 3·86=99·34, Fisher. 29-74 2.88 4 Fluvanna Co., Va., 35-77 6.81 54.81=100, Fisher. 58.80, Au, Fe, Si 2.70=100.20, Jackson. 37.96 7.23 6. Whitehall, Va., 85-05 3.65 7. Davidson Co., N. C. 38.84 5.27 61.35=100.46, Genth; G=7.287. trace

& Brazil Bornite, 15.98 8.15 1.48 79.15=99.71, Damour. 4.58

15.68

Dr. F. A. Genth finds no sulphur and little selenium in the Fluvanna Co. mineral. B.B. fuses instantly, tinging the flame blue, and covering the charcoal with a whitish or yellow color, red at the margin in the seleniferous variety. In an open tabe gives off white fumes; also a reddish sublimate, and the odor of selenium from the Virginian ore.

78:40=98:66, Damour.

Occurs at Schubkau near Schemnitz; at Retzbanya; at Tellemark in Norway; at Bastnaes, Sweden; at Deutsch-Pilsen in Hungary. San José in Brazil (Damour's analysis). In the United States, at the Whitehall gold mines, Spotsylvania Co., at Monroe mine, Stafford Co., and Tellurium mine, Fluvanna Co., Virginia, associated with native gold; in Davidson Co., North Carolina, about five miles west of Washington mine, in foliated scales and lamellar masses along with gold, copper pyrites, magnetite, epidote, limonite, etc.; it was partly altered to a combination of tellurous acid and oxyd of bismuth, with but little of carbonate of bismuth (Genth, loc cit.)

ANTIMONY. Gedigen Antimon. Spiesglas, W. Antimoine Natif. H.

Rhombohedral. $R: R=87^{\circ}$ 35', Rose, $O: R=123^{\circ}$ 32'; a=1.3068. Observed planes, R, O, $\frac{1}{4}$,—2, i2; $O:\frac{1}{2}$ (cleavage plane) = 142° 58′, $\frac{1}{2}:\frac{1}{2}=117°$ 7′, 2:2=89° 25′, $\frac{1}{4}:\frac{1}{4}=144°$ 24′, $O:\frac{1}{4}=159°$ 26′, O:2=108° 20′. Cleavage: basal, highly perfect;— $\frac{1}{2}$ distinct. Generally massive, lamellar; sometimes botryoidal or reniform with a granular texture.

H.=3-3.5. G.=6.646-6.72, 6.65-6.62, crystals, Kengott. Lustre metallic. Color and streak tin-white. Rather brittle; not ductile.

Composition.—Antimony, containing sometimes silver, iron, or arsenic. Analysis by Klaproth, (Beit. iii, 169): from Andreasberg, Antimony 98, silver 1, iron 0.25 **=**99·25.

B.B. soon melts to a globule, which continues to burn though the heat be removed; a continuation of the heat causes it to evaporate in white fumes, which are deposited around the globule. Under the microscope, yellowish-white octahedrons are seen to be first formed, and subsequently, prismatic crystals of oxyd of antimony, with which at last the whole globule is covered. Crystallizes readily

Occurs in lamellar concretions in limestone at Sahlberg, near Sahl in Sweden; at Andreasberg in the Hartz; in argentiferous veins in gneiss at Allemont in Dauphiny; at Przibram in Bohemia; in Mexico, and other places.

ALTERED FORM.—Oxydizes on exposure and forms Valentinite, (Sb).

ARSENIC. Gediegen Arsenik, W. Arsenicum. Apperikov, Apoerikov.

Rhombohedral. $R: R=85^{\circ} 41', O: R=122^{\circ} 9', a=1.3779.$ Observed forms R, $-\frac{1}{2}$, O; $-\frac{1}{2}$: $-\frac{1}{2}$ =113° 21′. Cleavage: basal, imperfect. Often granular massive; sometimes reticulated, reni-

form, and stalactitic. Structure rarely columnar. H.=3.5. G.=5.93. Lustre nearly metallic. Color and streak tin-white, tarnishing soon to dark-gray. Fracture uneven and

fine granular.

Composition. - Arsenic, often with some antimony and traces of iron, silver, gold, or bismuth.

B.B. volatilizes in white fumes, having the odor of garlic; if heated nearly to redness it burns with a pale bluish flame, giving out alliaceous fumes.

Native arsenic commonly occurs in veins in crystalline rocks and the older schists,

and is often accompanied by ores of antimony, red silver ore, realgar, blende, and

other metallic minerals.

The silver mines of Freiberg, Annaberg, Marienberg, and Schneeberg, afford this metal in considerable quantities; also Joachimstahl in Bohemia, Andreasberg in the Hartz, Kapnik in Transylvania, Orawitza in the Bannat, Kongsberg in Norway, Zimeoff in Siberia, in large masses, and St. Maria aux Mines in Alsace. In the United States it has been observed by Jackson at Haverhill, N. H., on the estate of

Mr. Francis Kimball, in thin layers in dark-blue mica slate, stained by plumbago, and containing also white and magnetic pyrites; also at Jackson, N. H.

The name Arsenic is derived from the Greek αρρενικον or αρσενικον, masculine, a term applied to orpiment or sulphuret of arsenic, on account of its potent properties. Breithaupt's arsenglanz from Marienberg, is arsenic impure with 3 per cent. of Bismuth. G.=536—539. H.=2.

ALTERED FORMS. - Oxydizes on exposure, producing a black crust, which is a mixture of arsenic and arsenolite (As), and also pure arsenolite.

ARSENICAL ANTIMONY. Arsenikantimon. Antimon-arsen, Naum.

Rhombohedral. In reniform masses and amorphous; structure

curved lamellar; also fine granular.

H.=3.5. G.=6.13, Thomson; 6.203, Rammelsberg. Lustre metallic, occasionally splendent; sometimes dull. Color tin-white, or reddish-gray; often tarnished brownish-black.

Composition.—SbAs³=Arsenic 63.62, antimony 36.38. Analysis by Rammelsberg of the Allemont ore (1st Supp. 13): Arsenic 62.15, antimony 37.85=100.

B.B. emits fumes of arsenic and antimony, and fuses to a metallic globule, which takes fire and burns away, leaving oxyd of antimony on the charcoal.

It occurs sparingly at Allemont; also at Przibram in Bohemia, where it was observed by Zippe in metallic veins, associated with blende, antimony, spathic iron, &c.; at Schladming in Styria, and Andreasberg in the Hartz.


NATIVE SULPHUR. Natürlicher Schwefel. Soufre, H.


Trimetric. $I: I=101^{\circ} 46', 0:1\overline{\imath}=113^{\circ} 6'; a:b:c=2\cdot344:1$:

 $O: \frac{1}{3} = 134^{\circ} 47'$. $O: 1\frac{1}{3} = 115^{\circ} 53'$. $1: 1 \text{ (mac.)} = 106^{\circ} 25'$. $O: \frac{1}{3} = 123^{\circ} 30'$. $O: 1\frac{1}{4} = 117^{\circ} 41'$. $1: 1 \text{ (brach.)} = 85^{\circ} 07'$. $O: 1 = 108^{\circ} 19'$. $O: \frac{2}{3}i = 128^{\circ} 12'$. $1: 1 \text{ (bas.)} = 143^{\circ} 23'$.

Cleavage: I, and 1, imperfect. Twins, composition-face, I, sometimes producing cruciform crystals. Also massive, sometimes consisting of concentric coats.

H.=1.5—2.5. G. =2.072, of crystals from Spain. Lustre resinous. Streak sulphur-yellow, sometimes reddish or





greenish. Transparent—subtranslucent. more or less perfect. Sectile.

Fracture conchoidal,

Composition.—Pure sulphur, but often contaminated with clay or bitumen; burns with a bluish flame at a low temperature, with the strong odor of sulphurous acid; becomes resinously electrified by friction; is insoluble in water, and not acted on by the acids.

Sulphur is dimorphous, the crystale being obtuse oblique rhombic prisms, of 90° 32′, and inclination of the vertical axis—95° 46′, when formed at a moderately high

temperature, (125 C., according to Frankenheim).

The great repositories of sulphur are either beds of gypsum and the associate rocks, or the regions of active and extinct volcanoes. In the valley of Noto and Mazzaro in Sicily, at Conil near Cadiz in Spain, Bex in Switzerland, and Cracow in Poland, it occurs in the former situation. Sicily, and the neighboring volcanic ides, the Solfatara near Naples, the volcanoes of the Pacific ocean, &c., are localities of the latter kind. The crystals from Sicily are sometimes two or three inches in dameter. It is also deposited from hot springs in Iceland; and in Savoy, Switzerland, Hanover, and other countries, it is met with in certain metallic veins; near Cracow and in Upper Egypt there are large deposits. A fibrous variety is found near Siena in Tuscany.

Sulphur is found near the sulphur springs of New York, Virginia, &c., and also in coal deposits and elsewhere, where sulphuret of iron is undergoing decomposition; also in microscopic crystals at some of the gold mines of Virginia and North Carolina; and as a powder in the Western lead regions in fissures in the limestone. It occurs in small masses in limestone on the Potomac, twenty-five miles above Washington

The sulphur mines of Sicily, the crater of Vulcano, and the Solfatara near Naples, afford immense quantities of sulphur for commerce. It is also largely obtained in coating the sulphurets of iron and copper.

This species is homeomorphous with Barytes and Marcasite if \$1 be taken as the unit macrodome. The above figure is by Scacchi of Naples.

NATIVE SELENIUM.

Monoclinic, according to Mitscherlitch. In incrustations of a submetallic lustre, and grayish or brownish black color; translucent and red in thin splinters. Powder deep red. H.=2.0. 0.=4.3—4.32. Brittle.

Observed by Del Rio, at Culebras in Mexico.

SELENSULPHUR.


Resembling sulphur, but of an orange or brownish color.

B.B. on charcoal burns readily, yields fumes of selenium and sulphurous acid. From Vulcano, one of the Lipari Islands. Also observed by the author at Kilaues, Hawaii.

CARBON GROUP.

DIAMOND. Adamant. Demant, W. Diamant, L. and H. 'Adamas.

Monometric. Observed planes, 1, 2, I, O, $3\frac{2}{2}$, $i\frac{3}{2}$, $i\frac{4}{3}$; often tetrahedral in planes 1, 2, and $3\frac{3}{2}$. The annexed figures, (266, 267, planes $3\frac{3}{2}$); also f. 11, 14, 15, 19, 49, 51, $i\frac{4}{3}$, similar to f. 33; 65, 66, 185. The faces often convex. Cleavage: octahedral, highly perfect. Twins, f. 200, plane of composition octahedral; also f. 185, of the same kind, but the crystal shortened in the direction of an octahedral axis; also f. 267A, same repeated. Rarely massive.



II.=10. G.=3.5295, Thompson; 3.55, Pelouze. Lustre brilliant adamantine. Color, white or colorless: occasionally tinged yellow, red, orange, green, brown, or black. Transparent; translucent when dark colored. Fracture conchoidal.

Composition.—The diamond is pure carbon crystallized. It burns, and is wholly consumed at a temperature of 14° Wedgewood, producing carbonic acid gas. It is not acted on by acids or alkalies. Exhibits vitreous electricity when rubbed.

Index of refraction 2.439. The refraction of light by the diamond is often irregular, probably arising from the cause which has produced the convex forms. In

Index of refraction 2:439. The refraction of light by the diamond is often irregular, probably arising from the cause which has produced the convex forms. In some plates from crystals, Descloiseaux has observed a fixed star of six symmetrical rays, and in others, allied in character, the rays were replaced by three large elliptical areas. Descloiseaux shows that the rays are symmetrical with reference to the faces of the octahedron, and supposes them to be due to foreign matter.

rays, and in others, allied in character, the rays were replaced by three large elliptical areas. Descloiseaux shows that the rays are symmetrical with reference to the faces of the octahedron, and supposes them to be due to foreign matter.

The diamond appears generally to occur in regions that afford a laminated granular quartz rock, called itacolumite, which pertains to the talcose series, and owes its lamination to a little take or mica. This rock is found at the mines of Brazil and the Urals; and also in Georgia and North Carolina, where a few diamonds have been found. It has also been detected in a species of conglomerate, composed of rounded siliceous pebbles, quartz, chalcedony, &c., cemented by a kind of ferruginous clay. Diamonds are usually, however, washed out from the soil. According to M. Denis (Ann. des M. [8], xix, 602) the diamond in Minas Geraes, Brazil, is found

DIAMOND. 25

in two different deposits; one called gurgulho, consisting of broken quartz, and covered by a thin bed of sand or earth; the other, cascalho, of rolled quartz pebbles, united by a ferruginous clay, resting usually on talcose clays, the whole, the debris from talcose rocks. The first deposit affords the finest diamonds, and both contain also gold, platinum, magnetic iron, rutile, &c. The most celebrated mines are on the rivers Jequitinhonha and Pardo, north of Rio Janeiro, where the sands (the waters being turned off) are washed by slaves. It has lately been found in Bahia, on the river Cachoeira, at the mines of Surua and Sincora; and Damour has recognized in the sand of the locality, quartz, feldspar, rutile, brookite, anatase, zircon crystals, diaspore, magnetic iron, gold in grains, anhydrous phosphate of alumina and lime, a silicate of yttria, and a hydro-phosphate of yttria. At Bagagem, Minas Geraes, an enormous diamond of 247‡ carats has recently been found.

The Ural diamonds occur in the detritus along the Adolfskoi rivulet, where

worked for gold, and also at other places.

In India, the diamond is met with at Purteal, between Hyderabad and Masulipatam, where the famous Kohinoor was found; but there are now only two places of exploration, and these are let to some of the natives for less than 25 transs a year; and if the hands find a stone worth four or five rupees (\$2 to \$2\frac{1}{2}) a month, they consider themselves fortunate. To such a state are the famous mines of Golconda now reduced. Found also near Parma in Bundelcund, where some of the most magnificent specimens have been found; also on the Mahanuddy near Ellore. The locality on Borneo is at Pontiana, on the west side of the Ratoos mountain. The river Gunil, in the province of Constantine in Africa, is reported to have afforded some diamonds. In the United States, a few crystals have been met with in Rutherford Co., N. C., and Hall Co., Ga. (Am. J. S. [2], ii, 253, and xv); in Australia, on the banks of the Turon.

The diamond has been found massive in Brazil, in small black pebbles, having the specific gravity 3.012—3.416. They proved on trial to be pure carbon excepting 207 to 0.27 per cent. This compact diamond is sold in the region at 75 cents the

carat of three and one-sixth grains troy.

The largest diamond of which we have any knowledge is mentioned by Tavernier, as in possession of the Great Mogul. It weighed originally 900 carats, or 2769·3 grains, but was reduced by cutting to 861 grains. It has the form and size of half a hen's egg. It was found in 1550 in the mine of Colone. The Pitt or Regent diamond weighs but 136·25 carats, or 419‡ grains; but is of unblemished transparency and color. It is cut in the form of a brilliant, and is estimated at £125,000. The Kohinoor measured on its arrival in England about 1‡ inches in its greater diameter, over ‡ of an inch in thickness, and weighed 186½ carats. It has since been recut and reduced to a diameter of 17 by 1‡ nearly; and thus diminished over one third in its weight. It is supposed by Mr. Tennant to have been originally a dodecahedron, and he suggests that the great Russian diamond and another large slab weighing 130 carats were actually cut from the original dodecahedron. Tavernier gives the original weight at 787½ carats. The Rajah of Mattan has in his possession a diamond from Borneo, weighing 367 carats. The mines of Brazil were not known to afford diamonds, till the commencement of the 18th century. Maure mentions one crystal from these mines of 120 carats, but they rarely exceed 18 or 20.

Colorless diamonds are most highly esteemed. When cut and polished, a diamond of the purest water in England, weighing one carat, is valued at £8; and the value of others is calculated by multiplying the square of the weight in carats by 8, except for those exceeding 20 carats, the value of which increases at a much more rapid rate. This rule is scarcely regarded in market, as the standard of purity and taste for different countries differs, and the slightest tinge of color affects greatly the commercial value.

The method of polishing diamonds was discovered in 1456, by Louis Berquen, a citizen of Bruges, previous to which time, the diamond was known only in its uncertainty.

The diamond is valuable for the purposes of engraving and cutting glass, and the curvature of the crystalline faces much improves it for this purpose. It is also used in powder for polishing and cutting other gems, and in splinters for drilling. It has been used for lenses for microscopes, on account of its slight chromatic aberration, and the large field it consequently affords; but the crystals often have an

4

irregularity of internal structure, even when clear, which unfits them for this

purpose.

The diamond is supposed to be of vegetable origin. It has probably proceeded from the slow decomposition of some vegetable material or bitumineus matter. Black specks, like charcoal, have been observed in some crystals: but this proves nothing necessarily respecting their origin, since this is the form which carbon uncrystallized assumes, whatever its source.

MINERAL COAL. Bituminous—Bituminous Coal. Common Coal. Brown Coal. Black Coal. Cherry Coal. Splint Coal. Cannel Coal. Jet. Lignite. Braunkohle. Pechkohle. Blätterkohle. Bituminöses Holz. Houille. Jayet.—Non-bituminous—Anthracite, H. Glance Coal. Mineral Carbon. Blind Coal. Columnar Coal. Kilkenny Coal. Stangenkohle. Glanzkohle, W. Anthraxit, Haus. Kohlenblende, L.

H=1-2.5. G=1.2-1.75. Lustre more or less resinous, sometimes submetallic. Streak and color black or brown: often grayish when impure, sometimes iridescent. Opaque. Fracture conchoidal—uneven. Brittle, or sectile. No distinct crystallization.

Composition.—Carbon, with usually a few per cent. of silica and alumina, and sometimes oxyd of iron; often contains a large proportion of bitumen. Potash and soda have also been detected.

The bituminous varieties burn with a bright yellow flame and bituminous odor; while those destitute of bitumen afford only a pale blue flame arising from the decomposition of the water present, and the formation of the gas carbonic oxyd.

The bituminous and non-bituminous varieties are usually arranged as distinct mineral species, although more properly but one.

VARIETIES. 1. Without bitumen.

Anthracite.—II.=2-2.5. G.=1.32-1.7, Pennsylvania; 1.81, Rhode Island; 1.26-1.36, South Wales. Lustre bright, often submetallic, iron-black, and frequently iridescent. Opaque. Fracture conchoidal. Usually contains 80 to 90 per cent. of carbon, 4 to 7 of water, with some earthy impurities.

The anthracites of Pennsylvania contain 85 to 92 per cent. of carbon; those of South Wales, 88 to 95; of France, 80 to 83; of Saxony, 81; of Russia, sometimes

94 per cent.

Anthracites differ much in hardness and readiness of combustion. The softer are

called free-burning coals, and contain a trace of bitumen.

Fossil Coak.—More compact than artificial coak, and some varieties contain considerable bitumen. From the Edgehill mines near Richmond, Va., according to Genth, who attributes its origin to the action of a trap eruption on bituminous coal.

II. Bituminous Coal.—The proportion of bitumen is indefinite, varying from 10 to 60 per cent., and the coal is said to be Dry or Fat, according to the amount of bitumen. The coal is softer than anthracite, less highly lustrous, of a more purely black or brownish-black color, and the specific gravity varies between 1:14 and 1:5; 1:26—1:37, Pennsylvania; 1:27, Newcastle, England; 1:199, Lancashire cannel; 1:27—1:32, Scotland; 1:2—1:33, France; 1:27—1:3, Belgium; Albert coal, Hillsboro, 1:129; Jet coal, Grayson Co., Ky., 1:166; ib. Breckenridge Co., Ky., 1:14—1:16.

Of bituminous coal, there are several varieties.

Pitch or caking coal, when heated, breaks into small pieces, which, on raising the heat, unite in a solid mass. Its color is velvet black, or grayish-black. Specific gravity, 1 269. It burns readily, with a yellow flame, but requires frequent stirring to prevent its caking, by which the ingress of air for combustion is prevented.

Cherry coal resembles caking coal, but does not soften and cake, when heated. It is very frangible, and hence, in mining it, there is considerable waste. Near Birmingham, the loss in mining, including the pillars, amounts to two-thirds of the whole. It burns more rapidly than caking coal, with a clear yellow flame.

Splint coal is a dry coal, harder than the cherry coal; it is a coarse kind of cannel coal.

There are other varieties which are still less bituminous; the fint coal of En-

gland is of this kind, and approaches anthracite; the fice coal of Wedgebury in Staffordshire is of a similar nature, and the coal of wedgebury in staffordshire is of a similar nature; and the crow coal of Cumberland at Alston Moor is almost without bitumen.

Cannel coal has a dark grayish-black or brownish-black color, a fine compact texture, a large conchoidal fracture, and receives a good polish. It burns readily, without melting, with a clear yellow flame, and it has been used as a substitute for candles, whence its name. It abounds at Lesmahago, about twenty miles from Glasgow, also in different parts of Ayrshire, where it is made into inkstands, snuff-boxes, and other similar articles.

The Albert coal of Nova Scotia has the appearance of asphaltum, and is partially soluble, (about 20 per cent.), but it has not the fusibility of asphaltum. It is the melanasphalt of Wetherill. The Jet Coal of Breckenridge and Grayson Cos., Kentucky, is like jet in compactness and beauty, and is worked with tools like Cannel Coal. Both this variety and the Albert Coal are strongly electrical when rubbed.

Jet resembles cannel coal, but is blacker, and has a more brilliant lustre. It occurs in detached pieces in clay, on the coast near Whitby in Yorkshire, and at Ballard Point, and elsewhere. It is the Gagates of Dioscorides and Pliny, a name derived from the river Gagas in Syria, near the mouth of which it was found.

Brown coal is more recent in origin than the carboniferous era of geologists. It sometimes closely resembles common bituminous coal. Other varieties have a brownish-black color, bright coal-like lustre, with something of the texture of wood remaining; and often the form and fibre of the original tree is retained: this is called Lignite. Lignite burns with an empyreumatic odor. Brown coal occurs in beds, usually of small extent, and is seldom as pure from pyrites as the more ancient bituminous coal. There are, however, some workable mines.

Professor W. R. Johnson obtained the following results in his analyses of coals:

	Moisture.	Vol. combus- tible matter.	Fixed carbon.	Ash and clinkers.
1. Pennsylvania anthracites,	1.34	3·84	87 · 45	7:37
2. Maryland free-burning bituminous coal,	1.25	15.80	73.01	974
3. Pennsylvania free-burning bituminous co	al, 0.82	17.01	68.82	13.35
4. Virginia bituminous,	1.64	36.63	50.99	1074
5. Cannelton, Indiana, bituminous,	2.20	33.99	58· 44	4.97

The following are other analysis: 6-13, by B. Silliman, Jr.; 14, Frazer, (Am. J. 8ci. [2], xi, 301).

		Vol. matter.	Fixed carbon.	Ash.
6.	Grayson Co., Jet Cannel,	61.95	30.07	7.98=100.08
7.	a a	65.29	27.22	7.27 = 99.91
8.	Breckenridge Co., Jet Cannel	, 64·30	27.16	8.48= 99.93
9.	Grayson Cannel, G.=1:371,	62.03	14.36	28.62=100.00
10.	" bitum.,	41.06	54.94	4.11=100.11
11.	Albert Coal,	61.74	36.04	2.22=100.00
12.	Boghead Cannel, (Scotch,)	66.35	30.88	277=100.00
18.	Pittsburgh bitum.,	32.95	64.72	2.31 = 99.98
	Cowlitz, Oregon, (Brown coal	l), 49·5	42.9	2.7, water 4.9=100

In the Albert coal, Prof. Booth found 5975 per cent. of volatile matter, and Dr. Jackson 58.8 to 61.67 per cent. Dr. Wetherill obtained, (Trans. Amer. Phil. Soc. x, 358), Carbon 82.670, H 9.141, O, N, 8.189=100; and he states that 4 parts were soluble in ether and 30 in turpentine.

For the geological evidence distinguishing coal of the true carboniferous era, reference may be made to geological treatises

The beds of coal occur interstratified with clay slate, and sandstone, or grit rock, forming distinct layers, varying from a fraction of an inch to 80 feet or more in thickness. In the United States, the anthracites occur east of the Alleghany range, in rocks that have undergone great contortions and fracturings, while the bituminous are found farther west in rocks that have been less disturbed; and this fact and other observations have led some geologists to the view that the anthracites have lost their bitumen by the action of heat.

Extensive beds of mineral coal occur in Great Britain, covering about one-tenth the whole area, or 11,859 square miles; in France; in Spain; in Belgium, covering one twenty-second the whole area, or 518 square miles; in Netherlands, Prussia, Bavaria, Austria, Northern Italy, Silesia, Spain, Russia on the south near the Azof. It is found in Asia, abundantly in China, in Persia in the Cabul territory, and in the Khorassan or Northern Persia, in Hindostan, north of the gulf of Cutch, in the province of Bengal (the Burdwan coal field) and Upper Assam, in Borneo, Labnan, Sumatra, several of the Philippines, Formosa, Japan, New South Wales and other parts of New Holland, New Zealand, Kergueler's Land; in America, besides the United States, in Chili, at the Straits of Magellan, Northwest America on Vancouver's Island near the harbor of Camosack, at Bellingham Bay in Puget's Sound, at Melville Island in the Arctic seas, and in the British Provinces of Nova Scotia, New

Brunswick and Newfoundland.

In the United States there are four extensive coal areas. One of these areas, the Apalachian coal field, commences on the north, in Pennsylvania and southeastern Ohio, and sweeping south over western Virginia and eastern Kentucky and Tennessee, to the west of the Apalachians, or partly involved in their ridges, it continues to Alabama near Tuscaloosa, where a bed of coal has been opened. It has been estimated to cover 65,000 square miles. It embraces several isolated patches in the eastern half of Pennsylvania. The whole surface in Pennsylvania has been estimated at 15,437 square miles, or one-third the whole area of the State. A second coal area (the Illinois) lies adjoining the Mississippi, and covers the larger part of Illinois, the western part of Indiana, and a small northwest part of Kentucky; it is but little smaller than the preceding. A third occupies a portion of Missouri and Iowa west of the Mississippi. The second and third are separated by only a narrow belt of silurian rock, and properly belong together as one; and the united area is half larger than that of the Apalachian coal field. A fourth covers the central portion of Michigan. Besides these, there is a smaller coal region (a fifth) in Rhode Island, which crops out across the north end of the island of Rhode Island, and appears to the northward as far as Mansfield, Massachusetts. Out of the borders of the United States, on the northeast, commences a sixth coal area, that of Nova Scotia and New Brunswick, which covers, in connection with that of Newfoundland, 18,000 square miles, or 2-9ths the whole area of these Provinces.

The mines of western Pennsylvania, commencing with those of the Blossburg basin, Tioga Co., those of the States west, and those of Cumberland or Frostburg, Maryland; Richmond or Chesterfield, Va., and other mines south, are bituminous. Those of eastern Pennsylvania, constituting several detached areas,—one the Schuylkill coal field, on the south, worked principally at Mauch Chunk on the Lehigh, and at Pottsville on the Schuylkill; another, the Wyoming coal field, worked at Carbondale, in the Lackawanna region, and near Wyoming, besides others intermediate, those of Rhode Island and Massachusetts, and some patches in Virginia, are anthrocites. Cannel coal is found near Greensburg, Beaver Co., Pa. in Kenawha Co.,

cites. Cannel coal is found near Greensburg, Beaver Co., Pa. in Kenawha Co., Va., at Peytona, etc.; also in Kentucky, Ohio, Illinois, Missouri, and Indiana. In England, the principal coal fields are the Mañchester of Lancashire and Cheshire; the Great Central of South Yorkshire, Nottingham, and Derby; that of South Wales, Glamorganshire, &c.; the Newcastle field of northern England. In Sectland, a range of beds extends across from the Firth of Forth to the Firth of Clyde; whole area 1650 square miles. In Ireland, the three are the Limeric fields about the mouth of the Shannon, the Kilkenny fields to the eastward, and those of Ulster on the north.* Mineral coal occurs in France, in small basins, 88 in number, and powering in all, according to Taylor, 1-117th of the whole surface. The most important are the basin of the Loire, between the Loire and the Rhone, and that of Valenciennes on the north, adjoining Belgium. In Belgium, it occupies a western and eastern division, the western in the provinces of Namur and Hainault, and the eastern extending over Liege.

Coal beds more recent than the true coal era are sometimes worked. That of

^{*} For full statistics with reference to coal and coal fields, reference may be made to the very complete work on coal by R. C. Taylor, 754 pp. 8vo. Philadelphia, 1848. Also, for results of investigations into the values of different coals, to a Report to the Navy Department of the United States on American Coals applicable to Steam Navigation, and to other purposes, 600 pp. 8vo., Washington, 1844, and Am. Jour. Sci. xix, 310; also to Memoire Geol. Survey of Great Britain by De La Beche, vol. ii. Also, on Coals for making Gas, by A. Fyfe, Jameson's Jour. 1848, and Amer. Jour. Sci., [2], vii, 77, 157.

Richmond, Virginia, is supposed to be of the lias era; the coal of Brora, in Sutherland, and of Bovey, Yorkshire, are colitic in age. Tertiary coal occurs on the Cowlitz, in Oregon, (anal. 14).

Bituminous coal, Carboniferous in age, (See J. Hall, in Rep. of Stansbury's Exped. 1852, 401), occurs on the Rocky Mountains, according to Lieut. Abert, near the Raton Pass—lat. 37° 15′, long. 104° 35′—also according to Fremont, and probably of the same age, near lat. 41‡°, long. 111°, on Muddy river.

R. C. Taylor, in his extensive work on coal gives the following table showing the proportional areas of coal land in Europe and America, p. xv.

	Entire area each country.	Area of coal land.	Proport'ns of coal to	parts in	
COUNTRIES.	Sq. miles English.	Square miles.	their whole areas.		
Great Britain, Ireland, Scotland and Wales,	120,290	11,859	1-10	64	
Spain, [Asturias region],	177,781	8,408	1-52	18	
France, [area of fixed concessions] in 1845,	203,736	1,719	1-118	9	
Belgium conceded lands,	11,372	518	1-22	8	
Pennsylvania, United States,	43,960	15,437	1-8	84	
British Provinces of New Brunswick, Nova		,		1	
Scotia, Cape Breton, and Newfoundland,		18,000	1-44	98	
Prussian Dominions,	107,937		•		
Austrian Prov. containing coal or lignite,	150,000	ļ	l		
The United States of America,	2,280,000	ŀ	1-17		
The twelve principal coal-producing States,		133,132	1-4	724	
		184,073	1	1000	

GRAPHITE. Black Lead. Plumbago. Carburet of iron.

Hexagonal. In flat six-sided tables, (O, I), having the basal planes (0) striated parallel to the alternate edges. Cleavage: basal, perfect. Commonly in imbedded, foliated, or granular masses.

H.=1-2. G.=2.0891. Lustre metallic. Streak black and shining. Color iron-black—dark steel-gray. Opaque. Sectile; soils paper. Thin laminæ flexible. Feel greasy.

Composition .- Carbon and usually a variable quantity of iron, which is mechanically mixed with the carbon. The following are a few of the analyses:

Carbon,	Scheele. 81	Berthollet.	Vauquelin. 92	Saussure. 96	. Vanuxe 94·4	
Iron.	10	9.0	8	4	oxyd 1.4	
Oxygen,	97	_	_	_	silica 2.6	alumina 1·2

Fuchs obtained from a graphite from Wunsiedel only 0.33 per cent. of ash, (J. f. pr. Ch. vii, 353).

At a high temperature it burns without flame or smoke, leaving usually some red oxyd of iron. B.B. infusible, both alone and with reagents. Unaltered by acids. Graphite occurs in beds and imbedded masses, laming, or scales, in granite, gness,

mica slate, crystalline limestone, and gray-wacke, and is sometimes connected with

deposits of coal; also met with in greenstone.

A fine variety of graphite occurs at Borrowdale in Cumberland, in nests in trap, which occurs in clay slate. In Glenstrathfarrar in Invernesshire, it forms nests in gueiss, and is associated with garnet. At Arendal in Norway, it is found in quartz. It occurs at Pargas in Finland, in various parts of Austria, Prussia, France. At Craigman in Ayrshire, it occurs in coal beds, which have been formed by contact with trap. Large quantities are brought from the East Indies.

Graphite is disseminated in large masses forming veins in gneiss, at Sturbridge, sional approximation to distinct crystallizations; also at North Brookfield, Brimfield, and Hinsdale, Mass.; extensively in Cornwall, near the Housatonic, and in Ashford, Conn.; also in Brandon, Vt.; at Grenville, C. E., associated with sphene and tabular spar in granular limestone; in Wake, N. C.; on Tyger river, and at Spartenburgh near the Cowpens Furnace, S. C. Foliated masses of graphite occur near Ticonderoga, on Lake George, upon Roger's Rock, associated with pyroxene and sphene. Near Amity, Orange Co., N. Y., it is met with in white limestone, accompanying spinel, brucite, hornblende, &c.; at Rossie, St. Lawrence, Co., N. Y., with iron ore, and in gneiss; also in Bucks Co., Penn., three miles from Attleboro', associated with tabular spar, pyroxene, and scapolite; and one and a half miles from this locality, it occurs in abundance in syenite, at Mansell's black lead mine. There is a large deposit at St. John, New Brunswick.

Graphite is used for pencils, crucibles, and for diminishing friction in heavy machinery, &c.

machinery, &c.

In the United States, the mines of Sturbridge, Mass., of Ticonderoga and Fishkill,
N. Y., of Brandon, Vt., and of Wake, N. C., are worked; and that of Ashford, Conn.,
formerly afforded a large amount of graphite.

The name black lead, applied to this species, is inappropriate, as it contains no lead. The name graphite is derived from γραφω, I write. Graphite has probably the same vegetable origin as mineral coal.

Tremenheerite, Piddington, appears to be an impure variety of graphite, or it is between coal and graphite. It is scaly in structure, deep black, and highly metallic in lustre. It burns with great difficulty, reddening only at first, and is long in consuming. It afforded Piddington Carbon 85'70, water and sulphur 4'00, peroxyd of iron 2'50, earthy impurities, chiefly silica, 7'50, water and loss 0'30=100; the iron occurs as sulphuret. Tenasserim, Rev. F. Mason, Maulmain, 1852, p. 52.

II. COMBINATIONS WITH ELEMENTS OF THE ARSENIC GROUP.

1. Binary Compounds.

- I. Compounds of Elements of the Arsenic Group with one another-Elements of the Arsenic Section of the Arsenic Group being combined with elements of the Sulphur Section.
- II. Compounds of Elements of the Arsenic Group with those of the Hydrogen Group.

2. Double Binary Compounds.

- III. Compounds in which the persulphuret is a sulphuret of elements of the Hydrogen Group, as Iron, Cobalt, Nickel.
- IV. Compounds in which the persulphuret is a sulphuret of elements of the Arsenic Group.

^{*} Under this head, the Atomic weights of Arsenic, Antimony and Bismuth are taken at half the value given in the table under Chemical Mineralogy, as it is in this state that they approximate to Sulphur in the forms and relations of their compounds.

I. BINARY COMPOUNDS.

L COMPOUNDS OF ELEMENTS OF THE ARSENIC GROUP WITH ONE ANOTHER.

REALGAR GROUP. Composition RS. Crystallization Monoclinic.

REALGAE, As S.

ORPIMENT GROUP. Composition Rº Sº. Crystallization Trimetric. As S. BISMUTHINE, ORPIMENT, Bi³ S³.


Sb² S³. DIMORPHINE, STIBNITE,


REALGAR. Red Orpiment or Ruby Sulphur, J. Red Sulphuret of Arsenie. Rothes Rauschgelb, W. Arsenie Sulfuré Rouge, H. Risigallo. Arsenieum Sandaraca, Lina. Euriapann, Theoph. Discor. Sandaraca, Plin. Vitr.

Monoclinic. $C=66^{\circ}$ 5', $I: I=74^{\circ}$ 26' (Marignac, Sceachi) O: 1i=138° 21'; a:b:c=0.6755:1:0.6943.

 $O: \vec{I} = 104^{\circ} \ 12'. \quad O: \vec{i} = 113^{\circ} \ 55'. \quad \vec{i}: \ 1 = 133^{\circ} \ 1'. \\ O: \ 1\vec{i} = 139^{\circ} \ 38'. \quad \vec{i}: \ 1\vec{2} = 113^{\circ} \ 6'. \quad \vec{i}: \ 1\vec{2} = 115^{\circ} \ 1'.$

Cleavage: ii, O rather perfect; I, ii in traces. Also granular. coarse or fine; compact.





Observed Planes.

H=1.5-2. G=3.4-3.6. Lustre resinous. Color aurora-red or orange-yellow. Streak varying from orange-red to aurora-red. Transparent—translucent. Fracture conchoidal, uneven. Sectile.

Composition.—As S Sulphur 29 91, arsenic 70 09=100.

B.B. fuses readily, burns with a blue flame, and is dissipated in fumes of an alli-

seeous odor, with some sulphurous seid.

Fine crystallizations of this species have been observed with ores of silver and Josephinsthal in Bohemia, at Schneeberg in Saxony, at Andreasberg in the Hartz. At Tajowa in Hungary, it occurs in beds of clay; at St. Gothard it Switzerland, imbedded in dolomite; near Julamerk in Koordistan; also in the Vesuvian lavas, in minute crystals. Strabo speaks of a mine of sandaraca (the ancient name of this species) at Pompeiopolis in Paphlagonia.

Realgar artificially prepared has long been used as a pigment.


ALTERED FORMS.—Changes, on exposure, to Orpiment (As² S³) and Arsenolite (As² O³), 6 of As S becoming 2 As³ S³, and 2 As being set free which changes to As² O³ or Arsenolite, (Volger). A black crust sometimes forms on Realgar, which is supposed by Volger to be a sulphuret containing less sulphur than Realgar.

ORPIMENT. Yellow Sulphuret of Arsenic. Gelbes Rauschgelb, W. Rauschgelb, Haus. Operment. Auripigment, L. Arsenic Sulfuré Jaune, H. Resigallum. Auripigmentum, Vitr. Αρσενικόν, Dioseor. Αρρενίκον, Theoph. Arsenicum, Plin.

Trimetric. $I: I=100^{\circ} 40', O: 1\bar{\imath}=126^{\circ} 30': a:b:c=1.3511:1:1:2059$. Observed planes as in the annexed figure.

 $0:1i=131^{\circ}45'$. i i i i $(ov.ii)=117^{\circ}49'$. 1i: $1i=83^{\circ}30'$.

 $O: 25=127^{\circ}27'$. $2: 25 \text{ (adj.)}=94^{\circ}20'$. $2: 25 \text{ (ov. 15)}131^{\circ}36'$.



Cleavage: ii highly perfect, ii in traces. ii longitudinally striated. Also massive, foliated, or columnar, sometimes reniform.

II.=1.5—2. G.=3.48, Haidinger: 3.4, Breithaupt. Lustre pearly upon the faces of perfect cleavage; elsewhere resinous. Color several shades of lemon-yellow. Streak yellow, commonly a little paler than the color. Subtransparent—subtranslucent. Sectile. Thin laming obtained by cleavage, flexible but not elastic.

Composition.—As S³=Sulphur 39 and arsenic 61. B.B. burns with a blue flame on charcoal, and emits fumes of sulphur and arsenic. Dissolves in nitromuriatic acid or ammonia.


Orpiment in small crystals is imbedded in clay, at Tajowa, near Neusohl in Lower Hungary. It is usually in foliated and fibrous masses, and in this form is found at Kapnik in Transylvania, at Moldawa in the Bannat, and at Felsobanya in Upper Hungary, where it exists in metalliferous veins, associated with realgar and native arsenic; at Hall in the Tyrol it is found in gypsum; at St. Gothard in dolomite; at the Solfatara near Naples, it is the result of volcanic sublimation; in brown coal of Fohnsdorf, Styria. Near Julamerk in Koordistan, there is a large Turkish mine. Small traces are met with in Edenville, Orange Co., N. Y., on arsenical iron.

The name orpiment is a corruption of its Latin name aurigmentum, "golden paint," which was so called in allusion to its color, and also because it was supposed to contain gold.

It it used as a pigment, but is usually prepared artificially for that purpose.

DIMORPHINE. Scacchi, Mem. Geol. sulla Campania, Napoli, 1849.

Trimetric. Two types; (A) $I: I=98^{\circ} 6'$; $O: 17=127^{\circ} 50'$; a:b:c=12876:1:11526; (B) common form, $I: I=100^{\circ} 32'$.



0:17=127° 1', a:b:c= 1·3262:1:1·203. Observed planes as in the annexed figures.

In A, $\partial: 1 = 120^{\circ}$ 23', $\partial: 1 = 131^{\circ}$ 50', $\partial: \frac{1}{2} = 150^{\circ}$ 49', 15: 15 (over \mathcal{O})=83° 40', 1: 1 (ov. 17)=111° 10', In B, $\partial: \frac{5}{4} = 121^{\circ}$ 6', $0: 11=151^{\circ} 7', 0: \frac{5}{4}=116^{\circ} 40', i : i = 112^{\circ} 45'.$ Cleavage none. Crystals minute.

H=1.5. G=3.58. Lustre splendent adamantine. Color orange-yellow: powder saffron-yellow. Translucent and transparent. Fragile.

Composition.—From imperfect trials by Scaechi, perhaps As' S'—Sulphur 24.55, Arsenie 75.45. Heated in a porcelain crucible with a spirit lamp, affords an agreeable odor and becomes red; with more heat becomes brown, gives off yellow fumes, and exporates, leaving no residue; with soda a garlie odor. Completely soluble

From a fumarole of the Solfatara, Phlegreean fields. Crystals not over half a millimeter in their longest direction.

BEMUTHINE, Bend. Sulphuret of Bismuth. Wismuthglanz. Bismuth Sulphure, H.

Trimetric. $I: I=91^{\circ} 30'$. Observed planes I, ii, ii, ii, iii, Brooke. Cleavage: brachydiagonal perfect; macrodiagonal less so; basal perfect. In acicular crystals. Also massive, with a foliated or fibrous structure.

H.=2-2.5. G.=6.4-6.549. Lustre metallic. Streak and color lead-gray, inclining to tin-white, with a yellowish or iridescent tarnish. Opaque. Sectile.

Composition.—Bi² S²—Sulphur 18.4, bismuth 81.6; isomorphous with Stibnite.

Analyses: 1, H. Rose, (Gilb. Ann. lxxii, 192); 2, Wehrle, (Baumg. Zeits. x, 385);

§ Scheerer, (Pogg. lxv, 299); 4, Hubert, (Haid. Ber. iii, 401); 5, Rammelsberg, (5th Suppl. 281) Sappl., 261).

```
Bi
                         1872 80.98=99.70, Rose.
18.28 80.96=99.24, Wehrle.
1. Riddarhyttan,
2 Retzbanya,
                                    79-77, Fe 0·15, Cu 0·14=99·18, Scheerer; G. 6·408.
74-55, Fe 0·40, Cu 3·13, Au 0·53, Pb 2·26=100·33, Hubert.
& Gjellebäk,
                           19.12
4 Orawitz,
                           19:46
```

5. Cornwall,

Puses in the flame of a candle. B.B. is volatilized, and covers the charcoal with Yellow, throwing out small drops in a state of incandescence. Dissolves readily in

18:42 78:00, Fe 1:04, Cu 2:42=99:88, Rammelsberg.

hot nitric acid, and a white precipitate falls on diluting with water.

Accompanies molybdenite and apatite in quartz, at Caldbeckfell in Cumberland, having a foliated structure; near Redruth; at Botellach near Land's End; at Johanngeorgenstadt, Altenberg, Schneeberg, in limestone; with cerium ore at Basthas, Sweden. Shepard reports its occurrence with Chrysoberyl at Haddam, Ct.


STIBNITE. Stibine, Beud. Antimony Glance. Sulphuret of Antimony, P. Gray Antimony, Antimonite, Haid. Grauspiessglaserz, W. Grauspiessglanzerz, Haus. Antimonglanz. Antimonine Sulfuré, H. Stibium. Στιμμι. Πλατυόφθαλμον. Leo Ruber. Plumbum Nigrum, Vetr. Lupus Metallorum, Alchem.

Trimetric. $I: I=90^{\circ} 45', O: 1\bar{\imath}=134^{\circ}; a:b:c=1.0352:1:$

```
\begin{array}{lll} 0: \frac{1}{3} = 154^{\circ} \ 7'. & O: 1\frac{1}{2} = 134^{\circ} \ 23\frac{1}{2}. \\ 0: 1 = 124^{\circ} \ 31'. & i\frac{1}{2}: i\frac{1}{2} \ (\text{mac.}) = 127^{\circ} \ 28'. \\ 0: 2\frac{1}{2} = 113^{\circ} \ 36'. & 1\frac{1}{2}: 1\frac{1}{2} \ (\text{top}) = 88^{\circ} \ 47'. \end{array}
                                                                                  O: 1i=134^{\circ} 23\frac{1}{2}. 1: 1 \text{ (mac.)}=109^{\circ} 16'. i\overline{2}: i\overline{2} \text{ (mac.)}=127^{\circ} 28'. 1: 1 \text{ (brach.)}=108^{\circ}10'.
                                                                                                                                                                                                       1:1 \text{ (bas.)}=110^{\circ} 58'.
```

\$1

11



Lateral planes deeply striated longitudinally. Cleavage: ii highly perfect. Often columnar, coarse or fine; also granular to impalpable. H. = 2. G. = 4.516,Haüy; 4.62, Mohs.-Lustre metallic. Color and streak lead-gray, inclining to steel-gray: subject to blackish tar-

nish, sometimes iridescent. Fracture small subconchoidal. Sectile. Thin laminæ a little flexible.

15 36

Composition.—Sb² S²—Sulphur 27·12, antimony 72·88. Analyses: 1, Bergman, (Chem. Opus. ii, 167); 2, J. Davy, (Phil. Trans. 1812, 196); 8, Thomson, (Min. i, 86); 4, Brandes, (Trommsdorff's N. J. iii, 252):

74.06 73.5 Antimony, 74 78-77 26=100, Berg. 25-94=100, D. 26-28=100, T. 26-5=100, Brandes. Sulphur,

Fuses readily in the flame of a candle, coloring it greenish. B.B. on charcoal emits white fumes and a strong sulphurous odor, and yields a white slag. pure perfectly soluble in muriatic acid.

Gray antimony occurs with spathic iron in beds, but generally in veins. It is

often associated with blende, heavy spar, and quartz.

It is met with in veins at Wolfsberg, in the Hartz, and at Pösing, near Presberg in Hungary. Its most celebrated localities, however, are Felsobanya, Schemnitz. and Kremnitz in Hungary, where it often occurs in diverging prisms, several inches long, accompanied by crystals of heavy spar and other mineral species. In Dunfriesshire it occurs fibrous and laminated; in Cornwall massive; and compact at Magurka in Hungary. Also abundant in Borneo.

In the United States, it occurs at Carmel, Penobscot Co., Me, and at Cornish and Lyme, N. H.; also at "Soldier's Delight," Md.

This ore affords nearly all the antimony of commerce. The crude antimony of the shops is obtained by simple fusion, which separates the accompanying rock. From this product most of the pharmaceutical preparations of antimony are made,

and the pure metal extracted.

This ore was employed by the ancients for coloring the hair, eyebrows, &c., to increase the apparent size of the eye; whence they called the ore πλατοδφθαλμου. from πλατυς, broad, and οφθαλμος, eye. According to Dioscorides, it was prepared for this purpose by enclosing it in a lump of dough, and then burning it in the coals till reduced to a cinder. It was then extinguished with milk and wine, and again placed upon coals and blown till ignition; after which the heat was discontinued, lest, as Pliny says, "plumbum fiat," it become lead. It hence appears that the metal antimony was occasionally seen by the ancients, though not distinguished

Altered Forms.—Changes on exposure by partial oxydation to Antimony Blende, (2 Sb² S²+Sb² O²), and by further oxydation to Valentinite, (Sb² O²); Antimony Ochre, (Sb² O²+Sb² O³), and also Sb² O³+5H, are other results of alteration.

IL BINARY COMPOUNDS OF THE ARSENIC GROUP WITH THE OTHER ELEMENTS.

- 1. Discrasite Division. Composition R2 A.*
- 1. DISCRASITE GROUP.—Composition R² Sb. Trimetric.
 - 2. Galena Division. Composition R A.
- 1. GALENA GROUP.—Composition R (S, Se, Te). Monometric, bolohedral.
 - 2. Blende Group.—Composition R.S. Monometric, tetrahedral.
 - 3. STROMEYERITE GROUP.—Composition R S. Trimetric.
- 4. Pyrrhotine Group.—Composition R (S, Se), or R (As, Sb). Hexagonal.
 - 3. Pyrites Division. Composition R A2.
- 1. Pyrites Group.—Composition R S², or R, (As, Sb)², or R, (8, As, Sb)². Monometric.
- 2. MARCASITE GROUP.—Composition R S², R (As, Sb)², or R(S, As, Sb)². Trimetric.
 - 3. NAGYAGITE GROUP.—Composition R (Te, S)². Dimetric.
 - 4. COVELLINE GROUP.—Composition R S2. Hexagonal.
 - 4. Skutterudite Division. Composition R A3.
 - 1. SKUTTERUDITE GROUP. Monometric.

1. DISCRASITE DIVISION.


The Discrasite Group here included contains the species DISCRASITE, (Ag' Sb). DOMETERE, which follows, may belong to a separate section, but is of somewhat Incertain constitution.

DISCRASITE, Frobel. Antimonial Silver. Antimoniet of Silver. Spiesglas-Silber, W. Silber-Spiessglanz, Haus. Antimon-silber, L. Argent Antimonial, H.

Trimetric. $I: I=119^{\circ} 59'; O: 1\bar{\imath} 130^{\circ} 41'; a:b:c=1.1633:$ 1:17315.

- 1: 1 (brach.)=92°.
- $0:18=142^{\circ}12'$ $1:1 \text{ (mac.) } 132^{\circ} 42^{\circ}.$ $i\tilde{s}:i\tilde{s}=120^{\circ}$ 1'.

^{*} A is put for any element of the Arsenic Group. We repeat that the halved atomic weights of As, Sb, Bi are here adopted, as well as beyond. R S° and R As°, or R S and R As, are then approximately isomorphous.



Observed Planes.

Cleavage: basal distinct; 1% also distinct; I imperfect. Twins: stellate forms and hexagonal prisms. Also massive, granular; particles of various sizes, weakly coherent.

H.=3·5—4. G.=9·44—9·8; 9·4406, Haüy. Lustre metallic. Color and streak silver white, inclining to tin-white; sometimes tarnished yellow or blackish. Opaque. Fracture uneven.

Composition.—Ag² Sb=Antimony 23, silver 77=100. Also Ag² Sb=Antimony 16-6, silver 83-4. Analyses: 1, 2, 5, Klaproth, (Beit. ii, 298, iii, 173); 3, Vauquelin, (Haūy's Min. iii, 392); 4, Abich, (Crell's Ann. 1798, ii, 3):

```
1. Wolfach, coarse granular, Antimony 24:
2. Andreasberg foliated granular, 28:
3. "22: 78=100, Klaproth.
4. "24:25 75:25=99:5, Abich.
5. Wolfach, fine granular, 16: 84=100, Klaproth.
```

B.B. fumes of antimony are given off, and a gray metallic globule, which is not malleable, is left. By continuing the heat, on charcoal, silver is obtained. Soluble in nitric said leaving oxyd of antimony.

in nitric acid, leaving oxyd of antimony.

Occurs in veins at Altwolfach in Baden, Wittichen in Suabia, and at Andreasberg in the Hartz, associated with several ores of silver, native arsenic, and galena, and other species; also at Allemont in Dauphiné, Casalla in Spain, and near Coquimbo, S. A.

If less rare, this would be a valuable ore of silver. Named from \$15, two-fold, upage,

Arsenio Silver, (Arseniksilber) from Andreasberg, is shown to be a mixture of mispickel, arsenical iron, and discrasite, (Pogg. lxxvii, 262).

DOMEYKITE, Haid. Arsenical Copper. Cuivre Arsenical, Duf. Weisskupfererz, W. Arsenikkupfer. Condurrite, Faraday.

Reniform and botryoidal; also massive and disseminated.

II.=3—3.5. Lustre metallic. Color tin-white, a slightly yellowish or iridescent tarnish. Fracture uneven. Also black and soft, soiling the fingers (*Condurrite*) when impure.

Composition.—Eu³ As²=Arsenic 28.3, copper 71.7. Analyses: 1, 2, Domeyko, (Ann. d. Mines, [4], iii, 5); 3, 4, Rammelsberg, (Pogg. lxxi, 305); 5, Blythe, (J. of Chem. Soc. i, 213):

```
1. Calabazo, Chili,
                          As 28.36 Cu 71.64=100, Domeyko.
                             23.29
                                         7070
                                                 Fe 0.52
                                                             S 3.87=98.38, Domeyko.
2. Copiapo,
                                                     0 '66, Rammelsberg.
— gangue 1 '07, Rammelsberg.
0 '25, S 2 '33, H 2 '41, C 1 '62, H 0 '44,
  Cornwall, Condurrite, 1870
                                         70.51
                             17.84
                                         70.02
                    "
                             19.51
                                         60.21
                                                            N 0.06, O 13.17=100, Blythe.
```

The Conducrite is a mixture of the Domeykite with red copper ore, and arsenous acid, or arsenite of copper. Rammelsberg treated one specimen with muriatic acid, and analyzed the soluble and insoluble portions separately, obtaining

1. Soluble, As 13:89, Cu 12:81, S 2:20, Xs 3:70, Eu 62:29, H 5:33, gangue 0:70=101:42.
2. Insoluble, 13:89
4:16, Sulphuret of Copper 10:85.

Kobell, (J. f. pr. Ch. xxxix, 204), with the same treatment of another specimen, found the composition of the soluble part. As 8.03, &u 79.00, Fe 3.47, Ĥ 9.50=100; and the insoluble, consisted of arsenic and some sulphuret of copper in grains.

Blythe concludes, as a mean of many analyses, that the arseniuret of copper contained in Condurrite consists of Arsenic 28.85, copper 71.15, which corresponds with the Domeykite. Faraday's analysis (Phil. Mag. 1827, 286) leads to the same result, or Arsenic 29.88, copper 70.11.

B.B. fuses easily, with the odor of arsenic. Not dissolved in muriatic acid. The

Conducrite affords in a tube fumes of arsenous acid and water, and with soda and

borax yields a globule of copper.

From the Calabazo mine near Coquimbo, and also from Antonio mine, Copiapo, Chili; also from the Condurrow mine near Helstone, and according to Lettsom, the Huel Druid mine at Carn Brae, near Redruth, Cornwall.

2. GALENA DIVISION.

1. GALENA GROUP.—Monometric, holohedral.

SILVER GLANCE,	Ag S.	CLAUSTHALITE,	Pb Se.
Erubescite,	(Fe, Cu) S.	Tilkerodite,	(Pb, Co) Se.
GALENA,	Pb S.	Naumannite,	Ag Se.
CUPROPLUMBITE,	(Cu, Pb) S.	Berzelianite,	€u Se.
Manganblende,	Mn S.	l'Eucairite,	(Eu, Ag) Se.
Sympoorite,	Co S.	∮Hessite,	Ag Se.
Scheererite,	$(\frac{1}{3} \text{ Ni} + \frac{3}{3} \text{ Fe}) \text{ S.}$	Altaite,	Pb Te.

2 BLENDE GROUP.—Monometric, tetrahedral.

BLENDE,

Zn S, or (Zn, Fe, Cd) S.

3. STROMEYERITE GROUP.—Trimetric.

COPPER GLANCE, Cu S.

STROMEYERITE, (Gu, Ag) S.

4. PYRRHOTINE GROUP.—Hexagonal.

	_	
Cinnabar,	Hg S.	ONOFRITE, Hg (S, Se).
MILLERITE,	Ni S.	COPPER NICKEL, R (As, Sb).
Pyrrhotine,	Fe S [+} Fe' S'].	BREITHAUPTITE, Ni Sb.
GREENOCKITE.	Cd S.	!Kaneite. Mn As.

SILVER GLANGE. Argyrose, Beud. Vitreous Silver. Sulphuret of Silver. Glaserz, Haus. Silberglanz, L. Argent Sulfure, H. Argentite, Haid.

Monometric. Observed planes O, I, 1, 2, 22. Figs. 1, 11, 14 to 19, 37, 38, 39, 47. Cleavage: dodecahedral in traces. Also reticulated, arborescent, and filiform; also amorphous.

H.=2—2.5. G.=7.196—7.365. Lustre metallic. Streak and

color blackish lead-gray; streak shining. Opaque. Fracture small subconchoidal, uneven.

Composition.—Ag S=Sulphur, 12.9, silver 87.1=100. Analysis by Klaproth, (Beit. i, 158), Sulphur 15, silver 85=100.

B.B. intumesces, and on charcoal soon affords a globule of silver. Soluble in di-

lute nitric acid, sulphur being deposited.

This important ore of silver occurs in Europe, principally at Annaberg, Joachimstahl, and other mines of the Erzgebirge, at Schemnitz and Kremnitz in Hungary, and at Freiberg. At the last place it accompanies other silver ores, in veins traversing gueiss. It is abundant also in Mexico and Peru. Found also in Cornwall.

A mass of sulphuret of silver is stated by Troost to have been found in Sparta,
Tennessee; it also occurs with native silver and copper in Northern Michigan. A
silver ore not yet analyzed, occurs, according to Jackson, with gray antimony, at

cornish, N. H.

A "silver ore" from Prince's mine, on the north shore of Lake Superior, fifteen miles west of Sturgeon Bay, afforded E. L. Seymour S 1.78, Ag 2.58, Zn 3.15, Cu 0.81, Pb 0.26, Fe 0.13, Au 0.02, gangue or rock 91.27=100. The average of three assays gave 4 per cent. of silver. Sulphuret of silver is said to occur at this mine with gray copper, vitreous copper, and argentiferous copper.

ERUBESCITE. Bornite, Haid. Variegated Copper. Purple Copper, P. Liver-colored Copper Ore. Phillipsite, Duf. Buntkupfererz, W. and L. Bunter Kupferkies, Haus. Cuivre Pyriteux Hepatique, H.

Monometric. Observed planes O, I, 1, 22. Fig. 1, 11, 14, 38, 43. Cleavage: octahedral in traces. Twins: f. 200. Imperfect

crystallizations, structure granular, strongly connected. H.=3. G.=4·4—5·003. Lustre metallic. Color between copper-red and pinchbeck-brown; speedily tarnishes. Streak pale grayish-black, and slightly shining. Fracture small conchoidal, uneven. Brittle.

Composition.—Fe S+2CuS or (Fe, Cu) S, Berzelius=Sulphur 23.7, copper 62.5, iron 13.8. 3CuS+Fe²S³, Ramm.—Sulphur 28.1, copper 55.5, iron 16.4, but mixed often with copper glance. Analyses: 1, 2, Berthier, (Ann. d. Mines, [3], iii, 48, vii, 540, 556); 3, Phillips, (Ann. Phil. 1822, 297;) 4, Brandes, (Schw. J. xxii, 354); 5—9, Plattner, (Pogg. xlvii, 351); 10, Varrentrapp, (ib); 11, Hisinger, (Afh. i Fys. iv, 362); 12, Chodnew, (Pogg. lxi, 395;) 13, Bodemann, (Pogg. lv, 115); 14, Staaf, (Ofv. K. V. Ak. Förh. 1848, 66); 15—18, C. Bechi, (Am. J. Sci. [2], xiv, 61); D. Forbes, (Jameson's J. l. 278). (Jameson's J. 1, 278).

		S	Cu	Fe
1.	Montecastelli, Tuscany,	21.4	67.2	6.8, gangue 4.0=99.4, Berthier.
2.	St. Pancrasse,	22.8	59.2	13.0, gangue 5.0=100, Berthier.
8.	Ross L, L. Killarney,	23:75	61.07	14.0, quartz 0.5=99.32, Phillips.
4.	Siberia,	21.65	61.68	12.75, " 3.5=99.53, Brandes.
5.	Sangerhausen, massive,	22.58	71.00	6.41=99.99, Plattner.
6.	Eisleben, massive,	22.65	69.73	7.54=99.91, Plattner.
7.	Woitzki, White Sea, mass.,	25.06	63-03	11.56=99.65, Plattner.
8.	Condurra M., Cornw. cryst.,	28 24	56.76	14.84=99.84, Plattner.
9.	Dalarne, massive,	25.80	56-10	17:36, Si 0:12=99:39, Plattner.
10.	"	26.98	58.20	14.85=100.03, Varrentrapp.
11.	Vestanforss, Westmannland,	24.70	63.33	11.80=99.83, Hisinger.
12.	Redruth, cryst.,	26.84	57.89	14.94, gangue 0.04=99.71, Chodnew.
13.	Bristol, Ct., massive,	25-70	62.75	11.64, quartz 0.04=100.13, Bodemn.
14.	Westmannland,	-	60:56	10.24, gangue 4.09=99.11, Stanf.
15.	Mt. Catini,	24.93	55.88	18.03=98.84, Bechi.
16.	H.	23.36	59.47	13.87, gangue 0.75 Fe 1.50=98.95, B.
17.	Miemo,	23.98	60.16	15:09=99:28, Bechi.
	Ferriccio,	2470	60.01	15.89=100.60, Bechi.
19.	Espedal, Norway,	24.49	59-71	11.12, Mn 0.1, Si 3.88=99.15, Forbes
				-G.=4·432

B.B. blackens and becomes red on cooling; at a higher temperature fuses to a globule, attracted by the magnet. Mostly dissolved by nitric acid.

Occurs with other copper ores. Crystalline varieties are found in Cornwall, and

mostly in the mines of Tincroft and Dolcoath near Redruth, where it is called by the miners "horse flesh-ore." Other foreign localities of massive varieties are at Ross Island in Killarney, in Ireland, in cupriferous shale in the Mansfeld district,

Germany, and in Norway, Siberia, Silesia, and the Bannat.


Massive varieties of erubescite are found in the United States at Mahoopeny, near Wilkesbarre, Penn., and in other parts of the same State, in cupriferous shale, associated in small quantities with vitreous copper; also in granite at Chesterfield, Mass., also in New Jersey. At the copper mine Bristol, Conn., it is abundant, and occurs in fine crystallizations, (f. 1, 14, 43, and 48 with planes O). At Cheshire, it is net with in cubes, along with heavy spar, malachite, and vitreous copper.

This species is a valuable ore of copper. Its name alludes to its liability to tar-

nish, thus receiving a reddish hue.

GALENA. Sulphuret of Lead. Blue Lead. Bleiglanz. Blau-Bleierz, W. Plomb Sulfuré, H.

Monometric. Figs. 1, 11, 14 to 19, 47 with planes 1. Cleavage, cubic, perfect and easily obtained. Twins, like f. 200; the same



kind of composition repeated, (f. 272A), flattened parallel to 1. Also reticulated, tabular, and coarse or fine granular, sometimes impalpable; occasionally fibrous.

H = 2.5 - 2.75. G = 7.25 - 7.7. Lustre metallic. Color and weak pure lead-gray. Surface of crystals occasionally tarnished. Fracture flat subconchoidal, or even. Frangible.

Composition.—Pb S=Sulphur 13.4, lead 86.6; contains also at times some selenium, (ore from Fablun, Berz.), zinc or sulphuret of zinc, silver, antimony, copper: and platinum is reported to have been found in a galena from the Department of Charente, France. Analyses: 1, Thomson, (Phil. Jour. 1829, 256); 2, 3, Lerch, (Ann. d. Ch. u. Pharm. xlv, 325):

1. Durham,

S 13·02 Pb 85·13 Fe 0·50=98·65, Thomson. 14·41 81·80 Zn 3·59=99·80, L. PbS to Zn S as 6:1. 2. Przibram, G.=7·252, 14·41 3. "G.=7·324, 14·18 2·18=99·97, L. PbS to ZnS as 12:1. 83.61

The silver present is detected easily by cupellation. The galena of the Hartz affords 03 to 05 per cent. of silver; the English 02 to 03; that of Leadhills, Scotland, 03 to 06; of Monroe, Ct., 3 per cent.; Eaton, N. H., 0-1, C. T. Jackson; Shelburne, N. H., 0-15; Arkansas, 003 to 05. Silliman, Jr., 44-71 oz. to the ton, Mather; Middletown, Ct., 40-70 oz. to the ton.

The following from Tuscany, contain antimony and silver, (C. Bechi, Am. Jour., Sei. [2], xiv, 60):

	S	Рb	Sb	Fe	Cu	Zn	Ag
1. Bottino,	12.840	80.700	3.307	1.877	0.440	0.024	0.325 = 99.013
2. "	15.245	78.238	4.431	1.828	trace.		0.485=100.227
3 . "	15.503	78.284	2.452	2.811			0.560 = 99.610
4. Argentiera,	16.780	72.440	4.308	1.855	4.251		0.650=100.289
5. "	15.62	72.90	577	1.77	1.11	1.33	0.72 = 98.22

No. 5 is the Jargionite of M. Bechi; it is near the Bleischweif of the Germans, and may be identical with Steinmannite; it occurs in octahedrons; G .= 6.932 B.B. on charcoal decrepitates unless heated with caution, fuses, gives off sulphur,

and at last affords a globule of pure lead.

Galena occurs in beds and veins, both in crystalline and uncrystalline rocks. It

Galena occurs in beds and veins, both in crystalline and uncrystalline rocks. It is often associated with blende, iron, and copper pyrites, the carbonate and other lead ores, and occurs in a gangue of heavy spar, cale spar or quartz.

At Freiberg in Saxony, it occupies veins in gneiss; in Spain in the granite hills of Linares, and also in Catalonia, Grenada, and elsewhere; at Clausthal and Neudorf in the Hartz, and at Przibram in Bohemia, it forms veins in clay slate; in Styria it occurs in the same kind of rock in beds; at Sala in Sweden, it forms veins in granular limestone; through the gray-wacke of Leadhills and the killas of Cornwall are disseminated voins of this ore; and in mountain limestone occur. of Cornwall, are disseminated veins of this ore; and in mountain limestone occur the rich repositories of Derbyshire, Cumberland, and the northern districts of England, as also those of Bleiberg, and the neighboring localities of Carinthia. In the Isle of Man, cubes 12 inches across occur. In the English mines it is associated with calcareous spar, pearl spar, fluor spar, heavy spar, witherite, calamine, and blende. Other localities are Joachimstahl, where it is worked principally for the silver; in Bohemia southwest of Prague; in the Daouria mountains, Siberia; in

Algeria; near Cape of Good Hope; in Australia.

Extensive deposits of this ore in the United States exist in Missouri, Illinois, Iowa, and Wisconsin. The ore occurs in what has been called "cliff" limestone, associated with blende, calamine, ("dry-bone" of the miners), carbonate and sulphate of lime, pyrites, and often an ore of copper and cobalt. The mines of Missouri were discovered in 1720, by Francis Renault and M. la Motte; they are situated in the counties of Washington, Jefferson, and Madison. The lead region of Wisconsin, according to D. D. Owen, comprises 62 townships in Wisconsin, 8 in Iowa, and 10 in Illinois, being 87 miles from east to west, and 54 miles from north to south. Throughout this region there is scarcely a square mile in which traces of lead may not be found. The occurrence of cale spar in the soil, or sink holes in lines, are considered indications of lead. The diggings seldom exceed 25 or 30 feet in depth. From a single spot, not exceeding 50 yards square, 3,000,000 lbs. of ore have been

raised. The mines of the Upper Mississippi afforded in 1847 about 77,000 pigs of 70 pounds, and in 1850, 570,000; those of Missouri 125,000 to 150,000 pigs.

Galena occurs also at Cave-in-Rock, in Illinois, associated with fluor spar. Veins at Rossie, in St. Lawrence Co., N. Y., traverse, nearly perpendicularly, the gneiss of the region, and vary from one to three or four feet in width. Crystals often very large, (like f. 272, without i). It occurs with calcite, iron and copper pyrites, and some blende and celestine. Near Wurtzboro, Sullivan Co., a large vein occurs in millblende and celestine. Near Wurtzboro, Sullivan Co., a large vein occurs in milstone grit; it is associated with blende, iron and copper pyrites. The Ancram lead mines, Columbia Co., have afforded considerable lead. In Maine, veins of considerable extent exist at Lubec, where the ore is associated with copper pyrites and blende; also less extensively at Blue Hill Bay, Bingham, and Parsonsfield; in New Hampshire at Eaton, with blende and copper pyrites, and also at Haverhill, Bath, and Tamworth; in Vermont at Thetford; in Connecticut at Middletown, in a vein in argillite, massive and crystalline. Southampton, Leverett, and Sterling, Mass, afford small quantities of galena; also Austin's mines in Wythe Co., Walton's gold mine in Louise Co. and other places in Virginia; at Brown's Creek, and at Havering at Brown's Creek, and at the Brown's Creek, and at the Brown's Creek, and at th mine in Louisa Co., and other places in Virginia; at Brown's Creek, and at Haysboro, near Nashville, it occurs with blende and heavy spar; in the region of Chocolate river and elsewhere, and Lake Superior copper districts.

Argentiferous galena occurs at Monroe and Middletown, Ct.; Bath, Haverhill, Eaton, Shelburne, and other places in New Hampshire, (C. T. Jackson). Galena in cubes is sometimes a furnace product, (Hausmann).

ALTERED FORMS.—Minium, anglesite, cerusite, pyromorphite, wulfenite, gray copper, dialogite, quartz, limonite, pyrites, calamine, occur as pseudomorphs after galena, partly from alteration and partly through removal and substitution. A change to the carbonate (cerusite) with the setting free of sulphur, is the most common. The supersulphuretted lead of Johnston is galena mixed with free sulphur. He obtained Pb S 90.38, S 8.71.

STEINMANNITE, Zippe.

Described as occuring at Przibram in octahedrons with cubic cleavage and massive; H.=2.5; G.=6.833, Zippe; color lead gray.

On charcoal gives fumes of sulphurous acid and antimony, and finally a globule of lead containing some silver.

CUPROPLUMBITE, Breit. Kupferbleiglanz.

Tesseral. Occurs massive granular; cleavage cubic. H.=2.5. G.=6.408-6.428. Lustre metallic. Color blackish lead-gray. Streak black. Rather sectile and brittle.

Composition.—CuS+2PbS, or (Gu, Pb) S=Sulphur 15:1, lead 65:0 copper 19:9. Analysis by Plattner, (Pogg. lxi, 671):

S (loss) 15·1 Cu 19.5 Silver 0.5=100.

B.B. on charcoal surrounds the assay with an areola of oxyd of lead and sulphate of lead; with soda affords a globule of metal. In an open tube fuses and gives off sulphurous fumes. From Chili,

MANGANBLENDE, Breit. Sulphuret of Manganese, P. Alabandine, Beud. Schwarzerz, Haus. Manganglanz, L. Manganése Sulfuré, H.

Monometric. In cubes and octahedrons. Cleavage: cubic, per-

fect. Usually granularly massive. H.=3.5—4. G.=3.95—4.014. Lustre submetallic. Color iron-black, tarnished brown on exposure. Streak green. Fracture uneven.

Composition.—MnS=Sulphur 36.7, manganese 63.3. Analysis by Arfvedson, (K. V. Ac. H. 1822):

Sulphur 37:90, Manganese 62·10=100.

A specimen from Siebenburg afforded Klaproth, (Beit. iii, 35), Mn 82, S 11, C 5= 98; and in another Vauquelin found, Mn 85, S 15=100. In one from Mexico, Del Rio found, S 39.0, Mn 54.5, Si 6.5=100.

B.B. on charcoal fuses on the thinnest edges. When pulverized and thrown into muriatic acid, or dilute sulphuric acid, sulphuretted hydrogen is evolved.

Manganblende occurs in veins in the gold mines of Nagyag in Transylvania, associated with tellurium, carbonate of manganese, and quartz.

SYEPOORITE, Nicol. Sulphuret of Cobalt, Kobaltsulfuret, Ramm, Graucobalterz.

Massive, disseminated in grains or veins.

G.=5.45. Color steel-gray, inclining to yellow.

Composition.—Co S=Sulphur 35.2, cobalt 64.8. Analysis by Middleton, (Phil. Mag. [3], xxviii, 352):

Sulphur 85.36, Cobalt 64.64=100.

From Syepoor, near Rajpootanah in North West India, where it occurs in ancient schists with magnetic pyrites. It is employed by the Indian jewelers to give a rose color to gold.

SULPHURET OF IRON AND NICKEL. Eisennickelkies, Scheerer.

Monometric. Cleavage octahedral. Massive, granular. H.=3.5-4. G.=4.6. Color light bronze yellow. Streak light bronze brown. Not magnetic.

Composition.—(1 Ni+1 Fe) S=Sulphur 36 0, iron 41 9, nickel 22 1=100. Analysis by Scheerer, (Pogg. lviii, 815):

> Sulphur 36.86, Iron 40.86, Nickel 22.28.

Occurs with copper pyrites in a hornblende rock near Lillehammer in Southern Norway. The ore is valuable for the extraction of nickel, this metal being now in great demand. An impure variety, slightly mixed with magnetite, is found at inverary, in Argyleshire, Scotland.

CLAUSTHALITE. Seleniuret of Lead. Seleniet of Lead. Selenblei. Plomb Seleniure, Levy. Tilkerodite, Haid. Raphanosmite, Kob. Zorgite, B. and M.

Monometric. Occurs commonly in fine granular masses; some specimens foliated. Cleavage cubic.

II.=2.5—3. G.=7—8.8. Lustre metallic. Color lead-gray, somewhat bluish; cupreous varieties yellowish. Streak darker. Opaque. Fracture granular and shining. Rather sectile.

Composition.—Pb Se=Selenium 27:6, lead 72:4, with part of the lead often replaced by silver. Analyses: 1, H. Rose, (Pogg. ii, 415, iii, 281); 2, Stromeyer. (Pogg. ii, 403); 3, Rammelsberg, (2d Supp. 127); 4, 5, 6, H. Rose, (Pogg. iii, 288): 7, 8, Kersten, (Pogg. xlvi, 265):

```
1. Tilkerode,
                                                 27:59 71:81, Rose.
                                                 28:11 70:98 Co 0:83=99:92, Stromeyer.
2. Clausthal,
8. Tilkerode, 26.52 60.15 Ag 11.67=98.34, Rammelsberg.
4. Clausthal, (selenkobaltblei), 31.42 63.92 Co 3.14, Fe 0.45=98.93, Rose.

Tilkerode, (selenkobaltblei), 31.42 63.92 Co 3.14, Fe 0.45=98.93, Rose.

    Tilkerode, (selenbleikupfer), 34.26. 47.43 Cu. 15.15 Ag. 1.29 Fe and Pb.2.08=100.51.
    "(selenkupferblei), 29.96. 59.67. 7.86 Fe 0.33, Fe and Pb.0.44, undecomp.

                                                                                                        1:00=99:26, Rose.
                                                                        8.02, Ag 0.05 Fe 2.00, S trace, quartz
7. Glasbach.
                                                 30.00 53.74
                                                                                                     4.5=98.31, Kersten.
                                                                                      0.07, Fe and S trace, quartz 2.06=99.35, Kersten.
                                                29:35 63:82
                                                                       4.00
```

In No. 3 part of the lead is replaced by silver=(Pb, Ag) Se.

Nos. 5 to 8 contain copper, and may be distinct species as they have been considered; but it may be more correct to view them as varieties of Clausthalite, in

which copper replaces part of the lead.

No. 4 is Tilkerodite, Haid.; 5, 6, Raphanosmite, Kobell; 4, 5, 6, are called Zorgite by Brooke and Miller.

No. 5 gives the formula, Pb Se+Cu Se; G.=56.

Nos. 6, 7=2 PbSe+Cu Se; G.=6.9-7.04.

No. 8=4 Pb Se+Cu Se; G.=7:4-7:45. Color dark lead-gray; powder grayish black.

No. 4 corresponds to 6 Pb Se+Co Se2.

B.B. in addition to the usual phenomena arising from the presence of lead, it gives off the odor of horseradish, and deposits on the charcoal a reddish brown substance. Heated in a glass tube closed at one end, the selenium almost immediately sublimes, forming a red ring within the tube, and on heating the tube to redness, the ore fuses and the red ring partially disappears, and a white crystalline deposit remains. The ores containing copper, give a copper reaction.

Clausthalite much resembles a granular galena; but its color is somewhat pecu-

liar in its slight tinge of blue. It occurs massive in a vein of hematite, near Harr-

gerode in the Hartz, at Clausthal, Tilkerode, Zorge, and Lehrbach; and at Reinsberg

near Freiberg, in Saxony.

Lehrbachite, B and M.—Selenid of Mercury and Lead, (Selenquecksilberblei). From Tilkerode and Lehrbach, and may be a mechanical mixture of Clausthalite and Selenid of Mercury. It is described as having the structure and color of Clausthalite. G.—7.3. Analyses by Rose:

Se 24.97 Pb 55.84 Hg 16.94=97.75. 27.98 27:33 44.69=100.

B.B. gives the odor of selenium and affords mercury with soda.

NAUMANNITE, Haid. Selensilber, Rose. Silberphyllinglanz, Breit.

Monometric; in cubes. Cleavage: cubic, perfect. Also massive, granular, and in thin plates.

H.=2.5. G.=8.0. Lustre metallic, splendent. Color and streak iron-black.

Composition.—Ag Se=Selenium 26.8, silver 73.2. Analysis by G. Rose, (Pogg. xiv, 471):

> Selenium 29.53. Silver 65.56, Lead 4.91=100.

B.B. on charcoal it melts easily in the outer flame; in the inner, with some intumescence. With sods and borax it yields a bead of silver.

Occurs at Tilkerode in the Hartz.

According to Del Rio, another selenid of silver occurs at Tasco in Mexico, crystallized in hexagonal tables.

The Silberphyllinglanz, according to Plattner, is a mixture of selensilver and selenmolybdena, containing a little gold. H.=1-2. G.=5.8-5.9. Color dark gray. Foliated, with one perfect cleavage. From Deutsch-Pilsen, Hungary, in gneiss.

BERZELIANITE. Selenid of Copper. Seleniuret of Copper. Selenkupfer, M. Cuivre Sélénié, H. Berzeline, Beud.

In thin dendritic crusts. Soft. Lustre metallic. Color silverwhite. Streak shining.

Composition .- Eu Se=Selenium 38.4, copper 61.6. Analysis by Berzelius, (Afhandl. vi, 42):

> Selenium 40, Copper 64.

B.B. the odor of selenium and fuses to a gray bead. With soda slowly reduced. Occurs at Skrikerum in Sweden, and also near Lehrbach in the Hartz. Beudant gave the name Berzeline to this species, which, as it has other applications in the science, we have changed to another form, as above.

EUCAIRITE, Berz. Seleniuret of Silver and Copper, P. Argentiferous Seleniet of Copper. Selenkupfersilber. Cuivre Sélénié Argental, H. Eukairit.

Massive; in black metallic films, staining the calcareous spar in which it is contained.

Soft; easily cut by the knife. Lustre metallic. Color between silver-white and lead-gray. Streak shining.

Composition.—Eu Se+Ag Se=(Eu, Ag) Se=Selenium 31.6, copper 25.3, silver 43.1. Analysis by Berzelius, (Afhandl. vi, 42):

gangue 8.90==96.88. Silver 38.93, Selenium 26:00, Copper, 23:05,

B.B. gives copious fumes of selenium, and on charcoal fuses readily to a gray metallic globule, leaving a bead of selenid of silver. With borax, a copper reaction.

Dissolves in boiling nitric acid.

It has been found only in small quantities in the Skrikerum copper mine in Smaoland, Sweden, in a kind of rock, imbedded in calcareous spar. It was discovered and analyzed by Berzelius, and named from so and sauses, opportunely, because the mineral was found soon after the discovery of the metal selenium.

HESSITE, Fröbel. Telluric Silver. Petzite, Haid. Bitelluret of Silver, Thomson. Tellursilber of the Germans.

Monometric? In coarse-grained masses, and granular. H.=2-3.5. G.=8.3-8.9. Lustre metallic. Color between lead-gray and steel-gray. Slightly malleable.

Composition.—Ag Te=Tellurium 37.2, silver 62.8 Analyses: 1, 2, G. Rose, (Pogg. zviii, 64); 3, 4, Petz, (Pogg. lvii, 467); 5, Rammelsberg, (4th Supp. 220):

```
    Savodinsky, Altai, Te 36-96 Ag 62-42 Fe 0-24=99-62, Rose.

                        86.89
                                   62.32
                                            0.50=99.71, Rose.
```

61.55, Au 0.69, Fe, Pb, S, trace=100, Petz. 46.76 18.26 " =100, Petz.

a. Nagyag, G.=8·31-8·45, 37·76 4. "G.=8·72-8·83, 34·98 5. Retzbanya, 27·96 5. Retzbanya, 54.67, Foreign substances 15.25-97.88, Ramm.

No. 4 is the Petzite of Haidinger, (Tellurgoldeilber of Hausmann); owing to the gold, the specific gravity is high.

B.B. on charcoal fuses to a black globule, which on cooling, after the action of the reducing flame, presents points or dendrites of silver on its surface. When heated in a glass tube it melts and gives a yellow color to the glass. Fused with carbonate of soda a globule of pure silver is obtained.

It occurs in the mine of Savodinski, about forty wersts from the rich silver mine of Siranowski, in Siberia, in a talcose rock, with iron pyrites, black blende, and copper pyrites. Specimens in the museum of Barnaul, on the Ob, are a cubic foot in size.

ALTAITE, Haid. Tellurid of Lead. Tellurblei.

Monometric. Usually massive; rarely in cubes. Cleavage: cubic.

H.=3-3.5 G.=8.159. Lustre metallic. Color tin-white, resembling that of native antimony, with a yellow tarnish. Sectile.

Composition .- Pb Te=Tellurium 38.3, lead 61.7. Analysis by G. Rose, (Pogg. **zvi**ii, 68):

> Tellurium 38.37. Silver 1:28. Lead 60:35.

BB. volatilizes in the reducing flame, excepting a minute bead of silver. ('olors the flame blue. Soluble in nitric acid.

Occurs at Savodinsky, near Barnaoul, in the Altai, with telluric silver.

GRUNAUITE, Nicol. Saynite, Nobell. Bismuth Nickel. Nickelwismuthglanz

Monometric. Figs. 11, 15, 16. Cleavage octahedral.

H.=4.5. (4.=5.13. Lustre metallic. Color light steel-gray to silver-white, often yellowish or grayish through tarnish. Brittle.

Composition.—Analyses: 1, Kobell, (J. f. pr. Chem. vi, 332): 2, 3, Schnabel. (Ramm. 4th Suppl. 164):


	s	Bi	Ni	Fe	Co	Cu	Pb
1.	38.46	14.11	40.65	3.48	0.28	1.68	1.58==100.24.
2.	31.99	10.49	22.08	5.22	11.24	11.59	7·11=100, Schnabel.
3.	88.10	10.41	22.78	6.06	11.78	11.56	4:86=100. Schnabel.

B.B. fuses to a gray brittle magnetic globule, coloring the charcoal greenish yellow. Dissolves in nitric acid, excepting the sulphur.

Found at Grünau, in Sayn Altenkirchen, with quartz and copper pyrites.

BLENDE. Sulphuret of Zinc. Black Jack. Zinc Sulfuré, H. Sphalerite, Gl. Cleiophane, Nuttal. Marasmolite, Shepard. Przibramite, Huot.

Monometric: tetrahedral. Observed planes, $O, I, 1, 2, 33, i\frac{3}{2}$. Figs. 14, 53 to 58. Cleavage: dodecahedral, highly perfect. Twins: face of composition 1, as in f. 273A, of which f. 273 is the simple form. Also botryoidal, and other imitative shapes; structure columnar impalpable; also massive, compact.



H.=3·5—4. G.=3·9—4·2. 4·063, white, New Jersey. Lustre resinous to adamantine. Color brown, yellow, black, red, green; white or yellow when pure. Streak white—reddish-brown. Transparent—translucent. Fracture conchoidal. Brittle.

Composition.—Zn S=Sulphur 33, zinc 67. Analyses: 1, Arfvedson, (K. V. Ac. H. 1822, 438, and Pogg. i, 62); 2, Löwe, (Pogg. xxxviii, 161); 3, Kersten, (Pogg. kxiii, 132); 4, Scheerer, (Pogg. kxv,300); 5, 6, 7, Jackson, (Geol. Rep. N. Hampshire, 208); 10, T. H. Henry, (Phil. Mag. [4], i, 23); 11, 12, C. Bechi, (Am. J. Sci. [2], xiv, 61); 13. Lecanu, (J. de Pharm. ix, 457); 14, Berthier; 15, 16, Boussingault, (Pogg. xvii, 399):

		S	Zn	Fe	Cd
1.		33.66	66.34		——=100, Arfvedson.
2.	Przibram, fibrous,	33.15	61.40	22.9	1.50=98.34, Löwe. [99.16, K.
3.	Carinthia, Raibel, rh. yw.	32.10	64.22	1.32	trace, Sb and Pb 0.72, H 0.80=
4.	Christiania, fibrous,	3373	53.17	11.79	-, Mn 0 74, Cu trace 99 43, Sch.
5.	Eaton, N. H. ywh. bn.,	33.22	63.62	3.10	0.6 including loss=100, Jackson.
6.	Shelburne, N. H.	32.6	52.0	10.0	3.2, Mn 1.3=99.1, Jackson.
7.	Lyman, N. H.	33.4	55.6	8.4	2·3==99·7, Jackson.
10.	White, N. Jersey,	32.22	67:46		trace, 99.68, Henry.
11.	Marmatite, Tuscany,	32.12	50.90	11:44	1 23, Fe S ² 0 75=96 44, Bechi.
12	" "	33.65	48.11	16.53	tr., Cu tr.=97 99, Bechi.

```
ZnS FeS

13. Charente, 82.76 13.71=96.47, Lecanu.

14. England, 91.8 6.4=98.2, Berthier.

15. Marmatite, Marmato, 77.5 22.5=100, Boussingault.

16. " 76.8 23.2=100. "
```

Part of the zinc, as shown by the analyses, is often replaced by iron and cadmium. The Marmatite (anal. 15, 16) affords the formula 3ZnS+FeS=77 Zn S and 23 FeS; (anal. 11, 12), 4 Zn S+FeS. Marasmolite of Shepard (Am. J. Sci. [2], xiv, 210) is a marmatite from Middletown, Ct., partially decomposed and containing some free sulphur. Przibramite is cadmiferous blende.

B.B. infusible both alone and with borax, or only the thinnest edges rounded. By a strong heat in the outer flame on charcoal vapors of zinc are evolved, which cost the charcoal. Dissolves in nitric acid, during which sulphuretted hydrogen is disengued. Some specimens phosphoreace when struck with a steel or by friction.

engaged. Some specimens phosphoresce when struck with a steel or by friction.

Blende occurs in both crystalline and sedimentary rocks, and is usually associated with galena; also with heavy spar, copper pyrites, fluor, spathic iron, and frequently in silver mines.

Derbyshire, Cumberland, and Cornwall, afford the black varieties; also Transylvania, Hungary, and the Hartz. Sahla in Sweden, Ratieborzitz in Bohemia, and many Saxon localities, afford splendid black and brown crystals. A variety having a divergent fibrous structure and presenting botryoidal forms, is met with in Cornwall; at Raibel; and at Geroldseck in Baden.

Blende abounds with the lead ore of Missouri, Wisconsin, Iowa, and Illinois. In New York, Sullivan Co., near Wurtzboro', it constitutes a large part of a lead vein in millstone grit, and is occasionally in octahedrons; in St. Lawrence Co., brown blende occurs at Cooper's falls, in a vein of carbonate of lime; at Mineral Point with galena, and in Fowler, on the farm of Mr. Belmont, in a vein with iron and copper pyrites traversing serpentine; at the Ancram lead mine in Columbia Co., of yellow and brown colors; in limestone at Lockport, in honey and wax-yellow crystals often transparent; with galena on Flat Creek, two miles southwest of Spraker's Basin. In Massachusetts, at Sterling of a cherry-red color, with galena; also yellowish brown at the Southampton lead mine; at Hatfield with galena. In New Hampshire at the Eaton lead mine; at Warren, a large vein of black blende. In Maine it occurs at the Lubee lead mines; also at Bingham, Dexter, and Parsonsfield. In Connecticut, yellowish-green, at Brookfield; at Berlin of a yellow color; brownish-black at Roxbury, and yellowish-brown at Lane's mine, Monroe; a white blende (Cleiophane of Nuttall) occurs at Franklin, N. Jersey. In Pennsylvania at the Perkionen lead mine. In Virginia at Walton's gold mine, Louisa Co., and more abundantly at Austin's lead mines, Wythe Co., where it occurs crystallized, or in radiated crystallizations; at Prince vein, Lake Superior, abundant; near Rosiclare, Illinois, with galena and calcite; in Tennessee, at Haysboro', near Nashville.

The Leber-blende (hepatic-blende) of Breithaupt, (J. f. pr. Ch. xv, 321), contains carbon, and is considered by Berzelius common zinc-blende, impure with a mineral resin, or some other mineral with carbon in its composition.

Altered Forms.—Blende by oxydation changes to zinc vitriol. Calamine (2n² Si+1¼ H), Smithsonite, (2n C), and Limonite occur as pseudomorphs. The sulphate is decomposed by bicarbonate of lime, producing Smithsonite; and the alkaline silicates in solution, acting on the sulphate or carbonate, afford Silicate of zinc.

COPPER-GLANCE. Chalkosine, Bend. Vitreous Copper. Sulphuret of Copper. Redruthite, Nicol. Glance Copper. Kupferglas, W. Kupferglanz, Haus. and L. Cuivre Sulfuré, II.

```
Trimetric. I: I=119^{\circ} 35', \ \theta: 17=120^{\circ} 57'; \ a:b:c=1\cdot6676: 1:1\cdot7176.
\theta: \frac{1}{2}=147^{\circ} 16', \qquad \theta: \frac{1}{2}=147^{\circ} 6', \qquad \widetilde{i3}: \widetilde{i3}=120^{\circ} 25', \\ \theta: \frac{1}{2}=136^{\circ} 2\frac{1}{2}', \qquad \theta: 27=117^{\circ} 16', \qquad 1:1 \text{ (mac.)}=126^{\circ} 56\frac{1}{2}', \\ \theta: 1=117^{\circ} 24', \qquad 27:27=125^{\circ} 28', \qquad 1:1 \text{ (brach.)}=79^{\circ} 48\frac{1}{2}'.
```


Cleavage: I, indistinct. Twins: (1,) composition-face I, producing hexagonal, or stellate forms, (f. 276B); (2,) composition-face $\frac{1}{2}$, a


cruciform twin, (f. 276A), crossing at angles of 92° 5' and 87° 55'; (3,) composition-face 2i (f. 276B) a cruciform twin, angle of intersection 125° 28'. Also massive, structure granular or compact and impalpable.

H.=2.5—3. G.=5.5—5.8; 5.7022, Thomson. Lustre metallic. Color and streak blackish leadgray; often tarnished blue or green; streak sometimes shining. Fracture conchoidal. Sectile.


Composition.—Cu S_Sulphur 20.2, copper 79.8. Analyses: 1, Ullmann, (Syst. tab. Uebers. 243); 2, 3, Scheerer, (Pogg. lxv, 290); 4, Schnabel, (Ramm. 4th Supp. 121); 5, C. Bechi, (Am. J. Sci. [2], xvi, 61); 6, Wilczynsky, (Ramnelsberg's 5th Suppl., 151):











276A

Bristol, Ct.

Bristol, Ct.

Bristol, Ct.

79.50 0.75, Si 1.00=100.25, Ullmann. Siegen, 2. Tellemark, Norway, G.=5.795, 20.43 77.76 0.91=99.10, Scheerer. G = 5.521, 20.3679.12 0.28=99.76, Scheerer. 1.26, Si 2.00=99.49, Schnabel. 4. Siegen, massive, 74.7321:50 76.54 5. Mt. Catini, 20:50 175=9879, Bechi. 21.81 7471 6. Chili. 3.33=99.85, Wilczynsky.

Scheerer infers from the structure of the specimens employed for his second anal-Jus above, that the crystallization was monometric, and therefore that this sulphuret of copper is dimorphous. Hany erroneously made the crystallization heragonal.

B.B. in the outer flame melts, gives out fumes of sulphur, and emits glowing drops with a noise, coloring the flame at the same time blue. In the inner flame becomes covered with a coating and does not melt. On charcoal the sulphur is driven off, and a globule of copper remains. In heated nitric acid forms a green solution, and the sulphur is precipitated.

Cornwall affords splendid crystals where it occurs in veins and beds with other ores of copper. It occurs also at Fassnetburn in Haddingtonshire, in Ayrshire, and in Fair Island, Scotland. The compact and massive varieties occur in Siberia, Hesse,

Saxony, the Bannat, &c.

In the United States, compact varieties occur in the red sandstone formation at Simsbury and Cheshire, Conn.; also at Schuyler's mines, N. J. Bristol, Conn., affords large and brilliant crystals, f. 276, 276A, 276B; fig. 276B a crystal with its strice and irregularities, compounded by two different methods. Another crystals are compounded by two different methods. tal has a small octahedral plane situated obliquely upon the intersection of 1, 1, and adjoining the brachydiagonal section, which is probably the plane 32. 27: 27 in the Bristol crystals=125° 43'.

In Virginia, in the United States copper mine district, Blue Ridge, Orange Co. Between Newmarket and Taneytown, Maryland, east of the Monocacey, with copper

The argent en epis or cuirre spiciforme of Hauy, which is merely vegetable matter impregnated with this ore, occurs at Frankenberg in Hessia, and also Mahoopeny,

This species, if \$1 be taken as 17, is closely homoomorphous with discrasite and aragonite.

ALTERED FORMS.—Copper pyrites, Erubescite, Black copper, constitute pseudo-

Cu S'), making it a compound of 1 of copper glance and 3 of covelline.

STROMEYERITE, Haid. Argentiferous Sulphuret of Copper. Cupreous Sulphuret of Silver. Sulphuret of Silver and Copper. Silberkupferglanz of the Germana Cuivre Sulfuré Argentifère.

Trimetric: isomorphous with Copper glance. $I: I=119^{\circ}$ 35'. Observed planes $O, ii, \frac{1}{4}i, \frac{1}{4}$; $O: \frac{1}{4}=154^{\circ}$ 16', $O: \frac{1}{4}i=155^{\circ}$ 7'. Also massive, compact.

II.=2.5—3. G.=6.2—6.3. Lustre metallic. Color dark steelgray. Streak shining. Fracture subconchoidal. Sectile.

Composition.—(eu, Ag) 8, or eu S+Ag S=Sulphur 15.8, silver 53.1, copper 31.1 Analyses: 1, Stromeyer, (Schw. J. xix, 325); 2, Sander, (Pogg. xl, 313); 3-7, Do meyko, (Ann. d. Mines [4], iii, 9):

			ĸ	Ag	Cu	Fe
1. Se	hlangenb	erg, Siberia,	15.782	52 272	30.478	0:333=98:875, Stromeyer.
2. Rt	idelstadt,	Silesia,	15.92	52.71	80.92	0·24=99·82, Sander.
3. S.	Pedro, ('l	hili.	20.79	2.96	75.21	0.74=100, Domeyko.
4. Ca	temo,	**	21:41	12:08	63:98	2·53=100, Domeyko.
5.	"	44	20.53	16.28	60.58	2:31=100, Domeyko.
6.	"	"	19.93	24.04	58.94	2.09=100, Domeyko.
7. 8.	Pedro,	"	17.83	2879	53:38	=100, Domeyko.

B.B. fuses easily to a gray metallic globule, which is a little malleable; with the fluxes gives the reaction of copper, and on a cupel with lead affords silver. Dissolves in nitric acid, affording sulphur. The blue solution, obtained with nitric acid, affords indications of copper when a plate of iron is dipped into it, and also

precipitates silver upon an immersed copper plate.


Found associated with copper pyrites at Schlangenberg, near Kolyvan in Siberia; at Rudelstadt, Silesia; also in Chili. A variety has been observed at Combavalla, in Peru, which contains some iron. It was first described and recognized as a distinct species by Stromeyer.


CINNABAR. Sulphuret of Mercury. Zinnober, Mercurblende of the Germans. Quecksilber Lebererz, W. Stinkzinnober Lebererz, Haus. Corallinerz. Mercure Sulfure, H. Kirpseapis, Theoph. c. 103. Appior, Dioscor. V. c. 109, 110. Minium. Vitrue., Plin.

Rhombohedral. $R: R=92^{\circ} 36', R: O=127^{\circ} 6'; a=1.1448.$ Observed planes: rhombohedrons, $\frac{1}{8}$, $\frac{1}{4}$, $\frac{3}{8}$, $\frac{2}{5}$, $\frac{1}{2}$, $\frac{3}{4}$, $\frac{4}{8}$, $\frac{4}{4}$, $\frac{4}{3}$, sometimes forming superficial coatings.

Cleavage: I, very perfect. Twins: composition face O. H.=2-2.5. G.=8.998, a cleavable va-

H.=2-2.5. G.=8.998, a cleavable variety from Neumarktel. Lustre adamantine, inclining to metallic when dark colored, and to dull in friable varieties. Color cochineal-red, often inclining to brownish-red and lead-gray. Streak scarlet, subtransparent, opaque. Fracture subconchoidal, uneven. Sectile.





B.B. in a matrass wholly sublimes; and with soda yields mercury, sulphurous

The hepatic cinnabar or liver ore is an impure variety, sometimes affording a brownish streak; it is occasionally slaty, though commonly granular or impalpable in structure.

Cinnabar occurs in beds in slate rocks, and rarely in granite or porphyry. It has been observed in veins, with ores of iron.

Good crystals occur in the coal formations of Moschellandsberg and Wolfstein in the Palatinate; also in Japan, Mexico, and Brazil. The most important European beds of this ore are at Almaden in Spain, and at Idria in Carniola, where it is usually massive. It occurs at Richenau in Upper Carinthia; in beds traversing gneiss at Dunbrawa in Transylvania; in graywacke at Windisch Kappel in Carinthia; at Neumarktel in Carniola; at Ripa in Tuscany; at Schemnitz in Hungary; in the Urals and Altai; in China abundantly, and in Japan; at San Onofre in Mexico; at Huanca Velica in Southern Peru, abundant; in the Province of Coquimbo at Guallilinga and Punitaqui; and forming extensive mines in California. The California beds occur at New Almaden, in a mountain to the south of San José, between the Bay of Francisco and Monterey. This ore is very abundant, and of easy access. The variety coralliners, from Idria, has a curved lamellar structure. This ore is the source of the mercury of commerce, from which it is obtained by

This ore is the source of the mercury of commerce, from which it is obtained by sublimation. When pure it is identical with the manufactured vermillion of commerce.

The above figure is from an elaborate paper by Schabus, Wien. Akad. vi, 63.

MILLERITE, Haid. Capillary Pyrites. Sulphuret of Nickel. Haarkies, Schwefelnickel. Nickel Sulfuré, Levy. Nickel Natif, H.

Rhombohedral. $R: R=144^{\circ}$ 8', Miller; a=0.32955. Observed planes: rhombohedral, $R, -1, \frac{1}{2}, -\frac{1}{2}, -3$; prismatic, $I, i2, i\frac{3}{2}$; R: I=

110° 50′, I: -3=138° 47′, $-\frac{1}{2}: -\frac{1}{2}=161°$ 22′, O: R=159° 10′. Cleavage: rhombohedral, perfect. Usually in delicate capillary crystallizations.

H.=3-3.5. G.=5.25-5.65. 4.601, Kengott, Joachimstahl. Lustre metallic. Color brass-yellow, inclining to bronze-yellow, with a gray irridescent tarnish. Streak bright. Brittle.

Composition.—Ni S=Sulphur 35:1, nickel 64:9. Analyses: 1, Arfvedson, (K. V. Ac. H. 1822, 427); 2, Rammelsberg, (1st Supp. 67):

1. S 34-26 Ni 64-35=98-61, Arfvedson.

2. Saalfeld, S 3579 Ni 61:34, Cu 1:14, Fe 1:73=100, Rammelsberg. G. 5:65.

B.B. fuses to a brittle metallic magnetic globule. With warm nitric acid partly dissolved, forming a gray or pale-green solution. Wholly soluble in aqua regia. In an open tube gives sulphurous acid.

Occurs in capillary crystals in the cavities, and among crystals of other minerals. at Joachimstahl in Bohemia, Johanngeorgenstadt, Przibram, Riechelsdorf, Andreasberg, Cornwall, and other places. Near Merthyr Tydvil, at Dowlais, it is found in regular crystals, occupying cavities in nodules of spathic iron. In capillary crystals with spathic iron at the Sterling Mine, Antwerp, N. Y.; the largest crystal yet observed was about a fifth of a line in diameter. In some cases crystals of spathic iron are transfixed by the needles of millerite. (Am. J. Sci. [2], ix, 287). Also in Lancaster Co., Pa., with chromiciron, emerald nickel, and kæmmererite.

PYRRHOTINE, Breit. Magnetic Pyrites. Magnetkies, W. Fer Sulfuré ferrisère. Fer Sulfuré magnetique, H.


Hexagonal. $0: 1=135^{\circ} 8'; a=0.862$. Observed planes 0. $I, \frac{1}{2}, 1, 12, i2$.

O: I=90°. O: 22=119° 53′. 1: 1=138° 48′. O: 2=116° 28′. 2: 2=126° 52′. I: I=120°.

Cleavage: O, perfect; I, less so. Commonly massive and amorphous; structure granular.

amorphous; structure granular.

H.=3·5—4·5. G.=4·4—4·7; 4·631,
a crystalline variety. Lustre metallic.
Color between bronze-yellow and copper-red. Streak dark-grayish black.
Fracture small subconchoidal. Brittle.
Slightly attracted by the magnet, and subject to speedy tarnish.



Composition.—Fe S[+\frac{1}{5} Fe^3 S^3]=Fe^7 S^6=Sulphur 39.5, iron 60.5, G. Rose. Schaffgotsch makes also the compounds FeS+Fe\frac{1}{5}^3, and 9 FeS+Fe\frac{1}{5}^3, but they are rejected by Rose. Analyses: 1, Stromeyer, (Gilb. Ann. xviii, 183, 209); 2, 3, Plattner, (Pogg. xlvii, 369); 4, 5, Berthier, (Ann. d. Mines, [3], xi, 499); 6, II. Rose, (Pogg. xlvii); 7, Schaffgotsch, (Pogg. l, 533); 8, Stromeyer, (loc. cit.):

8. Fahlun 4. Sitten 5. Sitten 6. Bodenmais 7. Bavaria 9. Barèges 1. Harts 2. Brazil Sulphur, 40.22 40.15 40.48 40.2 39.0 3878 89.41 48.63 Iron, 59.85 59.63 5972 59.8 61.0 60.52 60.59 56.37

100 00, S. 100 06 P. 99 94, P. 100 0, B. 100 0, B. 100 00, R. 100, Sch. 100, St.

Frankenheim considers the mineral essentially Fe S=Sulphur 36.4, iron 63.6, considering the species isomorphous with greenockite (Cd S).

A nickeliferous variety analyzed by Berzelius, (Jahresb. xxi, 182), and another by M. Boye, (Am. J. Sci. [2], xiii, 219), afforded,

Fe Co Mn Cu Gangue Ni l. Klefva, 38.089. 57.643, 3.044, 0.094. 0.223. 0.447, 0.460. 4.55, Pb 0.27, 2 Lancaster Co. Pa. 24 84, 27.16.2 41.34, 1.30.

Deducting the impurities in Boye's analysis there are 21.01 sulphur to 40.19 iron. In another specimen from Modum, Norway, Scheerer detected 2.8 per cent. of nickel.

B.B. affords fumes of sulphurous acid and the odor of sulphur. On charcoal in the exterior flame, converted into a globule of red oxyd of iron; in the interior flame it fuses and continues to glow, after the blowpipe is removed. The mass on cooling, is magnetic and has a metallic crystalline structure, and a yellowish color on a surface of fracture. Dissolves in muriatic acid, excepting the sulphur.

Crystalline plates of this species have been observed at Kongsberg in Norway, and at Andreasberg in the Hartz; but they are of rare occurrence. It generally occurs massive, in fissures of crystalline rocks; also found at Kupferberg in Siberia, Bodenmais, Breitenbrunn, Fahlun; at Joachimstahl on crystals of pyrargyrite. Cleavable varieties accompany iolite at Bodenmais in Bohemia. The compact specimens are abundant in Cornwall, at Appin in Argyleshire, Saxony, Siberia, and the Hartz. It has also been observed in the lavas of Vesuvius, and in some meteoric stones.

Trumbull, Conn., and the adjoining town of Monroe, afford the cleavable variety of this species; at the former place it occurs in the topaz and fluor vein, at the latter in a quartz vein, in gneiss. Compact varieties occur with iron pyrites, at Stafford, Corinth and Shrewsbury, Vt., and in many parts of Massachusetts; also a mile and a half north of Port Henry, Essex Co., N. Y., near Natural Bridge in Diana, Lewis Co., and with magnetic iron ore at O'Neil mine, and elsewhere, in Orange Co., N. Y. In Canada in large veins at St. Jerome, &c.


Its inferior hardness is sufficient to distinguish it from common pyrites.

GREENOCKITE, Brooke and Connel, Jameson's Jour. xxviii, 390; Breithaupt, Pogg. li, 274. Sulphuret of Cadmium.

Hexagonal; hemihedral, with the opposite extremities dissimilar. $0:1=136^{\circ}\ 24'$; a:0.8247. Observed planes as in the annexed figure, with also 4 and i2.

```
O: \frac{1}{4} = 154^{\circ} \ 32'. I: 1 = 133^{\circ} \ 36' 1: 1 \ (pyr.) \ 139^{\circ} \ 39'. O: 2 = 117^{\circ} \ 42'. I: 2 = 152^{\circ} \ 18' 2: 2 " = 127^{\circ} \ 26'.
```

Cleavage: I, distinct; O, imperfect.
H.=3-3.5. G.=4.8, Brooke; 4.9-4.999,
Breithaupt; 4.5, the artificial, Söchting. Lustre
adamantine. Color honey-yellow; orangeyellow—veined parallel with the axis. Streak
powder between orange-yellow and brick-red.
Nearly transparent. Strong double refraction.
Not thermo-electric, (Breithaupt).



Composition.—Cd S=Sulphur 22.3, cadmium 77.7. Analysis by Connel, (loc. cit.), Sulphur 22.56, and cadmium 77.30=99.86.

B.B. on charcoal decomposed, and a yellowish-red ring of oxyd of cadmium is deposited. Soluble in muriatic acid, affording sulphuretted hydrogen.

Greenockite occurs in short hexagonal crystals at Bishoptown in Renfrewshire, Scotland, in a porphyritic trap and amygdaloid, associated with prehnite. It was named in honor of Lord Greenock, its discoverer. This species is related in form to copper nickel and broithauptite. It has been found as a furnace product, (Ann. Ch. Pharm. lxxxvii, 34, and Halle Zeitschr., i, 346, 1853).

ONOFRITE, Haid. Selenid of Mercury. Merkurglanz, Br. Selenquecksilber. Selenschwefelquecksilber.

Massive; texture compact granular; no cleavage.

H.=2.5. G.=7.1—7.37, Clausthal ore. Lustre metallic. Streak shining. Color steel to blackish lead-gray.

Composition.—Analyses: 1, H. Rose, (Pogg. xlvi, 315); 2, 3, Kerl, (B. u. H. Ztg., 1852, No. 47):

```
1. Mexico, 6·49 10·30 81·33=98·12, Rose.
2. Clausthal, 21·27 0·36 65·52, quartz 10·28=99·57, Kerl.
3. " 24·05 0·12 72·26, " 2·86=99·74, Kerl.
```

Analysis: 1, Hg (S, Se), with S to Se as 4:1; 2, 3, Hg Se=Selenium 28:3, quick-silver 71.7=100:0; or more nearly Hg⁶ Se⁸=Selenium 24.7, quicksilver 75:2=100.

B.B. on charcoal gives off the odor of selenium, and a white incrustation covers the coal.

Occurs with other ores of mercury in Mexico, near San Onofre; also with copper pyrites near Clausthal in the Hartz. It has nearly the color and lustre of gray copper.

COPPER NICKEL. Arseniet of Nickel, Thom. Kupfernickel, W. Arseniknickel, L. Nickel Arsenical, H. Nickelkies. Rothnickelkies.

Hexagonal, and isomorphous with Breithauptite. $O:1=136^{\circ}$ 35'; a:0.81944. Observed planes, O and 1; 1:1 (pyr.)=138° 48'. Usually massive—structure nearly impalpable; also reniform with a columnar structure; also reticulated and arborescent.

H.=5-5.5. G.=7.33-7.671. Lustre metallic. Color copperred, with a gray to blackish tarnish. Streak pale brownish-black. Opaque. Fracture uneven. Brittle.

Composition.—Ni As=Arsenic 55.9, nickel 44.1. Analyses: 1, Stromeyer, (Gött. gel. Anz. 1817, 204); 2, Pfaff, (Schw. J. xxii, 256); 3, Suckow, (Verwitt. im Min., 58, Ramm. 4th suppl. 122); 4, Berthier, (Ann. Ch. Phys. xiii, 52); 5, Scheerer, (Pogg. lxv, 292); 6, Ebelmen, (Ann. d. M. [4], xi, 55); 7, Schnabel, (Ramm. 4th Suppl. 122):

```
Ni
                                   Fe
                                         Pb
                                                     Sb
                                                Co
                      As
1. Riechelsdorf,
                     5473 44.21
                                  0.84
                                         0.82
                                                           0.40= 99.99, Strom.
                     46.42
                            48.90
                                   0.84
                                                           0.80= 97.02, Rfaff.
2.
                                         0.26
        ..
                            45.78
                                                           0.15=102.30, Suckow.
8.
                     58.69
                                   270
                                              0.16 8.00
4. Allemont,
                     48.80
                           89-94
                                                          2.00= 99.90, Berth.
5. Krageroe, G. 7 662, 54 85
                            44.98
                                   0.51
                                               Cu 0.16
                                                           0.14= 99.79, Scheer.
6. Ayer, G=7 89,
                     54 05
                           43.50
                                              0.32 0.05 2.18, gangue 0.20=
                                   0.45
                                                                      10075, E
                                                         0.48, Cu 1.44=100, S.
                     52.71 45.87
7. Westphalia,
```

An ore from Balen in the Pyrenees, afforded Berthier,

As 33.0, Sb 27.8 Ni 33.0, Fe 1.4, S 2.8, quartz 2.0=100, in which, as in his Allemont ore, part of the arsenic appears to be replaced by antimony.

B.B. on charcoal emits arsenical fumes and fuses to a white globule, which darkens by exposure to the air. In nitric acid soon assumes a green coating, and in nitromuriatic acid is dissolved.

Copper nickel accompanies cobalt, silver, and copper, in the Saxon mines of Annaberg, Schneeberg, &c.; also in Thuringia, Hesse, and Styria, and at Allemont in Dauphiny. It is occasionally observed in Cornwall, as at Pengelly and Huel Chance. and at the Leadhills, Scotland.

It is found at Chatham, Conn., in gneiss, associated with smaltine. This is the most important of the ores of nickel.

BREITHAUPTITE, Haid. Antimonial Nickel. Antimoniet of Nickel. Antimonnickel.

Hexagonal. $O: 1=135^{\circ} 15'; a=0.8585$. Observed planes: $0, \frac{1}{2}, \frac{3}{2}, I$. $O: \frac{1}{2}=153^{\circ} 38', O: \frac{3}{2}=123^{\circ}55'$. In thin hexagonal plates. Also arborescent and disseminated.

H.=5.5. G.=7.541, Breithaupt. Lustre metallic, splendent. Color in the fresh fracture light copper-red, inclining strongly to violet. Streak reddish-brown. Opaque. Fracture uneven—small subconchoidal. Brittle. Not acted on by the magnet.

Composition.—Ni Sb=Antimony 68.6; Nickel 31.4. Analyses: 1, 2, Stromeyer, (Pogg. xxxi, 184):

- 1. Sb 63 734 Ni 28 946 Fe 0 866 Galena 6 437=99 983.
- 2. 59706 27.054 0.842 12.857=99.959.

B.B. on charcoal antimony sublimes.

Formerly found in the Andreasberg mountains, with calcite, galena, and smaltine, but long since exhausted. Has been observed as a furnace product, crystallized.

KANEITE, Haid. Arsenical Manganese. Arseniuret of Manganese. Arsenikmangan.

In botryoidal masses, also amorphous; structure foliated or granular.

H. above 5 f stated as hard. G.=5.55, Lustre metallic. Color grayish-white, with a black tarnish. Opaque. Fracture uneven. Brittle.

Composition.—Mn As=Manganese 42.4, arsenic 57.6. Analysis by Mr. Kane, (Quarterly J. of Sci., New Ser., vi, 382):

Manganese 45.5, Arsenic 51.8, and a trace of Iron=97.3.

B.B. burns with a blue flame, and falls to powder; at a higher temperature the arsenic evaporates, and covers the charcoal with a white powder. Dissolves in aqua regia, without leaving any residue.

It is supposed to be from Saxony, and was first observed by Mr. R. J. Kane of

Dublin, attached to a mass of galena.

SCHREIBERSITE, Haidinger.

In steel-gray folia and grains. Folia flexible. H.=6.5. G.=7.01-7.22. Magnetic.

Composition.—Analysis by M. Patera, (Mitth. v. Freund. d. Nat. in Wien, 1847; and Am. J. Sci. [2], viii, 439): Phosphorus 7.26, iron 87.20, nickel 4.24=98.70, carbon undetermined.

Found in the meteoric iron of Arva. A similar substance was distinguished by Berzelius in the meteoric iron of Bohumilitz, consisting of iron, nickel, and sulphur.

The Dyslytite of Prof. Shepard, (Am. J. Sci. [2], ii, 380), is supposed to be a phosphuret of iron, nickel, and magnesium. It occurs as a blackish-brown powder in many meteoric irons, constituting usually 0.25 to 2.25 per cent.

The Schreibersite of Shepard, (Am. J. Sci. [2], ii), from a meteorite, is supposed to be a "Sesquisulphuret of chromium." The name has been changed to Shepardite by Haidinger.

3. PYRITES DIVISION.

1. PYRITES GROUP.-Monometric.

Pyrites, Fe S². Cobaltine, Co (S, As)².

Hauerite, Mn S². Gersdorffite, Ni (S, As)².

Smaltine, (Co, Ni) As². Ullmannite, Ni (S, Sb, As)².

Chloanthite, (Ni, Fe, Co) As².

5. MARCASITE GROUP.—Trimetric.

Margabite, Fe S². Mispickel, Fe (S, As)².

Rammelsbergite, Ni Ab². Glaucodot, (Co, Fe) (S, As)³.

Leucopyrite, Fe Ab². Sylvanite, (Ag, Au) Te².

3. NAGYAGITE GROUP.—Dimetric.

Nagyagite. ! (Pb, Au) (Te, S).

4. COVELLINE GROUP.—Hexagonal.

€u S³.


COVELLINE,

PYRITES. Cubic Pyrites. Mundic. Marcasite. Bisulphuret of Iron, Thomson. Schwefelkies, W. Eisenkies, L. Fer Sulfuré, H. worling.

MOLYBDENITE, Mo S3.

Schweselkies, W. Eisenkies, L. Fer Sulfure, H. supling.

Monometric; pyritohedral. Common form, the cube. Observed



Cleavage: cubic and octahedral, more or less distinct. Planes O and I often striated, as in f. 167. Twins: composition parallel to I; this composition sometimes parallel to each of the edges, when the form in f. 182A is produced. Also radiated subfibrous, and massive. Often reniform or globular with a crystalline sur-

H.=6-6.5. G.=4.83-5.031. Lustre metallic, splendentglistening. Color a characteristic bronze-yellow, nearly uniform. Streak brownish-black. Opaque. Fracture conchoidal, uneven. Brittle. Strikes fire with steel.

Composition-Fe S2=Iron 46.7, sulphur 63.5. B.B. becomes red in the oxydating flame, and gives off sulphur; ultimately yields a globule of oxyd of iron, attractable by the magnet. Soluble in nitric acid, except a white residue. Some varie-

ties are very liable to decomposition on exposure to the atmosphere.

A variety from Cornwall, Lebanon Co., Pennsylvania, gave J. C. Booth (as communicated to the author) 2.39 per cent. of copper, affording the formula (Fe, Cu)

S. The analysis afforded,

S 53.37, Fe 44.47,

This variety tarnishes, readily, assuming the bluish tarnish of steel.

The ballesterosite is a variety in cubes from Galicia, containing traces of zinc and tin, (Bull. Geol. de F. vii, 21). A variety occurring with millerite at the Kearney Ore bed, Gouverneur, N. Y., is nickeliferous; it is pale bronze and radiated botryoidal in structure; H.=5.5; G.=4.863, (Am. J. Sci., [2], xv, 444.)

It sometimes contains mechanically mingled, a minute quantity (perhaps one five thousandth part) of gold, and is then termed auriferous pyrites. Auriferous

pyrites occurs in most gold regions.

Iron pyrites occurs abundantly in rocks of all ages, from the oldest crystalline to the most recent alluvial deposits. It usually occurs in small cubes, but often modified as above described; also in irregular spheroidal nodules and in veins, in clay slate, argillaceous sandstones, the coal formation, &c. Cubes of gigantic dimensions have been found in some of the Cornish mines; pentagonal dodecahedrons and other forms occur on the island of Elba, sometimes three or four inches in diameter. Large octahedral crystals are found at Persberg in Sweden. Magnificent crystals have been brought from Peru; but still more brilliant and well-finished crystals occur at Traversella in Piedmont. Alston Moor, Derbyshire, Cornwall, Fahlun in Sweden, Kongsberg in Norway, are well-known localities. The clay at Münden in Hannover, and the chalk at Lewes in Surry, have afforded some remarkable compound crystals. It has also been met with in the Vesuvian lavas in small irregular

At Rossie, N. Y., fine crystals (f. 180, 181) occur at the lead mine in green shale; At Rossie, N. Y., fine crystals (f. 180, 181) occur at the lead mine in green shale; at Scoharie, a mile west of the court house in single and compound crystals, often highly polished and abundant; in interesting crystals at Johnsburgh and Chester, Warren Co., N. Y.; in gneiss near Yonkers; in Orange Co. at Warwick and Deerpark; in Jefferson Co., in Champion, and near Oxbow on the banks of Vrooman's lake, in modified octahedrons, (f. 16); in limestone at Shoreham, Vt., crystals abundant; at Hartford, Vt., in cubes of 2 to 4 inches; at Lane's mine, Monroe, Conn., in small octahedrons; in cubes in chlorite slate, at Orange and Milford, Conn., and in mica slate at Stafford; in Massachusetts at Heath in handsome crystals; in Maine at Corinna, Peru, Waterville and Farmington; in Connecticut at Middletown lead mine, (f. 15), sometimes acicular; in Pennsylvania, in crystals, at Little Brittain, Lancaster Co.; at Chester, Delaware Co.; in Carbon and York Cos.; at Knauertown, Chester Co.; in Cornwall, Lebanon Co., in lustrous cubo-octahedrons, and with an elegant steel tarnish, sometimes an inch through; at Pottstown, near French Creek, in large yellow octahedrons; with magnetic and copper pyrites. Massive varieties are abundant in Connecticut in gneiss at Colchester, Ashford, Tolland, Stafford, and Union; in Massachusetts at Hawley and Hubbardston; in Maine at Bingham, (sawmills). Brooksville, and Jewell's Island; in New Hampshire at Unity; in New York in Franklin, Putnam, and Orange Coa., and elsewhere.

This species affords the greatest part of the sulphate of iron and sulphuric scid of

commerce, and also a considerable portion of the sulphur and alum.

The name purites is derived from the Greek, repires, a term applied to this mineral, because, as Pliny states, "there was much fire in it," as was made apparent by frie tion. This term was applied to flint and some siliceous millstones for a similar reason.

ALTERED FORMS.—Pyrites readily changes to sulphate of iron by oxydation, some sulphur being set free; also to limonite on its surface, by the action of bearbonate of lime carrying off the sulphuric acid, as change proceeds; and from lime nite to red oxyd of iron. Green vitriol, Limonite, Göthite, Red iron ore, also Quarts, Graphite, occur as pseudomorphs after pyrites.

HAUERITE, Haid. Naturwiss. Abhandl. of Vienna, 4to. 1847, i, pp. 101 and 107.

Monometric; hemihedral, like pyrites. Figures 11, 16, 15, 19, 73 $(0, 3\frac{3}{2})$, 67 (0, i3); octahedral form most common. Crystals sometimes clustered in spheroidal forms. Cleavage: cubic, imperfect.

G.=3.463, v. Hauer. Lustre metallic adamantine Color reddish-brown, brownish-black. Streak brownish-red.

Composition.—Mn S2-Sulphur 53.7, manganese 46.3. Analysis by Patera, (lot. cit. and Pogg. lxx, 148):

8 53.64, Manganese 42.97, Iron 1:30, Silica 1.20=99.11.

B.B. gives off much sulphur and is reduced to a simple sulphuret Mn S; with

soda a manganese reaction.

From Kalinka in Hungary, in clay with gypsum and sulphur, in a region some thing like a solfatara, trachytic and dioritic rocks decomposing and adding to the clay, and at the same time the sulphur which is given off producing some deposited sulphur, besides gypsum and sulphurets.

SMALTINE. Gray Cobalt. Tin-white Cobalt, J. Binarseniet of Cobalt, Then Temeralkies, Breit. Weisser-Speiskobold, W. Speisskobalt, Haus. and L. Cobalt Arsenical, H.—Chloanthite, Breit. Rammelsbergite, Haid. White Nickel. Chathamite, Shepard. Weissnickelkies. Arseniknickel.

Monometric. Observed planes: O, 1, 22, I. Figures 9, 11, 15, 17, 19, 37. Cleavage: octahedral, distinct. Cubic, in traces Also massive and in reticulated and other imitative shapes.

II. = 5.5—6. G. = 6.466—7.2. Lustre metallic. Color tin-white, inclining, when massive, to steel-gray, sometimes iridescent, or grayish from tarnish. Streak grayish-black. Opaque. Fracture granular and uneven. Brittle.

Composition.—(Co, Fe, Ni), As²=, with cobalt alone, Arsenic 71.8, cobalt 28.3; with nickel alone, Arsenic 91.7, nickel 28.3; with equal parts of cobalt, iron and nickel, Arsenic 72.1, cobalt 9.4, nickel 9.5, iron 9.0. Anal. 6, R⁷ As⁶, 5, 7, 8, R⁶ As⁶. The species varies between an ore of cobalt and nickel, (or perhaps cobalt alone), with assenie, and one of nickel alone; G. Rose doubts if it ever occurs without nickel, and states that in the earlier analyses of Stromeyer and Varrentrapp, the nickel was probably overlooked.

Hundline has included the cobaltic variety, and Chloanthite the nickel variety,

between which there are gradual transitions.

Analyses: 1, Stromeyer, (Gött. gel. Anz. 1817, 72); 2, Varrentrapp, (Pogg. xlviii, 50t); 3, Hofmann, (xxv, 485); 4, Kobell; 5, Jückel, (Rose's Kryst.-Chem., 52); 6, Klauer, (Ramm. 5th Suppl. 225); 7, Weber, (ib.); 8, Rammelsberg, (ib.); 9,

Sartorius, (Ann. Ch. Pharm. lxvi, 278); 10, 11, B. W. Bull, (Rose's Kryst. Ch. Min.
52); 12, Karstedt, (Ramm. 5th Suppl. 225); 13, Booth, (Am. J. Sci., xxix, 241); 14,
Rammelsberg, (J. f. pr. Chem. lv, 486); 15, 16, ib. (1st. Suppl. 15); 17, C. U. Shepard, (Am. J. Sei., xlvii, 351):

		As	Co	Fe	Cu	Ni
	Riechelsdorf,	74.21	20.31	3.42	0.16	—— S 0.88=98.98, Stromeyer.
	Tunaberg.	69.46	23.44	4.95	-	— S 0.90=98.75, Varrentrapp.
3.	Schneeberg,	70.37	18.95	11.71	1.39	1.79 S 0.66, Bi 0.01=99.88, Hofm.
4.		71.08	9.44	18.48	trace	— S trace, Bi 1.00=99.92, Kob.
5,	Riechelsdorf,		21.21	11.60	1.90	— S 0.49, Bi 0.04=101.26, Jäckel,
6.	" cryst.	68-73	16.37	2.30	0.45	12·15=100, Klauer. [G=6·84.
7.	" cubes,	59.38	18:30	0.72	-	19.38 S 2.22=100, Weber, G=4.374.
8.	4	60.42	10.80	0.80	-	25.87 S 2.11=100, Ramm. G=4.374.
9.		73.53	9.17	2.24	-	14.06 S 0.94=99.94, Sartorius.
10.	" cryst.	76.09	4.56	6.82	-	12·25=99·72, Bull.
	Schneeberg,	75.85	3.32	6.52	0.94	12·04=98·67, Bull, G=6·537.
12.	"	74.80	3-79	7.33	-	12.86 S 0.85=99.63, Karstedt.
13.	Riechelsdorf,	72.64	3.37	3.25	-	20.74=100, Booth.
14.	"	71.11	-	6.82	-	18-71 S2-29=98-93, Ramm. G=6-411.
15.	Kamsdorf,	70.34	-	trace	-	28.40=100.43, Ramm. G=6.735.
16,	"	70-93	-	trace	_	29.50=100.43, "
17.	Chathamite,	70.00	1.35	17.70	-	12·16=101·21, Shepard.

B.B. on charcoal emits copious arsenical fumes, and melts to a white brittle metallie globule. It colors borax and other fluxes blue, and produces with nitric acid, a pink solution, depositing arsenous acid; or gives the reactions of nickel.

Usually occurs in veins, accompanying ores of cobalt or nickel, and ores of silver and copper; also, in some instances, with copper nickel and mispickel; often hav-

ing a coating of nickel green.

With silver and copper it occurs at Freiberg, Annaberg, and particularly Schneeberg in Saxony; at Joachimstahl in Bohemia, the reticulated varieties are frequently found imbedded in calc spar; also at Huel Sparnon in Cornwall; at Riechelsdorf in Hesse, in veins in the copper schist; at Tunaberg in Sweden; Allemont in Dauphine. See analyses above, for the varieties at these localities.

At Chatham, Conn., the Chloanthite (Chathamite) occurs in mica slate, associated generally with mispickel and sometimes with copper nickel; affords but 1 or 2 per

cent. of cobalt.


ALTERED FORMS.—Smaltine occurs altered to Cobalt Bloom, (arsenate of cobalt), a change due to the oxydation of the arsenic and cobalt on exposure to moisture.

COBALTINE, Beud. Silver White Cobalt. Bright White Cobalt. Glance Cobalt. Glanzkobalt, W. Kobalt Glanz, Haus. and L. Cobalt Gris, H.

Monometric; pyritohedral. Observed planes, as in the annexed figure. Cleavage: cubic, perfect. Planes O striated. Also

massive, granular or compact.

H.=5.5. G.=6-6.3. Lustre metallic. Color silver-white, inclined to red; also steel-gray with a violet tinge, or grayish black when containing much iron. Streak grayish black. Fracture nneven and lamellar. Brittle.



Composition. -Co S2+Co As2 or Co (S, As)2=Sulphur 19:3, arsenic 45:2, cobalt 35:5. Analyses: 1, Stromeyer, (Schw. J. xix, 336); 2, Schnabel, (Ramm. 3d Supp. 65); 3, Huberdt, (Ramm. 4th Supp. 116); 4, Patera, (ib.); 5, Ebbinghaus, (ib.); 6, 7, Schnabel, (ib.); 8, Schnabel, (ib. 5th Suppl. 149); 9, Heidingsfeld, (ib.)

```
Co
1. Skutterud.
                    20 084
                            43.46
                                    38.101
                                               3 232=99 882, Stromeyer.
                             4475
                                    29.77
                                               6:38=100, Schnabel.
2. Siegen,
                    19.10
                                               575=100, Huberdt.
3. Oratwitza,
                    1975
                             44.13
                                    30.37
      " columnar, 19:78
                             43.68
                                    32.08
                                               4.56=100, Patera.
                                               8.42, quartz 1.63=100.34, Ebbinghaus.
5. Skutterud,
                    20.25
                             42-97
                                    82-07
  Siegen, massive, 1935
                             45.31
                                    8371
                                               1.62=99.99, Schnabel.
         plumose, 19 98
7.
                             42.58
                                      8.67
                                              25-98, Sb 2-84=100, Schnabel.
                                             28 03=100 75, Schnabel. [75, Heid. 24 99, Sb 1 04, Cu 3 26, gangue 0 52=100
8.
      44
                    20.86
                             42.94
                                      8.92
      "
                    19.08
                             43.14
                                     9.62
```

The last 3 analyses have three-fourths of the cobalt replaced by iron; they are of the Stahlkobalt or Ferrocobaltine, from the Hamberg mine, Siegen.

B.B. gives off fumes of arsenic, and affords, after roasting, a dull black metallic globule, which attracts the magnet. Colors borax blue, and effervesces in heated nitric acid. Soluble in warm nitric acid, depositing arsenous acid.

Occurs at Tunaberg, Riddarhyttan, and Hokansbö, in Sweden, in large, splendid. well defined crystals; also at Skutterud in Norway. Other localities are at Querbach in Silesia, Siegen in Westphalia, and at Botallack near St. Just, and in other places in Cornwall. The most productive mines are those of Vena in Sweden, where it occurs in mica slate. These mines were first opened in 1809.

This, and the preceding species, afford the greatest part of the smalt of commerce. It is also employed in porcelain painting.

GERSDORFFITE, Haid. Nickel-Glance. Nickelglanz. Nickelarsenikglanz.
Monometric; pyritohedral. Observed planes 0, 1, i2. Figs. 11, 15, 16, 68. Cleavage: cubic, rather perfect. Also lamellar and granular massive.

H.=5.5. G.=5.6-6.9. Lustre metallic. Color silver-white-steel-gray, often tarnished gray or grayish-black. Streak grayish-black. Fracture uneven.

Composition.—Ni S²+Ni As² or Ni, (S, As)²—Sulphur 19·3, arsenic 45·3, nickel 35·6. Analyses: 1, Berzelius, (K. V. Ac. H. 1820); 2, Rammelsberg, (Pogg. lxviii. 511); 3, Kobell, (J. f. pr. Ch. xxxiii, 402); 4, Löwe, (Berichte Fr. Nat. in Wien. 1847); 5, Döbereiner, (Schw. J. xxvi, 270); 6, Rammelsberg, (Handw. ii, 14); 7. Heidingsfeld, (Ramm. 5th Suppl., 174); 8, 9, Löwe, (Ramm. 2d Suppl. 102, Pogg. lv. 503); 10—12, Pless, (Ann. d. Ch. u. Pharm. li, 250); 13, Ludwig, (Archiv d. Pharm. 1847, 288):

```
Νi
                                                   0.92ª, $i 0.9=100.58, Berzeliu-
 1. Loos, Sweden,
                        45.37 19.34 29.94 4.11
 2. Harzgerode, G. 5.65, 44.01
                                             6.00
                              18.83
                                      80.30
                                                    ---- Sb 0.86=100, Ramm.
 8. Amoibite, G. 6.08, 45.34 14.00
                                             2.50 trace, Pb 0.82=100, Kobell.
                                      37.34
 4. Prakendorf.
                                      28.75
                                            8.90
                                                    ---=100, Löwe.
                       46.10 16.25
                                                       -=100, Döbereiner.
                                      27 -
                                           11.
 5. Kamadorf.
                       48.
                               14.
                                      81.82
                       48.02 20.16
                                                       -=100, Rammelsberg.
 Lobenstein,
                       46.12
                              18-96
                                      33 04
                                             1.81
                                                   0.60 Cu 0.11, Sb 0.33=100.97.
 8. Geradorffite. 49:83
9. Schlad., G. 6:7-6:9, 42:52
                       49.83 14.13
                                      26.14
                                             9.55
                                                      —=99<sup>-65</sup>, Löwe.
                                             2.09
                                                        -, quartz 1 87=99 12, Löwe
                              14.22
                                      88.42
                                                    14·12=100·23, Pless.
10.
       " cryst., G. 6 64, 89 04 16:35
                                      19:59 11:13
                        39.88 16.11
                                      27-90 14-97
                                                     0.88=99.69, Pleas,
11.
                                                     2.88=100, Pless
                       39.40 16.91
                                     28.62 12.19
12.
                                                       —Pb 9·29. Ca 12·58, Fe 8·26.
18. Oelsnitz,
                       35.26
                               8.90
                                     20.94 -
                                                           Mn 1:02=87:25, Ludwig.
                . with some Cu.
                                     b, by loss.
                                                   c, with some Co.
```

Analyses 1, 2 and 7 give the formula Ni S²+Ni As²=Ni (S. As)², iron replacing some of the nickel.

Analysis 3 (Amoibite) afforded Kobell, Ni²S³+2Ni As²(=As⁴S³ Ni⁴)=Arsenic 47·4, sulphur 15·2, nickel 37·4. The ratio for the arsenic, sulphur, and nickel, is more nearly 4: 3: 41.

is more nearly 4: 3: 4\frac{1}{2}.

Analysis 4 corresponds nearly to Kobell's formula for the Amoibite—(Ni, Fe)²
S²+2 Ni As²; equivalent to 1 of [Ni S²+Ni As²] and \frac{1}{2} of copper nickel.

Analysis 8, Gersdorffite, according to Löwe, has the formula just mentioned for No. 4. The ratio 3: 2: 3 is nearer the analysis than 4: 3: 4, and affords the formula Ni As²+2(Fe, Ni)S. This is equivalent to 1 of [Ni S²+Ni As²] and \frac{1}{2} of copper nickel. Analysis 5 may belong here or under the formula for No. 4.

Analyses 10 to 12 by Pless, give the formula 2NiS+Ni As². The Oelsnitz ore, No. 13, was mixed with spathic iron and cale spar. It corresponds to Ni S²+2Ni As², and comes under the general formula Ni(S, As)².

These discordant results do not seem to admit of being harmonized entirely.

When heated it decrepitates with great violence. Ignited in a glass tube, sulphuret of arsenic sublimes as a transparent yellowish-brown mass, which remains

phuret of arsenic sublimes as a transparent yellowish-brown mass, which remains clear on cooling. Partly soluble in nitric acid, depositing sulphur and arsenous

Occurs at Loos in Helsingland, Sweden; in the Albertine mine, near Harzgerode in the Hartz, with copper pyrites, galena, calcite, fluor spar, and quartz; at Schladming in Styria, and Kamsdorf near Lobenstein in Thuringia.

The Amoibite occurs in small octahedrons at Lichtenberg near Steben, in Fich-

telgebirge. H.=4. Color light steel-gray.

ULLMANNITE, Fröbel. Nickel Stibine. Nickeliferous Gray Antimony. Nickel spiesglanzerz. Antimonnickelglanz. Nickelantimonglanz. Antimoine Sulfuré Nickelifère, H.

Monometric. Observed planes O, 1, I; f. 15-17. Cleavage:

cubic, perfect. Occurs also massive; structure granular. H.=5-5.5. G.=6.2-6.51. Lustre metallic. Color steel-gray, inclining to silver-white. Brittle.

Composition.—Ni S²+Ni(Sb, As)², Ramm. or Ni (S, Sb, As)²=(arsenic excluded) Nickel 26.9, antimony 58.6, sulphur 14.5. Analyses: 1, Klaproth, (Beit. vi, 829); 2. Ulimann, (Syst. tab. Uebers. 379); 3, 4, H. Rose, (Pogg. xv, 588); 5, Rammelsberg, (Pogg. lxiv, 189):

		Aв	Sb	S	Ni
1.	Freusberg,	11.75	47.75	15.25	25·25=100, Klaproth.
2	Siegen,	9-94	47.56	16.40	26·10=100, Ullman.
3.	"		5576	15-98	27:36=99:10, H. Rose.
4.	"		54.47	15-55	28·04=98·06, H. Rose.
5.	G. 6.506,	2.65	50.84	17:38	29.43, Fe 1.83=102.13, Rammelsberg.

B.B. partly volatilizes, and the charcoal is covered with a white coating, with fames of sulphurous acid and antimony; ultimately yields a metallic globule, which often gives a blue color with borax. In a tube decrepitates and gives a dark brownish sublimate without odor.

Occurs in the Duchy of Nassau, in the mines of Freusberg, with galena and

copper pyrites; in Siegen, Prussia; at Harzgerode and Lobenstein.

Rammelsberg calls an ore from the Hartz Bournonit-Nickelglanz. It occurs in cubes; H.=4.5. G.—5.635—5.706. Analysis, (Pogg. lxxvii, 254):

As 28-00, Sb 19-53, S 16-86, Ni 27-04, Co 1-60, Pb 5-13, Cu 1-33, Fe 0-51=100.

It comes from Wolfsberg in the Hartz. Rammelsberg considers this and a nickel-bournonite, (see under Bournonite), compounds of ullmannite and bournonite, and shows by calculation that the atomic volume of nickel glance and bournonite are the same.

MARCASITE, Haid. White Iron Pyrites. White Bisulphuret of Iron. Radiated Pyrites. Spear Pyrites. Hepatic Pyrites. Cellular Pyrites. Spearkies, Strahlkies, Kammkies, Leberkies, Zellkies, Spärkies, Rhombischer Eisenkies. Fer Sulphuré A-iculaire Radié, Fer Sulfuré Blanc, H. Weisskupfererz and Kyrosite, Breit.

 $I: I=106^{\circ} 5', O: 17=122^{\circ} 26', a:b:c=1.5737:$ Trimetric. 1: !3287.


```
0:1=116^{\circ}55'.
                          1:1 \text{ (mac.)} = 115^{\circ} 10'. 1i:1i=64^{\circ} 52'.
                          1:1(brach.)=89^{\circ}6'.
0:\frac{1}{3}i=158^{\circ}\ 27'.
                                                           1i:1i=80^{\circ}20'.
Q:15=130^{\circ}\ 10'.
                          1:1 (bas.) =126° 10′. I: \tilde{n}=126° 57′.
```


-	0	
		11
		11
		11
11	1	11
	I	iĭ

Cleavage: I rather perfect; 1½ in traces. Twins: plane of composition I, sometimes consisting of five individuals, united by the acute lateral angle (f. 285): also others with composition parallel to 17. Also globular, reniform, and other imitative shapesstructure straight columnar; often massive, columnar, or granular.

H=6-6.5. G.=4.678-4.847. Lustre metallic. Observed Planes. Color pale bronze-yellow, sometimes inclined to Streak grayish or brownish-black. Fracture

green or gray. uneven. Brittle.





Composition.—Fe S2, or same as for Pyrites. Analyses: 1, Hatchett, (Phil. Trans. 1804, 325); 2, 3, Berzelius, (Schw. J. xxvii, 67); 4, Scheidhauer, (Pogg. lxiv, 282):

1.	Fe 46.4	S 53.6=100, Hatchett.
2.	45.66	54-34=100, Berzelius.
3. Speerkies,	45.07	52 35, Mn 0 70, Si 0 80=99 92, Berzelius.
4. Kyronite,	45.60	53 05, Cu 1 41, As 0 93=100 99, Scheidhauer.

B.B. like pyrites. Very liable to decomposition, more so than pyrites. This species was formerly subdivided according to the different forms the mineral presents. Radiated pyrites included the radiated masses and more simple crystals; spear pyrites, the macled crystals; hepatic pyrites, or leberkies, (so called from free, liver), the decomposed liver-brown tessular crystals, which were originally iron pyrites, and also certain hexagonal pseudomorphs; cockscomb pyrites, or kamenkies, the crest-like aggregations of this species of pyrites; cellular pyrites, the cellular varieties formed by the decomposition of crystals of galena, which contained films

of pyrites between its layers, thus producing a honeycomb appearance.

The spear pyrites occurs abundantly in the plastic clay of the brown coal formation, at Littmitz and Altsattell, near Carlsbad in Bohemia, and is extensively while for its sulphur and the manufacture of the sulphate of iron. The radiated variety occurs at the same place; also at Joachimstahl, and in several parts of Saxony. The cockscomb variety occurs with galena and fluor spar in Derbyshire. It occurs in stalactitic concretions in Cornwall.

The kyronite (Weinskupfererz, or arsenid of copper, as it has been called) is from

the mine Briccius, near Annaberg.

The Chilian Weisskupfererz contains, according to Plattner, 12-9 per cent. of copper, besides iron and sulphur, but no arsenic. (Breit. Pogg. lviii, 281).

At Warwick, N. Y., it occurs in simple and compound crystals, in granite, with green. Hustis's farm, in Phillipstown, N.Y., affords small crystals, referred by Beck to this species, occurring in magnesian limestone. Massive fibrous varieties seek to this species, occurring in magnesian limestone. Massive nbrous varieties abound throughout the mica slate of New England, particularly at Cummington, Mass., where it is associated with cummingtonite and garnet. Occurs at Lane's mine, in Monroe, Conn., and in the topaz and fluor vein in Trumbull; also in gneiss at East Haddam; at Haverhill, N. H., with common pyrites.

Cockscomb pyrites is employed in the manufacture of sulphur, sulphuric acid, and sulphate of iron, though less frequently than the common iron pyrites. Its color is considerably paler than the ordinary pyrites, and it is also more liable to decomposition.

decomposition.

Hydrous pyrites, or Wasserkies of the Germans. This mineral, hitherto considered a variety of white iron pyrites, contains water, according to Glocker, in chemical combination; (Pogg. lv, 489). H.=3-4. G.=3.33-3.5. From Moravia and Upper

LONCHIDITE, Breit. and Plattn. Pogg. Ann. lxxvii, 135, (Kausimkies).—This mineral appears to be a variety of marcasite. Breithaupt gives for it the angles 104° 24′ for I: I and 100° 36′ for the brachydome. H. =6.5. G. =4.925—5. Color tin-white, sometimes greenish or grayish; streak black. Analysis by Plattner (loc. cit.) S 4961, As 4.40, Fe 44.23, Co 0.35, Cu 0.75, Pb 0.20=39.54, equivalent to 24 of marcasite (Fe S²) and 1 of Fe As². From Freiberg, Schneeberg, and Cornwall.

ALTERED FORMS.—Limonite and pyrites occur as pseudomorphs after marcasite.

RAMMELSBERGITE. Weissnickelkies.

Trimetric; $I: I=123^{\circ}-124^{\circ}$ (?)

H.=5.25-5.75. G.=7.099-7.188, Breit. Slightly ductile. Otherwise like the preceding.

Composition.—The same as for Chloanthite, Ni As2—Arsenic 717, Nickel 28.8. Analysis: 1, Hoffmann, (Pogg. xv, 491, 494):


Schneeberg, As 71:30, Ni 28:14, Bi 2:19, Cu 1:50, S 0:14=102:27.

Occurs at Schneeberg and at Riechelsdorf. It was first separated from the tesseral white nickel by Breithaupt.

LEUCOPYRITE, Shepard. Glanzarsenikkies. Arseneisen. Arsenikeisen, Arsenikalkies. Arsenosiderit. Lölingite, Haid. Mohsine, Chapman.

Trimetric. I: I=111°30′, Greg; 122°, Rose. Cleavage: rather perfect, in one direction. Also massive.

H.=5-5.5. G.=7.0-7.4; 7.228, from Silesia; 7.337 from Bedford Co., Pa.; 8.67—8.71 from Schladming, Weidenbusch. Lustre metallic. Color between silver-white and steel-gray. Streak grayishblack. Fracture uneven. Brittle.



Composition.—Fe As*—Arsenic 72.8, iron 27.2; or (Fe, Ni, Co) As*. Sometimes Fe* As*—Arsenic 66.8, iron 33.2. Analyses: 1, Hoffmann, (Pogg. xv, 485); 2, Meyer, (Pogg. 1, 154); 3, Karsten, (Eisenhüttenkunde, ii, 19); 4, 5, Scheerer, (Pogg. xlix, 536, and l, 153); 6, Hoffmann; 7, 8, Weidenbusch, (Rose's Kryst.-Chem., 54):

		Δs	8	F'e	N1	Co
l.	Reich'stein,	65.99	1 .94	28-06		—, serpentine 2:17=98:16, Hoffmann.
2	**	63.142	1.631	80.248		" 3.550=98.566, Meyer.
1.	**	65.88	1.77	32.35		——=100, Karsten. G.=7:09.
4.	Fossum,	70.09	1.33	27.39		=98.81, Scheerer.
5.	u '	70.22	1.28	28.14		=99.64, Scheerer.
6.	Schladming,	60.41	5.20	13.49	18.37	5·10 = 97·57, Hoffmann.
	Reich'stein,		1.09	31.51		gangue 1.04=99.25, Weid.
8.	Schladming,	72.18		26.48		=99 86, Weid.

B.B. in a glass tube metallic arsenic sublimes; on charcoal yields arsenic fumes and a magnetic globule is left. In nitric acid dissolves with a separation of arsenous acid.

Occurs associated with copper nickel at Schladming, in Styria; with serpentine at Reichenstein in Silesia, and at Löling, near Hüttenberg in Carinthia, in a bed of sparry iron, associated with bismuth and scorodite; at Ehrenfriedersdorf, (G.=7.219—7.290).


A crystal, weighing two or three ounces, was found in Bedford Co., Penn., but it is not known under what circumstances. In Randolph Co., N. C., a mass was found weighing nearly two pounds.

The name leucopyrite is derived from houses, white, and pyrites; it was given to the species by Shepard in 1885, thus autodating Haidinger's Lölingite, and Chapman's Mohsine.

The prism in this species is usually stated as having the angle 122° or 122° 26'. But according to observations by R. P. Greg, Jr., as he informs the author, the angle is 111° 30'. The angle 122° is near 11: 17 in mispickel.

MISPICKEL. Prismatischer Arsenikkies. Fer Arsenical, H. Danaite. Plinian, Breit. Arsenopyrite, Glocker.

Trimetric. $I: I=111^{\circ}53', O:1\overline{\imath}=119^{\circ}37'; a:b:c=1.7588:1:1.4793$. Observed planes as in the annexed figures.



 $O: 1\bar{\imath} = 118^{\circ} 18'.$ $O: \frac{1}{8}\bar{\imath} = 158^{\circ} 23'.$ $1\bar{\imath}: 1\bar{\imath} \text{ (bas.)} = 120^{\circ} 46'.$ $O: 1 = 115^{\circ} 12'.$ $O: \frac{1}{8}\bar{\imath} = 149^{\circ} 16'.$ $1\bar{\imath}: 1\bar{\imath} \text{ (bas.)} = 99^{\circ} 52'.$ $O: 3 = 98^{\circ} 55'.$ $O: 1\bar{\imath} = 130^{\circ} 4'.$ $3\bar{\imath}: 3\bar{\imath} \text{ (ib.)} = 148^{\circ} 40'.$ $O: 3\bar{\imath} = 99^{\circ} 37'.$ $O: 3\bar{\imath} = 105^{\circ} 40'.$ $1\bar{\imath}: \frac{1}{8}\bar{\imath} \text{ (top)} = 118^{\circ} 32'.$

Cobaltic variety of Skutterud, according to Scheerer, $I:I=111^{\circ}$ 40'—112° 2', $1\bar{\imath}:1\bar{\imath}$ (basal) 121° 30'; that of Franconia (Danaite) according to Teschemacher, $I:I=112^{\circ},1\bar{\imath}:1\bar{\imath}$ (bas.)=121° 30', $1\bar{\imath}:1\bar{\imath}$ (bas.)=100° 15'; according to Kengott, $I:I=112^{\circ}$ 33', $1\bar{\imath}:1\bar{\imath}=121^{\circ}$ 20', $1\bar{\imath}:1\bar{\imath}=99^{\circ}$ 54'. Cleavage: I rather distinct; I0, faint traces. Compound crystals: planes of composition I1, and I1. Also columnar, straight and divergent, or irregular; compact granular, or impalpable.

H.=5.5—6. G.=6-6.4; 6.269, Franconia, Kengott. Lustre metallic. Color silver-white, inclining to steel-gray. Streak dark grayish-black. Fracture uneven. Brittle.

Composition.—Fe As³+Fe S³(=Fe (As, S)³)=Arsenic 46 0, sulphur 19 6, iron 34 1; or (Fe, Co) (As, S)³ (Danaite and Skutterud variety). Analyses: 1, Stromeyer, (Schw. J. x, 404); 2, Chevreul, (Gilb. Ann. xvii, 84); 3, Thomson, (Ann. Lyc. Nat. H., N. Y., iii, 85); 4, Scheerer, (Pogg. xlii, 546); 5, Wöhler, (Pogg. xliii, 591); 6, Hayes, (Am. J. Sci. xxiv, 386); 7, Plattner, (Pogg. lxix, 430); 8, Weidenbusch, (Rose's Kryst.-Chem., 56);

	As	S	Fe	Co
1. Freiberg,	42.88	21.08	86 O4	=100, Stromeyer.
2 "	48.418	20.132	84.938	=98.488, Chevreul.
3. "	45.74	19.60	83.98	——=99·32, Thomson.
4. Skutterud,	4676	17.34	26.36	9.01=100.47, Scheerer.
5. "	47.45	17:48	80.91	4.75=100.59, Wöhler.
6. Danaite,	41.44	17.84	32·94	6.45=98.67, Hayes.
7. Plinian,	45.46	20.07	84.46	=99.99, Plattner. [G.=5.896.
8. Reichenstein,	45.92	19.26	80.88	— gangue, 1 97=100 25, Weid.

B.B. on charcoal, copious arsenical fumes, and a globule of nearly pure sulphuret of iron, which acts on the needle. Gives fire with steel, emitting an alliaceous odor. Dissolves in nitric acid, excepting a residue of sulphur.

Found principally in crystalline rocks, and its usual mineral associates are ores of silver, lead, and tin, iron and copper pyrites, and blende. Occurs also in serpentine.

Abundant at Freiberg and Munzig, where it occurs in veins; at Reichenstein in Silesia, in serpentine; and also in beds at Breitenbrunn and Raschau, Andreasberg, and Joachimstahl; at Tunaberg in Sweden. Huel Mawdlin, and Unanimity, in Cornwall, are other localities.

Met with in fine crystallizations in gneiss in New Hampshire at Franconia, associated with copper pyrites; also at Jackson, and at Haverhill. In Maine, at Blue Hill, Corinna; Newfield, (Bond's mountain), and Thomaston, (Owl's head). In Vermont at Brookfield, Waterbury, and Stockbridge. In Massachusetts, at Worcester and Sterling. In Connecticut at Chatham, with smaltine and copper nickel; at Monroe with wolfram and pyrites; at Derby in an old mine, associated with quartz. In New Jersey at Franklin. In New York, massive, in Lewis, ten miles south of Keeseville, Essex Co., with hornblende; in crystals and massive, near Edenville, on Hopkins's farm, and elsewhere in Orange Co., with scorodite, iron sinter, and thin scales of gypsum; also in fine crystals at two localities a few rods apart, four or five miles northwest of Carmel, near Brown's serpentine quarry in Kent, Put-

Plinian of Breithaupt, stated to be monoclinic, with the composition of mispickel, is shown by G. Rose to be nothing but mispickel. G.—6.3. Reported from St. Gothard, Ehrenfriedersdorf and Zinnwald. Jordan has analyzed a mispickel from near Andreasberg, (J. f. pr. Chem. x, 436), and obtained As 55 000, S 8.344, Fe 86.437, Ag 0.011—99.792, giving nearly the formula 2FeS+3FeAs²—Arsenic 56.7, sulphur 8.0, iron 35.2. Jordan made out 3As, S, 3 Fe, which requires arsenic 52.9, sulphur 7.5, iron 39.6.

ALTERED FORMS.—Pyrites pseudomorph.


GLAUCODOT, (Breithaupt and Plattner, Pogg. Ann. 1849, lxxvii, 127). Trimetric, like Mispickel. In Prisms; I: I=112° 36'. Cleavage: basal, very distinct, Prismatic less so. Also massive.

H.=5. G.=5-975—6-003. Lustre metallic. Color

H.=5. G.=5.975—6.003. Lustre metallic. Color grayish tin-white. Streak black.

Composition.—(Co, Fe) S²+(Co, Fe) As², with Co to Fe as 2:1, (or Co, Fe) (S, As)²—Sulphur 19:4, arsenic 45:5, cobalt 23:8, iron 11:8=100. Analyses: 1, Plattner, (loc. cit.); 2, Patera, (Pogg. lxxxi, 578):

S As Co 1. Chili, 20 210 43 200 (and trace of Ni) 24 774 2. Orawitza, 1978 43 63 Cobalt 32 02




Fe 11.900=100.84, Plattner. 4.56=99.99, Patera. B.B. gives the reaction of cobalt, iron, sulphur, and arsenic.

Occurs in chlorite state with cobaltine, in the province of Huasco, Chili; also at Orawitza in the Bannat with a pale yellow calcite.

This species has the composition of Mispickel, excepting the replacement of onethird of the cobalt by iron. It is essentially a cobaltic mispickel, with which species it agrees nearly in crystallization.

SYLVANITE, Raid. Graphic Tellurium. Graphic Gold. Schrifterz. Schrift-tellur. Tellure Natif Auro-argentifere. H. Aurotellurite. Mullerite. Weisstellur.

Trimetric. $I: I=110^{\circ} 48^{\circ}$, B and M., $O: 17=119^{\circ} 26\frac{1}{2}^{\circ}$, a:b:c=1.7721:1:1.4406.



Cleavage: highly perfect in one direction. Twins: prisms intersecting at 60% nearly. Also massive, imperfectly columnar and granular.

II.=1:5-2. G.=5:732; \$:28, Petz. Lustre metallic. Streak and color pure steel-gray, to silver-white, and sometimes nearly brass-yellow. Fracture uneven. Very seetile.

Composition.—(Ag. Au) Te², G. Rose, —(Ag. Au) being as 1:2) Tellurium 55%, gold 28%, silver 15%, Analyses: I. Klaproth, (Beit. iii, 16); 2, Berzelius. (Jahresh. xiii. 162, analysis imperfect); 3, 4, Petz. (Pogg. lvii, 472): 5, Klaproth, (Beit. iii, 20); 6-10, Petz. (Pogg. lvii, 473):

			Tellurium	S.	Gold	Silver	Pb
ı.	Offenbanya,		60.		20.	10.	=100, Klaproth,
2.	••		25.	tr.	547)	11.3	1 5. Cu. Fe. S. As, traces, B.
3.	**	nenlles,	59-97	0.28	54.42	11-17	0.25, Cu 0.76=100, P.
4.	••	sub-ryst.	58.81	00°C)	56.12	11:31	2·75=100, Petz
5.	(jelher:,	_	44.75		26.73	8:50	19:50, S 0:5=100, K.
б.	White cryst.	. G.=8:5	7, 55.39	2.50	54.89	14 68	2:54=100, Petz
7.	••	G.=74	9, 48:40	8.15	58.58	10.69	3:51=100, Petz.
8.	Yellow cryst.	., G.=8:	33. 51.52	5.73	27:10	7.47	8·16=100, Petz.
9.	" mass	irr.	44.24	8:54	25.81	10:40	11:21=100, Petz.
10.	**		49.96	3.82	29-62	2.78	13-82=100, Petz.

B.B. fuses easily, tinging the flame greenish-blue, and covering the charcoal with a white oxyd; finally a ductile metallic globule is obtained. Dissolves in nitric acid.


Occurs with gold at Offenbanya in Transylvania, in narrow veins, which traverse porphyry; also at Nagyag in the same country. Probably also at Gold Hill, Rowan Co., N. C. (Genth) in minute crystals, with gold, pyrites, and chalcopyrite in chlorite slate.

The name graphic tellurium alludes to the arrangement of the crystals, like writing characters.

The large amount of gold it contains renders it a


highly valuable ore.

The above angles and observed planes are from Brooke and Miller. Haidinger makes the Aurotellurite (or Weisstellur of Werner) (Analyses 5 to 10) different in its dimensions, and gives the following angles: M: M=105° 80', O: a=108° 30', O: a=143° 5'. It is from Nagyag. G=7.99-8:33.



NAGYAGITE, Haid. Elasmose, Beudant. Foliated Tellurium. Bitelluret of Lead, Thom. Black Tellurium, P. Tellurium Glance. Nagyager-erz, W. Blättertellur, Haus. and L. Blättererz. Tellure Natif Auro-Plombifère, H.

 $O: 1i=127^{\circ} 37'; a=1.298.$ Observed planes as in the annexed figure. $0:1=118^{\circ} 37', 1:1=103^{\circ} 14', 0:2i=$ 111° 4', 2i:2i (bas.) 137° 52'. Cleavage: basal. Also granularly massive, particles of various sizes; generally foliated.



H.=1-1.5. G.=6.85-7.2. Lustre metallic, splendent. Streak and color blackish lead-gray. Opaque. Sectile. Flexible in thin laminæ.

Composition.—Analyses: 1, Klaproth (Beit. iii, 32); 2, Brandes, (Schw. J. xxxv. 409); 3, P. Schönlein, (J. f. pr. Ch. lx, 166):

	Te	S	Pb	Au	Ag	Cu
1.	32-2	3.0	54°0	9.0	0.5	1·3=100, Klaproth.
2.	31 -96	3.07	55.49	8.4.1	trace	1·14=100, Brandes.
3.	30.52	8.07	50.78	9.11	0.23	0.99=100, Schönlein.

Schönlein found in other trials, Pb 51 01, 51 06, Te 26 67, S 9 62, 10 59; and Petz obtained (Pogg. 1vii, 478), 8 54, 7 81, 6 48 per cent. of gold. Wöhler deduces from Schönlein's analysis, Pb 4 Au, Te 1 S 2 Tellurium 31 36, sulphur 9 24, lead 50 65, gold 8 74 = 100; and proposes the formula (5 Pb S, 6 Pb Te, Au Te) + 4 Te S 3, or perhaps 3 R(S, Te), + Te S 3, sulphuret and telluret of lead being considered isomorphous.

R(S, Te), +Te S³, sulphuret and telluret or lead being compact.

This formula further simplified becomes nearly (Pb, Au) (Te, S)³.

B.B. on charcoal fuses readily to a malleable metallic button, tinging the flame at the same time blue, and covering the charcoal with a white coating. it affords a bead of gold, with a little silver. It dissolves partially in nitric acid, and also in nitro-muriatic.

Occurs at Nagyag and Offenbanya in Transylvania, in foliated masses and cryatalline plates, accompanying, at the former place, silicate of manganese, blende, and

gold; and at the latter, associated with antimony ores.

Berthier has analyzed another ore very similar to the above in physical characters, consisting of Tellurium 13 0, sulphur 11 7, lead 63 1, gold 6 7, antimony 4 5, copper 1 0=100; corresponding to 218, 6Te, 4Sb, 18Pb, 2Au, but probably impure with sulphuret of antimony.

COVELLINE, Beud. Indigo Copper. Kuferindig. Blue Copper.

Hexagonal; O, I. Cleavage: basal, very perfect. Commonly massive or spheroidal, surface crystalline.

H.=1.5-2. G.=3.8-3.85. Lustre resinous, faint. indigo-blue or darker. Streak lead-gray, shining. Opaque. Thin leaves, flexible. Sectile.

Composition.—Cu S2=Sulphur 38.5, copper 66.5. Analyses: 1, Walchner. (Schw. J. xlix, 158); 2, Covelli, (Ann. Ch. Phys. xxxv, 105):

1. Badenweiler, S 32:64 Cu 64:773 Fe 0:462, Pb 1 046=98 921, Walchner.

2. Vesuvius, 320 66.0=98.0, Covelli.

A Dillenberg covelline afforded Grimm, (Lieb. Jahresb. 1850, 702), 66.82 bisulphuret of copper, 3.96 iron pyrites, 18.63 quartz, and 10.57 Fe Mn H.

B.B. burns, before becoming red hot, with a blue flame, and fuses to a globule which is strongly agitated and emits sparks; finally yields a button of copper.

Occurs with other copper ores near Badenweiler at Leogang in Saltzburg; Keilce in Baland Sanghayan in Sanghayan Managhayan in Sanghayan Managhayan in Sanghayan in S in Poland; Sangerhausen in Saxony; Mansfeld, Thuringia; at Vesuvius on lava.

MOLYBDENITE. Sulphuret of Molybdena, P. Molybdene Sulfuré, H. Molyb-Idanglanz, L. Wasserblei, W.

Hexagonal. In short or tabular hexagonal prisms with replaced terminal edges. Cleavage: basal, eminent. Commonly foliated massive, or in scales.

II.=1-1.5, being easily impressed by the nail. G=4.44-4.8. Lustre metallic. Color pure lead-gray. Streak similar to color, slightly inclined to green. Opaque. Laminæ highly flexible, not elastic. Sectile, and almost malleable. A gray trace on paper, a greenish on porcelain.

Composition .- Mo S2=Sulphur 41:0, molybdenum 59:0. Analyses: 1, Brandes. (Schw. J. xxix, 325); 2, Seybert, (Am. J. Sci. iv, 1822, 320); 3, 4, Svanberg and Struve, (J. f. pr. Ch. xliv, 257); 5, Wetherill, (Am. J. Sci. [2], xv, 443):

1.	Altenberg,		Mo 59·6	S 40·4=100, Brandes.
2.	Chester, Pa.	G = 4.444	59.42	39.68=99.10, Seybert.
3.	Smaoland,		58.627	40.573, gangue 0.800, S & S.
4.	Bohüslan,		57.154	39.710, " 3.136, S & S.
	Reading, Pa.		55.727	38 198, Fe 3 495, Si 2 283,
				H. 0.297, Wetherill.

B.B. infusible, but sulphurous fumes emitted, which are deposited on the charcoal. In the forceps, flame greenish; a dull brown pearl with borax on adding nitre. Dissolves in nitric acid, excepting a white or grayish residue.

Molybdenite generally occurs imbedded in, or desseminated through, granite, Molybdentte generally occurs imbedded in, or desseminated through, grante, gneiss, zircon-syenite, granular limestone, and other crystalline rocks. At Numedal in Sweden, Arendal in Norway, and Greenland, it has been observed in hexagonal prisms. Altenberg and Ehrenfriedersdorf in Saxony, Schlackenwald and Zhnnwald in Bohemia, Rathausberg in Salzburg, Laurvig in Norway, Chessy in France, Peru, Brazil, are among its foreign localities. At Caldbeck Fell in Cumberland, it is associated with tungstate of lime and apatite; it also occurs at several of the Cornish mines; in Scotland at Peterhead, Glenelg, and at Corby on Loch

In Connecticut at Haddam, and the adjoining towns on the Connecticut river, it occurs in gneiss in crystals and large plates; also at Saybrook. In Vermont at West-moreland, there is a large vein of molybdenite; at Newport, with crystals of white apatite. In Massachusetts at Shutesbury, east of Locke's pond; at Brimfield, with folite. In New Hampshire, at Westmoreland, four miles south of the north village meeting house, in a vein of mica slate, where it is abundant; at Llandaff, in regular tabular crystals; at Franconia. In Maine at Blue Hill Bay and Camdage farm, in tabular crystals; at Franconia. In Maine at Blue Hill Bay and Camdage farm, in large crystallizations; also at Brunswick, Bowdoinham, and Sanford, but less intersating. In Now York, two miles southeast of Warwick, in irregular plates associated with rutile, zircon, and pyrites. In Pennsylvania, in Chester, on Chester trash, near Reading; near Concord, Cabarras Co., N. C., with pyrites in quartz. In that and thalaam Lake, Terrace Cove, Lake Superior and St. Jerome, C. E. That to such as a business by its business and also by its babesies.

Distinguished from plumbago by its lustre and streak, and also by its behavior

before the blowpipe and with seids.

4. SKUTTERUDITE DIVISION.

SKUTTERUDITE, Haidinger. Tesseralkies, Breit. Hartkobaltkies. Hartkobalterz. Arsenikkobaltkies. Modumite, Nicol.

Monometric. Observed planes O, 1, 2, I. Figs. 1, 11, 14, 39. Cleavage: cubic, distinct; I, in traces. Also massive granular. II.=6. (†.=6.74—6.84. Lustre bright metallic. Color between tin-white and pale lead-gray, sometimes iridescent

Composition.—Co As = Arsenic 79°2, cobalt 20°8. Analyses: 1, Scheerer, (Pogg. xlii, 545); 2, 3, Wöhler, (ib. xliii, 591):

- 1. Skutterud,
 As 77.84
 Co 20.01
 Fe 1.51
 S 0.69=100.05, S.

 2. " cryst.
 79.2
 18.5
 1.3 =99.0, W.

 3. " mass.
 79.0
 19.5
 1.4 =99.9, W.
- B.B. nearly like smaltine. Yields a sublimate of metallic arsenic in a closed tube. From Skutterud near Modum, in Norway.

2. DOUBLE BINARY COMPOUNDS.

- I. THE PERSULPHURET A SULPHURET OF AN ELEMENT OF THE HYDROGEN GROUP, AS OF IRON, COBALT, OR NICKEL.
 - 1. LINNÆITE GROUP.-Monometric.

LINNEITE, (Eu, Co) S+Co² S³. SIGENITE, (Ni, Co, Fe) S+(Ni, Co, Fe)² S³.

2. CHALCOPYRITE GROUP.—Dimetric, Tetrahedral.

Chalcopyrite, CuS+Fe²S². ?Tin Pyr.

?Tin Pyrites, Eu S+(Fe2 S2, Sn2 S3).

3. STERNBERGITE GROUP.-Trimetric.

STERNBERGITE,

Ag S+2 Fe2 S3.

LINN.EITE, Haid. Cobalt Pyrites. Sulphuret of Cobalt. Kobaltkies. Schwefelkobalt. Kobaldine, Beud. Carrollite, Faber. Siegenite.

Monometric. Figs. 11, 15, 16. Cleavage: cubic, imperfect. Twins; plane of composition octahedral. Also massive, granular to impalpable.

H.=5.5. G.=4.8—5; 4.85, Carrollite, S. and B. Lustre metallic. Color pale steel-gray, tarnishing copper red. Streak blackish-gray. Fracture uneven or subconchoidal.

Composition.—Co S+Co² S³, (Frankenheim)—Sulphur 420, cobalt 580. Cobalt sometimes replaced by copper or nickel. Analyses: 1, Hisinger, (Afhaud. iii, 319); 2, 3, Wernekink, (Schw. J. xxxix, 306, and Leonh. Zeit. f. Min. 1826); 4, 5, Smith and Brush, (Am. J. Sci. [2], xvi, 367); 6, Schnabel, (Ramm. 4th Suppl. 117); 7, Ebbinghaus, (ib.):

```
Co
1. Riddarhyttan, 38.50
                                 48-20
                                          14.40
                                                    3.53, gangue 0.38=99.96, Hisinger.
                                                    5·31, gangue 0·67=94·94, Wernekink.
2·30=98·87, Wernekink.
2. Müsen,
                       41.00
                                 43.86
                                            4.10
                                                   2 00=98 87, Wernekink. [4 85. 1 26, Ni 1 54, As tr.=99 46, S. & B. G.= 1 55, " 1 54, " tr.=100 03, S. & B. 2 29, " 33 64.=100 Saknakal C.
                       42.52
                                 53.35
                                            0.97
   Carrollite,
                                 37.25
                                          17.48
                       41.98
                       40.94
                                 38.21
                                          1779
                                                    2·29, "33·64,=100 Schnabel. G.=4·8.
   Siegenite,
                       41.98
                                 22.09
                                                    4.69, "42.64=100.63, Ebb. G.=5.0.
                       42.30
                                 11.00
```

Carrollite, according to the analyses of Smith and Brush, is a Copper-Linnwite en S-Co² S².

Siegenite (Kobalt-Nickelkies, Rammelsberg) is a Nickel-Linnaite=(Ni, Co, Fe) S+(Ni, Co, Fe) S.

B.B. on charcoal gives a sulphurous odor, and after roasting colors glass of borax blue. Dissolves in nitric acid, excepting the sulphur.

Occurs in gneiss with copper pyrites at Bastnaes near Riddarhyttan, Sweden, and at Müsen near Siegen, in Prussia, with heavy spar and spathic iron. Also at Mine La Motte, Missouri, with galena and black cobalt. Carrollite is found at Finksburg, Carroll Co., Maryland, with copper pyrites, (W. L. Faber, Am. J. Sci., [2], xiii, 418). The Siegenite is from Siegen and occurs in octahedrons.

CUBAN, Breit., Pogg., lix, 325, 1848.

Monometric. In cubes or massive. Color between bronze and brass-yellow. Streak dark-reddish bronze, black. II.=4. G.=4.026, Br.; 4.169, Booth.


Composition.—Cu S+Fe² S³, Booth. Analyses: 1. Eastwick. (communicated by J. C. Booth); 2, Magee, (ib.); 3, Stevens. (ib.); 4, Scheidauer. (Pogg. lxiv, 280):

s	Cu	Fe	₿i
39:01	19:80	38.01	2.30 = 99.12
39:35	21.05	38.80	1.90=101.10.
39.05	20.12	38.29	2.85 = 100.31
34.78	22:96	42:51	Ph tr 100:95


Breithaupt obtained in repeated trials 19 per cent. of copper. B.B. fuses easily, giving off fumes of sulphur, but no arsenic. With 2 of copper instead of 1, the composition would be analogous to that of Linneite.

From Barracanao, Cuba.

CHALCOPYRITE, Bend. Copper Pyrites. Yellow Copper Pyrites, Pyritou Copper. Kupferkies. Cuivre Pyriteux. Towanite, B. & M.



```
Dimetric; tetrahedral. O: 1i=135^{\circ} 25'; a=98556.
O: \frac{1}{4} = 145^{\circ} 8'. \quad O: 2i = 116^{\circ} 54'.
                                                                 2:2 (pyr.)=96° 33′.
                             0:\frac{3}{4}i=124^{\circ} 5'. \frac{3}{4}:\frac{3}{4} (pyr.)=100° 44'. 1:1(pyr.)=109° 53'. 1:1 (f.294)=71° 20' and
O: \bar{1} = 125^{\circ} 40'.
0:2=109^{\circ}44'.
```



Cleavage: 2i sometimes distinct; O, indistinct. Twins: plane

of composition, (1) 1i, f. 295, 295A; in the last, composition parallel to 4 terminal edges of a pyramid: (2) 1, similar to f. 200; (3) ii, similar to f. 207. Often massive and impalpable.

II.=3.5—4. G.=4.1—4.3. Lustre metallic. Color brass-yellow; subject to tarnish, and often iridescent. Streak greenish-black—a little shining. Opaque. Fracture conchoidal, uneven. Rather sectile.

Composition.—Eu S+Fe S, Ramm.=Sulphur 34.9, copper 34.6, iron 30.5=100. But some analyses give other proportions, and probably from admixture with iron pyrites. Analyses: 1, II. Rose, (Gilb. lxxii, 185); 2, Hartwall, (Leonh. Handb. 646); 3, 4, C. Bechi, (Am. J. Sci. [2], xiv, 161); 5, S. D. Forbes, (Jameson's J. l, 278):

1. Sayn, S 35·87 Cu 34:40 Fe 30:47 quartz 0:27=101:01, Rose. 2. Finnland, 2.23=100.79, Hartwall. 36:33 32.20 80.03 3. Val Castrucci, 35.62 4. Mt. Catini, 36.16 —=100.00, Bechi. 0.86= 99.56, Bechi. 34 09 30.29 29.75 32.79 5. Norway, 33.88 32.65 32.77 Mn tr. Si 0.32=99.62, Forbes.

Other analyses: Malaguti and Durocher, (Ann. des M. [4], xvii, 299).*

This ore is often mixed with iron pyrites indefinitely, and the color becomes correspondingly paler.

B.B. on charcoal blackens, but becomes red on cooling. After a continued heat it fuses to a globule which is magnetic. With borax affords pure copper. Dissolves in nitric acid, excepting the sulphur, forming a green solution. A drop of liquid ammonia changes it to a deep blue.

Chalcopyrite is the principal ore of copper at the Cornish mines, and 10 to 12,000 tons of pure copper are smelted annually from 150 to 160,000 tons of ore. It is there associated with tin, erubescite, copper glance, galens, gray copper, and blende. The copper beds of Fahlun in Sweden, are composed principally of this ore, which

For analyses of different ores from New Hampshire, see Geol. Rep. of that State, by C. T. Jackson, p. 214.

occurs in large masses, surrounded by a coating of serpentine, and imbedded in gneiss. At Rammelsberg, near Goslar in the Hartz, it forms a bed in graywacke slate, and is associated with iron pyrites, galena, blende, and minute portions of silver and gold. The Kurprinz mine at Freiberg affords well, defined crystals. It occurs also in the Bannat, Hungary. Thuringia; in Scotland in Kirkeudbright and Wigtonshires, in Perthshire and Invernessshire; in Tuscany, (analyses, 3, 4); in South Australia.

In the United States it occurs at the Southampton Lead Mines, Mass., at Turner's falls on the Connecticut, near Deerfield, and at Hatfield and Sterling, Mass.: in Vermont, at Stafford, and at Corinth, Waterbury, and Shrewsbury: in New Hampshire, at Franconia, in gneiss; at Unity, on the estate of James Neal; at Warren, on Davis's farm; at Eaton, two miles northeast of Atkins's tavern; at Lyme, east of East Village; at Haverhill and elsewhere: in Maine, at the Lubec lead mines, and at Dexter: in Connecticut, at Bristol and Middletown, sometimes in crystals: in New York, at the Ancram lead mine; five miles from Rossie, beyond DeLong's mills at the Rossie lead mines in crystals; in crystals and massive near Wurtzborough, Sullivan Co.; crystals and massive at Ellenville, Ulster Co.: in Pennsylvania, at Phenixville; at Pottstown, Chester Co., (Elizabeth Mine): in Virginia at the Phenix copper mines, Fauquier Co., and the Walton gold mine, Louisa Co.: in North Carolina near Greensboro', abundant massive, (Fenress or North Carolina, and Macculloch Mines), along with spathic iron in a quartz gangue: in Tennessee, 30 miles from Cleveland, in Polk Co., (Hiwassee Mines), with black copper and pyrites: in the Catoetin Mts., Maryland, and between Newmarket and Taneytown; also abundant near Finksburg, Carroll Co., Md., (Patapseo and other Mines), along with erubescite, carrollite, and malachite; in Canada, in Perth; extensively mined at Bruce mines, on Lake Huron.

The Cornwall copper pyrites is not a rich ore; what is picked for sale at Redruth rarely yielding 12, generally only 7 or 8, and occasionally but 3 or 4 per cent. of metal. Its richness may in general be judged of by the color; if of a fine yellow hue, and readily yielding to the hammer, it may be considered a good ore; but if hard, and pale-yellow, it is poor from admixture with iron pyrites.

Copper pyrites is readily distinguished from iron pyrites, which it somewhat re sembles, by its inferior hardness; it may be cut by the knife, while iron pyrites will strike fire with steel. The effects of nitric acid are also different. It differs from gold in being brittle, on which account it cannot be cut off in slices, like the latter metal; and moreover gold is not attacked by nitric acid.

Occurs as a furnace product near Goslar. Chalcopyrite is from χαλκος, brass and pyrites.

ALTERED FORMS.—Changes on exposure with moisture, especially if heated, to a sulphate. Malachite, Covelline, Chrysocolla, Black Copper, Copper glance, and oxyd of iron, are other forms into which it is sometimes altered.

TIN PYRITES. Stannine, Beud. Sulphuret of Tin, P. Bell Metal Ore. Zinnkies, W. Etain Sulfuré, H.

Probably dimetric and hemihedral like chalcopyrite, Kengott. Commonly massive, granular, and disseminated.

H.=4. G.=4·3—4·522; 4·506, Zinnwald. Lustre metallic. Streak black. Color steel-gray to iron-black, sometimes a bluish tarnish; often yellowish from the presence of copper pyrites. Opaque. Fracture uneven. Brittle.

Composition.—Qu S (Sn² S³, Fe² S³), Kengott, analogous to Chalcopyrite—(ratio of S, Sn, Qu, Fe, being 4:1:1:1). Sulphur 30:0, tin 27:2, copper 29:7, iron 13:1=100. Analyses: 1, Klaproth, (Beit. v. 228); 2, Kudernatsch, (Pogg. xxxix, 146); 8, Johnston, (Rep. Geol. Cornwall, &c., 1839); 4, Rammelsberg, (Pogg. lxxxviii, 607); 5, Mallet, (Am. J. Sci., [2], xvi, 33);

Я Sn Cu 1. Huel Rock, 30.2 26.5 30.0 120 =990, Klaproth. 12.44 29.64 25.55 29.89 177, gangue 1 02=9981, Kud. 3, St. Michael's Mt., 29'929 31'618 23'549 4.791 10.113=100, Johnston. 29.46 26.85 29.18 6.73 7.26, gangue 0.16=99.64, Mal. 9.66=99.98, Rammelsberg. 29.38 5. Zinnwald, 29.05 25.65 6.24

B.B. on charcoal sulphur is expelled, and afterwards a black scoriaceous globule s obtained; the charcoal is covered with the oxyd of tin. With soda and borax rields a globule of impure copper. Soluble in nitro-muriatic acid, with the excepion of sulphur.

This species is found at Huel Rock, in the parish of St. Agnes. Cornwall, where it orms a considerable vein, and is accompanied by iron pyrites, blende, and other ninerals; also in granite at St. Michael's Mount; also at Zinnwald in the Erzgepirge with blende and galena. It frequently has the appearance of bronze or bell netal, and hence the name bell-metal ore.

STERNBERGITE, Haidinger, Edinb. Phil. Trans. xl, 1, and Brewster's Journal,

296 $I: I=119^{\circ} 30', O:17=$ Trimetric. 124° 49′, B. & M.; a:b:c=1.4379:1:1.7145. O:1 (e)=121°, O:2 (e)=106° 43', O:2i=120° 48'. Strike of O macrodiagonal, of sides horizontal. Cleavage: basal highly eminent. Commonly in implanted crystals, forming rose-like or fan-like

aggregations. Sometimes compound parallel to I.
H.=1-1.5. G.=4.215. Lustre of O brightly metallic. Color pinchbeck-brown, occasionally a violet-blue tarnish on e and e'. Streak black. Opaque. Thin laminæ flexible; may be smoothed down by the nail when bent, like tin foil. Very sectile. Leaves traces on paper like plumbago.

Composition. Ag S+2 Fe² S³ (!)=Sulphur 33.7, silver 32.5, iron 33.7. Ratio of sulphur, iron and silver more exactly 6: 4:1. Analysis by Zippe, (Pogg. xxvii,

Sulphur 30.0. Silver 33.2, Iron 36.0=99.2.

Heated in a glass tube it gives off a sulphurous odor, loses lustre, and becomes dark-gray and friable. B.B. on charcoal burns with a blue flame, and melts to a globule which is generally hollow, has a crystalline surface, is covered with metallic silver, and acts on the magnetic needle, exhibiting the properties of sulphuret of iron. With borax, a globule of silver may be obtained.

Occurs with ores of silver, particularly Pyrargyrite and Stephanite, at Joachimstahl in Bohemia, and Johanngeorgenstadt in Saxony. Named after Count Casper Stephaner of Prague.

Sternberg of Prague.

The Flexible silver ore (Argent sulphuré flexible, Bour., Biegsamer Silberglanz) from Himmelsfürst, near Freiberg, is referred here. According to Brooke & Miller the figure by Phillips is a distorted figure of silver glance. The angles of sternbergite, above given, are from very perfect crystals in Mr. Brooke's collection, which were formerly in the possession of Count Bournon, (B. & M., p. 180). The plane 21 is on the edge O: ii; and besides this, there is another 100, represented by these authors. with also the macrodome 61, and the pyramid 27.

II. THE PERSULPHURET A SULPHURET OF ELEMENTS OF THE ARSENIC GROUP.*

1. Persulphuret of the form R² S³.

1. WOLFSBERGITE GROUP, III.	Wolfsbergite,	eu s+sb³ s³
	? TANNENITE,	Cu S+Bi ³ S ³
	Berthierite,	Fe S+Sb ² S ²
	Zinkenite,	Pb S+Sb2 S2
2. MIARGYRITE GROUP, IV.	Miargyrite,	Ag S+Sb* S*
8. PLAGIONITE GROUP, IV.	Plagionite,	Pb S+48b2 S2
4. JAMESONITE GROUP, III.	Jamesonite,	Pb S+4Sb2 S2
5. HETEROMORPHITE GROUP, II	I. Нетевомоврніте,	Pb S+4Sb* S*
	i Brongniardite,	(Pb, Ag) S+1 Sb2 S3
	? Chiviatite,	(Cu, Pb) S+1 Bi S
6. DUFRENOYSITE GROUP, I.	DUFRENOYSITE,	Pb S++ As S
7. FREISLEBENITE GROUP, IV.	FREISLEBENITE,	i (Pb, Ag) S+4Sb ³ S ³
8. PYRARGYRITE GROUP, VI.	Pyrargyrite,	Ag S+1 Sb2 Sb2
	PROUSTITE,	Ag S+1 As2 S2
9. BOURNONITE GROUP, III.	Bournonite,	(Eu, Pb) S+1 Sb2 S3
	Boulangerite,	Pb S+1 Sb2 S2
	? Aciculite,	(Cu, Pb) S+1 Bi S S
	Wolchite,	
10. KOBELLITE GROUP,	Kobellite,	(Pb, Fe) S+3 (Sb, Bi) S1
11. TETRAHEDRITE GROUP, 1.	Tetrahedrite,	R S+1 (Sb, As)2 S2
	TENNANTITE,	R S+1 As2 S2
12. GEOCRONITE GROUP, III.	Geograpite,	Pb S+1 (Sb, As)2 S2
13. STEPHANITE GROUP, III.	STEPHANITE,	Ag S+1 Sb2 S2
14. POLYBASITE GROUP, VI.	POLYBASITE,	(Ag. Cu) S+1 (Sb. As) S

2. Persulphuret of the form R2 S5.

ENARGITE, III. R S+1 (As, Sb) Sb. XANTHOCONE, VI. $(3Ag S + As^2 S^5) + 2(3Ag S + As^2 S^3).$ FIREBLENDE.

APPENDIX. WITTICHITE, eu s+Bi2 S1

* In this table, the system of Crystallization is indicated by Roman numerals, 45 follows:

I. Monometric System,
II. Dimetric System,
III. Trimetric System,
VI. Hexagonal System,
VI. Hexagonal System,
III. Trimetric System,
III. Trimetric System,
III. Trimetric System,
III. Trimetric System,
VI. Hexagonal System,
VI. Hexagonal System,
III. Trimetric System,
VI. Hexagonal System,
III. Trimetric System,
VI. Hexagonal System,
III. Trimetric System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Triclinic System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VI. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII. Hexagonal System,
VII.

WOLFSBERGITE, Nicol. Antimonial Copper. Sulphuret of Copper and Antimony, H. Rose. Kupferantimonglanz, Zincken. Chalcostibites, Glocker.

Trimetric. $I: I=101^{\circ}, i_{\overline{2}}: i_{\overline{2}}=138^{\circ} 12', i_{\overline{2}}: i_{\overline{2}}=112^{\circ} 24'$. In small aggregated tabular prisms presenting the planes O, I, i_2, i_3 . Cleavage: ii, very perfect; O, less so.

H.=3-4. G.=4.748. Lustre metallic. Streak black. Color between lead-gray and iron-gray. Opaque. Fracture conchoidal. Composition.—Cu S+Sh2S2=Sulphur 25.0, antimony 50.2, copper 24.8=100.

Analysis by H. Rose, (Pogg. xxxv, 361);

S 26.34, Sb 46.81. Cu 24.46, Fe 1:39, Pb 0:56=99:56.

The iron is supposed to exist as pyrites, and the lead as feather ore.

B.B. decrepitates, fuses readily, and gives on charcoal fumes of antimony; also after a strong heat with soda a globule of copper.

From Wolfsberg in the Hartz, in nests imbedded in quartz. It is usually covered with a coating of pyrites. Glocker's name antedates Nicol's, but it was given as a Latin generic name, the species being called by him Chalkostibites Hercynius.

TANNENITE. Kupferwismuthglanz, R. Schneider, Pogg. xc, 166, 1853.

Trimetric? In thin striated prisms. Lustre bright metallic. Color grayish to tin-white.

Composition.—Gu S+Bi² S³=Sulphur 19·1, bismuth 62·0, copper 18·9. Analysis by R. Schneider, (loc. cit.):

Sulphur 18.83, Bismuth 62.16, Copper 18.72=99.71.

In an open tube yields sulphur; B.B. on coal fuses easily with intumescence, and gives with soda a globule of copper. Nitric acid solution deep bluish green, becoming dark blue with ammonia.

From Tannenbaum in Johanngeorgenstadt.

BERTHIERITE, Poggendorff. Haidingerite of Berthier.

In elongated prisms or massive; a longitudinal cleavage rather indistinct. Also fibrous massive, plumose; also granular.

H.=2-3. G.=4-4.3. Lustre metallic, less splendent than gray antimony. Color dark steel-gray, inclining to pinchbeckbrown: surface often covered with iridescent spots.

Composition.—Fe S+Sb²S²=Sulphur 28.9, antimony 58.4, iron 12.7=100. Anal yees: 1, 2, 3, Berthier, (Ann. Ch. Phys. xxxv, 51); 4, 5, Rammelsberg, (Pogg. xl, 153); 6, Pettko, (Haid. Ber. i, 62):

```
Sb
                                               0:30=98.6, Berthier.
==100, Berthier.
1. Chazelles,
                   80.3
                            52·0
                                      16.0
2. Martouret,
                  28.81
                            61.34
                                       9.85
  Anglar,
                                      12.17
                                                    -=100, Berthier.
                   29.18
                            58.65
                                               trace, Mn 0.456=97.834, Rammeleberg. 0.737, " 2.544=100.739, "
4. Braunsdorf,
                  80.575
                            54.338
                                      11.965
                  31.326
                            54.700
                                      11.432
6. Arany Idka, 29.27
                            57.88
                                      12.85
                                                    -=100, Pettko. G.= 4:043.
```

Anal. 3-6 correspond to the above formula.

No. 1=3FeS+2Sb²S³=Sulphur 29.6, antimony 53.1, iron 17.3=100. No. 2=3FeS+4Sb²S²=Sulphur 28.6, antimony 61.4, iron 10.0=100.

B.B. on charcoal fuses readily, gives out fumes of antimony, and forms a black magnetic slag. Dissolves readily in muriatic acid, giving out sulphuretted hydrogen. Occurs at Chazelles and Martouret in Auvergne, associated with quartz, calcareous par, and iron pyrites; in the Vosges, Commune of Lalaye, containing about 32 of to 18 of Fe; at Anglar in La Creuse; also at Bräunsdorf in Saxony, and at Tintagel and Padstow in Cornwall; at Arany Idka in Hungary. Yields antimony, but of inferior quality.

ZINKENITE, G. Rose, Pogg. vii. Brewster's Journal, vi, 17.

Trimetric. I: I=120° 39', Rose; 120° 34, Kengott. Usual in twins, as hexagonal prisms, with a low hexagonal pyramid at summit; angle at pyramidal edge=165° 26'; I on face of pyramid=104° 42'. Lateral faces longitudinally striated. Sometimes columnar, fibrous or massive. Cleavage not distinct.

 $H_{\bullet}=3-3\cdot5.$ $G_{\bullet}=5\cdot30-5\cdot35.$ Lustre metallic. Color and streak steel-gray. Opaque. Fracture slightly uneven.

Composition.—PIS+Sb³S³=Sulphur 21.6, antimony 43.5, lead 34.9=100. Analyses: 1, 2, H. Rose, (Pogg. viii, 99); 3, Kerl, (B. u. H. Ztg., 1853, No. 2):

- Cu 0.42=99.23. 1. Wolfsberg, S 22.58 Sb 44.39 Pb 31.84
- 44.11 undet. 31.97 undet.
- 21.22 48.98 30.84 Ag 0.12, Fe 1.45=97.61, K.

B.B. alone on charcoal, decrepitates briskly, and fuses as readily as gray anti-mony, affording small metallic globules, which are volatilized, and the charcoal is covered with a coating of oxyd of lead. With carbonate of soda, yields globules of metallic lead. With muriatic acid forms chlorid of lead.

Occurs in the antimony mine of Wolfsberg in the Hartz; the groups of columnar crystals occur on a massive variety in quartz; the crystals sometimes over half as inch long, and two or three lines broad, frequently extremely thin and forming fibrous masses. Named in honor of Mr. Zinken, the director of the Anhalt mines, by G. Rose. Has been reported from St. Trudpert in the Schwarzwald.

Resembles gray antimony and bournonite, but may be distinguished by its sup-

rior hardness and specific gravity.

Kengott makes the crystallization monoclinic, and the pyramidal planes oblique basal planes; but such twins with pyramids so formed are not known among monoclinic species. (See page 152, vol. 1).

MIARGYRITE, H. Rose.

Monoclinic; <i>U</i> =81° 36′, <i>I</i> : <i>I</i>	i				<u> </u>			
$39^{\circ} 38', 0: 1i=109^{\circ} 9'; a:b:$ $a: b: 3565.$;	·					176	<u> </u>
$O: 1i = 138^{\circ} 26'$	-	 :					1	
$O: 3i-116^{\circ} 2'$		<u> </u> '.		· 	-		1	
$0: \frac{1}{4} = 142^{\circ} 6'$	-	; :		· -		·		
$(t): \frac{1}{8} = 134^{\circ} 17'$	·	Ĺ					3	
$O: \frac{1}{2} = 123^{\circ} 38'$	1	:					2	
$O: \bar{1} = 109^{\circ} 36'$	1i				,	. 12	1	11
$O: I = 92^{\circ} 40'$ $O: -2 = 119^{\circ} 47'$. —	·				22		
1: 1 (front)= 53° 16′	9:	<u> </u> -		33				
2: -2 " = 38° 44′	31	·			·——	40		
$22: 22 \text{``} = 77^{\circ} 13'$;			' 	42		
55: 55 " =115° 54′		·	55					
38: 33 " = 95° 59' $13: 13 " = 106° 21'$					73			
13: 13 " =106° 21′ 16: -16 " =141° 1′	ii			iS			1	iì
i3: i3 " = 90° 30'	-		_				-2	
Crystals thick tabular, pyra-		-16		-18				11
midal or short prismatic. Lateral			_					
planes deeply striated. Cleav-	·							
age: ii, 1i, imperfect.			Of	BOTTE	Plan	95 .		

G = 5.2 - 5.4Lustre submetallic-adamantine. H = 2 - 2.5. Color iron-black. Streak dark cherry-red. Opaque, except in thin splinters, which, by transmitted light, are deep blood-red. Fracture subconchoidal. Very sectile.

Composition.—Ag S+Sb²S²=3ulphur 21·2, antimony 42·9, silver 35·9. Analysis by H. Rose, (Pogg. xv, 469):

S 21.95, 8b 89·14, Ag 36:40 Cu 1.06, Fe 0.62=99.17.

In an open tube fuses easily and gives a sublimate of oxyd of antimony and sulphurous acid. On charcoal with soda reduced, and a globule of silver obtained. Observed only at Braunsdorf, near Freiberg in Saxony, associated with argentiferous arsenical pyrites. Named from μειων, less, άργυρος, silver, because it contains less silver than some kindred ores.

The Hypargyrite of Breithaupt contains, according to Plattner, 35 per cent. silver, and is probably a variety of the above.


PLAGIONITE, G. Rose, Pogg. xxviii, 421, 1833.

Monoclinic. $C=72^{\circ}$ 28', $I:I=85^{\circ}$ 25', $O:1i=158^{\circ}$ 9', Rose; a:b:c=0.37015:1:0-8802. Observed planes as in the annexed figure.

O: 1=154° 20, O: ii=107° 32′. O: 2=138° 52, 1:1=142° 3′. $0:-1=149^{\circ}$. $2:2=120^{\circ}49'$.

Crystals thick tabular; the plane O shining and smooth; others striated. Cleavage: 2, perfect, but seldom affording smooth surfaces. Also massive, granular.

H.=2.5. G.=5.4. Lustre metallic. Color blackish lead-gray. Opaque. Brittle.



Composition.-PbS+4Sb2S2-Sulphur 20.6, antimony 38.3, lead 41.1. Analyses: 1, H. Rose, (Pogg. xxviii, 428); 2, Kudernatsch, (Pogg. xxxvii, 588):

Sb 37.94 1. Wolfsberg, S 21.53 Pb 40.52=99.99, Rose. 40.98=100, Kudernatsch.

B.B. decrepitates and fuses easily, affording fumes of sulphur and oxyd of anti-

Dony, and coating the charcoal with oxyd of lead.

Occurs at Wolfsberg in geodes and druses of crystals in massive plagionite, or crystallized on quartz, and was discovered by Zincken. Named, in allusion to its

Taking the planes 2, 2, as the lateral faces of the fundamental prism, the lateral angle is nearly the same as in Freislebenite.

JAMESONITE, Haid. Bleischimmer.

Trimetric. $I: I=101^{\circ} 20'$ and $78^{\circ} 40'$. Observed planes, I, ii. **Cleavage:** basal, highly perfect; I and ii less perfect. Sometimes capillary. Also massive, structure columnar, particles delicate, straight, and parallel or divergent.

H.=2-2.5. G.=5.5-5.8; 5.564, Haidinger. Lustre metallic. Color and streak steel-gray. Opaque. Sectile.

Composition.-PhS+4 Sb2 S1-Sulphur 202, antimony 362, lead 436. Analys 1, 2, H. Rose, (Pogg. viii, 101); 3, Schaffgotsch, (Pogg. xxxviii, 403); 4, C. Bechi, (Am. J. Sei. [2], xiv, 60):

```
8
                22.15
                         34.40
                                  4075
                                          230 0-13-9973, Rose.
1. Cornwall,
                                               0-19, Fe, Pb, Zn 0-74-9972, Rose.
                22.53
                         34-90
                                  3871
                                          265
                                          3-63
                                                   - Bi 1-06, Zn 0-42--99-48, Sch.
3. Estremadura, 2178
                         32.62
                                 39-97
                20.53
                         32.16
                                 43.38
                                         0.94
                                               125, Zn 174=160, Bechi
4. Tuscany,
```

B.B. in an open tube affords dense white fumes of oxyd of antimony; on charcoal

decrepitates, fuses readily, and almost wholly passes off in fumes.

Occurs principally in Cornwall, associated with quartz and minute crystals of Bournonite; occasionally also in Siberia, Hungary, Spain, and Brazil. Its perfect cleavage at right angles with the vertical axis, is sufficient to distinguish it from the species it resembles. Named after Prof. Jameson of Edinburgh.

HETEROMORPHITE, Ramm. Feather Ore. Plumosit, Heid. Federerz.

In capillary forms resembling a cobweb. Also massive.

H = 1 - 3. G. = 5.67 - 5.9; 5.6788, massive, Poselger. Lustre dull metallic. Color dark lead-grav—steel-grav, sometimes irised.

Composition.—PbS+1 Sb3 Sasuphur 19-2, antimony 31-0, lead 49-8. Analyses: 1, H. Rose, (Pogg. xv, 471); 2, Rammelsberg, (Pogg. Ann. lxxvii, 241); 3, Poselger, (Ramm. 3d Supp. 44); 4, 5, C. Bechi, (Am. J. Sci., [2], xiv, 60):

```
Sb
   Wolfsberg, plumose, 1972
                                    46.87
                                           1.30 0.08=99.01, Rose.
1.
                             31 04
2.
                      20.86
                             30.67
                                    4279
                                           2-83
                                                 1.84, Cu 1.01=100, Rose.
                                                      =10178, Poselger.
             massine,
                      20.82
                             32.98
                                    48.48
4. Tuscany, capil.
                       18.89
                             30.19
                                    47.68
                                                 1.08, Cu 1.11=9871, Bechi.
           acic.,
                       19.25
                            29.24
                                    49.31
                                                 0-21, " 2-00=100-01, Bechi.
```

Fuses instantly in the flame of a candle, evolving white fumes.

Occurs at Wolfsberg in the Eastern Hartz; also at Andreasberg and Clausthal; at Fraiberg and Schemnitz; in the Anhalt at Pfaffenberg and Meiseberg; in Twenny, near Bottino.

The name Feather Ore or Plumosite being inapplicable, since a massive variety has been found, Rammelsberg substituted Heteromorphite.

ZUMINERER, (Tinder Ore), supposed formerly to be Red Antimony, proves to be an impure arenical sulphuret of antimony and lead, supposed to be mixed with red silver ore and mispickel. Bornträger obtained in an analysis, (J. f. pr. Chem. saxv, 49), S 19'57, As 12'60, Sb 16'88, Pb 48'06, Ag 2'56, Fe 4'52-96'19. It is soft like tinder, and has a dirty dark reddish color. From Andreasberg and Clausthal in the Hartz

BROGNIARDITE, Damour, Ann. des M. [4], xvi, 227.

Massive without cleavage.

II. above 3. G. =5.950. Lustre like that of bournonite. Streak grayish-black.

Composition.—Pb S+Ag S+Sb2 S3, or (Pb, Ag) S+1 Sb2 S2=Sulphur 190, antimony 307, silver 257, lead 24.6=100. Analyses by Damour, (loc. cit.):

	н	Sb	Ag	Pb	Cu	Fe	Zn
1.	19.38	29.95	25.08	24.74	0.54	0.30	0.40=100.84
٧.	19.21	29.60	24.46	25~05	0.61	0.26	0.82 = 99.51.
g g	10.14	99.75	94.81	94.04	0.70	0.38	0.87-00.08

B.B. on charcoal decrepitates, fuses easily, giving off an odor of sulphur and white vapors; after roasting, yields a globule of silver, surrounded with a yellow

of lead. In a closed tube a feeble orange sublimate with a white one above; pen tube fuses, affords an odor of sulphur and a white sublimate of oxyd of ny. Rapidly attacked by concentrated nitric acid.

Mexico.

CHIVIATITE, Rammelsberg, Pogg. lxxxviii, 820.

liated massive; cleavable in three directions in one zone, one ng an angle with the second of 153°, and with the third of Miller.

=6.920. Lustre metallic. Color lead-gray.

position.—(Eu, Pb) S+1 Bi2 S3, R. Analysis by Rammelsberg, (loc. cit.):

S Bi Pb Cu Fe Ag insol. 18:00 60:95 16:73 2:42 1:02 trace 0:59=99:71.

like needle ore, which it is near in constitution.

n Chiviato, in Peru; along with Pyrites and Barytes. Resembles Bismuth

DUFRENOYSITE, Damour. Gotthardite, Rammelsberg.

onometric. Figure 43. Cleavage not distinct. =5.549. Lustre metallic. Color steel-gray. Streak reddishn. Brittle.


uposition.—PbS+\frac{1}{2}As^2S^2\leftharpoonup Stromorphite, arsenic replacing the antimony. Analyses by Damour, (Ann. bys. [3], xiv, 379):

matrass affords a red sublimate of sulphuret of arsenic. B.B. fuses easily, ig sulphurous acid and arsenical fumes, and a globule of lead. Dissolves in

are in dolomite at St. Gothard, with realgar, orpiment, blende, and pyrites.


RGYRITE. Dark-red Silver Ore. Ruby Silver, P. Black Silver. Ærosite. hgültigerz, W. Argyrythrose, Beud. Dunkles Rothgültigerz, G. Argent imonié Sulfuré, H. Antimonsilberblende. Argentum rubrum, Linn.

iombohedral. Opposite exities of crystals often unlike. $R=108^{\circ}$ 42', B. and M., $\ell = 137^{\circ}$ 42'; a=0.788. Obd planes: rhombohedral, $\frac{1}{4}$, $\frac{1}{4}$, $\frac{1}{4}$, $\frac{1}{5}$, $\frac{1}{7}$, $\frac{1}{7}$, $\frac{1}{4}$, $\frac{2}{5}$, $\frac{1}{8}$, $\frac{1}{4}$, pyramidal, $\frac{2}{3}$ 2; and $\ell = 0$, $\ell = 0$, $\ell = 0$.



$$\begin{array}{lll} :\frac{1}{2}=155^{\circ}\ 32', & \frac{1}{2}:\frac{1}{2}=137^{\circ}\ 58', & R:\frac{1}{2}=144^{\circ}\ 21', \\ :1^{3}=112^{\circ}\ 33', & i2:R=125^{\circ}\ 39', & R:\frac{1}{2}=164^{\circ}\ 5', \\ :1^{7}=100^{\circ}\ 14', & i2:1^{3}=155^{\circ}\ 4', & i2:2=120^{\circ}. \end{array}$$

Cleavage: R rather imperfect. Twins: plane of composition—as in f. 300, which consists of four individuals; O or basal plane, as in f. 300A; also R and I. Also massive, structure granular, sometimes impalpable.



H.=2-2.5. G.=5.7-5.9. Lustre metallic-adamantine. Color black, sometimes approaching cochineal-red. Streak cochineal-red. Translucent—opaque. Fracture conchoidal. Sectile, yielding readily to the knife.

Composition.—Ag S+1 Sb³ S²=Sulphur 17·5, antimony 23·5, silver 59·0. Analyses: 1, Bonsdorff, (K. V. Ac. H. 1821, 338); 2, Wöhler, (Ann. d. Pharm. xxvii, 157; 3, Böttger, (Ramm. Handw. ii, 106):

	S	Sb	Ag
 Andreasberg, 	16.61	22 85	58.95, gangue 0.30=98.70, Bonsdorff.
2. Mexico,	18.0	21.8	60·2 =100, Wöhler.
3. Zacatecas, Mex.,	17-76	24.59	57.45=99.80. Böttger.

B.B. fuses and gives out fumes of antimony; ultimately on charcoal a globule of silver is obtained. Dissolves in heated nitric acid, leaving sulphur and oxyd of antimony.

The dark-red silver ore occurs principally with calcareous spar, native arsenic, and galena, at Andreasberg in the Hartz; also in Saxony, Hungary, Norway, at Gaudalcanal in Spain, and Cornwall. In Mexico it is worked extensively as an ore of silver.

A light-red ore from Andreasberg, according to Zincken, contains no arsenic. A gray ore from the same locality contains both arsenic and antimony, and may be miargyite.

ALTERED FORMS.—Occurs like Proustite, changed to Silver glance, (Ag S); also to

PROUSTITE. Light red Silver Ore. Lichter Rothgültigerz. Arseniksilberblende.

Rhombohedral. $R: R=107^{\circ}$ 48', $O: R=137^{\circ}$ 9'; a=0.78506. Observed planes: rhombohedral, $\frac{1}{4}$, 1(R), -2, $-\frac{3}{2}$, $-\frac{1}{2}$; scalenohedral, 1^{3} , 1^{5} , $\frac{1}{4}^{3}$; prismatic I, i^{2} ; basal, $O: \frac{1}{4}: \frac{1}{4}=137^{\circ}$ 16'. Simple forms and twins as in the preceding species. Also granular.

H.=2-2.5. G.=5.422-5.56. Lustre adamantine. Color cochineal-red. Streak cochineal-red, sometimes inclined to aurora-

red. Subtransparent—subtranslucent. Fracture conchoidal—uneven.

Composition .- Ag S+1 As2S2=Sulphur 19.4, arsenic 15.2, silver 65.4. Analysis by H. Rose, (Pogg. xv, 472):

Joachimstahl, S 19.51, As 15.09, Ag 64.67, Sb 0.69=99.96.

B.B. like the preceding, excepting it gives off arsenical fumes instead of oxyd of


Occurs in Saxony at Johanngeorgenstadt, Marienberg, and Annaberg; at Joachimstahl in Bohemia, Wolfach in Baden, Markirchen in Alsace, Chalanches in Dauphine, Guadaleanal in Spain, in Mexico and Peru.


FREISLEBENITE, Haid. Antimonial Sulphuret of Silver. Sulphuret of Silver and Antimony, P. Schilfglaserz, Freisleben. Silber-und-Antimon. Argent Sulfuré Antimonifère et Cuprifère, Levy.

Monoclinic. C=87° 46', I: I=119° 12', O: 1i=137° 10', (B. & M.); a:b:c=1.5802:1:1.7032.

Prisms longitudinally striated. Cleavage: I perfect.

H.=2-2.5. G.=6-6.4; 6.194, Hausmann. Lustre metallic. Color and streak light steel-gray, inclining to silver-white, also blackish lead gray. Yields easily to the knife, and is rather brittle. Fracture conchoidal—uneven.





301

Composition.—(PbS+Sb2S3)+2[3(Pb, Ag)S+Sb2S3, or (Pb, Ag)S+3/7 Sb2S3, Wöhler (Pb, Ag)S+4 Sb2 S3, is nearer the analysis, which may correspond to (Pb, Ag) S+4 Sb² S², together with $\frac{1}{9}$ Sb²S² (or gray antimony) as impurity. Analyses by Wöhler, (Pogg. xlvi, 146):

S 1877 Sb 2772 Pb 30 00 Ag 22 18, Fe 0 11 Cu 1 62 = 100. 1872 27 05 30 08 23 78 = 99 60.

B.B. on charcoal emits copious white vapors and a slight sulphurous odor, deposits oxyd of antimony and lead around the assay, and finally a white metallic globule remains.


Occurs with silver glance, spathic iron, and galena, in the Himmelsfürst mine, at Freiberg in Saxony, and Kapnik in Transylvania; also at Ratieborzitz, the ore of this region containing bismuth, according to Zincken.


An antimonial sulphuret of silver is said to occur with native ailver and native copper, at the copper mines of Michigan.

BOURNONITE. Endellionite, Bournon. Schwarz-spiessglaserz, W. Bleifahlerz, Spiessglanz-bleierz, Haus. Wheel Ore. Radelerz. Antimonić Sulfurė Plumbo-cuprifère, H.

Trimetric. $I: I=93^{\circ} 40', O: 1\bar{\imath}=136^{\circ} 17', a:b:c=0.95618: : 1.0662.$

```
O: \frac{1}{4}\bar{\imath}=154^{\circ}\ 27'. O: \frac{1}{4}=146^{\circ}\ 45'. 1:1\ (mac.)=114^{\circ}\ 6'. 0:\frac{2}{3}\bar{\imath}=147^{\circ}\ 29'. O:1=127^{\circ}\ 20'. 1:1\ (brach.)=109^{\circ}\ 6'. 0:1_{\bar{2}}=133^{\circ}\ 26'. O:\frac{2}{3}\bar{\imath}=144^{\circ}\ 29'. i_{\bar{2}}:i_{\bar{2}}\ (ov.\ i_{\bar{1}})=129^{\circ}\ 44'. 0:2_{\bar{2}}=115^{\circ}\ 20'. O:1_{\bar{1}}=138^{\circ}\ 6'. i_{\bar{2}}:i_{\bar{2}}\ (ov.\ i_{\bar{1}})=123^{\circ}\ 52'.
```





Observed Planes.

Cleavage: it imperfect; it and O less distinct. Twins: plane of composition I; crystals often cruciform, crossing at angles of 93° 40' and 86° 20'. Also massive, granular, compact.

H.=2·5-3. G.=5·7-5·9. Lustre metallic. Color and streak steel-gray, inclining to blackish lead-gray or iron-black. Opaque Fracture conchoidal or uneven. Brittle.

Composition.—(Eu, Pb)S+\(\frac{1}{4}\)Sb\(\frac{1}{2}\)S, or (8 Eu S+Sb\(\frac{1}{2}\)S\(\frac{1}{2}\)+2(8 Pb S+Sb\(\frac{1}{2}\)S\(\frac{1}{2}\), Rammelsberg.—Sulphur 19·4, antimony 26·0, lead 41·8, copper 12·8. Analyses: 1, E. Rose, (Pogg. xv, 573); 2, Sinding, (Ramm. Handw. 123); 3, 4, Dufr\(\frac{1}{2}\)no. (Ann. \(\frac{1}{2}\)Min. [8], x, 371); 5, 6, 7, 8, Rammelsberg, (Pogg. Ann. lxxvii, 253):

```
Sb
                                        Cu
1. Pfaffenberg,
                 20.31
                         26.28
                                40.84
                                       12.65=100.08, Rose.
                 19.63
                         25.68
                                41.38
                                        12.68=99 37, Sinding.
                                38.9
                                        12.8=100, Dufrénoy.
3. Alais,
                 19.4
                         29.4
                                        18.3=99.6, Dufrénoy.
                 17.8
                         28.3
                                40.2
4. Mexico.
                                        13.06=97.57, Ramm.
                 19.49
                         24.60
                                40.42
5. Meiseberg,
                                        15·16=99·01, Ramm.
18·06=100·04, Ramm.
                         24.82
                 18.99
                                40.04
7. Wolfsberg,
                 1976
                                42.88
                         24.84
                               35.52
                                        9.05, Ni & Co 5.47, Fe 0.84, As 3.22=98.26, R.
                 19.87
                        24.28
```

The Meiseberg mineral (No. 6) is light gray, and occurs in tabular crystals with an uneven conchoidal fracture, and submetallic lustre. G.=5703. Zincken; 5725, and 5-792, Bromeis; 5-779, Rammelsberg.

Another variety (No. 5) is iron-black, with the faces of a rhombic octahedros largely developed. Fracture conchoidal. Lustre metallic. G. = 5.822 and 5.847. Bromeis; 5.844, Zincken; 5.863, Rammelsberg.

The Wolfsberg ore, (No. 7), is iron black. The crystals are rectangular prismatic. Fracture conchoidal. Lustre metallic. G.=5.726, Rammelsberg; 5.796, Zincken; 5.801 and 5.855, Bromeis.

In the last analysis, part of the lead is replaced by nickel and cobalt. The specific gravity is 5.524-5.590. Rammelsberg calls the mineral Nickel-bournonite.

B.B. decrepitates, fuses easily and gives off sulphur and fumes of antimony. Ultimately, fuses to a black globule. In a strong heat, the charcoal is covered with oxyd of lead. Readily dissolves in nitric acid, forming a blue solution.

Good crystals of this species occur in the mines of Neudorf in the Hartz, where they occasionally exceed an inch in diameter; with quartz, gray copper, and phosphoreseent blende, at Kapnik in Transylvania, in flattened crystals; at Servoz in Piedmont, it is associated with pearl spar and quartz. Other localities are at Braunsdorf and Gersdorf in Saxony, Clausthal, and Andreasberg in the Hartz, &c.; also Endellion, near Redruth in Cornwall, where it was since been named. Occurs ed Endellionite, by Count Bournon, after whom it has since been named. Occurs also at Beeralston in Devonshire; and in Chili.

BOULANGERITE. Sulphuret of Antimony and Lead, C. Boulanger, Ann. des Mines, 3d ser. vii, 1835. Plumbostib, Br. Embrithite, Br. Schwefelantimonblei.

In plumose masses, exhibiting in the fracture a crystalline struc-

ture, generally massive; also granular and compact. H.=2.5—3. G.=5.75—6.0. Lustre metallic. Color bluish lead-gray; often covered with yellow spots from oxydation.

Composition.—Pb S+1 Sb² S³=Sulphur 17-9, antimony 24·1, lead 58·0. Analyses: 1, Boulanger, (Ann. d. Mines, [2], viii, 575); 2, Thaulow, (Pogg. xli, 216); 3, Bromeis, (Pogg. xlvi, 281); 4, Brüel, (ib.); 5, Abendroth, (Pogg. xlvii, 493); 6, Rammelsberg, (3d Supp. 28); 7, 8, C. Bechi, (Am. J. Sci., [2], xiv, 60).

		S	Sb	Pb
1.	Molières,	18.5	25.5	53.9, Fe 1.2, Cu 0.9=100, Boulanger,
2.	Nasafjeld,	18.86	24.60	55.57=99.08, Thaulow.
3.	Nertschinsk,	18-21	25.04	56.29=99.54, Bromeis.
4.		19.11	23.66	53.87, Fe 1.78, Ag 0.05=98.47, Brüel.
5.	Ober-Lahr,	19.05	25.40	55.60=100.05, Abendroth.
6.	Wolfsberg,	18.91	25.94	55·15=100, Rammelsberg.
7.	Tuscany, mas.	17.99	26.08	53.15 Cu 1.24 Zn 1.41 Fe 0.35=100.23, Bechi.
8.	" acic.	17.82	27.74	55:39 " 1:25 " 0:09 " 0:23=101:52, Bechi.

B.B. fuses readily, with exhalations of sulphurous acid and fumes of oxyd of antimony. On charcoal, a yellow circle indicates the presence of lead. Easily attacked by nitric acid. Boiling strong muriatic acid decomposes it with the extrication of sulphuretted hydrogen.

Occurs quite abundantly at Molières, department of Gard, in France; also at Nasafjeld in Lapland; at Nertschinsk, and Ober-Lahr; Wolfsberg; near Bottino in Tuscany, both massive, acicular, and fibrous. Specimens from Wolfsberg gave Rammelsberg G.—5·75, and pulverized 5·96.

IKINITE, Chapman. Aciculite, Nicol. Acicular Bismuth. Needle Ore, J. Plumbo-cupriferous Sulphuret of Bismuth. Nadelerz. Bismuth Sulfuré Plombo-AIKINITE, Chapman. Cuprifère, H. Belonit, Glocker.

Trimetric. I: I=110° nearly, Hörnes. In imbedded long

acieular crystals, longitudinally striated. Also massive.

H.=2-2.5. G.=6.1-6.8. Lustre metallic. Color blackish lead-gray, with a pale copper-red tarnish. Opaque. Fracture uneven.

Composition.—(3 CuS+Bi² S²)+2(3Pb S+Bi² S²)=(Cu, Pb)S+1 Bi² S²-Sulphu 16.7, bismuth 36.2, lead 36.1, copper 11.0=100: supposed to be isomorphous with Bournonite.

Analyses: 1, 2, Frick, (Pogg. xxxi, 529); 3, Chapman, (Phil. Mag. [3], xxxi, 541):

		S	Bi	Pb	Cu	
1.	Beresof,	16.05	34.62	35.69	11 79==98·15, Frick.	
2.	"	16.61	36.45	36.05	10.59=99.70, "	•
3.	"	18.78	27 .93	40.10	12.53=99.64, Chapman.	G.=6·1.

B.B. gives off fumes of sulphur, fuses, and emits numerous burning globules, and yields a bead of lead, containing copper, which colors glass of borax greenish-blue. Partly dissolved in nitric acid.

Acicular bismuth occurs imbedded in white quartz, and accompanies gold, malachite, and galena, at Beresof, near Ekatherinenberg in Siberia.

An ore of bismuth, according to Jackson, occurs at the Lubec lead mines, in Maine.

Chapman's name, after Mr. Aikin, the chemist, given in 1848, claims priority.
ALTERED FORMS.—Occurs altered to bismuth ochre.

WOLCHITE, Haid. Antimonial Copper Glance. Antimonkupferglanz, Breit.

Prismatic. In short rhombic prisms; observed planes O, \tilde{u} , \tilde{u} , I, 17. Angles not ascertained. Cleavage: brachydiagonal, imperfect. Also massive.

II.=3. G.=5.7—5.8. Color blackish lead-gray. Fracture conchoidal to uneven. Brittle.

Composition.—Analysis by Schrötter, (Baumgart. Zeit. viii, 284): S 28:602, Sb 16:647, As 6:036, Pb 29:902 Cu 17:352, Fe 1:404=99:943. Occurs in the iron mines at St. Gertraud, in Carinthia.

KOBELLITE, Sätterberg, K. V. Ac. H. 1839, p. 188,—Berz. Jahreeb. xx, 215.

Resembles gray antimony, but brighter in lustre; structure radiated.

G.=6·29—6·32. Soft. Color blackish lead-gray to steel-gray. Streak black.

Composition. — (8Fe S+2 Sb² S³)+4(8 Pb S+Bi³ S³) = (Fe, Pb)S+ $\frac{2}{3}$ (Sb, Bi)² S²= Sulphur 17-9, antimony 8-7, bismuth 28-3, lead 42-2, iron 2-8. Analysis by Sätterberg, (loc. cit.):

S 17.86, Sb 9.24, Bi 27.05, Pb 40.12, Fe 2.96, Cu 0.80, gangue 1.45=99.48.


B.B. fuses, colors the charcoal yellow, passes off mostly in fumes, and yields a white metallic globule. Dissolves in concentrated muriatic acid, affording sulphuretted hydrogen.

From the cobalt mine of Hvena in Sweden. Named after von Kobell.

TETRAHEDRITE, Haid. Gray Copper. Fahlerz, P. Panabase, Bend. Schwar zerz, W. Kupferfahlerz. Weissgiltigerz. Schwarzgiltigerz and Graugiltigers in part, or Polytelite, Glocker. Cuivre Gris, H. Aphthonite, Bunnberg-Aftonite. Quecksilberfahlerz, or Spaniolite, Kobell.

Monometric: tetrahedral. Observed planes as in the annexed figures, with also 33. Figs. 54-59, 61-64. Cleavage: octahedral in traces. Twins: plane of composition a face of the octahedron-Also granular, coarse or fine, to impalpable, compact.

H.=3-4.5. G.=4.5-5.11. Lustre metallic. Color between steel-gray and iron-black. Streak sometimes inclined to brown,





but generally the same as the color. Opaque or subtranslucent in very thin splinters, with a cherry-red transmitted color. Fracture subconchoidal, uneven. Rather brittle.

Some varieties contain silver and quicksilver: the former are called *Polytelite* by Glocker, the latter *Spaniolite* by Kobell. But the limits between these varieties are indefinite.

Composition.—(Eu, Ag, Fe, Zn) S+\(\frac{1}{2}(Sb, As)^3\) S\(\frac{1}{2}\), in which Ag+Eu is to Zn+Fe as 2 to 1. Analyses: 1, Klaproth, (Beit. iv); 2—6, H. Rose, (Pogg. xv, 576); 7, 8, Kersten, (Pogg. lviii, 161, lxvii, 428); 8\(\frac{1}{2}\), C. Bechi, (Am. J. Sci. [2], xiv, 60); 9, Bromeis, (Pogg. lv, 117); 10, Amelung, (Ramm. 3d Supp. 51); 10\(\frac{1}{2}\), Ebelmen, (Ann. des. M. [4], xi, 47); 11, Klaproth, (Beit. iv); 12, 13, H. Rose, (loc. cit.); 14, Sander, (Ramm. 1st Supp. 52); 15, Svanberg, (Oefv. K. V. Ac. Förh. iv, 85); 16, 17, 18, Rammelsberg, (Pogg. Ann. lxxvii, 251); 18\(\frac{1}{2}\), xvi, 83); 19, Scheidhauer, (Pogg. lviii, 161); 20, H. Weidenbusch, (Pogg. 1849, lxxvi, 86); 21, 22, v. Hauer, (Jahrb. d. Geol. Reichs. 1852, 98, J. f. pr. Ch. lx, 55):

I. Containing little or no Silver.

	_			_	_		
	8	Sb	Aв	Cu	Fe	Zn	Ag
1. Kapnik,	28.00	22.00		37.75	3.25	5.00	0·25=96·25, Klap.
2 "	25.77	23.94	2.88	87.98	0.86	7.29	0.62=99.34, Rose.
Gersdorf,	26.33	16.52	7.21	38.68	4.89	276	2.37=98.71, Rose.
4. Elsace,	26.88	12.46	10.19	40.60	4.66	3-69	0.60 quartz 0.41, R.
5. Dillenburg,	25.03	25.27	2.26	88.42	1.52	6.85	0.83=100.18, Rose,
6. Clausthal,	24.78	28.24		84.48	2.27	5.55	4.97=100.24, Rose.
7. V. di Castello,	24.17	27.47		85.80	1.89	6.05	0.33=Hg 2.70, K.
& Angina, Tusc.		27.47		85.90	1.93	6.24	0.33=Hg 2.70, Au trace
							e and loss 2.03, Kersten.
84. Angina,	24.14	26.52		37.72	1.64	6.23	0.45, Hg 3.03=99.78, B.
9. Durango, Mex				37.11	4.42	5.02	1.09, Pb 0.54, undec.
				••••			0.47=98.38, Bromeis,
10. Camsdorf.	28.78	28.87	trace	38-78	5.03	3.28	—=100, Amel'g.
101. Algeria,	27.25	14.77	9.12	41.57	4.66	2.24	=99.61, Ebelm.
			. •	a		n	
11. Containing Sil							lytelite). G. of 15, 4.87;
	of 16,	4.852;	of 17, 4	·892—4	·946;	of 18,	4.926.
11. Wolfach,	25.50	27.00		25.50	7.00		13-25==98-25, Klap.
12. "	23.22	26.63		25.23	872	3.10	17.71=99.91, Rose.
12 Freiberg,	21.17	24.63		14.81	5.98	0.99	31·29==98·87, Rose.
14. Clausthal,	24.1	26.8		35.7	4.5		8.9, Pb 0.9=100.9, S.
15. Aphthonite,	30.05	24.77	trace	32.91	1.31	6.40	3·09, Pb 0·04, Co 0·49,
-							gangue 1.29=100.87, S.
la Meiseberg, cry	24.80	26.56		30.47	8.52	8.39	10.48, Pb 0.78, Ramm.
17. Neudorf, mass	.24.22	26.44		81.58	4.86	8.25	7.27=97.07, Ramm.
18. ""	24.69	2574		32.46	4.19	3.00	7.55=97.63, Ramm.
181. Cabarras N. C.	25.48	17.76	11.55	30.78	1.42	2.53	10.58=100, Genth.
	20 10		00	0010		_ 00	

III. Containing Quicksilver, Spaniolite, (see also, Nos. 7, 8, 84, above). G. of No. 20= 5.107, of No. 21, 4.605, of No. 22, \$107.

Sb As Cu Fe Zn Ag Hg 19. Iglo, Hungary, 23:34 18:48 3:98 35:90 4:90 1:01 trace, 7:52, quartz 2:78= 97-86, 8,

20. Schwatz, Tyrol, 22·96 21·35 — 21. Poratsch, Hung. 25·90 26·70 tr. 22. " 24·37 25·48 tr. 84.57 2.24 - 15.27, insol, 0.80 W. 36:59 7:11 - 0.11 3.07=99.37, H. 30.58 1.46 - 0.09 16.69=98.58, IL

The ore of Moschellandsberg also, according to Zincken, contains mercury. A variety from Guadaleanal in Spain, according to Vauquelin, contains from one

A variety from Guanacanar in Spain, according to vacqueins, contains to ten per cent. of platinum.

B.B gives off fumes of antimony and arsenic, finally melts, and after reasting, affords a globule of copper. When pulverized, dissolves with a little residue in nitric acid; the solution has a brownish-green color.

The Cornish mines, near St. Austle, afford large tetrahedral crystals; their surfaces are commonly rough and dull. More brilliant and highly modified crystallizations occur at Andreasberg in the Hartz, Kremnitz in Hungary, Freiberg in Sayong, Kappaki in Transylvania, and Dillanherg in Nassau. Those belonging to the sations occur at Andreasberg in the Hartz, Kremnitz in Hungary, Freiberg in Saxony, Kapnik in Transylvania, and Dillenberg in Nassau. Those belonging to the Fahlerz (gray ore) of Werner, have a steel-gray color. The Schwarzerz is nearly iron-black; this variety occurs principally at the old mine of Schwatz in the Tyrol, and at Kapnik in Transylvania; also at Clausthal in the Hartz, where it is imbedded in red manganese. The Silberfahlerz has a light steel-gray color, G.=4*8-51. A variety from McMakin's mine, Cabarras Co., N. C. (Anal. 18½) afforded Genth the ratio 4:5 between the sulphur of the sulphobases and sulphacids, instead of 4:3, we have formula; but the appear of the sulphobases are sulphacids, instead of 4:3. as in the above formula; but the amount analyzed he observes was too small to authorize a separation of the mineral as a distinct species. It occurs with pyrites, galena, blende, tale, etc.

It is associated usually with copper pyrites, and is worked as an ore of copper. An ore from mine Altar, 30 leagues from Coquimbo, afforded F. Field (Quart. J. Chem. Soc. iv, 332), S 30·35, As 3·91, Sb 20·28, Cu 36·72, Zn 7·26, Fe 1·23, Ag 0·075 Au 0.003. It is soft, of greasy appearance, greenish gray, slightly reddish, with powder bright red. Domeyko considers it impure with blende, pyrites, and galena-Prof. Ettling observes (ib. vi, 140) that the constitution is analogous rather to enargite than tetrahedrite, corresponding to the formula 4 (Cu, Zn, Fe, Ag) 8+(Sb,

The Aphthonite of Svanberg, (or Aftonite), from Wermland, (analysis 15), occurs massive of a steel-gray color and black streak; G.=487. H.=3. It gives the formula 7 R S+(Sb, As) S². It resembles an argentiferous tetrahedrite.

A Weissgultigers from the mine "Hoffnung Gottes" near Freiberg, contains 36 to 38 per cent. of lead. It afforded 8 22 53, antimony (loss) 22 39, lead 36 51—38 26. Ag 5 92-5 78, Fe 3 72-3 83, Zn 3 15-6 79, Cu 0 19-0 32=100. It occurs massive, fine granular, mixed with a little blende and pyrites. G.=5 438 and 5 465. The sulphur ratio for the bases and acid is 3:2; but it becomes the tetrahedrite ratio 4: 3, if part of the bases exist as impurities.

ALTERED FORMS.—Chalcopyrite malachite, azurite, occur as pseudomorphs after

tetrahedrite.

TENNANTITE. Graukupfererz. Kupferblende, Breit.

Monometric; tetrahedral. Observed planes, O, I, 1, 22, 31 Figs. 55, 57, 58, and 18 with planes of 55. Cleavage: dodecahedral, imperfect. Twins, as in tetrahedrite. Not observed massive.

H.=3·5—4. G.=4·375—4·491. Lustre metallic. Color blackish lead-gray to iron black. Streak dark reddish-gray. Fracture uneven.

Composition .- (Cu, Fe) S+1 As2 S2, isomorphous with tetrahedrite. Analyses: 1, Phillips, (Quart. Jour. vii, 95); 2, Kudernatsch, (Pogg. xxxviii, 397); 3, Fearnley, (Scheerer, in Pogg. lxv, 298); 4, Plattner, Pogg. lxvii, 422):

Fe Cu As

1. Trevisane, Cornwall, 30·25 12·46 47·70 9·75=100·16, Phillips.
2. " 27·76 19·10 48·94 3·57, Ag tr., quartz 0·08=99·45, K.
3. Skutterud, G. 4·53, 29·18 19·01 42·60 9·21=100, Fearnley.
4. Freiberg, Kupferblende, 28·111 18·875 41·07 2·219, Zn 8·894, Ag and Sb trace, * Determined by the loss. Pb 0.341=99.51, Plattner.

B.B. decrepitates slightly, burns with a blue flame, emits copious fumes having an alliaceous odor, and finally fuses to a black scoria which acts upon the magnet.

Occurs in the Cornish mines, particularly near Redruth and St. Day, commonly in very splendent crystals investing other ores of copper. Also found at Skutterud

in Norway, and in Algeria.

The Kupferblende of Breithaupt or Zincfahlerz, from near Freiberg, has part of the iron replaced by zinc, (anal. 4): it has a brownish-red or dirty cherry red

GEOCRONITE, Svanberg. Kilbrickenite, Apjohn. Schulzite.

Trimetric; I: I=119° 44, Kerndt. Observed planes, I, ii, 12. : 12:12 (pyram.) about 153° and 64° 45' (bas.) 122°. Cleavage:

I. Usually massive. Also granular or earthy. H.=2-3. G.=6·4-6·6. Lustre metallic. Color and streak

light lead-gray—grayish blue. Fracture uneven.

Composition.-Pb S+1 (Sb. As)2 S2-Sulphur 16.5, antimony 16.7, lead 66.8. Analyses: 1, Svanberg, (Jahresb. xx, 203); 2, Sauvage, (Ann. d. Mines, [3], xvii, 525); 3, Kerndt, (Pogg. lxv, 302); 4, Apjohn, (Trans. Roy. Irish Acad. for 1840); 5, Svanberg, (Ofv. K. V. Ak. Förh. 1848, 64):

Sb Pb 1. Sala, Sweden, G.=6:54, 16:26 9:58 4:69 2. Merido, G.=6:43, 16:90 16:00 — 65.45 1.51 0.42, Zn 0.11=99.03, Sv. 64.89 1.60 -=99.39, Sauvage. 2. Merido, G.=6·45=6·47, 17·32 9·69 4·72 4. Kilbrickenite, G.=6·407, 16·36 14·39 — 5. Fahlun, G.=6·434, 15·16 5·66 4·62 66.55 1.15 1.73=100.95, Kerndt. 68·87 — 0·38=100, Apjohn. 64·17 4·17 0·08, Ag 0·24, Zn 0·59, Cu 4.17, Al 1.9=98.35, Svanberg.

Svanberg deduces for the last the formula Pb S+1 (Sb, As)2 S2.

B.B. fuses readily, gives off fumes of antimony and sulphur, and colors the char-

coal around, yellow.

Geocronite comes from the silver mines of Sala in Sweden; also in Gallicia, at Meredo in Spain, in nodules in galena; it crumbles easily and soils the fingers; in the valley di Castello near Pietro Santo, in Tuscany. The Kilbrickenite is from Kilbricken, Clare Co., Ireland. The name geocronite is derived from γn , earth, and Kpovos, Saturn, the alchemistic name for lead.

POLYBASITE, H. Rose. Eugenglanz.

Hexagonal. $0:1=121^{\circ}30'$; $\alpha=1.4132$. Observed planes 0, I, 1. 1:1 (pyr.)=129° 32′, (bas.)=117°. Usually in short tabular hexagonal prisms; terminal planes triangularly striated, parallel to the alternate terminal edges. Cleavage: basal, imperfect. Also massive and disseminated.

H.=2-3. G.=6.214. Lustre metallic. Color iron-black; in thin tabular crystals, cherry-red by transmitted light. Streak iron-

black. Opaque. Fracture uneven.

Composition. - (Ag, Eu)S+1 (Sb, As)2 S=with silver alone, Sulphur 14.9, antinony 9.9, silver 75.2=100. Analyses: 1-3, H. Rose, (Pogg. xv, 578); 4, C. A. Joy, (Inaug. Dissert., 24):

Sb Cu Fe Zn 1. Durango, Mexico, 17 04 5.09 3.74 64-29 9-98 0.06 =100·15, R. 0.25 6.23 72.43 3-04 0.33 0.59=99.70, R. 2. Schemnitz, 16.83 =100·30, R. 16.35 8.39 1.17 69-99 4.11 0.29 3. Freiberg 72.01 3.36 0.34 15.87 5.46 3.41 ==100**·45**, **J**oy. 4. Cornwall,

B.B. decrepitates somewhat, and fuses easily. In an open tube gives a white sublimate and a sulphurous odor; on charcoal an area colored with oxyd of antimory; with the fluxes a copper reaction; with soda, arsenical fumes. With acids like bournonite.

Occurs in the mines of Guanaxuato and Gaudalupe y Calvo in Mexico; also at Guarisamez in Durango, with copper pyrites and calcareous spar.

Named from wolve, much, and faces, base, in allusion to the large amount of the base sulphuret of silver, as compared with the sulphurets of arsenic and antimony.

ALTERED FORMS.—Stephanite and Pyrites, occur as pseudomorphs after polybasite.

STEPHANITE, Haid. Brittle Silver Ore. Brittle Silver Glance. Black Silver. Brittle Sulphuret of Silver. Sprödglaserz, W. Sprödglanzerz, Haus. Melanglanz. Argent Noir, Argent Antimonié Sulphuré Noir, H. Argent Sulphuré Fragile.

Trimetric. $I: I=115^{\circ} 39', O: 1\bar{\imath}=132^{\circ} 32\frac{1}{3}'; a:b:c=1.089\bar{\imath}: 1:1.5844.$ Observed planes $O, I, i\bar{\imath}, i\bar{\imath}, 1, 2, 1\bar{\imath}$ 2 $\bar{\imath}$.

304

$$O: \frac{1}{2} = 147^{\circ} 14'.$$
 $1i: 1i \text{ (ov. } ii) = 68^{\circ} 52'.$ $O: 1 = 127^{\circ} 50'.$ $2i: 2i \text{ (ov. } ii) = 107^{\circ} 48'.$ $O: 2 = 111^{\circ} 14'.$ $1: 1 \text{ (mac.)} = 131^{\circ} 16'.$ $0: 2i = 126^{\circ} 6'.$ $1: 1 \text{ (brach)} = 96^{\circ} 8'.$

Cleavage: 2% and ii imperfect. Twins: plane of composition I; forms like those of Aragonite frequent. Also massive, compact, and disseminated.

11.=2-2.5 G.=6.269, Przibram. Lustre metallic. Color and streak iron-black. Fracture uneven. Sectile.

Composition.—Ag S+1 Sb S Sulphur 15.6, antimony 14.0, silver 70.4. Analyses: 1, II. Rose, (Pogg. xv, 474); Kerl, (B. u. H. Ztg. 1858, No. 2).

In an open tube gives a sublimate of arsenic acid, or of oxyd of antimony. B.B. fuses and gives out on charcoal fumes of sulphur and antimony, and is reduced to a dark colored metallic globule, which may be further reduced by the addition of sods. Soluble in dilute heated nitric acid, sulphur and oxyd of antimony being deposited.

It occurs in veins with other silver ores at Freiberg, Schneeberg, and Johann georgenstadt in Saxony, at Przibram and Ratieborzitz in Bohemia, at Schemnitz and Kremnitz in Hungary, at Andreasberg in the Hartz, at Zacatecas in Mexico, and is Peru. A valuable ore of silver. Homeomorphous with aragonite.

ENARGITE, Breithaupt, Pogg. lxxx, 383.

Trimetric. $I: I=98^{\circ} 11'$. Observed planes $O, I, i\bar{i}, i\bar{i}$. Cleavage: I, perfect, ii, ii distinct, O indistinct. Also massive, granular or columnar.

II.=3. $G_{\cdot}=4.43-4.45$; 4.362, Kengott. Lustre metallic. Color iron-black; streak black. Brittle. Fracture uneven.

Composition.—(Cu, Fe, Zn) S+1(As, Sb)³ S⁵(?)—Sulphur 32·5, Arsenic 19·1, Copper 48·4. Analysis by Plattner, (loc. cit.):

In a glass tube decrepitates and affords easily a sublimate of sulphur; and with more heat reddish-yellow sulphuret of arsenic. B.B. on charcoal gives out fumes of arsenous acid, oxyd of antimony and oxyd of zinc, and in the reduction flame with borax yields a globule of copper.

From Morococha, Cordilleras of Peru, at a height of 15,000 feet, in large masses,

occasionally with small druses of crystals, along with Tennantite, imbedded in crystalline limestone.

XANTHOCONE, Breithaupt, J. f. prakt. Chem. xx, 67, and Pogg. lxiv, 272.

Rhombohedral; $R: R=71^{\circ} 34'; O: R=110^{\circ} 30', a=2\cdot3163$. Observed planes $R, -2, O. O: 2=100^{\circ} 35'$. Cleavage: R, and O. Usually in reniform masses, with the interior consisting of minute crystals.

G.=5.0-5.2. Color dull-red to clove-brown; crystals orange-yellow on the edges by transmitted light. Streak-powder yellow. Brittle.

-(3 AgS+As*3*)+2(8AgS+As*S*)=Sulphur 18:5, arsenic 15:3, silver 662=100. Analyses by Plattner, (Pogg. lxiv, 275):

	S	As (loss)	Ag	
1.	21.358	18 491	64·181	Fe 0.97=100.
2.	21.798	14.322	63.880=	:100.

B.B. in a matrass fuses easily and affords a sublimate of sulphuret of arsenic; on charcoal fumes of sulphur and arsenic, and a grain of silver remains.

Occurs with Stephanite at the Himmelsfürst mine, near Freiberg. Breithaupt, in allusion to its yellow powder, from fartles, yellow, and rores, powder.

RITTINGERITE, Zippe. (Ber. Wien. Akad, ix, 2, 345). Monoclinic; $C=88^{\circ}$ 26'. In small rhombic tables with replaced basal edges. Observed planes: $O, \frac{1}{2}, I, \pm 6, \pm 1$. Observed angles: $O: I=91^{\circ}$ 24', $I: I=126^{\circ}$ 18', $O: 1=182^{\circ}$ 24', $O: -1=180^{\circ}$ 50', $1: -1=96^{\circ}$ 20', $O: -6=98^{\circ}$ 30, $O: \frac{1}{2}=150^{\circ}$, $-1: -1=140^{\circ}$ 1'. H.=1'5-3. Lustre submetallic adamantine. Color: O blackish brown in the larger crystals, less dark in the more minute; other parts iron-black. Translucent and dull honey-yellow to hyacinth-red in the direction of the axis. Break orange yellow. Brittle.

Composition.—Probably a compound of sulphuret of silver and antimony. B.B. fuses very easily, gives an arsenical odor, and finally a globule of pure silver. From Joschimsthal, in small crystals.

This mineral is considered identical with Xanthocone by Breithaupt, (B. u. II. Ztg. 1858, 16).

FIREBLENDE Feuerblende, Breithaupt.

Monoclinic. In delicate crystals grouped like stilbite. Observed planes, according to Brooke and Miller, I, ii, $1\bar{2}$, 1i, 2i: $I: I=139^\circ$ 12'. 2i: 2i (top)=74°. $ii: 1i=123^\circ$ 34'. 1i: 1i (top)=112° 52'. $ii: 2i=148^\circ$ 42'. $1\bar{2}: 1\bar{2}=62^\circ$ 36'.

Cleavage: ii, and crystals flattened in this direction. Faces ii striated parallel to the clinodiagonal. Twins: plane of composition ii. (orthodiagonal).

11.=2. G.=4·2—4·3. Lustre pearly adamantine. Color hyacinth-red. Translucent. Sectile and somewhat flexible.

(Composition.—Contains 62.3 per cent. of silver, along with sulphur and antimony, (Plattuer). R.R. like pyrargyrite. Rammelsberg has referred the species to Xanthocone.

From the Kurprinz mine near Freiberg, and from Andreasberg.

Appendia.

WITTICHITE, Avoid. Cupreous Bismuth. Kupferwismutherz, Klap. Kupferwismuthglanz.

Trimetric! Massive and disseminated, also coarse columnar or an aggregate of imperfect prisms. Cleavage in one vertical direction.

11.=3.5. G.=5. Color steel-gray, tin-white, tarnishing pale lead-gray. Streak black.

Composition.—CuS+Bi2S! According to Klaproth, (Beit. iv, 91): Bi 47:24, Cu 34·66=94·48. 8 12:58,

It it tuses easily in an open tube, and gives sulphur and a white sublimate. On charcoal decrepitates, fuses, and yields a bismuth slag; and after roasting with sods, a globule of copper. Klaproth supposes the loss in his analysis to be oxygen. From cobalt mines near Wittichen in Baden.

III. FLUORIDS, CHLORIDS, BROMIDS, IODIDS.

I. BINARY COMPOUNDS.

- 1. Calomel Division. Composition R2 (Cl, I, Br).
- 1. CALOMEL GROUP.—Dimetric.

CALOMEL,

Hg2 Cl.

- 2. Rock Salt Division. Composition R(Cl, I, Br) or R F.
- 1. ROCK SALT GROUP.-Monometric.

Sylvine, K Cl.
Rock Salt, Na Cl.
Sal Ammoniac, NH*Cl.
Kerargyrite, Ag Cl.

EMBOLITE, Ag (Cl, Br).
BROMYRITE, Ag Br.
FLUOR SPAR, Ca F.
YTTROCERITE, (Ca, Ce, Y) F.

KERARGYRITE, Ag Cl.
2. IODYRITE GROUP.—Hexagonal.

Ag L ·

FLUOCERITE,

Ce F1

3. COTUNNITE GROUP.—Trimetric.

COTUNNITE,

Pb Cl.

II. DOUBLE BINARY COMPOUNDS.

CRYOLITE,

IODYRITE,

Na F+1 Al'F'.

CHIOLITE,

Na F-12Al3F3.

CALOMEL. Horn Quicksilver. Dichlorid of Mercury, *Thom.* Chlorquecksilber. Chlormercur. Quecksilberhornerz. Mercure Chloruré.

Dimetric. $O: 1i=129^{\circ} 4'; a=1.232$. Observed planes $\frac{1}{2}$, 1, $\frac{1}{2}$, $\frac{1}{2}$, $\frac{1}{2}$, $\frac{1}{2}$, $\frac{1}{2}$.

 $0:1i=112^{\circ}$ 5'. $0:1=119^{\circ}$ 51'. 2i:2i (pyr.)= 98° 8'. $0:\frac{2}{3}i=140^{\circ}$ 36'. $0:\frac{1}{3}=149^{\circ}$ 51'. 1:1 (pyr.)=104° 20'.

Pyramid 2i when alone gives a very acute termination to the prism. Cleavage: I, indistinct. Also in crystalline coats, and granular.

H.=1—2. G.=6.482, Haid. Lustre adamantine. Color yellowish-gray, or ash-gray, also grayish, and yellowish-white, brown. Streak white. Translucent—subtranslucent. Fracture conchoidal. Sectile.

Composition.—Hg3Cl=Chlorine 15.1, mercury 84.9.

When pure it is entirely volatilized before the blowpipe, on charcoal. It is inadable in water.

Found at Moschellandsberg in the Palatinate, coating the cavities of a ferrugilous gangue, associated with cinnabar; crystals often large and well defined; also at
the quicksilver mines of Idria in Carniola, at Almaden in Spain, and Horzowitz in
Bohemia.

SYLVINE, Beud. Chlorid of Potassium. Muriate of Potash. Kali Salzsaures.

Monometric. Figs. 1, 15, 11. Cleavage cubic. Also compact. H.=2. G.=1.9-2. White, or colorless. Vitreous. Soluble. taste like common salt.

Composition.—KCl=Potassium 52.5, chlorine 47.5.

' Occurs, according to Smithson, at Vesuvius about the fumaroles of the volcano.

KREMERSITE.—Kremers has analyzed ruby-red octahedrons from Vesuvius, (Pogg. lxxxiv, 79), which gave, Cl 55·15, Fe 16·89, K 12·07, Na 0·16, Am 6·17, H 9·56=100. Formula 2, (K, Am, Na), Cl+Fe Cl²+2H.

COMMON SALT. Rock Salt. Muriate of Soda. Chlorid of Sodium. Kochsalt. W. Steinsalz, L. Soude muriatée, H. Sal gemme.

Monometric. Observed planes, O, 1, I, i2. Figs. 1, 11, 15, 32, and 15+32, 196. Cleavage: cubic, perfect. Massive and granular rarely columnar.

II.=2.5. G.=2.1—2.257. Lustre vitreous. Streak white. Color white, also sometimes yellowish, reddish, bluish, purplish; often colorless. Transparent—translucent. Fracture conchoidal. Rather brittle. Taste purely saline.

Composition.—NaCl=Chlorine 60.7, sodium 39.3. Commonly mixed with some sulphate of lime, chlorid of calcium, and chlorid of magnesium, which render it liable to deliquescence. Analyses: 1-8, Berthier, (Ann. d. Mines, [1], x, 259); 9, Fournel, (ib. [4], ix, 551):

		NaCl	MgCl	ĊaŜ	ΝaŜ	MgS	
1.	Vic, white,	8.66		0.5		<u> </u>	Clay 0.2=100, B.
2.	" grayish,	97.8		0.3			1.9=100, B.
3.	" gray,	80.3		50	20		2 0 H 0 7=100, B.
4.	red,	8.66	_				— Ĥ 0·2=100, B.
5.	Marennes, whitish,	97.2	0.4	1 -2		0.2	07=100, B.
Ú.	" yellow,	9670	0.53	1.21		0.66	1·20=100, B.
7.	" red,	9678	0.68	1 09		0.60	0.85 = 100, B.
8.	" green,	96.27	0.27	1-09		0.80	1.57=100, B.
9.	Algiers,	97.8	1.1		Silice	1.5	Ĥ 0.6=100, F.

Dissolves in three parts of water; attracts moisture, but is unchanged in a dry atmosphere. When heated, it usually decrepitates, owing to water between the lamins; the native rock salt, containing no water, fuses at a red heat without decrepitation.

The martinsite of Karsten (J. f. pr. Ch. xxxvi, 127) contains 9 02 per cent. of sulphate of magnesia, which is equivalent to 10 parts of common salt to 1 of sulphate of magnesia. It is from Stassfurth.

Common salt usually occurs in extensive but irregular beds in rocks of various ages, associated with gypsum, polyhalite, clay, sandstone, and calcarcous spar; also dissolved, and forming salt springs.

In Europe it usually occurs in the new red sandstone, or associated with red mark, but it is not confined to these rocks. At Durham, Northumberland, and Leicestershire, England, salt springs arise from the carboniferous series; in the Alps, some salt works are supplied from colitic rocks; the famous mines of Cardona and Wieliczka are referred the former to the green sand formation, and the latter to tertiary rocks. Salt springs also occur in volcanic regions. In the United states the brines mostly come from Silurian sandstones. Salt also occurs as efflorescences over the dry prairies of the Rocky Mountains, and California; and in most desert or semi-desert regions there are numerous salt lakes.

The principal mines of Europe are at Wieliczka, in Poland; at Hall, in the Tyrol; and along the range through Reichenthal in Bavaria, Hallein in Saltzburg, Halstadt, Ischl, and Ebensee, in Upper Austria, and Aussee in Styria; in Hungary, at Marmoros and elsewhere; in Transylvania; Wallachia, Gallicia, and Upper Silesia; Vic and Dieuze in France; Valley of Cardona and elsewhere, in Spain, forming hills 300 to 400 feet high; Bex, in Switzerland; and Northwich in Cheshire, England. At Cheshire it occurs in a basin-shaped deposit, and is arranged in spheroidal masses, from 5 to 8 feet in diameter, which are composed of concentric coats, and present polygonal figures. It is but little contaminated with impurities, and is prepared for use by merely crushing it between iron rollers. At the Austrian mines, where it contains much clay, the salt is dissolved in large chambers, and the clay thus precipitated. After a time, the water fully saturated with the salt, is conveyed by aqueducts to evaporating houses, and the chambers, after being cleared out, are again filled; at Berchtesgaden, the water is saturated in a month, at Hall it takes nearly a year.

It also occurs forming hills and extended plains near Lake Oroomiah, the Caspian, &c. In Algeria, abundant; in Abyssinia; in India in the province of Lahore, and in the valley of Cashmere; in China and Asiatic Russia; in South America, in Peru, and at Zipaquera and Nemocon, the former a large mine long explored in the Cor-

dilleras of Grapada.

In the United States, salt has been found forming beds with gypsum, in Virginia, Washington Co., 18 miles from Abingdon, and in the Salmon River Mts. of Oregon. Brine springs are very numerous in the Middle and Western States. The most famous of these springs are at Salina, in N. Y., in the Kenawha Valley, Va., and Muskingum, Ohio, and in Kentucky. The salt water is obtained by boring, and raised by means of machinery, and thence conveyed by troughs to the boilers, where it is evaporated usually by the direct application of artificial heat; sometimes by the heat of steam, and occasionally by exposure to the heat of the sun.

The following table by Prof. Beck, (Mineralogy of New York, p. 112), gives the amount of brine required for a bushel of salt at the principal salt springs in the

United States:

	Galls,		Galls.
Boon's Lick, Missouri,	450	Kenawha, Virg.	75
Conemaugh, Penn,	300	Grand River, Ark.	80
Shawneetown, III.	280	Illinois River, Ark.	80
Jackson, Ohio,	213	Montezuma, N. Y.	70
Lockhart's, Miss.	180	Grand Rapids, Mich.	50-60
St. Catherines, Upper Can	nda, 120	Muskingum, Ohio,	50
Zanesville, Ohio,	95	Salina-Old wells,	40-45
Personal principal and Paris		New wells,	30-35

Sea water at Nantucket gives a bushel of salt for every 350 gallons.

Composition of New York brines, according to Beck:

Carbonic acid.	Syracuse. 0:007	Salina, old well.	Liverpool. 0.007
Oxyd of iron, silica, and trace of carb, lim	A40.00 P. S. S. S. S. S. S. S. S. S. S. S. S. S.	0.004	0.008
Sulphate of lime,	0.569	0.472	0.404
Carbonate of lime,	0.014	0.017	0.013
Chlorid of magnesium,	0.046	0.051	0.077
Chlorid of calcium,	0.083	0.104	0.172
Chlorid of sodium, (pure salt),	13-239	14.002	14.285
Water, with a trace of organic matter, etc.	86:040	85:341	85:039

Vast lakes of salt water exist in many parts of the world. Lake Timpanogos in the Rocky mountains 4,200 feet above the level of the sea, is 2,000 square miles in area. L. D. Gale found in this water 20'196 per cent. of chlorid of sodium, (Stansb. Exped. cited in Amer. Jour. Sci. [2], xvii, 129). The Dead and Caspian Seas are salt, and the waters of the former contain 20 to 26 parts of solid matter in 100 parts. Prof. Gmelin, who analyzed a portion of these waters of specific gravity 1'212, found them to contain chlorid of calcium 3'336, chlorid of magnesium, 12'167, chlorid of sodium 7'039, sulphate of lime 0'052, bromid of magnesium, 0'443, chlorid of potassium 1'088, chlorid of aluminium 0'144, chlorid of ammonium 0'007, chlorid of manganese 0'161=24'435, with 75'565 water=100'000. This result is given as corrected by Marchand.

ALTERED FORMS.—Anhydrite, Gypsum, Polyhalite, occur as pseudomorphs after this species; also Celestine, Dolomite, Quartz, Hematite, Pyrites; the removal of the salt cubes by their solution, leaves a cavity which any mineral may then occupy. The hopper-shaped crystals often leave an impression of their form on clays.

SAL-AMMONIAC. Muriate of Ammonia. Chlorid of Ammonium. Salmiak, L. Naturlicher Salmiac, W. Ammoniaque muriatée, H.

Monometric. Observed planes, O, 1, I, 22. Figs. 1, 11, 14, 15, 43, 39. Cleavage octahedral. Also stalactitic and in globular masses; in crusts, or as an efflorescence.

H.=1.5-2. G.=1.528. Lustre vitreous. Color white; often yellowish or grayish. Streak white. Translucent-opaque. Fracture conchoidal. Taste saline and pungent.

Composition.-NH4Cl=Ammonium 33.7, chlorine 66.3. Klaproth obtained:

Section 1 to 1 to 1	Vesuvius.	Bucharia.
Muriate of ammonia,	99.5	97.50
Sulphate of ammonia,	0.5	2.50

B. Silliman, Jr. obtained (Dana's Geol. Rep. Exp. Exp., p. 202) for a specimen from Kilauca, Hawaii, Chlorid of ammonium 65-53, chlorid of iron 12-14, peroxyd of iron 8.10, chlorid of aluminium 13.00, insoluble matter and loss 1.23=100.

Dissolves in three times its weight of water, but does not deliquesce. B.B. sublimes in a matrass without fusing. Pulverized with quicklime, or soda, it gives out

the pungent odor of ammonia.

Occurs about volcanos, as at Etna, the island of Vulcano, Vesuvius, and the Sandwich Islands, and near Hecla after the cruption of 1845, as observed by Bunsen. It has been observed in small quantities in the vicinity of ignited coal seams, as at St. Etienne, in France, and also at Newcastle, and in Scotland; crystallized near Duttweiler in Palatia, Germany, where a coal seam has been burning for more than a hundred years. It occurs also in Bucharia; at Kilauea in Hawaii, a variety which contains largely of iron, and becomes rusty yellow on exposure; in Guano from the Chincha Islands.

The ἀλς ἀμμωνιακός, sal-ammoniac of Dioscorides, Celsius, and Pliny, is proved by Beekmann (Hist. of Inventions, iv, 360) to be common rock salt, dug in Egypt, near the oracle of Ammon. The name was afterwards transferred to the muriate of ammonia, when, subsequently manufactured in Egypt. Sal-ammoniac is supposed to have been included by the ancients, with one or two other species, under the name of nitrum, which, according to Pliny, gave the test of ammonia when mingled with quicklime.

KERARGYRITE, Beud. Horn Silver. Kerate, Haid. Chlorid of Silver. Horners, Wern. Silberhornerz. Hornsilber, Haus. Buttermilcherz. Argent Muriaté, H.

Monometric. Observed forms, O, 1, I; f. 1, 11, 14, 15, 16, 17. Cleavage none. Usually massive and looking like wax; some-

times columnar, or bent columnar; often in crusts.

H.=1-1.5. G.=5.552; 5.31-5.43, Domeyko. Lustre resinous, passing into adamantine. Color pearl-gray, greenish, whitish, rarely violet-blue; brown on exposure. Streak shining. Translucent-feebly subtranslucent. Fracture somewhat conchoidal. Sectile.

Composition .- Ag Cl=Chlorine 24.7, silver 75.3. This constitution corresponds

with Klaproth's analyses, (Beit. i, 132, and iv, 10).

Fuses in the flame of a candle, with an emission of acrid fumes. On charcoal easily reduced; and if rubbed with a plate of moistened iron, the iron becomes covered with a thin film of metallic silver. Not soluble in nitric acid or water.

Horn silver occurs in veins of clay slate, accompanying other ores of silver, and usually only in the higher parts of these veins. It has also been observed with ochreous varieties of brown iron ore; also with several copper ores, calc spar, heavy

spar, &c.

The largest masses, and particularly those of a green color, are brought from Peru, Chili, and Mexico, where it occurs with native silver. In Chilli it is a company of the Savon mining districts of mon ore of silver. It was formerly obtained in the Saxon mining districts of Johangeorgenstadt at Freiberg, but is now rare. A mass weighing six and three-quarter pounds, from this region, is now in the Zwinger collection, at Dresden. It also occurs in Siberia; at Kongsberg in Norway; in Alsace; in Cornwall, and at Huelgoet in Britanny.

At Andreasberg in the Hartz, an earthy variety is met with, called by the Germans Buttermilcherz, which, according to Klaproth, contains silver 24.64, muriatic

acid 8-28, alumina 67-08.

Horn silver is valuable as an ore of silver.

EMBOLITE, Breith. Chlorobromid of Silver, Domeyko.

Monometric. In cubes and cubo-octahedrons, f. 1, 15, 16. Also massive.

H.=1-1.5. G.=5.31-5.43, Domeyko; 5.53, Yorke; 5.79-5.81, Breith. Lustre resinous and somewhat adamantine. Color asparagus-green to pistachio, olive, and grayish-green.

Composition.—3 Ag Cl+2 Ag Br (or Ag (Cl, Br))=Chlorine 13.2, bromine 19.8. silver 67.0. Analyses: 1, 2, 3, Domeyko, (Elementos de Mineralogia, 1845, 203); 4, Yorke, (Quart. J. Chem. Soc. iv, 2):

> Chlorid of Silver. 510 53.2 52.8 49.0, D. 47.2, D. 49.0, D. 46.8. Y. Bromid of Silver.

Plattner obtained Silver 66.862, bromine 20.088, chlorine 13.050, (Pogg. lxxvii, 134). Impure varieties from Quillota, Chili, of a grayish green color, afforded Domeyko, 81:4, 72:9, 66:4 and 65:6, of the chlorid of silver. His other specimens were from Chanarcillo. Abundant in Chili; found also at Eulalia in Chihuahua, Mexico, and at Colula in Honduras.

BROMYRITE. Bromic silver. Bromite, Haid. Bromsilber. Bromure d'Argent.
Plata Verde.

Monometric: in cubo-octahedrons. Figs. 1, 15, 18. Occurs in small concretions, rarely in crystals.

H.=1-2. G.=5.8-6.Lustre splendent. Color when pure bright-yellow, slightly greenish; often grass-green or olive-green externally. Sectile.

Composition.—Ag Br=Bromine 42.6, silver 57.4. Analysis by Berthier, (Ann. d. Mines, [4], ii, 526):

> Bromine 42.44, Silver 57.56.

B.B. fuses easily. Imperfectly dissolved by acids; soluble in heated concentrated


Occurs with other silver ores in the district of Plateros, Mexico, and at the mine of San Onofre, seventeen leagues from Zacatecas, associated with chlorid of silver and carbonate of lead; also at Chanarcillo, Chili, with chlorid of silver; also at Huelgoet in Brittany, with horn silver.


As the word Bromite has the form used for a class of salts in chemistry, a sylla-

ble has been added, giving it a termination like that of Argyrite.

FLUOR. Fluor Spar. Fluorid of Calcium. Fluate of Lime. Ratoffkit, John. Chlorophane. Blue John. Chaux Fluatée, H. Flussspath. Muria Phosphorans, Linn. Liparite, Gl.

Monometric. Observed planes: O, I, 1, 2, 3, 22, 42, $\frac{1}{3}\frac{1}{3}$, $\frac{7}{1}$, 33, i2, i5, i3. Figs. 1 (common), 11, 14, 15 to 18, 34, 38, 39, 41, similar to 48, (planes 1, and 33), 50. Cleavage: octahedral, perfect Twins: plane of composition, 1, f. 200; also f. 306, in which the





composition is parallel to each octahedral face. Rarely columnar; often granular, coarse or fine.

II.=4. G.=3·14—3·19; 3·1800—3·1889, Kengott, from 43 specimens, mean 3·183. Lustre vitreous; sometimes splendent; usually glimmering in the massive varieties. Color white, yellow, green, rose and crimson-red, violet-blue, sky-blue, and brown: wine-yellow, greenish and violet-blue, most common; red, rare. Streak white. Transparent—subtranslucent. Brittle. Fracture of fine massive varieties flat conchoidal and splintery.

Composition.—CaF=Fluorine 48.7, and calcium 51.3.

Berzelius found 0.5 of phosphate of lime in the fluor spar of Derbyshire. Kersten, in a fluor from Marienberg and Freiberg, detected a little muriatic acid. Schaffhäutl (Ann. d. Ch. u. Ph. lxvi, 344) states that a violet-blue fluor of Welsendorf contained 0.02073 nitrogen, 0.00584 hydrogen, 0.0365 carbon, and 0.08692 chloric (or chlorous) acid. Ratoffkite is a granular or earthy-blue variety impure with clay, from Ratoffka, Russia.

Below a red heat, the coarsely pulverized spar is vividly phosphorescent; the light is of various colors, and independent of the external color. The variety chlorophane emits a bright emerald-green light. At a high temperature, phosphorescence ceases, but it is partially restored by an electric discharge. B.B. decrepitates, and ultimately fuses to an enamel. If the flame be continued, the fluorine is in part expelled, and the specimen assumes a cauliflower appearance. Gives the reaction of fluorine.

Seldom in beds, but generally in veins, intersecting gneiss, mica slate, clay slate, and also several secondary rocks. In the North of England, it is the gangue of the lead veins, which intersect the coal formations of Northumberland, Cumberland, Durham, and Yorkshire; the Cumberland fluor often contains drops of fluid within, especially the green variety, (Greg and Lettsom). In Derbyshire, it is abundant; and also in Cornwall, where the veins intersect much older rocks. Common in the mining district of Saxony. In the dolomites of St. Gothard it occurs in pink octahedrons; at Münsterthal in Baden in flesh-red hexakisoctahedrons. It has been detected in cannel coal by Prof. Rogers.

A remarkable locality of fluor spar in the United States, now exhausted, was discovered on the borders of Muscalonge lake, in Jefferson Co., N. Y., where cubical crystals, some of them more than a foot through, and having a greenish tinge, were found in

granular limestone, (occasionally f. 305). Rossie and Johnsburgh, St. Lawrence Co., have afforded some fine crystals of fluor. In Gallatin county, Illinois, for thirty miles along the Ohio, in the region southwest of Cone's Rock, 10 to 15 miles below Shawneetown, and other places, a dark purple fluor, often in large crystals, occurs through the soil, or in carboniferous limestone with galena. At the north village of Westmoreland, N. H., two miles south of the meetinghouse, of white, green, and purple shades, constituting a vein with quartz; also, sparingly, at the Notch in the White Mountains, green octahedrons in a crystalline quartz. Some fine veins have been discovered on Long Island, Blue Hill Bay, Maine. It also occurs sparingly of a green color at Putney, Vt.; in Shenandoah county, Virginia, near Woodstock, in the fissures of a limestone; on the Potomac, at Shepardstown, in white limestone; in Smith county, Tennessee, in white and purple cobes; at Locknow N. V. in white only with colories in limestone; in party Potos Bayes. Lockport, N. Y., in white cubes with celestine in limestone; in cubes near Rochester and Manlius in limestone; at Amity, N. Y., in thin seams with spinel and tourmaline; at the Southampton lead mines in Massachussetts; the lead mine, Middletown, Ct.; and near the Franklin Furnace, New Jersey.

The variety chlorophane forms two veins in gneiss, each about 18 inches wide, in

the town of Trumbull, Conn., along with topaz and magnetic pyrites.

ALTERED FORMS.—Fluor spar is slightly soluble in waters containing bicarbonate of lime in solution. The alkaline carbonates decompose it, producing carbonate of lime or Calcite, and a subsequent change of the calcite may produce other forms of pseudomorphs. Fluor spar occurs changed to quartz, by substitution, and also to Limonite, Hematite, Lithomarge, Psilomelane, Calamine, Smithsonite, and Cerusite.

YTTROCERITE, Berz.

Massive; crystalline-granular and earthy. Cleavage: in two directions inclined to one another 108° 30'.

H.=4-5. G.=3.447, Berz. Lustre glistening; vitreous pearly. Color violet-blue, inclining to gray and white, often white; sometimes reddish-brown. Fracture uneven.

Composition .- Contains CaF, CeF and YF, in different proportions. Analyses by Gahn and Berzelius, (Afhand. iv, 151 and Schw. J. xvi, 241):

> **Ca** 47.63, 50.00, **€**e 18·21, " 16·45, FH 25.05. Y 9·11, " 8·10, " 25.45.

B.B. on charcoal alone infusible; with gypsum the yttrocerite of Finbo fuses to a bead, not transparent, and that of Broddbo is infusible. With the three fluxes, the Finbo mineral behaves like fluor spar; the glass is however yellow in the oxy-dating flame as long as hot, and becomes opaque sooner than the glass given by fuor spar. In a pulverized state, it dissolves completely in heated muriatic acid, forming a yellow solution.

Occurs sparingly at Finbo and Broddbo, near Fahlun in Sweden, imbedded in quartz, and associated with albite and topaz. Also at Amity, Orange Co., N. Y.; and in Mass., probably Worcester Co. The Amity mineral has been examined by J. E. Teschemacher. The Massachusetts mineral afforded Dr. C. T. Jackson, (Proc. Bost. Soc. N. Hist. 1844, p. 166), lime, yttria, oxyd of cerium, with some Al, Fe and Si, and a loss of 19 4. The mineral is mixed with fluor spar in the vein, and probably the specimen analyzed was not pure from it.

Yttrocerite has been considered a fluor spar in which part of the lime is replaced by exyds of cerium and yttrium. The angle of cleavage reported, 108° 30', differs

but a degree from the angle between faces of an octahedron.

IODYRITE. Iodic Silver. Iodite, Haid. Argent ioduré, Duf. Iodsilber, M.

Hexagonal. $O: 1=136^{\circ} 46'$; $\alpha=0.81438$. Observed planes, (Descloizeaux), O, I, 4, 2, $\frac{1}{2}$. Angles, (Descl.):

 $O: 2=118^{\circ}$. $O: \frac{1}{2}=154^{\circ} 49'$. $2: 2 \text{ (pyr.) } 127^{\circ} 36'$. $O: 4=104^{\circ} 53'$. $\frac{1}{2}: \frac{1}{2} \text{ (pyr.)} =155^{\circ} 26'$. 4: 4 " =122° 12'.

Cleavage: basal highly perfect. Also in thin plates with a lamellar structure.

Soft. G.=5.504. Lustre resinous to adamantine. Color citron and sulphur-yellow, to yellowish-green. Streak yellow. Translucent. Plates flexible, sectile.

Composition.—Ag I=Iodine 54, Silver 46, Domeyko, (Elementos de Min. p. 206,

B.B. on charcoal, fuses immediately, producing a vapor which tinges the flame of a fine violet color, affording a globule of silver.

lodic silver occurs in thin veins in steatite at Abarradon, near Mazapil, in Zectecas, Mexico, and at Delirio, mines of Chañarcillo, Chili. It has also been found at Guadalajara in Spain. Descloizeaux has pointed out its homœomorphism with Greenockite. (Ann. Ch. Phys. [3], xl).

COCCINITE, Haid. Iodic Mercury, Del Rio. Mercury ioduré, Duf. Iodqueck-

In particles of a reddish-brown color on selenid of mercury. Lustre adamantine.

Composition.—Probably Hg I=Mercury 44.1, iodine 55.9. Fuses and easily sublimes. From Casas Viejas, Mexico.

Artificial crystals of Hg I are dimetric, and have I: 1=160° 30'; 1: 1 (pyram.)=

FLUOCERITE, Haid. Fluorcerium neutrales. Fluate of Cerium. Flucerine, Bend

Hexagonal. In hexagonal prisms and plates. Cleavage: basel most distinct. Also massive.

II.=4-5. G.=4.7. Lustre weak. Color dark tile-red or almost yellow; deeper when the mineral is wet. Streak white or slightly yellowish. Subtranslucent—opaque.

Composition.—Berzelius obtained in an analysis, (Afhandlingar, v, 56), Te 8264

Y 1-12, HF 16-24.

B.B. infusible alone, but darkens. In borax and salt of phosphorus, fuses slowly but completely. The globule is blood-red in the exterior flame, but becomes color less on cooling. In the interior flame, colorless at all temperatures. In carbonate of soda does not fuse, but swells out and is decomposed. In a glass tube at a strong heat, yields fluorine.

Occurs at Finbo and Broddbo near Fahlun, in Sweden, imbedded in quarts and albite, accompanying pyrophysalite and orthite.

FLUOCERINE, Hausm. Basic flucerine. Basicerine, Beud. Fluorcerium basisches-

Monometric! Supposed to show traces of the rhombic dodecahedron; usually massive. II.=4.5-5. Lustre vitreous or resinous. Color a fine yellow, with some red, and when impure, brownish-yellow. Streak yellow, brownish. Subtranslucent to opaque.

Composition.—Ce² F²+8e Ĥ—Cerium 17·56, fluorine 10·88, peroxyd of cerium 66·41, water 5·15. Berzelius obtained (Afhand. v. 64) e 84·20. HF 10·85, fl 4·95. From Finbo. A mineral from Bastnäs afforded Hisinger, (K. V. Ac. H. 1838, 189), Peroxyd of Ce (and La) 36·43, fluorid, ibid. 50·150, water 18·413, which corresponds to the formula Ce² F²+e H⁴.

COTUNNITE. Cotunnia, Monticelli. Cotunnite, von Kobell. Chlorid of Lead,

May be scratched by the nail. G.=5.238. Lustre adamantine; inclining to silky or pearly. Color white. Streak white.

Composition.—Pb Cl=Chlorine 25.5, lead 74.5.

B.B. fuses readily and colors the flame blue, giving off white vapors, which condense on the charcoal. With soda, yields a globule of lead. Dissolves in about twenty-seven times its weight of cold water.

Observed by Monticelli and Covelli, in the crater of Vesuvius, after the eruption of 1822, accompanied by chlorid of sodium, and chlorid and sulphate of copper. Named after a distinguished medical man at Naples. Angles very near those of Haidingerite.

IODID AND BROMID OF ZINC.

Iodine and bromine are stated by Mentzel to occur along with a cadmiferous zinc in Silesia, and hence it is inferred that iodid and bromid of zinc exist in nature, though not yet distinguished.

MURIATIC ACID. Hydrochloric Acid. Chlorhydric Acid.

G.=1.2847. Colorless. Odor pungent. Taste acid. Gaseous.

Composition.—HCl=Hydrogen 2.74, chlorine 97.26. Muriatic acid is one of the constituents of the vapors that issue from active volcances. It is sometimes found in solution in crevices about their slopes.

CRYOLITE, Andrada. Alumine Fluatée Alcaline, H. Kryolite. Eisstein. Chodneffite.


Trimetric or dimetric. Cleavage: rectangular or nearly so; basal, perfect; lateral, less so. Occurs in cleavable masses, sometimes showing a compound structure like albite, (Genth).

H.=2.5. G.=2.9-3.077. Lustre vitreous; slightly pearly on O. Color snow-white; sometimes reddish or brownish. Subtransparent—translucent. Immersion in water increases its transparency. Brittle.

Composition.—Na F+1 Al2F2=Aluminium 13.0, sodium 32.8, fluorine 54.2. Berzehus obtained, (K. V. Ac. II. 1823, 315): Aluminium 13 00, sodium 32 93, fluorine 54 07. Chodney obtained, (Verh. d. K. Russ. min. Gcs. 1845—46, p. 208), excluding the fluorine, Alumina 24 83, soda 43 89, Mg and Mn 0 83. Durney obtained from the Miask Cryolite, (Pogg. lxxxiii, 588), Aluminium 13:41, sodium 32:31, fluorine 58:48, calcium 0:25, Fe and Mn 0:55=100. G.=2:95. Durney; 2:962, Kokscharov.

Fusible in the flame of a candle, and hence its name, from *pvos, ice. Heated in an open tube, yields water, and by directing the flame in the tube the glass is corroded. B.B. fuses, then becomes hard, white, and opaque; ultimately a crust of alumina remains; soluble in sulphuric acid and hydrofluoric acid evolved. Found at Arksutfiord, in West Greenland, where it was discovered by Giesecke. in two veins in gneiss, associated with galena, pyrites, and spathic iron. Specimens may be obtained there from six inches to a foot in diameter; also with chiolite, lithia mica, and fluor, at Miask in the Urals.

CHIOLITE, Hermann and Auerbach, J. f. pr. Chem. xxxvii, 188.



Dimetric; a=1.077. Observed form f. 307 (Kokscharov). Pyramidal edges 107° 32′, basal 113° 25′. Cleavage indistinct. Occurs massive granular, resembling cryolite; structure crystalline.

H.=4. G.=2.72, Hermann; of powder, 2.842—2.898, Rammelsberg. Color snowwhite. Lustre somewhat resinous. Translucent.

Composition.—NaF+‡Al²F²=Aluminium 18·6, sodium 23·4, fluorine 58·0=100. Analyses: 1, Hermann, (loc. cit.); 2, 3, Rammelsberg, (Pogg. lxxiv, 1848, p. 315); 4, Pearce, in Rammelsberg's laboratory, (ib.):

	1. <i>H</i> .	2. <i>R</i> .	3. R.	4. P.
Sodium,	23.78	24.69	24.56	22.91
Aluminium,	18.69	18.02	17.72	19.59
Fluorine.	57.53=1	00. H.		

Rammelsberg's analyses, supposing the undetermined part to be fluorine, giverespectively, 57.29, 57.72, 57.50 per cent. B.B. fuses easily like cryolite, and gives the reaction of fluorine.

From Miask, where it occurs in granite, with fluor, topaz, phenacite, and cryolite -

FLUELLITE, Levy, Edinb. Jour. Sci. 1825, p. 168. Fluate of Alumine. Fluorics of Aluminium.

Trimetric; in acute rhombic octahedrons with truncated apex -1:1 (pyram.)=109° 6′, 82° 12′, and (basal) 144°; I: I=105° nearly.

H.=3. Color white. Transparent.

Composition.—Fluorine and aluminium, according to Wollaston.

Fluclite is a rare mineral found at Stenna-gwyn, in Cornwall, with wavellite aus uranite, in minute crystals, on quartz.

IV. OXYGEN COMPOUNDS.

I. OYYDS.

- 1. OXYDS OF ELEMENTS OF THE HYDROGEN GROUP.
 - a. Anhydrous.
 - b. Hydrous.
- 2. OXYDS OF ELEMENTS OF THE ARSENIC GROUP.
- 3. Oxyde of Carbon, Boron or Silicon.

. OXYDS OF ELEMENTS OF THE HYDROGEN GROUP.

a. Anhydrous Oxyds.

I. MONOMETRIC.

1. PERICLASE GROUP.—Composition RO.

Periclase, Mg.

RED COPPER, Ou.

2 MARTITE GROUP.—Composition R² O².

MARTITE, Fe

3. SPINEL GROUP.—Composition RO+R² O².

ISERINE, Fe (Fi, Fe.)

IRITE, R (Ir, Fe).

SPINEL, Mg (XI, Fe).

AUTOMOLITE, Pi XI.

KRETTTONITE, (Zn Fe) (XI, Fe).

MAGNETITE, Fe Fe.

FRANKLINITE, (Zn, R) (Fe, Mg) (XI Gr).

CHEOMIRON, (Fe, Mg) (XI Gr).

PITOHBLENDE, U G.

14. MELACONITE GROUP.—Composition RO. MELACONITE, Gu O.

II. HEXAGONAL.

1. ZINCITE GROUP.-Composition, R O.

WATER, H.

CHALCOTRICHITE, Gu.

Zencite,

Źn.

2. CORUNDUM GROUP.—Composition Rº O's.

Corundum, 🚮

LEMENTE, Fe, Ti.

SPECTLAR IRON, Fe.

13. TENORITE GROUP.—Composition R O2.

TENORITE.

€u O³.

III. DIMETRIC.

. RUTILE GROUP.—Composition RO3.

Cassiterite, Sn.

Anatase, Ti.

RUTILE, Ti.

Appendix—

! BRAUNITE, ! HAUSMANNITE.

IV. TRIMETRIC.

CHALCOTRICHITE GROUP.—Composition, RO.

CHALCOTRICHITE,

€u O.

CHRYSOBERYL GROUP.—Composition Rº Oº (or RO+Rº Oº).

CHRYSOBERYL,

Be+Al' or Be Al.

BROOKITE GROUP.—Composition R O'.

BROOKITE,

Ti.

† Pyrolusite,

₫n.

HETEROCLIN.

Appendix to Anhydrous Oxyds.

MINIUM, Pb³ O⁴.

CREDNERITE, (Ba, Cu)³ Mn².

V. COMBINATIONS OF OXYDS, AND CHLORIDS OR SULPHUREN

MATLOCKITE, II.

Pb Cl+Pb O.

MENDIPITE, III.

Pb Cl+2 Pb O.

VOLTEITE,

Zn S++ Zn O.

I. OXYDS OF ELEMENTS OF THE HYDROGEN GROUP.

A. Anhydrous Oxyds.

I. MONOMETRIC OXYDS.

PERICLASE. Periclasia, Scacchi, Mem. Min. Naples. Periklase.

Monometric. Figs. 1 and 11. Cleavage: cubic, perfect. Also in grains.

H.=nearly 6. G.=3.674, Damour. Color grayish to dark-green. Transparent to translucent.

Composition.—Mg, or magnesia, with 1 part in 25 of protoxyd of iron. Analyses: 1, Scacchi, (loc. cit.); 2, 3, Damour, (Ann. d. M. [4], iii, 360, and Bull. Soc. Geol. de France, 1849, p. 313):

1.	Mg 89∙04	Fe 8.56=97.60, Scacchi.
2.	93.86	5.97=99.88, Damour
3.	93.38	6:01-99:39 Damour

B.B. infusible. When pulverized dissolves slowly in nitric acid, but rapidly when heated. Moistened on test paper shows an alkaline reaction.

Occurs disseminated through ejected masses of a white limestone, and in spots of clustered crystals, on Mt. Somma, sometimes with white olivine and earthy magnesite.

RED COPPER. Cuprite, *Haid.* Red Oxyd of Copper. Oxydulated Copper, *P.* Tile Ore. Rothkupfererz, Ziegelerz, *W.* Cuivre Oxide Rouge, Cuivre Oxidule, *H.* Zigueline.

Monometric. Observed planes 1, O, i2, i5, 2, 3, 22, $3\frac{3}{2}$. Figs. 1, 14, 15 to 19, 32, and also 144, p. 92; forms commonly octahedral. Cleavage: octahedral. Also massive, granular; sometimes earthy.

H.=3.5—4. G.=5.85—6.15; 5.992, Haidinger. Lustre adamantine or submetallic—earthy. Color red, of various shades, particularly cochineal-red; occasionally crimson-red by transmitted light. Streak several shades of brownish-red, shining. Subtransparent—subtranslucent. Fracture conchoidal, uneven. Brittle.

Composition.—Eu=Copper 88.8, oxygen 11.2. B.B. in the reducing flame on charcoal, affords a globule of copper. Dissolves with effervescence in nitric acid. The ore formerly included the earthy variety, usually of a brick-red or reddish-brown color, and frequently mixed with oxyd of iron. Occurs in the Bannat, at Camsdorf and Saalfield, in Thuringia, at Les Capanne Vecchie, in Tuscany; on Elba in cubes; and in Cornwall; fine translucent crystals of red copper ore occur with native copper and quartz at Huel Gorland and other Cornish mines. Isolated crystals, sometimes an inch in diameter, are found imbedded in lithomarge at Chessy, near Lyons; they are generally coated with malachita. Splendid specimens are brought from the Bannat and Ekatherinenberg in Siberia. It is abundant also in

South Australia.

The zigueline (or ziegelerz of the Germans) is the earthy red oxyd of copper, or tile ore.

It has been observed crystallized and massive at Schuyler's, Somerville, and Flemington copper mines, N. J., associated with chrysocolla and native copper; also in red shale near New Brunswick, N. J.; with green malachite in trap, two miles from Ladenton, Rockland Co., N.Y.; at Cornwall, Lebanon Co., Pa.; in the Lake Superior Region.

When found in large quantities, this species is valuable as an ore of copper.

ALTERED FORMS.—A deoxydation of the Red Copper Ore sometimes takes place, producing native copper. It also becomes carbonated and green, by means of carbonated waters, changing to Malachite or Azurite; or through a silicate in solution it is changed to Chrysocolla. Limonite occurs as a pseudomorph by substitution after Red Copper.

MARTITE, Breit.

Monometric. In octahedrons like magnetite; f. 11, 16, 19; often flattened, and octahedral faces striated parallel to the edges. Cleavage indistinct.

II.=6. G.=4.82, Brazil; 4.65, Puy de Dome; 3.80, Peru, Breit.; 5.33, Monroe, N. Y., Hunt. Lustre submetallic. Color iron-black, sometimes with a bronzed tarnish. Streak brown or purplish-brown. Fracture conchoidal. Not magnetic.

Composition.—Fe=Oxygen 30, iron 70, same as for specular iron.

Found in the localities above mentioned, and at Framont. The Monroe crystals, occur in a rock containing quartz, flesh-colored feldspar and dark-green hornblende, and are imbedded in each of these minerals; they are sometimes half an inch through. The association with hornblende which contains protoxyd of iron is urged by Mr. T. S. Hunt, (Am. J. Sci. [2], xiii, 370), as evidence that the crystals are not pseudomorphous, as some have supposed. The change from magnetic iron to the peroxyd is one that may and does take place in nature, as is believed, and some of the so-called martite may be altered specular iron, although probably not all.

Scacchi has observed regular octahedrons of specular iron at Vesuvius, which he considers compound crystals after the rhombohedral primary. But it is more prebable that they are actually simple crystals of martite.

G. H. O. Volger endeavors to show that the crystals are dimetric (Entwick Min., 1854, 368) and pseudomorphous, probably, after the oxyd Fe O2, supposed by him to be isomorphous with anatase, whence he derives the name for the mineral Eisenanatas.

ISERINE.

Monometric. Figs. 15 to 17; faces usually rounded and rough. Cleavage indistinct.

H.=6-6.5. G.=4.85-5.1. Lustre metallic or submetallic. Color iron-black; streak black. Brittle. Magnetic.

Composition.—Fe (Fe, Fi). Analyses: 1, Rammelsberg, (Pogg. liii, 129); 2, Rhodius, (Ann. d. Ch. u. Pharm., lxiii, 218); 3, Waltershausen, (Vulk. Gest. 121):

Тi Fe 1. Unkel, Rhine, 11.51 48.07 39·16=9874, Ramm. 8.69 61.27 31.80=101.76, Rhod. G.=5.1. 11.14 58.86 80.00=100, Waltersh. G.=4.43. 2. Rheinbreitenbach, 8. Etna,

No. 1 has been called Slag-like magnetic iron. Waltershausen deduces the above from his analysis, which afforded Fe 92:19, Ti 12:37=104:56. No. 2 is strongly magnetic. B.B. infusible.

From basalt at the localities mentioned, and also in Bohemia, Saxony, Calabria, and near l'uy-de-dome in France.

Iserine has been regarded as having the formula (Fe, Ti), and related to Martite.

IRITE, Hermann.

Monometric. In octahedrons, Kengott. Structure thin foliated. Color black. Lustre shining. G.=6.506. Magnetic.


Composition.—Probably RH or (Îr, Ôs, Fe) (Ir, Os, Cr)2O3, and isomorphous with spinel, magnetic iron, etc. Analysis by Hermann, (J. f. pr. Ch. xxiii, 276): Peroxyd of iridium 62.86, protoxyd of osmium 10.30, protoxyd of iron 12.50, peroxyd of chromium 13.70—99.36, with traces of manganese.

Occurs in the Ural with native platinum, titanic iron, iridosmine, and hyacinth.

SPINEL, W. Ceylanite. Pleonaste. Spinelle Ruby. Balas Ruby. Almandine Ruby. Rubicelle. Candite, Bournon. Zeilanit, W. Automolite. Gahnite. Dysluite. Hercinite. Kreittonite. Chlorospinel.

Monometric. Observed planes: 1, I, O, 2, 33. Figs. 308, 11, (common), 16, 19, 41. Cleavage: octahedral. Twins: f. 200; face of composition 1.

H.=8. G.=3.5-4.9; 3.523, Haid.; 3.575, red spinel. Lustre vitreous; splendent-nearly dull. Color red of various shades, passing into blue, green, yellow, brown, and black; occasionally almost white. Streak white. Transparent—nearly opaque. Fracture conchoidal.



Composition.—(Mg, Fe, Ca, Zn, Mn) Xl. Pure spinel, sometimes Mg Xl=Magnesia 28.0, alumina 72.0; but the magnesia is often partly replaced by protoxyds of iron, zinc, or manganese, or by lime; and the alumina sometimes by peroxyd of

Analyses: 1, 2, Abich, (Pogg. xxiii, 305); 3, Berzelius, (Gehl. N. J. d. Chem. vi, 304); 4, 5, Thomson, (Min. i. 214); 6, C. Gmelin, Jahresb. iv, 156); 7—10 Abich, (loc. cit.); 11, Abich, (K. V. Ac. H. 1842, 6); 12, Scheerer, (Pogg. lxv, 294); 13, 14, H. Rose, (Pogg. 1, 652); 15, Erdmann, (K. V. Ac. H. 1848); 16, Zippe, (Ann. d. Ch. Pharm. lv, 357); 17, Ekeberg (Gehlen's N. J. v, 418); 18, 19, Abich, (loc. cit.); 20, Thomson, (Min. i, 221); 21, Kobell, (J. f. pr. Ch. xliv, 99).

I. Containing Magnesia, Lime, or Iron.

		X 1	Mg	Ĉa	Fe	The second second
1.	Ceylon, red,	69.01	26.21	_	071	Er 1.10, Si 2.02=99.05, Ab.
	Aker, blue,	68.94	25.72	_	3.49	Si 2.25=100.47, Abich.
3.	a a	72.25	14.63	-	4.26	" 5.48=96.62, B. and H.
4.	Franklin, N. J., green,	73.31	13.63	7.42	-	" 5.62=99.98, Thomson.
5.	Amity, N. Y.	61.79	17.87	10.56	-	CaC 2.80, H 0.98=99.60, T.
	Ceylon, Ceylanite,	57.20	18.24	-	20.51	Si 3·15=99·11, Gmelin.
7.	Ural, Pleonaste,	65.27	17.58	-	13.97	" 2.50=99.32, Abich.
8.	Monzoni, "	66.89	23.61	-	8.07	" 1.23=99.80, Abieh.
9.	Vesuvius, "	67.46	25.94	_	5.06	" 2:38=100:85, Abich.
10.	Iserwiese, "	59.66	1770	-	19-29	" 1.79=99.17, Abich.
11.	Vesuvius, "	62.84	24.87	-	3.87	Fe 6.15, Si 1.88=99.56, A.
12.	Arendal,	55.17	17.65	-	18:33	Si 5 09, Mn 2 71=98 95, S.
13.	Ural, Chlorospinel,	64.13	26.77	0.27	-	Fe 8.70, Cu 0.27=100.14, R.
14.	44 44	57.34	27.49	-	-	" 14.77, " 0.62=100.22, R.
15.	Tunaberg,	62.95	13.03	-		=99.44, Erdmann.
16.	Hercinite,	61.17	2.92	-	35.67=	=99.76, Zippe.

II. Containing Oxyd of Zinc.

	Æl	Йg	Мn	Źn	8i
17. Fahlun, Automolite,	60.00		trace,	24.25	4-75, Fe 9-25=98-25, E
18. " "	55.14				3·84, " 5·85=100·10, A.
19. North America,	57.09	2.22	trace,	34.80	1·22, Fe 4·55=99·38, A.
20, Sterling, N. J. Dysl.	30.49		7.60	16.80	2·97, N 0·40, Fe 41·93, L
21. Bodenmais, Kreitt.	44.66	3.05	Ča 1.30	24.00,	Fe 16 63, insol. 10=99 64, K

Automolite (or gainite): a zinc-spinel=ZnX1; color dark-green or black; G.=4.1—4.6.

Hercinite: an iron spinel=Fex1; G .=3.91-3.95.

Ceylanite, (or piconaste): an iron and magnesia spinel=(Mg, Fe)X1; G.=3575.

Dysluite: a zinc, manganese, and iron spinel; color yellowish-brown or grayish-brown; (Zn Mn) (Xl, Fe); G.=455.

Chlorospinel, (G. Rose): a grass-green spinel from Slatoust; Mg(XI,Fe); G.= 3:591-3:594.

Kreittonite: a black spinel, (G.=4.49); Kobell writes for the formula, ZnAl+Pe Fe, or (Zn. Fe) (Al, Fe), and corrects the analysis as regards the iron as follows: Al 49.73, Fe 8.70, Zn 26.72, Fe 8.04, Mg 3.41, Mn 1.45=98.05.

B.B. alone infusible; red variety changes to brown, and even black and opeque, as the temperature increases, and on cooling becomes first green, and then nearly colorless, and at last resumes the red color. Fuses with difficulty with borax, but somewhat more readily with salt of phosphorus. Black varieties yield a deep green globule, owing to the iron they contain. The zinc varieties afford with sods oxyd of zinc.

The varieties of this species have been denominated, according to their colors, so follows; the black varieties pleonaste: the scarlet spinelle ruby; the rose red bals ruby: the yellow or orange-red rubicelle: the violet colored almandine ruby. The oriental ruby is sapphire.

Spinel occurs imbedded in granular limestone, and with calcareous spar in serpes-

tine and gneiss. It also occupies the cavities of volcanic rocks.

In Ceylon, in Siam, and other eastern countries, it occurs of beautiful colors, so rolled pebbles in the channels of rivers. Pleonaste is found at Candy, in Ceylon, and hence was called Candite, by Bournon. At Aker, in Sweden, is found a paleblue and pearl-gray variety in limestone. Small black splendent crystals occur in the ancient scoria of Mount Somma, with mica and idocrase; also in compact

gehlenite, at Monzoni, in the Fassa valley.

From Amity, N. Y., to Andover, N. J., a distance of about thirty miles, is a region of granular limestone and serpentine, in which localities of spinel abound. At Amity, crystals are occasionally 16 inches in diameter; and one collected by Dr. Heron, weighs forty-nine pounds; it is in three pieces, and contains cavities studded with crystals of corundum; colors, green, black, brown, and less commonly red, along with chondrodite, and other minerals. A mile southwest of Amity, on J. Layton's farm, is a remarkable locality; also on W. Raynor's farm, smile to the north; another half a mile north, affording grayish-red octahedrom; and others to the south. Localities are numerous about Warwick, and also at Monroe and Cornwall, though less favorable for exploration than those at Amity, (form 1, also 1, i, 33, f. 308). Franklin, N. J. affords crystals of various shades of black, blue, green, and red, which are sometimes transparent, and a bluish-green ceylanite variety here, has the lustre of polished steel; Newton, N. J. pearl-gray crystals along with blue corundum, tourmaline, and rutile; at Bryan, red, brown, green, and black colors, along with chondrodite. At Sterling, Sparta, Hamburgh, and Vernon, N. J., are other localities. Light blue spinels occur sparingly in limestone in Antwerp, Jefferson Co., N. Y., two and a half miles south of Oxbov, and rose and reddish brown in Gouverneur, two miles north and three-fourths of a mile west of Somerville, St. Lawrence Co.; green, blue, and occasionally red varieties occur in granular limestone at Bolton, Boxborough, Chelmsford, and Little ton, Mass. Soft octahedral crystals occur in Warwick, which, according to Beck, are spinels permeated with steatite or serpentine, (Min. N. Y., p. 318). They have

cen considered pseudomorphs. Good black spinel in Burgess, Canada West; blue with clintonite at Daillebout, C. E.

The automolite occurs in talcose slate near Fahlun and elsewhere in Sweden. The

The automotite occurs in talcose state near Fahlun and eisewhere in Sweden. The dysluite is from Sterling, N. J., along with franklinite and willemite. Kreittonite is from Bodenmais; and chlorospinel from Slatoust.

The fine colored spinels, when of large size, are esteemed as gems.

ALTERED FORMS.—Acted on by silicate of magnesia in solution, and changed to Steatite or Serpentine, also when the alumina is not wholly removed by the process of change it becomes Völknerite, (MgeAl+15H).

MAGNETITE, Haid Magnetic Iron Ore. Oxydulated Iron. Magneteisenstein, Magneteisenerz. Fer Oxydulé, H.

Monometric. Observed planes O, 1, I, i2, 2, 22, 33, 10-10, 16-16, 33. Figs 11 and 14 (common), 15 to 19, 168. Cleavage: octahedral, perfect to imperfect. Dodecahedral faces commonly striated parallel to the longer diagonal. Twins like f. 200, Massive, structure granular—particles of various sizes, sometimes impalpable.

H.=5.5-6.5. G.=4.9-5.2; 5.168-5.180, crystals, Kengott, and 5-27 after long heating. Lustre metallic-submetallic. Color iron-black; streak black. Opaque. Fracture subconchoidal, shining. Brittle. Strongly magnetic, and sometimes possessing polarity.

Composition.—Fe Fe=Iron 72.4, oxygen 27.6, or Fe 68.97, Fe 31.03=100. Breithaupt describes a magnetite from Sparta, N. J., containing magnesia; G.=441—442. A variety from the Mourne Mts. gave Prof. Andrews, (Chem. Gaz., 1852, 379), Fe 71.41, Fe 21.59, Mg 6.45=Fe (Fe, Mg).

An earthy magnetite (Eisenmulm) from near Siegen afforded Genth, (Ann. Ch. Pharm, lxvi, 277), Fe 66.20, Fe 13.87, Mn 17.00, Cu 0.09, sand, &c. 1.75=98.91=Fe (Fe, Mn). G.=3.76.

B.B. becomes brown, and loses its influence on the magnet, but fuses with great difficulty. With borax, in the oxydizing flame, fuses to a dull-red glass, which becomes clear on cooling, and often assumes a vellow tint; in the reducing flame be-

comes clear on cooling, and often assumes a yellow tint; in the reducing flame becomes bottle-green. Dissolves in heated muriatic acid, but not in nitric acid.

Magnetite occurs in beds in gneiss or syenite, also in beds or isolated crystals in
clay slate, hornblende slate, chlorite slate, greenstone, basalt, and occasionally in

clay state, hornblende state, chlorite state, greenstone, basalt, and occasionally in limestone. Often associated with emery.

The beds of ore at Arendal and nearly all the celebrated iron mines of Sweden, consist of massive magnetite. Dannemora, and the Täberg in Smaoland, are entirely formed of it. Still larger mountains of it exist at Kurunavara and Gelivara, in Lapland. Fahlun in Sweden, and Corsica, afford octahedral crystals, (f. 11), imbedded in chlorite state. Splendid dodecahedral crystals occur at Normark in Wermland. The most powerful native magnets are found in Siberia, and in the Hartz; they are also obtained on the island of Elba.

Extensive helds of magnetic occur in the contricts of Wayren. Essex and

Extensive beds of magnetite occur in the counties of Warren, Essex, and Clinton, New York, in granite, syenitic granite, or allied rocks; and in Orange, Putnam, Saratoga, Herkimer counties, &c., in gneissoid granite, either in isolated masses or layers alternating with the layers of gneiss, (Beck); also in the mountainous districts of New Jersey and Pennsylvania, and on the eastern side of Willis mountain in Buckingham Co., Virginia; at Franconia, N. H., in epidote and quartz, mountain in Buckingham Co., Virginia; at Franconia, N. H., in epidote and quartz, (f. 14); at Warwick, N. Y.; near Morgantown, Berks Co., Penn., (f. 11, 14); at Marlboro', Rochester, Bethel and Bridgewater, Vt., in chlorite or chlorite slate, (f. 11); at Swanzey, near Keene, and Unity, New Hampshire; at Deer Creek, Md.; at O'Neil mine, Orange Co., N. Y., (f. 1, 11, 14, 15, 17); at Webb's mine, Columbia Co., Penn.; at Haddam, Conn., (f. 18, 19, 169); at Hamburg, near Franklin furnace, N. J.; at Raymond, Davis's Hill, Maine, in an epidotic rock, Masses strongly magnetic occur at Marshall's Island, Me.; also at Magnet Cove, Arkansas; at Goshen, Chester Co., Pa. Large beds at Hull, South Crosby, Marmora and Madret Canada West, and Bromet Sutton Canada East, at Sutton in crystals. dre, Canada West, and Bromet, Sutton, Canada East, at Sutton in crystals.

No ore of iron is more generally diffused than the magnetic, and none superior for the manufacture of iron. It is easily distinguished by its being attracted readily by the magnet, and also by means of the black color of its streak or powder, which is some shade of red or brown in specular iron and brown iron ore. The ore when pulverized may be separated from earthy impurities by means of a magnet, and machines are in use in many parts of Northern New York for cleaning the ore on a large scale.

Disagnetite of Shepard (Am. J. Sci. [2], xiii, 392) appears to be a magnetite pseudomorph. The slender rhombic prisms occur upon a surface which is covered with small cubo-octahedrons, dodecahedrons and cubo-dodecahedrons of magnetite, and some small irregular cavities in the dimagnetite crystals contain similar crystals; moreover no difference of lustre is perceived in a fractured surface of the magnetite and dimagnetite. The species imitated in the pseudomorph is probably Lievrite. The angle of the prism varies between 110° and 115°, according to the author's measurements; (Shepard gives the angle 130°.). One crystal gave approximately 110° and 70°; another 114° 20' and 65° 40'; another 112° and 68°, and the obtuse edge was beveled in this last crystal by planes (12) inclined to the larger ones at an angle of about 16010. The faces are even but not very bright. From

Monroe, Orange Co., N. Y.

ALTERED FORMS.—By deoxydation through organic matter changed to protoxyd, which may become a carbonate or spathic iron. By oxydation becomes seaquioxyd of iron or Specular iron. Pseudomorphs of chlorite after magnetite have been reported.

PRANKLINITE, Berth.

Monometric. Observed planes 1, I, O, 2, 22. Figs. 11, 16, 19, common. Cleavage: octahedral, indistinct. Also massive, coarse or fine granular to compact.

H.=5.5-6.5. G.=5.069, Thomson; 5.091, Haidinger. Lustre metallic. Color iron-black. Streak dark reddish-brown. Opaque. Fracture conchoidal. Brittle. Acts slightly on the magnet.

Composition.—(Fe, Zn, Mn), (Fe, Mn). Analyses: 1, Berthier, (Ann. des Mines. iv, 189); 2, Thomson, (Min. i, 438); 3, Abich. (Pogg. xxiii, 342); 4, 5, G. J. Dickerson, (C. T. Jackson's Rep. on N. J. zinc mines):

	₽e	₩n	Z n
1.	66.	16.	17. = 99, Berthier.
2.	66.10	14-96	17:48, Si 0:20, H 0:56=99:25, Thomson.
3.	68-88	18.17	1081 " 040, Al 078=98.99. Abich.
4.	66-07	12-24	21:39 " 0:29=100, Dickerson.
5.	66.12	11-99	21.77 " 0.13=100, Dickerson.

B.B. infusible. On charcoal affords oxyd of zinc at a high heat. Manganese reaction with borax.

Stated to occur in amorphous masses at Altenberg, near Aix la Chapelle.

Abundant at Hamburgh, N. J. near the Franklin furnace, with red oxyd of zinc and garnet, in granular limestone; also at Stirling Hill, in the same region, where it is associated with willemite, in a large vein, in which cavities occasionally contain crystals from one to four inches in diameter.

The attempts to work this ore for sinc have proved unsuccessful; but it is ground up for a dark paint, and is used also as an ore of iron. The zine is said to give increased tenacity to the iron.

CHROMIC IRON. Chromite, Haid Chromate of Iron. Chromeisenstein. Eisenchrom. Fer Chromaté, H.

Monometric. In octahedrons, (f. 11). Commonly massive, structure fine granular, or compact.

H.=5.5. G.=4.321, crystals, Thomson; 4.498, a variety from Styria; 4.568, Texas, Pa. Lustre submetallic. Streak brown. Color between iron-black and brownish-black. Opaque. Fracture uneven. Brittle. Sometimes magnetic.

Composition.—Fe Cr, or (Fe, Mg) (Al, Cr). Analysis: 1, 2, Seybert, (Am. J. Sci. iv, 321); 3, 4, Abich, (Pogg. xxiii, 335); 5, 6, Laugier, (Ann. d. Mus. d'Hist. N. vi); 7, 8, T. S. Hunt, (Logan's Rep. Geol. Canada, 1849); 9, Moberg, (J. f. pr. Ch. xliii, 119); 10, A. Rivot, (Ann. Ch. Phys. [3], xxx, 202); 11, C. Bechi, (Am. J. Sci. [2], xiv, 62); 12, 13, Starr and Garrett, (Am. J. Sci. [2], xiv, 45):

		Ėе	Mg	ër	X 1	Ŝi
1.	Chester Co. Pa.,	35'14		51.56	9.72	2.90=99.32, Seybert.
2.	Baltimore,	36.00	-	39.51	13.00	10.60=99.11, Seybert.
3.	Baltimore, massive,	18.97	9.96	44.91	13.85	0.83=98.25, Abich,
4.	" cryst.	20.13	7'45	60.04	11.85	=99.45, Abich.
5.	Siberia,	24	-	53.	11.	1. Mn 1=100, Laugier.
6.	Röraas,	25.66	5.36	54.08	9.02	4.83=98.95, Laugier.
7.	Bolton, Canada,	35.68	15.03	45.90	3.20	=99.81, Hunt.
8.	L Memphramagog,	21.28	18.13	49.75	11.30	=100'46, Hunt.
9.	Beresof,	18.42	6.68	64.17	10.83	0.91=101.01, Moberg.
	Baltimore,	80.04	-	63.37	1.95	2.21 a Ca 2.02=99.60, Rivot.
	Volterra, Tuscany,	33.93	-	42.13	19.84	4.75=100.65, Bechi.
		38.95	-	60.84	0.93	0.62, Ni 0.10, Starr.
13.	Texas, Pa.	38.66		63.38	-	" 2.28, Garrett.
			a Wit	h some Ti	tanic Ac	id?

In Moberg's analysis, the chromium is supposed to be partly protoxyd, giving the formula (Fe, Mg, Cr) (Cr, A). Garrett's analysis of the Texas ore corresponds to Fe Cr 93·16+Fe Fe 0·59+Ni Fe 7·15. In grains that were magnetic, Garrett found Cr 41·55, Fe 62·02, Si 1·25, corresponding to Fe Cr 61·07+Fe Fe 38·64+Si 1-25=100.96, (loc. cit.)

B.B. alone, infusible. With borax fuses with difficulty, but completely, to a beautiful green globule.

Chromic iron occurs in serpentine, forming veins, or in imbedded masses. It as-

sists in giving the variegated color to verde-antique marble.

Occurs in the Gulsen mountains, near Kraubat in Syria; in crystals in the islands of Unst and Fetlar, in Shetland; in the Department du Var in France; in Silesia and Bohemia; abundant in Asia Minor, (Am. J. Sci. [2], vii, 285); in the Eastern

At Baltimore, Md., in the Bare Hills, it occurs in large quantities in veins or At Baltimore, Md., in the Bare Hills, it occurs in large quantities in veins or masses in serpentine; also in Montgomery Co., six miles north of the Potomac; at Cooptown, Harford Co. and in the north part of Cecil Co., Md. In Pennsylvania, in W. Goshen, (crystals), Nottingham, Mineral Hill, and elsewhere; Chester Co., near Unionville, abundant; near Texas, Lancaster Co., very abundant. Massive and in crystals at Hoboken, N. J., in Serpentine and dolomite; sparingly at Milford and West Haven, Conn.; in the southwestern part of the town of New Fane, and in Jay, Troy, and Westfield, Vt.; Chester and Blanford, Mass.; on L à Vache, near San Domingo; in the gold sands of California; at Bolton and Ham, Canada East.

This ore affords the oxyd of chrome, used in painting, etc. The ore employed in England is obtained mostly from Baltimore. Drortheim, and the Shetland Isles: it

England is obtained mostly from Baltimore, Drontheim, and the Shetland Isles; it

amounts to about 2000 tons annually.

PITCHBLENDE. Protoxyd of Uranium. Pecherz, W. Pechuran, Haus. Nasturan, Kob. Gummierz, Pittinerz, Breit. Uranpecherz. Urane Oxydule, H.

Monometric. Observed forms, f. 11, 16, 19. Usually massive and botryoidal; also in grains; structure sometimes columnar or curved lamellar.

H.=5.5. G.=6.468-8. Lustre submetallic or greasy to dull. Color grayish, greenish, brownish, red, or velvet-black. Streak, brownish-black, or olive green, a little shining. Opaque. Fracture conchoidal, uneven.

Composition.—UT? Ramm. Analyses: 1, Klaproth, (Beit. ii, 197); 2, Pfaff, (Sehw. J. xxxv, 326); 3, Rammelsberg, (Pogg. lix, 35); 4, Ebelmen, (Ann. Ch. Phys. 1848, 498); 5, Scheerer, (Pogg. lxxii, 561); 6, Kersten, (Schw. J. lxvi, 18); 7, von Hauer, (Jahrb. geol. Reichs. 1853, 107):

U 86.5 FeFe 2.5 PbS 6.0 Si 5.0=100, Klaproth.

84.52

Fe 8-24 4-20 2-02, Co 1-42=100-46, Pfaff.
Fe 8-03 Pb 6-20 As 1-13, Oa 2-81, Mg 0-46, Si 5-30, Bi (with Pb and Cu) 0-65, H 0-36=99-09, Rammelsberg.
Fe 8-10 4-22 Mn 0-82, Ca 5-24, Mg 2-07, Na 0-25, O 3-32, Si 3-48, S 0-60, H 1-35=100-89, Ebelmen. 8. UU 79·15

" 75-91 **Fe 3**·10

76.6, Pb, met. acids, and Si 15.6 Mn 1.0 H 4.1, loss and rock 2.7, Scheerer.

5. 76.6, PD, met. scius, and Si 10.0 and 11., as trace, P 2.80, HF trace=99.36, K. 7. PU 80.52, Fe 2.86, Pb 6.07, Sb 2.09, S 1.18, Si 1.79, Ca. 2.97, Mg 0.64, H 0.48, C 0.89, v. Hauer.

The specimens for these analyses were from Joachimsthal, excepting Nos. 2, 6, and 7; and 6 is the so-called Gummiers; No. 5 is the crystallized variety; No. 7 was from Przibram. Vanadium and also selenium occur in the ore from Johans-

georgenstadt.

R.B. alone infusible, but in the forceps colors exterior flame green. With borax, melts to a dark yellow glass, which is dirty green in the reducing flame. With soda not dissolved, but yields the smell of arsenic. In the state of powder dissolves alowly in nitric acid, evolving red fumes of nitrous acid. Not acted on by muriatic acid, but affords easily a yellow solution with nitric acid. Not attractable by the magnet.

Pitchblende accompanies various ores of silver and lead at Johanngeorgenstadt, Marienberg, and Schneeberg in Saxony, at Joachimsthal and Pribram in Bohemia, and Retzbanya in Hungary. It is associated with uranite at Tincroft and Tolcarn mines near Redruth, in Cornwall; also near Adrianople, Turkey; at the Middletown feldspar quarry in octahedrons with truncated edges, according to Shepard.

It is very valuable in porcelain painting, affording an orange color in the enamelling fire, and a black color in that in which the porcelain is baked. A laboratory has been opened at Joachimstahl, where the ore is converted into uranate of sods for use.

The Pittiners of Breithaupt has an olive-green streak. H.=3-8.5. G.=4.8-5. The Gummiers of the same author has H.=2.5-8. G.=3.9-4.18. Color: hyacinthred, yellowish and reddish-brown, and looking like gum; contains nearly 15 per cent. of water.

CORACITE, Leconte, (Am. J. Sci. [2], iii, 173).

Resembles pitchblende. Amorphous, with a pitch-black color and gray powder. H.=3. Afforded J. D. Whitney, (Jour. Bost. Soc. N. H. 1849, vi, 36, and Am. J. Bci. [2], vii, 484):

Pb Ca O Fe Al H Si 59:30 5:36 14:44 7:47 2:24 0:90 4:64 4:35, Mg, Mn trace=98-70.

Excluding the carbonate of lime as impurity, the percentage becomes:

₽ 72.60, Pb 6.56, Ca 5.99, Fe 2.74, £l 1.10, Ĥ 5.68, Ši 5.88=100.

B.B. does not change nor tinge the flame. Gives the reaction of uranium with the fluxes. Dissolves readily without heat in dilute muriatic acid, effervescing strongly and yielding a green solution. On account of the ready solubility in acids, Mr. Whitney supposes the uranium to be in the state of peroxyd (3), and not U3, as in common pitchblende.

ELLASITE, Haidinger, (Pogg. 1853, iv, Erganz. 848). Resembles pitchblende and coracite and may be an impure mineral. Occurs in flattened pieces, occasionally

1alf an inch thick. H .= 3.5. G .= 4.086-4.237, v. Zepharovich. Lustre greasy-Color dull reddish-brown, inclined to hyacinth-red on thinnest dull, wax-yellow to orange. Subtranslucent. mbvitreous. dges; streak dull, wax-yellow to orange. Subtrans Composition.—According to F. Ragsky, (loc. cit.):

Fe Fe Ca Mg Pb \$\overline{\ove

B.B. like pitchblende. Decomposed by muriatic acid. At 100°C loses 5.81 per sent., and at 300°C, 4.77, making 10.58 per cent. of water. From the Elias mine, Joachimstahl, with fluor, dolomite, quartz, etc.

The carbonic acid may be combined with the lime and part of the magnesia as carbonate, making 5.7 per cent.

MELACONITE, D. Black Oxyd of Copper. Kupferschwärze.

Monometric? Occurs in cubes (pseudomorphs?) with truncated

angles. Cleavage: none distinct. Mostly massive.

H.=3. G.=6.25, J. D. Whitney; 5.952, Ramm. metallic to earthy. Color dark steel-gray in crystals, to black or grayish-black when massive. Opaque. Streak shining.

Composition.—CuO²—Oxygen 20·15, copper 79·85. Often with one to two per sent of impurities, consisting mostly of silica, lime, and iron, J. D. Whitney. B.B. in the inner flame yields easily a globule of copper.

Occurs at Copper Harbor, Kewenaw Point, Lake Superior, forming a vein in con-

glomerate, from which about 40,000 lbs. of the ore were removed; it is now exhausted. The crystals are imbedded in the masses, and Teschemacher and Hayes have considered them pseudomorphs after red oxyd of copper. J. D. Whitney objects to this view on the ground that the red copper of the vein is in octahedrons and not cubes, and that no evidence exists to prove that such a change has taken place. (See J. D. Whitney in Foster and Whitney's Report on Lake Superior Region, Part 2, p. 99).

The Kupferschwärze or Black Copper of Werner is an impure, earthy black oxyd

of copper, resulting from the decomposition of other ores, being mixed with more

or less sulphuret of copper, pyrites, and other impurities.

PLUMBIC OCHRE. Lead-ochre. Bleiglätte. Glätte.

Massive. Structure sometimes scaly crystalline.

G.=8.0. Lustre dull. Color between sulphur and orpimentyellow. Streak lighter than the color. Opaque. Does not soil.

Composition.—Pb=Oxygen 7:17, lead 92:83; more or less impure. Analysis by John, (Schw. J. iv, 219 and xxxii, 106):

Pb 89·10. Ö 3·84, Fe and Ca 0.48.

Melts readily before the blowpipe, and is easily reduced on charcoal to the metallic state.

It is said to occur at Badenweiler in Baden, in quartz. Gerolt states that it has been ejected from the volcanoes of Popocatapetl and Jztaccituall, in Mexico. It is found in many places in the provinces of Chihuahua and Cohahuila in considerable quantities, having been collected along the streams between Ceralvo and Monterey, being supposed to come from the range of mountain. sing supposed to come from the range of mountains running nearly north of Monterey. The specimens (often 2 or more cubic inches in size) are between orpi-ment and sulphur yellow in color, and glisten like a granular mica of a nearly solden color. The natural surface is slightly crystalline and shining; and when solden color. The natural surface is engage, yet broken it shows a scaly texture, (Bailey in Am. J. Sci. [2], viii, 420). Occurs also at Austin's mines, Wythe Co., Va.

This species may belong with the Trimetric Oxyds.

2. HEXAGONAL OXYDS.

WATER.

Rhombohedral. Usual in compound stellate forms, f. 210. Liquid above 32° F., and boils at 212° F. A cubic inch of pure water at 60° F., and 30 inches of the barometer weighs 252.458 grains. Colorless. Inodorous. Tasteless.

Composition.—HO=Oxygen 88.89, hydrogen 11.11.

The density of water is greatest at 39° 1 F., according to Joule and Playfair, (Phil. Mag., xxx, 41, 1847), the most recent investigators of this subject.

Observa obtained 89° 176; Hallström 89° 38; Blagden and Gilpin 89°; Hope 89° 5; Muncke 88.804. Below this temperature it expands as it approaches 32°, owing to incipient

water as it occurs in nature is seldom pure. It ordinarily contains some state as it occurs in nature is seldom pure. pheric air, often pure oxygen and carbonic acid, besides various saline ingredients. For analyses of the waters used in Boston, New York, and Philadelphia, by B. Hilliman, Jr., see Am. Jour. Sci. [2], ii, 218; and for another of that last mention by M. II. Boyo, see same Journal, ix, 123. In different mineral waters are found salts of magnesis, lime, iron, sods, potash, and sometimes traces of sine, aremie, lest, copper, antimony, and even tin, these ingredients being derived from the rocks of soil of the region. For citation of numerous recent analyses of Waters, see Kesgott's Min. Forsch., 1844–1849, and 1850–51. 2 vols. 4to. Vienna.

Note on the Crystallization of Ice, Leydolt, Wien. Akad. vii, 477. It also eccurs

under Trimetric forms, and is regarded as dimorphous.

ZINCITE, Haid. Red Zinc Ore. Red Oxyd of Zinc. Zinkoxyd, L. Zinc Oxyd. Rothzinkerz. Spartalite, B. and M.

Hexagonal; $O: 1=118^{\circ} 7'$; a=1.6208. In quartzoids with truncated summits, and prismatic faces I. 1:1=127° 40′, (to 43′), Rose, I:1=151° 53′; 152° 20′, Levy. Cleavage basal, eminent Usual in grains or coarse particles and disseminated masses, structure foliated; also granular.

11. =4-4.5. (1.=5.432-5.524. Lustre subadamantine. Street orange-yellow. Color deep red, also inclining to yellow. Translucent subtranslucent. Fracture subconchoidal. Brittle.

Composition.—Zn=Oxygen 1974, zinc 80°26; containing oxyd of manganest as an unessential ingredient. Analyses: 1, Berthier, (Ann. d Mines, iv, 483); 2, 3, Whitney, (Pogg. lxxi, 169); 4, A. A. Hayes, (Am. J. Sci. xlviii, 261):

1. Zn 88 Mn In 12=100, Berthier.

Mn trace, gangue (franklinite) 4.49, ign 1.09=100-03, Whitsey **2**. 94.45

96:19

3.70, undecomp. 0.10=99.99, Whitney. Mn 5.50, Fe 0.36, scales of specular iron 0.44=89.78, Hayes

Thin scales magnified and viewed by transmitted light are deep yellow. The author finds by means of a high magnifying power that this ore is free from forest sealer of red oxyd of iron or other substances; and consequently the color is pro-testly due as held by G. Rose and J. D. Whitney, to the presence of Mn. 18.18 alone infusible; with borax yields a yellow transparent glass. Dissolve

without effervescence in nitric acid. On exposure to the air, it suffers a partial decomposition at the surface, and becomes invested with a white coating, which is carbonate of zinc.

Occurs with Franklinite and also with calcareous spar at Stirling Hill, Sussex Co., sometimes in lamellar masses in pink calcite. It was first noticed, described, and analyzed, by Dr. Bruce, (Bruce's American Mineralog. Journ., vol. i. p. 96).

Mitscherlich has observed minute six-sided prisms in the iron furnaces of Königs-hütte, in Silesia, which he believes to be identical with this species. Similar crystals have been met with in the zinc furnaces near Siegen. It has been observed in considerable quantities in the furnaces and roast-heaps at the New Jersey zinc mines; surface drusy, color white to amber-yellow, (Am. J. Sci. [2], xiii, 417); also by M. Stadtmuller at the iron furnace of Van Deusenville, Mass. An oxyd of zinc mixed with hydrate of iron occurs on marmatite at Bottino in Tuscany, which sfforded C. Bechi (Am. J. Sci. [2] xiv, 62) Zn 31 725, Fe 47 450, H 20 825.


CORUNDUM. Sapphire. Emery. Oriental Amethyst, Topaz, Ruby, Emerald. Adamantine Spar. Rubin. Salamstein Smirgel. Korund. Demanthspath. Telésie. Corindon. Asteria of Pliny.

Rhombohedral; $R: R=86^{\circ} 4', O: 1(R)=122^{\circ} 26; a=1.363.$ Observed planes: rhombohedrons, $\frac{1}{3}$, $\frac{1}{2}$, 1(R), -2, -1; pyramids, $\frac{1}{4}2$, $\frac{1}{4}2$, 22, $\frac{1}{3}2$, $\frac{3}{3}2$, 42, $\frac{1}{3}62$, 82; scalenohedrons $\frac{2}{3}$, $\frac{2}{3}$, $\frac{1}{4}$, $(=\frac{1}{5},\frac{5}{4},\frac{5}{4})$; also I, i2, $i\frac{5}{7}$, O.

- $\frac{42}{3}$: $\frac{4}{3}$ 2 (pyr.)=128° 2′. 22: 22 "=124°.
- $i2: R=136^{\circ} 58'$.
- $2: 2=78^{\circ} 45'$

Cleavage: basal, sometimes perfect, but interrupted, commonly imperfect in the blue variety; also rhombohedral. Large crystals usually rough. Twins: face of composition R. Also massive granular or impalpable; often in layers from composition parallel to R.

H.=9. G.=3.909—4.16. Lustre vitreous; sometimes pearly on the basal planes, and occasionally exhibiting a bright opalescent star of six rays in the direction of the axis. Color blue, red, yellow, brown,



gray, and nearly white; streak uncolored. Transparent-translucent. Fracture conchoidal, uneven. Exceedingly tough when compact.

Sapphire is pure alumina crystallized.

The species Corundum includes sapphire, emery, corundum, and other varieties. Corundum embraces the opaque specimens, usually of dingy colors and often dark; emery the massive granular or compact variety, more or less impure, and sapphire, the brightly colored varieties. The following are analyses by J. Lawrence Smith, taken from an elaborate paper in the Amer. J. Sci. [2], x, 854, xi, 58. The column of hardness, gives the effective abrasive power of the powdered mineral, that of sapphire being 100; Mag. stands for Magnetite:

				H.	G.	₩ı	Mag.	Ċа	S i	Ĥ
1.	Sapphire of	of I	ndia,	100	4.06	97.51	1.89		0.80	—=10020 .
	Ruby of I			90		97.32	1.09		1.21	= 99·62 .
			Asia Minor,	77	3.88	92.39	1.67	1.12	2.05	1.60= 98.83.
4.	44	of	Nicaria,	65	8.92	87.52	7.50	0.82	2.01	0.68 = 99.53.
5.	44	of	Asia,	60	3.60	86.62	8-21	070	8.85	1.16=101.04
6.	"	of	India,	58	3.89	93.12	0.91	1 02	0.96	2.86 = 98.87 .
7.	66	of	India,	55	8.91	84.56	7.06	1.20	4.00	8.10= 99.92
	Emery,		·				₽e			
8.	Kulah,			57	4.28	68.20	33.25	0.92	1.61	1.90 = 101.18.
9.	Samos,			56	3.98	70.10	22.21	0.62	4.00	2·10== 99·08.
10.	Nicaria,			5 0	375	71.06	20.32	1.40	4.12	2.58= 99.48.
11.	Kulah,			58	4.02	63.00	30:12	0.20	2.36	8.36 = 98.34
12.	Gumuch,			47	3.82	77.82	8.62	1.80	8.13	3.11 = 99.48.
13.	Naxos,			46	8.75	68.53	24.10	0.86	3.10	4.72 = 101.31.
14.	Nicaria,			46	374	75.12	13.06	072	6.88	8·10== 98·88.
15.	Gumuch,			42	4.31	60.10	33.20	0.48	1.80	5.62 = 101.20
16.	Kulah,			40	3.89	61.05	27.15	1.30	9.63	2.00-101.18

B.B. unaltered, both alone and with soda; fuses entirely with borax, though with great difficulty; and also, if pulverized, with salt of phosphorus. Not attacked by acids. Friction excites electricity, and in polished specimens the electrical attraction continues for a considerable length of time.

The red sapphire is sometimes called Oriental ruby; the yellow, topaz; the

green, emerald; violet, amethyst; and hair-brown, adamantine spar; the asteriated

crystals, asteria, a name used by Pliny.

This species is associated with crystalline rocks, as granular limestone or dolomite, gneiss, granite, mica slate, chlorite slate. The fine sapphires are usually obtained from the beds of rivers, either in modified hexagonal prisms, or in rolled masses, accompanied by grains of magnetic iron ore, and several species of gema. emery of Asia Minor, according to Dr. Smith, occurs in granular limestone.

The best ruby sapphires occur in the Capelan mountains, near Syrian, a city of Pegu, and in the kingdom of Ava; smaller individuals occur near Bilin and Merowitz in Bohemia, and in the sand of the Expailly river in Auvergne. Blue sapphires are brought from Ceylon; this variety was called Salamstein by Werner. Corundum occurs in the Carnatic on the Malabar coast, in the territories of Ava, and elsewhere in the East Indies; also near Canton, China. At St. Gothard it occurs of a red or blue tinge in dolomite, and near Mozzo in Piedmont, in white compact feldspar. Adamantine spar is met with in large coarse hexagonal pyramids on the Malabar coast, in Gellivara, Sweden. Emery is found in large boulders at Naxos, Nicaria and Samos of the Grecian islands; also in Asia Minor, 12 miles east of Ephesus, near Gumuch-dagh, where it was discovered in situ by Dr. J. Lawrence Smith, associated with margarite, chloritoid, pyrites, calc spar, etc.; and also at Kulah, Adula, and Manser, the last, 24 miles north of Smyrna; also with the nacrite (1) of Cumberland, England. Other localities are in Bohemia, near Petachau, in the Ural, near Katherinenburg, and in the Ilmen mountains, not far from Miask; Frederick Valley, Australia.

Blue sapphire occurs at Newton, N. J., (now rare), with hornblende, mica, feldspar, and tourmaline, in granular limestone; red variety at Vernon, N. J., near State line, crystals often several inches long; crystals of bluish and pink colors occur at Warwick, N. Y., in the cavities of large crystals of spinel. At Amity, N. Y., white, blue and reddish crystals accompany spinel and rutile in granular limestone. In Pennsylvania, grayish corundum occurs in large crystals in Delaware Co.; near Village Green in Aston; at Mineral Hill in loose crystals; also in crystals at Unionville, Chester Co., abundant, with tourmaline in margarite, and in albite some masses weighing 4000 pounds, and crystals being occasionally 4 inches long. Pale blue crystals are found with kyanite at West Farms, Conn. near Litchfield. A boulder of blue massive corundum, affording broad cleavage surfaces, has been found in Buncombe Co., North Carolina; and crystals and massive corundum in place in Gaston Co.; and a fine red sapphire has been obtained in Cherokee Co., Georgia. In Canada at Burgess, red and blue. Red sapphire is the most highly esteemed. A crystal weighing four carats, perfect in transparency and color, has been valued at half the price of a diamond of the same size.

They seldom exceed half an inch in length. Two splendid red crystals, however, having the form of the pyramidal dodecahedron, and "de la longueur du petit doigt," with a diameter of about an inch, are said to be in the possession of the king of Arracan. Transparent blue sapphires are sometimes over three inches long.

The sapphire is cut by means of diamond dust, and polished on copper or lead

The sappnire is cut by means of diamond dust, and pointed on copper or lead wheels with the powder of emery.

The word sapphire is from the Greek σασφειρος, the name of a blue stone, and probably the lapis lazuli, which agrees with the character given it by Theophrastus, Pliny, Isidorus, and others. The latter remarks, "Sapphirus cœruleus est cum purpura, habens pulveres aureos sparsos," particles of iron pyrites, which are frequently disseminated through lapis lazuli, looking like gold. Corundum is a word of Asiatic origin.

ALTERED FORMS.—Corundum under some circumstances absorbs water and changes to disspore; and perhaps also to the mica-like mineral margarite. It is also re-

placed by silica, forming quartz pseudomorphs.

HEMATITE. Specular Iron. Iron Glance. Peroxyd of Iron. Red Iron Ore. Oligiste Iron. Micaceous Iron Ore. Red Hematite. Red Clay Ironstone. Red Ochre. Iron Foam. Eisenglanz. Rotheisenstein, W. Blutstein, Haus. Rotheisenerz. Eisenoxyd, L. Rother Glaskopf. Fer Oligiste, H.


Rhombohedral. $R: R=86^{\circ} 10', O: R=122^{\circ} 30'; a: 1.3591.$ Observed planes: rhombohedrons, $\frac{1}{16}$, $\frac{1}{4}$, $\frac{4}{5}$, $\frac{5}{8}$, 1(R), $\frac{5}{2}$, 4, -5, -2, $-\frac{3}{2}$, -1, $-\frac{1}{2}$, $-\frac{7}{4}$, $-\frac{1}{6}$, $-\frac{1}{8}$; scalenohedrons, 1^3 , $\frac{2}{3}^3$, $-\frac{1}{2}^3$, $\frac{1}{8}^3$, 2^3 ; $\frac{1}{4}$, $-\frac{1}{8}^3$; pyramids, $\frac{1}{3}2$, $\frac{2}{3}2$, $\frac{4}{3}2$, $\frac{1}{3}0^2$, 42; prisms, I, I, I, I, I, I, and the basal plane O.

O: 2=107° 40′. 2:2=68° 47′. O: \$2=137° 49′. 5:5=61° 34′. O: \$2=118° 53′. ½: ½=143° 7′. $R: \frac{4}{3}2=154^{\circ} 2'.$ $R: \frac{1}{4}=143^{\circ} 55'.$

 $R:i2=136^{\circ}55'$.

 $O: 1^3 = 103^\circ 32'$. $\frac{1}{2}: \frac{1}{2} = 115^\circ 22'$. $1^3: i^2 = 162^\circ 41'$

Cleavage: parallel to \tilde{O} and R; often indistinct. Twins: face of composition R; also O. Also columnar—granular, botryoidal,



and stalactitic shapes; also lamellar—laminæ joined parallel to O. and variously bent—thick or thin; also granular—friable or compact.

H.=5.5-6.5. G.=4.5-5.3; of some compact varieties, as low as 4.2. Lustre metallic and occasionally splendent; sometimes earthy. Color dark steel-gray or iron-black; when earthy, red. Streak cherry-red or reddish-brown. Opaque, except when in very thin laminæ, which are faintly translucent, and blood-red. Fracture subconchoidal, uneven. Sometimes slightly attractable by the magnet.

Composition .- Fe=Iron 70, oxygen 30.

Composition.—Fe=Iron 70, oxygen 30.

B.B. infusible alone; with borax forms a green or yellow glass. Dissolves readily in heated muriatic acid, when pulverized.

This species includes the old species specular iron and red iron ore, the latter uncrystallized, and presenting the color of the former when in powder. Specular iron includes specimens of a perfect metallic lustre; if the structure is micaceous, it is called micaceous iron. The varieties of a sub-metallic or non-metallic lustre, were included under the name of red hematite, fibrous red iron; or if soft and earthy, red ochre, and when consisting of slightly coherent scales, scaly red iron, or red iron froth. Under this species must also be included different clay or argillaceous iron ores, many of which contain but small portions of iron; reddle or red chalk, the common drawing material, which has an earthy appearance and a flat conchoidal fracture; jaspery clay iron, more firm in its structure than the preceding, and having a large and flat conchoidal fracture; columnar and lenticular argillaceous iron, distinguished by a columnar or flat granular structure. Itabirite is a granular slaty rock consisting of specular or magnetic iron and quartz. rock consisting of specular or magnetic iron and quartz.

Specular iron occurs in crystalline rocks; also among the ejected lavas of Vesus, etc. Argillaceous ores form beds in secondary rocks. It is usually an associate

Fine specimens of this species are brought from the island of Elba, which has afforded it from a very remote period, and is described by Ovid as "Insula inexhautis chalybdum generosa metallis." The surfaces of the crystals often present a irised tarnish, and brilliant lustre. The faces O and 4 are usually destitute of this irised tarnish, and brilliant lustre. The faces O and ‡ are usually destitute of this tarnish and lustre, and may therefore assist, when present, in determining the situation of other planes when the crystal is quite complex. St. Gothard affords beautiful specimens, composed of crystallized plates grouped in the form of rosettes, and accompanying crystals of feldspar. Near Limoges, France, it occurs in large crystals. Fine crystals are the result of volcanic action at Etna and Vesuvius, and particularly in Fossa Kankarone, on Monte Somma, where it increases the ejected lavas. Arendal in Norway, Langbanshyttan in Sweden, Framont in Lorraine, Dauphiny, and Switzerland, also afford splendid specimens. Red hematite occurs in reniform masses of a fibrous concentric structure, near Ulverstone in Lancashire, in Saxony, Bohemia, and the Hartz. In Westphalia it occurs as pseudomorphs of calcareous spar. In Brazil it is associated with quartz.

Hematite, both compact, micaceous, and jaspery, is abundant in St. Lawrence

calcareous spar. In Brazil it is associated with quartz.

Hematite, both compact, micaceous, and jaspery, is abundant in St. Lawrence and Jefferson Cos., N. Y., at Gouverneur, Hermon, Edwards, Fowler, Canton, &c. Handsome irised crystallizations of specular iron are found at Fowler, in cavities in granular micaceous iron ore, associated often with splendid groups of quartz crystals. Other localities are Woodstock and Aroostock, Me., and Liberty, Md. Occurs also in the Blue Ridge, in the western part of Orange Co., Va. Micaceous iron in large masses, composed of irregular curved laminæ, occurs at Hawley, Mass, and Piermont, N. H.; also eight miles above Falmouth, Stafford Co., Va., on the Rappaleannock river: St. Armand Canada East. Red hematite is found at Ticonderogs. pahannock river; St. Armand, Canada East. Red hematite is found at Ticonderoga, upon Lake George. The iron mountain and Pilot Knob of Missouri are situated about fourteen miles from the La Motte lead mines, and ninety miles south of St. Louis. The Iron Mountain is 300 feet in height, and consists wholly of massive peroxyd of iron lying in loose blocks, which are largest about the summit, many 10 to 20 tons in weight. The Pilot Knob is estimated by J. D. Whitney at 650 feet in height; it is made up of a quartzose rock of the azoic period and is capped with specular iron which has an appearance of stratification and is micaceous in structure. Lenticular argillaceous ore is abundant in upper Silurian rocks, in Oncida, Herkimer, Madison, and Wayne Cos., N. Y., constituting one or two beds, ten to twenty inches thick, in a compact sandstone; and the same exists in similar strata in Pennsylvania and as far south as Alabama. Large beds exist at Wallace Mine, Lake Huron and McNab, and Marmora, Canada West.

This ore affords a considerable portion of the iron manufactured in different coun-ies. The varieties, especially the specular, require a greater degree of heat to smelt than other ores, but the iron obtained is of good quality. Pulverized red hematite is employed in polishing metals, and also as a coloring material. This species is readily distinguished from magnetite by its reddish streak.

Hematite, a word in use among the ancients, was applied to this species on account of the red color of the powder, from dips, blood. The term specular alludes


to the brilliant lustre it often presents.

ALTERED FORMS.—By deoxydation through organic matter forms magnetite or protoxyds; and from the latter comes spathic iron by combination with carbonic acid; or by further deoxydation through sulphuretted hydrogen, forms pyrites. By combination with water, forms Limonite. Limonite, magnetite, and pyrites, constitute occurring pseudomorphs after Hematite.

ILMENITE, Kupffer. Titanate of Iron. Crichtonite, Bournon. Titaniferous Iron. Menaken, Menaccanite, Kibdelophan, Basanomelan, Kobell. Titaneisen. Hystatite. Washingtonite, Shepard. Mohsite, Levy. Titaniferous Iron.

Rhombohedral; tetartohedral to the hexagonal type. R:R=85° 40'-86° 10', 86° 5, Rose and Descloizeaux, 85° 59', Mohs.

Observed planes: rhombohedrons $\frac{2}{5}$, 1(R), -5, $-\frac{2}{5}$, -2, $-\frac{1}{2}$; pyramids, $\frac{2}{5}$ 2, $\frac{4}{5}$ 2, which are hemihedral; also I, i2, O. Angles nearly as in Hematite. Often a cleavage parallel with the terminal plane, but properly due to planes of composition. Crystals usually tabular. Twins: face of composition O; sometimes producing when repeated a form resembling f. 313.



Often in thin plates or laminæ, angular masses or grains. H.=5-6. G.=4.5-5. Lustre submetallic. Color iron-black.

Streak metallic, black to brownish-red. Opaque. Fracture conchoi-Influences slightly the magnetic needle.

VARIETIES.—This species includes several varieties which have been considered distinct species. They are however identical in crystallization, and the differences arise, as shown by Rose, from the isomorphous nature of titanic oxyd and peroxyd

of iron. The following are the most important of these varieties:

Azotomous Iron, Kibdelophan of Kobell.—Physical characters as above. H.=5 —5.5. G.=4.661, Mohs; 4.723-4.735, Breit. Occurs in crystals; usually massive, or in thin plates or laminæ; $R:R=85^{\circ}$ 59.

Ilmenite. - Occurs crystallized and massive at Lake Ilmen, near Miask, whence the name *Umenite*. In general the physical characters the same as above. H.=6. G.=4.895, Breit.; R: R=85° 43′.

Mennaccanite.—Occurs massive with traces of cleavage and in grains. Fracture uneven to flat conchoidal. II.=5.5. G.=4.7—4.8. Streak black. Color light iron-black to steel-gray. Magnetic. First observed at Mennaccan, Cornwall. Crichtonite.—In acute rhombohedrons; R:R.=86° 64'; -5:-5=61° 27'. H.

=6. G.=479. Cleavage imperfect. From Oisans.

Hystatite. Hystatisches Eisenerz, Breit.—Titaniferous iron from Arendal. R: R=86° 10'. Cleavage, and color as in Ilmenite. H.=6. G.=5.

The Washingtonite of Shepard, (Am. J. Sci. xliii, 364), is near Hystatite. It oc-

curs in large tabular crystals, sometimes two inches in diameter. They are hexagonal tables with the faces of the rhombohedron; $R:R=86^{\circ}$, (obtained by varnishing the faces). Rhombohedral cleavage often distinct; O the brightest face, R the least so. H .= 575. G .= 4.963, from Westerly; 5.016, from Litchfield . Anal. 13, 14.

Eisenrose, Basanomelan of Kobell, is placed by Breithaupt along with hystatita Titaniferous iron sand or trappisches eiseners of Breithaupt, is described as occurring in octahedrons and cubes in roundish grains. It is iserine, (p. 102).

The titaniferous iron of Aschaffenburg.—Occurs massive and in plates, with imperfect cleavage in one direction. H.=6. G.=4.78. Color iron-black.

Composition.—Ti and Fe in various and probably indefinite proportions. H. Rose. Rose holds that the Ti (titanic acid) and Fe (protoxyd of iron) found in analyses, arise from an oxydation of the titanic oxyd (Ti) of the mineral, at the expense of the Fe, which takes place during the investigation. Berzelius sustained the view of Rose both on atomic grounds, and on that of the magnetism of the mineral. Rose shows that the specific gravity increases with the proportion of iron.

Analyses: 1, Kobell, (Schw. J. lxiv, 59, 245); 2, Marignac, (Ann. Ch. Phys. [3], xiv, 50); 3, 4, Mosander, (K. V. Ac. H. 1829, 220, and Pogg. xix, 211); 5, Delesse. (Thèse sur l'empl. de l'anal. etc. p. 46); 6, H. Rose, (Pogg. iii, 163); 7, Kobell, (loc. cit.); 8-12, Mosander, (loc. cit.); 13, Kendall, (This work, 2d edit. p. 527); 14, Marignac, (loc. cit.); 19, Plantamour, (J. f pr. Chem, xxiv, 302); 16-18, Kobell, (loc. cit.); 19, Rammelsberg, (3d Supp. 122); 20, T. S. Hunt, (Logan's G. Rep. 1849, 1850, 105, and Amer. Jour. Sci. [2], xi, 231);

```
Fe
                                                        Fe
                                    Ti
  1. Kibdel. Gastein,
                                             4.25 36.00, Mn 1.65=100, Kobell.
                                  59:00
                                                     36.00, Mn 1.05—10.46.53=100, Marignac.
37.86, Mn 2.73, Mg 1.14=99.89, Mos.
35.37, Mn 2.39, Mg 0.60, Ca 0.25, Cr 0.38, Si 2.80=100.17, Mesander.
  2. Uricht. St. Cristophe, 52.27
                                            1·20
10·74
     Ilmenite, Ilmen, Mts., 46 92
                                  46.67
                                            11.71
  4.
                                                      14·1, Ca 0·5, Sn 0·5, Pb 0·2=101·4, D. 13·57=100, Rose.
  5.
                                  45.4
                    Egersund, 4373
          46
                                            4270
  6.
     Menace.
                                  48.24
                                            28.66
                                                      27.91=99.81, Kobell.
  7.
                                                      29-27, Ca 0.50, Mg 1.22, Er 0.33, Si 1.65=
                                  42.57
                                            23.21
                                                      29 04, Ca 0 49, Mg 1 94, Yt and Te 0 58, Si
  9.
                                  41.08
                                            25.93
                                           29·16 27·23, Ča 0·96, Mg 2·30, Mn 0·21, Er 0·12. Ši
         n. all
10.
                                  39.04
                                                                                            0.31=99-13, M
                                                      19-91, Ča 0-33, Mg 0-68, Ši 1-17=99-29, M. 13-90, Ča 0-86, Mg 1-10, Čr 0-44, Ši 1-88,
                                  24:19
                                            53.01
11. Hystatite, Arendal,
                                  28.59
                                            58.51
12.
                                                                                                 =100.28, M.
                                                      22.86=99.98, Kendall.
                   Conn.
                                  25:28
                                            51.84
13
                                                      18.72=100, Marignac.
11.32 F. Si and loss 1.87=100, Plant.
10.04, Mn 0.80,=100, Kobell.
                                  22.21
                                            59.07
15. Titan. I. Uddewalla, 15:56
                                            71-25
        " Aschaffenberg, 14:16
                                           75'00
17. Basanom. Schweiz, 12-67
18. Titanic I. " 10-0
                                                       4.84=100, Kobell.
1.5 with Mn=100, Kobell.
                                            82.49
18. Titanic I. " 10.0 88.5 1.5 with Mn=100, Kobell.

19. "Binnen, Ti 8.58 Fe 91.42=100, Rammelsberg. [Hunt. G.=4.66.

20. St. Paul, Canada, Ti 48.60 Fe 46.44, including some peroxyd, Mg 3.60=98.64,
```

A large crystal from Miask gave E. E. Schmid (Pogg. lxxxiv, 498), Ti 28:05, Fe 707, In 07:=99.9. Specific gravity of Miask mineral, 4:579—4:780, and after long heating 4:950—4:963, Kengott, (Min. Unters. ii, 124).

The proportion of peroxyd of titanium to peroxyd of iron in analyses 1 to 20, according to the view of Rose, is as follows:—

```
1: #6 (G. 4-66)=53-6 peroxyd of Ti, to 46-4 peroxyd of Fe.
1: 1 (G.4-727)=48-1 " " 51-9 " "
4: 5 (G. 4-77)=42-5 " " 57-5 " "
2: 3 (G. 4-74)=38-2 " " 61-8 " "
1: 3 (G. 4-93)=23-6 " " 76-4 " "
1: 4 (G. 4-96)=18-8 " " 81-2 " "
1: 6 (G. 4-78)=13-4 " " 86-6 " "
Anal. 1,
             2,
              3-5,
              6-9,
            11,
            14,
            15,
            17,
                              1:8
                                                                =10.4
                                                                                                                              89.6
                              1:10(G.5·127)= 8·5
                                                                                                                              91.5
```

B. B. alone unchanged. With salt of phosphorus in the reduction flame, a dull red glass. Dissolves very slowly in muriatic acid.

Fine crystals of ilmenite, sometimes an inch in diameter, occur in Warwick, Amity, and Monroe, Orange County, N. Y., imbedded in serpentine and white limestone, and associated with spinel, chondrodite, rutile, &c.; also four miles west of Edenville, and near Greenwood furnace with spinel and chondrodite; also at South Royalston, Mass. Vast deposits or beds of titanic iron occur at St. Paul's Bay and Canada, with rutile in syenite; one bed 200 feet long and 90 broad; also at Vandreuil Beauce, mixed with magnetite as a vein in serpentine; G.=4.56-4.66. Also with labradorite at Chateau Richer. Grains are found in the gold sand of California.

PLATTNERITE, Haid. Superoxyd of Lead. Schwerbleierz, Breit.

In hexagonal prisms with replaced basal edges, planes O, I, 1, but pseudomorphous after pyromorphite, (Greg); cleavage indistinct. G.=9:39-9:45. Lustre metallic adamantine. Color iron-black. Streak brown. Opaque.

Composition.—Pb O²=Lead 86.6, oxygen 13.4. Probably from Leadhills, Scotland. A doubtful species.

TENORITE, Semmola. Opere Minori di Giovanni Semmola, Napoli, 1841, p. 45. Bull. Soc. Geol. de la France, xiii, 1841-42, p. 206.

Hexagonal? Crystals small tabular or like scales. Lustre metallic. Color dark steel-gray. Streak black. Thin folia translucent and brown.

Composition.—Cu O²=Oxygen 20·15, copper 79·85.

Found on lava at Vesuvius, in minute scales from 2¹0 to 1 of an inch in diameter, often hexagonal, and sometimes triangular. Usually associated with common

The Melaconite (p. 109) may belong here, if the observed cubes of the mineral were pseudomorphs, which is hardly probable.

III. DIMETRIC OXYDS.

BRAUNITE. Hartbraunstein, Haus.

Dimetric; $0:1i=135^{\circ}26'; a=0.98525$. Observed planes O, 1, 2, 22:

O: 1=125° 40′. *O*: 2=109° 45′.

2: 2 (pyr.)= 96° 33′. 22: 22 (pyr. axial)=128° 17′.

22: 22 (pyr. diag.)=144° 4′. $1: 1 \text{ (pyr.)} = 109^{\circ} 53'.$

1:1=109° 46′ and 108° 53′, according to Descloizeaux. Occurs also massive.

H = 6 - 6.5G = 4.75 - 4.818. Lustre submetallic. and color dark brownish-black. Fracture uneven. Brittle.

```
Composition.—Mn(—MnMn)—Manganese 69.68, oxygen 30.32. Analyses: 1, Turner, (Edinb. Trans. xi); 2, Tronsager, (Pogg. lxv, 276); 3, C. Bechi, (Am. J. Sci., [2], xiv, 62); 4, A. J. Scott, (Jameson's J., 1852, liii, 277); 5, Damour, (Ann. d. Mines, [4], i, 400):
```

- 1. Eglersburg, Mn 86 94 Tellemark, Mn 86 40 O 9.85 Ba 2.26 H 0.95 Si trace=100, Tur.; G. 4818. 6.22, Fe 1.57, gangue 3.62 1.98
- Mn 88.31 3.08 1.08 2:08 075, Fe 475=100, Bechi. 4. Vizianagram, Mn 7379 1.86 Mg 2.34. 0.24 8.30, Fe 12.91=99.74, S. G.=4.50.
- " 67.37 Mn 19.17 Oa 1.22 771, Pe 1.45, gangue, 272. 5. Marceline.

B.B. alone infusible. With concentrated muriatic acid evolves chlorine, and Marceline gelatinizes.

Occurs both crystallized and massive, in veins traversing porphyry, at Oehresstock, near Ilmenau, at Eglersberg in Thuringia; also near Ihlefeld in the Hart, at St. Marcel in Piedmont; at Elba; at Vizianagram in India. Found also at Brandon and Chittenden, Vt. The species was named in honor of Mr. Braun of

Marceline is an impure Braunite, as shown by Damour and Descloizeaux. Descloi-

zeaux's measurements were from St. Marcel crystals. G.=475, Damour.
Braunite is supposed by Volger (on the ground of an approximation in form to rutile) to be an altered mineral, changed by deoxydation from Mn; but the angle differ rather widely.

HAUSMANNITE. Black Manganese. Red Oxyd of Manganese. Braunstein, Haus. Manganèse Oxydé Hydraté, H.

Dimetric; $O: 1i=130^{\circ} 25'; a=1.1743$. Observed planes 1, $\frac{1}{3}$, 1*i*; forms octahedral.

```
$ : \frac{1}{3} (pyr.)=139° 57'.
1i: 1i "=114° 52'.
O: 1=121^{\circ} 3'.
1:1 (pyr.)=105° 25'.
                                             1 : 1i 142° 42'.
O: \frac{1}{3} = 151^{\circ} 2'.
```

Cleavage: basal, nearly perfect. Twins, parallel to 1i; nearly like f. 200; the same kind of composition sometimes between four

individuals. Also granular, particles strongly coherent. II.=5-5.5. G.=4.722. Lustre submetallic. Color brownishblack. Streak chestnut-brown. Opaque. Fracture uneven.

Composition.—Mn In = Manganese 72.1, oxygen 27.9 = In 69, Mn 31. Analyses: 1, Turner, (Trans. Roy. Soc. Edinb. xi); 2, Rammelsberg, (Pogg. xiv, 222):

```
₩n
                               0
                                       Вa
                                                8i
                                                        Ĥ
                98.902
                                                       0.435=100, Turner.
1. Ihlefeld,
                              0.215
                                       0.111
                                               0.337
2. Ilmenau, 92 487
                              7.004
                                       0.150
                                                            -99.641, Ramm.
```

B.B. acts like manganite. Dissolves in heated muriatic acid, affording chlorine Occurs with porphyry, along with other manganese ores, in fine crystals, near Ilmenau in Thuringia, and Ihlefeld in the Hartz. Reported also from Framont is Alsace. Observed at Lebanon, Penn.

CASSITERITE, Beud. Tin Ore. Oxyd of Tin. Peroxyd of Tin, Thom. Tin Stone. Wood Tin. Stream Tin. Zinnerz, Zinnstein, W. Etain Oxydé, H.


Dimetric; $(i): 1i=146^{\circ} 5'; a=0.6724.$

```
O: 1 = 136^{\circ} 26'. O: 3\frac{3}{2} = 112^{\circ} 25'.
                                                                   I: 1 = 133^{\circ} 34'.
```

$$O: \frac{5}{4} = 112^{\circ} 49'$$
. $1:1'(pyr.) = 121^{\circ} 40'$. $1i:1i(pyr.) = 133^{\circ} 31'$. $O: 13 = 144^{\circ} 40'$. $1:1(bas.) = 87^{\circ} 7'$. $I: i\frac{3}{2} = 168^{\circ} 42'$.

$$O: 13 = 144^{\circ} 40'$$
. $1: 1 \text{ (bas.)} = 87^{\circ} 7'$. $I: i\frac{3}{2} = 168^{\circ} 42'$.

Cleavage: I and ii hardly distinct. Twins: f. 205 plane of composition 1i; also f. 316. Often in reniform shapes, structure fibrous divergent; also massive, granular or impalpable.



H.=6-7. G.=6·3-7·1; 6·96, crystallized variety; 6·514, thin columnar variety. Lustre adamantine, and crystals usually splendent. Color brown or black; sometimes red, gray, white, or yellow. Streak white, grayish, brownish. Nearly transparentopaque. Fracture subconchoidal, uneven. Brittle.

Composition .- Sn=Tin 78.38, oxygen 21.62. Berzelius, (Afhand.iv, 164), found in a Finbo specimen:

> Sn 93.6 Ta 2.4, Fe 14, Mn 0.8=98.2.

In another specimen from the vicinity of Fahlun, Berzelius found 7 per cent. of columbic acid. Vauquelin obtained 9 per cent. of peroxyd of iron from wood tin.

B.B. on charcoal, reducible, but with difficulty; reduction takes place more rapidly if mixed with borax and carbonate of soda. Alone in the forceps infusible. Insoluble in acids. Fused with caustic potash it yields a mass which is mostly soluble in water; hydriodic acid throws down from the solution a yellow precipitate.

Tin ore is met with in veins traversing granite, gneiss, mica or clay slate, and

porphyry.

Cornwall affords remarkable simple crystals, associated with fluor, apatite, topaz, blende, wolfram, &c. The singular compound crystals come mostly from Bohemia and Saxony. The twin forms from Zinnwald and Schlackenwald often weigh several pounds. At Limoges splendid crystals occur. Also found in Galicia, Greenland, Sweden, and the peninsula of Malacca and the island of Banca in the East

The fibrous or wood tin occurs in botryoidal and reniform shapes of a radiated structure, and composed of concentric coats, and is found in Cornwall and Brazil.

Toad's eye tin is the same, on a small scale. Stream tin is the alluvial debris of tin veins which is separated from the gravel by washing. It occurs in the low grounds

The United States have afforded a few small crystals of tin at Chesterfield and Goshen, Mass., associated with albite and tourmaline; also at Lyme, N. H., and somewhat more abundantly on the estate of Mr. Eastman, in the town of Jackson, N. H., where it was discovered by Dr. C. T. Jackson; also observed sparingly in some of the gold mines of Virginia, by Prof. Rogers, imbedded in a talco-micaceous slate.

RUTILE. Nigrine. Gallicinite. Sagenite, Saussure. Crispite. Titane Oxydé, H. Titanic Acid, Thom. Eisentitan, Hausm.


Dimetric. $O: 1i=147^{\circ} 12\frac{1}{4}$, a=0.6442.

 $0:1=137^{\circ}40'$.

1:1 (pyr.)=123° 8′. I:i2=161° 34′. 1:1 (bas.)=84° 40′. I:i3=153° 26′. $0:33=113^{\circ}18'$.

 $I: i\frac{3}{2}=168^{\circ} 42'$. $0:1\bar{3}=145^{\circ}49'$. $ii: i2=153^{\circ}\ 26'$

1: 1=123° 7½', Kokscharov, Pogg. xci, 154, 1854. Cleavage I and ii, distinct. Vertical planes usually striated. Crystals often acic-



			0			
8						
1			13			16
	3 3 2					31
1	$i\frac{3}{2}$	i2	i3	i4	<i>i</i> 7	ii

Observed Planea

Often in singly and doubly geniculated crystals, (f. 206); composition parallel to 1i; also rarely parallel to 3i. Massive, compact.

II.=6-6.5. G.=4.18-4.25; 4.249, Ohlapian, Nigrine; 4.244, Snarum. Lustre metallic-adamantine. Color reddish-brown, passing into red; sometimes yellowish, also black. Streak pale brown Subtransparent-opaque. Fracture subconchoidal, uneven. Brittle

Composition.—Titanic Acid, Ti=Titanium 60.98, oxygen 39.02. The black variety nigrine, contains 1.5 to 2.5 per cent. of oxyd of iron. Analyses: 1, Damour, (Ana. Ch. Phys. [3], x, 417); 2, Kersten, (J. f. pr. Chem. xxxvii, 170); 3, 4, Demoly, (Lieb. u. K. Jahresb. 1849, 728); 5, H. Müller, (J. f. pr. Ch. lvii, 184):

Ti ₽e

1. St. Yrieix, rdh. subtrp. G.=1·209, 97·60 1·55=99·15, Damour.
2. Freiberg, nigrine. G.=4·242, 96·75 1·40 with magnetite=99·15, Kersten.
3. Ti 96·41 Fe 1·63 Mm 0·13, Si 1·83=100, Demoly.
4. 96·45 1·62 "0·14, "1·79=100, "
5. Terschenreuth, 86·2 Fe 14·2 =100·4, H. Müller. G.=4·56.

The magnetite in No. 2 was easily separated by a magnet after pulverizing. B.B. unaltered. With borax forms a hyacinth-red bead in the outer flame, less pure than the color with anatase.

Rutile occurs in granite, gneiss, mica slate, and syenitic rocks, and sometimes in granular limestone. It is generally found in imbedded crystals, often in masses of quartz or feldspar, and frequently occurs in acicular crystals penetrating quartz. It has also been met with in specular iron.

Brazil affords acicular crystals in limpid quartz; also occurs in Arendal in Norway; Saualpe, Carinthia; in the Urals; in the Tyrol; at St. Gothard; at Yrieix, in France; Krummhennersdorf, near Freiberg; in Castile, in geniculated crystals, often large. At Ohlapian in Transylvania, Nigrine in pebbles; in large crystals in Porthshire; at Cairngorm, Scotland; at Craig Cailleach near Killin, and in Benderick in the Caring Charles of the Caring Charles o gloe, in isle of Burray, Shetland A variety from Karingsbricka in Sweden contains a small percentage of chrome, and is the titane oxyde chromifere of Hauy. Rough octahedrons, reticulated within, from Brazil, are supposed to be pseudomorphs after anatase.

Fine rutiles occur in Massachusetts, in gneiss at Barre, crystals occasionally an nch and a half in diameter; at Windsor, in feldspar veins intersecting chlorite date; at Shelburne, in fine crystals in mice slate; at Leyden, with scapolite; at Conway, with gray epidote. In Vermont, at Waterbury, Bristol, Dummerston, and Putney; also in capillary forms in transparent quartz, exceedingly beautiful, but schausted. In New Hampshire, sparingly at Lyme, with tourmaline; near Hanver, rarely in magnificent specimens of acicular crystals in quartz, only in loose nasses. In Maine, at Warren, along with tremolite and copper pyrites. In Consecticut, at Lane's Mine, Monroe, and in the adjoining town of Huntington. In New York, in Orange Co., a mile north of Edenville, with pargasite in linestone boulders; two miles east of Warwick, in granite with zircon; a mile east of Amity, in quartz with brown tourmaline, and two miles west, with spinel and corundum, and also two miles southwest, in dark-blue eight-sided prisms with red spinel and thondrodite; near Warwick, in slender prisms penetrating quartz; in New York Co., in veins of quartz, feldspar, and mice traversing granular limestone, at Kingsbridge; and in the limestone of Essex Co. In Pennsylvania, in fine long crystals, at Sadsbury, Chester Co., and the adjoining district in Lancaster Co.; at Parksburg, Concord, West Bradford, and Newlin, Chester Co.; at the Poor House quarry, Chester Co., in delicate crystals, sometimes iridescent, on dolomite. In New Jersey, & Newton, with spinel. In North Carolina, at Crowder's Mountain. In Georgia, in Habersham Co. In the district of Columbia, sparingly, at Georgetown. In Canada, small crystals with specular iron at Sutton, C. E.; in the ilmenite of Bay St. Paul, C. E., orange translucent grains, pure Ti, and probably rutile or brookite. The oxyd of titanium is employed for a yellow color, in painting porcelain, and also for giving the requisite tint to artificial teeth.

Rutile is so named from the Latin rutilus, which signifies a shining red. Saussure

named a reticulated variety sagenite, from saynva, a net.


ANATASE. Octahedrite, J. Oisanite. Titane Anatase, H.

Dimetric; commonly octahedral, or tabular: $0:1i=119^{\circ}26';$ a=1.7723.

 $O: \frac{1}{2} = 153^{\circ} 22'$. $O: 2i = 105^{\circ} 45'$. $2i: 2i \text{ (bas.)} = 148^{\circ} 30'$.

 $O: \frac{1}{2} = 160^{\circ} 47'$. $1: 1 \text{ (pyr.)} = 97^{\circ} 55'$. $1i: 1i \text{ (bas.)} = 121^{\circ} 8'$. $O: 1 = 111^{\circ} 45'$. $1: 1 \text{ (bas.)} = 136^{\circ} 30'$. $O: I = 90^{\circ}$.

Cleavage: 1 and O, perfect.



	0	
7		
15		31
	195	
$\frac{1}{3}$		
1		11
		21
I		ii

H.=5.5—6. G.=3.83—3.95; sometimes 4.11—4.16 after heating. Lustre metallic-adamantine. Color various shades of brown, passing into indigo-blue; greenish-yellow by transmitted light. Streak uncolored. Fracture subconchoidal. Brittle.

Composition.—Anatase, like rutile and brookite, is pure titanic acid. When heated it gives out a reddish-yellow phosphorescent light, which appears suddenly like a flame and is soon over. Rose found in crystals from Brazil 1.25 per cent. peroxyd of iron, and Damour obtained in an analysis, (Ann. Ch. Phys, [3], 10, 417). Ti 98-86, Fe 1-11, Sn 0-20=99-67.

Anatase occurs most abundantly at Bourg d'Oisans in Dauphiny, with feldspar, axinite, and ilmenite. Found in mica slate in the Grisons, in Bavaria, near Hof in the Fichtelgebirge, Norway, and the Urals; in chlorite in Devonshire; with Brookite at Tremadoc, in North Wales; in Brazil in quartz, and in detached crytals so splendent as to be sometimes mistaken for diamonds.

According to Beck, anatase accompanies native titanium in slags from the iron

furnaces of Orange County, N. Y.

IV. TRIMETRIC OXYDS.

CHALCOTRICHITE, Glocker. Capillary Red Oxyd of Copper. Haarformige Rothkupfererz. Kupferblüthe, Haus.

Trimetric. I: I=140°-150°, the prisms with the acute and obtuse edges truncate, Kengott. Observed planes, I, ii, ii. Usaally in fine capillary crystallizations grouped or reticulated. Cleavage: rhombohedral, perfect.

G = 5.8. Color cochineal and crimson-red.

Composition.—Identical with Red Copper. Kersten detected Selenium.
Occurs at Rheinbreitenbach, Moldawa, and at N. Tagilsk. Kengott's speciment were from each of these localities. A capillary red copper occurs also at the Ferkiomen copper mine, according to C. M. Wheatley.


Mr. Brooke has shown that the fibrous red copper of Cornwall and Siberia is monometric, the fibres being enlongated cubes. Kengott has recently confirmed

his own measurements.

CHRYSOBERYL. Cymophane, H. Krisoberil, W. Alexandrite.

Trimetric. $I: I=119^{\circ} 46'; 0: 1\bar{\imath}=140^{\circ} 59'; \alpha: b: c=0.81:$ 1:1.72.

- $\begin{array}{l} O: \frac{3}{2}\tilde{\imath} = 129^{\circ}\ 27',\ O: 1\tilde{\imath} = 154^{\circ}\ 49', \\ O: 1 = 136^{\circ}\ 52',\ O: 2\tilde{\imath} = 136^{\circ}\ 46', \\ O: 2 = 118^{\circ}\ 05',\ O: 3\tilde{\imath} = 125^{\circ}\ 20', \end{array}$ 1:1 (brach.)=93°44'. 1ī: 1ī (top)=101° 58'.
- 1%: 1% (top)=129° 38'. O: 22=128° 52'. 1:1 (mac.)=139° 53'. 3%; 3% (top)=70° 41'.



Cleavage parallel to ii; O less distinct. Twins: face of com-

position, 7, f. 209, 322.

H.=8·5. G.=3·5-3·8; 3·597, Haddam; 3·733, Brazil; 3·689, Ural, Rose. Lustre vitreous. Color asparagus-green, grass-green, emerald-green, greenish-white, and yellowish-green: sometimes raspberry or columbine-red by transmitted light. Streak uncolored. Transparent—translucent. Sometimes a bluish opalescence internally. Fracture conchoidal, uneven.

Composition.—(语e+基1*)=Alumina 80-2, glucina 19·8=100. Analyses: 1, 2, 3, Avdejev, (Pogg. lvi, 118); 4, 5, Damour, (Ann. Ch. Phys. [3], vii, 173):

```
₿e
                                                                                                                                                                                                                                        Æl
                                                                                                                                                                                                                     78.10 17.94 4.47=100.15, Avdejev; G.=8.7837.
  1. Brazil,
                                                                                                                                                                                                                  78-71 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-24, "
78-72 18-06 8-47=100-
2. "
3. Ural,
  4. Haddam, Ct., 76-02
```

B.B. alone unaltered; with soda, the surface is merely rendered dull. With borax,

or salt of phosphorus, fuses with great difficulty. No action with acids.

Chrysoberyl occurs in Brazil and also Ceylon, in rolled pebbles, in the alluvial deposits of rivers; at Marchendorf, in Moravia; also in the Ural 85 wersts from Exatherinenberg in mica slate, with beryl and phenacite; this variety, which is of an emerald-green color, and columbine-red by transmitted light, has been called Alexandrite. It is supposed to be colored by chrome like the emerald. At Haddam, Ct., 'it occurs in granite traversing gneiss, with tourmaline, garnet, beryl, automolite, and columbite. Found also in the same rock at Greenfield, near Saratoga, N. Y., with tourmaline, garnet, and apatite; in the granite of Orange Summit, Vt., at the deep cut of the northern railroad.

When transparent, and of sufficient size, chrysoberyl is cut with facets, and forms a beautiful yellowish-green gem. If opalescent, it is usually cut en cabochon.

The name Chrysoberyl, from χρυσος, golden, βηρυλλος, beryl, was employed by the ancients for a different mineral, which possibly was chrysoprase. The name Cymophane, from κθμα, wave, φαινω, to appear, alludes to a peculiar opalescence it sometimes exhibits.


BROOKITE, Levy. Jurinite, Soret. Arkansite, Shepard. Eumanite, Shepard.

Trimetric. $I: I=99^{\circ} 50' (-100^{\circ} 50'): 0: 1=131^{\circ} 42'; a:b:$ c=1.1260:1:1.1883.


```
O: \frac{1}{2}i = 150^{\circ} 42'.
                                 ii: i2=157^{\circ} 11'.
Q: \frac{13}{23} = 147^{\circ} 14'.
                                 ii:i7=159^{\circ}30'.
0:\bar{1}=124^{\circ}17'
                                  i\bar{2}:i\bar{2} (mac.)=134° 22′.
0: \frac{1}{3} = 143^{\circ} 45'.
                                             " =135° 14′.
                                  \frac{1}{2} : \frac{1}{2}
0:\bar{2}_{\frac{4}{3}}=111^{\sigma}34'.
                                              " =115^{\circ} 43'.
                                  1:1
O:1^{3}_{2}=132^{\circ}19'.
                                  1\tilde{2}: 1\tilde{2} (mac.)=101^{\circ} 3'.
0:55=101^{\circ}38'.
                                  12: 12 (brach.=135° 37'.
0:2i=117^{\circ}54'.
                                  2i : 2i \text{ (top)} = 55^{\circ} 48'.
I: ii = 139^{\circ} 55'.
                                 ii : 4i = 141^{\circ} 33'.
```


Cleavage: I, indistinct; O, still more so.


H.=5.5-6. G.=4.12-4.17, Brookite; 4.03-4.085, Arkansite, Whitney and Damour, 3.86—3.95, Rammelsberg; 3.81, Ural, Hermann. Hair-brown, yellowish or reddish, with metallic adamantine lustre and translucent, (brookite); also iron-black, opaque, and submetallic, (arkansite). Streak uncolored—grayish, yellowish. Brittle.



Observed Planes. Add? $i^{\frac{23}{4}}$, $\frac{7}{9}i^{\frac{1}{6}}$, Kokscharov; $\frac{4}{9}i^{\frac{1}{6}}$? D.







Composition.—Pure titanic acid, (Ti), like anatase. Analyses: 1, Hermann, (J. £ pr. Chem. xlvi, 404); 2, Demour, (Ann. d. M. [4], xv, 447):

Ti 94.09, 1. Urals, Fe 4.50, Al trace, ign. 1.40=100.00, Hermann. 99.36, 1.36, 078 -=101.45, Damour. 2. Arkansas,

Rammelsberg obtained 94.23 per cent. of titanic acid from the arkansite, and a

corresponding low specific gravity, while Whitney and Damour found little impurity and a higher specific gravity.


Brookite occurs at Bourg d'Oisans in Dauphiny; at St. Gothard, with albite and quartz; in the Urals, district of Slatoust, and near Missk; rarely at Val del Bove, Etna, with rutile; on Snowdon and near Tremaddoc, Wales; in thick black crystals (arkansite, f. 323) at Magnet Cove, Ozark Mts., Arkansas, along with elseolite and schorlamite; in small crystals from the gold washings of North Carolina; rare at Chesterfield albite vein, (Eumanite). Also lead mine at Ellenville, Ulster Co., N. Y., on quartz, (f. 325), with copper pyrites and galena.

I: I in Arkansite= $100^{\circ}-100^{\circ} 80'$, $12:12=101^{\circ} 80'$, and $185^{\circ} 15'$ to $135^{\circ} 50'$. In Eumanite, (f. 327, 328), some of the observed angles are I: I=100° to 101°, $\frac{4}{3}$ i: $\frac{4}{3}$ i=77° 49′, $i\frac{\pi}{4}$: $i\frac{\pi}{4}$ =140°—140° 15′, ii: $\frac{4}{3}$ =128° 20′—128° 80′, ii: $i\frac{\pi}{4}$ =108°. Am. J. Sci. [2], xii, 211, 897, xiii, 117. The chemical identity of eumanite and brookite has not yet been ascertained.

In Brookite from the Urals, I: I=99° 50', Kokscharov.

PYROLUSITE. Gray Ore of Manganese. Wad. Anhydrous Binoxide of Manganese, Turner. Graubraunsteinerz. Weichmangan. Weichbraunstein.

Trimetric. $I: I=93^{\circ}40', O:11=142^{\circ}11';$ a:b:c=0.776:1:1.066. Observed planes as in the figure. $O: \frac{1}{2}i = 160^{\circ}, I: ii = 136^{\circ}$ 50', $I: ii=133^{\circ} 10'$, $\frac{1}{4}i: \frac{1}{2}i'$ (top)=140°. Cleavage: I and ii. Also columnar, often divergent; also granular massive, and frequently in reniform coats. Often soils.



H.=2-2.5. G.=4.819, Turner; 4.97 when pure. Lustre metallic. Color iron-black, dark steel-gray, sometimes bluish. Streak black. Opaque. Rather brittle.

Composition.—Mn=Manganese 68.3, oxygen 36.7. Analyses: 1, Arfvedson, Schw. J., xlii, 210); 2, 3, Turner, (Edinb. Trans. 1828); 4, Scheffler, (Arch. d. Pharm. xxxv, 260):

	MnMn	0	Ba	Si	Ĥ
1. Undenaes,	88.56	14.58	-	-	1.86=100, Arfvedson.
2. Eglersburg,	84.05	1178	0.23	0.51	1.12=100, Turner.
3. Ihlefeld,	85.62	11.60	0.66	0.55	1.57=100, Turner.
4 Ilmenan	87-0	11:6	1.2	0.8	5.8. Fe 1.3. Ca 0.3. \$10.3. Scheffler.

In another specimen Scheffler found 97 per cent. of baryta. Specimens from near Battenberg, Hesse, afforded Schwarzenberg and Engelhardt, 96:45 to 100 per cent. of pure superoxyd of manganese, (Ann. d. Ch. u. Pharm. lxi, 262).

B.B. alone infusible; on charcoal loses oxygen. A manganese reaction with

borax. Affords chlorine with muriatic acid.

This ore is extensively worked at Eglersberg, Ilmenau, and other places in Turingia; also at Vorderehrensdorf near Mährish-Trübau, in Moravia, which place annually affords many hundred tons of the ore. Fine crystals occur near Johanngeorgenstadt, and at Hirschberg in Westphalia,, and crystalline plates at Matzka, Transylvania; also found in Timor. Occurs in the United States with psilomelane, abundantly in Vermont, at Bran-

don, Irasburg, Bennington, Monkton, Chittenden, &c., both crystallized (f. 328 A) and massive; at Conway, Mass., in a vein of quartz; at Plainfield and West Stockbridge, Mass.; at Winchester, N. H.; at Salisbury and Kent, Conn., forming velvet-

like coatings on limonite.

Pyrolusite parts with its oxygen at a red heat, and is extensively employed for discharging the brown and green tints of glass. It hence receives its name from $\pi\nu\rho$, five, and $\lambda\nu\omega$, to wash; and for the same reason it is whimsically entitled by the French, le savon de verriers. It is easily distinguished from psilomelane by its inferior hardness.

Appendix to Anhydrous Oxyds.

MINIUM. Mennige, Haus. Plomb Oxidé Rouge, H.

Pulverulent, occasionally exhibiting, under the miscroscope, crystalline scales.

G.=4.6. Color vivid red, mixed with yellow.

Composition.—Pb*O* [=Pb+2Pb*]=Oxygen 9°34, lead 90°66=100.

In the reduction flame of the blowpipe, globules of lead are obtained.

Occurs at Bleialf in the Eifel; in Badenweller, in Baden; in Brillon in Westphalia; island of Anglesey; and Grassington Moore and Weirdale, in Yorkshire Usually associated with galena, and also with calamine.

Found at Austin's mine, Wythe Co., Va., along with cerusite.

CREDNERITE, Rammelsberg. Mangankupferoxyd, Haus. Mangankupferers.

Monoclinic. Foliated crystalline. Cleavage: basal very perfect; less distinct in two other directions obliquely inclined to one another.

H.=4.5 G.=4.9-5.1. Lustre metallic. Color iron-black to steel-gray. Streak black, brownish.

Composition.—Cu* Mn*=Oxyd of copper 42.9, oxyd of manganese 57.1; but often mixed with oxyd of manganese. Analysis: 1, Credner, (Pogg. lxxiv, 555); 2-4, Rammelsberg, (Pogg. lxxxiv, 559):

```
Mn Mn Ou Ba Ca Ĥ O

1. Friedericharode, 22 96 81 25 42 18 0 52 0 63 0 25 — gangue 0 63 88 35, Cred.

2. " 52 55 — 40 65 1 48 — 5 78 = 100 46, Ramm.

3. " 54 72 — 34 65 2 71 — 6 51 = 98 49, Ramm.

4. " 64 24 — 23 73 2 01 — 8 83 = 98 81, Ramm.
```

B.B. fuses only on thin edges when strongly heated. With borax gives a dull

violet color, and with salt of phosphorus a green glass.

From Fredericherode, with volborthite, malachite, and manganese ores. Rammelaberg observes that this ore is the source undoubtedly of the cupreous manganese, a secondary product.

HETEROCLIN, Breithaupt; Evreinoff, Pogg. xlix, 204.

Monoclinic. An oblique rhombic prism of 128° 16': acute lateral edges of prism usually truncated, and two of the terminal edges replaced, (I: e=151° 87), and one of the front solid angles. Cleavage in one direction not very distinct. Also massive. H.=5. G.=4.652. Lustre submetallic. Color iron-black, inclining a little to steel-gray. Streak black, brownish. Fracture uneven to small conchoidal.

Composition.—Analyses by Evreinoff, (Pogg. xlix, 204): . Pe Βi ₩n Ċа ĸ 1. 10.80 85.86 872 0.62 0.44 = 100.942. 10.02 85.88 3.05 0.60 0.44-99.99.

B.B. acts like the peroxyd of manganese. This species occurs at St. Marcel in Piedmont, mixed with manganesian epidote and quartz. Named from δτεροκλῖνής, in allusion to its oblique form of crystallization.

Berzelius obtained for a manganese ore from Piedmont, Si 15·17, En 75·80, Fe 4·14, Al 2·80=97·91.

V. COMBINATIONS OF OXYDS WITH SULPHURETS OR CHLORIDS.

VOLTZITE. Voltzine, Fournet.

In implanted spherical globules; structure thin curved lamellar. H.=4.5. G.=3.66. Lustre vitreous to greasy; or pearly on a cleavage surface. Color dirty rose-red, yellowish, brownish. Opaque or subtranslucent.

Composition.—4Zn S+Zn O=Sulphuret of zine 82.73, oxyd of zine 17.27. Anal ysis: 1, Fournet, (Ann. Ch. Phys. zli, 426):


Zn S 82.92, Zn O 15.34, Fe 1.84, resinous matter trace=100.10.

J. F. Vogl finds the same composition for a specimen from Joachimstahl, (Jahrb. k. R. 220).

B.B. like blende. In muriatic acid affords fumes of sulphuretted hydrogen.
Occurs at Rosières in Puy de Dome; and Elias mine near Joachimstahl, with galena, blende, native bismuth, etc. Observed by Kersten in the slags of the iron works of Freiberg and Altenberg.

MATLOCKITE, R. P. Greg, Phil. Mag., [4], ii, 120, 1851.

Dimetric. $O: 1i=128^{\circ} 42'; a=1.2482.$ Observed planes, $O, I, 1, 2i. O: I=90^{\circ}, O: 2i=111^{\circ} 50\frac{1}{2}' O: 1=119^{\circ} 34', 2i: 2i \text{ (pyram.)} = 97^{\circ} 58', \text{ (basal)} = 136^{\circ} 19', 1: 1 \text{ (pyram.)} = 104^{\circ} 6', \text{ (basal)} 120^{\circ} 52'. \text{ Cleavage: basal not perfect. Crystals tabular.}$



H.=2·5—3. G.=7·21; 5·3947, in powder, Rammelsberg. Lustre adamantine, occasionally pearly. Color clear yellowish, sometimes a little greenish. Transparent to translucent.

Composition.—Pb Cl+Pb O=Chlorid of lead 55.5, oxyd of lead 44.5. Analysis by Dr. R. A. Smith, (loc. cit):

Pb Cl 55:177. Pb O 44.300, Moisture 0.072=99.549. Rammelsberg found, (Pogg. lxxxv, 141), Pb Cl 52:45, Pb O 46:42. Decrepitates when heated. B.B. fuses to a grayish-yellow globule.

From the old mine of Cromford near Matlock, with cerasine. Largest crystals an inch square and one-eighth thick.

MENDIPITE, Breit. Chlorid of Lead. Berzelite, Lovy. Kerasine, Beud. Cerasite.

Trimetric; I: I=102° 36'. Observed planes, O, I, ii, ii. Occurs in fibrous or columnar masses, often radiated. Cleavage I, highly perfect, diagonal less perfect.

H.=2·5—3. G.=7—7·1. Lustre pearly and somewhat admentine upon cleavage faces. Color white, with a tinge of yellow. red or blue. Streak white. Feebly translucent—opaque.

Composition.—Pb Cl+2PbO=Chlorid of lead 384, oxyd of lead 61 6 Analyses: 1, Berzelius, (K. V. Ac. H. 1823, Pogg. i, 272, and Ramm. 1st Supp. 24); 2, Schnsbel, (ib. 8d Supp. 78):

> 1. Pb Cl 39-82 PbO 60:18=100, Berzelius by Rammelsberg. 61-26=100, Schnabel. 8874

B.B. decrepitates slightly, and readily fuses, producing a globule of a deeper yellow color than the original specimen. On charcoal, lead may be obtained. Treated with peroxyd of copper and salt of phosphorus, the flame assumes an intensely blue color. Easily soluble in nitric acid.

This rare mineral occurs at the Mendip Hills, in Somersetshire, on earthy black manganese. Also at Tarnowitz, Silesia, in clay in opaque prismatic crystals; and near Brillon in Westphalia.

B. Hydrous Oxyds.

DIASPORE GROUP .- Ratio of oxygen of oxyd and water 8:1. Trimetric.

Æl Ĥ. DIASPORE, MAGANITE. ₩n H. (1 ₩n H'). **G**öтштв, ₽e Ĥ. POLIANITE,

LIMONITE GROUP.—Ratio of oxygen of oxyd and water 2:1.

LIMONITE,

BRUCITE GROUP.—Ratio of oxygen of oxyd and water, 1:1. Hexagonal.

Мg П. BRUCITE. GIBBSITE. Ăl Ĥ.


Appendiz .- Völknerite, Mg. Al+16H.-Psilomelane, B Mn. H.-Wad. Combination of Oxyde and Chloride.—ATACAMITE, Cu Cl+8Cu H.

DIASPORE. Hauy. Dihydrate of Alumina, Thom. Stephanite.

Trimetric. $I: I=93^{\circ} 52', 0: 1\bar{\imath}=147^{\circ} 38', a:b:c=0.634:1$: 1.07. Observed planes as in the figures.

Crystals usually thin flattened prisms, sometimes acicular; commonly implanted. Cleavage ii, eminent; also iz less perfect. Occurs foliated massive.

II.=6·5-7. (†.=3·3-3·5; 3·4324, Haüy; 3·452, Duf.; 3·30—3·34, Schemnitz diaspore. Lustre brilliant and pearly on cleavage faces; elsewhere vitreous. Color greenish-gray or hair-brown, yellowish to colorless, sometimes violet-blue in one direction, reddish plumb-blue in an-



other, and pale asparagus-green in a third. When thin, translucent—subtranslucent. Very brittle.

Composition.—Älff=85·1 alumina, 14·9 water. Analyses: 1, 2, Dufrénoy, (Ann. des Mines [3]. x, 577, 1837); 3, Hess, (Pogg. xviii, 255); 4, Damour, (Comptes Rend. xxi, 322); 5, Löwe, (Pogg. lxi, 307); 6, 7, J. L. Smith, (Am. J. Sci. [2], xi, 58); 8, Damour, (L'Institut, 1853, 78):

	X l	Ĥ	Fе	₿i
 Siberia, 	74.66	14.58	F e 4:51	2.90, Ca and Mg 1.64=98.29, Duf.
2.	78.93	15.13	" 0.52	1·39, Ča 1·98=97·95, Duf.
3. Miask,	85.44	14.26		=100, Hess.
4. Siberia,	79.91	14.90		unattacked 5.80==100.61, Dam.
Schemnitz,	85.131	15.00		—=100·131, Löwe. G.=3·303.
6. Gumuch-dag	h,83·12	14.28	0.66	0.82 Ca. Mg, trace=98.88, S. G.3.45.
7. Naxos,	82.94	14.81	1.06	0.26 Ca 0.35=99.42, S.
8. Bahia, S. A.,	84 02	14.59	₽ e 0.68	Si 0.43=99.72, Damour. G.=3.464.

In a matrass decrepitates strongly and separates into small white scales; finally yields water. B.B. infusible. With borax and salt of phosphorus dissolves slowly to a clear colorless glass. Not acted on by soda. A fine blue with cobalt solution. Not at all altered by concentrated and boiling sulphuric scid, except after calcins-

Occurs in chlorite slate, near Koroibrod, district of Katharinenburg in the Ural, and at Schemnitz in veins between dolomite and limestone; also at Broddbo near Fahlun; with corundum in dolomite at St. Gothard; at Gumuch-dagh and Manser, Asia Minor, and the Grecian Islands Naxos, Samos, and Nicaria, with emery, as detected by J. L. Smith.

GÖTHITE, Beud. Pecheisenerz, (in part). Nadeleisenerz, Naum. Pyrrhosiderite, Haus. Onegite. Lepidokrokite. Sammetblende. Stilpnosiderite. Rubinglimmer. Eisenrutil. Chileit, Breith.

Trimetric. I: I=94°52', B. and M. (95° 14', Levy, 96° Yorke), $O: 1\bar{\imath} = 146^{\circ} 33', a:b:c=0.66:1:1.089.$

- $O: 3\overline{3} = 115^{\circ} 44'.$ $O: 15 = 148^{\circ} 48'.$ $O: 1\overline{2} = 143^{\circ} 55'.$ $O: \frac{5}{2}5 = 121^{\circ} 8'.$ $1\frac{1}{2}: 1\frac{1}{2}$ (mac.)=151° 35, $i\frac{1}{2}: i\frac{1}{2}$ =130° 40′.
- $1:1(brach.)=121^{\circ} 4'. \ i\tilde{2}:i\tilde{(}ov.i\tilde{i})=122^{\circ} 52',$ $O: 1=138^{\circ} 6'$.



Observed Planes.

In prisms longitudinally striated, and often flattened parallel to the shorter diagonal. Cleavage: brachydiagonal, very perfect. Also fibrous; reniform; foliated or in scales; massive.

H.=5-5.5. G.=4.0-4.4. Lustre imperfect adamantine. Color yellowish, reddish, and blackishbrown. Often blood-red by trans-

mitted light. Streak brownish-yellow-ochre-yellow.

Composition.—Fe H=Peroxyd of iron 89.89, water 10.11. Analyses: 1-5, Kobell, (J. f. pr. Chem. i, 181, 319); 6, Brandes, (Nög. Geb. in Rheinl. Westph. i, 358); 7, Breithaupt, (J. f. pr. Chem. xix, 103); 8, Yorke, (Phil. Mag. [3], xxvii, 264):

```
₽e
                                                                           H

9·47=100, Kobell.

11·50, Mn 2·50, Ši 0·35=100, Kobell.

11·38, Mn 0·51, Ši 0·85, Ču 0·90=99·99, K.

10·68, P 1·08, Ši 2·00=100, Kobell.

10·80, Ši 2·88=100, Kobell.

10·75, Mn 0·50, Ši 0·5=99·75, Breithaupt.

10·3, Ču 1·9, Ši 4·3=100, Breithaupt.

10·07, Mn 0·16, Ši 0·28=100·06, Yorke.

    Lepidokrokite, Oberkirchen, 90.53
    H. Zug, 85.65

                                                              85.65
3. Göthite, Eiserfeld,
                                                               86.35
4. Stilpnosiderite, Amberg,
                                                               86.24
    Massive, Maryland,
                                                              86.82
6. Lepidokrokite, H. Zug,
                                                               88.00
7. Chileite, Chili,
                                                               83.2
8. Crystals, Lostwithiel, G.4.37,89.55
```

Before the blowpipe the varieties act like limonite.

The Lepidokrokite occurs in minute radiating crystals, or granular scales and feathery aggregations, imbedded in fibrous red oxyd of iron, in quartz, and in nodules of chalcedony. It has been found at Spring Mills, Montgomery County, Pa. The Göthite of Eiserfeld, in the County of Nassau, occurs in foliated crystallizations, (Rubinglimmer), of a hyacinth red color, with brown hematite. Other localities of Göthite are at Clifton, near Bristol, near Lostwithiel, and Botallack, in Cornwall, and at Lake Onega (Onegite) in Siberia, at Oberkirchen in Westerwald, Zwickau in Saxony, Eiserfeld in Siegen, Przibram, &c. A capillary variety (Sammetblende) occurs at Przibram and elsewhere. Stilpnosiderite occurs amorphous and stalactitic or massive. H.=45-5. G.=3.6-3.8; pitch-black and blackish-brown. Some specimens, according to Vauquelin's and Ullmann's analyses, are Limonite. The Sammetblende has been called Przibramite, from Przibram, where it occurs.

MANGANITE. Gray Manganese Ore. Gray Oxyd of Manganese. Acerdese, Bend. Grauer Bräunstein. Manganese Oxyde, H. Newkirkite, Thomson.

Trimetric. $I: I=99^{\circ} 40', O: 1i=147^{\circ} 9\frac{1}{2}'; a:b:c=0.6455:$ 1:1.185. Hemihedral in plane $\frac{6}{2}$.

```
0:2i=127^{\circ}46'.
                                O: 2\overline{2} = 128^{\circ} 18'.
                                                                      1\bar{3}: 1\bar{3} \text{ (mac.)} = 162^{\circ} 39'.
                                0:1i=151^{\circ}25'.
                                                                      i\bar{2}: i\bar{2}(\text{mac.})=134^{\circ}14'.
0:1\bar{3}=146^{\circ}9'.
0:1\overline{2}=144^{\circ}59'.
                               1:1(mac.)=130^{\circ}49'.
                                                                     i\tilde{z}: i\tilde{z} \text{ (br.)} = 118^{\circ} 48'.
O: 1 = 139^{\circ}49'. 1:1(\dot{b}rach) = 120^{\circ}54'. i = i = (\dot{b}r.) = 136^{\circ}54'.
```

Twins: plane of composition 1%. Cleavage: in very perfect, I perfect. Crystals longitudinally striated and often grouped. Also

columnar and granular.

II.=4. (1.=4.2-4.4. Lustre submetallic. Color dark steel gray—iron-black. Streak reddish-brown, sometimes nearly black. Opaque; minute splinters, sometimes brown by transmitted light. Fracture uneven.





Composition.—MnH=Mn 89-79, (=Mn 62-78, O 27-22), H 10-21. Analyses: 1, Arfvedson, (Schw. J. xxvi, 262); 2, Gmelin, (ib. xlii, 208); 3, 4, Turner, (Edinb. Trans'

		Mn	0	H
1.	West Gothland,	89-92	No. Sec.	10.08, Arfvedson.
2	Ihlefeld,	62.86	27:64	9.50, Gmelin.
3.	"	62.68	27.22	10-10, (by loss), Turner.
4.	44.	62.77	27.13	10-10. " Turner.

B.B. alone fusible; with borax yields a violet-blue globule. Insoluble in nitric acid; in muriatic acid gives off chlorine, and dissolves without a residue.

Occurs in veins traversing porphyry, associated with calcareous spar and heavy spar, at Ihlefeld in the Hartz; also at Ilmenau and Ochrenstock in Thuringia; in Aberdeenshire; at Undenaes in Sweden, and Christiansand in Norway.

Newkirkite, according to Lettsom, is nothing but manganite. Volger endeavors to show that the analyses of manganite are doubtful with regard to the water, and probably correspond to Mn H², like Xanthosiderite, (Stud. z. Entw. 391).

ALTERED FORMS.—By loss of water changes to pyrolusite, hausmannite, or braunite. Varvacite of R. Phillips, from Warwickshire, is considered an altered manganite, consisting largely of pyrolusite. Analysis by Phillips afforded, Mn 63°3, O 31°7, H 5°0. Breithaupt observed a crystal with nearly the angles of manganite, giving I: I=80° 24′ and 99° 36′. H.=2°5-3. G.=4°283-4°623.

POLIANITE, Breit.

Trimetric. $I: I=92^{\circ}$ 52·, $O: 1\bar{\imath}=147^{\circ}$ 43'; a:b:c=0.6317: 1: 1.0513. Observed planes $O,\ I,\ i\bar{\imath},\ i\bar{\imath},\ i\bar{\imath},\ i\bar{\imath},\ i\bar{\imath},\ i\bar{\imath},\ i\bar{\imath},\ i\bar{\imath}$ 2 $\bar{\imath}.\ 1\bar{\imath}:1\bar{\imath}=$ 118°, O: 11=149°. Cleavage: brachydiagonal, perfect. H.=6.5-7. G.=4.84-4.88. Resembles pyrolusite.

Composition .- Plattner obtained, (Pogg. lxi, 192),

Mn Mn 87-274, O 12:111, Fe and Al 0:165, quartz 0:132, H 0:318=100, and this is the composition of pyrolusite, or Mn. But according to Volger (Stud. z. Entw. Min.) it is an altered MnH, it being isomorphous with Göthite.

Occurs near Platten in Bohemia, also at Schneeberg, Geyer, and Johanngeorgenstadt in Saxony, and in Siegen; near Schwarzenberg, and near Ilmenau in Thuringia.

LIMONITE, Beud. Brown Hematite. Brown Iron Ore. Hydrous Peroxyd of Iron. Brown Ochre. Iron Stone. Yellow Clay Iron Stone. Brauneisenstein, Thoneisenstein, W. Gelberde. Eisenoxydhydrat. Brauner Glaskopf. Bog Iron Ore. Raseneisentein (bog ore), Morasterz, Sumpferz. Bohnerz.

Usually in stalactitic and botryoidal or mammillary forms, having a fibrous or subfibrous structure; also massive and occasionally earthy.

H.=5-5.5. G.=3.6-4. Lustre silky, often submetallic; sometimes dull and earthy. Color various shades of brown, commonly dark, and none bright. Streak yellowish-brown.

Composition .- Fe2 H2=Peroxyd of iron 85.6, water 14.4=100. The bog iron ore is often mixed with phosphates, (sometimes 10 or 11 per cent.), and also with some salts of organic acids formed in marshy ground. Analyses: 1, 2, Kobell; 3, 4, Karsten, (Arch. xv, 1); 5, Hermann, (J. f. pr. Ch. xxvii, 53):

15·01 1·61=100, Kobell. 13·46 0·67, P 3·00, Mn, Cu, Ča trace=100, Kobell. 26·40* 2·80, "0·12, Fe 3·6, Mn 0·75=100, Karsten. 29·50* 8·60, "3·90, "10·8, "1·75, Sand 22·75, Kar. 13·00 Mn 100, P 3·50, humic acid 2·5, Sand 47·5, Her. 1. Perm, fibrous, 83:38 2. Siegen, Pitchy Ore, 82.87 3. Bog ore, New York, 66.33 4. " Neumark, 57.50 Novgorod, 32.75 · With organic substances.

Hermann writes for the last (his Quellerz) the formula Fe H²—Fe 74.8, H 25.2.

A very pure stalactitic limonite from Amenia, N. Y., gave Beck, (Min. N. Y. p. 33), Peroxyd of iron 82.90, silica and alumina 3.60, water 13.50, with a trace of oxyd of manganese. In a limonite (bohnerz) from Staatswald Hardt, Württemberg, A. Müller found (J. f. pr. Chem. lvii, 124) 0.05 per cent. of chromic acid, and 0.08 per cent. of vanadic acid.

In a matrass yields water. B.B. blackens and becomes magnetic and thin splint-

ers fuse; with borax gives an iron reaction. Dissolves in warm nitro-muriatic acid.

The following are the principal varieties of this species. Brown hematite includes compact mammillary and stalactitic varieties. Scaly and ochrey brown iron ore are decomposed earthy varieties, often soft like chalk; yellow ochre is here included. Bog iron ore is a brittle or loosely aggregated submetallic ore, occurring in low marshy grounds. It proceeds from the decomposition of other species, and often takes the form of the leaves, nuts or stems, found in the marshy soil. Brown and yellow clay iron stone are hard and impure from admixture with clay or iron.

Limonite occurs in secondary or more recent deposits, in beds associated at

times with spathic iron, heavy spar, calcareous spar, aragonite, and quarts;

and often with ores of manganese.

Found in Cornwall, Clifton, Sandloge in Shetland, in Carinthia and Bohemia, at Siegen near Bonn, and at Villa Rica in Brazil. The bog ore forms large beds in

Germany, Poland, and Russia.

This ore is abundant in the United States. We mention a few only of its localities, and would refer to the various geological reports for more complete lists. Extensive beds exist at Salisbury and Kent, Conn., also in the neighboring towns of Beekman, Fishkill, Dover, and Amenia, N. Y., and in a similar situation north at Richmond and Lenox, Mass. At Hinsdale it is the cement in a conglomerate quartz rock. It is very abundant at Bennington, Vt., also at Monkton, Pittsford, Putney, and Ripton, of the same State. Nantucket and Martha's Vineyard are other localities; also near Tinder's Gold Mine, Louisa Co., Va, there is an abundant deposit; at Birmingham and elsewhere, Mo. The argillaceous varieties are abundant in Pennsylvania, near Easton, and through the Lehigh range in Fayette Co., at Armstrong, Upper Dublin, and in Washington Co. In nodules from one inch to a foot in diameter, it is met with at Bladensburg, Md.; also in gravel hills, near Marietta in Ohio. An argillaceous ore is also found on Mount Alto, in the Blue Ridge, in Shenandoah Co., Va., and in Chatham and Nash Co., N. C.: also near the Iron Mountains, Missouri.

Limonite is one of the most important ores of iron. The plg iron, from the purer varieties, obtained by smelting with charcoal, is readily convertible into steel. That yielded by bog ore is what is termed cold short, owing to the phosphorus present, and cannot therefore be employed in the manufacture of wire, or even of sheet iron, but is valuable for casting. The hard and compact nodular varieties

are employed in polishing metallic buttons, &c.

Turgite, Hermann, a reddish-brown mineral from the Turginsk Copper Mines in the Urals, and the Altai afforded Fe 94-15, H 5-85, whence the formula Fe' H

=sesquoxyd of iron 94.7, water 15.3. G.=3.54-3.74. It may be only a red hematite.

Kaliphite, Ivanoff. A mixture of brown iron ore, oxyd of manganese, and sili-

Alternative of zinc with lime, from Hungary.

Alternative of zinc with lime, from Hungary.

Alternative Forms.—By deoxydation through organic matter, if carbonic acid is present, may form spathic iron, (Ca C). By losing water becomes hematite, (Fe). Hematite occurs as pseudomorphs after limonite. This species forms numerous pseudomorphs of other species, (see under Chemical Mineralogy).

Xanthosiderite, E. E. Schmid, (Pogg. lxxxiv, 495).—In fine needles or fibres stellate and concentric. Golden yellowish-brown to brownish-red, silky or greasy in lustre. H.=2.5.

Composition. - Fe H. Analyses by E. E. Schmid, (loc. cit.):


Æl ₩'n 1. Yellow, 74.96 1.32 1.82 2.51 15.67=96.28, 2. Brown, 75.00 1.51 1.33 5.02 14.10=96.96,

leaving a loss due to undetermined carbonate of lime, magnesia, alkalies, antimony, and lead or bismuth, present as impurities.

Occurs associated with manganese ores at Ilmenau.

BRUCITE. Native Hydrate of Magnesia, Bruce's Min. Jour. i, 26. Native Magnesia, Cleav. Talk-Hydrat. Magnesia-hydrat. Magnésie Hydratée, H. Nemalite, Amianthoid Magnesite, Nuttall, Am. Jour. Sci. iv, 19, 1822.

Rhombohedral; $R: R=82^{\circ} 15', O: R=119^{\circ}; a=1.527$. Observed angles $O: R=119^{\circ}-119^{\circ} 55', O: 2R=105^{\circ} 30'$. Cleavage: basal, eminent, folia easily separable. Usually foliated; massive. Also fibrous, fibers separable and elastic.



333

H.=1.5. G.=2.35, Haidinger. Lustre pearly. Color white, inclining to gray, blue, or green. Streak white. Translucent—subtranslucent. Sectile. Thin laminæ flexible.

Composition.—Mg H=Magnesia 68.97, water 31.03. Analyses by Bruce, (Min. Jour. i, 26); Wurtz, (This. Min. 3d edit., 682); Stromeyer, (Untersuch, p. 467); Thomson, (Min. i, 157), J. D. Whitney, (Jour. Bost. Soc. Nat. Hist. 1849, p. 36), Wurtz, (loc. cit.) Rammelsberg, (Pogg. lxxx, 284):

. 1	Ioboken.	Hoboken.	Swinaness.	Hoboken.	Swinaness.	Nemalite.	Nemalite,	Nemal its.
Mg	70	69.11	66.67	68.345	67 . 98	62.89	66-05	64.86
Ĥ	30	30.42	30.39	30.902	30.96	28.36	80.18	29.48
Mg H Mn Fe Ca			1.57	0.637	1.57			
Рe		0.47	1.18	0.116	1.01	4.65	5.63	4.05
Ċa	_		0.19	_	· —	O 4·10		Š i 0 ·27

100, B. 100·00, W. 100·00, S. 100·00, S. 100·51, T. 100·00, Wh. 101·81, W. 98·65, R.

The fibrous variety is called Nemalite.

B.B. loses weight, becomes opaque and friable, but does not fuse. In the matrass gives off water. Entirely soluble in the acids without effervescence; gives the test of magnesia.

Brucite accompanies other magnesian minerals in serpentine. Occurs in considerable veins traversing serpentine, at Swinaness in Unst, one of the Shetland Isles, where it is sometimes found in regular crystals; at Pyschminsk in the Urals, and at Goujot in France. It is also found in the same rock at Hoboken, N. J., opposite the city of New York, in veins which are sometimes an inch in width, rarely in minute polished crystals, as above figure; also in Richmond Co., N. Y., and on the peninsula east of New Rochelle, Westchester Co.

The fibrous variety (nemalite) occurs at Hoboken, and Xettes in the Vosges. This mineral was discovered and described by the late Dr. Bruce of New York. ALTERED FORMS.—Changed through carbonated waters, to hydromagnesite, as at Hoboken.

GIBBSITE, Torrey, N. Y. Med. and Phys. Jour. 1, 68. Hydrargillite, G. Rose, Pogg. xlviii, 564. Felsobanyite.

Hexagonal; in small crystals with replaced lateral edges and eminent basal cleavage. Planes vertically striate. Occasionally in lamello-radiate spheroidal concretions. Usually stalactitic or small mammillary and incrusting, with smooth surface and often a faint fibrous structure within.

H.=3-3.75. G.=2.3-2.4; from Richmond, 2.385, B. Silliman, Jr.; Hydrargillite of the Ural, 2.287, Hermann. Color white, grayish, greenish, or reddish-white. Lustre of O pearly; of surface of stalactites faint. Translucent. A strong argillaceous odor when breathed on. Tough.

Composition.—Alft=Alumina 65.56, water 34.44. Analyses: 1, Torrey, (loc cit.); 2, 3, 4, B. Silliman, Jr., (Am. Jour. Sci. [2], vii, 411); 5, 6, Smith and Brush, (Am. Jour. Sci., [2], xvi, 51, 1853); 7, Hermann, (J. f. pr. Chem. xl, 11); 8, Kobell, (J. f. pr Chem. xli, and l, 491):

		Χl	Ħ	₽
1.	Richmond, Mass.,	64.8	84.7	=99·5, Torrey.
2.	44	63.446	34.477	—— Mg 0.3, insol. 1.777=100, B. S.
8.	"	64.955	34.073	0.590 Mg 0.3, insol082=100, B. S.
4.	"	64.160	34.151	trace Mg 0.3, insol. 1.627=100.288, B. S.
5.	44	64.24	33.76	Si 1 33, P 0 57, Mg 0 10, Fe tr=100, S. & B.
6.	"	63.48	34.68	"1.09, " tr " 0.05, " tr==99.30, S.&B.
7.	Hydrarg., Ural.	64 03	34.54	1.43=100, Herm.
8.	" Villa Rica,	65.6	34.4	—=100, Kobell.

Silliman, Jr., did not find the phosphoric acid attributed to the Gibbeite by Hermann, and ascertained that the silica of Thomson's analyses was due to a mixture with allophane, with which mineral it is often associated. More recent results confirm this fact. The species hydrargillite therefore falls into Gibbsite.

In a matrass, yields water. B.B. infusible; on charcoal decrepitates, becomes the superior of the property of

In a matrass, yields water. B.B. infusible; on charcoal decrepitates, becomes opaque, and crystals exfoliate; phosphoresces. A fine blue with cobalt solution. Dissolves wholly in concentrated sulphuric acid.

The crystallized gibbsite (hydrargillite of authors) was discovered by Lissensko in the Schischimskian mountains near Slatoust in the Ural. The larger crystals were 1 to 2 inches long. This species occurs with corundum at Gumuch-dagh, Asia Minor; also on Corundum of Unionville, Pa.; in Brazil, resembling wavellite. The stalactitic occurs at Richmond, Mass., in a bed of limonite; also at Lenox, Mass.; at the Clove mine, Union Vale, Duchess Co., N. Y., on limonite; in Orange Co., N. Y.

This species was named after Col. George Gibbs, the original owner (after extensive foreign travel) of the large Gibbs' cabinet of Yale College.

Appendix to Hydrous Oxyds.

VÖLKNERITE, Hermann, J. f. pr. Chem. xl, 11, and xlvi, 257.

Hexagonal. Cleavage: basal, eminent; lateral, distinct. Also lamellar massive.

G=2.04. Color white. Lustre pearly, and feel greasy.

Composition.—Mg*Äl+16H.=Alumina 16.29, magnesia 38.05, water 45.66=100. nalysis by Hermann (loc. cit.) Mg 37.07, Äl 16.95, H 46.87=100.

Analysis by Hermann (loc. cit.) Mg 37-07, Al 16-95, H 46-87=100.

In a matrass yields much water. B.B. exfoliates somewhat and gives out light, but infusible. A weak rose-red with cobalt solution. With the fluxes intumesces and affords a clear colorless glass.

Occurs at the mines of Schischimsk, district of Slatoust, implanted on tale schist,

Named in honor of Captain Völkner.

Hydrotalcite of Hochstetter, (J. f. pr. Ch. xxvii, 376) is referred to Völknerite by Hermann, (ib. xlvi, 237,) part of the alumina being replaced by peroxyd of iron, =Mg*(Al, Fe) +16H. It is a foliated pearly mineral, translucent, or in thin folia transparent, with a greasy feel, and hardness=2.0. Hochstetter obtained

#1 12.00, Fe 6.90, Mg 36.30, H 32.06, C 10.54, insoluble 1.20=99.60.

It occurs at Snarum in Norway.

Houghite of Shepard, (Am. J. Sci. [2], xii, 210), resembles Völknerite, and is probably the same compound. The color is white; lustre faint, pearly. H.=2.5. G.=2.0-2.1. It is the material of pseudomorphous

spinel, near Oxbow, and in Rossie near Somerville, St. Lawrence Co., New York. The crystals are in all conditions from the pure spinel to octahedrons with rounded edges and pitted or irregular surfaces, and it also occurs in flattened nodules. The surfaces are sometimes soft and altered, when the edges or angles have the hardness of spinel. Mr. S. W. Johnson, who has redescribed the mineral, obtained in one analysis, (Am. Jour. Sci., [2], xii, 363), Ål 19 743, Mg 36 292, C 8 458, insoluble spinel, &c., 8 264, silica 3 020, water (by diff.) 24 223. The whole loss by ignition in one trial was 40 86 p. c. This would give 33 to 34 p. c. of water. He observes that his results are not satisfac-



tory and that he intended completing them. They are sufficient to show a close relation to the above species. It is associated with dolomite, spinel, phlogopite, graphite and serpentine in crystals, (pseudomorphous.)

PSILOMELANE, Haid. Compact and Fibrous Manganese Ore. Black Hematite. Compact Gray Oxyd of Manganese. Black Iron Ore. Schwarzeisenstein, W. Schwarzbraunstein, Haus. Schwarzmanganerz, L. Hartmanganerz. Manganese Oxydé Hydraté Concretionné, H.

Massive and botryoidal.

H.=5-6. G=3.7-4.328. Lustre submetallic. Streak brownish-black, shining. Color iron-black, passing into dark steel-gray. Opaque.

Composition.—Ř Mn³+Ĥ mixed with Mn, Ramm., a large part of the superoxyd being considered mechanically combined. Analyses: 1, 2, Turner, (Edinb. Trans. xi); 3, Fuchs, (Schw. J. lxii, 255); 4, Rammelsberg, (Handw. ii, 73); 5, Clausbruch, (Ramm. 1st Supp. 121); 6, Scheffler, (Arch. d. Pharm. xxxv, 260); 7, Ebelmen, (Ann. d. Mines, [3,] xix, 155); 8, Rammelsberg, (Pogg. lxviii, 512):

		Mn	М'n	0	Ва	Ř	
1.	Schneeberg,	6	9.80	7.36	16.36	-,	Si 0.26, H 6.22=100, Turner.
2	Romanêche,	7	0.97	7-26	16.69		Si 0.95, H 4.13=100, Turner.
3.	Baireuth,	8	1.8	9.5	-	4.5,	H 4.2=100, Fuchs.
4.	Horhausen,	8	1.36	9.18	-	3.04,	Si 0.53, Cu 0.96, Fe 1.43, Ca 0.38, Na
	ALC: NO I		and an		2.20		nd Mg 0.32, H 3.39=100.61, Ramm.
5.	Ilmenau,	-	77.23	15.82	0.12		Ca 0.91, Cu 0.40, Si 0.52=100.29, CL
6.	"		83.3	9.8	5.8	,	Ca 1.8, Al 2.1, Fe 0.3, Si 1.7, H 4.3=
							99:1, Scheffler.

Йn Вa 0

405, Mg 105, Fe 077, Si 0 60, H167= 7. Gy, IL Saône, 70.60 14.18 6.55

99.47, Ebelmen. 8.08 2.62, Ča 0.60, Mg 0.21, Ču 0.30, Čo 0.54, 8. Heidelberg, 70.17 15.16 Si 0.90, H and loss 1.43=100, Rammelsberg.

In analyses 5 and 6, Rammelsberg considers 50 and 40 per cent. of the superoxyd of manganese a mixture, and a similar allowance is made by him for the others. As the mineral occurs only massive, the nature of the species cannot be satisfactorily ascertained. No. 7 contains potassa as well as baryta. No. 5 is anhydrous

B.B. yields water, gives a violet color to borax, and is completely soluble in muri-

atic acid, excepting a small quantity of silica, affording chlorine.

This is a common ore of manganese. It is frequently in alternating layers with pyrolusite. It occurs in botryoidal and stalactitic shapes, in Devonshire and Cornwall; at Ihlefeld, in the Hartz; also at Johanngeorgenstadt, Schneeberg, Ilmenau, Eglersburg, Siegen, etc.

It forms mainmillary masses, at Chittenden, Irasburgh, and Brandon, Vt.

Named from ψιλος, smooth or naked, μελας, black.

NEWKIRKITE.

Occurs in small needles, under the microscope apparently rectangular prisms. Lustre metallic, splendent. Color a brilliant black. II.=3-8·5. G.=3·824. Opaque. Rather sectile.

Composition.—According to Muir, (Thom. Min. i, 509): An 56:30, Fe 40:35, H 6:70 =103.35.

Forms a coating on red Hematite at Newkirchen, in Alsace.

WAD. EARTHY COBALT. CUPREOUS MANGANESE. Earthy Manganese. Bog Manganese. Manganechaum. Groroilite, Berthier. Schaumartiger Wad-Graphit, M.-Erdkobold. Schwarzer Erdkobalt, Haid. Cobalt Oxide Noir, H. Asholan, Breit. Kakochlor, Breit.-Kupfermanganerz. Lampadite.

The manganese ores here included occur in amorphous and reniform masses, either earthy or compact, and sometimes incrusting or as stains. They are mixtures of different oxyds and cannot be considered chemical compounds or distinct mineral species.

11.=0.5-6. G.=3-4.26; often loosely aggregated and feeling very light to the hands. Color dull black, bluish or brownish black.

Composition.—Rammelsberg considers them related essentially to Psilomelane under the formula R Mn+H (or H2), but mixed with other ingredients.

Wad or Bog Manganese consists mainly of oxyds of manganese and water, with some oxyd of iron, and often silica, alumina, lime or baryta. Groroilite occurs in roundish masses of a brownish-black color and reddish brown streak; it is from Groroi in Mayenne, Vicdessos and Cautern, in France. Hardness sometimes 6 to 6.5.

Cupreous Manganese (Kupfermanganerz) contains, besides hydrous oxyds of manganese, 14 to 25 per cent. of black oxyd of copper, and 4 to 18 per cent. of oxyd of cobalt, with various impurities. G .= 3.1-3.2.

Pelokonite is a variety of cupreous manganese, having a liver-brown streak; H. =3; G.=2.567.

Earthy Cobalt (Asbolan) is a wad in which oxyd of cobalt sometimes amounts to 88 per cent.

Analyses: 1, Klaproth, (Beit. iii, 311); 2, 3, Turner, (Edinb. J. Sci. N. S., ii, 213); 4, 5, Berthier, (Ann. Ch. Phys. li, 19); 6, Wackenroder, (Kastn. Archiv. xiii, 302, xiv, 257); 7, Scheffler, (Arch. d. Pharm. xxxv, 260); 8, Rammelsberg, Pogglxii, 157); 9, Igelström, (Jahresb. xxv, 342); 10, 11, Beck, (Rep. Min. N. Y., p. 55);

12, Berthier; 13, Bahr, (J. f. pr. Ch. liii, 308, fr. Oefv. Ak. Förh. 1850. p. 240); 14, Klaproth, (Beit. ii, 308;) 15, Döbereiner, (Gilb. Ann. lxvii, 333); 16, Rammelsberg, (Pogg. liv, 551); 17, Kersten, (Schw. J. lxvi, 1); 18, Rammelsberg, (Pogg. liv, 545); 19, Böttger, (ib); 20:

I. Wad.

	Min ∰an	0 F e	Ba Ču	Ħ
1. Clausthal,	68.	6:5	1.0	17.5, Si 8.0, C 1.0, Klaproth,
2. Devonshire,			- 1.4	10.66=100 Turner.
3. Derbyshire,			34 5.4	10.29, insol. 2.74=109.36, T.
4. Vicdessos,				12.4, Al 7.0=100.9, Berthier.
5. Groroilite.	62.4 ——			15.8, clay, 3.0=100, Berthier.
6. Baden,	3273			31 33, Pb 12 33, Pb 8 0, Ce 0 33,
,				Si 0.13, quartz 2.60, W.
7. Ilmenau,	66.5	12.1 14	0 8.1	9 8, Si 2 5=100, Scheffler.
8. Rübeland,	67:50	13.48 11	01 0.36	10·30, Ši 0·47, Ča 4·22, K 8·66,
9. Westgothlan	d,—— 82·51	0·		5.58, Si 1.43, Al 6.80, Ca 1.91,
-				Mg 0.69==99.21, Iglst.
Hillsdale, N.	Y 68·50	16	75 —— ——	11.50, insol. 3.25=100, Beck.
				17 00, insol. 2.50=100, Beck.
12. Siegen,	58.5	10.4 5	7	12.9 (with loss,) X 10.7, quartz
-			_	1.8, Berthier.
Skidberg,	66.16	27	0 1 5 ·34 Čo 0·	02 12 07, Si 0 92, A l 0 75, Ca 0 59,
				Mg 0.28, K 0.28=99.11, Bahr.

II. Earthy Cobalt, (Asbolan.)

		Йn	₩n	0	₽e	Вa	Ċо	Ċч	Ħ
14.	14. Oberlausitz,	1	160				19.4	0.2	17·0, \$\overline{8}i24·8,\overline{\X}\overline{120·4}==97·8, K.
									22.90=92.94, Döbereiner.
16.	44	40 05 -		9.47	4.26	0.20	19.45	4.35	21.24, K 0.37=99.94, Ramm.
With oxyd of Manganese.									

III. Cupreous Manganese. Kupferschwärze, or Black Copper, in part.

	Min Man O Fe Ba Co Cu H
17. Schlackenwald,	74·10 0·12 4·80 20·10, Si0·8, gypsum 1·05
18. Camsdorf,	=100 47, Kersten. 49 99 8 91 4 70 1 64 0 49 14 67 14 46, Mg 0 69, K 0 52, Si 2 74 Ca 2 25 = 101 06 R.
19. "	58·22 9·14 1·88 1·70 0·14 ^b 16·85 16·94, K 0·65 Ca 2·85= 108·44. Böt.
20. Lauterberg,	— 30·05 — 29·00 — — 11·50 29·45.

b With oxyd of nickel.

The following formulas have been suggested for several of the above results:—No. 5.—Mn II=Mn 83·17, Ĥ 16·83.

7 and 8.—(Mn, Ca, Ba, K) Mn²+3\Overline{1}, mixed with Mn (Ramm.) suggesting a relation to Psilomelane. For No. 8, R Mn⁴+3\Overline{1}, Berz.

9.—2 (Mn, Al)+H, Svanberg.

No. 13 has H.=6.5; G.=4.254.

15.—(Co, ₩n)+6H f

16.—(Co, Cu) Mn²+4H mixed with Mn—or near Psilomelane, Ramm.

17.—Mn+2H, mixed with Cu, Kersten.—Cu Mn +6 Mn H, Berz.—or Cu Mn H +3 Mn H.

18, 19.—R Mn³+2Ĥ, Ramm.; but mixed with some brown iron ore, oxyd of manganese and other impurities. This is the general formula given by Rammelsberg for the above minerals.

The above ores are results of the decomposition of other ores—partly of oxyds, and partly of manganesian carbonates. They occur at the localities above mentioned, and many other places. Wad or Bog manganese is abundant in the counties of Columbia and Duchess, N. Y., at Austerlitz, Canaan Centre, and elsewhere, where it occurs as a marsh deposit, and according to Mather has proceeded from the alteration of brown spar; also in the southwest part of Martinsburg, Lewis Co., in a swamp. There are large deposits of this bog manganese at Blue Hill Bay, Dover, and other places in Maine.

Earthy Cobalt occurs with cobalt pyrites at Riechelsdorf in Hesse, Saalfeld in Thuringia, at Nertschinsk in Siberia; at Alderly Edge in Cheshire. An earthy cobalt occurs at Mine la Motte, Missouri, which contains 10 or 11 per cent. of oxyd of nickel, besides oxyd of cobalt and copper with iron, lead and sulphur; also near Silver Bluff, South Carolina, affording 24 per cent. of oxyd of cobalt to 76 of oxyd of

manganese.

Cupreous manganese is found at Schlackenwald, and at Camsdorf near Saalfeld; at Lauterberg in the Hartz; *Pelokonite*, a variety of it, H.=3, G.=2.5—2.6, is from Chili, where it occurs with Chrysocolla, (Richter, Pogg. xxi, 591; Kersten, Schw. J. lxvi. 7).

ATACAMITE, Jameson. Salakupferers, W. Remolinite, B. and M.

Trimetric. $I: I=112^{\circ}$ 20', $O:1\overline{\imath}=131^{\circ}$ 29'; $a:b:c=1\cdot131:1:1\cdot492$. Observed planes, $I, 1, 1\overline{\imath}$ $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$: i

H.=3=3.5. G.=4-4.3; 3.7, Breit. Lustre adamantine—vitreous. Color various shades of bright green, rather darker than emerald, sometimes blackish green. Streak apple-green. Translucent—subtranslucent.

Composition.—Cu Cl+3Cu H=Oxyd of copper 55.8, chlorid of copper 31.5, water 12.7=100. Others, as that of Cobija, afford the formula Cu Cl+3CuH=Oxyd of copper 49.6, chlorid of copper 27.9, water 22.5=100. Analyses: 1, Berthier, (Ann. d. Mines, [3], vii, 542); 2, Ulex, (Ann. Ch. u. Pharm. lxix, 361).

Bolivia, Cobija, Cl 14-92
 Chili,
 16-18
 56-28
 11-99
 14-56, Si 1-10=100, Ulex.

B.B. tinges the flame bright green or blue, and gives off fumes of muriatic acid; on charcoal, the copper is reduced to the metallic state. In acids easily soluble.

This species was originally found in the state of sand in the Atacama province, northern part of Chili. It occurs in different parts of Chili, especially at Los Remolinos; also in veins in the district of Tarapaca, Bolivia; at Tocopilla, 16 leagues north of Cobija, is an important locality in Bolivia; with malachite in Bouth Australia; it also invests some of the lavas of Vesuvius and Etna, being formed by the action of the volcano; Schwarzenberg in Saxony, is another locality.

It is sometimes ground up in Chili, and sold under the name of Arsenillo, as sand for letters.

II. OXYDS OF ELEMENTS OF THE ARSENIC GROUP.

I. ARSENIC DIVISION.

1. ARSENOLITE GROUP.—Composition RO. Monometric.

ARSENOLITE,

As O3.

SENARMONTITE,

Sb O3.

2. VALENTINITE GROUP.—Composition RO. Trimetric.

VALENTINITE,

BISMUTH OCHRE,

Bi O3.

 KERMESITE GROUP.—Composition RO³, (S replacing part of O). Monoclinic. 8b (O, 8)3. KERMESITE,

4. CERVANTITE GROUP.—Composition RO4 or RO3+RO4. 8b0°+8b0°. CERVANTITE,

5. VOLGERITE GROUP.—Composition R O*+5H.

Appendiz.—Bleinierite, Pb Sb O +4H; Ammolite.

II. SULPHUR DIVISION.

SULPHUROUS ACID GROUP.—Composition RO.

SULPHUBOUS ACID, SO2.

SULPHURIC ACID GROUP.—Composition RO.

SULPHURIO ACID, 803.

WOLFRAMINE GROUP.—Composition RO. Monometric.

WOLFRAMINE,

WO.

MOLYBDINE,

MO3.

I. OXYDS OF ARSENIC, ANTIMONY, ETC.

ARSENOLITE, Arsenous Acid. Arsenite, Haid. White Arsenic. Arsenikblüthe. Arsenic oxidé, H.

Monometric; f. 11. Usual in minute capillary crystals, stellarly aggregated, or crusts investing other substances. Also botryoidal and stalactitic.

H.=1.5. G.=3.698, Roget and Dumas. Lustre vitreous or silky. Color white, occasionally with a yellowish or reddish tinge. Streak white. Transparent—opaque. Taste astringent, sweetish.

Composition.—As-Oxygen 24.24, arsenic 65.76.

B.B. completely volatilized in white fumes. In the inner flame blackens, and gives off an alliaceous odor. Slightly soluble in hot water.

Found accompanying ores of silver, lead, arsenical iron, cobalt, nickel, etc., at Andreasberg in the Hartz, and formed by the decomposition of other species. October 15 and 15 an curs also at Joschimsthal in Bohemia, at Kapnik in Hungary, and in the old mines of Biber in Hanau.

I fiftee from misconsenite, which is much remained in being soluble.

mandinger : name America, being a general name for mile of arsenous acid, ve mere mangel I il Lumnita.

Native Linema is often arrared by a biochinic cross or powder, which has been remaineral a substrate last the according to Substrate it is a mixture of metallic ice andered in unexe

Answerstame. Brestiants has time named a mineral of the composition of Arsentite, recurring under a transcription, homeomorphism with Valentinite.

SEVERNINGER J.—E is Somerouse Am. (h. Para [3], xxxi, 504.

Minimetric: in simple retailedness 2.11. Cleavage: octabe-

draining to subadamanine. Transparent—transitioent. Colories or gravish. Street with

Companions.—So like Valentanne == Exygen 15-98, antimony 84-32, with some-ness 7, 2, 16 and and 1 to 1 7, 2 of grayant may. Soluble is muristic acid. B.B. Bu Vanesaise

From the restricts of Constantine, Algeria, at Sense, and also from Pernock near Maintain in Françairy. The estabolisms are sometimes more than a continuoter in Frances.

VALENTINIE Sumi White Antimony. Curve of Antimony. Antimony Bloom. Weinsposestratures. U. Err. Spiengingsweine. Antimonolisthe, L. Antimonexpl. Tribeie, Issai. Antonoccie Criste, E.

134

Trimetrie. I: I=138° 58'; O:11=105° 35'; a: 注: == まがめ: 1: 25365. Observed planes, I, 前, 前, 1i, 4i, 2i. 1i:1i adj. =70° 32, \$i:\$i=129° 32', $I: \vec{n}=111^{-3}1'$. Often in rectangular plates with the lateral edges beveled, and in accular rhombic prisms. Cleavage: I, highly perfect, easily obtained. Twins: plane of composition ii, producing an aggregation of thin plates. Also massive; structure lamellar, columnar, and granular.

H=2.5-3. G=5.566, crystals from Braunsdorf. Lustre adamantine. it often pearly; shining. Color snowwhite, occasionally peach-blossom red, and ash-gray to brownish. Streak white. Translucent—subtransparent. Sectile.

Composition.—SbO2=Oxygen 15-68, antimony 84-32. Analysis by Vauquelin. (Hauy's Min. iv, 274):

Silica 8=97. Oxyd of Antimony 86. Thid. and iron 3,

Fusce in the flame of a candle, and before the blowpipe is entirely volatilised. covering the charcoal with a white coating.

This species results from the alteration of gray antimony, native antimony, and other antimonial ores.

The tabular crystallizations of this species occur in small quantities at Przibram in Bohemia, in veins traversing primitive rocks; and the prismatic, at Braunsdorf. near Freiberg in Saxony, Malacaka in Hungary, Allemont in Dauphiny, and elsewhere in Europe.

Antimonophyllite contains oxyd of antimony, and occurs in thin inequiangular six-sided prisms. Locality unknown.

BISMUTH OCHRE. Oxyd of Bismuth. Wismuthochre, W. Bismuth Oxydé, H.

Crystalline form not observed. Occurs massive and dissemina-

ted, pulverulent, earthy; also passing into foliated.
G.=4·3611, Büsson. Lustre adamantine—dull, earthy. Color greenish-yellow, straw-yellow, grayish-white. Fracture conchoidal—earthy.

Composition.—Bi=Oxygen 10.35, bismuth 89.65, along with some iron and other impurities. Analysis by Lampadius, (Handb. z. Chem. Ann. p. 286):

Oxyd of bismuth 86.4, oxyd of iron 5.1, carbonic acid 4.1, water 3.4=99.

Suckow obtained for another derived from the decomposition of aciculite, (Die Verwitt. im Min. 14), Bi 96.5, As 1.5, Fe, H^o 2.0=100. B.B. on charcoal, easily reduced to the metallic state, and subsequently the

greater part may be dissipated.
Occurs pulverulent at Schneeberg in Saxony, at Joachimstahl in Bohemia, and with native gold at Beresof in Siberia. Dr. Jackson reports an oxyd of bismuth not carbonated, as occurring with the tetradymite of Virginia. An earthy steatitic mineral from Agnes in Cornwall, afforded Macgregor, Oxyd of bismuth 28.8, carbonic acid 51.8, peroxyd of iron 2.1, alumina 7.5, silica 6.7, water 8.6.

KERMESITE. Red Antimony. Rothspiesglaserz, W. Rothspiesglanzerz, Haus.
Antimonblende, L. Antimoine Hydro-Sulfuré. Antimoine Oxydé Sulfuré, H.
Pyrantimonite, Br. Pyrostibite, Gl. Kermesome, Chapman. Kermes, B. & M.

Monoclinic. C=77° 51'; O: ii=102° 9', O: 1i (plane on acute edge)=115° 36′, $O: \frac{1}{8}i=149°$ 57′. Cleavage: basal. Usually in tufts of capillary crystals, consisting of elongated, slender six-sided prisms.

H.=1-1.5. G.=4.5-4.6. Lustre adamantine, inclining to metallic. Color cherry-red. Streak brownish-red. Feebly translucent. Sectile. Thin leaves slightly flexible.

Composition.—SbO3+2SbS3=Oxyd of antimony 30.2, sulphuret of antimony, 69.8 =100. Analyses: H. Rose, (Pogg. iii, 453, the sulphur separately determined):

Antimony 74:45, 75:66, sulphur 20:49. oxygen 5.29, 4.27, 20.49.

B.B. fuses readily on charcoal, and at last is entirely volatilized. In nitric acid

it becomes covered with a white coating.

Results from the change of gray antimony. Occurs in veins in quartz, accompanying gray and white antimony, at Malaczka near Posing in Hungary, at Bräunsdorf near Freiberg in Saxony, and at Allemont in Dauphiny.

The tinder ore has been shown to be wholly distinct from red antimony.

CERVANTITE, D. Antimonoxyd. Antimonosaures Antimonoxyd. Antimonocher,

Also massive, as a crust, or a In acicular crystallizations. powder.

G.=4.084. Lustre greasy, bright, or earthy. Color Isabellayellow, sulphur-yellow, or nearly white.

Composition.—SbO³+SbO³=Oxygen 19.9, antimony 80.1. Analysis by Dufrenoy: Sb Ċa Ĉ ₽e

16.85 67:50 11.45 1.50 insol. 2.70=99.80. C. Bechi obtained from needle crystals from Pereta, Tuscany, O 19:47, Sb 78:83, Fe 1:25, gangue 0:75=100:30, giving the same formula, (Amer. Jour. Sci., [2], xiv, 61).

B.B. infusible; but easily reduced on charcoal. Soluble in muriatic acid. Found with gray antimony, and resulting from its alteration at Cervantes, in Galicia, Spain, Chazelles in Auvergne, Felsobanya, Kremnitz and elsewhere in Hun-

STIBLOONISE, Beud. (Antimonochre, Spiessglanzocher, Haus., Stiblite, Blum.,) is considered a mixture of valentinite, cervantite, and hydrous antimonic acid, by G. H. O. Volger, (Entwick. Min. 1854, 72). It occurs massive, and yellowish in color; H.=5.5. G.=5.28. Blum and Delffs obtained in an analysis (J. f. pr. Chem. xl, 318), O 19.54, Sb 75.83, As tr., H 4.63. From Goldkronach in Bavaria.

VOLGERITE. Hydrous Antimonic Acid. Antimonocher, in part.

A white powder or crust ocurring with cervantite, and resulting from its alteration, having the formula, according to Volger, (Entw. Min., 77), Sb O°+5 H= oxygen 18.8, antimony 60.3, water 21.0.

A white antimony f0.3, water 21.0.

A white antimony from the province of Constantine, Algeria, analyzed by E. Cumenge, (Ann. d. M. [4], xx, 80), afforded O 17, Sb 62, H 15, Fe 1, gangue 3=98.

BLEINIERITE, Nicol. (Bleinière, Haus. Antimonate of Lead. Antimonsaures Bleioxyd.) Probably a mechanical mixture of lead and antimony ochres. Occurs amorphous, reniform, spheroidal; also earthy or incrusting; structure often curved lamellar. H.=4. G.=3.933, Karsten; 4.6—4.76, Hermann. Lustre resinous, dull, or earthy. Color gray, brownish, yellowish. Streak grayish or yellowish. Opaque

Composition. — Pb² Sb+4H, according to Hermann=Antimonic acid 31·3, oxyd of lead 62·0, water 6·7. Analyses: 1, Plaff, (Schw. J. xxvii, 1); 2, Hermann, (J. f. pr. Chem. xxxiv, 179):

- 1. Sb 43-96, As 16-42, Pb 33-10, Cu 8-24, Fe 0-24, Si 2-34, S 0-62, Fe Mn 3-32 =103-28, P.
- 2. Sb 31-71, Pb 61.83, H 6.46=100, Hermann.

B.B. on charcoal fuses to a metallic globule, gives out fumes of antimony, and finally yields a bead of lead. From Nertschinsk, Siberia, and supposed to result from the decomposition of other ores of antimony.

AMMIOLITE, D. Antimonite of Quicksilver, Domeyko. Annales des Mines, 4th ser. vi, 183. Quecksilberoxyd Antimonigsaures.

A red powder, consisting, according to Domeyko, of

Sb 12.5, Hg 14.0, Fe 22.3, Si 26.5, H and loss 24.7=100,

being an antimonite of quicksilver mixed with clay and hydrated oxyd of iron.

From the mines of mercury in Chili, accompanying ores of antimony, copper, and mercury. Also at Silberg, near Olpe, Westphalia, where it is produced by the decomposition of a quicksilver gray copper. The name Ammiolite is derived from august, vermilion.

approv, vermilion.

This mineral may be only a mixture, and is therefore placed here with the oxyds, rather than among the salts.

II. OXYDS OF SULPHUR, TUNGSTEN, MOLYBDENUM, ETC.

SULPHUROUS ACID.

Gaseous. G.=2.234, Thenard. Colorless. Taste acid. Odor pungent.

Composition.—S=Sulphur 50.0, oxygen 50.0. Dissolves readily in water, forming an acid solution, which reddens vegetable blues; destroys life and extinguishes combustion.

Sulphurous acid is evolved from most active volcanoes. The sulphur about volcanoes is sometimes produced by the meeting of this gas with sulphuretted hydrogen, causing a mutual decomposition and a deposition of sulphur.

SULPHURIC ACID.

Liquid. G.=1.85. Colorless. Odor pungent. Taste intensely acid.

Composition.—H S—Sulphuric acid 81.6, and water 18.4—100.

This acid, in a dilute state, has been found in the neighborhood of several volcances. It occurs near Sienna, in the cavities of the small volcanic mountain named Zocolino, and in a cavern near Aix, in Savoy. Water strong with sulphuric acid occurs at Alabama, Genessee Co., N. Y.; also at Tuscarora, near Brantford, at Chippewa, Niagara, and at St. David's, Canada West. The first afforded W. J. Craw and H. Erni for 1000 parts of water, (Am. J. Sci. [2], ix, 449:

Free S FeS #18° CaS MgS KS NaS Si NaCl 2·0122 0·4356 0·3702 1·1065 0·4592 0·1061 0·1196 0·0656 ——4·6750, Erni. 2·0070 0·4266 0·3232 1·1161 0·5305 0·0822 0·0945 0·0363 0·0684=4·6848, Craw.

The specific gravity of the water is 1.00482 at 15° C., Erni.

The Tuscarora water afforded T.S. Hunt 4.2 parts of sulphuric acid in 1000, with above 2 of the sulphates of iron, alumina, lime, magnesia, besides traces of alkalies, and some sulphuretted hydrogen, (Logan's Geol. Rep. 1847, 150). Sulphuric acid results from the oxydation of sulphuretted hydrogen.

Paramo de Ruiz in New Granada, and Rio Vinagre, are volcanic localities.

WOLFRAMINE, Lettsom and Greg. Tungstic Ochre, B. Silliman, Am. J. Sci. iv, 52.
Tungsten ochre, Nicol. Wolframochre, Haus. Scheelsaure, Naumann.

Monometric. In cubes, also pulverulent and earthy. Color bright yellow, or yellowish-green.

Composition.—W or pure tungstic acid=Oxygen 20.7, tungsten 79.3.

B.B. on charcoal becomes black in the inner flame, but infusible. A clear glass in the outer flame with borax; with more of the mineral enamel-white on cooling; in the inner flame a yellowish glass, but if a larger proportion be added, it is bloodered on cooling.

Occurs at Lane's mine, Monroe, Ct., filling small cavities in other ores of tungsten, or coating them, and has resulted from their decomposition. Also found at St., Leonard, near Limoges, rarely in distinct cubes of a sulphur-yellow color on wolfram and quartz, a fine specimen of which is contained in the cabinet of M. Adams of Paris; also with wolfram in Cumberland. Also in Cabarras Co., N. C.

MOLYBDINE, Lettsom and Greg. Molybdena Ochre. Molybdanocher, Kersten. An earthy yellow powder or incrustation.

Composition.—Mo=Oxygen 34-29, molybdenum 65-71.

B.B. on charcoal fuses to a slag. With borax forms a colorless glass in the outer flame and a brown glass in the inner. Reduced with sods. Easily soluble in muriatic acid, and the solution is rendered blue by metallic iron.

Occurs with molybdenite, from which it is probably derived, at the foreign localities of this species; also at Westmoreland, N. H., and Chester, Delaware Co.,

Pennsylvania.

Molyblate of Iron !—Deep yellow and sub-fibrous, or in tufted imperfect crystals; and also pulverulent. According to an imperfect analysis by D. D. Owen, (Proc. Ac. N. Sci. Philad., vi, 108), contains Mo 40, Fe 35, Mg 2, Alkali 8, H 15. B.B. fuses casily. From the gold region, California, near Nevada City.

III. OXYGEN COMPOUNDS OF CARBON, BORON, AND SILICON.

CARBONIC ACID,	Õ.
Samolin,	B.
QUARTZ,	Š i.

CARBONIC ACID.

Gaseous. G = 1.5245. Colorless. Taste, slightly acid. Excites a pungent sonsation in the nostrils, and destroys life.

Composition.—C=Carbon 27.27, oxygen 72.78. Extinguishes combustion. Evolved from many mineral waters, and also about some volcanoes. The Saratoga and Ballaton waters owe their briskness to this gas, which is constantly escaping. The mineral waters of Germany are famous localities. Near Naples, on lake Albano, there is a small cave called Grotto del Cane, which is filled with carbonic said to the level of its entrance; the lake is supposed to occupy the erster of a volcano and the hot baths of San Germano are situated on its banks.

SASSOLIN, Rouse. Boracic Acid. Acid boracique, H.

Triclinic. $I: I=118^{\circ} 30', O: I=95^{\circ} 3', O: I=80^{\circ} 33'$ B. and M. Twins, compounded parallel to the base. Cleavage: basal very perfect. Usually in small scales, apparently six-sided tables, and also in stalactitic forms, composed of small scales.

II.=1. G.=148. Lustre pearly. Color white, except when tinged yellow by sulphur; sometimes gray. Feel smooth and Taste acidulous, and slightly saline and bitter.

Composition.—BH =Boracic acid 56:4, water 48:6. The native stalactitic salt, according to Klaproth, (Beit. iii, 97), contains mechanically mixed, sulphate of magnesia and iron, sulphate of lime, silica, carbonate of lime, and alumina. Erdmann has stated, (J. f. pr. Ch. xiii, 7, 8), that sassolin contains 3 18 per cent. by weight of ammonia, and instead of being pure boracic acid, that it is a borate of ammonia.

145 QUARTZ.

Fuses in a candle, and at first tinges the flame green; but this color disappears when the water of crystallization has evaporated. The cooled globule is glassy, and

opaque if any gypsum is present.

Found abundantly in the crater of Vulcano, one of the Lipari isles, forming a layer on the sulphur, and around the fumaroles or exits of the sulphureous exhala-tions. It is obtained for the arts from the volcanic fumaroles of Tuseany. The first locality known was at Sasso, whence the name, Sassolin. The hot vapors at the lagoons or boiling springs of Tuseany, consist largely of boracic acid. The vapors are made to pass through water, which absorbs the boracic acid; the waters are then evaporated by means of the steam from the springs. They yield seven to


eight thousand pounds troy per day.

These lagoons spread over a surface of about 30 miles, and in the distance, clouds of vapor are seen rising in large volumes among the mountains. On approaching the places, the earth seems to pour out boiling water, as if from volcances of various sizes, and the heat in the immediate vicinity is intolerable and the sulphurous smells suffocating. (Am. Jour. Sci. xxxvii, 1836, 270, and [2], ix, xi, 199; Quart.

J. Geol. Soc. vi, 367.)


QUARTZ. Flint. Silex. Chalcedony. Agate. Jasper. Hornstone. Cat's Eye. Amethyst. False Topaz. Rose Quartz. Prase. Chrysoprase. Cantalite. Iron Flint. Heliotrope. Eisenkiesel. Berg-crystal. Kalzedon.

Rhombohedral. $R: R=94^{\circ} 15', O: R=128^{\circ} 13'; a=1.0999.$ the forms following, of the above, excepting i and i 2. Faces Roften brighter than -1; i generally striated horizontally.



 $R: 1-(\text{ov. }i)=103^{\circ}34'.$ R: -1 (adj.)=133° 44'. $\begin{array}{c} i: 13 \stackrel{13}{\downarrow} = 174^{\circ} \ 39' & R: i \ (\text{ov.} \ 22) = 1\\ i: \frac{4}{3} \stackrel{4}{\cancel{3}} \ (\text{ov.} \ 22) = 125^{\circ} 28' & R: 22 = 151^{\circ} \ 6'.\\ i: \frac{9}{8} \stackrel{9}{\cancel{5}} \ (\text{ov.} \ 22) = 118^{\circ} 7' & R: \frac{9}{8} \stackrel{9}{\cancel{5}} = 175^{\circ} \ 1'.\\ i: i = 120^{\circ} & -1: \frac{4}{3} \stackrel{4}{\cancel{3}} = 167^{\circ} \ 40 \end{array}$: 2=158° 31' R: i (ov. 22)=113° 8. : 3=165° 18' : 22=142° 2' $R: \frac{9}{8} \frac{9}{8} = 175^{\circ} \cdot 1^{\circ} i: 33=154° 55' i: 43=161° 31' i: is=171° 33'

Cleavage: R, -1, and i very indistinct; sometimes effected by plunging a heated crystal into cold water. Twins: face of composition, o, (basal plane); plane truncating pyramidal edge, (f. 342); R, (f. 343 A, B, (Rose), opposite views of the same crystal). The two crystals in twins compounded parallel to o, some-



times penetrate one another very irregularly, while the external planes are regular and even. Also f. 345, 346, metagenic twins, (p. 131). Figs. 188, 189, 193 represent distorted crystals. Also stalactitic and mammillary forms. Often massive, either impalpable, or coarse granular. Sometimes coarsely tabular and reticulated.

H.=7. G.=2·5—2·8; 2·6413—2·6541, Beudant; 2·6701, Haüy. Lustre vitreous, sometimes inclining to resinous; splendent—nearly dull. Colorless, when pure; often various shades of yellow, red, brown, green, blue, black. Streak white, of pure varieties; if impure, often the same as the color, but much paler. Transparent—opaque. Fracture perfect conchoidal—subconchoidal. Tough—brittle—friable.

147 QUARTZ.

Composition .- Pure silica in the insoluble state, that is, not taken up by a potash solution. Impure varieties contain variable quantities of oxyd of iron, alumina, oxyd of manganese, nickel, &c. B.B. alone undergoes no change, but with soda,

The varieties arise either from crystallization, mode of formation, or impurities; and are naturally distributed into three series. (1st), presenting the bright glassy lustre of broken quartz crystal; (2d), presenting the glistening subvitreous or waxy lustre, and translucency, or subtransparency of Chalcedony; (3d), with the nearly dull lustre, dull colors, and opacity of Jasper.

I. The vitreous varieties.

Rock crystal includes pure crystals of quartz. This stone, when cut for jewelry, is called "white stone." An asteriated variety contains whitish impurities or

opacity arranged along the diametral planes.

Amethyst is a clear purple or bluish-violet variety of quartz crystal. The color is supposed to be due to a small percentage of oxyd of manganese. But Heintz, in an analysis of a Brazilian specimen, obtained, besides silica, 0.0187 oxyd of iron, 0.6236 lime, 0.0133 magnesia, and 0.0418 soda; and he considers the color owing to

a compound of iron and soda.

Rose quartz has a rose-red or pink color, and is transparent, or nearly so. G. 2-6569 before heating, 2-6578 after heating, E. Wolff. It becomes very pale on exposure to the light. Usually massive, and often much cracked. The lustre is vitreous, sometimes a little greasy. The color is attributed by Fuchs to oxyd of titanium, who detected 1 to 1½ per cent. in specimens from Rabenstein, near Bodenmais. Berthier states that the color is due to organic matter. It probably arises from manganese, the color being similar to that of manganese spar.

False topaz is a light yellow pellucid variety of quartz crystal. It resembles yellow topaz, but is distinguished by its crystalline form, and the absence of cleavage. Smoky quartz, or Cairngorm stone, has a brownish smoky tint. The crystals are

often pellucid; but occasionally the color is so deep as to render them nearly

opaque, except in thin fragments.

Milky quartz, as the name implies, has a milk-white color. It is a massive vitreous variety, and one of the most common. It has sometimes a greasy lustre, and is then called greasy quartz.

Prase is a leek-green variety of massive quartz.

Aventurine quartz is minutely spangled throughout the mass with yellow scales. It is usually translucent, and of a gray, brown, or reddish brown color.

Siderite. An indigo or Berlin-blue variety, from Golling, near Saltzburg.

Ferruginous quartz is of an opaque-red, brownish-red, or ochre-yellow color, which is due to oxyd of iron. It occurs in distinct crystals; the crystals are sometimes minute and aggregated into masses, like the grains of sand in sandstone.

II. Chalcedonic varieties.

Chalcedony has usually the subdued lustre of wax, either translucent or subtransarent; some milk-white varieties opaque. Occurs in mammillary and botryoidal shapes; also as stalactites, in cavities lined or roofed with chalcedony. According to Fuchs, it is true quartz with some opal disseminated through it.

Chrysoprase. An apple, or leek-green variety of chalcedony; it is colored by

Carnelian. A reddish variety of chalcedony, generally of a clear bright tint. Passes into common chalcedony through grayish-red varieties. Heintz by his analysis shows that the color is due to oxyd of iron; he found peroxyd of iron 0.050

per cent., alumina 0.081, magnesia 0.028, potash 0.0043, soda 0.075.

Sard, a deep brownish-red chalcedony, of a blood-red color by transmitted light.

Agate, a variegated chalcedony, the colors in clouds, spots, or bands, the banded consisting of parallel or concentric layers, and either in straight, circular, or zigzag forms. The last are called fortification agates, from a resemblance to the angular outlines of a fortification. In other agates the colors are owing to foreign matter disseminated through the mass. Moss agate or Mocha stone is a chalcedony containing within dendritic or moss-like delineations of an opaque brownish-yellow color, which are due to oxyd of manganese or iron. color, which are due to oxyd of manganese or iron.

from Learning and it has some small a long team hower soil as seen a fine an arming to the seems on the same. When he haves seen a serious of the fine seems of the fine seems of the fine seems.

A SO TARREST TO SECURE TO SECURE AND ASSESSED TO DESCRIPTION OF THE PROPERTY O

Fig. concerns alled a simulation on more owner and of bull colors, usual from energy energy and respectively. The concerns district from more was line or shall a water a simulation. The colors and a sharp entire age substituted from the color was a second to the color of the colors and a sharp entire entire and other more production. The effect of first according to Fisch is party entire entire entire and have a more or entire than the color of persons. There is more persons of the color

moreover, described first our more restrictive finite more minimage the parties.

Power I have reserved therefore approximating what have a gree-

I in my

June A that return in them in the allegans rock sometimes has an inside common beauty in the order of the order manual in the beauty man possible. Then the context are it extress the collect frames in Land June - Equation June 2 and the first them to be a state of the collect frames of the collect frames for the blow and infinite from the passent in terms frames to the object the blow-state of the collect frames are supported in the collect frames and is also supported that the

There were to Belowings. Indications grown, with interspectable libraries spots. The frace of these.

Leaders were I mechanics to december. A value black allocates stone or firsty justice used in account of its luminess and black note for trying the parity of the presence metals. The roter with it me stone after marking the metal across it, inclinates to the experienced eye the amount of alloys.

Employ the above there is a light special variety of sparts called flow some partition of flowers of Hally—which is a light as to 5 as its water. It consists of five in 1 amounts investals appropriate the a special representation of flowers make the continuent of the continuents of the special application a similar variety of space. To have present consists of the places, which arranged parallel or consists in a sample parallel or consists in a sample parallel or consists in a sample arranged parallel or consists in a sample arranged parallel or consists in a sample sample.

Telliment with earthy deposits like that in appearance, controlling in the lower part of the that's formation at Farnham. English and elsewhere, are found by J. T. Way to contain 6. 4, per cents of soluble solubs soluble in solutions of caustic potack or solub in telling in open vessels, and 41 fit of insoluble sillon, with 14-50 alumina etc. Qu. J. Chem. Sol. vi. 1 no. It is therefore related to opal.

Granular quarts is a massive quarts rock of a granular texture. Its colors are various a ware full. Hacolomite is a fissile quarts selected excitating some mica. Budretone is a cellular fility quarts rock. Pleasure Kieselschiefert is a flinty fissile rock, gran, black or greenish. Sende we usually consists of quarts sand. Pleasile sandstone is a fissile variety, this state of which are somewhat flexible; it is a variety of its columite. Siliciaed wood is wood petrified by silica or quarts. It has usually the structure of the original wood. A delicate silvous quarts occurs at Orange river, near the cape of Good Hope.

Haytorite is a name given to pseudomorphous quartz having the form of Datholite.

Quartz, in some of its varieties, occurs in almost every rock-stratum. It is an essential constituent of granite, gneiss, and mica slate, and other allied rocks. The chalcedonic varieties occur principally in the vesicular cavities of basaltic and allied rocks. Flint occurs imbedded in chalk. Hornstone is sometimes imbedded in limestone. Jasper is associated with limestone, like hornstone, and also with basaltic rocks and porphyry.

QUARTZ. 149

Switzerland, Dauphiny, Piedmont, the Carrara quarries, and numerous other foreign localities, afford fine specimens of rock crystal. The most beautiful amethysts are brought from India, Ceylon, and Persia, where they occur in geodes, and as pebbles; inferior specimens occur in Transylvania, in large crystalline groups; in the vicinity of Cork, and on the island of May, in Ireland. The false topaz is met with in Brazil. Rose quartz occurs in a vein of manganese, traversing the granite of Rabenstein, near Zwiesel, in Bavaria. Prase is found in the iron mines of Breitenbrunn, near Schwartzenberg, in Saxony. The amygdaloids of Iceland, and the Faroe Islands, afford magnificent specimens of Chalcedony; also Hüttenberg and Loben in Carinthia, &c. A small blue variety, in cubical crystals, (pseudomorphs of fluor), occurs at Treszytan, in Transylvania. The finest carnelians and agates are found in Arabia, India, Surinam, and Saxony. Perthshire, and other parts of Scotland, afford smaller, but handsome specimens. Chrysoprase occurs at Kosemütz in Silesia. Aventurine quartz at Cape de Gata in Spain. Cat's cye, in Ceylon, the coast of Malabar, and also in the Hartz and Bavaria. Plasma, in India and China, whence it is usually brought in the form of beads. Heliotrope, in Bucharia, Tartary, Siberia, and the island of Rum in the Hebrides. Float stone, in the chalk formation of Menil Montant, near Paris, and in some of the Cornish mines. The banks of the Nile afford the Egyptian jasper; the striped jasper is met with in Siberia, Saxony, and Devonshire. A yellow jasper is found at Vourla, bay of Smyrna, in a low ridge of limestone, to the right of the watering place, between the harbor and these minerals seem to occupy in the limestone the place of hornstone, which is found in various parts of the adjoining country, and also at Napoli di Romania, in Greece. The plains of Argos are strewn with pebbles of red jasper. A variety of sandstone occurs in thin layers at Villa Rica, Brazil, remarkable for its flexibility, owing apparen

Quartz crystals are abundant in Herkimer Co., N. Y., at Middleville, Little Falls, Salisbury, and Newport. They lie loose in cavities in the calciferous sand-rock, or imbedded in loose earth, and sometimes, according to Beck, in powdered anthracite. Fine dodecahedral crystals are obtained at the beds of specular iron in Fowler, Hermon, and Edwards, St. Lawrence Co., New York. In Gouverneur, crystals occur with tourmaline, &c., in limestone, which have rounded angles as if they had been partially fused. On the banks of Laidlaw lake, Rossie, there are large implanted crystals. The Sterling ore bed, Antwerp, Jefferson Co., affords interesting dodecahedral crystals. Four miles east of Warwick, crystals presenting the primary form occur in jasper. At Palatine, Montgomery Co., crystals occur having one end terminated with the usual pyramid, while the other is rounded and smooth. Diamond Rock, near Lansingburg, is an old but poor locality. At Ellenville lead mine, Ulster Co., N. Y., in elegant groups. At Diamond Island and Diamond Point, Lake George, quartz crystals occur, as in Herkimer Co. Crystals with unusual modifications occur sparingly at the Charlestown syenite quarry, Mass., one of which from the cabinet of Mr. J. E. Teschemacher is represented in fig. 344 B. It has the adjacent planes, 22 and 32 uneven, and - with a triangular furrow but sharp edges; the rest are lustrous; with the reflective goniometer, reflecting the sun's rays, R: $\frac{9}{8}$, =175°. Pelham and Chesterfield, Masa, Paris and Perry, Me., Benton, N. Il., Sharon, Vt., and Meadow Mount, Md., are other localities of quartz crystal. Near Quebec, fig. 344°C., and other crystals similar, but the inverse. At Chesterfield, small unpolished rhombohedrons have been found in granite. Paris, Me., affords handsome crystals of brown or smoky quartz. In large crystals often perfect and weighing several pounds at Minnesota mine, Lake Superior, occasionally enveloped in metallic copper, as if cast around the crystals. Drusy quartz, of brown, apple-green, and other tints, occurs at Newfane, Vt. For other localities, see the catalogue of localities in the latter part of this volume.

Rose quarts occurs at Albany, and Paris, Me., Acworth, N. H., Williamsburg, Mass., Southbury, Conn., and Port Henry, Essex Co., N. Y.; smoky quarts at Goshen, Mass., Richmond Co., N. Y., &c.; amethyst in trap at Keweenaw Point, Pic Bay, and Gargontwa, on Lake Superior; also in the same rock at Bristol, Rhode Island, and sparingly throughout the trap region of Massachusetts and Connecticut; in Surry, New Hampshire; in Pennsylvania in East Bradford, Aston, Chester, and Provi-

dence, (one fine crystal over 7 pounds in weight), in Chester Co.; very handsome at the Prince vein, Lake Superior, but now hardly obtainable as the mine is not worked; also very large fine crystals near Greensboro, N. C. Crystallized green quartz occurs in tale, at Providence, Delaware Co., Penn. Chalecdony and agates of moderate beauty are found in the same trap region; more abundantly about Lake Superior, the Mississippi, and the streams to the west; at Natural Bridge, Jefferson Co., N. Y.; about the Willamet, Columbia, and other rivers in Oregon; abundant and beautiful on N. W. shore of Lake Superior. Belmont's lead mine, St. Lawrence Co., N. Y., has afforded good chalcedony and chrysoprase, associated with cale spar. Red jasper is found on Sugar Loaf Mt., Maine, and in pebbles on the banks of the Hudson at Troy. Yellow jasper occurs with chalcedony at Chester, Mass. Heliotrope occupies veins in slate at Bloomingrove, Orange Co., N. Y.

Quartz, chalcedony, prase, carnelian, hornstone, constitute many of the pseudomorphs formed by substitution (see chapter on Chemical Mineralogy). Pseudomorphs, after hexagonal and scalenohedral crystals of calcite and cubes of fluor, occur at Westhampton, Mass.; after heavy spar, probably, in Rutherford Co., N. C. often filled with water. Petrified wood consists of quartz, and sometimes of chalcedony or agate, of

rare beauty.

Quartz crystals occasionally occur of enormous size. A group in the museum of the university at Naples, weighs nearly half a ton. A crystal, belonging to Sig. Rafelli of Milan, measures three and a quarter feet in length, and five and a half in circumference, and its weight is estimated at eight hundred and seventy pounds; another at Paris is three feet in diameter, and weighs eight hundred weight About a century since, a drusy cavity was opened at Zinken, which afforded 1000 cwt. of rock crystals, and at that early period brought \$300,000. One crystal weighed 800 pounds. A group from Moose Mountain, New Hampshire, at Dartmouth College, weighs 147½ pounds, and contains 48 crystals; four of them are from 5 to 54 inches in diameter, ten from 4 to 42 inches. A crystal from Waterbury Vt.

College, weight 1474 pounds, and contains as crystals; four of them are from 5 to 54 inches in diameter, ten from 4 to 44 inches. A crystal from Waterbury, Vt. 2 feet long and 18 inches through, weight 175 pounds.

Crystals often exhibit internal iridescences, owing to fissures or fractures. Foreign Crystals often exhibit internal iridescences, owing to assures or tractures. Foreign substances frequently penetrate or thoroughly permeate crystals of quartz. Oxydof iron has already been alluded to as one of these permeating substances. Chlorite is sometimes so thoroughly intermingled, that the crystals appear to be composed entirely of this material; their hardness, however, shows their siliceous nature. Anthracite, asbestus, actinolite, tourmaline, silver and copper are other penetrating substances. Specimens containing acicular crystals of rutile are often very beautiful. The most interesting of the substances occurring in quartz are the fluids, which occupy small cavities in the interior of crystals; they are either water, peculiar resinous liquids, or mineral solutions. Mr. Allan describes a crystal of amethys the fluids dilates and fills all the cavities partly filled with a bituminous fluid; at 85° F., the fluids dilates and fills all the cavities, and on cooling reappears with ebullition.

Silica is held in solution in the Geysers of Iceland and New Zealand, whose solvent powers are due to their temperature, and a small quantity of alkali present.

It is also present in traces in ordinary waters, as alkaline silicates.

Several varieties of this species have long been employed in jewelry. The assethyst has always been esteemed for its beauty. Like most other stones, it is less brilliant by candle light; it appears to best advantage when surrounded with pearls and set in gold. The color of the amethyst is often irregularly diffused, as is well described by Pliny, "ad viciniam crystalli descendet albicante purpure defectu," purple, gradually fading into white. It was called amethyst, apidverse, on account of the color of the same of the color of the color of the same of the color count of its pretended preservative powers againt intoxication, from a, not, and poten to intoxicate. This is not, however, the only amethyst of the ancients. The violet colored sapphire, the violet fluor spar, (scalpturis faciles, Plin. easily graven), and some other purple species, were designated by the same name; and it has been supposed that garnet was also included.

Cameos are in general made of onyx, which is well fitted for this kind of ministure analyture. The figure is carved out of one layer, and stands in relief on another of different color. The most noted of the ancient cameos, is the Mantan vass at Brunswick. It was cut from a single stone, and has the form of a cream put, about seven inches high and two and a half broad; on its outside, which is of a brown color, there are white and yellow groups of raised figures, representing

151 QUARTZ.

Ceres and Triptolemus in seach of Proserpine. The Museo Borbonico, at Naples, contains an onyx measuring eleven inches by nine, representing the apotheosis of Augustus, and another exhibiting the apotheosis of Ptolemy on one side, and the head of Medusa on the other; both are splendid specimens of the art, and the former is supposed to be the largest in existence.

The carnelian (sarda of Pliny) receives a fine polish, and is often rich in color; but is too common to be much esteemed. When first obtained from the rock, carnelians are usually gray or grayish-red; they receive their fine colors from an exposure of several weeks to the sun's rays, and a subsequent heating in earthen pots. The colors of agate, when indistinct, may be brought out by boiling in oil, and afterwards in sulphuric acid; the latter carbonizes the oil absorbed by the apparently porous layers, and thus increases the contrast of the different colors. Agate is often made into mortars for chemical and pharmaceutical preparations, and according to Pliny, it was employed for the same purpose by the physicians of and according to Pliny, it was employed for the same purpose by the physicians of his day. The royal collection at Dresden contains a table service of German agate; and at Vienna, in the imperial cabinet, there is an oval dish twenty-two inches in length, formed from a single stone. The agate, or achates of the Greeks, was so called from the river Achates, in Sicily, whence, according to Theophrastus, these stones were originally brought. Iaspachates corresponded to our jasper agate; Sardachates contained layers of the sard, or carnelian; Dendrachates (from ἐινέρον, a tree and achates) was moss agate; Hæmachates (from ὑιμα, blood, and achates) was an agate, sprinkled with spots of red jasper, (Moore's An. Min.)

Jasper admits of a brilliant polish, and is often formed into vases, boxes, knife-

handles, &c. It is also extensively used in the manufacture of Florentine mosaics. The inspis of the ancients, whence our word jasper is derived, appears to have included the green or blue colored variety, together with some other stones, not of the

jasper kind.

Quartz is distinguished by its Hardness,—Scratching glass with facility; Infusibility,—Not fusing before the blowpipe; Insolubility,—Not attacked by water or the acids; Uncleavability,—One variety is tabular, but proper cleavage is never distinctly observed. To these characteristics the action of soda may be added.

OPAL. Hyalite. Müller's Glass. Hydrophane. Menilite. Cacholong. Siliceous Sinter. Pearl Sinter. Fiorite. Girasol. Eisenopal, Haus. Manganopal. Schwimmkiesel. Quartz hyalin concretionée. Quartz rèsinite, H. Opalus, Pæderos, Pliny. οπαλλιος. Michaelite. Alumocalcite. Geyserite.

Massive, amorphous; sometimes small reniform, stalactitic, or

large tuberose.

H.=5.5-6.5. G.=1.9-2.3. Lustre vitreous, frequently subvitreous, and often inclining to resinous, and sometimes to pearly. Color white, yellow, red, brown, green, gray, generally pale; dark colors arise from foreign admixtures. Streak white. Sometimes a rich play of colors, or different colors by refracted and reflected

There are many varieties of this species. The precious opal exhibits a play of rich colors. Fire opal or girasol presents bright hyacinth-red and yellow reflections. Common opal and semi-opal are common varieties not opalescent. Hydrophane is not transparent, but becomes so when immersed in water. Cacholong is phane is not transparent, but becomes so when immersed in water. Cacholong is nearly opaque, and of a porcelain or bluish white color; it adheres to the tongue, and contains a small portion of alumina, with 3.5 p. c. of water. It is closely allied to hydrophane, and often associated with it. Hyalite, or Muller's glass, occurs in small reniform, botryoidal, and occasionally stalactitic shapes, either colorless and pellucid, or white. Menilite is brown and opaque, occurring in compact reniform masses, occasionally slaty. Opal jasper contains several per cent, of iron, and is the analogue in this species of jasper in the preceding. Silicious Sinter is a loose silicious aggregate, deposited by the Geysers of Iceland, where it presents porous stalactitic, fibrous, "cauliflower-like," and occasionally campact concretions, called reversite by Damour. Pearl sinter, or fiorite, occurs in the cavities of volcanic geyserite by Damour. Pearl sinter, or fiorite, occurs in the cavities of volcanie

tufa, in smooth and shining globular and botryoidal masses. Which have a pearly lustre. Wood opal has a peculiar ligneous structure. Michaelite (from the island of St. Michaels, Azores) is a white fibrous pearly variety. Sp. gr.=188. Alumocalcite is an impure opal, of a bluish milk-white color, containing 6 per cent. of line. Some if not all the deposits of silicious earth formed of infusorial remains, consist of soluble silica, and the name Randanite has been applied to a variety, composed mainly of silica of this kind. (See analyses below).

Composition.—Silica in the soluble or gelatinizing state, but often combined with insoluble Silica; more or less hydrous, but the water is not considered essential.

Analyses: 1, Klaproth, (Beit. iv); 2—6, Damour. (Bull. Geol. de France, 1848,

hanjae: 1, Kaproth; 8, Forehhammer, (Pogg. xxxv, 331); 9, Stucke, (Rose, Beschreib, p. 73); 10, Damour, (loe. cit.); 11, Pattison. (Phil. Mag., [3], xxv, 495); 12, Damour, (loe. cit.); 13, G. J. Brush, (communicated); 14, Damour, (loe. cit.); 15, Klaproth, (Beit. iv, 156); 16, Mallet, (Phil. Mag. [4], v, 2°5); 17, Damour, (loe. cit.); 18, Schaffgotsch, (Pogg. Ixviii, 147); 19, Forehhammer, (loe. cit.); 20, Wrightson, (Ann. Ch. Pharm. liv. 358):

```
775 Pe 0-25=100, Klaproth.
     Fire opal, Mexico,
                                         92:00
     Limpid,
                           G.=2.029, 91·12
 2
                                                       8-88=1(0), Damour.
     Chaloyant, "
                                 2024, 8990
 3.
                                                      10:10, and some combust., Damour.
     Geyserite, white,
                                                       877=100, Damour.
                                         91-23
 5. " gray opaque, 2081, 92.59
6. Bilex resinite, Iceland, 2095, 9203
                                                       7.41=100,
                                                       7-97=100,
                                                      11:00 Pe 0:5, Al 1:5, Ca 0:5, Klaproth.
7:97, K, Na 0:34, Ca 0:49, Mg 1:48 Al
 7. Menilite, Menil Montant,
                                         85.50
 8. Fire opal, Faroe,
                                         8873
                                                                                           0-99, Foreh.
                                                      10 00, Pe 3 00, Ca 0 25, Al 3 50=99 50 S. 10 40, Al, Pe 0 71, Ca 0 40, Na 0 82, K sr.,
9. Semi-opal, Hanau,
10. Iceland, Geyser,
                                         8275
                                         87-67
                                                                                       =100, Damour.
11. Sil. incrust, N. Z. G.=1968, 77-35
                                                       7.66, ±1 970, Pe 372, Ca 174=100-17,
12. Prec. opal, Hun., G=21099, 93-90
                                                       6·10=100, Damour.
                                                                                              [Pattison.
13. Fire opal, Georgia, G.=2 07, 91 89
                                                       5.84, <del>X</del>l 1.40, Mg 0.92=100.06, Brush.
14. Silex resinite, Mex., G .= 1.21, 95.40
                                                       4-60=100, Damour.
15. Yellow opal, (Pechopal) Telk. 93.50
                                                       5 00, Fe 1 0, Klaproth. [=99 86, Mallet.
16. Bil. incrust, N. Zeal.,
                                                       8-06, Al 1-58, Fe 0-17, Ca tr., Cl Na 0-85
                                                      8 106, ±1 1 100, ±2

8 106, Damour.

3 0, Fe 0 8, Ca 0 2=99 5, Sch.

8 47, K 0 07, Na 0 06, Ca 0 06, ±1 0 2,

Mg 0 4=99 58, F.

2 73, Fe 4 11, Mg 0 86, K 0 8, ±1 1 86,

Na 0 9, S 0 31, W.
17. Hyalite, Waltsch, Bohemia, 96-94
18. Bohemia, 95-5
19. Cacholong, Faroe,
                                          95.32
20. Semi-opal, Schiffenberg,
                                          90-20
                  Kaschau.
                                         92.16
```

The precious opal of Hungary afforded Kobell 10.94 p. c. of water. A resin opal from Vourla, Smyrna, afforded Mr. G. J. Brush, 5-10 p. c. of water. G.=2.054. (This. Min. 3d edit. p. 691). Another from near Harmanjick, Asia Minor, contains, secording to J. L. Smith, 3 per cent. of magnesia, besides 92 Si and 4-15 H. A hyalite, called water opal, from Pfaffenreith, afforded Schmitz 35 per cent. of water. For other analyses, see Schnabel and v. der Mark, Verh. nat. Ver. Rheinl. 1852, 377, 459, 561; Bickell, Ann. Chem. Pharm. lxx, 290.

The Randanite of Salvetat, (silice gelatineuse), corresponds to the formula Si'll when dried at 16° C. and Si'll when dried at 100° C. Fournet and Salvetat obtained, (Ann. Ch. Phys., [8], xxiv, 348):

- 1. Ceyssat, Sol. Si 87-20, H, C, and org. matters 10-00, Al and Fe 2-00, and
- Algiers, Sol. Si 80, H 9, insol. Si 6:48, 41 1:41, Fe 0:55, Ca 0:56, Na, K, and loss 2:00, 8.

It occurs as a fine earth or in compact earthy masses, and consists mainly of the easts of infusoria.

The Michaelite afforded Kobell, Bi 83.65, II 16.35.

B.B. opal is infusible, but gives out water and becomes opaque. Some varieties containing iron turn red.

Opal occurs in short irregular veins in porphyry: also in the vesicular eavities of amygdaloid. Common opal sometimes occurs in limestone. Menilite is met with in clay slate. Some varieties are found with galena and blende, in metalliferous veins. It also occupies the interior of fossils in sandstone.

The precious opal occurs in porphyry at Czerwenitza, near Kashau in Hungary, at Frankfort, and at Gracias a Dios in Honduras, S. A. Fire opal is brought from Zimapan in Mexico, and from 'the Faroe Islands. The common opal is abundant in Hungary, in Faroe, Iceland, the Giants' Causeway, and the Hebrides; found also within a half mile, and to the southwest, of the watering place at Vourla, the harbor of Smyrna, along with yellow jasper and hornstone, imbedded in a low ridge of compact limestone, of a light yellow or grayish-white color; colors wax-yellow or grayish-green, occasionally white. Hungary affords also the hydrophane. The Giants' Causeway affords small masses resembling mountain cork, which though opaque, become translucent on immersion in water. Cacholong occurs in loose opaque, become translucent on immersion in water. Cacholong occurs in loose masses on the river Cach, in Bucharia, whence its name. Hyalite occurs in amygdaloid at Schemnitz, in Hungary, and in clinkstone at Waltsch, in Bohemia. Menilite is found imbedded in adhesive slate, at Menil Montant, near Paris. Wood opal forms large trees in the pumice conglomerates of Saiba, near Neusohl, and Kremnitz in Hungary, in Farce, near Hobart Town, Tasmania, and other trap countries.

The Randanite is abundant near Algiers, and was taken for Kaolin; also at Ceyssat near Randan in the Pay de Dome.

The Randanite is abundant near Algiers, and was taken for Kaolin; also at Ceyssat, near Randan in the Puy de Dome.

Hyalite occurs in the United States, sparingly at the Phillips ore bed, Putnam Co., N. Y. in thin coatings on granite; and rarely with the auriferous quartz of Cabarras Co., N. C.; also in Burke and Scriven Cos., Georgia. In Georgia it lines eavities in a siliceous shell-rock. The Suanna spring in Florida, affords small quantities of siliceous sinter. Good fire-opal is obtained in Washington Co., Ga.

The precious opal, when large, and exhibiting its peculiar play of colors in perfection, is a gem of high value. It is cut with a convex surface. The largest mass of which we have any knowledge, is in the imperial cabinet of Vienna; it is nearly as large as a man's fist, and weighs 17 ounces, but contains numerous fissures, and is not entirely free from the matrix. This stone was used as a gem by the Greeks and Romans, and was called opalus; also pæderos, παιδερως, in allusion to its color and lustre, as expressed in the Orphic poem, μερτοῦ τίριτα χρόα παιδες, "having the delicate complexion of a lovely youth," (Moore's An. Min.)

II. OXYGEN DOUBLE BINARY COMPOUNDS, OR SALTS.

product at the last of the las

1. Acid of the form RO'.

I. Silicates. Combinations of oxygen bases with Silica. APPENDIX. Unarranged Silicates containing Titanic acid or Columbic acid.

II. COLUMBATES, NIOBATES, TUNGSTATES, MOLYBDATES, CHROMATES, VANADATES.

III. SULPHATES, SELENATES.

IV. BORATES.

Acid of the form R² O⁵ (=R O ⁵/₂.)

V. Phosphates, Arsenates, Antimonates.

3. And of the form RO.

VI THANATES.

VII. CARBINATES.

4. Add of the form R O (ROL)

VIII. (Prairies.

L SILICATES.

I. Anhydrous.

[The different species of Silicates are widely varied in their characters through the mutual replacements of lime, potash, soda, magnesia, protoxyd of iron, and other protoxyds, represented by the general expression (B:) and also of the perceyds, alumina, perceyd of iron, etc. (B). The mere presence of one or another of these bases affords therefore no ground for distinctions in classification. The only general fact of a constant character is the almost total absence of magnesia from the feldspars, (and also the zeolites), and, in fact, from all those species in which the protoxyds and peroxyds are to one another in the ratio of 1:1, (1B:1B) that is, which have 1:3 for the oxygen ratio.

I divide the anhydrous silicates, as has been explained, into a few grand groups, dependent on the oxygen ratio for the oxygen of the bases and silica: these ratios being, 1:3, 1:2, $1:1\frac{1}{4}$, 1:1, $1:\frac{3}{4}$ or less than $\frac{3}{4}$.)

The feldspars, aithough seemingly unconformable to this system, still have been shown to have the type-ratio 1:1, this occurring in Anorthite; the additional silica in the other species, being added without changing the crystallization or typical structure.

A general principle is here indicated which modifies the law of ratios, and which is exemplified also in the micas, scapolite, hornblende, and some other species.

It has been observed that while some species contain water, without its affecting the crystalline form, so there are silicates, not hydrous, in which there is an addition of accessory substances which do not modify the form, and which substances thus appear to be in a certain sense unessential. Thus Sodalite, Hauyne and Nosean, have each the ratio 1:3:4, and a common formula, with the addition of some Na Cl for Sodalite, Ca S for Hauyne, and Na S for Nosean. By considering these as ingredients essential to the type, the species would be widely separated from their congeners.

The above facts contain the principles upon which the anhydrous silicates are arranged. They are more fully developed in the chapter on Chemical Mineralogy and Classification.

Besides the ordinary chemical formulas, which have the advantage of a familiar form and look, we add the condensed formulas, explained in our chapter on Chemical Mineralogy. There is little reason to doubt that the protoxyds and peroxyds replace one another, 3 parts of R replacing 1H; or generally that proportions of oxyds equal in amount of included oxygen are mutual substitutes in compounds. Thus R², H and R are equivalents. In this view, the complex silicates are simply silicates of a single complex base. Thus the general garnet formula is (R², H) Si; under which the following are among the special formulas,

Garnet,
$$(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$$
, $(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$, $(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$, $(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$,

which differ from one another only in the ratio of B° to H, it being 1:1 in Garnet, 1:2 in Epidote, 1:1 or 3:2 in Idocrase—the fractions within the brackets equaling together a unit and indicating this ratio. Such formulas give the constitution of the species with all the precision of the old formulas, exhibiting the exact relations of the constituents, without any hypothesis as to their atomic groupings.]

The following are the subdivisions of the Anhydrous Silicates.

- I. EDELFORSITE SECTION.—Oxygen ratio of bases and silica, 1:3.
- II. Augree Section.—Oxygen ratio, 1:2.
- III. EULYTINE SECTION.—Oxygen ratio, 1:11.
- IV. Garnet Section.—Oxygen ratio, 1:1.
- V. MICA SECTION.—Oxygen ratio in type, 1:1; Structure micaceous.
- VI. Feldspar Section.—Oxygen ratio in type, 1:1; Oxygen ratio of protoxyds and peroxyds, 1:3.
- VII. Andalusite Section.—Oxygen ratio 1 to less than 1.

I. EDELFORSITE SECTION.

EDELFORSITE. Neutral Silicate of Lime. Ædelforsite, Kobell.

Fibrous or feathery, and massive.

H.=6. (i) G.=2.58. Lustre shining. Color white or grayish.

Composition.—CaSi=Silica 62.2, lime 37.8. B.B. fuses to a white translucent glass. Gelatinizes.

Edelforsite is found at Aedelfors in Smaoland, Cziklowa in the Bannat, and at Gjelleback in Norway.

MANCINITE.

Plumose and shining, with two unequal cleavages inclined to one another, 92°. Color brown.

Composition.—Zn Si, probably, according to Jacquot, (Ann. d. Mines, [8], xix, 70\$). From Mancino near Leghorn. The species is a doubtful one.

II. AUGITE SECTION.

The oxygen ratio for the bases and silica in the Augite Section, is 1:2; varying in the species hornblende and acmite, to 1:2.

1. AUGITE GROUP. Crystallization monoclinic.

WOLLASTONITE, Ca Si , Hornslende, R Si = 2 Si 4

Pyroxene, B Si , Acmite, (2+1) Si = (2 + 1) Si (2 + 1) Si (3 + 1) Si (4 + 1) Si (4 + 1) Si (4 + 1) Si (5 + 1) Si (7

2. BABINGTONITE GROUP.—Triclinic.

BABINGTONITE.

8. BERYL GROUP.—Hexagonal.

Beryl, (|Be+|Al) Si2 Eudialte, (|B2+|Zr) Si2.

WOLLASTONITE, H. Tabular Spar. Table Spar. Grammite. Schaalstein, W. Tafelspath, M.


Monoclinic. $C=69^{\circ}$ 48', $I: I=87^{\circ}$ 28', $O: 2i=137^{\circ}$ 48'; a:b: c:=0.4338:1:0.89789. Observed planes as in the annexed figure.

```
O: 1i=160^{\circ} \ 30'. O: 3i=114^{\circ} \ 16. ii: 2=132^{\circ} \ 14. O: 3i=139^{\circ} \ 53'. O: ii=110^{\circ} \ 12'. ii: 2i=120^{\circ} \ 50'. O: 5i=130^{\circ} \ 42'. ii: -1i=95^{\circ} \ 23'. ii: i\frac{3}{2}=145^{\circ} \ 8'. ii: i=133^{\circ} \ 44'. ii: i=150^{\circ} \ 34'.
```

Rarely in distinct tabular crystals. Cleavage: O most distinct; ii less so; 1i and -1i in traces. Twins: composition-face ii. Usually cleavable mussive, with the surface appearing long fibrous, fibres parallel or reticulated, rather strongly coherent.

II.=4.5—5. G.=2.78—2.9; 2.785—2.895, (United States), Thomson; 2.805, (Bannat), Haidinger. Lustre vitreous, inclining

to pearly upon the faces of perfect cleavage. Color white, inclining to gray, yellow, red, or brown. Streak white. Subtransparent-translucent. Fracture uneven, sometimes very tough.



Composition.—Ca²Si²—Silica 51.9, lime 48.1. Analyses: 1, Stromeyer, (Untersuch., 1, 356); 2, H. Rose, (Gilb. Ann. lxxii, 70); 3, Kobell, (J. f. pr. Ch. xxx, 469); 4, Weidling, (K. V. Ac. Förh., 1844, 92); 5, Bonsdorff, (Schw. xxxiii, 368); 6, Vanuxem, (J. Ac. Nat. Sci. Philad. ii, 182); 7, Beck, (Min. N. Y. 271); 8, J. D. Whitney, (Bost. J. Nat. Hist. v, 486); 10, J. B. Bunce, (This Min. 3d Edit., 696):

		Si	Ča	Mg	Рe	Ĥ
1.		51.445	47412	_	0.401	0.076, \mathref{\mathref{M}}\n0.257=99.591, Str.
2.	Perhoniemi,	51.60	46.41	-		-gangue 1:11=99:12, Rose.
3.	C. di Bove,	51.50	45.45	0.55	_	2.00=99.50, Kobell.
4.	Göckum,	50-724	43.802	0.879	0.849	-Mn 0.834, CaO 2.732, W.
5.	Skräbböle,	52.58	44.45	0.68 1	e 0.13	0-99=99.83, Bonsdorff.
6.	Willsborough,	51.67	47.00	-	" 1.35	=100 02, Vanuxem.
7.	Diana,	51.90	47.55	-	" 0.25	—=99.70, Beck.
8.	Cliff Mine,	49.09	46.38	0.14	_	2.96, Mn 0.48, 31 0.23, Whit.
9.	"	49.6	44.87	-	-	2.96, Mn 0.93, Al 1.28, Whit.
10.	Grenville, U C	. 53.05	45.74	-	1.20=	=99.99, Bunce.
100	12					

In the matrass no change. B.B. on charcoal, fuses on the edges to a colorless bead : affords with borax a transparent glass and leaves a siliceous skeleton with salt of phosphorus; with some soda, a blebby glass, with more, swells up and infusible. With muriatic acid, gelatinizes. Phosphoresces when heated.

Wollastonite is found in regions of granite and granular limestone; also in basalt

It occurs in the copper mines of Cziklowa in the Bannat of Temeswar, and also at Dognaszka and Nagyag. It accompanies garnet, fluor, and native silver, in lime-stone, at Pargas in Finland, and Kongsberg in Norway; also at Perhoniemi, Skräb-böle, Finland. At Castle Rock, Edinburgh, it is met with in basalt, associated with prehnite, presenting a fibrous radiated structure. A greenish-white variety occurs in lava at Capo di Bove, near Rome.

In the United States, this species occurs at Willsborough, N. Y., forming the sides of a large vein of garnet, traversing gneiss; abundant at Lewis, ten miles south of Keeseville, with colophonite; half a mile north of Lewis corners, with garnet and quartz; at Roger's Rock, near the line between Essex and Warren Cos. with garnet and feldspar; Diana, Lewis Co., about a mile from the Natural Bridge, in abundance, of a snow-white color; at Boonville, Oneida Co., in boulders, with garnet and pyroxene: also at Grenville, Canada, with sphene and green coccolite; at St. Jerome and Morin, C. E., with apatite, in large tabular masses of a fibrous structure, in Bucks Co., Penn., three miles west of Attleboro', associated with scapolite, pyroxene and sphene; of a red color at the Cliff Mine, Kewenaw Point, Lake Superior, and on Isle Royale, a very tough variety, but now exhausted. Named after the English Chemist, Wollaston; also tabular spar from its lamellar forms and structure.

Dr. Thomson has described under the name of *Wollastonite*, a mineral from Kilsyth, occurring in greenstone veins. It differs from tabular spar in containing some silicate of soda. Formula, Na Si+Ca*Si*, or near acmite. It is referred by J. D. Whitney, to Pectolite.

PYROXENE, Hany. Augite. Coccolite. Diopside. Sahlite. Alalite. Mussite. Pyrgom. Fassaite. Pentaclasite. Jeffersonite, Keating. Asbestus, in part. Bronzite. Paulite. Green Diallage. Kokkolit, Baikilit, Omphazit, W. Pentaklasit, Haus. Malacolithe, Haüy. Funkite. Hudsonite, Beck. Polylite, Thom. Egerine, in part. Breislakite, Brocchi.

Monoclinic; $C=73^{\circ}$ 59', $I: I=87^{\circ}$ 5', $O: 2i=131^{\circ}$ 17'; a:b:c=0.5412:1:0.91346.


- $0:1i=155^{\circ}51'.$
- $O: -1i = 148^{\circ} 35'$.
- $O: -3i = 109^{\circ} 31'$.
- $0: ii = 106^{\circ} 1'.$
- $0:1=146^{\circ}9'.$
- $0:2=130^{\circ}6'.$
- $O: -1 = 137^{\circ} 49'$.
- $O: -2 = 114^{\circ} 28'$.
- $0:1i=150^{\circ}20'.$
- $0: ii = 90^{\circ}$
- $2i: 2i(ov.O) = 82^{\circ}34'.$
- $ii: 1i=130^{\circ} 10'.$
- $ii: -1i=105^{\circ} 24'.$
- $ii:i2=152^{\circ}15'$.
- $ii: I=133^{\circ} 33'.$
- $ii: i2 = 115^{\circ} 25'$.
- $ii:i8=107^{\circ}35'$.
- $i2:i2(ov.ii)=124^{\circ}30'.$
- $i\hat{2}: i\hat{2}(\text{ov}.ii) = 50^{\circ} 50'.$
- $ii: 3\hat{s} = 143^{\circ} 34'$.
- $-1:-1=120^{\circ} 32'$.
- $-2:-2=95^{\circ}30'$.
- $1:1=131^{\circ}24'$.
- $2:2=111^{\circ}10'$.

			(0			
11			1				1i
			2				21
						25	
					88		
				1.			41
ii	i3	<i>i</i> 2	I	12	ià		iù
			Uni				41
			-3				
-3i				$-\frac{8}{3}$ 2			
			-2				24
-1 <i>i</i>		\equiv	-1				11
- <u>1</u> i							

Observed Planes.

Cleavage: I rather perfect, often interrupted; ii and ii imperfect. Crystals usually thick and stout. Twins: face of composition ii, (f. 357). Often coarse lamellar, in large masses, parallel to O or ii. Also granular—particles coarse or fine; and fibrous, fibres often fine and long.

H.=5—6. G.=3.23—3.5. Lustre vitreous, inclining to resinous; some pearly. Color green of various shades, verging on one side to white or grayish-white, and on the other to brown and black. Streak white—gray. Transparent—opaque. Fracture conchoidal—uneven. Brittle.



Composition.—R25i2, in which R may be lime, magnesia, protoxyd of iron or manganese, or even soda; and in some instances alumina enters into the composition without changing essentially the crystallization, and usually replaces silica. When R=(Ca, Mg), the color is white or light green; when R=(Ca, Fe), the color varies in shade of green to black, according to the proportion of oxyd of iron; if R=Mn, the color is flesh-red, and the mineral is manganese spar. It may also be (Ca, Mn), or (Ca, Mg, Fe), or (Fe, Mn), and when iron is abundant the mineral is very dark

or (Ca, Mg, Fe), or (re, MH), and whole are in green or black.

There are other kinds arising from mode of crystallization, the species being sometimes in distinct crystals, sometimes thin foliated, sometimes granular, and often fibrous or asbestiform. The following are the prominent varieties:—

1 Diopside, White Augite, White Malacolite, Mussite.—Of white, grayish, or grayish-green color, either crystallized, lamellar or granular. The granular, when coarse and somewhat friable, is called white coccolite. Alalite is a diopside from the in Diadmont. Mussite has a grayish-green color, and is lamellar parallel to the Ala in Piedmont. Mussite has a grayish-green color, and is lamellar parallel to the base, the lamellæ sometimes contorted; it is from Mussa in Piedmont. These varieties contain the bases magnesia and lime, with little or no iron, and usually no alumina, (Ca, Mg) Si. G. = 3·23 - 3·26. Diopside is from δις, two-fold, and eψις, appearance; malacolite, from μαλακος and λιθος.

Sahlite resembles diopside, but has a dingy greenish color, and is coarse foliated, arising from composition parallel to 0; from Sahla, Sweden. Baikalite is a green variety, from Lake Baikal. Pyrgom is a dingy variety of sahlite, (named from the Greek *vopywa) Omphazite is a foliated leek-green variety. The same constitution

as above, but usually with some iron. G.=3.23-3.3.

Pyroxene, (from rup, fire, and feros, stranger).—Besides its general use, this name is specially applied to the green or grayish-green crystals, often of large size Green Mal-acolite is another name for this variety. Fassaits is handsome grass-green or pistachio

green, with high lustre; from the Fassa valley, Piedmont. Green Coccolite is a granular friable variety, consisting of bright green shining granules, named from serses, a grain. Funkite is a green coccolite. Lherzolite has a deep green, or olivegreen color, and occurs both crystallized and lamellar; from Lake Lherz in the Pyrenees. Baikalite (from Lake Baikal) is an olive-green sahlite. These species contain the bases lime, magnesia, and protoxyd of iron, (Ca Mg, Fe) Si. G. =3.25 **—3·3**.

Jeffersonite is a dark-green crystallized foliated variety, from Mine Hill, Franklin, New Jersey; it has the same constitution and angles as the last, with some oxyd of zinc. (Ca, Fe, Mg, Zn)² Si² G.=3.6. Named after Mr. Jefferson.

Augite (from avyn, lustre) includes the black and greenish-black crystals, common in basaltic and volcanic rocks. It contains the same bases as the last, together with alumina. (Ca, Fe, Mg) (Si, H). G.=3.33—3.36; 8.359, Etna; 3.356, Eiffel; 8.358, Fassa. Alumina is also contained at times in some of the above varieties. Egirine of Brevig is a black or greenish-black to leek-green pyroxene; G.=3.432 -8 504, (Pogg. lxxx, 815).

Breislakite occurs in wool-like forms at Vesuvius and Capo di Bove. Its crystallographic identity with pyroxene has been shown by Chapman, (Phil. Mag. xxxvii,

444, 1850). Named after Breislak, an Italian geologist.

Hedenbergite is a black pyroxene, containing largely of iron, little or no magnesia, and no alumina. (Ca, Fe) Si. G. =3.5. Named after the Swedish Chemist, L. Hedenberg.

Hudsonite, from Orange Co., N. Y., near the Hudson river, is black and cleavable like Hedenbergite, but differs in having a considerable part of the silica replaced by alumina, (Ca, Fe,)²(Si, Xl)². G.=3.5, Beck; 3.43—3.46, Brewer; streak green; often has a brown tarnish. It also contains at times some manganese. Polylite is the same compound.

A pure iron-augite analyzed by Grüner, (Anal. 47), has been called Grünerite.

Diallage, (from διαλλαγη, difference, alluding to the dissimilar cleavage).—Thin foliated and easily cleavable; laminæ brittle; color various shades of green, gray, and brown, and sometimes bronze or pearly-metallic. G.=3'11—3'227. It includes Schiller spar (in part) and Bronzite. Bronzite has a greenish-brown or brownish color, and metalloidal lustre; it cleaves in three directions, two of which meet at

an angle of 87°. G .= 3.125. From Gulsen in Styria.

Hypersthene, (from vere and oferes, very strong or tough), bears nearly the same relation to diallage that the dark varieties of pyroxene bear to the light. It contains a large proportion of iron and little lime, yet varies much in this respect, and some varieties, not distinguished by external characters, have the composition flearly of diallage. Its colors are grayish or greenish-black, and copper-red, with a bright metallic-pearly lustre. It cleaves easily, but not into as thin folia as the preceding. G.=33-36. The Paulite (G.=3:389) is from the island of St. Paul. Labrador Hornblende and Metalloidal Diallage are here included. The Bronzite has clove-brown and pinchbeck brown colors, with a metallic-pearly lustre. G .= 3-2-8.5. Cleavage orthodiagonal, very perfect. Diaclasite of Hausmann (analysis 43) is between diallage and hypersthene in composition, but has the pale colors of diallage, passing into brass-yellow. Named from διακλαω, to cleave through.

Analyses: I.—1, Nordenskiöld, (Schweig J. xxxi, 457); 2, H. Rose, (Schw. xxxv. 86); 3, T. Wachtmeister, (Schw. xxx, 334); 4, Hermann, (J. f. pr. Ch. xxxvii, 190); 5. Wackenroder, (Kastn. Archiv. xiii, 84); 6, Kussin, (Ramm. 4th Suppl. 12); 7,

a, waczenroger, (Rastn. Archiv. XIII, 84); 6. Russin, (Ramm. 4th Suppl. 12); 7.
 Reutersköld, (Jahresb. xxv, 362); 8, Richter, (Pogg. lxxxiv, 384).
 II. 9, Seybert, (Am. J. Sci. iv, 340); 10-13, H. Rose, (loc. cit.); 14, Wolff, (J. f. pr. Ch. xxviv, 236); 15, Hochstetter, (J. f. pr. Ch. xxvii, 375).
 III. 16-20, Kudernatsch, (Pogg. xxxvii, 577); 21, Gmelin, (Leonh. u. Bronn, N. Jahrb. 1840, 549); 22, Delesse, (Ann. d. Mines, [4], xii, 293); 23, Rammelaberg, (Pogg. lxxxiii, 458); 24-26, Waltershausen, (Vulk. Gest. 107 to 110).
 IV. 27 T. S. Hunt. (Logan's Geol. Rep. 1852)

(Pogg. 1xxxiii, 458); 22-26, watersnausen, (Vulk. Gest. 107 to 110).

IV. 27, T. S. Hunt, (Logan's Geol. Rep. 1853).

V. 28, 29, Smith and Brush, (Am. J. Sci., [2], xvi, 369); 80, Thomson, (Min. i, 495):

VI. 31, 32, Köhler, (Pogg. xiii, 101); 33, Delesse, (Ann. d. M. [4], xvi); 34-36,

Regnault, (Ann. des M. [3], xiii, 147); 37, Kobell, (J. f. pr. Ch. xxxvi, 303); 38,

Schaf häutl, (Ann. d. Ch. u. Ph. li, 254); 39, Beck, (Min. N. Y., p. 310); 40, Seybert;

41, Muir, (Thom. Min. i, 202); 42, Damour, (Ann. des Mines, [4], v. 157; 43, Köhler, (loc. cit.); 44, T. S. Hunt, (communicated).

VII. 45, Meitzendorf, (Pogg. lii, 626); 46, Gruner, (Compt. Rend. xxiv, 794); 47. Beck, (This Min. 3d Edit. 692); 48-50, Scheerer and Richter, (Pogg. lxxxiv, 381):

I. White or pale green, containing little or no iron.—Analyses 2 to 7 correspond nearly to the formula (\$\frac{1}{2}Ca+\frac{1}{2}Mg)^2\Si^2=Silica 55.7, magnesia 18.5, lime 25.8. G. of 4, 3.28; of 6, 3.37; of 7, 3.27.

```
Йg
                                     Ĉа
                                             Fе
                                                   Йn
1. Pargas, bh-gn. 55:40
2. Wermland, ywh. 55:32
                                                              -₩n 0·48==99·48, Nord.
                            22.57
                                    15.70
                                           2.50
                                                   2.83
                                                              -Fe 2·16, Mn 1·59, R.
                            16.99
                                    28:01
                                                          0.43 " 0.20=97.87, Wacht.
3. Norway, wh.
                     57:40
                            1074
                                    23.10
   Achmato'sk, wh.
                     53-97
                             17.86
                                    25.60
                                            2.00
                                                   0.57
                                                              -=100, Herm.
                                                          0.20, Mn 0.18=100 Wack.
  Fassa.
                     54.15
                             18.22
                                    24.74
                                           2.51
6. Brazil,
                             17.82
                                    25.11
                                                                 =99 74, Kussin.
                     55.61
                                           1-20
                                                   1.87
                                                           0.25=100.29, Reut.
7. Langbanshyttan, 53:56
                            16.27
                                    23.86
                                            4.48
                                                          1.10,H1.19=100.16,Richt.
8. Reichenstein,
                     54.50
                            18.96
                                    21.41
                                           3.00
```

II. Dark green to black, containing lime and iron, with more or less magnesis and no alumina. Analyses, 10 and 11=(\frac{1}{2}Ca+\frac{1}{2}Mg+\frac{1}{2}Fe)^2\sin^2=\silica 537, magnesis 13.4, lime 24.9, protoxyd of iron 8.0. Analyses 13 and 14=(\frac{1}{2}Ca+\frac{1}{2}Fe)^2\sin^2=\silica 48.6, lime 22.5, protoxyd of iron 28.9. G. of 15=3.174.

```
50:38
                          6.83 19.33
9. L. Champl. gn.
10. Dalecarlia,
                   54.08
                         11:49
                                23.47
                                                   0.14 " 0.78=99.02
                   54.55
                         15.25
                                20.21
                                       8.14
11.
12. Wermland, bk.
                   53:36
                                22.19
                                      17:38
                                             0109
                                                      =98 v1, Rose.
                          4.99
13. Tunaberg, Hed.
                                                       =98.94, Rose.
                                      26.08
                   4901
                          2.98 20.87
                                                      =97 74, Wolff.
14. Arendal, bk.
                   4778
                                22.95
                                      27.01
                          2.40
                                21.10
                                      22:00
                                                   2.99, ign 0.30=99.19,
15. Azores.
                   50.40
                                                               Hochstetter.
```

. With some Mn.

III. Black or brownish-black, containing alumina, with magnesia, lime and iron; mostly from basalt and porphyry. G. of 21, 2705; of 24, 2886; of 25, 8204.

```
50.11
16. Rhone,
                             1572
                                     18.66
                                              7.55
                                                             6.68=98.72, Kudern atsch
17. Vesuvius,
                      50.90
                              14.48
                                     22-96
                                              6-25
                                                             5.37=99.91,
18. Etna,
                      50.55
                             13.01
                                     22-29
                                              7-96
                                                             4.85=98.66,
                                                                                 44
                                                             4-02=99-26,
                                                                                44
                      50.15
                                             12-04
19. - Fassa
                             13.48
                                     19.57
                                                             6 00=99 25
20. Eifel,
                      49.39
                             13.93
                                     22.46
                                              7.89
                                             12·06 ₩ 872
7·19 ₩ trace
21. Wetterau,
22. Vosges,
                                                            15.82, Na 3.14, K 0.34, G.
                      56.80
                              5.05
                                      4.85
                      49.16
                             15.95
                                     18.87
                                                             5-08, H 2-26=98-51, Del.
23. Härtlingen,
                      47.52
                             1276
                                     18.25
                                             13-02 M 0-40
                                                              8·18=100·08, Ramm.
24. Etna, black,
                      47.63
                                     20.87
                                             11.39
                                                     0.21
                                                             674 H 0-28=100-02, Walt.
                             12.90
         gnh. bk.
                      5170
                                                             4.38 " 0.49=99.94,
                             21.11
                                     18-02
                                              4.24
26. Iceland.
                                              5.92
                                                             6.05=100, Walt.
                      49.87
                             16.16
                                     22100
```

a This augite forms with the feldspathic mineral Vosgite, the porphyry of Termusy.

IV. White aluminous, like diopside in appearance.

27. Perth, C. W. 50.90 18.14 23.74 \$\overline{F}\$ 0.85 --- 6.15, ign 0.90=100.18, H.

V. Black, containing alumina, with iron and lime without magnesia. Hudsonite corresponds to the formula $\mathbb{R}^2(\overline{\mathbb{S}}i, \frac{X}{2}i)^2$.

```
978, K, 248, Na 1-66,
28. Hudsonite
                    39.80
                            2.98 10.39 80.40
                                                  0.67
                                                          ign 1 95=98 61, 8. & B.
                                                        11 v5, K, Na 4·16, ign.
29.
                     38.58
                                  10.83
                                        80.57
                                                            1 95=100 17, B. & B.
30. Polylite,
                     40-04
                                    9.42 34.08
                                                  6.60
                                                       21.54. II 0.4=103.08. Th.
```

VI. Thin foliated. Nos. 31 to 33, Diallage; 34 to 37, Bronzite; 39, Vanadiferous Bronzite; 39, 40, a kind of Hypersthene; 41, 42, Hypersthene; 44, ib., from Chatess Richer, Canada; 43, Diaclasite of Hausmann.

```
Йg
                      Bi
                                     Ċa
                                            Р́е
                                                   Йn
                                                           Χı
31. Hartz,
                     58.71
                            17.55
                                   17.06
                                                808
                                                          2.82, H 1.04=100-27, K
82. Florence
                     58.20
                            14.91
                                    19.09
                                            8.67
                                                   0.88
                                                          2.47, H 1.77=100.49, K.
38. Odern, diallage,
                     49.30
                            17.61
                                    15.43
                                            9.48
                                                          5 50, Er 0 30, ign. 0 85=
                                                   0.21
                                                                      98 93, Delesse.
                     50.05
                            17:24
                                    15.63
                                           11.98
                                                          2.58, H 2.13=99.61, Reg.
34. Piedmont.
                                                          3.27, "1.59=99.68,
35. Ural.
                            16:48
                                            5.35
                     52.80
                                    20.44
                                                          1-09, " 1-80==99-98,
36. Ultenthal.
                            30.37
                                           10.78
                     KK-N4
                                                          1.33=100.13, Kobell.
                                                   1.00
37. Greenland,
                     58.00
                            29.66
                                           10.14
38. Genoa, G. 3.25.
                                                          5 55, V 3 65, Na 375, H
                     49.50
                                    18.12
                                            8.28
                            14.12
                                                                             177.8
39. Lake George,
                     45.45
                             18.00
                                    24.38
                                                                  99.27, Beck.
                                           11.49
                                                           4 00, H 1 0=99 23, Seyb.
40. Wilmington,
                     52.17
                             11.83
                                    20.00
                                           1078
                                                                 " 0.5=98.70, Muir.
41. Skyo, Hypers.
                     51.35
                             11.09
                                     1.84
                                           33.92
                                                           0.87=98.72, Damour.
                                                    1.32
42. Labrador, "
                     51.36
                            21.31
                                     8.09
                                           21.27
                                                           1.84 H 3.76=100.40,Köh.
48. Banto, Diacl.
                     53.74
                             25.09
                                     4.78
                                                    0.23
                                           11.51
44. Canada, Hyp.
                     51.85
                            22.59
                                     1.68
                                           20.56
                                                           3·70, ign. 0·10=99·93, H.
```

VII. Asbestiform varieties. Analysis 45 has the composition of a diopside; 46 is an iron augite, with the formula Fe Si²—Silica 57·1, protoxyd of iron 54·3; G.= 3·713. No. 50 is from Zillerthal; oxygen ratio 13·94: 29·70 (water excluded.)

```
45. Zillerthal,
                      55.87
                             20:33
                                     1776
                                              4.81
                                                      1.12
                                                                 =99.39, Meitzendorf
46. Collobrières,
                      48.9
                                                             1.9=99.6, Gruner.
                              1.1
                                       0.2
                                             52.2
                                                          - Ĥ 2·25=100, Beck.
47. Htaten Id.,
                      55.20
                              80.73
                                             11.82
                                                           " 2.36=100.25, Scheerer.
48. Tyrol,
                      57:50
                             28109
                                     13:42
                                              3.88
                                              5·22 <del>X</del>10·56 " 2·15, Cu 0·40=99·83, Rr.
49. Roichonstein.
                      55.85
                             23.99
                                     11.66
                             22.85
                                     13.89
                                                         - " 2·48=100·24, Scheerer.
50. Rock Cork.
                      57.20
                                              4.87
```

Jeffersonite afforded Hermann, (J. f. pr. Chem. xlvii, 13, 1849):

31. Bi 40 01 Ca 15 48 Ma 7 00 Za 4 89 Fe 10 53 X 1 1 93, Mg 8 18, ign. 1 20.

Other analyses: by Lory, (Bull. Soc. Geol. Fr. [2], vii, 540); Delesse, (Ann. d.M. [4], xviii, 800, xx, 145); A. Erdmann, (K. V. Ac. H. 1848, and Ramm., 5th Sappl., 58); Deville (Etudes, 1848); Breidenstein, (Ramm. 5th Suppl., 60); Frölich, (ib. 62.

B.B. the whitish or pale varieties fuse with some effervescence to a colorless glass; with borax afford a clear glass. Varieties containing iron afford an iron reaction, which is more intense the greater the proportion. The Hedenbergite and dark augites fuse readily to a shining black glass. Diallage yields some water in a matram, and becomes of a paler color; on charcoal it fuses with difficulty on the edges to a gray slag; with borax it forms a glass colored with iron. Bronsite becomes of a paler color, but alone is infusible. Hypersthene generally fuses on charcoal rather easily to a grayish-green glass, not clear. Hudsonite fuses with effervescence to a black magnetic bead; with soda, a manganese reaction.

Pyroxene is principally confined to crystalline or volcanic rocks, and is associated at different localities with granite, granular limestone, serpentine, greenstone, basalt or lavas. Diallage occurs generally in serpentine or greenstone; and hypersthene with foldspar and quarts forms hypersthene rock, which occurs extensively in some districts of crystalline rocks.

Pyroxone, with labradorite or oliglocase, forms Greenstone or Diabase; and when the texture is very compact, it constitutes Melaphyre, which is reddish-brown to black. With labradorite and magnetite, forms Dolerite or Basalt, often crystalline granular, and called basalt more especially when the texture is impalpable. Pyroxone is common in lavas, and is a constituent of Tufas.

Foreign localities are numerous and we mention but few.

Augite occurs at Aussig and Teplits, in Bohemia, in large crystals imbedded in basalt; and in small highly polished crystals in the lavas of Vesuvius, with nepheline, idocrase, and mica. Diopside is met with in crystals at Ala, in Piedmont, as-

 sociated with garnets and tale in veins traversing serpentine. Its more transparent crystals from this locality are sometimes cut and worn as gems. Sahlite is met with in granite rocks at Sahla, and elsewhere. Baikalite occurs principally on the borders of Lake Baikal. Omphazite accompanies granular garnet at the Sau Alp, in Carinthia, and near Hof, in Bayreuth, with the smaragdite variety of hornblende,

which it much resembles.

White subtransparent crystals are met with at Bytown, Lower Canada, in limestone, often measuring an inch by one and a half inches; grayish-green in lime-stone with phlogopite at Grand Calumet, Id.; crystals sometimes 1 ft. long and 4 in. wide, and having attached small crystals of greenish hornblende, at the high falls of the Madawaska, Canada. White flattened prismatic crystals, two or three inches long by one or two in breadth, occur in dolomite at Canaan, Conn.; large green crystals in the limestone of Trumbull; small transparent crystals with granular pyroxene, in Reading, Conn., on the turnpike near the line of Danbury. The Bolton quarries, Mass., afford good crystals. The dolomite of New York Co., N. Y., affords white crystals, often several inches long, and also the abandoned quarries at Kingsbridge, about 208th street. In Orange Co. there are interesting localities, affording, besides fine crystals, many of the massive varieties, from white to black colors, the former in limestone, the latter usually with magnetic iron; at Two-Ponds, in Monroe, in simple or grouped crystals, often large, associated with scapolite, zircon, and sphene in white limestone: another, half a mile east of Greenwood furnace, along with mica in limestone, where one crystal was obtained six inches long and ten in circumference; two and a half miles north of Edenville, gray crystals. Near Amity and Fort Montgomery, are other good localities. Dark green or black crystals in limestone a mile northwest of Edenville. In Putnam Co., near Patterson, grayish-white crystals are abundant, strewed over the surface and in limestone. In Westchester Co., white at the Sing Sing quarries. Other good localities in New York, are at Rogers' Rock, Lake George, massive, and granular, (coccelite), of gray, green, and brown colors; on the banks of Vrooman lake, near Oxbow; in Diana, Lewis Co., in black crystals; at Fine, St. Lawrence Co., where the crystals are very large. Franklin, N. J., also affords good pyroxene. Massive varieties occur at most of the above mentioned localities. Crystals of black augite in trap at Montreal, Boucherville and Rougement Mountains, C. E. A beautiful green coccolite, and also crystals (f. 356) occur near Long Pond, Essex Co. N. Y., and a black coccolite in Monroe, Orange Co., a mile west of Coffee's Hotel; at Willsboro', N. Y., green coccolite is associated with sphene and tabular spar. A lamellar variety of a dark-green and bronze color is abundant in the Forest of Dean, Orange Co., N. Y., along with black coccolite; and fine sahlite with coccolite about three miles southeast of Greenwood furnace. Diopside occurs on Hustis's farm, Phillipstown, N. Y., and in the Bolton limestone quarry. Raymond and Rumford, Maine, afford massive varieties, diopside, sahlite, &c. At Berkshire, Mass., a white variety is abundant. A broad lamellar sahlite of a white color at Watertown, Conn., at the lime quarry near the Naugatuck, and a less interesting grayish-green variety at the verd antique quarries of Milford and New Haven. Both crystals and granular pyroxene near Attleboro', Penn. Diopside in Burnett's quarry, Pennsbury. Diallage in serpentine in Westfield and Blanford, Mass., at Deer Isle, Maine, Cooptown, Harford Co., Md. A massive fassaite with red sapphire and sphene, at Burgess, Canada West.

Hungestheme is stated to occupin Fesce Co. in much of the granite of that region

Hypersthene is stated to occur in Essex Co., in much of the granite of that region, often associated with labradorite; also near Wilmington, Delaware. But the mineral from these localities, although presenting the external characters of this varieral from these localities, although presenting the external characters of this variety, differ much from one another in composition, (analyses 39, 40), and still more from the Labrador hypersthene, (analysis No. 42). It is also found with andesite rock at Chateau Richer and at St. Adèle, Mille Isles, Canada, (analysis 44), grayish-black and brown, with laminæ curved. The *Hudsonite* of Beck (analyses 28 and 29) occurs in a vein of quartz in Cornwall, Orange Co., N. Y. The *Polylite* of Thomson may possibly come from the same locality; Thomson attributes it to Hoboken, which Beck states must be an error.

Pyroxene was thus named by Haüy from τυρ, fire, and ξενος, stranger, in allusion to its occurrence in lavas, where Haüy supposed it did not belong, or was a stranger.

Crystals of this species have been obtained by fusion, and are not unfrequent, of a black color, among the iron slags of Sweden. Mitscherlich and Beudant have formed white crystals by heating together silica, lime, and magnesia.

ALTERED FORMS.—Pyroxene undergoes alteration in different ways, as has been well explained by Bischof. When containing much protoxyd of iron, as in many varieties, the iron, if moisture is present, undergoes oxydation, becoming brown or brownish-red and hydrated, or of a red color and anhydrous; or is carbonated and becomes gradually removed and the result uncolored, if carbonic acid is present. In an early stage of alteration, crystals often develop a basal cleavage. The carbonic acid of infiltrating waters when lime is present, carries off the lime, leaving the most of the regression as in the heavy and result in the present of the regression as in the heavy and results are the result in the most of the regression as in the heavy and results are the results in the results are the results and the results are the results and the results are the results are the results and the results are the results and the results are the resul the most of the magnesia, as in the change to Rensselaerite; or by continuing its action, carries off the magnesia and gives origin, if the pyroxene is aluminous to a hydrous silicate of alumina, like Cimolite; an addition of alumina may probably take place through the accompanying decomposition of associated feldspar. Acted on by sulphuric or sulphurous acid about volcanoes, the protoxyd bases are rapidly removed, and a hydrous aluminous silicate is left, and often a siliceous deposit of sinter. Acted on by alkaline carbonates in solution, a similar result is produced. but alkalies take the place of the removed bases, and an alkaline silicate of alumins or of iron and alumina is formed, as Green earth; or under different circumstance there is a change to mica. Acted on by waters containing traces of bicarbonate of magnesia in solution, magnesia is exchanged for the lime, and thus pyrallolite, hyperthene and hornblende, may be formed from Augite; and the removal of the lime tirely, and its replacement by magnesia, gives origin to serpentine, steatite, tale, seponite. Silicates of iron and magnesia may also proceed from the action of alkalias silicates or carbonates.

Tufas consist largely of altered augite, and are formed from augitic sands under the action of steam or heated waters, thus becoming a hydrous silicate of alumina, etc.; such, according to Bunsen, is the *Palagonite* of Waltershausen

The following are analyses and descriptions of some of the more prominent to

sults of alteration.

sults of alteration.

1, 2, Waltershausen, (Vulk. Gest. 305); 3, Beudant; 4, Beck, (Min. N. York, 297);
5, Nordenskiöld, (Schw. J. xxxi, 386); 6, Köhler, (Pogg. xi, 192); 7, Rammelsberg, (3d Suppl. 106, and Pogg. xlix, 387); 8, Klaproth, (Beit., ii, 180, v, 22); 9, Sraberg, (K. V. Ac. H. 1840, and Pogg. Ivii, 165); 10, 11, Smith & Brush, (Am. J. Sc., [2], xvi, 368); 12, Svanberg, (Pogg. liv, 267); 13, 14, Rammelsberg, (Pogg. xlix, 387); 15, Delesse, (Bib. Univ. Genève, June, 1848, 106); 16, 17, Waltershausen, (loc. cit., 301); 18, Rammelsberg, (loc. cit.); 19, Klaproth, (Beit., i, 291); 20, Ilimoff, (Ann. J. M. Russ., 1841, 336); 21, Rammelsberg, (loc. cit.);

1. CALCAREO-MAGNESIAN.-1. Hydrosilicite. 2. Ibid.

Mg Ča Na K Si 2·11 1·86 13·21=100, Waltershausen. 4.60 33.32 1. 44.90 170 3.14 14.48=100, Waltershausen. 2. 43.81 8.66 2870

II. MAGNESIAN.—3. Sahla, Pseudomorph. 4. Rensselaerite. 5. Pyrallolite 6. Schiller Spar. 7. Ibid. 8. Saponite, Cornwall. 9. Ibid. 10. Thalite, Lake Superior. 11. Ibid. 12. Piotine.

	Si	#1	Fe	Ťе	Mg	Ča	Ña	Ř	Ĥ
3.	60-65		-	4.18	25.20	4.97	Mn 0.78	-	4.38=100.16, Beud.
4.	59.75	-	340	-	32.90				2.85=99.90, Beck.
	56.62			-	28.38	5.58			3.58Bit and loss 6-38, Nor.
				10.91	26.16	2.75			12.43 Er 2.37=100, Köhler.
	41.48			16.61	27.24	-			10.13=101.95, Ramm.
8.	45-00	9.25	1.00	-	2475				18.00=98.75, Klap.
	46.8		0.4		33.3	0.7			11.00=100.2, Svanb.
	45.60			-	24.10	1.07	-	15	20.66=08.84, S. and B.
	48.89			-	24.17	-		31	15.66=39.22, S. and B.
79	80-80	9-40	9:08	-	96.59	0.78		-	10:5-100:15 Swanh

III. ALKALINE.—13. Green Earth, Fassa. 14. Ibid. 15. Green Earth, Mt. Balde. 16. Green Earth, Iceland. 17. Ibid.

```
Bi
            X1
                   ₽e
                                       Ċа
                          Рe
                                              Ňα
                                                            ĸ
                                                                  Ħ
                                Мg
13. 45.87
           11.18
                         24.68
                                0.28
                                       1.50
                                                    6.72
                                                                 9.82=100, Ramm.
                                       Ca C 15-24, alkali and H 8-67=100, Ramm.
14. 39.48
           10.31
                   8.94
                         15.66
                                170
15. 51-25
            7.25
                         20.72
                                6.16
                                              1.92
                                                          6.21
                                                                 6.49=100, Del.
16. 52-04
            4.93
                         25.54
                                       1:38
                                                           6.03
                                                                 5.19=99.37, Walt.
                                4.26
17. 60-09
            5.28
                         1572
                                               2.51
                                4.95
                                       0.09
                                                          5.04
                                                                 4:44=98:12, Walt.
```

IV. ALUMINOUS.—18. Bilin, Pseudomorph. 19. Cimolite, Argentiera. 20. Cimolite, Alexandrowski.

δi ₩l Йg Čа Ħ 18. 60.63 23.08 4.21 0.91 1.28 9.12==99.23, Rammelsberg. 19. 63.00 23.00 12 00=99 25, Klaproth. **20.** 63.52 12:00=99:07, Ilimoff. 23.55

V. SILICEOUS.—21. Vesuvius, Pseudomorph.

Si Æı Fe Йg Ċя

21. 85.31 1.28 1.67 1.70 2.66 5.47=98.42, Rammelsberg.

Hydrosilicite, Waltershausen, (Analyses 1, 2).—Occurs amorphous or as a crust, at Palagonia and Aci Castello, in Sicily, associated or mixed with Herschelite, Phillippsite and Calcite. Formula R³ Si²+3H, or a hydrous augite.

Rensselaerite, Emmons, (Analysis 4).—Compact steatitic, with an unctuous feel, fine compact texture, either gray, whitish, greenish, brownish, or at times black. H.=3-4, G.=2.87. Translucent. Has often the cleavage of pyroxene. On account of its softness, translucency and fine texture, it is worked in a lathe into inkstands and other forms. Occurs over large areas in Northern New York, in the towns of Fowler, Dekalb, Edwards, Russel, Gouverneur, Canton and Hermon, St. Lawrence Co.

Pyrallolite, Nordenskiöld, (Analysis 5).—Cleavable or granular massive, and like pyroxene. H.=3.5—4. G.=2.555—2.594. White, sometimes greenish; subtranslucent to opaque. Formula Mg³ Si³ with water. B.B. at first blackens and then becomes white. From Storgord in Finland, in limestone, with pyroxene and

scapolite. Closely related to the Rensselaerite.

Schiller Spar, (Analyses 6, 7).—Cleavable, massive, like some pyroxene. H.=3.5

—4. G.=2.5—2.76. Lustre metallic pearly, to subvitreous. Dark green, inclining to pinchbeck brown. Subtranslucent. B.B. fuses on thinnest edges. From Baste in the Hartz with serpentine. It is considered an altered augite by G. Rose. name is from the German for a play of colors or lustre. Called also Bastite.

Saponite, Scifenstein, (Analyses 8-11).—Occurs like Green Earth in amygdaloidal cavities. It is soft, almost like butter, brittle on drying; white, yellowish, bluish, reddish .- not adhering to the tongue. B.B. fuses with difficulty on the edges. Wholly soluble in sulphuric acid. From Lizard's Point, Cornwall; amygdaloid of northern shore of Lake Superior Region, (Owen's Thalite, Proc. Acad. Philad. 1852, and Am. J. Sci., [2], xiii, 420, Anal. 10, 11); Svärdsjö in Dalarne, (Piotine of Svanberg, Pogg, liv, 267, Analysis 12).

Green Earth, (Seladonite).—Earthy or a minutely crystalline appearance, dark olive green, to colandine green, and quite soft, with an unctuous feel. It occurs in amygdaloidal cavities. The green earth from Mt. Baldo is nearly apple green; G.=2907. That from Iceland where it occurs with zeolites, afforded a trace of vanadium; G .= 2.677. Analyses of Green Earth Nos. 13 to 17; 13, 14, Fassa, 15,

Mt. Baldo, 16, 17, Iceland.

Picrophyl according to Breithaupt is also altered Augite.

Cimolite, (Analyses 18-20).—Massive, earthy, very soft. G.=2:18-2:30. Color white, grayish. Lustre of steak greasy. Absorbs water but does not fall to pieces. Corresponds in composition nearly to \overline{A} Si²+3 (or 2) H. B.B. infusible. The original Cimolite was from Cimolis, on the island of Argentiera, Greece. Analysis 18 is of a pseudomorph after augite from Bilin, identical in composition with Cimolite.

Acmite is considered by Bischof and Rose, pyroxene altered by the alkaline process.

Augite altered to Hornblende is found in Uralite, which has the form of Augite, with the cleavage and composition of hornblende. Pyroxene from Taberg and Pargas, and a variety from the Azores, also have a hornblende composition, while some hornblendes, as a tremolite from Pennsylvania, and a hornblende from Hartlingen, have the composition of Augite. These transitions are explained by Bischof, as above, (see p. 164). Scheerer considers them cases of paramorphism, or a change from one of the two forms of a dimorphous compound to the other, augite and horn-blende being dimorphous. The annexed table shows the relations in form of the two species referred to the augite type; it presents the symbols of the planes in hornblende. Sandberger has observed crystals of augite and hornblende forming a macle together; and in some cases the hornblende crystals are implanted

		0		
11		12		11
			33	
ii	i6	i 2	13	iì
			-33	
-2i		-22		
-1 <i>i</i>		-12		12

Observed Planes in Hornbler (p. 171), referred to the Augite Axes.

around the augite. Sandberger and Blum regard facts of this kind as proving that the two species may form simultaneously. (Sandberger, Pogg., lxxxiii, 453).

Other pseudomorphs after augite, are as follows:—steatite and serpentine by al-

teration; opal, quartz, limonite, calcite, by substitution.

Palagonite of von Waltershausen occurs amorphous and in grains and fragments forming much of volcanic tufa or conglomerate, H.=4-5. G.=2.4-2.7. Lustre vitreous or greasy, or like pitchstone. Color amber-yellow, yellowish-brown, garnet-red, colophonite-brown, blackish. Streak yellow.

Composition .- Analyses by von Waltershausen (Vulk. Gesteine, 1853). Means after gangue excluded:

		Si	X 1	₽e	Ċa	Мg	Ñа	Ř	Ĥ
I.	1. Krisuvik,	40.68	14.59	14.24	6.95	7.65	1.84	0.45	13.60=100.
II.	2. Hecla,	4075	8.42	17.99	8.64	4.54	0.62	0.44	18.60=100.
	3. Laxá,	42.28	11.14	1671	5.68	6.39		1.80	16.00 = 100
	4. Val di Noto,	38.69	13.61	14.51	8.38	6.13	1 07	1.35	16.26 = 100.
III.	Galapagos,	38 07	13.03	6.66	7.54	6.58	0.70	0.94	$28 \cdot 15 = 100$.
	6. "	36.94	11.26	10.71	7.95	6.28	0.55	078	25.23 = 100
IV.	7. Südafell,	41.46	10.81	18.12	8.54		0.64	0.40	14.49==99.37.
	8. Val di Noto,		8.60	25.32	5.59	4.84	1.06	0.54	12.79 = 100.
V.	9. "	40.86	10.07	20.54	4.46	3.58	3.99	1.10	1570 = 100.
VI.	10. "	34.99	6.02	20.50	6.08	11 02	0.92	0.93	19.54 = 100

Waltershausen calculates for chrysolite and sometimes carbonate of lime present in the above, and makes out for the correct composition, as mean results for many analyses under the above types, I to VI:

Si Æl Fe Ca Mg Na K H Palagonite, 41 90 12 72 16 74 6 71 6 86 1 92 0 99 12 16 = R Si = +2R Si +6 R " 40 62 11 03 15 86 7 23 5 44 0 62 1 53 17 67 = " +9R Si +12R S II. III.

The Korite is a hydrous labradorite; it is in dull brown grains, and is associated with Sideromelane, which has the same composition excepting the absence of water. It may well be doubted whether these substances are, all of them, distinct chemical compounds.

Waltershausen makes out another allied compound which he calls Trinscrite. constituted as above given. It is dull brown and cleavable or micaceous, and is mixed with his Siderosilicite, a hydrous silicate of peroxyd of iron and alumina It may be remarked that decomposed chrysolite in one of its stages has the brown appearance and structure of the mixed Trinacrite and Siderosilicite.

unsen regards the Palagonite of Iceland, (Pogg. lxxxiii, 219, and Ann. Ch. s. [3], xxxviii, 237), as consisting of silicates R² Si²+Aq and H Si+Aq, combined 1 one another. To the Palagonite of Iceland, he gives the formula, R² Si²+2H Aq, to that of the Galapagos, R² Si²+H Si+Aq; and he observes that the parite occurs as the basis of the basaltic tufas of Germany, France, Azores, Cana-Cape Verdes, Tortugas, and probably also of the Pacific Islands. He gives lyses which show great uniformity of composition in the basaltic tufas, and pares it with the constitution of pyroxene, the alteration of which is the source he peculiarities of the tufa. He also observes that the Palagonite may be made ficially by putting powdered basalt into a large excess of caustic potash in fuand pouring on water; the product, after washing, is hydrated, pulverulent, gelatinizes with weak acids, and its composition is like that of the purest parite of Iceland. The origin of the Palagonite is hence attributed to the alteratof pyroxene rocks, in which process the iron is peroxydized.

OLTONITE, Shepard. Disseminated massive. Cleavage rather distinct in one ction; in two others oblique to the first, indistinct. H.=5.5. G.=2.8—2.9, pard; 3.008, Silliman. Lustre vitreous. Streak white. Color bluish-gray, yelish-gray, wax-yellow, yellowish-white. The darker colors turn yellow on extre. Transparent—translucent.

omposition .- Analysis by Silliman, Jr., (Am. J. Sci., [2], viii, 392):

Si 46 062, \$\frac{1}{40} 5 \cdot 667, Mg 38 149, Fe 8 \cdot 632, Ca 1 \cdot 516=100 \cdot 026.

gives the formula $\hat{R}^2 \stackrel{\sim}{S}i + 1 \stackrel{\sim}{M}g^2 \stackrel{\sim}{A}l$ or $\hat{R}^2 \stackrel{\sim}{S}i, \stackrel{\sim}{A}l$). But it is quite probable that species is an altered augite.

species is an altered augite.

B. alone, it is bleached and rendered transparent, but does not fuse. With boit forms a transparent glass.

oltonite is disseminated through white limestone at Bolton, Mass., and also at bury and Littleton.

r. Saemann attributes the change of color in boltonite to minute grains of magc iron disseminated in the substance of the crystals, which undergo change on soure, and leave the mineral of a lighter color than it was when fresh.

osure, and leave the mineral of a lighter color than it was when fresh. homson's bistlicate of magnesia, (Ann. Lyc. Nat. Hist. N. Y., iii, 50), the analysi which has been referred to this species, is shown by Silliman (loc. cit.) to be nolite.

ODONITE, Beud. Manganese Spar. Bisilicate of Maganese, Thomson. Rother angankiesel. Kieselmangan. Photizite, Dumenil. Allagite. Corneous Mannese. Bustamite, Brongn. Fowlerite. Marceline, Beud. Dyssnit, Kobell. sisbergit, Igelström.

Monoclinic, and like pyroxene, $I: I=87^{\circ} 7'$. Observed planes, $I: I=87^{\circ} 7'$. Ob

conserve is the crystallized Rhodonite of Franklin, N. J.; it is often black exally from alteration. Named after Mr. S. Fowler. The name Rhodonite alludes he red color.

Rotisite is a mixture of Rhodonite and carbonate of manganese. Marceline n St. Marcel) is an impure silicate into which the Rhodonite changes on expoBustamite, from Mexico, is grayish-red, and at times somewhat fibrous; it aims much lime. Allagite is greenish-gray, verging towards black, and is swhat fibrous, resembling altered bustamite; named from allayn, change, alludto change on exposure.

psimose of Beudant, from Franklin, N. J., is the fowlerite partially altered.

10 dyssnite of Kobell, is from the same region and of similar character. Thom11 analysis of fowlerite (Ann. Lyc. N. Y., iii, 28) is from a partially altered

imen of this kind.

Composition.—Mn² Si²—Silica 45.9, protoxyd of manganese 54.1=100, or a true manganese augite; usually (Mn, Ca)³ Si² or (Mn, Fe, Ca)³ Si³. Analyses: 1, Ber zelius, (Afhandl. i, 110, iv, 382); 2, 3, Ebelmen, (Ann. d. Mines, [4], vii, 8); 4, Dumas, (Ann. des Sci. Nat. viii, 411); 5, Ebelmen, (loc. cit.); 6, 7, Hermann, (J. f. pr. Chem. xlvii, 6, 8); 8, A. Schlieper, (this Min., 3d edit., 463); 9, Igelström, (J. f. pr. Chem, liv, 190).

		Š i	Йn	Ċa	Йg	F e
1.	Langbanshytta,	48.00	49.04	3.12	0.52	=100.38, Berzelius.
2.	Algiers,	45.49	39.46	4.66	2.60	6.42=98.63, Ebelmen; G.=3.599.
3.	St. Marcel,	46.37	47.38	5.28		=99·23, Ebelmen.
4.		48.90				0.81=100.34, Dumas; G.=3.12-3.35.
5.						1·15, Ca C 12·27=99·90, Ebelmen.
						7·23, Zn 5·85, ign. 1·00=99·67, H.
7.	Cummington,					trace=100, Hermann. G.=3.42.
8.	"	51.21				4.84=101.13, Schlieper.
9.	Paisbergite,	46.46	41.88	8.13	0.91	3:31=100:69, Igelström. G.=3:63.

Schlieper found his specimen (one furnished by the author and seemingly unaltered) to consist partly of carbonate of manganese and other bases. By digestion in concentrated muriatic acid, it afforded 90.15 per cent. of silicate of manganese, and 9.85 soluble portion. The latter gave on analysis,

 $\dot{\mathbf{M}}$ n $\ddot{\mathbf{C}}$ 50·52, $\dot{\mathbf{F}}$ e $\ddot{\mathbf{C}}$ 8·60, $\dot{\mathbf{C}}$ a $\ddot{\mathbf{C}}$ 37·17, $\dot{\mathbf{M}}$ g $\ddot{\mathbf{C}}$ 2·44, $\dot{\mathbf{H}}$ and loss 1·27=100.

Ten per cent. of carbonates had been previously found in the Cummington mineral, by E. Hitchcock. Allowing that the ten per cent. of carbonates in Schlieper's specimen had been formed at the expense of the bases in the Rhodonite, and also that there was some free silica in minute points or grains, as was obvious to the eye, the oxygen ratio cannot be taken as different from that of Rhodonite.

B.B. becomes dark brown, and malts to a reddish-brown glassy globule; with the fluxes gives the reaction of manganese. In powder, partly dissolves in muristic acid, and the insoluble part becomes of a white color. Darkens on exposure to the air, and often becomes nearly black.

Occurs at Langbanshytta, near Phillipstadt in Sweden, in iron ore beds, in broad folia, and also granular massive; also at Elbingerode, in the Hartz; in the district of Ekatherinenburg, in Siberia; with gray copper ore at Kapnik, in Transylvania; in Cornwall. Paisbergite is from Paisberg's iron mine in Phillipstadt. Sweden.

Occurs in boulders in the town of Cummington, Mass., and some of the neighboring towns, and has been observed also in Warwick, of the same State, on the other side of the Connecticut. Also in an extensive bed on Osgood's farm, Blue Hill Bay, Maine; in Irasburgh and Coventry, Vt.; near Winchester and Hinsdale, N. H. An ore from Stirling, New Jersey, gave Thomson the angle 123° 30', which is near the angle of hornblende, but we have not been able to verify the result. Thomson's analysis of this ore, if correct, would make it a manganese augite or Rhodonite, (Min. i, 515), and this sets aside his measurements, or at least throws doubts upon them. He found the specific gravity 3.586.

The Fowlerite which occurs in large crystals with franklinite, at the Franklin Furnace, Hamburgh, at Stirling, N. J., has been analyzed by W. Camac, (Am. J. S. [2], xiv, 418), and the following composition obtained:—

Si Mn Fe Zn Ca Mg 42·20 25·37 11·00 4·15 9·66 5·27, feldspar 3·56=101·20.

This gives the oxygen ratio for the silica and protoxyds 3: 1.85, corresponding nearly to 9 R, 5 Si. The result needs confirmation.

A rose-colored ore from Kapnik, in concretionary forms afforded Brandes, \$53.50, Mn 41.93, Fe 1.00, \$\frac{1}{4}\$1.24, \$\hat{H}\$3.00, and it has been considered a trisilicate, \$\hat{M}\$n \$\bar{B}\$i; \$G.=2.8. Its purity is denied by Dufrénoy, who attributes part of the silicat to the quartz with which it is associated.

Mangan-Amphibole, Hermann, (J. f. pr. Chem. xlvii, 7). Hermann separates from Rhodonite, without good reason, the Cummington Manganese spar under the idea that it is a hornblende, and not a manganese augite. He unites with it Thomson's Stirling ore.

ALTERED FORMS.—Rhodonite changes partly to a carbonate, by the action of waters holding alkaline carbonates in solution, as exemplified in remarks above; and also becomes altered by the tendency of protoxyd of manganese to pass to a higher state of oxydation, accompanied with the absorption of water. By the last process, the red color becomes brown and black, and indefinite compounds or mixtures result, which may be either partly silicates, or wholly an oxyd of manganese. Marceline and Allagite, etc., are of this kind. The following also probably belong here as altered Rhodonite.

Stratoprite, Igelström.—From the Pajsberg iron mine in Philipstadt. Amorphous, massive. Easily scratched with a knife blade. G.=2.64. Color pitch-black, brown or brownish red in thin splinters. Streak brown. Fracture flat conchoidal. B.B. fuses to a black translucent globule. With muriatic acid, much chlorine is evolved.

The following are analyses of this and other allied impure silicates by Igelström, Bahr, and Svanberg, (Octv. V. Ak. Förh. 1850, 1851, and J. f. pr. Ch. liii, 308, liv, 190).

		Š i	Æl	₽e	₩n	Ċa	Йg	II
1.	Stratopeite,	35.43		10.27	32.41		8.04	13.75, Igelström.
2.	Klapperud,	36.20	1.11	0.70	47:01	0.61	4.13	9·43=100·39, Bahr.
3.	• • • • • • • • • • • • • • • • • • • •	36:11	0.90	11:31	42.00	0.70	0.57	9.43=101.39, Svanberg.
4.	"	34.72	1.09	10:45	42.64	0.56	0.36	9.76=99.98, Bahr.
5.	**	23.69	0.61	9.14	56.51		0.33	9:51=100:05, B.
6.	**	33.81	1.03	7:53 M	[n 46·18	0.72	1.42	
7.	16	43:30	6.80	4:57 M	[n 9·88	15:96	11.90	6·13, Čo 0·39=98·98.

Igelström writes for Stratopcite, (Anal. 1), the formula Mg² Si²+4 (Mn. Fe), Si+12 H. A related mineral has been called Neotokite; formula deduced, Mg Si+4 (Mn. Fe) Si+9 H: G.=2·70. Wittingite is similar, formula given it, 2 (Fe, Mn) Si+3 H; G.=2·71-2·76; from Wittinge, Finland.

Analyses 2 to 4 are of a dull lead gray mineral; they give the oxygen ratio for the peroxyds, silica and water, 2:2:1. Analysis 5 gives the ratio 2·5:15:1; color pure black; fracture earthy; rather soft: G.=3·207. Analysis 7 is of a light yellow mineral, hard and without distinct cleavage: lustre between vitreous and

yellow mineral, hard and without distinct cleavage; lustre between vitreous and greasy; G .= 3.320; the oxygen ratio which the analysis gives for the protoxyde, peroxyds, silica and water is, 2:5:1:5:12.

SPODUMENE, d'Andrada. Triphane, H.

Monoclinic. $I = 69^{\circ} 40', I: I = 87^{\circ}, O: 2i$ =130° 30'.

 $O: ii = 69^{\circ} 40'$. $ii :-2 = 117^{\circ} 19'$. $Q:=1=134^{\circ}12'$. $ii:=22=125^{\circ}12'$.


O:-2=110° 50'. ii:-1=101° 6'.

 $ii: I=133^{\circ}30', \quad ii:-2=134^{\circ}19', \\ ii: i3=107^{\circ}33', \quad I:-2=145^{\circ}50', \\ I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \\ I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=145^{\circ}50', \quad I:-2=14$

 $2i: 2i \text{ (top)} = 80^{\circ}. \ I:-1=121^{\circ} 28'.$ $\vec{n}: 2\mathbf{i} = 139^{\circ} 30'$. $-1:-1=116^{\circ} 19'$.

ii:2i=102°5434. -2:-2=91°244.

Crystals large. Cleavage: ii very perfect; I also perfect; 1i in traces, seen in strice on Twins, face of composition ii. Also cleavable massive.



H.=6.5-7. G.=3.1-3.2; 3.17, Haidinger; 3.188, Thomson, specimen from Dublin Bay; 3:132—3:137, Rammelsberg. Lustre pearly. Cross fracture vitreous. Color gravish green, rasing into greenish white and grayish white, rarely faint reddict; street uncolored. Translucent—subtranslucent. Fracture uneven.

Composition. —(1R°+4H)Si°=Silica 64·5, alumina 29·3, lithia 6-2.

Analyse4: 1, R, Hagen, (Pogg. xlviii, 361); 2, Thomson, Min. i, 3-2: 3, 4, Remelaberg, (Pogg. lxxxv, 544); 5-8, Smith and Brush, (Amer. Jour. Sci. [2], xvi, 372;

		Bi	Æl	₽e	Li	Ňа	Ĉa.
1.	Uto,	66:136	27 024	0.321	37836	2 683	=100, Hazen
2.	Killiney,	63.812	28.508	Fe 0 828	5.604		0728, H 036-754 Then
8.	Uto,	65:02	29.14	Fe trace.	5.47	0.46	0-50, K 0-14, Mg 0-15, R.
4.	Tyrol,	65.53	29.04	Fe 1.42	4.49	リガイ	O. J. K O.Y. Meor. R
Б.	Norwich	64:04	27.84	0.64	5-20	0-66	034 ign.05), K (-16=393),
							SIR
6.	"	63.65	2	28-97	51)5	0-32	031 " 050=95 3) S. 4R
7.	"	63.90	5	28.70	4-99	0.80	0-26 - 0-6
8.	Sterling,	64.60	25.30	2.55	5.65	1.10	0.43 " 0.30, Mg0-06==97 N.
	***						2 A R

a With some soda; in 5, 6, 7, magnesia, trace.

In a specimen from Sterling, Mass., Hagen found Si 65-247, &1 Pe 27-556; and B another from Tyrol, Si 66-027, XI 26-451.

B.B. loses translucency and color, intumesces and fuses to a glassy globale; give

the reaction of lithia.

Occurs on the island of Utö, in Südermanland, Sweden, with magnetic iron ore, quartz, tourmaline, and feldspar; also near Sterzing and Lisens in the Tyrol and of a pale green or yellowish color, imbedded in granite, at Killiney Bay, new Dublin, and at Peterhead in Scotland.


It occurs in granite at Goshen, Mass., associated at one locality with blue tour-maline and beryl; also at Chesterfield, Chester, Norwich, and Sterling, Mass.; & Windham, Maine, near the bridge, along with garnet and staurotide; at Brockfeld. Ch., a few rods north of Tomlinson's tavern, in small grayish or greenish white individuals looking like feldspar. At Norwich, Mass., it is associated with triphylme, mica, beryl, and albite; one crystal from this locality was 161 inches long, and 10 inches in girt.

Named from snodes, nahes, because the mineral becomes ashy before the blowpips. The following are the angles obtained with the common goniometer, from the Korwich crystals: $O: ii=69^{\circ}$ 40', ii: $I=138^{\circ}$ 30', ii: $i \ge 107^{\circ}$, 21: 21 (top)=80°. 1:21 $I=139^{\circ}$ 40', ii: $I=130^{\circ}$ 30', ii: I=1

Attenno Forms. — Killinite of Thomson (Min. i, 330) has the appearance of spotumene, and occurs with it at Killiney Bay. Mallet states that it affords by cleavage a prism of 135°, which is very nearly the angle between the diagonal and prismatic cleavage of spodumene, both of which are perfect. H.—4. G.—256. Austre vitreous, weak. Color greenish-gray, brownish, or yellowish. Composition According to Lehunt and Blythe (loc. cit.) and Mallet, (Rammelsberg's 5th Sup. 143):

	Äi	Ä١	Fe	Ċэ	Mg	Mn	ĸ	Ħ
1.	49.04	30.60	2.27	0.68	1.08		672	10:00=100:43, L.
¥.	47.98	31:04	2:33	0.72	0.46	1.25	606	10.00=29.30, BL
8.	63.89	83.24	3.27	1.45			4.94	8 67, Li 0 46=99 92, M.

110)RNBLENDE. Amphibole. Green diallage. Actinolite. Actinote. Tremolite Calamite. Pargasite. Smaragdite. Asbestus, in part. Amiantha. Amianthinite. Amianthoid. Lotalite. Strahlstein, Tremolith, Kalamit, Amiant. W. Grammatit. Byssolith, Haus. Carinthine, Anthophyllite, Schumacher. Commingtonite, Dewey. Breislakite, Brocchi. Raphilite, Thom. Arfvedsonite, Hyanke Agirin, Tunnau, in part. Kymatin, Breit. Diastatite, Breit. Monoclinic. $C=75^{\circ}$ 2', $I: I=124^{\circ}$ 30', $O: 1i=164^{\circ}$ 10', a:b:c=0.5527:1:1.8825. Crystals sometimes stout, often long and



bladed. Cleavage: I highly perfect; ii, ii, sometimes distinct. Lateral planes often longitudinally striated. Twins: face of composition ii, as in f. 362, a twin of the form represented in f. 361.

```
O: 1i=155^{\circ} 33'.
                           ii: ii = 147^{\circ} 39'.
                                                                    11
0:-1i=149^{\circ}.
                            i\vec{s}: i\vec{s} = 115^{\circ} 18'.
O: -2i = 124^{\circ} 56'. ii: 3i = 124^{\circ} 14'.
O: ii = 104^{\circ} 58'. ii: -33 = 130^{\circ} 15'.
                                                                                      33
O: 1=152^{\circ} 36'.
                            2i : 2i(ov.O) = 120^{\circ} 52'.
                                                                    ii
                                                                          i3
                                                                                 I
                                                                                      i3
                                                                                            iż
O: -1 = 145^{\circ} 35'.
                             1:1=154^{\circ}26'.
O: -2=121^{\circ}29'.
                            1:-1=148^{\circ}28'.
                                                                                      33
0:2i=150^{\circ}26'.
                           -2:-2=131^{\circ}36'.
                                                                    -2i
                                                                                -2
                                                                                             21
0: \ddot{u} = 90^{\circ}.
                            8\hat{s}: 8\hat{s}=111^{\circ} 32'.
O: I=103^{\circ} 12'.
                            -3 \circ : -3 \circ = 99^{\circ} 30'.
                                                                    -1i
\vec{u}: i3=99^{\circ} 57'.
                                                                          Observed Planes.
```

Imperfect crystallizations: fibrous or columnar, coarse or fine, fibres often like flax; sometimes lamellar; also granular, coarse or fine, and usually strongly coherent; sometimes friable.

H.=5—6. G.=2.9—3.4. Lustre vitreous to pearly on cleavage faces; fibrous varieties often silky. Color between black and white, through various shades of green, inclining to black in green. Streak uncolored or paler than color. Sometimes nearly transparent; usually subtranslucent—opaque. Fracture subconchoidal, uneven.

Composition.—R'Si²=R'Si⁴=R'Si²+RSi.

Isomorphism leads to the same variations of constitution in hornblende, as in vroxene, and R may be either lime, magnesia, protoxyd of iron or manganese.

pyroxene, and R may be either lime, magnesia, protoxyd of iron or manganese. Alumina replaces silica, in some varieties. The prominent varieties are the following:—

Tremolite, (fr. Tremola valley, Switzerland), Grammatite, (fr. γραμμη, a line)—White, grayish, greenish, or yellowish-white specimens. Crystals often in long slender blades, either distinct and traversing the gangue, or aggregated in columnar and radiated masses. G.=2.93. Transparent—translucent. Calamite (fr. calamis, a reed) is asparagus green in crystals. Raphilite (fr. ραφις, needle) is an asbestiform tremolite from Lanark, Canada. Formula, CaSi+Mg³ Si³=Silica 60.7, lime 12.5, magnesia 26.8.

Actinolite, (fr. arriv, a ray), Actinote, Strahlstein. Bright-green bladed crystals or columnar forms; if in distinct crystals, glassy actinolite. The crystals are long, slender prisms, and break easily across the prism. The fibrous or radiated crystalizations are often named asbestiform actinolite. The green color is owing to a small proportion of oxyd of iron, and on account of the iron present, the specific gravity of actinolite is above that of tremolite, usually between 312 and 315.

Anthophyllite, (fr. anthophyllum). Fine columnar, or made up of acicular fibres of brown or grayish-brown color, often submetallic. G.=2.94—3.16. The cleavage affords prisms of 124° 30°, like other varieties of hornblende. Formula, FeSi+Mg' Si²—Silica 58.6, magnesia 25.9, protoxyd of iron 15.5.

Asbestus, (fr. achieros, unconsumable), when of a white color or some light shade is a fibrous variety of tremolite or actinolite. The fibres are often as fine as flax, and may be separated with the fingers. By traversing limestone or the gangue that contains it, it often gives an asbestiform appearance to large masses of the rock. The more delicate varieties, presenting the lustre of satin, are called Amianthus, (fr. apiarros, undefiled).—The fibres of asbestus are sometimes so interlaced that the fibrous structure is not apparent; this variety is called mountain leather, and rock or mountain cork; the former occurs in flexible laminm or sheets, resembling leather, and the latter has the feel and nearly the texture of cork; both are so light, owing to the loose interlacing of fibres, as to float on water.

Pargasite. Pargasite includes crystallized varieties (crystals usually thick and stout) of high lustre and rather dark shades of green; it is also granular.

Hornblende. The name hornblende, as originally applied, belonged only to the dark green and black varieties, whether in crystals or massive. It contains much iron and alumina; G.=3.1 to 3.4. The name alludes to the toughness.

Carinthine is a hornblende (aluminous and ferruginous) from Carinthia. G .= 3:127.

Arfeedsonite. A black hornblende containing largely of iron and also soda, and according to Brooke, having I: I=123° 55′. Lustre vitreous, inclining to resinous. G.=3'44. Formula, NSi+Fe'Si'=silica 49'4, protoxyd of iron 3'03, soda 11'3. It is very fusible, melting even in the flame of a candle. Named after Professor Arfvedson of Sweden.

Egirine, as analyzed by Plantamour, is a black hornblende related to Arfvedsorite. A black or greenish-black Brevig mineral so-called is pyroxene.

Hornblende Rock and Amphibolite are names of rocks consisting of hornblende, and having a crystalline granular texture, sometimes slaty.

Corncine is a compact hornblende rock of smooth fracture, extremely tough and sonorous when struck. The name is from the Latin for horn.

Diastatite. A hornblende from Wermland, differing a degree, according to Breithaupt, in the angle of the prism from hornblende. G=3.09-3.1.

Uralite (from the Urals) has the cleavage structure and composition of horn-blende, though the external form of augite, and is considered a pseudomorph. The two species are variously mingled in different specimens, showing the change in different stages of progress.

Analyses: 1, 2, 3, Bonsdorff, (Schw. J. xxxi, 414, xxxv, 123); 4, Seybert, (Am. J. Sci. vi, 333); 5, Damour, (Ann. Ch. Ph. [3], xvi); 5½, 6, Ramm., (5th Sup. 131, 1st Sup. 73); 7, Murray, (ib. 2d Sup. 60); 8, Bonsdorff; 9, T. S. Hunt, (Amer. J. Sci. [2] xii, 213, Phil. Mag. [4], i, 322); 10, Richter, (Pogg. lxxxiv, 367); 11, Vopelius, (Pogg. xxiii, 355); 12, 13, Thomson, (Rec. Gen. Sci. xvii); 14, Heintz, (Pogg. lviii, 168); 18, 16, Smith and Brush, (Am. J. Sci. [2], xvi, 48); 17, Kobell, (J. f. pr. Ch. xiii, 3); 18. Plantamour, (J. f. pr. Ch. xxiv, 300); 19, 20, Bonsdorff; 21, 22, 23, Hisinger, (Schw.

J. xxxi, 289); 24, Bonsdorff; 25, Arfvedson, (Jahresb. iv, 149); 26, Göschen, (Ramm. 2d Sup. 61); 27, Clausbruch, (Ramm. 1st Sup. 72); 27½, Kudernatsch, (Pogg. xxxvii, 585); 28, Rammelsberg, (Pogg. lxxxiii, 458); 29, 30, 31, Waltershausen, (Vulk. Gest. 111); 32, 33, Klaproth, (Beit. v, 150); 34, Hisinger.

I. Tremolite and Actinolite, containing lime and magnesia, without alumina.

```
Βi
                               Mg Ċa
                                              Fe Min Hil
                                                      - trace HF 0.94, H 0.10, B.
                          59.75 25.00 14.11
 1. Wermland, white,
                                             0.50 -
                                             1.00 0.47 0.42
                          60.10 24.31 12.73
                                                               " 0.83, H 0.15, B.
 2. Fahlun,
                                                               " 076=100·12, B.
3. Taberg, greenish,
4. Concord, Pa., green,
                         5975 21.10 14.25
                                             3.95 0.31 ----
                                             4.30 — 1.67, Ĥ 1.03=100, Seyb.
                         56:33 24:60 10:67
                                                         5. St. Gothard,
                          58.07 24.46 12.99
                                             1.82 -----
 51. Gouverneur, N.Y. wh. 57.40 24.69 13.89
                                             1.36 — 1.38, Ĥ 0.40=99.12, R.
                                                     - 0.58=100.21, Ramm.
- = 100.05, Murray.
6. Kymatin, Asbestus,
7. Taberg, "
                          57.98 22.88 12.95
                                             6.32 -
                          59.50 19.30 12.65
                                             8.60 -
                  "
                          58-20 22-10 15-55
                                             308 021 014, HF 066, H 014, B.
 8. Tarentaise,
 9. Raphilite,
                          55.30 22.50 13.36
                                             6.30 trace 0.40, Na 0.80, K 0.25, ign.
                                                                0.30=99.81, Hunt.
                         58.89 23.37 9.57
                                             3.79 -
                                                     - 0.67, H 3.60=99.89, Richter.
10. Reichenstein,
```

II. Anthophyllite, containing magnesia and iron, without alumina

11. Kongsberg, 12. Perth, C. E., 13. Tyrol, Asbestus, 14. Ural, " 15. Cummingtonite,	57·60 29·30 3·55 54·92 26·08 — 59·23 31·02 — 51·09 10·29 tr.	13·94 2·38 —, Ĥ 1·67=99·08, Vop. 2·10 — 3·20, Ĥ 3·55=99·30, Th. 12·60 — 1·64, Ĥ 5·28=100·52, Th. 8·27 — 0·19, ign. 1·31=100, H. 32·07 1·50 0·95, Ña 0·75, K tr., Ĥ 3·04
16. "	50·74 10·31 tr.	=99.69, S. & B. 33.14 1.77 0.89 " 0.54 K tr., H 3.04 =100.48 S. & B.

III. Arfvedsonite, containing soda and iron, without alumina.

```
17. Greenland, 49.27 0.42 1.50 36.12 Mn 0.62 2.00 Na 8.00, Cl 0.24, K. 18. Brevig, Ægirine, 46.57 5.88 5.91 24.38 " 2.07 3.41 " 7.79, K 2.96, Ti 2.02, F. undermined=100.99, Plantamour.
```

With trace of K.

IV. Containing alumina, with lime and magnesia.

- 19. Aker, Grammatite, 47.21 21.86 12.73 2.28 0.57 13.94, HF 0.9, H 0.44, B.
- V. Containing alumina, with iron, lime, and magnesia. G. of 29=2.893; 31, 3.284.

```
7:32 0:22 12:18, HF 1:50=99:53, B. 7:75 0:25 15:75, H 0:5=97:24, H.
20. Pargas,
                               45.69 18.79 13.83
                               41.50 19.40 14.09
21.
22. Fahlun,
                               47.62 14.81 12.69 15.78 0.32 7.38=98.60, Hisinger.
23.
    Westmanland,
                               45.38 16.34 13.92
                                                      7.74 1.50 13.82, II 0.23=98.92, H.
24. Wetterau,
                               42.24 13.74 12.24 14.59 0.33 13.92=97.06. Bonsd.
25. Greenland, Arfued.
26. Wolfsberg, Boh.
                               41.81 11.20 11.55 19.50 1.47 12.14=97.67, Arfvd.
40.27 13.38 13.80 15.34 — 16.36, H 0.46=99.61, Gös.
                                                                     8·37=100·55, Clausbruch.
4·56=99·35, Kud.
27. Carinthia, Carin.
                               46 08 18 48 10 23 F17 44
271. Uxalite,
                               53·03 12·90 12·47 16·37
                                                                  - 11 00, Na 1 71, K 1 92, Ti
28. Härtlingen,
                               42.52 13.45 12.25 16.59 -
                                                                                1.01 = 100.45, R.
                                                                    9.27, H 0.81=99.49, Walt.
29. Etna, V. d. Bove, bk.
                               43.84 1170 12:05 2179 ---
                              40.91 13.19 13.14 17.49 tr. 13.68 "0.85=99.56, Walt. 39.75 13.01 12.99 14.40 1.06 15.29 "1.02=97.52, Walt.
80.
             Mascali,
     "
             Zoccolaro,
```

b Probably 2 1-2 per cent. of alkali to be added, W.

VI. Containing alumina, with iron and lime.

Si Mg Ca Fe . Min Al

82. Westmanland, 42.00 2.25 11.00 30.00 0.25 12.00, H 0.75, K, trace=

98.25, Klap.

83. Fuldaischen,

47.00 2.00 8.00 15.00 --- 26.00, H 0.5=98.50,

VII. Containing alumina, with iron and magnesia.

84. Garpenberg,

53.50 11.85 4.65 22.52 0.85 4.40, H 0.6=97.10, His.

Cummingtonite is an anthophyllite variety containing largely of oxyd of iron resembling an asbestiform tremolite, often scopiformly arranged; color ash-gray, lustre silky. B.B. alone fuses with great difficulty. Formula, (* Fe+* Mg)* Si*, Smith and Brush, (Anal. 15, 16.)

The analysis by Thomson, (Ann. Lyc. Nat. Hist. New York, iii, 50), referred by Shepard to Boltonite, is shown by B. Silliman, Jr., (Am. J. Sci. [2], viii, 391), to pertain probably to an actinolite from Bolton. The Raphilite, according to Hunt, has the surjet avecar ratio 2: 1 (anal. 9)

the augite oxygen ratio 2: 1, (anal. 9).

The fluorine in any hornblendes is supposed to exist as fluorid of calcium, and this ingredient, according to Bonsdorff may constitute 1 part in 5 of the mineral.

B.B. the tremolite and pale varieties, containing no iron, fuse readily with intumescence to a glass nearly transparent to milk-white; and with borax form a transparent colorless glass. The lighter colored varieties containing iron, fuse alone with more or less difficulty to a dark yellowish glass, and with borax give a transparent glass, tinged with iron. The darker green varieties afford a deeper iron color. The hornblende, containing alumina and little iron, acts much like tremolite; but the black varieties fuse to a brilliant black bead, and the borax glass is tinged with iron. Anthophyllite fuses with great difficulty to a glass colored by iron. Arfvedsonite fuses readily with intumescence to a black magnetic globule.

Green or black hornblende is one of the constituents of syenite and greenstone, as well as hornblende rock and slate. Tremolite is most common in dolomite and granular limestone. Hornblende also occurs in granular limestone and in trachyte. Actinolite is found in the greatest perfection in talcose rocks. Asbestus often traverses serpentine rocks and granular limestones. Much of the so-called asbestus in

serpentine is Chrysotile.

Aussig and Teplitz in Bohemia, Tunaberg in Sweden, and Pargas in Finland, afford fine specimens of the dark colored hornblendes. Actinolite occurs at Saltburg and Greiner, in the Zillerthal; Tremolite at St. Gothard, in granular limestone or dolomite, the Tyrol, the Bannat, Gulsjö in Sweden, &c. Calamite occurs at Normarken in Sweden, in prisms in serpentine. Asbestus is found in Savoy, Saltzburg, the Tyrol; also in the island of Corsica, where it is so abundant that Dolomieu employed it in packing his minerals. Rock cork is obtained in Saxony. Portsoy, and Leadhills, where also mountain leather occurs. Oisans, in France, affords a variety of amianthus, composed of fibres having some degree of elasticity; it is the amianthoide of Haüy. Anthophyllite comes from Kongsberg, Norway, &c. Arfvedsonite was brought first from Greenland, where it is associated with sods-

It occurs also at Fredericksvärn, in Norway.

In the United States, black crystals of hornblende occur at Franconia, N. H.; at Chester, Mass.; at Thomaston, Me.; at Moultonboro', Me., in Syenite; at Willsboro', N. Y., presenting interesting crystalline forms; also near the bridge at Potadam, St. Lawrence Co., N. Y.; near Greenwood Furnace, and in Warwick, Orange Ca., N. Y. (f. 365.) Crystals of a dark green color occur near Two Ponds, and also a mile north, two and a half miles north, and a mile south of Edenville, together with gray or hair brown crystals and tremolite, sphene, and chondrodite, in graular limestone. Near Amity, hornblende occurs of various forms and colora, and often in large and perfect crystals: in dark green crystals, with ilmenite, at the Stirling mines, Orange Co.; at Gouverneur, in short green crystals, sometimes two or three inches in diameter, along with apatite; in Rossie, two miles north of Orbow, the variety pargasite in neat bright green crystals. Pargasite occurs also at Phipsburg and Parsonsfield, Me. Gray hornblende or tremolite in good crystals is found at Bryam, N. J., and other varieties at Franklin and Newton of the same State.

Large flattened crystals of a white color abundant in dolomite at Cansan, Conn., between the falls and the post office, and other places in Litchfield Co.; also at Lee (one and a half miles southwest of the meeting house) and Newberg, Mass.; in Diana, Lewis Co., N. Y. Glassy actinolite in good specimens occurs in the steatite quarries of Windham, Readsboro' and New Fane, Vt., and at Middlefield and Blanford, Mass.; also near a hamlet called Pecksville, in Fishkill, N. Y. Radiated or asbestiform actinolite at the same localities; at Unity, Me.; at Brown's serpentine quarry, 3 miles N. W. of Carmel, Putnam Co., N. Y.; at Franklin, N. J.; at Carlisle, Pelham, and Windsor, Mass.; in Buckingham Co., Willis's Mt., Va. Actinolite occurs also in Pennsylvania, in Providence, Mineral Hill, Delaware Co.; at Unionville; at Kennett, Chester Co., often in fine crystals; radiated and asbestiform tremolite abundant in the dolomite of New England and New York; at Thomaston and Raymond, Me.; Lee and Great Barrington, Mass.; in New York at Dover, Kingsbridge, the Eastchester quarries, at Hastings and near Yonkers in Westchester Co.; at Knapp's quarry, Patterson, and on the banks of Yellow lake and elsewhere in St. Lawrence Co., N. Y. The same varietics occur at Franklin, N. J.; in Pennsylvania, at Chesnut Hill, near the Wissahiccon; near Philadelphia, at Lon-

don Grove, Chester Co.; at the Bare Hills, Md.

Asbestus is met with at many of the above localities; at West Farms, Winchester, Wilton, and Milford, Conn.; at Brighton, Sheffield, Pelham, Newbury, and Dedham, Mass.; in New York, near Greenwood Furnace, Roger's farm in Patterson, Colton rock and Hustis's farm in Phillipstown, (both asbestus and amianthus), near the quarantine, Richmond Co., asbestus with the fibres between two and three feet in length; at Chesnut Hills, Penn.; Cooptown and Bare the days of the property o Hills, Md.; and Barnet's Mills, Fauquier Co., Virginia. Mountain leather occurs at the Milford quarries, Conn., also at Brunswick, New Jersey.

Cummingtonite is from Cummington and Plainfield, Mass.

A variety of hornblende, on the island of Corsica, admits of a high polish, and is the Verde de Corsica duro. Asbestus was manufactured into cloth by the ancients, who were acquainted with its incombustibility. This cloth was sometimes the material for napkins; which could be cleansed by throwing them into the fire. This material was also employed for the wicks of lamps in the ancient temples, and it is now used for the same purpose by the natives of Greenland. The name amianthus was applied to it because of the simplicity of the means of restoring it, when soiled, to its original purity. The best United States locality for collecting it for this purpose is near the quarantine, Richmond Co., New York. It is extensively used in making safes.

GEDRITE.—Resembles anthophyllite. Dufrénoy obtained Si 38.81, Al 9.31, Fe 45.83, Mg 4.13, Ca 0.67, H 2.30. From Gedré in the Pyrences.

ALTERED FORMS.—Alterations of Hornblende are mostly like those of Augite. Varieties often contain some water from hydration, (as in analyses 10, 12, 13, etc.) especially asbestiform or anthophyllite varieties. The ferruginous change by oxydation is common; and all varieties are exposed to alteration from infiltrating waters holding carbonates, silicates, etc., in solution, thus giving rise to magnesian, ferruginous, magnesio-ferruginous, (chlorite), alkaline, or aluminous forms. Beck has analyzed hornblende pseudomorphs from Warwick, N. Y., (Am. J. Sci. xlvi,

has analyzed hornblende pseudomorphs from Warwick, N. Y., (Am. J. Sci. xlvi, 25); and Rammelsberg, another from Madrell, (Pogg. lxii, 142, and 2nd Suppl. 61.)
The so-called Hydrous anthophyllite of Thomson (from New York Island) is an altered asbestiform tremolite. Fresh specimens afforded Smith and Brush as the mean of two analyses, (Am. J. Sci. [2], xvi, 49), Si 58 43, Mg 29 34, Fe 8 76, Na 0 88, K tr., ignition 2 26, Kl tr. = 99 67, corresponding to the hornblende formula. Thomson found 11 45 per cent. of water, (Min. i, 209). It occurs also in Scotland. Tale, steatite, serpentine, chlorite, mica, pinite, chabasite, limonite, magnetite, occur as hornblende pseudomorphs. Chabasite, as Bischof observes, has the same oxygen ratio for the bases and silica as hornblende; but part of the protoxyd of hornblende (the magnesia) is removed and alumina substituted, probably through the results of the decomposition of feldspar in progress at the same time.

the results of the decomposition of feldspar in progress at the same time.

Groppite, and perhaps Rosite, as L. Saemann has suggested to the author, may be altered Pargasite.

NEPHRITE. Jade. Beilstein.-A hard compact, light green, bluish, or whitish stone, translucent, tough, breaking with a splintery fracture and glistening surface; but varying in composition, and not a distinct mineral. G .= 2.9-3.1. H .= 6-7.

Composition .- Analyses: 1, Kastner, (Gehlen's J. ii, 459); 2, Rammelsberg, (1st Supp. 105, Pogg. lxii, 148); 3, 4, Schafhäutl, (Ann. d. Ch. u. Pharm., xlvi, 338); 5, 6, Damour, (Λnn. Ch. Phys. [3], xvi):

	Si	$\dot{\mathbf{M}}\mathbf{g}$	Ċa	Ѓе	Æl	₽e
						5.50, €r 0.05, H 2.75=99.80, Kastner.
2.	54.68	26.01	16:06	2.15		—-, Mn 1 39, loss ign. 0 08=100 97, Remm.
3.	58.91	22.42	12.28		1.32	2.70, Mn 0.91, K 0.80, H 0.25=99.60, Sch.
4.	58.88	22.39	12.15		1.56	2·81, Mn 0·83, K 0·80, H 0·27=99·70, Sch.
5.	58.46	27.09	12.06	1.15		—— =98·76, Damour.
6.	58.02	27:19	11.82	1.12		=98·15. Damour.


Damour's nephrite—white oriental specimens—affords the composition of tremolite—Ca Si+Mg² Si². Schafhäutl obtained a similar result. Rannmelsberg's specimen, as he states, approaches augite. B.B. fuses with difficulty on the thinnest edges; sometimes more easily to a gray mass or white enamel. It is found in constitution with these rates or lates of gray parts of the property nection with talcose rock or slate, and granular limestone.

Nephrite is worked into images and ornaments in China, New Zealand, and Northwest America. The name is from recepos, kidney; it was supposed to be a cure for diseases of the kidney. The so-called Nephrite of Smithfield, Rhode Island, named Bowenite, is identical with Serpentine in composition.

ACMITE, Haidinger, Akmite. Achmite.

Monoclinic, and like augite. $I: I=86^{\circ} 56', I: ii=133^{\circ} 28', a: a=119^{\circ} 30', a: ii=103^{\circ} 47'.$ Cleavage: I distinct; lateral less so. Plane ii often longitudinally striated. Twins: face of composition parallel to ii, common.

II.=6. G.=3·2—3·53; 3·43, Ramm. piece of a crystal; 3·53, same pulverized. Lustre vitreous, inclining to resinous. Streak pale vellowish-gray. Color brownish or reddish-brown; in the fracture blackish-green. Opaque. Fracture uneven—earthy. Brittle.



Composition.—(Na+Fe Si³ (=Na Si+Fe Si²)=Silica 55:07, peroxyd of iron 324, soda 12:6. Analyses: 1, Berzelius, (K. V. Ac. H. 1821, p. 160); 2, Lehunt, (Thomson's Min. i, 480):

2. 56 02 28 08 Ma3 49 13 33 0 89 Mg 0 50, Al 0 69 = 98 98, Lehunt.

Rammelsberg in analyses directed towards determining the condition of the iron,

found 325-355-355-3144 peroxyd of iron, and with the last, 5413 silica.

B.B. readily fuses to a black bead, which is magnetic. Affords an iron-colored glass with borax; a silica skeleton with salt of phosphorus. With soda on platinum gives a manganese reaction. In powder partly decomposed by acids.

Aemite occurs at Rundemyr, about four miles north of Dunserud, near Kongs

berg in Norway, nearly a foot long, imbedded in feldspar and quartz; the crystals are often macled and bent, and quite fragile.

Named from aspn, a point, in allusion to the pointed extremities of the crystals. G. Rose suggests that Acmite as hitherto observed, is probably in a somewhat altered condition, and that possibly the Ægirine of Brevig is Acmite in an unchanged state, (Kryst. Chem. Min., 1852, p. 76).

WICHTYNE, Laurent. Wichtisite, Hausmann.

Massive; cleavage parallel to the sides of a rhombic prism, nearly rectangular, according to Laurent.

Scratches glass. G.=3.03. Color black. Lustre dull. Fracture

angular, or flat conchoidal.

Composition.—(1R3+1R) Si2. Analysis by Laurent, (Ann. Ch. Phys. lix, 109): Si 56.3, Al 13.3 Fe 4.0 Fe 13.0 Ca 6.0 Mg 3.0 Na 3.5=99.1.

B.B. fuses to a black enamel and becomes magnetic. Not attacked by acids. From Wichtis in Finland. Dufrénoy observes that a specimen examined by him had no cleavage.

GLAUCOPHANE, Hausmann. Probably same as Wichtyne. Trimetric or monoclinic. In indistinct long thin six-sided prisms, made up of the planes I and il, and longitudinally striated. Also granular massive. H .= 5.5. G .= 3.108. Color blue, lavender-blue, bluish-black, grayish. Streak-powder grayish-blue. Lustre vitreous to pearly. Translucent to opaque. Brittle. Powder slightly magnetic.

Composition.— $(\frac{3}{5}R^3 + \frac{2}{5}R)$ $\vec{S}i^2$; or if the iron be partly peroxyd (5.4 Fe, 6.0 Fe) $(\frac{1}{2}R^3 + \frac{1}{2}R)$ $\vec{S}i^2$, like Wichtyne, Kengott. Analysis by Schnedermann, (J. f. pr. Chem. xxxiv, 238):

Si 56.49, Xl 12.23, Fe 10.91, Mn 0.50, Mg 7.97, Ca 2.25, Na with trace K 9.28=99.63.

B.B. becomes yellowish-brown, and melts easily and quietly to an olive-green glass. An iron reaction with the fluxes. In acids, partly soluble.

Occurs at the island of Syra, one of the Cyclades, in mica slate, along with garnet, hornblende, and mica. The name is from γλανκος, bluish-green, and φαινω, to ap-

Violan of Breithaupt, (J. f. pr. Chem. xv, 321), resembles Glaucophane. It occurs massive with the cleavage of a rhombic prism. G.=3-233; H.=6. Lustre waxy. Color dark violet-blue. B.B. fuses to a clear glass; with borax in the outer flame a brownish-yellow glass, violet-red when cold; in the inner flame a yellow glass, colorless when cold. Found with Manganesian epidote at St. Marcel in Piedmont. Named from its color.

Sordawalite, Nordenskiöld's Bidrag, p. 86.—Massive; no eleavage apparent. H.=2.5. G.=2.53-2.58. Lustre vitreo-resinous, or like bitumen. Streak liver-brown. Color grayish or bluish-black. Opaque. Fracture conchoidal. Brittle.

Composition .- Analysis by Nordenskiöld,

Si 49-4, H 13-8, Fe 18-17, Mg 10.67, P 2.68, H 4.38=99.10.

Supposed by Berzelius to be a mixture of a silicate and phosphate, the silicate corresponding to (‡ (Mg, Fe)*+‡Al) Si*), which is essentially the formula of Wichtyne

B.B. alone, it is difficultly fusible to a blackish globule. With borax it forms a green glass. Partly soluble in muriatic acid. Becomes reddish on exposure to the

Forms thin layers on trap, near the town of Sordawala in Finland; at Bodenmais in Bavaria, it is associated with magnetic pyrites. It resembles pit-coal in sppearance.


TACRYLYTE. Hyalomelan.—Massive or in plates. No cleavage. H.=6.5. G.=2.5—2.54. Lustre vitreous to greasy. Color velvet-brown—black. Opaque. Fracture small conchoidal.

Composition.—Analysis by Gmelin, of the variety from Vogelsgebirge: Si Ti H1 Fe Ca Mg Na K Mn H&Am 50-22 1-42 17-84 10-27 8-25 3-37 5-18 3-87 0-40 0-50=101-31, 医二性三性性 医二甲甲基甲酰 斯特里 主持 医小线 自然知识

1.3 ment entire with management to a privation of someon plans.

There is because I must not write, and remarked elements or goldstole is attended in the second of the second in the se

LANGE TO SEE THE PART WHEN WE SEE



meri iere 0: I=92 34. 0 : I=39, f: f = 15.6 at I: I = 112.30 at I: N = 132.5 at I: I = 155.6 at I: N =11=17-7. 4:17 over 1=910 40. Levy. H=13-4 6.=335-35. Lustre rit more stumbers. Cour dark greenish-black;

tim solution green in the libertim of the and brown transversely. Fainty transference large tryans, respector faintly subtrans intent. Transper services are entitled.

position.— L. Fr 📆 Admiros L. Argue Berr Johnsch xxii, 205); L L T. Bonnson. Phil Mag unvi. 23 :

<u>S</u> S Ŀ X. Ŧŧ Ŧ (*3 igs. (*3=100-5, Arppa. 6 *6 igs. 1 *26=39-10, Thom 34 4 E4 15 360 153


4-4

Rechang the alumns with the alben, the two axalyses essentially agree; but the numeral requires further investigation. 6 of No. 20155.

N.S. functionally to a black magnetic bead. With borax affords a clear ame-

through product which becomes green in the reducing flame.

Reduction to occurs in medical structure at Armedal in Nerway, associated with epidence and massive garries, and in the Shesland Islan, imbedded in white quarts. It was named after I'm Bahington : it resembles some dark varieties of pyroxens.



In the United States it is said to coat crystals of federace, at Governour, St. Lawrence Ca, N. Y.
Small black polished crystals coating mice slate,
or miraceous gueint, at Athol. Mass., (fig. annexed),
have been referred here by Shepard. The authors measurements give the following approximate angles, O: I=N°-91°, O: I=85°, O: Y=153° 20′, I: F=110° 50′ and 69° 50′, I: Y=129°, I': Y=120° 30'. 0:-1=135° 40'. 0:1=135° 30', 0:1=95° 30', 0:1=


BERYL Emerald. Aquamarine. Smaragd. Emeraude, H. Davidsonite, Richardson. Goshenite, Shepard.

Hexagonal. $0:1=150^{\circ} 3': a=0.499$.

(): ==139° 10° $0:12=116^{\circ}37'$. $I: 33=142^{\circ} 11'$. $(): 2=130^{\circ} 58'.$ $0:22=135^{\circ}4'$.

 $I: 8\frac{4}{7} = 165^{\circ} 30'.$ $I: I = 120^{\circ}.$ (): $2\$ = 130^{\circ} 58'$. $0: I = 90^{\circ}.$

Cleavage: basal imperfect; lateral, indistinct. Ocasionally coarse columnar and large granular.



H.=7.5—8. G.=2.732, emerald, Haidinger; 2.678, apple-green. Lustre vitreous; sometimes resinous. Color pale green, emeraldgreen, passing into light-blue, impure yellow and white. Streak white. Transparent—subtranslucent. Fracture conchoidal, uneven. Brittle.

Composition.—(1Be+1AI) Si²—Silica 66.9, alumina 19.0, glucina 14.1=100. Analyses: 1, Du Menil, (Schw. J. xxxix, 487); 2, Berzelius, (Schw. J. xvi, 265, 277); 3, Klaproth, (Beit. iii, 215); 4, Moberg, (Acta Soc. Sci. Fenn. ii, 81); 5, Schlieper, (Ramm. 2d Supp. 34); 6, Bornträger, (Jahrb. Min. 1851, 185); 7, J. W. Mallet, (Am. J. Sci. [2], xvii, 180):

```
Si
                                                                                                             ₽e
                                                                                         ₩ı
                                 Beryl, 67-00 16-50 1-00 14-50, Ča 0-50=99-50, Du Menil.

68-35 17-60 0-72 18-13, Ta 0-72=100-52, Berzelius.

68-50 15-75 1-00 12-50 & 0-30, Ča 0-25=98-30, Klaproth.

Finland, 67-359 16-465 1-497 12-747, Ta 0-280=98-348, Moberg.

S. Amer. 69-51 14-49 — 15-41, Mg, Ča 1-64=101-05, Schlieper.

Cirschgasse, 66-90 18-15 2-95 12-20=100-20, Bornträger.

oshen, 66-97 17-22 2-03 12-91, Mn tr.=99-13, Mallet.
1. Siberia, Beryl,
        Broddbo, "
3.
       Emerald,
4.
Б.
6.
       Beryl, Hirschgasse, 66 90
                           Goshen,
```

Other analyses: Mallet, (Ramm. 5th Suppl. 66); W. Mayer, (Jahrb. Min. 1851, 185, and Lieb. Kopp, 1851, 779); Müller, (J. f. pr. Ch. lviii, 180).

B.B. alone unchanged or becomes clouded; at a high temperature the edges are rounded, and ultimately a vesicular scoria is formed. Glass with borax, clear and colorless for beryl, a fine green for emerald. Slowly soluble with salt of phosphorus without leaving a siliceous skeleton. A yellowish variety from Broddbo and Finbo yields with soda, traces of tin.

Emerald and beryl are varieties of the same species, the former including the rich green transparent specimens, which owe their color to oxyd of chrome, the latter, those of other colors. Fine emeralds are found in a vein of dolomite, which traverses a hornblende rock at Muzo, north of Santa Fé de Bogota.* A perfect hexagonal crystal from this locality, two inches long, is in the cabinet of the Duke of Devonshire; it measures across its three diameters 2½ in., 2½ in., 1½ in., and weighs 8 oz 18 dwts; owing to flaws, it is but partially fit for jewelry. A more splendid specimen, though somewhat smaller, weighing but 6 oz, is in the possession of Mr. Hope, of London. It cost £500. Emeralds of less beauty, but much

^{*} M. Lewy states that the rock is a black limestone, some parts of which contain fossils.

larger, occur in Siberia. One specimen in the Royal collection measures 144 inches long and 12 broad, and weighs 164 pounds troy; another is 7 inches long and 4 broad, and weighs 6 pounds troy. Mount Zalora, in Upper Egypt, affords a less distinct variety, and was the only locality which was known to the ancients Other localities are Canjargum in Hindostan, and Salzburg, where it is imbedded in

Pliny speaks of the finest beryls as those "qui viriditatem puri maris imitantur,"green like the sea,—and crystals of clear shades of sky-blue, or mountain-green, are hence termed aquamarine. This variety is found in Siberia, Hindostan, and Brazil. In Siberia they occur in the granite district of Nertschinsk, and in the Uralian and Altai ranges of Siberia. They have been obtained exceeding a foot in length, and are commonly striated longitudinally. The most splendid specimen of this variety of which we have any account, belongs to Don Pedro. It approaches in size, and also form, the head of a calf, and exhibits a crystalline structure only on one side; the rest is water-worn. It weighs 225 ounces troy, or more than 18½ pounds. The specimen is transparent, and without a flaw. Less clear crystals of beryl occur at the Mourne mountains, Ireland, county Down; rarely at Cairngorum in Aberdeenshire; at Limoges in France; Finbo and Broddbo in Sweden; Pfitscher-Joch, Tyrol; Bodenmais and Rabenstein in Bavaria, tin mines of Schlackenwald, also in Apetrelia, and alcorders.

Australia, and elsewhere.

Beryls of gigantic dimensions have been found in the United States, at Acworth and Grafton, N. H., and Royalston, Mass. One beryl from Grafton, N. H., weighs 2900 pounds; it is 32 inches through in one direction and 22 in another transverse. and is 4 feet 3 inches long. Another crystal from this locality, according to Prof. Hubbard, measures 45 inches by 24 in its diameters, and a single foot in length, by calculation weighs 1076 lbs., making it in all nearly 2½ tons. At Royalston, one crystal exceeded a foot in length. The smaller crystals are often limpid and a yellowish variety, forms a gem resembling chrysolite; the colors are mostly aquamarine, grass-green, and yellowish-green; one locality is in the southeast part of Royalston, near the school-house, on the land of Mr. Clarke; the best crystals are imbedded in quartz. A still better is situated 4 miles beyond the old one in South Royalston; some crystals of a sky-blue color in white quartz are beauti-South Royalston; some crystals of a sky-blue color in white quartz are beautiful. At Barre, Mass., there is a similar locality, though less remarkable; also at Pearl Hill, in Fitchburg, Goshen, and Chesterfield, Mass. At Compton, N. H., the beryls are as fine as at Royalston. Albany, in Maine, and Norwich, a few miles above Bethel, towards Waterford, afford fine large beryls with green and black tournalines; crystals, often large, are also obtained at Streaked Mountain, with black tournaline and mica; at Bowdoinham and Topham of a pale green or yellowish white color in veins of graphic granite; at Georgetown, Parker's Island, at the mouth of the Kennebec; at Wilmot, N. H.; with modified terminations, (f. 369), at Haddam, Conn., in a feldspar vein in gneiss, on the east side of the river; the crystals are limpid at the extremity for about a twelfth of an inch, as indicated by the dotted line in f. 369: the chrysoberyl locality affords less interesting specimens; also dotted line in f. 369; the chrysoberyl locality affords less interesting specimens; also the Middletown feldspar quarry, and the granite of Chatham, near the cobalt mine. At Monroe, Conn., beryl occurs in a granite vein, and the crystals often consist naturally of several pieces separated by plates of quartz, (f. 194). Crystals, sometimes 10-12 in. long and 1½ in. in diameter, occur with black tourmalines at Leiperville and Chester, Penn., Delaware Co.; also less interesting at Mineral Hill.

The emerald derives its color from the presence of a minute quantity of oxyd of the control of the color from the presence and heavyl from oxyd of iron.

chrome, and beryl from oxyd of iron.

The species Dioptase and Pyrosmalite are homeomorphous with Beryl, and have the same oxygen ratio between the bases and silica, if the water and chlorine be

ALTERED FORMS.—Kaolin, Mica, Limonite and Quartz, occur as pseudomorphs after Beryl, the last two by substitution, the others by alteration. The change to Kaolin is the same essentially as in feldspar. An altered beryl, from Tirschenreuth afforded H. Müller, (J. f. pr. Chem, lviji, 182), Si 58.8, Xl 24.7, Be 10.2, Fe 2.6, H 25.

371

EUDIALYTE, Stromeyer. Eudyalite, improper orthography.

Rhombohedral. R: R=126° 25′, O: R= 148° 38'; a=0.52793. Observed planes: rhombohedrons 1(R), 4, 1, -8, -2; scalenohedrons, 4², 4³; prism i2. O: 4=112° 18'.

 $i2:4^3=166^\circ 1'$. $0:i2=90^{\circ}.$ $i2:4=143^{\circ}15'$.

O: 2=129° 22'. 4:4=73° 30" Cleavage O, very perfect, R, imperfect. Also massive.

H.=6. G.=2.9036; 2.898, Levy. Lustre Color brownish-red; streak uncolored. Opaque to vitreous. slightly translucent. Fracture subconchoidal or splintery.

Composition.—(1R3+1Zr) Si2=2R3 Si2+Zr Si2, Ramm. Analyses: 1, Pfaff, (Schw. J. xxix, 1); 2, 3, Stromeyer. (Gilb. Ann. lxiii, 379); 4, Rammelsberg, (Pogg. lxiii, 142):

Zr Fe Mn Ca Na 54·10 11·58 7·86 2·93 10·80 11·40, HCl 0·30, H 1·86, Ču 0·92=101·55, Pfaff.

53:33 11:10 6:75 2:06 9:78 13:82, " 1:03, " 1:80=99:68, Stromeyer. 52:48 10:90 6:86 2:57 10:14 13:92, " 1:03, " 1:80=99:71, "

Rammelsberg makes the iron and manganese protoxyd, and thus gives

Zr Fe Mn Ca Na

3, bis. 5248 1080 616 231 1014 1392, Cl 100, ign. 180=9870, Stromeyer. 4. 4992 1688 697 115 1111 1228, K 065, Cl 119, ign. 037=10052, R.

B.B. fuses to a grayish-green scoria or opaque glass. Intumesces and forms a pearl with salt of phosphorus. When pulverized, gelatinizes with acids.

Found at Kangerdluarsuk, in West Greenland, associated with arfvedsonite and sodalite, or imbedded in compact white feldspar. Crystals usually small, but sometimes an inch or more in length. The name alludes to its easy solubility in acids,

from ev, easily, and διαλυω, to dissolve.

III. EULYTINE SECTION.

Oxygen ratio 1: 13.

EULYTINE, Bi Si3. EULYTINE GROUP. Monometric.

LEUCOPHANE (1 Ca2+1 Be)Si2+1 NaF. LEUCOPHANE GROUP. Trimetric!

EULYTINE, Breit. Bismuth Blende. Kieselwismuth. Silicate of Bismuth, Thom.

Monometric: tetrahedral. Usually in minute crystals and edges often rounded, figs. 59, 61. Observed planes, 1, O, 22. Cleavage: dodecahedral, very imperfect. Twins: plane of compostion parallel to a dodecahedral face. Sometimes globular, and columnar, lamellar, or granular.

11.=4/5. G.=5/912-6/006. Lastre resinous or adamantite. Color dark hair-brown, yellowish-gray, grayish-white, and strayyellow. Streak yellowish-gray or uncolored. Subtransparentopaque. Fracture uneven. Rather brittle.

Composition -BiBi, with some phosphate and flaorid of iron, Frankeshein Analysis by Kersten, (Pogg. xxvii, 81):

HF and H 1-01=984 Bi 22.23. P 3-31, Pe 2:40, Ba 0:30,

The loss includes some HP. In a matrice decrepitates, and affords a trace of water. It is fuses to a dark-yellow mass, and gives out incolorous fumes. Fuse And froths on charcoal, staining it yellowish-brown, sometimes with a tinge of green.

Finess readily with sods, to a button, at first greenish-yellow, and them reddies yellow, and finally affords metallic bismuth. With salt of phosphorus, it fuses to s yallow globula, with a silica skeleton, which becomes colorless on cooling.

Found near Schneeberg, Saxony, in quartz, and at Braunsdorf, sear Freiberg.

Atelesite, -- Breithaupt thus names small monoclinic crystals containing bismuth tementring at Schneeberg, with Bismuth Blende; they have a sulphur yellow color and whomantine lustre.

Путев підовіти, Schüler, Girüne Eisenerde). Minute crystalline. H.=6. G.=29.

3. Lustra vitraous, faeble color, green. Streak light green. Brittle; fracture avan to flat conchoidal.

Composition. Analyses by Schüler:-

Bi 18:03 Pe 10:54 P 9-62 XI 14.65 Mn tr. or perhaps a mixture of a silicate of bismuth and iron, and a phosphate of alumina 18 18. grown dark, but infusible; a yellow deposit on the coal. Insoluble is mejela.

In minute crystals and grains, or massive and earthy, at Schneeberg, Johansgeorgenetadt, and Braunsdorf in Saxony.

LEGOTIANE, Kamark, Berz. Jahresbericht, xx and xxi. Leucofanite.

Trimetric, (Descl.) Cleavage: imperfect in three directions inclined to one another at angles of 53\forallow and 36\forallow. Usually masrive and columnar.

11. 3.5 4. (1.=2.974. Lustre vitreous on a cleavage surface. Color pale dirty green to wine-yellow; thin fragments transparent and colorless. Powder white, and strongly phosphorescent, whether heated or struck. Electric when heated. Optically biaxial. (Descl.)

Composition. (1 Ca²+1 Be)Si²+1 Na F=Ca² Si²+Be Si+NaF=Silica 45:3. Hime 28:0, glueina 12:7, sedium 7:7, fluorine 6:3. Analysis by Erdmann, (K. V. Ac H. f. 1840):

Ri 47-82, Ro 11-51, Mn 1-01, Ca 25-00, Na 7-59, K 0-26, F 6-17==99-36.

B.B. fuses to a clear violet glass, which becomes clouded on cooling. With borax fuses easily to an amethystine glass; with salt of phosphorus dissolves except a skeleton of silica. Gives the reaction of fluorine.

Leucophane occurs in syenite with albite, elscolite, and yttrotantalite, on a small rocky islet near the mouth of the Langesundfiord in Norway, where it was found by Famark. It resembles somewhat a light green variety of apatite.

The name leucophane is from λευκος, white, and ψαινω, to appear.

MELINOPHANE, Th. Scheerer, J. f. pr. Chem. lv. 449.

Dimetric or hexagonal; optically uniaxal, Descl. Massive, with a scaly and sometimes foliated structure. Cleavage in one direction. H.=5. G.=30, Richter. Lustre vitreous. Color sulphur, citron, or honey-yellow. Not phosphorescent.

Composition, according to an approximative analysis by R. Richter, (loc cit.):

This analysis gives for the ratio of the oxygen of the protoxyds, peroxyds, and

silics, if we suppose the fluorid as replacing protoxyds, 1\frac{1}{2}: 1: 3.

From the zircon-syenite of Norway, near Fredericksvärn, with elssolite, mica, fluor spar, and magnetic iron. An imperfect crystal in the cabinet of R. P. Greg, Req. gave him M: M'=183°, and edge M: M' replaced by a rough plane, apparently not equally inclined to M and M'. The place of this species in the system is doubtful

IV. GARNET SECTION.

Oxygen ratio for the bases and silica 1:1, varying to 1:2, (Chondrodite), and $1:\frac{4}{3}$, (Scapolite).

1. CHRYSOLITE GROUP .- Trimetric.

I

Mn° Si (Fe, Mg)3 Si, CHRYSOLITE, TEPHROITE, MONTICELLITE, (1 Ca+1Mg)33i, Knebelite, (Fe, Mn)Bi fe ' Si. CHOND BODITE, Mg⁴ Si FAYALITE,

2. PHENACITE GROUP.—Hexagonal. R: R=115°-117°.

WILLEMITE, Źn³ Ši, PHENAGITE, ∄e Si.

GARNET GROUP.—Monometric.

HELVIN, (1Rº+1Be) Si, in which R= GARNET, (1R3+1H)Bi, (Mn, Fe, MnS.)

(1R°+1H)Si. PYROPE,

4. SCAPOLITE GROUP .- Dimetric.

Zr Ši, $(\frac{1}{2}Oa^3+\frac{1}{2}\overline{A}l)\overline{S}i.$ ZIBOON, MEIONITE, (#R°+##)Bi, SCAPOLITE. (*R°+*X1)Si3. IDOCRASE. (表路*十美丑)Si, ! (†B°+‡基1)系i. (1R°+1H)Si. $(\frac{1}{2}R^3 + \frac{1}{2}\overline{A}1)\overline{S}i$, MELLILITE, SABCOLITE,

Dipyre may belong here. Taking 2i of Scapolite as the plane 1, (to which there is no objection), then O:1 in Zircon and the Scapolite Group will equal 137°-189°. Idoerase diverges more widely, giving for the corresponding angle 183° 8'.

5. EPIDOTE GROUP.—Monoclinic.

(+R°++#)Si. (#R*+#丑)Si, Zoisite, EPIDOTE. (計路*十計形)Bi, GADOLINITE, Rº Si. ALLANITE. (₹£°+₹±)Si.

6. AXINITE GROUP.—Triclinic.

(Ca3, B) Bi, (R1, H, B)Si. AXINITE. DANBURITE,

7. IOLITE GROUP.—Trimetic. Oxygen ratio for the bases and silica 1: 1;, as in some Mica, and perhaps not belonging to this section. Related to the Micas in the prismatic angle near 120°.

(}R'+}#)Si²·


CHRYSOLITE. Peridot, H. Olivine, Chusite. Limbelite, Saussure. Krisolith, W. Hyalosiderite. Batrachite, Breit. Glinkite, Romanowski. Monticellite, Brooks.

Trimetric. $I: I=94^{\circ}3'; O: 1\bar{\imath}=128^{\circ}27'; a:b:c=1.2594:1$: 1.0733.


 $O:1\overline{2}=125^{\circ}45'$. $O:1\overline{4}=130^{\circ}27'$.

 $O: 1i=130^{\circ} 27'.$ $i = (ov.i)108^{\circ} 50'.$ $1: 1(mac.)=107^{\circ} 46'.$ $i = (ov.i)108^{\circ} 34'.$ $0:1=120^{\circ}9'$.

 $O: \frac{3}{4} = 114^{\circ} 48'$. $1: 1(br.) = 101^{\circ} 32'$. $O: \frac{1}{4} = 149^{\circ} 36'$. $i_{\overline{2}}: i_{\overline{2}}(ov.i_{\overline{2}}) = 130^{\circ} 2'$. $i\bar{i}: 1\bar{2}=137^{\circ} 22'.$



Observed Planes.



Cleavage: in rather distinct. Massive and compact, or granular; usual in imbedded grains.

H.=6-7. G.=3.33-3.5; 3.441 of chrysolite, Haidinger; 3.33 -3.345, olivine; 3.3514, chrysolite. Lustre vitreous. Color green—commonly olive-green, sometimes brownish, black in some iron chrysolites; rarely white. Streak uncolored. Transparent translucent. Fracture conchoidal.

Chrysolite includes usually the transparent crystals of paler color, while olivine, (so called from the olive-green tint), is applied to imbedded masses or grains of inferior color and clearness.

Composition.—R²Si, in which R may be Mg, Fe, Mn, Ca, alone or in combination. Common chrysolite is usually (Mg, Fe) Si. Analyses: 1, 2, Walmstedt, (K. V. Ac. H. 1824, ii, 359, and Schw. J. xliv, 25); 3, 4, Stromeyer, (Gött, gelehrt. Anz. 1824, 208; Pogg. iv, 193); 5, Walchner, (Schw. J. xxxix, 65); 6, W. v. Beck, (Verh. Russ, Min. Ges. St. Petersb. 1847); 7, Rammelsberg, (Pogg. li, 446); 8, Walmstedt, (ib.); 9, Waltershausen, (Vulk. Gest. 117); 10, Deville, (Et. Geol. Canaries); 11, Domeyko, (Ann. des. M. [4], xiv, 187):

```
Þе
                        8i
                               Йg
                                               ₩ı
                                                      Йn
 1. Iserwiese,
                      41.54
                              50.04
                                       8.66
                                              0.06 0.25=100.55, Walmstedt.
   Mt. Somma,
                      40.08
                              44.22
                                      15.26
                                              0.18
                                                     0.48 = 100.24
                                              0.22\document0.09, Ni 0.32=99.68, Stromeyer.
 3. Orient chrys.
                      8978
                              50.13
                                       9.19
                                              0·19 "0·20, "0·37=99·51, "
2·21 "0·48, K 2·69, Cr. trace, Walchner.
    Vogelsberg,
                      40.09
                              50.49
                                       8.17
 5. Hyalosiderite,
                                     28.49
                      31.63
                              32.40
    Glinkite.
                                                        =100 72, Beck.
 6.
                      39.21
                              44.06
                                      17:45
                                                    Ca 85.45, H 1.27=99.19, Ramm.
    Batrachite.
                      87.69
                              2179
                                       2.99
                                              trace 0.29, Ca trace=100.39, Walmst.
0.64 — Ni 0.20, H 1.04=100.22, Walm.
 8. Pallas meteorite 40.83
                              4774
                                      11.58
 9. Etna,
                              47.27
                      41.01
                                      10.06
10. C. Verdes, Fog. 40:19
                                                     2.27 Ca 5.12=99.85, Deville.
                              8570
                                      15.27
                                              0.80
11. Antuco, Chili, 407
                                                        -=100, Domeyko.
                              39.7
                                      19.6
```

Berzelius detected oxyd of tin in the olivine of the Pallas meteorite, and Rummler a trace of arsenous acid. Other recent analyses: E. E. Schmid, (Pogg. lxxxiv, 51, Atacama); Erdmann (K. V. Ac. H. 1848, 15, Tunaberg).

No. 5, Hyalosiderite is (1Mg+1Fe)²Si, with an excess of Mg Si. It occurs at Kaiserstuhl in yellowish and reddish-brown crystals; H.=5.5. G.=2.875.

Tautolite, Breith. From volcanic rocks near Lake Laach, resembles hyalosiderite. H.=6.5: G.=3.865. Forms trimetric.

Forsterite, (Levy), from Vesuvius, is a white or colorless translucent chrysolite, occurring in small crystals, (Scacchi, Quad. Cryst. 63). Monticellite of Brooke, (Ann. Phil. 1831) is also Chrysolite. It is the peridot blane of Scacchi. Formula (†Ca*+†Mg*)Ši, Scacchi.

Glinkite is greenish chrysolite from a talcose slate, in Perm, Russia, and occurring also in gneiss at Tunaberg with augite and garnet, (Analysis No. 6).

Batrachite, from Rinzoni, Tyrol, has the formula of Monticellite; G.=8 038. Said to have two cleavages meeting at 115° and 65°, and a third diagonal to them.

With the fluxes gives the reaction of iron. Scarcely attacked by muriatic acid, but easily gelatinizes with sulphuric acid. Berzelius says that it also forms a jelly with muriatic. Scacchi's Vesuvian variety is easily attacked by the acids. The iron chrysolites are fusible before the blowpipe; hyalosiderite forms a black magnetic bead. Others are infusible.

Chrysolite is found near Constantinople, at Vesuvius, and the Isle of Bourbon in lavas; imbedded in obsidian, at Real del Montein Mexico; among sand at Expailly in Auvergne, in pale green transparent crystals. Olivine is of frequent occurrence in basalt and lavas. Crystals several inches in length, in greenstone at Unkel, on the Rhine; spheroidal masses at Kapfenstein in Lower Styria; and at Heela and Vesuvius, and various volcanic regions. Olivine is common in the lavas and basalt of the Sandwich and other Pacific Islands. It occurs in imbedded grains, and in masses sometimes several inches through in boulders of coarsely crystallized basalt in Thetford and in Norwich, Vermont.

Crystals of this species are commonly very fragile, and therefore unfit for an ornamental stone. The word chrysolite is derived from χρυσος, gold, and λιθος, stone, in allusion to its color; hyalosiderite is from ταλος, glass, and σιδηρος, iron.

FATALITE, (Iron-chrysolite, Eisenperidot).—Fayalite is a pure iron-chrysolite. Color black, greenish or brownish, sometimes iridescent. Cleavage in two directions at right angles with one another. H.=6.5. G.=4.11-4.14; 4.006, Delesse.

Composition.—Fe³Si≕Silica 29.55, protoxyd of iron 70.45.

Analyses: 1, Klaproth, (Beit. v, 222); 2, Thomson; 3, Delesse, (L'Institut, 1854, p. 52); 4, Gmelin:

```
₩l
                             8;
                                     Fе
                                            М'n
1. Volc. glass,
                            29.50
                                   66 00
                                                   40
                                                          0.25=99.75, Klaproth.
                                                             =100·11, Thomson.
• Mg 0·30=98·41, Delesse.
2. Slavcarrach, Ireland, 29:60
                                   68.73
                                            178
                                                   tr.
                            29.50
                                   63.54
                                            5.07
                                                             - Ču 0·60, FeS 2·77,Gmelin.
  Fayal,
                            24·93
                                   65.84
                                            2.94
                                                   1.84
```

Fuses readily to a black globule which is magnetic. Easily attacked by scids. From the Mourne Mts., Ireland, in Pegmatite; also from volcanic rocks at Fayal. The Obsidians or volcanic glass often approach Fayalite in composition.

24

Iron-chrysolite has been observed in crystals, as a furnace product, near Goalar.

ALTERED FORMS.—Alteration of chrysolite, often takes place through the oxydation of the iron; the mineral becomes brownish or reddish-brown and iridescent It also splits into thin laming as the change goes on, sometimes so as to resemble a mica. A basslt thus changed was once pointed out to the author as a mica slate, although no further change had taken place than that here mentioned. Chusite and Limbelite are chrysolite more or less altered. The process may end in leaving the cavity of the crystal filled with limonite or red oxyd of iron. Under the action of carbonated waters, the iron is often carried off instead of being peroxydized, and also some of the magnesia is removed at the same time; and thus may come serpentine, picrosmine, villarsite, which often retain the crystalline form of chrysolite. A further change may produce steatite and other magnesian species.

TEPHROITE, Breithaupt.

Dimetric? Massive, with cleavage parallel to the sides of a square or rectangular prism; also granular.

H.=5.5-6. G.=4-4.12. Color ash-gray. Streak pale-gray.

Darkens, on exposure, to brown and black.

Composition.—Mn°Si≕Silica 29.8, protoxyd of manganese 70.2. Analyses: 1. Thomson, (Min. i, 514); 2, Rammelsberg, (Pogg. lxii, 145):

Mn 66.60 Ši 29·64 Fe 0.92, Moisture 2.70=99.86, Thomson. 1. Franklin, Fe 2.92=100.46, Rammelsberg. 2. Sparta, 28.66 68.88

B.B. fuses easily to a black scoria. Gelatinizes perfectly in muriatic acid without evolving chlorine.

From Stirling, N. J., with franklinite, and at Sparta. This species has the gene-

ral formula of a chrysolite.

A black silicate of manganese from Klapperud, Dalecarlia, having a submetallic lustre and yellowish-brown streak, afforded Klaproth, (Beit. iv, 137), Si 250, Mn 558, H 13:00=93:8=Mn Si+3H, agreeing with the Tephroite, excepting the water. Klaproth obtained 60 per cent. of Mn Mn, whence the above is deduced by Berzelling.

KNEBELITE.

Massive, with an uneven and cellular surface, and quite hard. G.=3.714. Lustre glistening. Color gray, spotted dirty-white. red, brown, and green. Opaque. Brittle. Fracture subconchoidal.

Composition.—(Fe Mn)² Si, Fe and Mn being in equal proportions. Analysis by Döbereiner, (Schw. J xxi, 49); Silica 32.5, protoxyd of iron 32, protoxyd of manganese 35, and thus appearing to be a ferruginous tephroite. With muriatic acid decomposed, the silica separating. Unaltered alone before the blowpipe. Fusee with borax to a dark olive-green pearl.

Locality unknown. Named by Döbereiner after Major von Knebel.

CHONDRODITE, d'Ohsson. Condrodite, H. Maclurite, Seybert. Cleaveland. Humite, Bournon.

Trimetric; often hemihedral in octahedral planes, producing forms monoclinic in character. $I: I=94^{\circ} 26'$. Crystals of three types.*

^{*} Scacchi in Pogg. Ann. 1851, Ergänz ii, 161. The author adopts a modified view


of these types and their axes. (See Am. J. Sci., [2], xiv, 175).

The numbers given for the planes of these figures on page 59, vol. I, are based on a similar fundamental form, except that the longer lateral axis has twice the length here adopted.

```
Type I, a:b:c=1.4678:1:1.0805; II, 1.5727:1:1.0805; III, 1.4154:1:1.0805.
```

```
I. 0:1i=124^{\circ} 16'. 0:1=116^{\circ} 34'.
                                                  0:1\bar{2}=121^{\circ}44'.
                                                  1\bar{\imath}: 1\bar{\imath} \text{ (bas)}=111^{\circ} 28'.
        O: 31=102° 48'.
                                                  0: \frac{2}{3} = 112^{\circ} 24'.
        0:3i=103^{\circ}47'.
                                                  ix: ix (front)=71° 32′.
  II. O: 1\bar{\imath}=125^{\circ} 27'.
                                                   0:4\bar{2}=98^{\circ}13'.
        0:2=103^{\circ} 8'.
                                                   0:21=108^{\circ}58.
III. O: 1\bar{\imath}=125^{\circ} 14\frac{1}{4}'.
                                                  O: \frac{1}{2} = 119^{\circ} 17'.
        O: 2\bar{\imath} = 109^{\circ} \ 27^{\prime}.
                                                  O: 82 = 94^{\circ} 35'.
        O: 4=97^{\circ} 23'.
                                                  O: \frac{4}{5} = 111^{\circ} 15'.
       O: 4i = 119^{\circ} 47'.
                                                  1i:1i=109° 31'.
       0:4i=100^{\circ}48'.
                                                  1\bar{\imath}: \frac{4}{3}=134^{\circ}\ 23'.
        O: \frac{8}{15}\bar{2} = 140^{\circ} 15^{\circ}.
                                                  \frac{4}{3}: \frac{8}{72}(ov. I)=126° 52'.
```

Fig. 376, left-handed hemihedral; 377, right-handed hemihedral. Observed angles in chondrodite (D): $1\bar{\imath}:1\bar{\imath}=112^{\circ}$ (mean of same



in 3 types of Humite, $112^{\circ}2'$), $1\bar{\imath}:\frac{4}{3}=136^{\circ}$, $1\bar{\imath}:\frac{8}{72}=157^{\circ}$, $\frac{4}{3}:\frac{8}{72}=157^{\circ}$, $I:I(\text{side})=85^{\circ}(85^{\circ}34',\text{ calculated for Humite});$ 4% on edge above it 168°.

Compound crystals parallel to \$\foatsi in the third type, and \$\foatsi in the second, the former sometimes producing stellate forms of six crystals, each hemihedral. Cleavage indistinct. Usually in imbedded grains or masses of a somewhat granular texture; sometimes in

small implanted crystals.

H.=6-6-5. G.=3·118, from New Jersey, Thomson; 3·199, Finland, Haidinger; 3·234, white crystal, Type I; 3·199, brown of Type III; 3·186, yellowish, Type III; 3·177, yellow of Type II; Scacchi. Lustre vitreous—resinous. Color white, yellow, pale yellow or brown; sometimes red, apple-green, black, gray. Streak white, or slightly yellowish or grayish. Transparent—subtranslucent. Fracture subconchoidal—uneven.

Composition.—Mg* Si, with part of the oxygen replaced by fluorine, or 1 Mg* Si, with $\frac{1}{12}$ 4(Mg F, Si F*) in chondrodite, $\frac{1}{18}$ in Type II for humite, $\frac{1}{27}$ in Type II, $\frac{1}{36}$ in Type III, Rammelsberg. Analyses: 1, Seybert, (Am. J. Sci., v, 336); 2.3, 4, Rammelsberg, (Pogg. liii, 180, and 1st Supp. 38); 5, W. Fisher, (Am. J. Sci., [2], ix, 85); 6, 7, 8, Rammelsberg, (Pogg. lxxxvi, 413):

		Si	Mg	Fe	Fe	Ė
1.	New Jersey,	32.66	54.00	_	2.33	- HF 4.09, H 1.0, K 2:11, 8
2.	" yellow,	33.06	55.46	3.65	_	7.60= 99.77, Ramm.
3.	Pargas, yellow,	33.10	56.61	2.35	-	8.69=100.75, Ramm.
4.	" gray,	33.19	54.50	6.75	_	9.69=104.13, Ramm.
	New Jersey, red,	33'35	53.05	5.20	-	7.60= 99.50, W. Fisher.
6.	Humite, type 1,	34.80	60.08	2.40		8.47=100.75, Ramm.
7.	" type 2,	33-26	57.92	2:30	Ca 074	5.04 Al 1.06=100.32, Ramm
8.	" type 3,	36.67	56.83	1.67	-	2.61= 97.78, Ramm.

B.B. on charcoal infusible, but becomes paler in varieties containing little iron, sometimes showing traces of fusion on the edges. With borax dissolves slowly but perfectly to a transparent glass slightly tinged by iron; if the glass is saturated it becomes cloudy by flaming. With salt of phosphorus in the open tube, affords fluorine.

Chondrodite occurs mostly in granular limestone. It is found near Abō, in the parish of Pargas in Finland, and at Aker and Gulsjō in Sweden; at Taberg in Wermland; in Saxony; on Loch Ness in Scotland; at Achmatowsk in the Ural, along with perofskite, and in the mines of Schischimsk with red aparite. The humite occurs at Somma, in ejected masses of a kind of granite rock, along with

white olivine, mica, and magnetite.

Abundant in the counties of Sussex, N. J., and Orange, N. Y., where it is associated with spinel, and occasionally with pyroxene and corundum. At Bryam, orange and straw-colored chondrodite, and also a variety nearly black, occurs with spinel; at Sparta, a fine locality of honey-yellow chondrodite; a mile to the north of Sparta is the best locality of this mineral in New Jersey. It also occurs at Vernon, Lockwood, and Franklin. Chondrodite is abundant in Warwick, Monroe, Cornwall, near Greenwood Furnace, and at Two Ponds, and elsewhere in Orange Co., N. Y. Fine specimens may be obtained on the land of Mr. Houston, near Edenville. It is obtained also at Chelmsford, Mass., along with scapolite; in Harvy's quarry near Chaddaford, Pa., of yellow and orange colors and abundant. It occurs sparingly on the bank of Laidlaw lake in Rossic, N. Y.

Abundant in limestone at S. Crosby, Canada West, St. Jerome, St. Adèle, Gres-

ville, etc.

The name chondrodite is from Χονόρος, a grain, alluding to its granular structure.

ALTERED FORMS.—Chondrodite altered to Serpentine, has been observed at Sparts,

N. J., with spinel and mica.

378

R

20

379

12

WILLEMITE, Levy, Ann. d. Mines, 4th ser. iv. 513. Siliceous Oxyd of Zinc, L. Vanuxem and W. H. Keating, Jour. Acad. Nat. Sci. Philad. 1824, iv, 8. Williamsite, Wilhelmite. Hebetine. Anhydrous Silicate of Zinc. Troostite, Shepard.

Rhombohedral. $R: R=115^{\circ}, O: R=141^{\circ}$ 39½'; a=0.685. Observed planes in crystals from New Jersey, $R, \frac{1}{2}, i2$; in those of Moresnet $\frac{3}{4}, I, O$. $I: \frac{3}{4}=120^{\circ}$ 7', $\frac{1}{2}: \frac{1}{2}=142^{\circ}$ 52', $\frac{3}{4}: \frac{3}{4}=128^{\circ}$ 30', Levy, (127°33', from R: R in the N. J. crystal). Cleavage: lateral distinct; basal also distinct. Also in grains or massive.

H.=5.5. G.=3.935, Moresnet, Thomson; 4.16—4.18, ib., Levy; 3.89—4, N. Jersey, Vanuxem and Keating; 4.02, ib., Hermann; 3.98, ib. in powder, Wurtz. Lustre vitreo-resinous, rather weak. Color whitish or greenish-yellow, when purest; flesh-red, grayish-white, yellowish-brown; often dark-brown when impure. Streak

brown; often dark-brown when impure. Streak uncolored. Transparent to opaque. Brittle. Fracture conchoidal.

Composition.—Zn°Si—Silica 72.85, oxyd of zinc 27.15. Analyses: 1, 2, Vanuxem and Keating, (loc. cit.); 3, Hermann, J. f. pr. Chem. xlvii, 11); 4, Thomson, (Min. i, 545); 5, Levy, (Ann. d. M. [4], iv, 515); Rosengarten, (Ramm. 3d Supp. 65); H. Wurtz, (Rep. Amer. Assoc. iv, 147):

1. Stirling, 25·44 68·06, Fe and Mn 6·50=100·00, Vanuxem and Keating.
2. "25·00 71·33, "0·67 "2·66=99·66, Vanuxem and Keating.
3. "26·80 60·07, Mn 9·22, Mg 2·91, Fe trace, ign. 1·00=100, Hermn.
4. Moresnet, 26·97 68·77, Fe 1·48, Al 0·66, ib. and trace Zn, Fe 0·78, H 1·25
5. "27·05 68·40, "0·75, ign. 0·30=96·50, Levy. [=99·91, Thom.
6. Upper Silesia, 27·34 70·82, Fe, 1·81=99·97, Rosengarten.
7. Stirling, 27·91 59·93, Mn 3·73, Fe 5·35, Mg 1·66, Ča 1·60=100·18, W.

Other analyses, A. Delesse, Ann. d. M. [4], x, 213. Affords no water in a matrass. B.B. decrepitates and becomes opaque, but does not fuse, or only on the edges to a white enamel. With borax or salt of phosphorus, a transparent white globule, containing a cloud of silica. In powder gelatinizes easily in concentrated muriatic acid.

From Moresnet, in crystals and massive, the crystals but two or three millimeters long, and one thick. In New Jersey it occurs in large stout crystals at Stirling Hill, and also sparingly at Franklin.

This species was first correctly described and analyzed by Vanuxem and Keating.

PHENACITE. Phenakit, Nordenskiöld, K. V. Ac. H. 1823, 160, Pogg. xxxi, 57.

Rhombohedral; often hemihedral. $R: R=116^{\circ}$ 40', $O: R=142^{\circ}$ 41'; a=0.66. Observed planes: rhombohedrons, $R, -2, -1, -\frac{1}{2}$; scalenohedrons, $1^{2}, 1^{3}, -2^{2}, \frac{2}{3}$ (beveling terminal edge of R); pyramids $\frac{2}{3}$ 2, $\frac{4}{3}$ 2; prisms, $I, i2, i\frac{3}{2}$.

 $R: I=127^{\circ} \ 19'.$ $\frac{2}{3}2: i2=113^{\circ} \ 45'.$ $R: i2=121^{\circ} \ 40'.$ $\frac{1}{2}: \frac{1}{2}=144^{\circ} \ 4'.$ $2: 2=87^{\circ} \ 12'.$

Cleavage: R, and i2, imperfect. Twins: face of composition I.

H.=8. G.=2.969. Lustre vitreous. Colorless; also, bright wine-yellow, inclining to red. Transparent—opaque. Fracture similar to that of quartz.

Composition.—Be Si=Silica 54.3, glucina 45.7=100. Analyses: 1, Hartwall, (Pogg. xxxi, 57); 2, Bischof, (Pogg. xxxiv, 525):

1. Ural, Si 25·14 Be 44·47 Al and Mg trace=99·61, Hartwall.
2. Framont, 54·400 45·567 Ca and Mg 0·96=100·068, Bischof.

B.B. alone remains unaltered; with borax fuses with extreme slowness, unless pulverized, to a transparent glass. With soda affords a white enamel; with more, intumesces and becomes infusible. Dull blue with cobalt solution.


Occurs with emerald in mica slate, in Perm, 85 wersts from Katherinenberg, in

Occurs with emerald in mica slate, in Perm, 85 wersts from Katherinenberg, in the Ilmen mountains, Siberia, with topaz and green feldspar; also in highly modified crystals with quartz, in the brown iron ore of Framont, in Alsace. Named from ofraf, a deceiver, in allusion to its having been mistaken for quartz.

GARNET. Melanite. Pyrope. Grossularite. Topazolite. Almandine. Aplome. Essonite. Cinnamon stone. Greenlandite. Pyreneite. Colophonite. Allochroite. Granat. Ouvarovite or Uwarowite, Hess. Rothoffkit. Pirop. Kolophonit. Kaneelstein. Romanzovit, Nordenskiöld. Braunsteinkiesel, W. Grenat, H. Carbunculus. Polyadelphite, Thom.

Monometric: Observed planes: I, 22, $\frac{4}{3}$, $\frac{4}{3}$, $\frac{3}{2}$, $\frac{44}{3}$, i2, O. Figs. 14 and 39, common; also 43, 17, 43 with planes i2, and 380, 381.





Cleavage: dodecahedral, sometimes distinct. Twins: face of composition, octahedral. Also massive; granular, coarse or fine, and sometimes friable; lamellar, lamellæ thick and bent.

H.=6.5—7.5. G.=3.15—4.3, 3.504, a white lime-garnet, anal. 10. Lustre vitreous—resinous. Color red, brown, yellow, white, green, black; some red and green colors often bright. Streak white. Transparent—subtranslucent. Fracture subconchoidal, uneven.

Garnet is a silicate of different bases—alumina, lime, magnesia, oxyds of iron and manganese, with sometimes oxyd of chrome. It has been divided into aix subspecies.

I. Consisting of silicates of alumina and lime—alumina-lime garnet,—including cinnamon stone or essonite.

II. Containing alumina and magnesia,—alumina-magnesia garnet.

III. Consisting of silicates of alumina and iron—alumina-iron garnet—including almandine or precious garnet, with common garnet and colophonite in part.

IV. Consisting of alumina and manganese-alumina-manganese garnet-or manganesian garnet.

V. Consisting of silicates of iron and lime-iron-lims garnet-including allochroite, aplome, melanite and common garnet in part.

VI. Containing lime and chromic oxyd—lime-chrome garnet.

But these compounds pass into one another by imperceptible shades, as the following analyses show.

Composition.—R° Si+H Si=(1R°+1H) Si. Analyses: 1, Arfvedson, (K. V. Ac. H. 1822, 87); 2, C. Gmelin, (Jahresb. v, 224); 3, 4, Klaproth, (Beit. iv, 319, v, 138); 5, T. Wachtmeister, (K. V. Ac. H. 1823); 6, 7, Karsten, (Karst. Arch. f. Min. iv, 388); 8, T. Wachtmeister, (loc. cit.); 9, Nordenskiöld, (Schw. J. xxxi, 380); 10, t Croft, (G. Rose, Reise n. d. Ural, 132).

11, T. Wachtmeister, (loc. cit.); 12, Hisinger, (Schw. xxi, 258); 13, 14, Kobell, (ib. lxiv, 283); 15-17, Karsten, (loc. cit.); 17-20, T. Watchmeister, (loc. cit.); 21, Klaproth, (Beit. ii, 22, v, 131); 22, W. Watchtmeister, (Jahresb. xxv, 364); 25, Bahr, (Jahresb. xxv, 364); 24, A. Besnard, (Lieb. u. Kopp Jahresb. 1849, 745); 25, 26, Mallet, (J. Dubl. Geol. Soc. and Rammelsberg's 5th Supp. 125.)

27, H. Seybert, (Am. J. Sci. vi, 155, 1823); 28, Rammelsberg, (J. f. pr. Chem. lv. 487); 29, d'Ohsson, (Schw. J. xxx, 346); 30, Hisinger, (Jahresb. ii, 101); 31, Seybert, (Am. J. Sci. v, 118, where iron is made protoxyd); 32, Karsten, (loc. cit.); 33, 34, Bredberg, (K. V. Ac. H. 1822, i, 63); 35, Bucholz, (Scheerer's N. J. iv, 172); 36—41, Watchtmeister, (loc. cit.); 42, Thomson, (Ann. Lyc. N. York, 1829, iii, 9); 43, Vauquelin, (Jour. de Phys. Ann. viii, L. 94); 44, Klaproth, (Beit. v, 168, where the iron is made protoxyd); 45, Karsten, (loc. cit.); 46, Ebelmen, (Ann. des Mines, [4], vii, 19); 47, W. Fisher, (Am. J. Sci. [2], ix, 84); 48, Bahr (J. f. pr. Chem. liii, 312); 49, Weber, (Ramm. 5th Suppl., 193); 50, Baumann, (ib.); 51, Komonen, (Verh. min. Ges. St. Petersb. xxiii, 291); 52, Erdmann, (Jahresb. xxiii, 291);

I. Lime-Garnet.—Grossular.—Ca*Si+AlSi=(\(\frac{1}{2}\)Ca*+\(\frac{1}{2}\)H]Si=Silica 40'1, alumina 22'7, lime 37'2. Color pale greenish, clear red and reddish-orange, cinnamon color. G.=3'43-3'73. B.B. fuses to a glass or enamel slightly greenish; in powder, soluble in concentrated muriatic acid. Cinnamon stone, essonite, grossular, wiluite, romanzovite, topazolite, and succinite are names of varieties. Grossular or wiluite has a greenish color; G.=3'71. Succinite has a mamber color, to when the name alluder. Thereofits has a topozy color. Remanzant in the property of the color of th alludes. Topazolite has a topaz color. Romanzovite is brownish. Cinnamon stone or essonite (Kaneelstein, Germ.) has a clear cinnamon brown shade; G.=3.5-3.6.

	Bi	Æl	₽e	Ѓе	Йn	Мg	Ċa
 Malsjö, Cin. 	41.87	20.57	3.93		0.	89 Ŭ	88.94=100.70, Arfved.
2. Ceylon, "	40.01	23.00	8.67				30.57,K0.59,ign.0.33,G.
8. " "	38.80	21.20	6.20				31 25=97 75,Klaproth.
4. Wilui, Gross.	44.00	8.20	12.00		trace		33 50=98, Klaproth.
5. " "	40.55	20.10	5.00		0.48		84.86=100.99, Wacht.
6. " "	$88 \cdot 25$	19:35	7:38		0.20	2.40	31.75=99.58, Karsten.
7. St. Gothard, Cin.	37.82	1970	5.95	—	0.15	4.15	81.85=99.12, Karsten.
8. Tellemark, wh.	39.60	21.20		2.00	8.12		82·30=98·25, Wacht.
9. Romanzovite,	41.21	24 08	7.02		0.	92	24 76,ign. & loss 1 98, N.
10. Urals, white.	36.86	24.19					87·15=98·10, Croft.

II. Magnesia-Garnet.—(Mg, Fe)*Si+Xl Si=(1(Mg, Fe)*+1Xl)Si. Color deep coalblack. G.=3·157. Lustre somewhat resinous. B.B. easily fusible, intumescing and forming a dark grayish-green globule, which is not magnetic.

42.45 22.47 - 9.29 6.27 13.43 6.53=100.44, Wacht. 11. Arendal,

III. Iron-Garnet, or Almandine. Fc Si+AlSi=(1Fc+1Al)Si=Silica 36.3, alumina 20.5, protoxyd of iron 43.2.—Common Garnet. Precious Garnet.—Dark red, brownish-red to black. Allochroite is fine grained massive, of a dark dingy color. Precious garnet is deep red and translucent or transparent. Common garnet is dingy red. G. of these varieties 3.7—1.21. B.B. fuse rather easily with an iron reaction.

```
Mg
                                       X1
                                                                Mn
                                                                                 Ca
                                                       89.68
                                                                                -=100.80, Hising
5.76=100.04, Kobell
 12. Fahlun, Almand. 39.66 19.66
                                                                1.80
                                               6.00
                                                      27.28
                                                               0.80
 13. Zillerthal, bn.
                             39.12
                                      21:08
 14. Hungary, prec.
15. Zillerthal, "
                                                       32.70
                             40.56
                                      20.61
                                               5.00
                                                               1.47
                                                                                 -= 100.34, Kobell
                             39.62
                                      19:30
                                                       34.05
                                                                0.85
                                                                        2.00
                                                                                3.28=99.10, Karsten.
                                                                0-30 10-15 0-36=97-34, Karsten.

0-46 9-93 3-51=99-20, Karsten.

6-69 — —=101-17, Wacht.

5-49 — 1-07=101-79, Wacht.

1-74 — 5-78=101-20, Wacht.
 16. Ohlapian,
                             37.15
                                     18.08
                                                       31.30
 17. Greenland,
                             39.85
                                      20.60
                                                       24.85
 18. Engsö, dull red,
19. N. York, "
                             40.60
                                     19.95
                                                       33.93
                                      19.15
                                                       33.57
                             42.51
 20. Norway,
                                      18.04
                             52.11
                                                       23.54
                                                                                21. Oriental,
                             35.75
                                      27.25
                                                       32.33
                                                                0.25
 22. Garpenberg,
                             39.42
                                      28.28
                                                       24.82
                                                                7.51
                                                                        3.69
23. Brena, Westm.
                             37.16
                                      19.30
                                                       37.65
                                                                3.19
                                                                        2.03

    Albernreit, bnh-r. 38.76
    Wicklow, black, 35.77
    Killiney, brown, 37.80

                                                                                -=102·19, Bern.
-=98·73, Mallet.
                                                       32.05
                                      21.00
                                                                6:43
                                                                        3.95
                                      19.85
                                                       38.07
                                                                5.04
                                                                        4.46 1.53=99.75, Mallet
                                                       3843
                            37.80 21.13
```

IV. Manyanese-Garnet, Spessartine, Beud.—(1/Mn³+1/X1)Si. Brownish-red. BR gives the reaction of manganese. G.=3.7—1.2.

	Si	X 1	Рe	Мn
27. Haddam, Ct.	35.83	18.06	14.93	30'96=99'78, Seyb. G.=1'128
28. "	36.16	19.76	11.10	32.18, Ca 0.58, Mg 0.22, Ramm
29. Broddbo.	39.00	14:30	15:44	27.90, Sn 1=97.64, d'Ohsson,

V. Iron-Lime Garnet—Melanite, Pyreneite.—Ča°Ši+FeŠi=(‡Ča²+‡Fe)Ši. Dark red, brownish-black, black; either dull or shining. Sometimes with a resince lustre, then called colophonite; G. of Willsboro, 3°896, Seybert. Melanite has a velvet black color. Pyreneite is black or grayish-black, with often a submetalle lustre. G. of these varieties 3°6—4°0. Aplone has the faces striated parallel to the shorter diagonal, and is brown or orange brown, with G.—3°44.

	Si	Æl	Fe	řе	Mn	Mg	Ča
30. Westmanland,	37.55	-	31-35	-	470	-	26 74=100 34, His
31. Willsboro', coloph.	38.00	6.00	28.06		-	-	29.00=101.06, Sey.
32. Schwarzenberg, gn.	36.85	4.05	25.35	-	0.95	-	32.32=99.52, Kara
83. Sala,	36.62	7.58	22.18	-	-	1.95	31.80=100-08,Bred.
34. "	36.73	2.78	25.83	-	1	12.44	21 79=99-57, Bred
35. Thuringia, brown,	34.00	2.00	27.84	_	3.12	-	30-75, H, Cu 4-25, B
36. Langbanshytta, yw.	35.10	-	29.10	-	7.08	-	26 91, K 0 98=99 17.
To the same of the							Wacht.
37. Altenau, Aplome,	35.64	-	30.00	-	3.02	-	29-21, K 2-35, Wacht
38. Hesselkulla, bn.	37.99	2.71	28.53	-	1.62	-	30·74=100·59, W.
39. " gn.	38.13	7.32	19.42	-	3.30	1	31.65=99.82, W.
40. Arendal, bnh-bk.	40.20	6.95	20.50	2000	4.00	-	29.48=101.13, W.
41. Vesuvius, bn.	38.83	13.45	10.95	3.85	1:40	-	31-66=100-94, W.
42. Franklin, N. J. gn.	33.72	7.97	17.64	-	1670	-	22.88=98.92, Thom.
43. Frascati, black,	34.00	6.4	25.5	-	-	-	33-0=98-9, Vanq. [K
44. " black,	35.20	6.00	26.00	-	-	-	32.50, Mn0.4=100.4,
45. " black,	34.60	4.55	28.15	-	-	0.62	31 80=99 75, Kare
46. Beaujeu, black,	36.45	2.06	29.48	-	0.58	0.06	30.76, ign. 0.96, Eh.
47. Franconia, N.H. bk.	38.85	-	28.12	-	-	-	32.00=99.00, Fisher.
48. Gustafsberg,G=3.6,		11.18	15'66	4.97	0.13	trace	30·28=100·02,Bahr.
49. Polyadelphite,	34.83	1.12	28-73	-	8.82	1.42	24.05=98.97, Web.
50. "	85.47	3.10	28.55	-	5.41	2.13	26.74=101.40, Bau.

VI. Lime-Chrome Garnet—Ouvarovite—Ĉa®Si+(Ĉr, Æl)Si=(‡Ĉa®+‡ (Ĉr, Æl)Si. Color emerald green. G.=34184. H.=7·5. B.B. alone infusible; a clear chromegreen glass with borax.

51. Bissersk, 37·11 5·88 — 22·54 2·44 1·10 30·34, Ĥ 1·01=100·42, K. 52. " 36·93 5·68 1·96 21·84 — 1·54 31·66, Ču trace=39·58, E

Polyadelphite of Thomson (anal. 49, 50) is a brownish-yellow garnet from the Franklin Furnace, New Jersey.

Garnet occurs imbedded in mica slate, granite, and gneiss, and occasionally in

limestone, chlorite slate, serpentine, and lava.

The precious garnet occurs in Ceylon, Greenland, and Brazil. Common garnet is met with in dodecahedrons from three to four inches in diameter, at Fahlun in Sweden, Arendal and Kongsberg in Norway, and the Zillerthal; abundant smaller crystals in mica slate, in the Island of Mull, in Perth and Inverness, Shetland; green at Schwarzenberg in Saxony. The magnesia alumina garnet occurs at Arendal with calc spar; Melanite in the Vesuvian lavas, and also near Rome; Grossularite near the Wilui River in Siberia, etc. Cinnamon stone in masses of considerable size in Ceylon, at Malsjö in Wermland, and at St. Gothard; Romanzovite, a similar variety, at Kimito, Finland; Aplome on the banks of the river Lena in Siberia, and at Schwarzenberg in Saxony; Ouvarovite in emenald-green dodecahedrons, at Bissersk in Russia, with chromic iron. Other localities as above.

In New Hampshire at Hanover, small clear crystals in syenitic gneiss; blood-red dodecahedrons at Franconia, in geodes in massive garnet, with cale spar and magnetic iron; at Haverhill, in chlorite, some 1½ in. in diameter; at Unity, on the estate of J. Neal, with actinolite and magnetic iron, and at Lisbon, near Mink Pond, in mica slate with staurotide; at Grafton, ½ to 1 in. in diameter. In Massachusetts, at Carlisle, geodes of transparent cinnamon-brown crystals similar to figure 43, with scapolite in limestone; at Boxborough, in similar but less remarkable specimens; also in gneiss at Brookfield and Brimfield; massive with epidote, at Newbury, and in crystals at Bedford, Chesterfield, with the Cummington kyanite, and at the beryl locality of Barre. In Maine, beautiful yellow crystals or cinnamon stone (with idocrase) at Parsonsfield, Phippsburg, and Rumford; manganesian garnet at Phippsburg, as well as the finest yellow garnet in Maine; in mica slate near the bridge at Windham, with staurotide; in granite veins at Streaked Mountain, along with beryl; in large reddish-brown crystals at Buckfield, on the estates of Mr. Waterman and Mr. Lowe; the best red garnets in Maine, occur at Brunswick. In Vermont, at New Fane, in large crystals in chlorite slate; also at Cabot and Cavendish. In Connecticut, polished trapezohedrons, ½—1 in. in diameter, in mica slate, at Reading and Monroe; at Haddam, large brittle trapezohedrons of manganesian garnet, often 2 in.through, with chrysoberyl; at Lyme, large blackish brown crystals in limestone. In New York, in mica slate, in Dover, Duchess Co., small; at Roger's Rock, crystallized and massive, and colophonite of yellow, brown, and red colors, abundant; brown crystals at Crown Point, Essex Co.; a cinnamon variety, crystallized and massive, at Amity; on the Croton aqueduct, near Yonkers, in small rounded crystals, and a beautiful massive variety—the latter, when polished, forms a beautiful gem. In New Jersey, at Franklin, black, brown, yellow, red, and green dode-cahedral garn

The cinnamon stone from Ceylon and the precious garnet are used as gems when large, finely colored, and transparent. The stone is cut quite thin, on account of the depth of color, with a pavilion cut below and a broad table above bordered with small facets. An octagonal garnet measuring 8½ lines by 6½ has sold for near

\$700. Pulverized garnet is sometimes employed as a substitute for emery.

The garnet was, in part, the carbunculus of the ancients, a term probably applied also to the spinel and Oriental ruby. The Alabandic carbuncles of Pliny were so called because cut and polished at Alabanda. Hence the name Almandine, now in use. Pliny describes vessels of the capacity of a pint, formed from carbuncles, "non claros ac plerumque sordidos ac semper fulgoris horridi," devoid of lustre and beauty of color, which probably were large common garnets. The garnet is supposed also to have been the hyacinth of the ancients.

Authoric Poles—Party of Colors of the Colors of the Colors English Background for agency of the colors of the Colo ine pro-

🗗 is dan e Malia e a gazte e

The second of t

and the second second

Monte de la composition della composition della

The second of th

W. 34.

2 y --The state of the second TE- 125- ---

AMPERIES AS - Land Sec.

Bank Allegar (Corp. Balance Company) = :-

G. Rose writes the formula (Mn, Fe)³ Si³+Be Si+Mn S, Mn O. If in this formula Mn S be considered as replacing a portion of protoxyd, the oxygen ratio for the bases and silica is 8:9. The analyses correspond as well to the ratio 9:9=1:1, which is the garnet ratio; the formula may then be (\$\frac{1}{8}^3 + \frac{1}{18} \text{e}) \text{Si} or 2\frac{1}{8}^3 \text{Si} + \frac{1}{18} \text{Si}, which (if \$1\frac{1}{8} = \frac{4}{18} \text{Mn S} + \frac{3}{18} \text{Fe} + \frac{1}{18} \text{Mn}) = \text{Silica 34:1, glucina 9:6, sulphuret of manganese 14:6, protoxyd of manganese 32.7, protoxyd of iron, 9:0=100.

B.B. on charcoal fuses with intumescence in the reducing flame, to a yellow opaque globule. With borax gives the reaction of manganese. With muriatic acid evolves

Subplue with borax gives the reaction of manganese. With muriatic acid evolves sulphuretted hydrogen, and affords a jelly of silica.

Occurs in gneiss at Schwarzenberg in Saxony, associated with garnet, quarts, fluor, and calc spar; at Breitenbrunn, Saxony; also at Hortekulle, near Modum, in Morway.

It was named by Werner in allusion to its yellow color, from \$\text{\$\t the sun.

ZIRCON, W. Hyacinth. Jargon. Zirconite. Silicate of Zirconia. Erdmannite. Ostranite, Breithaupt. Calyptolite, Shepard.


Dimetric. $0:1i=147^{\circ} 21'; a=0.6407$. Observed planes as in £ 387, with also planes 2 and 3.

 $I: 1=132^{\circ} 10'$. $ii: 1=118^{\circ} 20'$. $ii: 44=155^{\circ} 8'$.

ii: 1i=122° 39′. 1i: 1i (pyr.)=135° 11′. $I: 2=151^{\circ} 6'$.

 $I: 3=159^{\circ} 48'$. $ii: 33=148^{\circ} 17'$. $1:1 (pyr.)=123^{\circ} 19'$.

Cleavage: I imperfect; 1, less distinct. Also in irregular forms and grains.



H.=7.5. G.=4.0—4.75; 4.505, Haidinger; 4.072 and 4.222, near Stockholm, Svanberg; 4.599 and 4.610, Ilmen, ib.; 4.453, Ceylon, ib.; 4.681, Thomson, Svanberg; 4.721, Lowry; 4.03 from Stockholm. Lustre more or less perfectly adamantine. Color red, Streak uncolored. Transparent brown, yellow, gray, white. subtranslucent. Fracture conchoidal, and brilliant.

Composition.—ZrŠi:—Silica 33.2, zirconia 66.8=100, the zirconia, being partly the earth noria according to Svanberg. Analyses: 1, Berzelius, (K. V. Ac. H. 1824); 2, Vanuxem, (J. Acad. Sci. Philad. iii, 59); 3, W. Gibbs, (Pogg. lxxi, 559); 4, Henneberg, (J. f. pr. Chem. xxxviii, 508); 5, T. S. Hunt, (Am. J. Sci. [2], xii, 214); 6, C. M. Wetherill, (Trans. Amer. Phil. Soc. x, 346, and Am. J. Sci. xv, 443):

Si Zr Expailly, N. Carolina; G.=4.453, 33.48 67.16 32.08 67.07 3. Litchfield, Me. G.=4.7, 35.26 4. G.=4.615-4.71, 33.85 0.79 undecomp. 0.29=99.74, Gibbs. 1.55 Ca 0.88=101.09, Henneberg. 63.33 64.81 5. Grenville, G .= 4.625-4.602, 33.7 66:3 - =101 0, Hunt. 6. Reading, Pa., G .= 4.595, 34.07 63.50 2.02, H 0.50=100.09, Wetherill.

Not acted on by the acids, excepting by sulphuric after long digestion.

B.B. loses color, but is infusible alone, and also with carbonate of soda and salted phosphorus. With borax melts with difficulty to a diaphanous glass, which with more of the flux is opaque. Klaproth discovered the earth zirconia in this species in 1789.

Hyacinth includes the bright colored varieties; Zirconite the grayish or brownish, frequently rough or opaque. The variety from Ceylon, which is colorless, or has a smoky-tinge, and is therefore sold for inferior diamonds, is sometimes called jarges. Hyacinth occurs in the sand and alluvial deposits of certain rivers in Ceylon; at Expailly near Le Puy, France; at Ohlapian in Transylvania; Pfitsch in the Tyrel (1: 1=123° 25'. Kobell); at Bilin, in Bohemia; Sebnitz in Saxony; occasionally in volcanic tufa in Auvergne; also in Greenland; in the zircon syenite of Frederick-värn in Norway; near Brevig, sometimes called Erdmannite, containing Si 3243, Zr (with some Fe and Mn) 65'97, ign. 0'70, Berlin, Pogg, lxxxviii, 162; at Miak, in the Urals; in the iron mines of Arendal; also in Scotland, at Scalpay in Harris, and in the granite of Criffel in Kircudbrightshire; at Vesuvius with ryacolite, in white and blue octahedrons; at Santa Rosa, (Antioquia), New Grenada, in small colorless crystals.

small colorless crystals.

In Buncombe Co., N. C., on the road from the Saluda Gap to Asheville, upon the first elevation after passing Green river, crystals are found loose in the soil, and inbedded in feldspar; in the sands of the gold washings of McDowall Co., N. C., (f 386). In New York, cinnamon-red, at Hall's mine in Moriah, Essex Co., in a veind sool. In New York, chinamon-red, at that's mine in Morian, Essex Co., in a vents quartz; near the outlet of Two Ponds, Orange Co., with scapolite, pyroxens, and sphene, in crystals sometimes 1 in. in length; on Deer Hill, a mile southeast of Carterbury, in the same Co., crystals abundant of a deep brownish-red or black color, and occasionally 1½ in. in length; chocolate-brown crystals in Warwick, at the southern base of Mount Eve, in limestone and scapolite; near Amity, and also in Monroe and Cornwall, at several localities, of white, reddish-brown, clove-brown, and black colors at Diana in Levis Co. in leave however are the contraction. Monroe and Cornwall, at several localities, of white, reddish-brown, clove-brown, and black colors; at Diana in Lewis Co., in large brown crystals sometimes 2 in long, with sphene and scapolite, but rare. In St. Lawrence Co., with apatite at Robinson's in the town of Hammond, near De Long's Mills; some of the crystals are 1½ in. long, and ½ inch wide, and they sometimes contain a nucleus of carbonate of lime. Crystals are found also at Rossie, (form I, 1, 3), at Johnsburg, in Warren Co., in New Jersey at Franklin, and in gneiss at Trenton; at Middlebury, Vt.; at Litchfield, Me.; near Reading, Pa., in large crystals in magnetic iron ore; in taleose slate at Easton, Pa.; at Grenville, St. Jerome and Mille Isles, Canada; in the Gold washings of the north fork of the American River and elsewhere in California.

Hyacinth occurs of sufficient dimensions to be valuable as a gem.

It is very doubtful whether the modern hyacinth is one of the stones that were called hyacinth (εάκωθος) by the ancients. Jameson seems to have supposed that they applied this name to the amethyst or sapphire.

Ostranite, Breit., is a zircon of a grayish-brown color. From Fredericksvarn!

ALTERED FORMS .- Zircon is one of the most unalterable of minerals, as it contains no protoxyds, and only the most insoluble of peroxyds. It however passes to a hydrous state, and is probably acted on by alkaline waters, which attack the silica, and thus Erstedite may have been formed. Malacone, Erstedite and Tackyaphaltite, are probably altered zircon.

Malacone, Scheerer, (Pogg. lxii, 436). Dimetric like zircon; 1: 1=124°40′ to 124° 57′ and 83° 30′. H.=6.5. G.=3.9-4.047. Brown and vitreous to subresinous, powder reddish brown or uncolored. Composition Zr Si+4H (or 4H). Analyses: 1, Scheerer, (loc. cit.); 2, Damour, (loc. cit.); 3, Hermann, (J. f. pr. Chem.

Si Zr Fe Y Ca Mg H

- 1. Hitteroe, 81.81 68.40 0.41 0.34 0.39 0.11 3.08=98.99, Scheerer.
- 2 Chanteloube, 30 87 61 17 3 67 0 08 3 09, \$\frac{\mathbb{M}}{\text{chanteloube}}\$ 0 14=99 02, D.
 3. Ilmen Mts., 31 87 59 82 Fe3 11 Mn1 20 4 00=100, Hermann.

B.B. like zircon, except it yields water. From Hitteroe in Norway, and Chanteloube, Haute Vienne, at the latter place occurring in thin plates rarely over 3 to 4 mm. thick and occasionally with crystals on their surface.

Calyptolite of Shepard, (Am. J. Sci., [2], xii, 210); occurs with chrysoberyl at Haddan, Ct., in minute, short square prisms like f. 382, of a dark brown or greenish brown color; angle 1: 1 stated at 122°—124°. G.=4:34; H.=6.5. It yields some moisture, and is probably zircon somewhat altered.

Erstedite, Forchhammer, (Pogg. xxxv, 630).—Dimetric; 1:1=128° 16½'. H.=55. G.=3.629. Reddish brown and splendent adamantine; opaque or subtranslucent.

Composition .- According to Forchhammer contains-

Si 19708 Ca 2.612 Mg 2.047 Fe 1.186 Ti and Zr 68.965 H 5.532=100.

B.B. infusible, and according to Berzelius gives a trace of tin. Occurs in brilliant crystals at Arendal in Norway, and commonly on crystals of pyroxene. Named after Ersted.

TACHYAPHALTITE, Berlin, Pogg. lxxxviii, 160.

Dimetric. In short thick prisms, 3 lines long; planes I and ii, with two octahedrons, one of 110° (edge of pyramid) and the other of 50° . Cleavage not distinct.

H.=5.5. G.=3.6. Lustre submetallic to vitreous. Color dark reddish-brown. Streak dirty yellow. Subtranslucent. Fracture conchoidal.

Composition .- Analysis by Berlin (loc. cit.):

B.B. infusible, but becomes dirty white; with borax dissolves with difficulty; with soda on platinum a dirty yellowish brown slag; in a tube gives water with a slight fluorine reaction. Partially decomposed by muriatic acid, after some time.

From granite veins in gareias, near Krageroe, with sphene. The name of the

From granite veins in gneiss, near Krageroe, with sphene. The name of the species is from raxus, quick, and aparts, the mineral flying readily from the gangue when struck.

IDOCRASE, H. Vesuvian. Egeran. Gökumite. Loboit, Frugardit, Idokras. Protheite, Urc. Wiluite. Cyprine. Xanthite, Mather.

Dimetric. $O: 1i=151^{\circ} 51'; a=0.53507.$

```
O: 1=142^{\circ} 53'. O: I=90^{\circ}. ii: i2=153^{\circ} 26'.
```

$$O: 2=123^{\circ} 27.$$
 $I: 1i=118^{\circ} 9'.$ $ii: i3=161^{\circ} 34'.$

$$O: 22=129^{\circ} 53'$$
. $ii: 22=133^{\circ} 20'$. $1: 1(ov.1i)=129^{\circ} 29'$.

$$O: 44=114^{\circ} 23'$$
. $ii: 33=144^{\circ} 45'$. $1:1(\text{ov.}I)=74^{\circ} 14'$.

$$O: \frac{2}{3}3 = 139^{\circ} 46'$$
. $ii: 44 = 152^{\circ} 5'$. $1i: 1i' (pyr.) = 141^{\circ} 1'$.

Cleavage: I not very distinct, O still less so. Twins: plane of composition 4i, (?) angle of divergence 56° to 60° ; also ii. Columnar structure rare, straight and divergent, or irregular; occasionally granular.

SARCOLITE, Thomson. Sarkolith. Analcime carnea, Monticelli.



Observed Planes.


Dimetric; $O:1i=156^{\circ}5'; a=0.4435$. Hemihedral in the planes 23, only the alternate occurring. $O:2=128^{\circ}33', 2:2$ (over terminal edge) $132^{\circ}52', O:\frac{2}{3}=157^{\circ}19', I:2=141^{\circ}27'$. Crystals small.

II.=6. G.=2.545. Lustre vitreous. Color flesh-red, reddish-white. Transparent to subtransparent. Extremely brittle.

According to an imperfect analysis by Scacchi, (Quadri Crystallographici, Naples, 1842, p. 66), contains

corresponding nearly to the composition of idocrase, and formula (皇(Na, Ca)³+ 基) Bi. B.B. fuses to a white enamel. With acids gelatinizes. Of rare occurrence at Mt. Somma.

MEIONITE, H. Mizzonite, Scaechi.



Dimetric: $O: 1i=156^{\circ}18'; a=0.439$. Observed planes, O, 13, I, 33, i3, 1i, ii; sometimes hemihedral in the planes 33, the alternate being wanting. $O: 1=148^{\circ}10', 1:1, pyr.=136^{\circ}11'$, basal 63° 40'.

Cleavage: ii and I rather perfect, but often interrupted.

II.=5.5—6. G.=2.5—2.74; 2.734—2.737, v. Rath. Lustre vitreous. Colorless to white. Transparent to translucent; often cracked within.

Composition.—Ca³Si+2\(\frac{7}{2}\) Si=\(\frac{1}{2}\) Ca³+\(\frac{1}{2}\) Ri\(\frac{1}{2}\) Si=\(\frac{1}{2}\) Si=\(\frac{1}{2}\) Siiica 42·1, alumina 31·9, lime 26 0.

Analyses: 1, L. Gmelin, (Schw. J. xxv. 36, xxxv. 348); 2, Stromeyer, (Untera 278);
3, Wolff, (De Comp. Ekeberg. etc., Ramm., 2nd Suppl. 133); 4, v. Rath. (De Comp. Wern., Pogg. xc, and Ramm., 5th Suppl., 211):

		Bi	æı	₽e	Ċa	Мg	Ňа	Ŕ				
1.	Somma,											
2.	61	40.53	3273		24.24			1.81 Fe 0.18=99.50, Str.				
8.	**	42.07	3171		22.43		0.45	0·31, ign 0·31=97·29, Wolf.				
4.	"	42.55	30.89	0.41	21.41	0.83	1.22	0.93, " 0.19=98.46, Rath				
	a With some Li.											


B.B. a colorless glass; a clear glass with soda. With acids does not gelatiniss, according to v. Rath., contrary to v. Kobell's statement.

Mizzonite, from Mt. Somma, afforded Scacchi the angles 1: 1=135° 56' and 64°06'; B.B. does not intumesce as much as Meionite, and is less easily attacked by acids. Occurs in small crystals in geodes, usually in limestone blocks on Monte Somma, near Naples.

Meionite was named from perws, less, the pyramid being less acute than in idocress

3CAPOLITE, Werner. Wernerite, H. Paranthine. Ekebergite. Nuttallite, Brooke. **Tetraklasit**, Haus. Glaucolite, Fischer. Atheriastite, Weibye. Terenite, Emmons. Porcellanspath, Fuchs. Stroganowite, Hermann. Schmelzstein, Skapolith, Spreustein, Wern.

2: 1=148° 6′. 2: 1=121° 54′. 1: i2=161° 34′. $I: i3=153^{\circ} 26'.$ 1:1 (pyr.)=136° 7'. $ii: i3=161^{\circ} 34'.$ 1:1 (bas.)=63° 48'. $ii: i2=153^{\circ} 26'.$ 1i:1i (pyr.)=146° 53'.



Cleavage: ii and I rather distinct, but interrupted. Also massive, granular, or with a faint fibrous appearance; sometimes columnar.

H.=5-5.5, nearly 6, a subtransparent variety from Gouverneur, N. Y. G.=2.612—2.749. Lustre vitreous to pearly externally, inclining to resinous; eleavage and cross fracture surface vitreous. Color white, gray, blue, green, and red; colors usually light;

interest uncolored. Transparent—faintly subtranslucent. Fracture

The species Scapolite undergoes but small variations in structure. It never becomes strictly fibrous, and usually occurs in distinct crystals which are occasionally of large size. The crystals when not glassy, are often rendered opaque externally or throughout by partial alteration, and sometimes have a chalky appearance over the surface, after exposure. The massive varieties have some resemblance to the feldspara. The following are names of so-called varieties.

Beapolite (named from **\sigma_{amos}, a club)** or *\sigma_{errorite}\$ includes common grayish the residual in the residual partial structures and the residual partial structures.

Beapolite (named from σκανος, a club) or Wernerite includes common grayish and white varieties. Nuttallite is essentially the name; colors bluish, grayish and dark greenish. Paranthine has included certain compact varieties and crystals of white and pale blue colors. Ekebergite is massive and subfibrous. The distinctions between these varieties are not well defined. Porcelain Spar is described as affording the prismatic angle 92°. But the analyses give the same oxygen ratio essentially as for Scapolite. G.=2.65—2.68. Glaucolite (Anal. 15, 26, 27) is referred to this place by G. Rose, as its cleavages are those of Scapolite and not of Labradorite; it is named from γλανος, greenish-gray. G.=2.72—2.9. Color lavender-blue, greenish; somewhat resembling blue Cancrinite.

Composition mostly R² Si²+2Xl Si,=(\frac{1}{2}R²+\frac{2}{3}Xl) Si\frac{1}{2}=(if R=Oa) Silica 49.3, alumina 27.9, lime 22.8.

Analyses: 1, v. Rath, (Pogg. xc); 2, 3, Wolff, (Foss. Ekeberg.); 4, 5, Rath, (loc. ett.); 6, Stadtmüller, (Am. J. Sci. [2], viii, 294); 7, H. Wurtz, (Am. J. Sci., [2], x, 325); 8, Hartwall, (Jahresb. iv, 155); 9, 10, Wolff, (loc. cit.); 11, 12, v. Rath, (loc. ett.); 18, Hartwall and Hedberg, (Jahresb. iv, 155); 14, Nordenskiöld, (Schw. J. xxxi, 417); 15, v. Rath, (loc. cit.); 16, Berg, (Jahresb. xxv, 356); 17, Wolff, (loc. cit.); 18, Ekeberg, (Afh. i Fys. ii, 153); 19, Fuchs, (Leonh. Tasch. f. Min., 1823, 94); 20, Kobell, (J. pr. Chem. i, 89); 21, Schafhäutl, (Ann. Ch. u. Pharm., xlvi, 325); 22, Hermann, (J. f. pr. Chem. liv, 420); 23, Wolff, (loc. cit.); 24, Hermann, (loc. cit.); 25, v. Rath, (loc. cit.); 26, Bergemann, (Pogg. ix, 267); 27, Giwartowaky, (Bull. Soc. Nat., Mosew. 1848, 548); 28, 29, Hermann, (loc. cit.)

Tow, 1848, 548); 28, 29, Hermann, (loc. cit.)

Specific gravity of 1, 2.654; 2, 2.712; 3, 2.718; 4, 2.748; 5, 2.788; 6, 2.748
7, 2.704; 9, 2.623; 10, 2.733; 11, 2.763; 12, 2.751; 15, 2.666; 16, 2.34; 17, 2.735
22, 2.70; 28, 2.712; 24, 2.69; 25, 2.683; 26, 27, 2.65—2.72; 28, 2.80; 29, 2.74.

```
ĸ
                                                  Йg
                      Si
                             ₩I
                                            Ċa
                                                         Ña
                                                               1·31 Ĥ 1·29=98·53, R
                                          17.22
                                                        2.29
 1. Pargas, gnh.
                    45.46
                            30.96
                                                               0.68 ign 1.04=98.18,W.
                                                        076
                                          17.84
                    45.10
                            3276
                                                               0.54 ig. 0.74=99.36, W.
                                                  1-29
                                                        4.52
 3. Bolton,
                    48.79
                            28.16
                                    0.32
                                          1502
                                                               0.63 H 0.78=98.51, R.
                                                        2.46
                            23.65
                                    3:38
                                          20.81
                                                  1.23
 4.
            bkh-gn. 45.57
                                                               0.51 " 1-24=98-74, R.
       "
 5.
                                    3.79
                                          20.18
                                                  101
                                                        209
                    44.40
                            25.52
                                                               3.48 " 1.63=100.27.S.
       "
                                                         tr.
                    4579
                            80.11
                                   1.86
                                          17:40
 6.
                                                                - =100 77, Wurtz
- ign.1 45=100,Har.
       "
                                                        776
              blue,
                                    2.26
                                          17:31
 7.
                    47.67
                            2575
 8. Pargas,
                                    1:40
                                          15.59
                                                  0.68
                                                         6.05
                    49.42
                            25.41
                                                               0.87 ign.0.77=99.90,W.
                                                  0.85
                                                        7.59
9. Wermland,
                    49.88
                            27.02
                                    0.21
                                          1271
                                                               0·12ign.0·85=98·45,W.
0·85 H 1·75=97 06.Rh
10. Finland,
                    48.15
                            25.38
                                   1.48
                                          16.63
                                                  0.84
                                                        4.91
11. Malsjö, blue
                     47:24
                            24.69
                                    tr.
                                          16-84
                                                  2.18
                                                        3:55
                                                               1.55 H 1-24=99 22, Rh.
12. Arendal, ywh.
                    45.05
                            25.31
                                    2.02
                                          17:30
                                                  0.30
                                                        6.45
                                                                —Ĥ 0.61=99.62, H.
18. Ersby,
                                          15.94
                                                         3.25
                    4877
                            81 05
                                          18.96
                                                                    H 1.03, Nord.
14.
                    43.83
                            35.43
                                                               0.60 Ho.55=97.49, Rh
15. L. Baikal, Gl.
                                                  0.48
                                                        4.70
                            27.20
                                    1.53
                                          15.98
                    46.60
16. Drothems,
                                                               0.32 ign. 1.60,undec.099
                            26.31
                                   0.32
                                          17:00
                                                  0.54
                                                        471
                    46.35
                                                                              =98·17, B
                                                               0.65 ign 0.69=98·12,W.
2.25=96·50, Ek
17. Hesselk. Ekeb. 49-26
                                                         6.14
                            96:40
                                    0.54
                                          14:44
                                                         5.25
18
                    46.00
                            28.75
                                    075
                                          13.50
                                                                    H 0-90=97-98, F.
19. Porcelain Sp
                     49:30
                            27:90
                                          14.42
                                                         5.46
                                                               0.17 =97.30, Kobell.
20.
                    50.29
                            27-37
                                          13.53
                                                         5.92
                                                               1 23 Clo 92, H1 2 Schaf
21.
        ..
                            27:30
                                                         4.53
                    49-20
                                          15.48
                                                        1 42 0 91 Mn 0 14, Fe VII.
C 2 94, H0 8, Li tr. = 98 81, H
                                                               0.91 Mn 0.14, Fe 0.12,
                                                  0.76
22. Bolton, red,
                    50.16
                            28.44
                                          13.12
                                                        7 09 0.85 ign.0.41=99.74,W
28. Arendal.
                    50.91
                            25.81
                                   0.75
                                          13:34
                                                  0.58
                                                              0.54 Mn 0.25, Fe 03, C
                            27.64
                                           9:10
                                                         6.89
24. Gullsjö,
                    52.94
                                                                       1.50=99.72,Her.
                                                               173 H 1,20=98-49, Rh.
                                                  078
                                                         870
25. Gouverneur.
                     52.25
                            23.97
                                            9.86
                            27.60 F 0.1
                                                               1 27 Mn 0 87, H 1 73, Be
26. Glaucolite,
                    50.58
                                          10.27
                                                  3.73
                                                        2.97
                            28.12 " 0.4
                                                               101 Mno 6 H1 79, Giw.
27.
                    50.49
                                          11.31
                                                  2.68
                                                        3.10
                            27.97 F 2.84
28. Ekebergite,
                                           973
                                                  0.39
                                                         4.83
                                                               0.86 Mn0.27=100, Her.
                    53.11
29. Diana,
                    51.81
                            32.45 F 2.53
                                            9.76
                                                        2.38
                                                               0.79 Mn0 28, H0 30,4H.

    1.35 p. c. of Ca C being excluded.
    5.17 Ca C excluded.

  · Na probably included.
  • 3.82 Ca C, excluded, Rammelsberg.
```

Bischof and G. Rose consider pure scapolite as having the oxygen ratio of Meionite, 1:2:3 for the protoxyds, peroxyds, and silica=(#R*+:12) Si=(if R=Ca) Silica 42:1, alumina 31:9, lime 26:0. But most of the analyses, as stated above, afford the ratio 1:2:4.

Analyses 1, 2, 6, give more nearly $1:2\frac{1}{2}:4$.

No. 14 corresponds to the ratio $1:3:4=(\frac{1}{4}Ca^3+\frac{1}{4}Kl)$ Si=Silica 43-2, alumins 36-8, lime 20-0. Nos. 24, 28, give the ratio 1:3:6; 25 the ratio 1:2:5; 29 the ratio $1:3\frac{1}{4}:6$.

Other intermediate ratios are also presented by the analyses; and even among specimen o the same locality. Thus Bolton alone has afforded to analysts the ratios (approximate)

1:2:4, 1:2:2:4, 1:2:2:25:4, 1:2:5:4, 1:3:6, 1:2\frac{1}{2}:6, 1:3-9:9.

and in one specimen analyzed by v. Rath the species contains potash replacing soda, (see beyond on Altered Forms.) It is obvious that the variations are largely due to alterations of one or two types. The ratio 1:2:4 is apparently the most prominent of these types, as recognized by Rammelsberg. Von Rath adopts, as a second, the Gouverneur scapolite, with the ratio 1:2:5

Second, the Gouverneur scapolite, with the ratio 1:2:5.

Usually found in crystalline rocks, and in granular limestone, most common near its junction with granute; also in beds of magnetic iron accompanying this rock. In the latter situation, scapolite occurs at Arendal, in Norway, and Wermland, is Swelen, also in fine crystallizations in Pargas, Finland, &c. At Arendal it is associated with hornblende and garnet in limestone, and occurs in long slender crystals. Wernerite is found in short thick crystals at the same locality. Paranthine occurs in the limestone quarries of Malsjö in Wernland. Other localities as above. Por-

celain spar occurs in granular limestone at Obernzell in Bavaria. Glaucolite is found near Lake Baikal, Siberia, in veins in granite.

Good crystals occur at Gouverneur, N. Y., in granular limestone, with apatite, sphene, and augite; at Two Ponds in Orange Co., N. Y., reddish-white crystals with pyroxene, sphene, and zircon, one crystal 10 in. long and 5 in diameter; in Warwick of the same county, milk-white crystals near Amity, with pyroxene, sphene, and graphite; five miles south of Warwick, and two miles north of Edenville, near Greenwood Furnace, (planes 1, 1, 12, 11), are other good localities; in Essex county, perfect crystals and massive, nearly fibrous, white and greenish-white, abundant near Kirby's graphite mine, four miles northwest of Alexandria, in Ticonderoga, associated with pyroxene; at Crown Point; in Lewis Co., N. Y., variety Nuttallite in fine crystals white, bluish, and dark gray, presenting the play of light usual with this variety; edges of the crystals often rounded. Bolton and Boxborough, Mass., afford good scapelite, both the common and the variety nuttallite, often in crystals sometimes large; also Chelmsford, Littleton, Chester, and Carlisle. At Parsonsfield and Raymond, near Dr. Swett's house, good crystals along with yellow garnet and adularia. At Franklin and Newton, N. J., and three miles west of Attleboro' crystallized scapolite occurs in limestone. At G. Calumet, Id., Canada, massive lilac-colored; in large crystals, at Hunterstown with sphene; at Grenville with pyroxene.

Massive scapolite occurs at many of the above localities; also at Marlboro', Vt.; Westfield, Mass.; Monroe, Conn., white and nearly fibrous; stone quarry at Paugatuck, Stonington, Conn.; West Point, N. Y., with pyroxene; and of white and bluish-white colors at Fall Hill, Monroe, in Orange Co., N. Y., along with lamellar py-

Canaanite of S. L. Dana is considered a grayish scapolite rock, from Canaan, Ct. Composition, Si 53:366, Fe 4:099, \$\frac{1}{4}\$1 10:380, Ca 25:804, Mg 1:624 C 4:00=99:673.

ALTERED FORMS.—Scapolite is exceedingly liable to alteration; and many of the analyses appear to have been made upon specimens that have lost part of their bases, so that the silica is in excess. The mineral in its more ordinary change loses its hardness and lustre. The action of carbonated waters is sufficient to produce this result, the carbonic acid taking up the lime; and by carrying off all the bases, the mineral may be thus reduced to a kaolin. By means of bicarbonate of magnesia in solution, steatite results. By alkaline carbonates in solution, alkalies may be introduced and lime removed, thus forming mica, algerite, etc., and perhaps zeolites; and the potash carbonate appears to be able under some circumstances to replace with potash, the soda of a soda silicate, as in algerite. By means of bicarbonate of iron in solution, an oxyd of iron may be introduced, the iron often peroxydizing in the process, and thus comes epidote after scapolite. Atheriastite, Stroganowite, Terenite, as well as Algerite are believed to be altered forms of scapolite.

Many of the analyses of scapolite already given, are to some extent of altered rms. The following are of specimens more altered.

I. Altered by removal of protoxyd bases, mostly by carbonic acid. II. Altered by addition of oxyd of iron or magnesia without potash, and partial removal of bases.

III. Altered by addition of potash, and sometimes magnesia or oxyd of iron, and partial removal of bases.

Analyses: I, Brewer, (this Min., 3d edit., 680), 3, 4, Hermann, (J. f. pr. Ch. xxxiv, 177, and liv, 410); 5, Weibye and Berlin, (Pogg., lxxix, 299);—II, 6, 7, v, Rath, (Pogg., xc, 288);—III, 8, T. S. Hunt, (Am. J. Sci. [2], viii, 103); 9, Crossley, (this Min. 3d edit., 680); 10, J. D. Whitney, (Am. J. Sci., [2] xvi, 207); 11, 12, 13, v. Rath, (loc. cit.); 14, 15, Bischof, (Geol., ii, 1433):

	· <u>.</u>		1.	ŗ.	I I
	••				·
					·
•	:	-			
	·			• .	# 12 1 14 14 14 14 14 14 14 14 14 14 14 14 1
					. a
	e 1 s	_	. •		
	• •	<u> </u>	. ,		
* • * * :		:	٠.	_	
Teller Book de 2018 et alles alles		:	-, - :	.	
Terres de la composición del composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la composición de la c	- 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1 - 1	:	÷ •		Factor Factor
The section of the se		: - · · 	-1 -1 -1 -1		

The west subsection of Table 100 and the section Artificial Control of the Control of the Control of Control o

And the second of the second o

This a marnessar maca.

In the pseudomorphs formed to the substruct of a sphesial for other pro-


oxyd bases, occur at Newton, in New Jersey, and Arendal in Norway. Nos. 6, 9, 12, 15, are examples of change in this direction.

A specimen of Esmarkete, according to L. Samann (private communication) given to Mr. Daubree of Paris by M. Esmark, has the rectangular cleavages of scapolite, and is probably an altered form of this species. Two different minerals appear therefore to be confounded under this name. The analyses were made upon a mineral resembling hydrous is lite (see under Islite) and not on the scapolite mineral.

MELLILITE, F. de Bellerue. Humboldtilite, Monticelli and Corelli. Somervillite. Brooke. Zurlite. Ramondini.

Dimetric: $\theta: 1i=147^{\circ}15'$; a=0.6432. Observed planes θ , I, ii, 1i, i2. 1i: 1i tover $ii = 65^{\circ} 30', 1i: 1i$ 397 (over terminal edge = 134° 45°. Cleavage: basal distinct.

H.=5. G.=2.9-3.104. Lustre vitreous. Color brown, pale yellow, honey-yellow; Translugreenish-vellow. reddish-brown. cent. and in thin laminæ. transparent; also opaque. Fracture conchoidal—uneven.



Composition. -2 R' Si-R Si or 1 R'+; R Si, analogous to the formula proposed for Helvin. Analyses: 1. Kobell. (Schw. J. lxiv. 298); 2, 8, 4. Damour. (Ann. Ch. Phys. [3], x, 591; 5, Kobell, Kast. Arch. iv. 8151;

- 5i H: Fe Ca Mg Na K 1. Humb, Somma, 48-96 11-20 51-26 6-10 4-25 0-28, Fe 2-82=100-20, Kob.
- 1. Hand, C. di Bove, Sort 642 1017 (247 644 195 146-2918, Damour; G. 24.

 2. Mell., C. di Bove, Sort 642 1017 (247 644 195 146-2918, "G. 248.

 4. Sold 861 1002 (208 671 212 151-2936, "G. 248.

 5. Mastire Geldenite, Sort 1280 207 (1764 464 030 H 200-3975, Kobell.

No. 3, yellow crystals; No. 4, brown do. The massive gehlenite of Kobell comes

under the formula of humboldtriite.

B.B. fuses with difficulty to a yellowish or blackish glass. With the fluxes the

reaction of iron and silica. In the acids gelatinizes.

Humboldtilite occurs at Vesuvius in lava. Mellilite (fr. mel. honey) of yellow and brownish colors, is found at Capo di Bove near Rome, with nepheline. Somervillite, which Descloir aux has shown to have the angles of this species, is found at Vesavius in dull yellow crystals.

DIPYRE, Havy. Schmelzstein, W.

In four-sided prisms, apparently dimetric like scapolite; ends rounded. Cleavage lateral and diagonal.

G.=2.646. Sufficiently hard to scratch glass. Color whitish or reddish. Lustre vitreous. Transparent to translucent. ()paque when weathered.

Composition.—4 (Ca. Na) Si+3AlSi. Delesse=Silica 58-8, alumina 26-2, lime 94. soda 10 5. Analysis by Delesse, (Compt. Rend. xviii, 994, 1844):

> **★** 0 %. 7. 64 Si 55.5. 五 24 % Ca 940

B.B. becomes opaque and fuses with little intumescence to a white blebby glass.


Melts easily with sait of phosphorus, except a skeleton of silica. Forms a limpid glass, with soda. Attacked with much difficulty by the strongest acids.

Occurs year Manloon in the Lower Pyrenees, with tall or illicrite, in an uncours argiffice. Named from the firstly and resulter, alluding to its both phosphoresing and fusing his to the fill wpipe.

which service of Chargesties. According to R. P. Greg. Fr., who has examined several crystals, cure ranks or resin square prisms, giving In Imma 3, and I. Am 1999. He suggests to the antilent the species is Impore. In occurre in rearly the same region. Conservation the Processes, and resembles ingree in appearance. The control of any minimum Information. Since I. Middle II will be Mid 149. Mid 1999. While I was a sense of the control of the Control of the Information of the control of the I observe has an other form. The operate are rough and may give the process to meet a

FUU's THE HEALTH STATE TO THE PARAMETER THEFTHE WITH ARRESTS AS THE TOTAL TO A REST IN THE FOR THE LONG THE PROPERTY AND THE

[=6995] (12] [=11495 [48] (12] [43] (1



The species epidote includes:—

1. Lime-and-iron-epidote, Pistacite, or epidote proper.—Color yellowish-green, pistachio-green, passing to olive and leek-green. G.=3.35—3.5. Here fall Puschkinite and Bucklandite; the former of green, yellow, and red colors; G.=3.43;—the latter black; G.=3.51.

2. Lime-epidote, Zoisite in part.—Color gray or brown to white. In crystals usu-

ally deeply striated, and often columnar massive. G.=3-2-3-45.

3. Manganesian-epidote.—Color reddish-brown or reddish-black, dark violet-blue. Streak reddish. G.=3.404.

Cerium-epidote, containing cerium.

Withamite is a bright red variety; the crystals are pale straw-yellow in one direction across the prism. Thulite has a rose or peach-blossom red color. G.=3:1 -3.34. Allanite is a true cerium-epidote.

Composition.— $\hat{R}^{3}\vec{S}i+2\vec{H}\vec{S}i=(\frac{1}{2}\hat{R}^{3}+\frac{1}{2}\vec{H})\vec{S}i$; probably also for some varieties $3\hat{R}^{3}\vec{S}i+2\vec{H}\vec{S}i=(\frac{1}{2}\hat{R}^{3}+\frac{1}{2}\vec{H})\vec{S}i$.

Analyses: 1, Bucholz, (Gehl. J. i, 200); 2, Besnard, (J. f. pr. Chem. v, 212); 8, Geffkin; 4, Rammelsberg, (3d Supp. p. 43, and Pogg. lxviii, 509); 5, Kühn, (Ann. d. Ch. u. Pharm. lix, 373); 6, Hermann, (J. f. pr. Chem. xliii); 7, Gmelin, (Pogg. xlix, 539); 8, N. J. Berlin, (Pogg. lxxviii, 414); 9, Geffken, (as above); 10, Rammelsberg, (2d Supp. 48); 11, 12, Kühn, (Ann. d. Ch. u. Pharm. lix); 13, Hermann, (Ann. d. Ch. u. Pharm. lix); 13, Hermann, (Ann. d. Ch. u. Pharm. lix); 13, Hermann, (Ann. d. Ch. u. Pharm. lix); 13, Hermann, (Ann. d. Ch. u. Pharm. lix); 14, Hermann, (Ann. d. Ch. u. Pharm. lix); 13, Hermann, (Ann. d. Ch. u. Pharm. lix); 14, Hermann, (Ann. d. Ch. u. Pharm. lix); 14, Hermann, (Ann. d. Ch. u. Pharm. lix); 14, Hermann, (Ann. d. Ch. u. Pharm. lix); 14, Hermann, (Ann. d. Ch. u. Pharm. lix); 14, Hermann, (Ann. d. Ch. u. Pharm. lix); 15, Hermann, (Ann. d. Ch. u. Pharm. lix); 16, Hermann, (Ann. d. Ch. u. Pharm. lix); 17, Hermann, (Ann. d. Ch. u. Pharm. lix); 18, Hermann, (loc. cit.); 14, Rammelsberg, (Pogg. lxxxiv, 463); 15, Baer, (J. f. pr. Chem. xivii, 46); 16, 17, Hermann, (loc. cit.); 18, Osersky, (Bull. Soc. Nat. Moscow, 1841, 112); 19, Hartwall, (K. V. Ac. H. 1828, 171); 20, Sobrero, (Arsb. 1840, 218); 21, Geffken,

```
(loc. cit.):
I. Lime-epidote. G. of No. 4, 3:387; of No. 6, 8:28; of No. 8, 3:34.
                        Ŗί
                                ¥Ι
                                        ₽a
                                                Fе
                                                         Ca
                                                      22.50, II 2.00=99.50, Bucholz.
 1. Fichtelgebirge, 40-25
                               30.25
                                        4.50
 2. Grossarl,
                       40.00
                               26.46
                                        6.83
                                                      20.66, Mg 8.6, K 1.5=98.55, B.
20.52, Mn 1.78, Mg 4.75=101.92, Geff.
 3. Falltigel,
                       4074
                               28.94
                                        5.19
                                                      24.71=101.32, Ramm.
 4. Rothlaue,
                       44.56
                               23.72
                                        8.33
                                                      22.67, Mg 0.73, ign. 0.42=99.81, Kuhn.
21.56, H 0.56, Ø 1.13=99.50, H.
18.73, Mg1.64 Na1.89H0.64=99.13,G.
 5. Zwiesel, Bav. 40.62
                               29.18
                                        6.19
 6. Falltigel, gray, 40.95
                               30.34
                                               4.96
 7. Thulite, Soul'd, 42.84
                                       2.29
                               31.14
                                                    21.42, "0.66 Mn0.95, V0.22, ign. 1.32,
      " Klodeberg, 40:28 31:84 1:54
                                                                    (alk. undet.)=98.23, Berl.
     II. Lime-and-iron-epidote. G. of No. 13, 3:37; No. 16, 3:51; No. 17, 3:43.
                                                      22.86, Mg 2.38, Mn 2.12=100.03, G. 93.74 " 1.11=100.85 Remm
                               22.24 14.29
 9.
                      36.14
     Arendal,
                               20.78 17.24
                                                      23.74,
                                                                  1·11=100·85, Ramm.
10.
                      37.98
                                                      30 00, " 2.76=101.24, Kühn.
11.
     Geier, Erzgeb. 40.57
                               14.47 13.44
                                                      22.15, " 0.3=100.52,
12. Dauphiny,
                      39.85
                               21.61 16.61
                                                      21.19, " 1.40 Ho.46. C1.22=98.36,H.
18. B. d'Oisans,
                      37.60
                               18.57 13.37
                                               5.55
                                                      28.58, " 0.17=100.22, Ramm.
14.
                      38.37
                               21.13 16.85
                                                      23.46, "0.60, Na 0.41=99.47, Br. 21.14, H 0.68 Ca 0.32=100.33, Herm.
15.
            "
                      37.78
                               21.25 15.97
    Bucklandite,
                                               9.19
16.
                      36.97
                               21.84 10.19
                                                      22.06, Na, Li (tr.) 2.28, H 0.65, C 0.79,
B trace=98.60, Hermann.
16.00, Mn 9.26, Mg 6.1, Na 1.67, Li
17. Puschinite,
                      37.47
                               18.64 14.15
                                               2.56
18.
                      88.88
                             18.85 16.34
                                                                         0.46=98.56, Osersky.
                                  III. Manganesian Epidote.
19. St. Marcel,
                      38:47
                               17.65 6.60
```

```
— 21.65, Mn 14.08, Mg 1.82=100.26, H. 7.41 13.42, Mn 18.96, Mg4.82, Sn, Cu0.4, S. 22.78, Mn 18.25=99.99, Geff ken.
20.
                                               16.30
                                  37.86
91.
                                  36.87 11.76 10.33
```

B.B. fuses on thin edges and swells up, but does not easily liquefy, the varieties containing most iron being most fusible; glass with borax colored by iron. The nanganesian variety fuses readily with intumescence; glass with borax amethystine in the exterior flame. In acids the varieties are but partially decomposed, except after a strong heating. The specific gravity changes with heating. An Arendal specimen examined by Rammelsberg, (No. 15 above), had G.—3:403 before heating, 3:271 after heating. Most specimens of epidote afford a minute globule heating, 3.271 after heating. of tin before the blowpipe.

Arendal, in Norway, affords fine crystals, whence the name Arendalite. Occurs

also in the Ural, Piedmont, Fichtelgebirge, Rothlaue in the Canton of Berne, Faltigel in Tyrol, Grossarl in Austria, Bourg d'Oisans, etc. In the last, Rammelsberg finds no Fe.

Bucklandite is from Achmatowsk, Arendal, and Lake Laach. Puschkinite is from west of the Urals, north of Katherinenburg. Thulite is from Souland in Tellemark, Norway, and also the iron mine near Klodeberg, Norway; specific gravity of the former 3:1-3:2, of the latter 3:34. The manganesian variety occurs at St. Marcel in the valley of Aosta, in Piedmont.


Marcel, in the valley of Aosta, in Piedmont.

At Franconia, N. H., both crystallized and granular epidote are abundant, the latter containing magnetic iron. Large crystals of unusual beauty are obtained at Haddam, Conn. Also in crystals at the gneiss quarries of Hadlyme and Chester; in limestone at Newbury, Mass.; in greenstone near Nahant; in hornblende slate at Rowe, Mass,; fine crystallizations in syenitic gneiss, at Athol, Mass., two miles southwest of the centre of the town; at Warren, N. H., with quartz and pyrites; at Cumberland, R. L, in a kind of trap; in gneiss at Harlem, on the banks of East River, near 38th st.; two miles southeast of Amity, N. Y., in quartz; two miles south of Carmel, Putnam Co., N. Y., with hornblende and garnet; two miles south of Coffee's, Monroe, Orange Co., N. Y., in granite; at Franklin, N. J., a massive variety occurs; six miles west of Warwick, N. Y., of a pale yellowish-green color, associated with sphene and pyroxene; in Pennsylvania, at E. Bradford; very common in the Lake Superior copper region, as a rock, and veinstone, the latter on the Ontanagon; at the Norwich mine it occurs beautifully radiated, with quartz and native copper. Zoisite, or gray epidote, in columnar masses, is found at Willsboro', Vt.; at Montpelier, of a bluish-gray color, associated with cale spar in mica slate; at Chester, Mass., in mica slate; also at Goshen, Chesterfield, Hinsdale, Heath, Leyden, Williamsburg, and Windsor in Massachusetts, and at Milford, Conn.; in Pennsylvania in West Bradford and West Goshen, Chester Co.; also in Kennet township and East Marlboro.

ALTERED FORMS.—Epidote is less liable to alteration than most other silicates, and partly because the iron it contains is mainly peroxyd. Hermann found carbonic acid in several epidotes, an evidence of partial alteration; and J. D. Whitney describes a green mineral from Isle Royale with the composition of epidote, containing 5 per cent. of water, (Rep. Geol. L. Sup. 1851, 97).

ALLANITE. Cerine, Hisinger, (1811). Orthite, Berz., (1815). Bagrationite. Kokscharov. Uralorthite, Hermann. Xanthorthit, Hermann.

Monoclinic, and isomorphous with epidote. $C=65^{\circ}$ 5', $O:1i=125^{\circ}$ $25\frac{1}{2}$; a:b:c=0.8702:1:0.56137. Observed planes as in the annexed figures, (Kokscharov.)



Crystals either long and slender, or flat tabular. Twins like those of epidote. Cleavage: ii in traces. Also massive, and in angular or rounded grains.

H.=5.5—6. G.=3.3—4.2. Lustre submetallic and pitchy or resinous—occasionally vitreous. Streak gray, greenish, or brownish-gray. Color pitch-brown, brownish-black, yellowish. Subranslucent—opaque. Fracture uneven or subconchoidal. Brittle.

This species includes the following varieties:—
Allanite. G.=3:53-3:54, from Jotun Field; 3:79, from Snarum. Occurs in

rrystals, and in masses or grains.

Cerine. In crystals and crystalline masses. H.=6. G.=3.77—3.8, Hisinger.

Lustre weak, greasy. Color brownish-black. In thin splinters, subtranslucent.

Orthite. Occurs in acicular crystals; also massive. Lustre vitreous, inclining to greasy. H.=5-5-75. G.=3-288; 3-63-3-65, from Fillefjeld; 3-546, Hitteroe, Ramm.; 8-878, Scheerer. Streak gray. Color pitch-brown. In very thin splinters mbtranslucent.

Xanthorthite. Yellowish; G.=2.78-2.9, (anal. 16 and 18). Contains much

Bagrationite. Has the same angles as uralorthite, as shown by Kokscharov. G .= I-115.

Uralorthite. G.=8.41-8.60. Pyrorthite is an impure orthite containing bitumen.

Composition.—R°Si+RSi=(\(\frac{1}{1}R^0+\(\frac{1}{1}R^1\)\)Si. Rammelsberg writes for the orthite of the Ural, R°Si+RSi+\(\frac{1}{1}R^1\); for that of Hitteroe R°Si+RSi+\(\frac{1}{1}R^1\). Scheerer's analysee give 8R°Si+2RSi=(\(\frac{7}{2}R^0+\(\frac{7}{1}R^1\)\)Si, which is the formula of some idocrase. Analyses: 1, Stromeyer, (Pogg. xxxii, 288); 2, 8, Scheerer, (Pogg. li, 407, 465); 8, Credner, (Pogg. lxxix, 414); 5, Rammelsberg, (Pogg. lxxx, 285); 6, Bergemann, (Pogg. lxxxiv, 485); 7, Zachau, (N. Jahrb. 1852, 662); 8, Hissinger, (Afh. i, Fys. iv, 827); 9, Scheerer, (loc. cit.); 10, 11, Berzelius, (Hisinger's Min. Schwed.); 12, 13, Berlin, (Jahresb. xvii, 221); 14, 15, Scheerer, (Pogg. li, lvi, 479); 16, 17, 18, Bahr and Berlin, (Efvers. Af. K. V. 1845, 86); 19, Hermann, (J. f. pr. Ch. xliii, 105); 20, Ulex and Choubine:

I. Allanite, (Anhydrous). 1, Iglorsoit; 2, Jotun Fjeld; 3, Snarum; 4, Krux, Thuringia, G.=379; 5, Chester Co., Pa.; 6, West Point, N. Y., G.=34917; 7, near Dresden.

```
Mg 0.40, H 3.0=99.40, Stromeyer.
     Si
                    Рe
                             Ċе
                                      Ċа
1. 33.02 15.23 15.10 21.60
                                     11.08
                                            1.09, Mn 1.55, H 0.52=99.40, Scheerer.
3. 34.69 15.58
                   14.42 19.65
                                    11.90
3. 35.75 15.49 15.19 19.96*
                                    11 25 0 77 == 98 41, Scheerer.
                                             0·22, La 9·30, Y 0·56, Mn 0·23, H 1·80=
99·27, Credner.
4. 27.55 15.99 16.83
                                     18.60
                           3.19
                                     10·15 1·67, La 2·40, Fe 3·58, ign. 1·11=101·17, R. 9·36 1·40, Fe 3·33, Mn 0·82, H 2·95=99·02, B.
5. 31·86 16·87 12·26 21·27
6 33·83 13·61 12·72 20·90°
```

7. 83.41 10.90 20.88b 20.73 10.52 ----, Y 0.69, H 3.12=100.25, Zechau. b With oxyds of iron and manganese. a With oxyd of Lanthanum.

II. Cerine, (Anhydrous). No. 8, from Bastnäs; 9, from Riddarhyttan.

```
9·12 —, Ou 0·87=100·38, Hisinger.
8·08 1·16, Fe 25·26, La 2·45, H 0·6=99·90, Sch.
8. 30.17 11.31 20.72 28.19
                     --- 23.80
9. 32.06 6.49
```

III. Orthite, (Hydrous). 10, from Finbo; 11, Fahlun; 12, 18, Ytterby; 14, Fille Field; 15, Hitteroe; 16, Erikberg, (Xanthorthite); 17, Thiergarten; 18, Kullberg, (Xanthorthite).

G. of 12 and 13, 3.5; of 15, 3.373; of 16, 2.78; of 17, 3.41; of 18, 2.88.

```
10. 36.25
                            11.42 17.39
                                                       4.87
                                                                            3.80, Mn 1.36, H 8.70=97.79, Bert.
                 14.00
                                                                3*80, Mn 1*36, H 8*70=97*79, Ben.

3*44, Mn 3*40, H 5*36=98*72,
0*61 29*81, H 4*59, K, Na 0*61=99*96, B
1*60 20*83, H 3*34, K, Na 0*62=100, B,
0*86 1*91, H 0*52, Mn 0*85=100*08, Sch.
0*38 1*45, K 0*67, H 3*38=98*30, Scheer,
2*15, 0*59, Mn 0*39, H and some C17*55
                            12:44 19:44
11. 32.00
                 14.80
                                                       7.84
12. 36.24
                   8.18
                              9.06
                                         4.98
                                                       5:48
13, 33.60
                 12.58
                             13.48
                                         4.56
                                                       9.59
14. 34.93
                 14.26
                            14.90 21.43*
                                                     10.42
15. 33.81
                 13.04
                             15.65b 20.50
                                                      9.42
16. 32.93
                 15.54
                              4.21 20.01
                                                       6.76
                                                                                                                   =100 · I #. Br.
                                                                 1.58<sup>b</sup>, 1.18, ign. 1.24=99.71, Berlin.
4.94, 2.12, Mn 1.55, H 11.46, C 671=
                                                     10.18
17. 33.05 15.29 16.64 20.55*
18. 27:59 16:14 16:01 11:75*
                                                      2.28
                                                                                                                  100.55, Bahr.
```

a Including oxyd of Lanthanum and Didymium. b Containing also manganese. c Undetermined.

IV. Uralorthite, G .= 3.4-3.647. From the Ilmen Mountains.

19. 3549 18:21 18:03 10:85 9:25 2:06, Mn 2:37, La 6:54, Ĥ 2=99:80, Herm 20. 34:47 14:36 7:67 14:79 10:20 1:08, Fe 8:24, La 7:66, Ĥ 1:56=100:03, U.

Rammelsberg has examined the orthite of Hitteroe, with special reference to its proportion of iron oxyds, (Pogg. lxxvi, 96), and corrects analysis 15 as follows: Si 33-81, Al 13-04, Fe 8-16, Fe 8-30, Ce 20-50, Y 1-45, Ca 9-42, Mg 0-38, K 0-67, H 3.38=99.11, which gives, excluding the water, the formula above. The water amounts to 1 H, with this formula. The same composition is derived from Hermann's analysis, No. 19.

B.B. Allanite fuses with intumescence, to a dark glass or slag, sometimes magnetic Cerine fuses easily. Orthite fuses slowly to a black blebby glass. Reaction of iros with the fluxes, and with soda a manganese reaction. Uralorthite intumescents.

often very easily, and fuses on the edges to a black blebby glass.

Some allanites, and also some orthites, gelatinize with acids; others are imperfectly decomposed. Uralorthite is dissolved in acids, somewhat gelatinizing.

These varieties occur in albitic and common feldspathic granite, zircon-syenite, porphyry, and white limestone. Allanite occurs in Greenland, in granite; at John Fjeld in Norway, in a kind of porphyry, and at Snarum in albite, along with rulle and apatite; at Plauensche Gründ, near Dresden; in granite near Suhl in the Thüringerwald. The Allanite from Jotun Fjeld gelatinizes with acids, while that from Snarum is not affected by acids; Cerine occurs at Bastnäs in Sweden with hornblende and copper pyrites. Orthite occurs in acicular crystals sometimes a foot long at Finbo near Fahlun, and at Ytterby in Sweden; at Skeppsholm near Stockholm, in black vitreous masses disseminated through gneiss; also at Kragerce. Hitterce and Fille Fjeld in Norway, at Miask in the Ural; at Dresden. The name is derived from ορθος, straight. Uralorthite occurs with small crystals of zircon in flesh-red feldspar at Miask in the Ural.

In the United States in large crystals in Allen's vein at the gneiss quarries, Haddam, Conn.; in small crystals at the Bolton quarry, Mass.; at South Royalston is boulders; at Athol on the road to Westminster in gneiss; in a feldspathic rock in tabular crystals near West Point, and of similar character near Bay St. Paul, in Canada; in S. Mountain near Bethlehem, Pa., in crystals sometimes as large as the hand; in New Jersey, near Moriah, at Sandford ore bed. A massive pitch-black mineral from Monroe, Orange Co., N. Y.; a similar variety is found at East Bradford, Chester Co., Pa.; G.=3.5, (Anal. 5); at St. Paul's, Canada West.

With Allanite belong probably Bodenite, (Breith. Pogg. kni, 273, Kersten, ib. kni, 135, Kerndt, J. f. pr. Chem. xliii, 219), and Muromontite, (Kerndt, J. f. pr. Chem. xliii, 202)

xliii, 228).

Bodenite occurs in long prismatic crystals, apparently rhombic, with 1: 1-110° —112°. H.=6-6.5. G.=2.528. Color brown, reddish-brown to nearly black, and lustre somewhat greasy. Analysis by Kerndt, (loc. cit.): Si 26.12, Al 10.34 Fe 12 05, Y 17 43, Če 10 46, La 7 57, Ča 8 32, Mg 2 34, Mn 1 82, K 1 21, Na 0 84, H 3 82=100. B.B. glows like gadolinite; in platinum forceps, fuses only on the edges after long heating, and gives to the flame the yellow color of sods in the outer flame. From Boden, near Marienberg, in the Saxon Erzgebirge, with oligoclase.

The Muromontite is found in grains half as large as a pea, and rarely larger; no trace of crystallization apparent. H.=7. G.=4.268. Color black or slightly greenish by reflection. Lustre vitreous or slightly greasy.

Analysis by Kerndt, (loc. cit.): Si 31.09, Al 2.24, Be 5.52, Y 37.14, Ce 5.54, La 3.54, Fe 11.23, Mg 0.42, Mn 0.91, Ca 0.71, Na 0.65, K 0.17, H and loss 0.85=100. B.B. like Bodenite. From Mauersberg, near Marienberg, in the Saxon Erzgebirge.

ALTERED FORMS.—The hydrous varieties of allanite or orthite are properly altered forms of the species. They often contain carbonic acid. It is probable that the carbonates of lanthanum and of cerium proceed at times from the alteration of allanite.

ZOISITE, (in part.)

Monoclinic. $I: I=116^{\circ}16', I: \ddot{u}=121^{\circ}52', \dot{i}2: \ddot{u}=107^{\circ}16',$ i2: i2=145° 48', Brooke and Miller. Crystals lengthened in the direction of the vertical axis, and usually deep striate. Cleavage clinodiagonal, very perfect. Lustre vitreous. Color grayishwhite, gray, yellowish, brown, greenish-gray. Streak uncolored.

Analyses by Klaproth, (Beit. iv, 179, and v, 41):

1. Carinthia, **S**i 45 0 #1 29 0 Fe 3 0 Ca 21 0=98, Klaproth. " 44 0 " 32·0 " 2·5 " 20.0, Mn trace=98.5, Klaproth.

BB. in forceps intumesces and fuses without difficulty into a slightly translucent reenish-white irregular mass. With borax in the outer flame, or with salt of reenish-white irregular mass.

greenish-white irregular mass. With borax in the outer flame, or with salt of phosphorus, a transparent glass, light yellow, hot, colorless cold.


This species was separated from Epidote on crystallographic grounds by Brooke, in 1831, and is so published by Brooke and Miller. But only the analyses of the so-called Zoisite specimens from the Saualp in Carinthia by Klaproth are recognized by these authors as belonging certainly to the species. It does not appear to include all the lime-epidotes, as thulite, peculiarly a lime-variety, has the form and cleavage of epidote, and is placed with that species by Brooke and Miller. We therefore leave the other analyses under epidote until the subject is further investigation. therefore leave the other analyses under epidote until the subject is further investigated. Klaproth's analyses lead nearly to the formula Ca'Si+3 Kl Si=(1Ca'+2L)Si=Silica 43.2, alumina 36.8, lime 20.0. The rest give the formula of epidote. Other localities mentioned by Brooke and Miller are Sterzing in the Tyrol, Fern

leite in Fusch in Salzburg, Baireuth, Conradsreuth near Hof in Bavaria, and the

Mr. Brooke observes that the form is near that of Euclase.

GADOLINITE. Gadolinit, W. Ytterbyte.

Monoclinic; rarely in crystals, with uneven faces. Angles, according to Levy, $I: I=115^{\circ}, O: I=95^{\circ}$ 22', $O: e=112^{\circ}$ 52', $O: ii=96^{\circ}$ 30', O: a=149° 49′, I: e=162° 50′. Brooke obtained I: I=119° 30′, O: ii=90°, O: e=112° 33′, I: e=157° 27′, $O: a=163^{\circ} 8'$, and supposes the crystals trimetric. Scheerer obtained I: $I=115^{\circ}$, $O: e=131^{\circ}$, a clinodiagonal prism (over O)= $70\frac{3}{4}$ °. No distinct cleavage. Usually massive, compact.



H = 6.5 - 7. G = 4.0 - 4.5; of Ytterby 4.097 - 4.226, but after

heating 4.286—4.456, H. Rose; 4.35, from Hitteroe, Scheerer. Lustre vitreous, inclining to resinous. Color black, pitch-black, greenish-black. Streak greenish-gray. Subtranslucent—opaque. Fracture conchoidal.

Composition.—Approximately R³Si. Analyses: 1, 2, 3, Berzelius, (Afhand. iv. 148, 389); 4, Richardson, (Thom. Min. i, 410); 5, 6, Scheerer, (De foes. allanit, orthit, cerin, gadol. Berolini, 1840, and Pogg. lvi, 479); 7, 8, 9, 10, Berlin, (Dissert Gadol. Upsal. 1844, and Ofvers. af K. V. Ac. 1845, 86):


		Ši	₿e	Ý	Ċе	Ѓе	Ċa				
1.	Finbo,	25.80		45.00	16.69	10.26		ign. 0.60=98.35, Berzelius.			
2.	Broddbo,	24.16		45.98	16.90	11.34		ign. 0.60=98.93, Berzelius.			
3.	Korarfvet	29.18	2.00	47.30	₹8.40			₩n 1·30, H 5·20=99·53, R			
4.	**				" 4·60			H 0.50=100.55, R.			
5.	Hitteroe,	25.78	9.57	45.67	C 1·81			Ea 475,=10071, Scheerer.			
6.	"	25.59	10.18	44.96				Ea 6.33=99.42, Scheerer.			
7.	Ytterby,	25.62		80.00	"7.90	14:44	1.30	Mg 0.54, Al 0.48, K 0.19,			
	-							Na 0·18=100·65, Berlin			
8.	"	25.26		45.53	" 6 ·0 8	20-28	0.20	Mg, 0·11, A l 0·28, K 0·21,			
								Na 0 20=98 45, Berlin			
9.	"	24.65	2.18	49.60	€7·64°			Mg, Mn trace=99 51, Berlin.			
10.	"	24.85	4.80	51.46	" 5·24 <u>-</u>	13.01	0.20	MnMg 1·11=100·97, B.			
	a With oxyd of Lathanum.										

Of Berlin's analyses, the first two were of the glassy gadolinite; the others, as cepting the last, did not present the glow of light when heated.

B.B. decrepitates and swells into cauliflower-like masses, but does not fuse into a bead; in the progress of the heat it exhibits a vivid glow, and the color becomes paler. With borax a dark glass deeply colored with iron, bottle-green in the reducing flame. Acted on by salt of phosphorus with great difficulty. A variety less glassy in appearance does not exhibit the glow on heating. Gelatinizes in mariatic acid.

Gadolinite occurs principally in the quarries of Korarfvet and Finbo, near Fahlun, in Sweden; also at Ytterby, near Stockholm; at each place indistinctly crystallized, and in rounded masses, which are often encircled with a yellow crust, and imbedded in coarse-grained granite. At Korarfvet crystals have been obtained four inches long. It has also been met with at Disko in Greenland; in trap acar Galway, Ireland; imbedded in granite in Ceylon; at Finbo and Broddbo, and at Krageröe and Hitteröe in the southern part of Norway, crystals sometimes four inches across and twins at this last locality. Named after the Russian chemist, M. Gadolin.

DANBURITE, Shepard, Am. Jour. Sci. xxxv, 139.



Triclinic. Approximate angles, P: M 110° and 70°, M: T 54° and 126°, P: T 93° nearly, P: e 135°. Cleavage: distinct, parallel to M and P, less so parallel to T. Crystals imbedded, and often an inch broad. Also disseminated massive, without regular form.

H.=7. G.=2.95, Silliman, Jr.; 2.957, Brush. Color pale yellow, whitish. Lustre vitreous, but usually rather weak. Translucent to subtranslucent. Very brittle.

Composition.—Ca*Si+3B Si=(\(\frac{1}{2}\)Ca*+\(\frac{1}{2}\)B Si=Silica 48.9, boracic acid 28.4, lime 12.7. Analyses by Smith and Brush, (Amer. J. Sci. [2], xvi, 365):

B.B. fuses rather easily, and in the dark the flame is seen to have a decided green inge, especially after having moistened and heated the mineral with sulphuric acid. lives the boracic acid test as strongly as borax. Affords easily a transparent seed with sods or borax. Yields no water.


Occurs with oligoclase in dolomite at Danbury, Connecticut. It has some resembance to Chondrodite in color, lustre, and brittleness, but is distinctly cleavable, although the planes of cleavage are often irregular.

AXINITE, Karsten. Thummerstein. Thumite. Yanolite.

Triclinic. Usual in thin oblique crystals with sharp edges; $P: u=135^{\circ} 10'$; $P: r=134^{\circ} 40'$; $u: r=115^{\circ} 17'$; $r: s=143^{\circ} 20'$; $u: s=152^{\circ} 5'$; $P: l=151^{\circ} 5'$. Cleavage: parallel to a plane of the sente edge. P: u' and also

on the acute edge P:u', and also parallel to a plane replacing edge v:P', but imperfect. Also massive, amellar, lamellæ often curved; sometimes granular.

H.=6.5—7. G.=3.271, Haidin-ant. P. ger; a Cornish specimen. Lustre highly glassy. Color clove-brown, plum-blue, and pearl-gray; exhibits richroism, different colors, as cinnamon-brown, violet-blue, olive-green, being seen in different directions. Streak uncolored. Transparent to subtranslucent. Fracture conchoilal. Brittle. Pyroelectric.



Composition.— \mathbb{R}^s Si+ $2\mathbb{H}$ Si+ $2\mathbb{H}$ Si= $(\mathbb{R}^s,\mathbb{H},\mathbb{B})$ Si. According to Rammelsberg and Rose \mathbb{R}^s Si, $\mathbb{B})^2+2\mathbb{H}$ Si, \mathbb{B} . Analyses: 1, Hisinger, (Min. Schwed., 170); 2, Wiegmann, (Schw. J. xxxii, 462); 3—6, Rammelsberg, (Pogg. 1, 363):

		Si	В	Æl	₽e	₩n	Ċa	Йg	Ŕ
									ign. 0.80=98.56, His.
									——=100, Wiegmann.
Ļ	Dauphiny,								0.64=100.48, Ramm.
L	- 66								und., Ramm.
Ĺ	Treseburg,	4874		15.66	11.94	1.37	18-90	177	B, K and loss 6.62, R.
L	Ural,	4872		16.93	10.21	1.16	19.97	2-21	——B, K and loss 5-81, R.

In the last two analyses Rammelsberg states that out of the last entry in each, sper cent. is not too large an estimate for the boracic acid.

B.B. fuses readily with intumescence to a dark-green glass, which becomes black a the outer flame; with borax yields an iron-colored glass which after long heating a the outer flame becomes amethystine.

Axinite is pyroelectric with two axes, and the analogue and antilogue poles are ituated, according to Rose, as marked in the figure.

Axinite occurs in implanted glassy clove-brown crystals, at St. Cristophe, near sourg d'Oisans in Dauphiny, with albite, prehnite, and quartz; at Santa Maria, witzerland; at the silver mines of Kongsberg, in smaller crystals; with horn-

blende or magnetic iron ore in Normark in Sweden, and of a dark color, at the Botallack mine in Cornwall, where it also occurs massive, forming a peculiar kind of rock with garnet and tourmaline; also at Thum near Ehrenfriedersdorf in Saxony, and called Thumite and Thummerstein. It occurs with gray cobalt, near Coquimbo, Chili; at Phipsburg, Maine, with yellow garnet and idocrase; also at Wales, Maine.


Axinite admits of a high polish, but is deficient in delicacy of color. It was named from afirm, an axe, in allusion to the form of the crystals.

IOLITE Dichroite. Peliom. Steinheilite. Cordierite, H. Sapphire d'eau. Hard Fahlunite.

Trimetric. In stout prisms often hexagonal. $O:1i=150^{\circ}49'$, $O: 1=132^{\circ} 12', I: I = 60^{\circ} 50', \text{ and } 119^{\circ} 10', is: is = 120^{\circ} 50'.$

	()	
		1	
11		1/2	
11		1	
21	7.5		
	33		
ii	iš	1	ìi

Observed planes.



Cleavage: O and ii indistinct. Crystals often transversely divided, or foliated, parallel with O. Also massive, compact.

H.=7-7.5. G.=2.5969, Greenland, Stromeyer; 2.65-2.6643, Haddam, Thomson; Ostgothland 2.64, Südermanland 2.61, Schütz. Lustre vitreous. Color various shades of blue, light or dark, smokyblue; often deep blue along the vertical axis, and brownish-yellow or yellowish-gray, perpendicular to it. Streak uncolored. Transparent—translucent. Fracture subconchoidal.

Composition.—R² Si²+3R Si, Berz =(1 R²+1 Al) Si⁵=Silica 49.6, alumina 33.6,

magnesia 8.7, protoxyd of iron 7.9.

Analyses: 1, 2, 3, Stromeyer, (Unters. 329, 431); 4, 5, Schütz, (Pogg. liv, 565): 6, Scheerer, (Pogg. lxviii, 319, mean of two analyses); 7, Thomson, (Min. i, 278): 8, Jackson, (this Min. 2nd ed. 406, and Geol. Rep. New Hampshire, 184):

	Si	Æl	Mg	$\mathbf{M}\mathbf{n}$	\mathbf{Fe}	H
1. Bodenmais.	48.35	3171	10.16	0.33	8.32	0.59=99.46, Stromeyer.
2. Greenland,	49.17	33.11	11.45	0.04	4.34	1.20=99.31, Stromeyer.
3. Fahlun,	50.25	$82 \cdot 42$	10.85	_	4.01	1.66, Mfn ().68=99.87, Strom.
4. Ostgothland,	48.6	80.2	8.2	0.1	107	1.5, undec. 0.2=100.8, S.
5. Südermannland,	497	82.0	9.5	0.1	6 O C	a 0.6, ign. 2.1, und. 0.6=100.6.8
6. Krageroe,	50.44	32.95	12.76		Ĥ	[102, Fe] 07, Ca 1·12=99·36.8
7. Haddam, Ct.	49.62	28.72	8.64			, Ca 0.28=100.30, Thom.
8. Unity, Me.	48.15	32.50	10.14	0.28	7-92	0·50=99·49, Jackson.

B.B. fuses slowly on the edges to a blue transparent glass; with borax forms a clear bead. In powder attacked by concentrated acids, but not perfectly dissolved Iolite is met with at Bodenmais, in Bavaria, occasionally in perfect crystals 1 in thick. This variety has been called *pelion*, from its smoky-blue color, from states.

It occurs in quartz, at Ujordlersoak, in Greenland; in granite at Cape de Gata, in

Spain; at Arendal, in Norway; at Orijerfvi, in Finland, (Steinheilite); at Tunaberg, in Sweden, &c. Ceylon affords a transparent variety, in small rolled masses, of an intense blue color, the sapphire d'eau of jewelers.

At Haddam, Conn., associated with garnet and anthophyllite in gneiss; also abundant in quartz with garnet and yellowish-green feldspar, near the Norwich and Worcester Railway, between the Shetucket and Quinnebaug, where the gneiss has been quarried for the road. At Brimfield, Mass., on the road leading to Warners near the Patrick's with adulating in gneises also good at Fishmond N. H. ren, near Sam Patrick's with adularia, in gneiss; also good at Richmond, N. H., in talcose rock, along with anthophyllite.

Iolite is occasionally employed as an ornamental stone, and when cut exhibits different colors in different directions. Named from 100, violet, and λιθος, stone; dichroite, from its dichroism; Cordierite, after M. Cordier, the geologist.

ALTERED FORMS.—The alteration of iolite takes place so readily by ordinary exposure, that the mineral is most commonly found in an altered state, or enclosed in the altered iolite. This change may be a simple hydration, (Fahlunite, etc.); or a removal of part of the protoxyd bases by carbonic acid; or the introduction of oxyd of iron through carbonate of iron; or of alkalies through waters containing alkaline carbonates, forming Pinite and mica; the first step in the change consists in a division of the prisms of iolite into plates parallel to the base, and a foliation of the surfaces of these plates; as the alteration proceeds, the foliation becomes more complete, but afterwards it is often lost.

Massalin, (Trommsdorff's N. J. iv, 2, 324); 4, Scott, (Ramm. Handw. ii, 61); 5, 6, Rammelsberg, (3d Supp. 94); 7-9, Marignac, (J. d. Pharm. Ch. [3], xii, 150); 10, 11, Trolle Wachtmeister, (K. V. Ac. H. 1827, p. 213); 12, Bonsdorff; 13, Erdmann, (Jahresb. 1841, 174); 14, C. T. Jackson, (2nd edit. p. 306); 15, Trolle Wachtmeister, (Pogg. xlv, 558); 16, Marignac, (J. de Pharm. et de Chem. [3], xii, 150); 17, Scheerer, (Pogg. lxviii, 323); 18, Erdmann, (K. V. Ac. H. 1840); 19, Wachtmeister, (K. V. Ac. H. 1827); 20, Nordenskiöld, (Jahresb. xii, 1833, 174); 21, Marignac, (v. Leonh. 1849, 201); 22, v. Hauer, (Jahrb. K. K. Geol. R., 1853, 147).

Analyses: 1 to 9, Pinite (or so called); 10, 11, Fahlunite; 12, Bonsdorflite; 13, Esmarkite; 14, Chlorophyllite; 15, 16, Gigantolite; 17, Aspasiolite; 18, Prascolite; 19, Weissite; 20, Pyrargillite; 21, 22, Liebenerite.

```
Si
                                 E
                                          Fe
                                                        Mg
                                        5.51 7.89 3.76
 1. Auvergne,* Pin. 55.96 25.48
                                                               1.41. Na 0.39=100.42, Gm.
                                                               1.2, Fe 7.8, Mn1.6=100.8, F.
==100, Massalin.
 2. Neustadt, red, " 54.6 23.6
                                          - 11.2
                                                        0.8
                        45.0 30.0
                                         12.6 12.4
                    48.00 28.00
                                          9.66 11.35
                                                                3 0, Ca 0 75=100 70, Scott.
                    " 47.00 38.36 Fe7.08 10.74
                                                                3.83, Ca 0.79, Na 1.07, R.
   Auc,
                    " 46.83 27.65
                                         7.84
                                                               7.80, Ča 0.49, Na 0.40, R.
                                                 6.52
                                                        1.02
                                                              5·03, Na1·78, Ca0·92=100, M.
5·45, Na 0·46=100, "
5·39, Na 0·95=100, "
 7. Auvergne, " 47.50 31.80 Fe3.92
                                                9.05
                    " 46.10 32.46
                                       " 4.27
                                                        2.26
     Saxony, G.
                                                 9.00
 9. Chamouny, G. " 44-70 31-64 " 6-57 7-89
                                                        2.86
              a In porphyry. The magnesia in the analysis includes some manganese.
                                         3·86 1·98 6·75 9·35, Mn 2·24, Na HF tr.
Ca 1·35=100·23, Wacht.
10. Grafen, Fahl.
                      44.60 30.10
                                                 1.38 6.04 8.65, Mn 1.90, Ca 0.95, W.

— 9.00 10.60, (some Mn with Mg)=
11.
                         44.95 30.70
                                          7.22
12. Abo, Bonsd.
                        45.05 30.05
                                          5.30
                                                 — 10·32 5·49, Mn 0·41, Ča, Pb, Cu, Co,
Ti, 0·45=98·55, Erdmann.
— 9·60 3·60, Mn 4·08, P tr.=98·32, J.
2·70 3·80 6·00, Mn 0·89, Na 1·20, F. tr.
Wachtmeister.
13. Brevig, Esmar. 45'97 32'08
                                          3.83
                                          8.24 -- 9.60
14. Unity, Chloroph. 45:20 27:60
15. Tamela, Gigant, 46.27 25.10 14.04 2.70 3.80
        " 42.59 26.78 14.21 5.44 2.72 5.70, Mn 1.07, Marignac.
```

a Reckoned as protoxyd by Marignac, instead of peroxyd, which reduces an excess in the analysis of Wachtmelster, and conforms it to Marignac's determination.

K Mg -- 8'01 Si **X1** 673=99 86, Schoerer. 7-38, Mn 0-32, Pb, Ču, Čs, Čo, 0-50=98-62, Erdmann. H and NH² 3-20, Mn 0-63, Na 17. Krageroe, Asp. 50.40 32.38 2:34 -18. Bräkke, Pras. 40-94 28-79 6.98 -- 1373 19. Fahlun, Weis. 53.69 21.70 143 4.10 8.99 0-68, Zn 0-2=100-72, Wacht 5-30 1-05 2-90b H15-47, Na 1-85=99-43, Nord 1-75 9.90 1-40 H O 4-49, Na 0-92=99-63, M 2-26 6-45 tr. "475°, Na 2-79, Ca 20. Helsingfors, Pyr. 43.93 28.93 21. Fleimser, Liebn. 44 66 36 51 175 9.90 140 22. " 44 45 38 75 Ft 2 26 6 45 tr. 1.58=101.03, v. H.

b With magnesia. * Reckoned as protoxyd by Erdmann.

Pinite includes the alkaline varieties of altered iolite, (analyses 1 to 9). In 6 or 12-sided prisms; cleavage often indistinct, sometimes basal; color gray to gray ish-green or brown. H.=2.5. Analysis 5 corresponds in formula to iolite+2H; 7, 8, 9, iolite +3H, Marignac; 6, to iolite +Al Si²+6H, Rammelsberg. RR whitens and fuses on edges. Occurs in Auvergne at the Puy-de-Dome, in decomposed feldspar porphyry; at Schneeberg in granite. Oosite related to pinite b from near Baden.

Fahlunite, Hisinger, (Anal. 10, 11), Bonsdorffite or Hydrous Iolite of Bonsdorf, (Anal. 12), Esmarkite, Erdmann, (Anal. 13), Chlorophyllite, Jackson, (Anal. 14)—These are very similar, occurring often in large 6 and 12-sided prisms, the form of These are very similar, occurring often in large 6 and 12-sided prisms, the form of the original iolite, (sometimes 6 inches across), with basal cleavage usually perfect and sometimes micaceous. Folia brittle. Color gray or grayish-green, greenish brown, dark olive green. Lustre pearly. G. in Fahlunite 2-6—2-79; in Ermakite 2-709; in Chlorophyllite, 2-705. B.B. fuse only on the thinnest edges. Bondorffite and Fahlunite correspond to Iolite+6H; Esmarkite, to Iolite+3H; Chlorophyllite to Iolite+2H; but the water is not constant, and the varieties are not distinct. Fahlunite occurs with iolite at Fahlun; Bonsdorffite at Abo; Esmarkite is from near Brayin: Chlorophyllite from Unity. Me., and Haddam. Ct.

is from near Brevig; Chlorophyllite from Unity, Me., and Haddam, Ct.

Gigantolite, Nordenskiöld, (Anal. 15, 16).—Forms and cleavage as in the last; Habout 3.5, but on cleavage surface 2; G.=2.862-2.878. Greenish to dark steelgray; between vitreous and waxy, approaching submetallic. Formula if part of the iron is peroxyd, (Fe 2.83, Fe 11.61), equivalent to Iolite +3H. B.B. fuses with intumescence to a light greenish slag. From Tamela, Finland, in a gneissoid granita. Crystals large.

Aspasiolite, Scheerer, (Anal. 17). In prisms like the preceding, but cleavage less distinct. H.=3·5. G.=2·764. Greenish gray to whitish. Lustre weak. Composition, Iolite + Al Si²+5H. B.B. infusible. From Krageroe in Norway, with quartz and iolite.

Praecolite, Erdmann, (Anal. 18). In prisms with basal cleavage, like the above Green, with lustre greasy. Fracture flat-conchoidal and splintery. H.=3.5. G.=2754. Composition if the iron is peroxyd, Iolite+3H, Rammelsberg. B.B. fuse on thinnest edges only to a bluish green glass. From Brakke, near Brevig, Norway, in granite.

Weissite, (Anal. 19). Similar to Fahlunite. Color blue, green. G.=2.8. Formula given, R. Si²+2R Si². From Fahlun, occurring in chlorite state in masses w large as hazlenuts.

large as hazlenuts.

Tennant has analyzed a mineral from Canada East, (Rec. Gen. Sci., 1836, May. 232), which has the composition of Weissite, affording Si 55-05, Kl 22-60, Mg 5-70, Fe 12-60, Mn trace, Ca 1-40, H 2-25=99-60. A relation to Weissite is doubtful.

Pyrargillite, Nordenskiöld, (Anal. 20). In prismatic forms; cleavage not distinct. H.=3-5. G.=2-5. Partly black, or bluish, liver-brown or dull red, and dull resisous. Odor argillaceous. Composition given, R Si+Al Si+4H. B.B. infinible, becoming a little glazed in a strong heat. Soluble in muriatic acid. Near Heliagfors, Finland, in granite. Pyrargillite is referred to altered iolite by Bischof.

Liebenerite, (Anal. 21, 22). In 6-sided prisms, without distinct cleavage. H=15

G.=2-814. Greenish-gray and somewhat greasy. Fracture splintery. Formula given R Si²+6Kl Si+5H. B.B. whitens and intumesces, but does not fuse. From a red feldspar porphyry at Mt. Viesena, Fleimser Valley, in porphyry. Von Hauer

a red feldspar porphyry at Mt. Viesena, Fleimser Valley, in porphyry. Von Hauer states that his specimen had no appearance of alteration. The reference of this mineral here may not be correct.

Iberite, Svanberg, from Montalvan near Toledo, Spain, probably belongs here. It occurs in large six-sided prisms with basal cleavage. H.=2.5. G.=2.89. Vitreous to pearly. Composition according to Norlin, (Ofv. af. K. V. Ac. Förh., 1844, 219), \$\overline{8}\$i 40.90, \$\overline{A}\$i 30.74, \$\overline{1}\$fe 15.47, \$\overline{M}\$n 1.33, \$\overline{C}\$a 0.40, \$\overline{M}\$g 0.81, \$\overline{K}\$ 4.57, \$\overline{N}\$a 0.04, \$\overline{H}\$ 5.56=99.82. B.B. fuses to a dark pearl.

Huronite of Thomson, (Min. i. 384), from Canada, near Lake Huron, is considered an altered mineral near Fahlunite, by T. S. Hunt. Thomson in his analysis obtained, Si 45-80, Al 33-92, Fe 4-32, Ca 8-04, Mg 1-72, H 4-16=99-96. Infusible. Not at-

tacked by acids.

4. MICA SECTION.

Oxygen ratio, (type ratio), 1:1; but ratio varying to 1:3. Structure micaceous.*

MUSCOVITE,	$(\frac{1}{3} \dot{\mathbb{R}}^3 + \frac{1}{3} \frac{2\pi}{3}) \dot{\mathbb{S}}i^{\frac{5}{4}}$	
MARGARODITE,	(in part), $(\frac{1}{7}\dot{\mathbf{R}}^2 + \frac{6}{7}\ddot{\mathbf{R}})$, $\ddot{\mathbf{S}}^{\frac{5}{4}} + \mathbf{n}$	ÂL.
Phlogopite,	(3 R 2+ 3R)Si.	
Вютите,	(½R³+}∄)Ši.	
Lepidolite,	(in part), (R3,H) Si3.	
"	" (Ř³, Ħ) Ši¾.	
"	" (Ř³ , #) Š i.	
LEPIDOMELANE,	(∤R°+ ∤ ⊞ Si.	

The micas have been considered as either monoclinic, trimetric or hexagonal. But Senarmont in his recent investigations has shown that monoclinic forms do not exist. He argues this from the fact that no twins have been observed in which the terminal faces are inclined to one another, while they are common parallel to the prismatic planes with these faces in one and the same plane, as observable by optical means when not otherwise apparent.

It is well known that slight admixtures of foreign ingredients change greatly the axes of polarization; moreover the same plate often varies several

degrees in the apparent optical angle in different parts.

But notwithstanding the variations thus occasioned, there is still a wide interval between the common micas and the phlogopites, the former varying in the angle between the apparent axes, from 45° to 78°, the latter not exceeding 20°. The following are the results of the examinations of micas by Silliman, Jr., (Am. J. Sci., [2], x, 372, and Senarmont, (Ann. de Ch. et de Phys. [3], xxxiii, 391, xxxiv, 171. They are important as identifying localities, independently of their optical interest.

^{*} The species Margarite and Euphyllite appear to be homocomorphous with the micas; but being hydrous they are arranged near chlorite.

I. Observations of Silliman, Jr.

1. American Muscovite and Lepidolite; Angle from 55° to 76°.

		Apparent Angle.
1.	New York Island, 4 m. from City, violet gray, containing	
	black grains,	56° 20'-56° 40'
2.	Royalston, Mass., dark brown, fine crystal,	57° 80′
3.	ib. ib ib. ib. another,	58° –59°
4.	Pennsbury, Penn., smoky brown, striated,	59°
5.	Philadelphia, Penn., greenish gray, banded,	60° 8 0′ -61°
6.		
	sembles No. 4,	60°-62° 80′
7.	Oxford, Maine, light brown,	62° 42′-68°
8.	Monroe, Conn., brown with patches,	64° 80′–65° 80′
	Royalston, Mass., violet brown; in thick plates,	650
10.	Local. I greenish gray; in crystals,	65° 80′–66°
11.	Falls road, 21 m. from Baltimore, transparent brown,	65° 80′–65° 40′
	Near Ellicott's Mills, Md., ib. ib.,	66° 80′
13.	"Jones Falls," near Baltimore, blackish green; symmetri-	000 1r/ 000 00/
14	cally banded,	66° 15′—66° 30′
15.	Greenfield, Conn., greenish yellow,	66° 80′–67° 67°
10.	Haddam, Conn., (Quarry Hill), clear brownish green, Grafton, New Hampshire, light brown, transparent,	67° 30′
	Unionville, Penn., white, Corundum locality,	67°-67° 28′
	Acworth, N. H., greenish gray, in granite,	67° 15′-67° 3 0′
19	Grafton, N. H., another specimen, light brown. with	01 10 -01 60
10.	quartz and tourmaline,	68° 5'-68° 20'
20.	Templeton, Mass., transparent brown,	69° 80′-69° 40′
21.	Orange, Mass., ib. ib, beautiful crystals,	690 30'-690 40'
22.	Willimantic Falls, Conn., brownish green, transparent in	
	granite,	69° 30′-69° 5 0′
23.	Pennsbury, Penn., brown crystals; another locality.	69° 27′-70°
24.	Royalston, Mass., dark brown; 2d locality.	69° 40′-70°
	Grafton, N. H., light brown; 3d specimen,	690-690 801
	Middletown, Conn., brownish, feldspar quarry,	700-700 301
27.	Chester, Hampden Co., Mass., greenish white,	70°-70° 80′
28.	Norwich, Mass., greenish yellow; Spodumene locality,	70° 80′
29.	Pennsbury, Penn., (3d local.), brownish green,	70°-70° 30 ′
30.	Goshen, Mass., greenish yellow, with spodumene, Greenfield, N. Y., brownish; Chrysoberyl locality,	70°-70° 80
81.	Greenfield, N. Y., brownish; Chrysoberyl locality,	70° 45′-71′
92.	Haddam, Conn., brownish; in large plates,	70° 70°
94	Gouverneur, N. Y., brownish-white, in boulder,	70° 15′
95	Templeton, Mass., (2d spec.,) transparent brown, Leiperville, Del. Co., Pa., faint greenish, plicated,	70° 30′-71°
96.	Laffarson Co. N. V. graenish: in a houlder	71°-71° 30′
27	Jefferson Co., N. Y., greenish; in a boulder, Hebron, Maine, light brown, transparent,	71° 40′-71° 50′
	Norwich, Mass., yellowish green transparent;	71° 45′
39.	Haddam, Conn., ib. ib.: Columbite locality.	71° 30′-71° 45′
40.	Haddam, Conn., ib. ib.; Columbite locality, E. Chester, Westchester Co., N. Y., yellowish green boulder,	710 80'-720
41.	Paris, Maine, ib. ib.,	72° 15′-72° 80'
42.	ib. ib., ib.,	72° 80'
48 .	Brunswick, Maine, whitish brown, silvery,	72° 37′-72° 50′
	Gouverneur, N. Y.? fair rose color; no lithia,	73°–78° 5′
	Paris, Maine, whitish green; with green tourmaline,	74°-74° 80′
46.	ib. ib. another,	73°
47.	Orange, N. H., gray, with flattened tourmaline, quartz and	****
40	feldspar,	730 74'
₹0.	Pounal, Maine, nearly colorless; lithia? mica.	74° 50-75′

49. Goshen, Mass., yellowish green; with indicolite, 50. ib., another, 51. Lenox, Mass., rose-colored lithia (f) mica; with albite,	Apparent Angle. 75° 75° 30'-76° 75°-75° 30'
2. American Phlogopite.	
 Pope's Mills, St. Lawrence Co., N. Y., glassy transparent, Edwards, N. Y., rich reddish brown, St. Lawrence Co. N. Y., yellowish, Vrooman's Lake, N. Y., in long crystals of a yellow color, Edward's, N. Y., rich yellowish brown color, Edward's, N. Y., rich yellowish brown color, Warwick, Orange Co., N. Y., in limestone, yellowish, Falls of the Grand Calumet, Canada, yellowish green crystals many inches long, Pope's Mills, St. Lawrence Co., N.Y., large crystals, fine yellowish brown, Edwards, N. Y.; 2d specimen, yellowish brown, Churches Mills, Rossie, N. Y., resembles the Pope's Mills, Near Skinner's Bridge, Rossie, N. Y., silvery yellow mica, Carlisle, Mass., rich yellowish brown, Rossie, N. Y., near Mrs. Story's, light yellowish, Pope's Mills, St. Lawrence Co., brownish yellow hexagonal crystal, Natural Bridge, Jefferson Co., N. Y., rich yellow; associated with serpentine; same as analyzed by Meitzendorff, bis. ib. ib., another specimen, Elwards, N. Y., white silvery, curved crystals, Vicinity of Rossie, N. Y., rich yellow brown; probably the same as Gouverneur, Essex, N. Y., in limestone, deep rich brown color, Upper Ottawa, Canada, reddish yellow transparent, Moriah, Essex Co., N. Y., very dark smoky red, Gouverneur, N. Y., brownish copper red; Pope's Mills, Somerville, N. Y., faint brownish, Burgess, Canada West, bronzy, almost metallic, semi-transparent if thin; opake in plates a line thick; slightly elastic only, found with apatite in sandstone, Franklin, N. J., bronzy yellow, Fine, St. Lawrence Co., N. Y., very dark olive brown, 	70-7° 80′ 10° \$ 10° \$ 10° \$ 10° \$ 10° \$ 10° \$ 11° \$ 11° \$ 18°-18° 12′ 18° 30′ 13° 30′ 13° 30′ 14° 14° 15° 15° 15° 16° 15° 30′-16° 30′ 16° 7′-16° 15′ 16° 30′ 17° 30′-18° Estd. 16°-17° 5°-7° Angle very low. About 1.0° Estd. 10°-12° 10° 12° 12° 12° 12° 12° 12° 12° 12° 12° 12
 Amity, N. Y., opake silvery white, Sterling Mine, Morris Co., N. J., rich yellowish brown, inclining to red: in limestone. Suckasunny Mine, N. J., deep olive brown, inclining to yel- 	10°–12°
low; in limestone. 30. Newton, N. J., yellow; imperfect and very small; in limestone.	
31. Lockwood, Sussex, Co., N.J., deep olive brown, like the mica of Fine, N. Y.; in limestone.	et event Residen

Nos. 20 to 27 are less transparent, and the observations are not exact. Besides the above American phlogopites, there is another found at Oxbow, N. Y., a brownish olive green variety at Warwick, Pa., of about 10°; a reddish coppery variety from St. Jerome, Canada, mentioned by Blake, (p. 221.)

Pb Cl 55.177. Pb O 44.300, Moisture 0.072=99.549.

Rammelsberg found, (Pogg. lxxxv, 141), Pb Cl 52:45, Pb O 46:42. Decrepitates when heated. B.B. fuses to a grayish-yellow globule.

From the old mine of Cromford near Matlock, with cerasine. Largest crystals an inch square and one-eighth thick.

MENDIPITE, Breit. Chlorid of Lead. Berzelite, Levy. Kerasine, Beud. Cerasite.

Trimetric; $I: I=102^{\circ} 36'$. Observed planes, $O, I, \tilde{n}, \tilde{n}$. Occurs in fibrous or columnar masses, often radiated. Cleavage I, highly perfect, diagonal less perfect.

H.=2.5—3. G.=7—7.1. Lustre pearly and somewhat adamantine upon cleavage faces. Color white, with a tinge of yellow, red or blue. Streak white. Feebly translucent—opaque.

Composition.—Pb Cl+2PbO=Chlorid of lead 38'4, oxyd of lead 61'6 Analyses: 1, Berzelius, (K. V. Ac. H. 1823, Pogg. i, 272, and Ramm. 1st Supp. 24); 2, Schnatter bel, (ib. 8d Supp. 78):

1. Pb Cl 39:82 PbO 60:18=100, Berzelius by Rammelsberg.
2. " 38:74 61:26=100, Schnabel.

B.B. decrepitates slightly, and readily fuses, producing a globule of a deeper yellow color than the original specimen. On charcoal, lead may be obtained. Treated with peroxyd of copper and salt of phosphorus, the flame assumes an intensely blue color. Easily soluble in nitric acid.

This rare mineral occurs at the Mendip Hills, in Somersetshire, on earthy black manganese. Also at Tarnowitz, Silesia, in clay in opaque prismatic crystals; and near Brillon in Westphalia.

B. Hydrous Oxyds.

DIASPORE GROUP.—Ratio of oxygen of oxyd and water 8:1. Trimetric.

私住 MAGANITE, Min H. (1 Min H.). DIASPORE, Göthite, ₽e Ĥ. POLIANITE, ! ₩n Ĥ.

LIMONITE GROUP.—Ratio of oxygen of oxyd and water 2:1.

Fe' H'. LIMONITE,

BRUCITE GROUP.—Ratio of oxygen of oxyd and water, 1:1. Hexagonal.

BRUCITE. Йg Ĥ. GIBBSITE. 五ì 中·

Appendix.—Völknerite, Mg. Al+16A.—Psilomelane, & Mn. A.—Wad. Combination of Oxyds and Chlorids.—ATACAMITE, Cu Cl+8Cu H.


DIASPORE. Hauy. Dihydrate of Alumina, Thom. Stephanite.

Trimetric. $I: I=93^{\circ} 52', O: 1\bar{\imath}=147^{\circ} 38', a:b:c=0.634:1$: 1.07. Observed planes as in the figures.

 $\begin{array}{lll} \textbf{\textit{O}}: \ 1 = 139^{\circ} \ 3'. & 1 : 1 \ (\text{mas.}) = 126^{\circ} \ 50'. & \textbf{\textit{i}} \$

Crystals usually thin flattened prisms, sometimes acicular; commonly implanted. Cleavage ii, eminent; also $i\overline{2}$ less perfect. Occurs foliated massive.

H = 6.5 - 7. G = 3.3 - 3.5; 3.4324, Hauy; 3.452, Duf.; 3.30-3.34, Schemnitz diaspore. Lustre brilliant and pearly on cleavage faces; elsewhere vitreous. Color greenish-gray or hair-brown, yellowish to colorless, sometimes violet-blue in one direction, reddish plumb-blue in an-



other, and pale asparagus-green in a third. cent—subtranslucent. Very brittle. When thin, translu-

Composition.—Alfi=95 l alumina, 14 9 water. Analyses: 1, 2, Dufrénoy, (Ann. des Mines [3], x, 577, 1837); 3, Hess, (Pogg. xviii, 255); 4, Damour, (Comptes Rend. xxi, 322; ; 5, Lowe, (Pogg. lxi, 307); 6, 7, J. L. Smith, (Am. J. Sci. [2], xi, 58); 8, Damour, (L'Institut, 1853, 78):

	æl	Ħ	Fе	₿i _
 Siberia, 	74.66	14.58	∓ e 4·51	2.90, Ca and Mg 1.64=98.29, Duf.
2.	78.93	15.13	" 0.52	1·39, Ca 1·98=97·95, Duf.
3. Miask,	85.44	14.56		==100, Hess.
4. Siberia,	79.91	14.90		unattacked 5.80=100.61, Dam.
Schemnitz,	85.131	15.00		—=100 131, Löwe. G.=3:308.
6. Gumuch-dagl	h,83·12	14.28	0.66	0.82 Ca, Mg, trace=98.88, S. G.8.45.
7. Naxos,	82.94	14.81	1.06	_ 0.26 Ca 0.35=99.42, S.
8. Bahia, S. A.,	84 ()2	14.59	∓ e 0:68	Si 0.43=99.72, Damour. G.=3.464.

In a matrass decrepitates strongly and separates into small white scales; finally yields water. B.B. infusible. With borax and salt of phosphorus dissolves slowly to a clear colorless glass. Not acted on by soda. A fine blue with cobalt solution. Not at all altered by concentrated and boiling sulphuric acid, except after calcination.

Occurs in chlorite slate, near Koroibrod, district of Katharinenburg in the Ural, and at Schemnitz in veins between dolomite and limestone; also at Broddbo near Fahlun; with corundum in dolomite at St. Gothard; at Gumuch-dagh and Manser, Asia Minor, and the Grecian Islands Naxos, Samos, and Nicaria, with emery, as detected by J. L. Smith.

GUTHITE, Bend Pecheisenerz, (in part). Nadeleisenerz, Naum. Pyrrhosiderite, Haus. Onegite. Lepidokrokite. glimmer. Eisenrutil. Chileit, Breith. Sammetblende. Stilpnosiderite. Rubin-

Trimetric. I: I=94°52', B. and M. (95° 14', Levy, 96° Yorke), $O: 17=146^{\circ} 33', a:b:c=0.66:1:1.089.$

- $O: 3_3 = 115^{\circ} 44'$. $O: 1_i = 148^{\circ} 48'$. $1\overline{2}: 1\overline{2}(\text{mac.}) = 151^{\circ} 35$,
- $i\bar{2}: i\bar{2}=130^{\circ} 40'$.
- $0: 1_2 = 143^{\circ} 55'$. $0: \frac{5}{22} = 121^{\circ} 8'$. $0: 1_{-1200}$ 8'. $1:1(brach.)=121^{\circ}4'.$ ii: i(ov.ii)= $122^{\circ}52'$. $0:1=138^{\circ}6'$.



In prisms longitudinally striated, and often flattened parallel to the shorter diagonal. Cleavage: brachydiagonal, very perfect. Also fibrous; reniform; foliated or in scales; massive.

H.=5-5.5. G.=4.0-4.4. Lustre imperfect adamantine. Color yellowish, reddish, and blackishbrown. Often blood-red by trans-

mitted light. Streak brownish-yellow-ochre-yellow.

Composition.—Fe H=Peroxyd of iron 89.89, water 10.11. Analyses: 1-5, Kobell, (J. f. pr. Chem. i, 181, 319); 6, Brandes, (Nög. Geb. in Rheinl. Westph. i, 358); 7, Breithaupt, (J. f. pr. Chem. xix, 103); 8, Yorke, (Phil. Mag. [3], xxvii, 264):

```
## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe ## Pe
```

Before the blowpipe the varieties act like limonite.

The Lepidokrokite occurs in minute radiating crystals, or granular scales and feathery aggregations, imbedded in fibrous red oxyd of iron, in quartz, and in nodules of chalcedony. It has been found at Spring Mills, Montgomery County, Pa. The Göthite of Eiserfeld, in the County of Nassau, occurs in foliated crystallizations, (Rubinglimmer), of a hyacinth red color, with brown hematite. Other localities of Göthite are at Clifton, near Bristol, near Lostwithiel, and Botallack, in Cornwall, and at Lake Onega (Onegite) in Siberia, at Oberkirchen in Westerwald, Zwickau in Saxony, Eiserfeld in Siegen, Przibram, &c. A capillary variety (Sammetblende) occurs at Przibram and elsewhere. Stilpnosiderite occurs amorphous and stalactitic or massive. H.=45-5. G.=36-38; pitch-black and blackish-brown. Some specimens, according to Vauquelin's and Ullmann's analyses, are Limonite. The Bammetblende has been called Przibramite, from Przibram, where it occurs.

MANGANITE. Gray Manganese Ore. Gray Oxyd of Manganese. Acerdèse, Beud. Grauer Bräunstein. Manganese Oxydè, H. Newkirkite, Thomson.

Trimetric. $I: I=99^{\circ} 40', O: 1i=147^{\circ} 9\frac{1}{2}'; a:b:c=0.6455:1:1.185.$ Hemihedral in plane $\frac{6}{3}2$.


```
O: 2\overline{\imath} = 127^{\circ} \ 46'. O: 2\overline{\jmath} = 128^{\circ} \ 18'. 1\overline{\jmath}: 1\overline{\jmath}: (mac.) = 162^{\circ} \ 39'. O: 1\overline{\jmath} = 144^{\circ} \ 9'. O: 1\overline{\jmath} = 144^{\circ} \ 59'. 1: 1(mac.) = 130^{\circ} \ 49'. i\overline{\jmath}: i\overline{\jmath}: (mac.) = 118^{\circ} \ 48'.
```

 $O: 1 = 139^{\circ} 49'$. 1:1(brach)=120°54'. $i\vec{3}: i\vec{3}$ (br.)=136° 54'.

Twins: plane of composition 1%. Cleavage: ii very perfect, I perfect. Crystals longitudinally striated and often grouped. Also columnar and granular.

II.=4. (1.=4.2-4.4. Lustre submetallic. Color dark steel gray—iron-black. Streak reddish-brown, sometimes nearly black. Opaque; minute splinters, sometimes brown by transmitted light. Fracture uneven.

					0				
10	13	12	-	1	1				11
			-			62			
21				2		23			
îī		iž	14	I	$i\frac{3}{2}$	iğ	<u>i5</u>	iš	iĭ



Composition.—MnH=Mn 89 79, (=Mn 62 78, O 27 22), H 10 21. Analyses: 1, Arfvedson, (Schw. J. xxvi, 262); 2, Gmelin, (ib. xlii, 208); 3, 4, Turner, (Edinb. Trans' 1828):

1. West Gothlan	d, 89-92	0	10.08, Arfvedson.
2. Ihlefeld,	62.86	27.64	9:50, Gmelin.
8. "	62.68	27.22	10·10, (by loss), Turner.
4. "	62.77	27.13	10.10, " Turner.

B.B. alone fusible; with borax yields a violet-blue globule. Insoluble in nitric acid; in muriatic acid gives off chlorine, and dissolves without a residue.

Occurs in veins traversing porphyry, associated with calcareous spar and heavy spar, at Ihlefeld in the Hartz; also at Ilmenau and Ochrenstock in Thuringia; in Aberdeenshire; at Undenaes in Sweden, and Christiansand in Norway.

Newkirkite, according to Lettsom, is nothing but manganite. Volger endeavors

New Mirkite, according to Lettsom, is nothing but manganite. Voiger endeavors to show that the analyses of manganite are doubtful with regard to the water, and probably correspond to \$\frac{\mathbf{H}}{m}\$ \hat{H}^2\$, like Xanthosiderite, (Stud. z. Entw. 391).

Altered Forms.—By loss of water changes to pyrolusite, hausmannite, or braunite. Varvacite of R. Phillips, from Warwickshire, is considered an altered manganite, consisting largely of pyrolusite. Analysis by Phillips afforded, Mn 63.3, O 31.7, H 5.0. Breithaupt observed a crystal with nearly the angles of manganite, giving I: I=80° 24' and 99° 36'. H.=2.5—3. G.=4.283—4.623.

POLIANITE, Breit.

Trimetric. $I: I=92^{\circ} 52^{\circ}, 0: 17=147^{\circ}, 43'; a:b:c=0.6317:$ 1:1.0513. Observed planes O, I, ii, ii, iz, iz, iz, 1i, 2i. 1i: 1i= 118°, 0:11=149°. Cleavage: brachydiagonal, perfect. H.=6.5-7. G.=4.84-4.88. Resembles pyrolusite.

Composition .- Plattner obtained, (Pogg. lxi, 192),

MnMn 87 274, O 12 111, Fe and XI 0 165, quartz 0 132, H 0 318=100, and this is the composition of pyrolusite, or Mn. But according to Volger (Stud. z. Entw. Min.) it is an altered MnH, it being isomorphous with Göthite.

Occurs near Platten in Bohemia, also at Schneeberg, Geyer, and Johanngeorgenstadt in Saxony, and in Siegen; near Schwarzenberg, and near Ilmenau in Thuringia.

LIMONITE, Beud. Brown Hematite. Brown Iron Ore. Hydrous Peroxyd of Iron. Brown Ochre. Iron Stone. Yellow Clay Iron Stone. Brauneisenstein, Thoneisenstein, W. Gelberde. Eisenoxydhydrat. Brauner Glaskopf. Bog Iron Ore. Raseneisentein (bog ore), Morasterz, Sumpferz. Bohnerz.

Usually in stalactitic and botryoidal or mammillary forms, having a fibrous or subfibrous structure; also massive and occasionally earthy.

H = 5 - 5.5. G = 3.6 - 4.Lustre silky, often submetallic; sometimes dull and earthy. Color various shades of brown, commonly dark, and none bright. Streak yellowish-brown.

Composition. - Fe 113=Peroxyd of iron 85.6, water 14.4=100. The bog iron ore is often mixed with phosphates, (sometimes 10 or 11 per cent.), and also with some salts of organic acids formed in marshy ground. Analyses: 1, 2, Kobell; 3, 4, Karsten, (Arch. xv, 1); 5, Hermann, (J. f. pr. Ch. xxvii, 53):

15:01 1:61=100, Kobell. 88:88 Perm, fibrous, 18'46 0'67, P 8'00, Mn. Cu, Ča trace=100, Kobell. 28'40° 2'80, "0'12, Fe 3'6, Mn 0'75=100, Karsten. 29'50° 8'60, "3'90, "10'8, "175, Sand 22'75, Kar. Siegen, Pitchy Ore, 82.87 Bog ore, New York, 66:33 "Neumark, 57:50 8. 13 00 Mn 100, P 3 50, humic acid 2 5, Sand 47 5, Her. 5. Novgorod, 32.75 With organic substances.

Hermann writes for the last (his Quellerz) the formula Fe H=Fe 74.8, H 25.2. A very pure stalactitic limonite from Amenia, N. Y., gave Beck, (Min. N. Y. p. 33), Peroxyd of iron 82.90, silica and alumina 3.60, water 13.50, with a trace of oxyd of manganese. In a limonite (bohners) from Staatswald Hardt, Württemberg, A. Muller found (J. f. pr. Chem. lvii, 124) 0.05 per cent. of chromic acid, and 0.03 per cent. of vanadic acid.

In a matrass yields water. B.B. blackens and becomes magnetic and thin splint-

The following are the principal varieties of this species. Brown hematite includes compact mammillary and stalactitic varieties. Scaly and ochrey brown iron ore are decomposed earthy varieties, often soft like chalk; yellow ochre is here included. Bog iron ore is a brittle or loosely aggregated submetallic ore, occurring in low marshy grounds. It proceeds from the decomposition of other species, and often the form of the leaves puts. takes the form of the leaves, nuts or stems, found in the marshy soil. Brown and yellow clay iron stone are hard and impure from admixture with clay or iron.

Limonite occurs in secondary or more recent deposits, in beds associated at times with spathic iron, heavy spar, calcareous spar, aragonite, and quartz;

and often with ores of manganese.

Found in Cornwall, Clifton, Sandloge in Shetland, in Carinthia and Bohemia, at Siegen near Bonn, and at Villa Rica in Brazil. The bog ore forms large beds in

Germany, Poland, and Russia.

This ore is abundant in the United States. We mention a few only of its localities, and would refer to the various geological reports for more complete lists. Extensive bods exist at Salisbury and Kent, Conn., also in the neighboring towns of Beckman, Fishkill, Dover, and Amenia, N. Y., and in a similar situation north at Richmond and Lenox, Mass. At Hinsdale it is the cement in a conglomerate quartz rock. It is very abundant at Bennington, Vt., also at Monkton, Pittsford, Putney, and Ripton, of the same State. Nantucket and Martha's Vineyard are other localities; also near Tinder's Gold Mine, Louisa Co., Va, there is an abundant deposit; at Birmingham and elsewhere, Mo. The argillaceous varieties are abundant in Pennsylvania, near Easton, and through the Lehigh range in Favette Co., at Armstrong, Upper Dublin, and in Washington Co. In nodules from one inch to a foot in diameter, it is met with at Bladensburg, Md.; also in gravel hills, near Marietta in Ohio. An argillaceous ore is also found on Mount Alto, in the Blue Ridge, in Shenandoah Co., Va., and in Chatham and Nash Co., N. C.: also near the Iron Mountains, Missouri.

Limonite is one of the most important ores of iron. The plg iron, from the purer varieties, obtained by smelting with charcoal, is readily convertible into steel. That yielded by bog ore is what is termed cold short, owing to the phosphorus present, and cannot therefore be employed in the manufacture of wire, or even of sheet iron, but is valuable for casting. The hard and compact nodular varieties are employed in polishing metallic buttons, &c.

Turgite, Hermann, a reddish-brown mineral from the Turginsk Copper Mines in the Urals, and the Altai afforded Fe 94:15, Il 5:85, whence the formula Fo Il

=sesquoxyd of iron 94.7, water 15.3. G.=3.54-3.74. It may be only a red hematite.

Kaliphite, Ivanoff. A mixture of brown iron ore, oxyd of manganese, and sili-

cate of zinc with lime, from Hungary.

ALTERED FORMS.—By deoxydation through organic matter, if carbonic acid is present, may form spathic iron, (Ca C). By losing water becomes hematite, (Fe). Hematite occurs as pseudomorphs after limonite. This species forms numerous vendomorphs of other spaces (see under Chemical Mineralem) pseudomorphs of other species, (see under Chemical Mineralogy).

XANTHOSIDERITE, E. E. Schmid, (Pogg. lxxxiv, 495).—In fine needles or fibres stellate and concentric. Golden yellowish-brown to brownish-red, silky or greasy in lustre. H.=2.5.

Composition.—Fe H². Analyses by E. E. Schmid, (loc. cit.):

₩n 1. Yellow, 74.96 1.32 1.82 2.51 15.67=96.28, 2. Brown, 75:00 1:51 1:33 5:02 14:10=96:96,

leaving a loss due to undetermined carbonate of lime, magnesia, alkalies, antimony, and lead or bismuth, present as impurities.

Occurs associated with manganese ores at Ilmenau.

BRUCITE. Native Hydrate of Magnesia, Bruce's Min. Jour. i, 26. Native Magnesia, Cleav. Talk-Hydrat. Magnesia-hydrat. Magnésie Hydratée, H. Nemalite, Amianthoid Magnesite, Nuttall, Am. Jour. Sci. iv, 19, 1822.

Rhombohedral; $R: R=82^{\circ}$ 15', $O: R=119^{\circ}$; a=1.527. Observed angles $O: R=119^{\circ}$ —119° 55', $O: 2R=105^{\circ}$ 30'. Cleavage: basal, eminent, folia easily separable. Usually foliated; massive. Also fibrous, fibers separable and elastic.

O R 2 R 2

H.=1.5. G.=2.35, Haidinger. Lustre pearly. Color white, inclining to gray, blue, or green. white. Translucent—subtranslucent. Sectile. Thin flexible.

Composition.—Mg H=Magnesia 68.97, water 31.03. Analyses by Bruce, (Min. Jour. i, 26); Wurtz, (This. Min. 3d edit., 682); Stromeyer, (Untersuch, p. 467); Thomson, (Min. i, 157), J. D. Whitney, (Jour. Bost. Soc. Nat. Hist. 1849, p. 36), Wurtz, (loc. cit.) Rammelsberg, (Pogg. lxxx, 284):

. 1	loboken.	Hoboken.	Swinaness.	Hoboken.	Swinaness.	Nomalite,	Nemalile,	Nomalite.
Мg	70	69.11	66.67	68.345	67:98	62.89	66.05	64.86
Ħ	80	30.42	30.39	80.902	30.96	28.36	30.13	29:48
Мn	_		1.57	0.837	} 1.57			
Mg H Mn Fe Ca	-	0.47	1.18	0.116	5 101	_ 4.65	5.68	_ 4.05
Ca	-		0.19			C 4·10		Bi 0·27

100, B. 100 00, W. 100 00, S. 100 00, S. 100 51, T. 100 00, Wh. 101 81, W. 98 65, R.

The fibrous variety is called Nemalite.

B.B. loses weight, becomes opaque and friable, but does not fuse. In the matrass gives off water. Entirely soluble in the acids without effervescence; gives the test of magnesia.

Brucite accompanies other magnesian minerals in serpentine. Occurs in considerable veins traversing serpentine, at Swinaness in Unst, one of the Shetland Isles, where it is sometimes found in regular crystals; at Pyschminsk in the Urals, and at Goujot in France. It is also found in the same rock at Hoboken, N. J., opposite the city of New York, in veins which are sometimes an inch in width, rarely in minute polished crystals, as above figure; also in Richmond Co., N. Y., and on the peninsula east of New Rochelle, Westchester Co.

The fibrous variety (nemalite) occurs at Hoboken, and Xettes in the Vosges. This mineral was discovered and described by the late Dr. Bruce of New York. ALTERED FORMS.—Changed through carbonated waters, to hydromagnesite, as at Hoboken.

GIBBSITE, Torrey, N. Y. Med. and Phys. Jour. 1, 68. Hydrargillite, G. Rose, Pogg. xlviii, 564. Felsobanyite.

Hexagonal; in small crystals with replaced lateral edges and eminent basal cleavage. Planes vertically striate. Occasionally in lamello-radiate spheroidal concretions. Usually stalactitic or small mammillary and incrusting, with smooth surface and often a faint fibrous structure within.

II.=3-3.75. G.=2.3-2.4; from Richmond, 2.385, B. Silliman, Jr.; Hydrargillite of the Ural, 2.287, Hermann. Color white, grayish, greenish, or reddish-white. Lustre of O pearly; of surface of stalactites faint. Translucent. A strong argillaceous odor when breathed on. Tough.

Composition.—Alfi*=Alumina 65.56, water 84.44. Analyses: 1, Torrey, (loc cit.); 2, 3, 4, B. Silliman, Jr., (Am. Jour. Sci. [2], vii, 411); 5, 6, Smith and Brush, (Am. Jour. Sci., [2], xvi, 51, 1853); 7, Hermann, (J. f. pr. Chem. xl, 11); 8, Kobell, (J. f. pr Chem. xli, and l, 491):

		X l	Ĥ	P
1.	Richmond, Mass.,	64.8	84.7	=99·5, Torrey.
2.	"	63:446	84· 4 77	Mg 0.3, insol. 1.777=100, B. S.
8.	"	64.955	34 (73	0.590 Mg 0.3, insol082=100, B. S.
4.	"	64.160	34.151	trace Mg 0.3, insol. 1 627=100 238, B. S.
5.	44	64.24	3376	Si 1.33, P 0.57, Mg 0.10, Fe tr=100, S. & B.
6.	"	63.48	34.68	"1.09, " tr " 0.05, " tr==99.30, S. &B.
7.	Hydrarg., Ural.	64 03	34.54	1.43=100, Herm.
8.	" Villa Rica.	65.6	84.4	—=100. Kobell.

Silliman, Jr., did not find the phosphoric acid attributed to the Gibbeite by Hermann, and ascertained that the silica of Thomson's analyses was due to a mixture with allophane, with which mineral it is often associated. More recent results

confirm this fact. The species hydrargillite therefore falls into Gibbsite.

In a matrass, yields water. B.B. infusible; on charcoal decrepitates, becomes opaque, and crystals exfoliate; phosphoresees. A fine blue with cobalt solution.

Dissolves wholly in concentrated sulphuric acid.

The crystallized gibbsite (hydrargillite of authors) was discovered by Lissensko in the Schischimskian mountains near Slatoust in the Ural. The larger crystals was a late 2 inches long. This species occurs with covardum at Guynnah-dech tals were 1 to 2 inches long. This species occurs with corundum at Gumuch-dagh, Asia Minor; also on Corundum of Unionville, Pa.; in Brazil, resembling wavellite. The stalactitic occurs at Richmond, Mass., in a bed of limonite; also at Lenox, Mass.; at the Clove mine, Union Vale, Duchess Co., N. Y., on limonite; in Orange Co., N. Y.

This species was named after Col. George Gibbs, the original owner (after extensive foreign travel) of the large Gibbs' cabinet of Yale College.

Appendix to Hydrous Oxyds.

VÖLKNERITE, Hermann, J. f. pr. Chem. xl, 11, and xlvi, 257.

Hexagonal. Cleavage: basal, eminent; lateral, distinct. Also lamellar massive.

G.=2.04. Color white. Lustre pearly, and feel greasy.

and affords a clear colorless glass.

Occurs at the mines of Schischimsk, district of Slatoust, implanted on tale schist.

Named in honor of Captain Völkner.

Hydrotalcite of Hochstetter, (J. f. pr. Ch. xxvii, 376) is referred to Völknerite by Hermann, (ib. xlvi, 237.) part of the alumina being replaced by peroxyd of iron, =Mg^o(Al, Fe) +16H. It is a foliated pearly mineral, translucent, or in thin folia transparent, with a greasy feel, and hardness=20. Hochstetter obtained #11200, Fe 6.90, Mg 36.30, H 32.06, C 10.54, insoluble 1.20

insoluble 1.20=99.60.

It occurs at Snarum in Norway.

Houghite of Shepard, (Am. J. Sci. [2], xii, 210), resembles Völknerite, and is probably the same compound. The color is white; lustre faint, pearly. H.=2.5. G.=2.0-2.1. It is the material of pseudomorphous 333 A

spinel, near Oxbow, and in Rossie near Somerville, St. Lawrence Co., New York. The crystals are in all conditions from the pure spinel to octahedrons with rounded edges and pitted or irregular surfaces, and it also occurs in flattened nodules. The surfaces are also occurs in flattened nodules. The surfaces are sometimes soft and altered, when the edges or angles have the hardness of spinel. Mr. S. W. Johnson, who has redescribed the mineral, obtained in one analysis, (Am. Jour. Sci., [2], xii, 363), Ål 19743, Mg 36:292, (28:458, insoluble spinel, &c., 8:264, silica 3:020, water (by diff.) 24:223. The whole loss by ignition in one trial was 40:86 p. c. This would give 33 to 34 p. c. of water. He observes that his results are not satisfactors and that he intended competing them. They

tory and that he intended completing them. They are sufficient to show a close relation to the above species. It is associated with dolomite, spinel, phlogopite, graphite and serpentine in crystals, (pseudomorphous.)

PSILOMELANE, Haid. Compact and Fibrous Manganese Ore. Black Hematite. Compact Gray Oxyd of Manganese. Black Iron Ore. Schwarzeisenstein, W. Schwarzbraunstein, Haus. Schwarzmanganerz, L. Hartmanganerz. Manganese Oxydé Hydraté Concretionné, H.

Massive and botryoidal.

H.=5-6. G=3.7-4.328. Lustre submetallic. Streak brownish-black, shining. Color iron-black, passing into dark steel-gray. Opaque.

Composition.—R Mn³+H mixed with Mn, Ramm., a large part of the superoxyd being considered mechanically combined. Analyses: 1, 2, Turner, (Edinb. Trans. xi); 3, Fuchs, (Schw. J. lxii, 255); 4, Rammelsberg, (Handw. ii, 73); 5, Clausbruch, (Ramm. 1st Supp. 121); 6, Scheffler, (Arch. d. Pharm. xxxv, 260); 7, Ebelmen, (Ann. d. Mines, [3,] xix, 155); 8, Rammelsberg, (Pogg. lxviii, 512):

	Man Min	0	Вa	Ŕ
1. Schneeberg,	69.80	7.86	16.36	-, Si 0.26, H 6.22=100, Turner.
2. Romanéche,	70.97	7.26	16.69	—, Si 0.95, H 4.13=100, Turner.
3. Baireuth,	81.8	9.5	-	4.5, H 4.2=100, Fuchs.
4 Horhausen,	81.36	9.18	-	3 04. Si 0:53, Cu 0:96, Fe 1:43, Ca 0:38, Na
J. C. Tono				and Mg 0:32, H 3:39=100:61, Ramm.
5. Ilmenau,	77-23	15.82	0.13	5-29, Ca 0-91, Ca 0-40, Si 0-52=100-29, Cl.
6. "	83.3	3.8	5.8	
				991, Scheffler.

Йn 0 405, Mg 105, Fe 077, Si 0-60, H1-67= 7. Gy, H. Saône, 70.60 14.18 6.55 99.47, Ebelmen. 8.08 2.62, Ca 0.60, Mg 0.21, Cu 0.30, Co 0.54, 8. Heidelberg, 70.17 15.16 Si 0.90, H and loss 1.43=100, Rammelsberg.

In analyses 5 and 6, Rammelsberg considers 50 and 40 per cent. of the superoxyd of manganese a mixture, and a similar allowance is made by him for the others. As the mineral occurs only massive, the nature of the species cannot be satisfactorily ascertained. No. 7 contains potassa as well as baryta. No. 5 is anhydrous.

B.B. yields water, gives a violet color to borax, and is completely soluble in muri-

This is a common ore of manganese. It is frequently in alternating layers with pyrolusite. It occurs in botryoidal and stalactitic shapes, in Devonshire and Cornwall; at Ihlefeld, in the Hartz; also at Johanngeorgenstadt, Schneeberg, Ilmenau, Eglersburg, Siegen, etc.

It forms mammillary masses, at Chittenden, Irasburgh, and Brandon, Vt.

Named from ψιλος, smooth or naked, μελας, black.

NEWKIRKITE.

Occurs in small needles, under the microscope apparently rectangular prisms. H.=3-3.5. G.=3.824. Lustre metallic, splendent. Color a brilliant black. Opaque. Rather sectile.

Composition.—According to Muir, (Thom. Min. i, 509): An 56:30, Fe 10:35, H 6:70 **=103** 35.

Forms a coating on red Hematite at Newkirchen, in Alsace.

EARTHY COBALT. CUPREOUS MANGANESE. Earthy Manganese. Bog Manganese. Manganschaum. Groroilite, Brithier. Schaumartiger Wad-Graphit, M.—Erdkobold. Schwarzer Erdkobalt, Haid. Cobalt Oxide Noir, H. Asbolan, Breit. Kakochlor, Breit.—Kupfermanganerz. Lampadite.

The manganese ores here included occur in amorphous and reniform masses, either earthy or compact, and sometimes incrusting or as stains. They are mixtures of different oxyds and cannot be considered chemical compounds or distinct mineral species.

H.=0.5-6. G.=3-4.26; often loosely aggregated and feeling very light to the hands. Color dull black, bluish or brownish

Composition.—Rammelsberg considers them related essentially to Psilomelane under the formula R Mn+H (or H2), but mixed with other ingredients.

Wad or Bog Manganese consists mainly of oxyds of manganese and water, with some oxyd of iron, and often silica, alumina, lime or baryta. Groroilite occurs in roundish masses of a brownish-black color and reddish brown streak; it is from Groroi in Mayenne, Vicdessos and Cautern, in France. Hardness sometimes 6 to 6.5.

Cupreous Manganese (Kupfermanganerz) contains, besides hydrous oxyds of manganese, 14 to 25 per cent. of black oxyd of copper, and 4 to 18 per cent. of oxyd of cobalt, with various impurities. G =3:1-3:2.

Pelokonite is a variety of cupreous manganese, having a liver-brown streak; H. =3; G.=2·567.

Earthy Cobalt (Asbolan) is a wad in which oxyd of cobalt sometimes amounts to

Analyses: 1, Klaproth, (Beit. iii, 311); 2, 3, Turner, (Edinb. J. Sci. N. S., ii, 213); 4, 5, Berthier, (Ann. Ch. Phys. li, 19); 6, Wackenroder, (Kasta, Archiv. xiii, 302, xiv, 257); 7, Scheffler, (Arch. d. Pharm. xxxv, 260); 8, Rammelsberg, (Pogg. lxii, 157); 9, Igelström, (Jahresb. xxv, 342); 10, 11, Beck, (Rep. Min. N. Y., p. 55);

SODALITE.

Monometric. In dodecahedrons; also f. 17, 18, 38, 39, 43. Cleavage: dodecahedral, more or less distinct. Twins: hexagonal prisms arising from a combination of dodecahedrons. Also massive.

H.=5.5—6. G. 2.26, Vesuvius; 2.289 Ural; 2.37, Greenland. Lustre vitreous inclining to greasy. Color gray, greenish, yellowish, white, and sometimes blue, lavender-blue. Subtransparent—translucent. Fracture conchoidal—uneven.

Composition.—Na³Si+3 Xl Si+Na Cl=(Na+Xl)Si³[+1Na Cl=Silica 37.2, alumina 31.7, soda 19.1, sodium 4.7, chlorine 7.8=100. The name alludes to the soda. J. D. Whitney suggests that the color may be owing to ferric acid present.

Analyses: 1, Ekeberg, (Thomson's Ann. Phil. i, 104); 2, Thomson, (Trans. Royal Soc.; Edinb. i, 890); 3, Arfvedson, (Jahresb. ii, 97); 4, Hofmann, (Pogg. xlvii, 877); 5, 6, Whitney, (Pogg. lxx, 431); 7, v. Borc, (Pogg. lxxviii, 413):

		Si	X 1	Na	HCl	₩e
1.	Greenland,	86.00	32·00	25.00	6.75	0·15=99·90, Ekeberg.
2.	"	38.52	27.48	23.50	3.00	1.00, Ca 2.7, ign, 2.1=98.80, T.
8.	44	33.75	85.20	26.23*	5.30	=100 78, Arfvedson.
4.	Ilmen Mount.	38.40	32.04	24.47	7.30	—, Ca 0·32=102·53, Hofmann.
5.	Litchfield, Me.,	37.30	32·88b	23.86	Cl 6.97,	K 0.59=101.60, Whitney.
6.	"	37.63	30.93	25.48	Fe 1 08,	rest undetermined, Whitney.
7.	Lamö, Norway,	38.86	30.82	22.03	K 0.51,	Ca 1.21,Mg0.44,Cl undet. =93.87,B.
	With some K.		b With	₽e.		^c Traces of Sn Mn, W, Mo.

The sodalite from Greenland fuses with difficulty before the blowpipe. The sodalite of Vesuvius forms a colorless glassy globule. Gelatinizes with nitric or muriatic acid.

Sodalite is met with in mica slate, granite, trap, basalt, and volcanic rocks.

Sodalite occurs in Greenland in mica slate, along with feldspar, hornblende, and endialyte; at Vesuvius in white translucent dodecahedral crystals; massive and of a gray color imbedded in trap at the Kaiserstuhl in Brisgau; also near Lake Laach; in Sicily, Val di Noto, with nepheline and analcime; at Miask, in the Ural, blue in granite with elæolite and feldspar; in nodular masses at Lamö near Brevig, Norway, with elæolite, of a lavender-blue color. A blue variety occurs at Litchfield, Me., massive with distinct cleavage, associated with elæolite, zircon, and cancrinite.

Bergemann obtained for a greenish mineral occurring with elæolite at Brevig in Norway, (Pogg. lxxxiv, 492), Si 46 03, \(\frac{1}{4} \) 23 97, \(\hat{N}a \) 21 48, \(\hat{Cl} \) 7 43, \(\hat{P} \) 0 86, \(\hat{Ca} \), \(\frac{1}{4} \) 8i 4 \(\hat{N}a \) 8i 4 \

ALTERED FORMS.—Sodalite occurs altered to Kaolin, like the feldspars.

LAPIS LAZULI. Lasurstein. Ultramarine.

Monometric. In dodecahedrons. Cleavage: dodecahedral, imperfect. Commonly massive, compact.

H.=5.5. G.=2.38—2.45. Lustre vitreous. Color rich Berlin or azure-blue. Translucent—opaque. Fracture uneven.

Composition.—A silicate of soda, lime, and alumina, with a sulphuret probably of iron and sodium. Analyses: 1, Klaproth, (Beit. i, 189); 2, Gmelin, (Schw. J. xiv., 329); 3, Varrentrapp, (Pogg. xlix, 515):

```
        Ši
        Š
        ±1
        Fe
        Ča
        Na
        H

        1. 460
        40
        14·5
        30
        17·5
        —
        20 Č 10·0=97·0, Klaproth.

        2. 49·
        2·
        11·
        4.
        16·
        8·
        — Mg 2=92, Gmelin.

        8. 45·50
        5·89
        31·76
        —
        3·52
        9·09
        0·12 Fe 0·86, Cl 0·42, S 0·95=98·11, V.
```

The above ores are results of the decomposition of other ores—partly of oxyds, and partly of manganesian carbonates. They occur at the localities above mentioned, and many other places. Wad or Bog manganese is abundant in the counties of Columbia and Duchess, N. Y., at Austerlitz, Canaan Centre, and elsewhere, where it occurs as a marsh deposit, and according to Mather has proceeded from the alteration of brown spar; also in the southwest part of Martinsburg, Lewis Co., in a swamp. There are large deposits of this bog manganese at Blue Hill Bay, Dover, and other places in Maine.

Earthy Cobalt occurs with cobalt pyrites at Riechelsdorf in Hesse, Saalfeld in Thuringia, at Nertschinsk in Siberia; at Alderly Edge in Cheshira. An earthy co-balt occurs at Mine la Motte, Missouri, which contains 10 or 11 per cent of over

Earthy Cobalt occurs with cobalt pyrites at Ricchelsdorf in Hesse, Saalfeld in Thuringia, at Nertschinak in Siberia; at Alderly Edge in Cheshire. An earthy cobalt occurs at Mine la Motte, Missouri, which contains 10 or 11 per cent. of oxyd of nickel, besides oxyd of cobalt and copper with iron, lead and sulphur; also near Silver Bluff, South Carolina, affording 24 per cent. of oxyd of cobalt to 76 of oxyd of

manganese.

Cupreous manganese is found at Schlackenwald, and at Camsdorf near Scalfeld; at Lauterberg in the Harts; *Pelokonite*, a variety of it, H.=3, G.=2.5—2.6, is from Chili, where it occurs with Chrysocolla, (Richter, Pogg. xxi, 591; Kersten, Schw. J. kwi, 7).

ATACAMITE, Jameson. Selskupferers, W. Remolinite, B. and M.

Trimetric. $I: I=112^{\circ}$ 20', $O:1\overline{\imath}=131^{\circ}$ 29'; $a:b:c=1\cdot131:1:1\cdot492$. Observed planes, $I, 1, 1\overline{\imath}$ $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$, $i\overline{\imath}$; $i\overline{\imath}$ (ov. $i\overline{\imath}$) = 106° 34', $i\overline{\imath}$: $i\overline{\imath}$ (ib.)=139°4', $1\overline{\imath}$: 1\(\times\$ (top)=105° 40', $I: 1=143^{\circ}$ 42', 1: 1 (mac.)=126° 40'. Usual in modified rectangular prisms, and rectangular octahedrons. Cleavage: $i\overline{\imath}$ perfect, $1\overline{\imath}$, imperfect. Occurs also massive lamellar.

H.=3=3.5. G.=4-4.3; 3.7, Breit. Lustre adamantine—vitreous. Color various shades of bright green, rather darker than emerald, sometimes blackish green. Streak apple-green. Translucent—subtranslucent.

Composition.—Cu Cl+8Cu H=Oxyd of copper 55.8, chlorid of copper 31.5, water 12.7=100. Others, as that of Cobija, afford the formula Cu Cl+8CuH=Oxyd of copper 49.6, chlorid of copper 27.9, water 22.5=100. Analyses: 1, Berthier, (Ann. d. Mines, [3], vii, 542); 2, Ulex, (Ann. Ch. u. Pharm. lxix, 361).

1. Bolivia, Cobija, Cl 14-92 50-00 21-75, Cu 18-28-200, Berthier.
2. Chili, "16-13 56-23 11-99 "14-56, \$\vec{8}{11}\cdot 10-100, Ulex.

B.B. tinges the flame bright green or blue, and gives off fumes of muriatic acid; on charcoal, the copper is reduced to the metallic state. In acids easily soluble.

This species was originally found in the state of sand in the Atacama province, northern part of Chili. It occurs in different parts of Chili, especially at Los Remolinos; also in veins in the district of Tarapaca, Bolivia; at Tocopilla, 16 leagues north of Cobija, is an important locality in Bolivia; with malachite in South Australia; it also invests some of the lavas of Vesuvius and Etna, being formed by the action of the volcano; Schwarzenberg in Saxony, is another locality.

It is sometimes ground up in Chili, and sold under the name of Arsenillo, as sand for letters.

```
Νi
                                                 র
                                                                X١
                                                                                      16 56, $\hat{F}e 1 \cdot 50, $\frac{\mathbf{M}}{m} n 1 \cdot 00, $\text{HS } 8 \cdot 00 == 99 \cdot 11, $\text{B}, $12 \cdot 24, $\hat{F}e 1 \cdot 15, $\frac{\mathbf{M}}{m} n 0 \cdot 50, $\text{HS } 1 \cdot 50 == 99 \cdot 59, $\text{B}. $17 \cdot 84, $\hat{F}e 0 \cdot 04, $\text{Cl } 0 \cdot 65, $\text{H } 1 \cdot 85 == 99 \cdot 22, $\text{Var.}$
1. Lake Laach, 38.50 8.16
                                                            29.25 1.14
2.
                                37.00 11.56
                                                            27.50 8.14
8.
                                             9.17
                                                             82.57
                                                                           1.12
                                85-99
                                               7.66
                                                                           1.09
                                                                                        23·12, Fe 0·44, Cl 0·61, ign. 1·37=100·34, W.
                                86.52
                                                            29.54
5.
                                                            29.42 1.62 22.97, Fe 0.44, Clo.61, ign. 1.37=100.99, W.
                                86.23
                                             7.18
```

B.B. loses color and fuses on the edges. Gelatinizes in acids, yielding no sulphuretted hydrogen.

From near Andernach on the Rhine, at Lake Laach, in loose blocks consisting largely of a glassy feldspar, with mica, magnetic iron, and occasionally zircon, the nosean occurring in cavities in the feldspar, in small grains or crystals; also found at Rieden and Volkersfeld in a leucite rock.

SKOLOPSITE, Kobell, J. f. pr. Chem. xlvi, 484.

Massive, imperfectly grauular; no trace of cleavage.

H.=5. G.=2.53. Color grayish-white, pale reddish-gray. Translucent in thin splinters. Rather brittle. Fracture splintery.

Composition.—R²Si²+Xl Si+1NaS. Analysis by Kobell, (loc cit.):

Si &l Fe, Fe Mn Ca Mg K Na S 41·13 15·42 2·49 0·86 15·48 2·23 1·30 10·06 4·09, with 7·78 of sodalite.

B.B. fuses with intumescence like idocrase, and forms a shining blebby greenish-white glass. With borax dissolves to a colorless glass. A sulphur reaction with sods on charcoal. Reaction of chlorine with salt of phosphorus and oxyd of copper. A trace of water which is not acid. In muriatic acid easily gelatinizes.

From Kaiserstuhl in Brisgau, with some carbonate of lime and magnetic iron.

LEUCITE, Werner. Amphigene, H.

Monometric. Usual form the trapezohedron, (f. 39). Cleavage: cubic, very imperfect. Surfaces of crystals even, but seldom shining. Often disseminated in grains; rarely massive granular.

H.=5.5-6. G.=2.483-2.49. Vitreous. Ash-gray or smokegray, white. Streak uncolored. Translucent-opaque. Fracture conchoidal. Brittle.

Composition.— $K^{2}Si^{2}+3$ \overline{K} $\overline{S}i^{2}=(K+\overline{A}1)\overline{S}i^{\frac{3}{2}}=Silica$ 55·1, alumina 23·4, potash 21·5=100. Analyses: 1—4, Klaproth, (Beit. ii, 39); 5, Arfvedson, (Afhandl i Fys. vi, 139); 6, Avdejev, (Pogg. lv, 107):

	B i	₹ì	依
1. Vesuvius.	58-750	24.625	21.350=99.725, Klaproth.
2. "	53.50	24.25	20.09=97.84, Klaproth.
8. Pompeii,	54.50	23.50	19:50=97:50, Klaproth.
4. Albano,	54	23.	22-99, Klaproth.
5. Vesuvius,	56.10	28.10	21·15, Fe 0·95=101·80, Arfvedson.
6. "	56-05	23.03	20.40, Na 1.02, Ca trace=100.50, Avdejev.

B.B. infusible, except with borax or carbonate of lime, with which it melts with difficulty to a clear globule. A fine blue with cobalt solution.

Leucite is abundant in trachyte between Lake Laach and Andernach, on the Rhine. Vesuvius, however, presents the finest and largest crystallizations. Near Rome, at Borghetta to the north, and Albano and Freezati to the south, some of the class to the algorithm of the company of it. older lavas appear to be almost entirely composed of it.

The Leucitic lava of the neighborhood of Rome has been used for the last two thousand years at least, in the formation of mill-stones. Mill-stones of this rock have lately been discovered in the excavations at Pompeii.

Named from heuros, white, in allusion to its color; and because its form is similar to a common variety of garnet, it has been designated white garnet.

ALTERED FORMS.—Feldspar and Kaolin occur with the form of Leucite, as a result of its alteration. Leucite changed to glassy feldspar has been observed at Mt. Somma by Scacchi.

Berzeline, Neckar. Occurs in octahedrons and cubo-octahedrons, and in twiss like f. 200; faces often uneven or rounded. Cleavage: cubic, tolerably perfect. Also massive. Colorless, gray, white, vitreous; H.=5. G.=2727—2428, Gmelia B.B. fuses with difficulty to a blebby glass; with borax a clear glass. In muristic acid soluble, and heated forms a jelly. Said to be near leucite in composition. Occurs in peperino at Mt. Albano and Marino, near Rome.

NEPHELINE, H. Sommite, P. Nefelina, Monticelli. Cavolinite, Mont. Davyse, Mont. Beudanite, Covelli. Pseudo-nephelin. Elseolite. Fettstein, W. Pierre

Fig. 10, 120. Observed planes and angles, Hexagonal. (Scacchi): O on $\frac{2}{3}$, 158° 54'; on $\frac{1}{2}$, 154° 15½'; on $\frac{2}{3}$, 147° 16'; on 1, 136° 2'; on 2, 117° 24'; on 4, 104° 32'; on 6, 99° 48'; besides also the form 42, and prisms, I, i2, i3. O: $42 = 120^{\circ}$ 54', I: $i\frac{3}{2} = 160^{\circ}$ 53'. Cleavage: I distinct, O imperfect. Also massive, compact; also thin columnar.

H.=5.5-6.G.=2.5—2.64, Nepheline and Electrical Lustre vitreous—greasy; little opalescent in some varieties. Colorless. white or yellowish; also when massive, dark green, greenish or bluish-gray, brownish and brick-red. Transparent-opaque. Fracture subconchoidal.

Nepheline includes the crystallized varieties from Vesuvius; Elecolite the coarse massive varieties having a greasy lustre.

Composition.—(Ña, K)² Si+2 Xl Si=(Ña, K+Xl)Si⁴ =(if Ña: K=5: 1) Silica 44.4, alumina 33.6, soda 16.9, potash 5.1=100.

Analyses: 1, Arfvedson, (Jahresb. ii, 97); 2, 3, 4, Scheerer, (Pogg. xlvi, 291, xlix, 359); 5, Gmelin, (Neph. im Dolerit, &c., Heidelberg, 1822); 6, Heidefreim, (J. f. pr. Chem. 1, 500); 7, Monticelli and Covelli, (Prod. min. Vesuv. 375, and Pogg. xi, 40); 80.1 10 Schoope, (Pogg. xlvi) 201 xlix, 380): 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 11 12 Republic, (Pogg. xlvi) 301 xlix, 380); 301 xlix, 380); 301 xlix, 380); 302 xlix, 380); 302 xlix, 380); 303 xlix, 380 xlix, 380 xlix, 380); 303 xlix, 380 8, 9, 10, Scheerer, (Pogg. xlvi, 291, xlix, 359); 11, 12, Bromeis, (Pogg. xlviii, 577); 18, Smith and Brush, (Am. J. Sci., [2], xvi, 371):

I. Nepheline.

	₿i	Æl	₽e	Ċа	Ňа	ĸ	Ĥ	
1. Vesuvius, ~	44.11	8878		_	20.46		0.62=98.92, Arfred	
2. "	44.08	33.28	0.65	* 177	15·4 4	4.94	0.21=100.32 Scheer.	
8. "	44.29	33.04	0.39	* 1·82	14.98	4.72	0.21=99.40 "	
4. Odenwald,	43.70				15.83		1.39=100.74	
5. "	43.86	38.49	1.50	0.90	13.36	7.18	1 ·39=101 ·13, Gmelin.	
6. Löbau,	43.50	32 ·3 8	1.42	3.22	14.18	5.03	0.82, Mg 0.11=10039, Heid	
7. Davyne,	42.91	33.28	1.25	2.02		7.48	=96.89, M. & C.	
* With M n.								

BISMUTH OCHRE. Oxyd of Bismuth. Wismuthochre, W. Bismuth Oxydé, II.

Crystalline form not observed. Occurs massive and dissemina-

ted, pulverulent, earthy; also passing into foliated.

G.=4.3611, Büsson. Lustre adamantine—dull, earthy. Color greenish-yellow, straw-yellow, grayish-white. Fracture conchoidal—earthy.

Composition.—Bi=Oxygen 10.35, bismuth 89.65, along with some iron and other impurities. Analysis by Lampadius, (Handb. z. Chem. Ann. p. 286):

Oxyd of bismuth 86.4, oxyd of iron 5.1, carbonic acid 4.1, water 8.4=99.

Suckow obtained for another derived from the decomposition of aciculite, (Die Verwitt. im Min. 14), Bi 96.5, As 1.5, Fe³, H⁵ 2.0=100.

B.B. on charcoal, easily reduced to the metallic state, and subsequently the

greater part may be dissipated.

Occurs pulverulent at Schneeberg in Saxony, at Joachimstahl in Bohemia, and with native gold at Beresof in Siberia. I)r. Jackson reports an oxyd of bismuth not carbonated, as occurring with the tetradymite of Virginia. An earthy steatitic mineral from Agnes in Cornwall, afforded Macgregor, Oxyd of bismuth 28.8, carbonic acid 51.3, peroxyd of iron 2.1, alumina 7.5, silica 6.7, water 8.6.

KERMESITE. Red Antimony. Rothspiesglaserz, W. Rothspiesglanzerz, Haus.

Antimonblende, L. Antimoine Hydro-Sulfuré. Antimoine Oxydé Sulfuré, H.
Pyrantimonite, Br. Pyrostibite, Gl. Kermesome, Chapman. Kermes, B. & M.

Monoclinic. C=77° 51'; $O: ii=102^{\circ}9'$, O: 1i (plane on acute edge)= 115° 36', $O: \frac{1}{8}i=149^{\circ}$ 57'. Cleavage: basal. Usually in tufts of capillary crystals, consisting of elongated, slender six-sided prisms.

II.=1-1.5. G.=4.5-4.6. Lustre adamantine, inclining to metallic. Color cherry-red. Streak brownish-red. Feebly translucent. Sectile. Thin leaves slightly flexible.

Composition.—SbO3+2SbS3=Oxyd of antimony 80.2, sulphuret of antimony, 69.8 =100. Analyses: H. Rose, (Pogg. iii, 458, the sulphur separately determined):

Antimony 74:45, 75:66, oxygen 5.29, sulphur 20.49. 4.27. 20:49.

B.B. fuses readily on charcoal, and at last is entirely volatilized. In nitric acid it becomes covered with a white coating.

Results from the change of gray antimony. Occurs in veins in quartz, accompanying gray and white antimony, at Malaczka near Posing in Hungary, at Bräunsdorf near Freiberg in Saxony, and at Allemont in Dauphiny.

The tinder ore has been shown to be wholly distinct from red antimony.

CERVANTITE, D. Antimonoxyd. Antimonsaures Antimonoxyd. Antimonocher, in part.

In acicular crystallizations. Also massive, as a crust, or a powder.

G.=4.084. Lustre greasy, bright, or earthy. Color Isabellayellow, sulphur-yellow, or nearly white.

Composition.—SbO3+SbO3=Oxygen 19-9, antimony 80-1. Analysis by Dufrency: Sh Ča Ĉ Fe

67.50 16.85 11.45 1.50 insol. 2.70=99.80. C. Bechi obtained from needle crystals from Pereta, Tuscany, O 19:47, Sb 78:83, Fe 1:25, gangue 0:75=100:80, giving the same formula, (Amer. Jour. Sei., [2], xiv, 61).

B.B. infusible; but easily reduced on charcoal. Soluble in muriatic seid. Found with gray antimony, and resulting from its alteration at Cervantes, in Galicia, Spain, Chazelles in Auvergne, Felsobanya, Kremnitz and elsewhere in Hun-

gary.

STIBICONISE, Bond. (Antimonochre, Spieseglanzocher, Haus., Stiblite, Blum.,) is considered a mixture of valentinite, cervantite, and hydrous antimonic acid, by G. II. O. Volger, (Entwick. Min. 1854, 72). It occurs massive, and yellowish in color; H.—5.5. G.—5.28. Blum and Delffs obtained in an analysis (J. f. pr. Chem. xl, 318), O 19.54, 8b 75.83, As tr., H 4.63. From Goldkronach in Bavaria.

VOLGERITE. Hydrous Antimonic Acid. Antimonocher, in part.

A white powder or crust occurring with cervantite, and resulting from its alteration, having the formula, according to Volger, (Entw. Min., 77), 8b $0^{\circ}+5$ $\dot{H}=$ oxygen 18.8, antimony 60.3, water 21.0.

A white antimony from the province of Constantine, Algeria, analyzed by E. Cumenge, (Ann. d. M. [4], xx, 80), afforded O 17, Sb 62, H 15, Fe 1, gangue 8=98.

BLEINIERITE, Nicol. (Bleinière, Haus. Antimonate of Lead. Antimonaures Bleioxyd.) Probably a mechanical mixture of lead and antimony ochres. Occurs amorphous, reniform, spheroidal; also earthy or incrusting; structure often curved lamellar. H.=4. G.=3'938, Karsten; 4'6—4'76, Hermann. Lustre resinous, dull, or earthy. Color gray, brownish, yellowish. Streak grayish or yellowish. Opaque.

Composition. — Pb⁵ Sb+4H, according to Hermann=Antimonic acid 81.3, oxyd of lead 62.0, water 67. Analyses: 1, Plaff, (Schw. J. xxvii, 1); 2, Hermann, (J. I. pr. Chem. xxxiv, 179):

- 1. Nb 43 96, As 16 42, Pb 33 10, Ou 8 24, Fe 0 24, Si 2 34, S 0 62, Fe Mn 3 32 =108 28, P.
- 2. Bb 31-71, Pb 61-88, H 6-46=100, Hermann.

B.B. on charcoal fuses to a metallic globule, gives out fumes of antimony, and finally yields a head of lead. From Nertschinsk, Siberia, and supposed to result from the decomposition of other ores of antimony.

AMMIOLITE, D. Antimonite of Quicksilver, Domeyko. Annales des Mines, 4th ser. vi, 183. Quecksilberoxyd Antimonigsaures.

A red powder, consisting, according to Domeyko, of

No 12.5, Hg 14.0, Fe 22.8, Si 26.5, H and loss 24.7=100,

being an antimonite of quicksilver mixed with clay and hydrated oxyd of iron.

From the mines of mercury in Chili, accompanying ores of antimony, copper, and mercury. Also at Silberg, near Olpe, Westphalia, where it is produced by the decomposition of a quicksilver gray copper. The name Ammiolite is derived from against rermition.

approx, errmition.

This mineral may be only a mixture, and is therefore placed here with the oxyds, rather than among the salts.

ning to pearly; of other faces vitreous. Color white, grayish, ish. Streak uncolored. Transparent—translucent. Fracture hoidal. Brittle.

nposition.—R²Si+3<u>X</u>l Si=(R+Xl)Si²=Silica 43·2, alumina 36·8, lime, 20·0. alyses: 1, G. Rose, (Gilb. Ann. lxxiii, 173); 2, 3, Abich, (Pogg. li, 519); 4, Reint, (Pogg. l, 351); 5, Forchhammer, (Jahreeb. xx, xxiii, 284); 6, Waltershausen, Gest., 22); 7, Erdmann, (Ofv. K. V. Ak. F. 1848, 67); 8, Nordenskiöld, xii, 174); 9, Svanberg, (Jahreeb. 238); 10, Chenevix; 11, Laugier, (Mem. us. d'hist. nat. vii, 341); 12, G. J. Brush, (Am. J. Sci. [2], viii); 13, 14, Her, (J. f. pr. Chem. xlvi, 387); 15, Damour, (Bull. G. Fr., [2], vii, 83); 16, Her, (J. f. pr. Ch. xlviii, 254); 17, 18, C. Gmelin, (Pogg. iii, 68):

```
₽e
                        <del>X</del>l
It. Somma,
                 44:49 34:46 0:74 15:68
                                                5.56
                                                                 -=100.63, G. Rose.
                                                       0.25 0.27=100.04, Abich.
                 44.12 35.12 0.70 19.02
                                                0.56
"
      "
                                                       0.54 0.68=100.84, Abich.
                 43.79 35.49 0.57 18.93
                                                0.34
                                                      - 0.6 =98.1, Reinw.
0.29 1.09=101.89, F.; G. 2.70.
                 46.0 87.0
                                     1.45
AVA.
                47.63 32.52 2.01 17.05
                                               1.30
eland,
                 45·14 32·10 2·03 18·32 ₩n0·78*
[ecla.
                                                      0.22 1.06, ign. 0.31=99.96, W.
                                                      0.52 0.89, ign. 0.39, Fe 1.35, undec. 0.57=100.19, E.
northite,
                43.34 35.37
                                  - 17·41 Mg0·35
                                                               –, Fe 1·70, Ĥ 1·85, Ň.
Imphod. Fin.
                45.80 35.45
                                                5.05
                                                          — —, ign. 0.6=100.23, S.

— 3.35, H 1.0=98.55, Ch.

— 2.6, H 1.0=97.7, Lang.
    Tunaberg, 44.55 85.91 0.07 15.02
                                                4.08
adianite, red,
               42.00 84.00 3.20 15.00
         white, 43.0 34.5 1.0 15.6
                 42.09 38.89 -
                                   - 15.78
                                                          - 4.08=100.84, Brush.
apol., Lojo,
                                                       1.50 —, ign 1.56=99.69, H.
1.69 —, ign 1.50=99.54, H.
                 42.80 35.12 1.50 14.94
                                               2.27
    Orrijervi, 42.50 33.11 4.00 10.87
                                                5.87
celand,
                                                          - 1.85, augite 0.69=100.12,
                45.97 33.28 1.12 17.21
                                                                                Delesse.
                                                      3·00 2·53, Fe 2·00, H 7·00, H.
6·58, Mn 3·16, H 2·04=102·16.
                                               8.85
inseite
                42.22 27.55 6.98
atrobite,
                44.65 36.81
                                      8.28
                                               0.63
                                               5.77b 6.58, H 2.04=98.78, Gmelin.
                41.78 32.83 ---
                                      9.79
            · With Ca and Ni.
                                                         b With Min.
```

b. like albite, except that it forms with soda an enamel. Entirely decomposed risatic acid, but anorthite does not gelatinize. Indianite gelatinizes readily. sphodelite [fr. $a\mu\phi\omega$, both, and obshos, a spear] is a reddish gray or dingy peachm-red variety, occurring crystallized and massive, with the angle $O: \tilde{n}=85^{\circ}$ and cleavage parallel to O and \tilde{n} . Indianite has a granular texture somewhat statuary marble, a glistening surface of fracture, and occurs massive. The scleave parallel to two planes inclined to one another 84° 45', which is not om the angle of anorthite, considering the difficulty in this case of obtaining atly accurate measurement.

orthite (Biotine) occurs at Mount Vesuvius, among the old lavas in the ravines onte Somma, associated with ice spar, augite, mica, and idocrase. Also on the l of Procida near the entrance to the bay of Naples; in the Faroe Islands, and

ephodelite occurs at Lojo, Finland, and at Tunaberg, Sweden. The Lepolite Lojo and Orrijerfvi, is the same mineral; the crystals are sometimes two s long; and Linseite is probably the same partly altered, containing a few ent. of water. The Indianite is from the gangue of the corundum in the tic, and is associated with garnet, kyanite, and hornblende. The specimen zed by G. J. Brush, was originally from the hands of Count Bournon, came from the Indian locality. Genth's Thiorsauite from Iceland has considered the same mineral that was analyzed by Forchhammer, (analysis 5); 688. H.=6. Color white to grayish. Genth obtained \$\tilde{\text{Si}}\$ is 48.36, \$\tilde{\text{Al}}\$ 80.59, 37, \$\tilde{\text{Mg}}\$ 0.97, \$\tilde{\text{Mn}}\$ in trace, \$\tilde{\text{Ca}}\$ 17.16, \$\tilde{\text{Na}}\$ 1.18, \$\tilde{\text{K}}\$ 0.62=100.20. Walmstedt's "Scapfrom Tunaberg is Anorthite, according to G. Rose, (Kryst. Chem. Min. 88). nineral from Bytown, U. C., analyzed by Tennant, has been referred to ampho. He obtained

MOLYBDINE, Lettsom and Greg. Molybdena Ochre. Molybdanocher, Karsten. An earthy yellow powder or incrustation.

Composition.—Mo=Oxygen 34 29, molybdenum 65 71.

B.B. on charcoal fuses to a slag. With borax forms a colorless glass in the outer flame and a brown glass in the inner. Reduced with soda. Easily soluble in muriatic acid, and the solution is rendered blue by metallic iron.

Occurs with molybdenite, from which it is probably derived, at the foreign localities of this species; also at Westmoreland, N. H., and Chester, Delaware Co.,

Pennsylvania.

Molybdate of Iron !—Deep yellow and sub-fibrous, or in tufted imperfect crystals; and also pulverulent. According to an imperfect analysis by D. D. Owen, (Proc. Ac. N. Sci. Philad., vi, 108), contains Mo 40, Fe 35, Mg 2, Alkali 8, H 15. B.B. fuses easily. From the gold region, California, near Nevada City.

III. OXYGEN COMPOUNDS OF CARBON, BORON, AND SILICON.

CARBONIC ACID,	Ö.
Sassolin,	B.
Quartz,	Si

CARBONIC ACID.

Gaseous. G.=1.5245. Colorless. Taste, slightly acid. Excites a pungent sensation in the nostrils, and destroys life.

Composition.—C=Carbon 27.27, oxygen 72.73. Extinguishes combustion. Evolved from many mineral waters, and also about some volcanoes. The Saratoga and Ballston waters owe their briskness to this gas, which is constantly escaping. The mineral waters of Germany are famous localities. Near Naples, on lake Albano, there is a small cave called Grotto del Cane, which is filled with carbonic acid to the level of its entrance; the lake is supposed to occupy the crater of a volcano and the hot baths of San Germano are situated on its banks.

SASSOLIN, Rouse. Boracic Acid. Acid boracique, H.

Triclinic. $I: I=118^{\circ} 30', O: I=95^{\circ} 3', O: I=80^{\circ} 33'$ B. and M. Twins, compounded parallel to the base. Cleavage: basal very perfect. Usually in small scales, apparently six-sided tables, and also in stalactitic forms, composed of small scales.

H.=1. G.=1.48. Lustre pearly. Color white, except when tinged yellow by sulphur; sometimes gray. Feel smooth and Taste acidulous, and slightly saline and bitter.

Composition.—BH³—Boracic acid 56.4, water 43.6. The native stalactitic salt, according to Klaproth, (Beit. iii, 97), contains mechanically mixed, sulphate of magnesia and iron, sulphate of lime, silica, carbonate of lime, and alumina. Erdmann has stated, (J. f. pr. Ch. xiii, 7, 8), that sassolin contains 3.18 per cent. by weight of ammonia, and instead of being pure boracic acid, that it is a borate of

145 QUARTZ.

Fuses in a candle, and at first tinges the flame green; but this color disappears when the water of crystallization has evaporated. The cooled globule is glassy, and


opaque if any gypsum is present.

Found abundantly in the erater of Vulcano, one of the Lipari isles, forming a layer on the sulphur, and around the fumaroles or exits of the sulphureous exhalations. It is obtained for the arts from the volcanic fumaroles of Tuscany. The first locality known was at Sasso, whence the name, Sassolin. The hot vapors at the lagoons or boiling springs of Tuscany, consist largely of boracic acid. The vapors are made to pass through water, which absorbs the boracic acid; the waters are then evaporated by means of the steam from the springs. They yield seven to eight thousand pounds troy per day.

These lagoons spread over a surface of about 30 miles, and in the distance, clouds of vapor are seen rising in large volumes among the mountains. On approaching the places, the earth seems to pour out boiling water, as if from volcances of various sizes, and the heat in the immediate vicinity is intolerable and the sulphurous smells suffocating. (Am. Jour. Sci. xxxvii, 1836, 270, and [2], ix, xi, 199; Quart. J. Geol. Soc. vi, 367.)


QUARTZ, Flint. Silex. Chalcedony. Agate. Jasper. Hornstone. Cat's Eye. Amethyst. False Topaz. Rose Quartz. Prase. Chrysoprase. Cantalite. Iron Flint. Heliotrope. Eisenkiesel. Berg-crystal. Kalzedon.

Rhombohedral. $R: R=94^{\circ} 15', O: R=128^{\circ} 13'; \alpha=1.0999.$



i: 65=167° 59' $R: 1-(\text{ov. }i)=103^{\circ} 34'.$: 3=154° 43' i: 88 = 171° 8' R: -1 (adj.)=133° 44'. : 2=158° 31' i: 13 13 = 174° 39' R: i (ov. 22) = 113°8.: 3=165° 18' $\begin{array}{c} i: \frac{4}{3} \frac{4}{3} \text{ (ov. 22)} = 125^{\circ}28' \quad R: 22 = 151^{\circ} \text{ 6'}. \\ i: \frac{9}{4} \frac{9}{8} \text{ (ov. 22)} = 118^{\circ}7' \quad R: \frac{9}{8} \frac{9}{8} = 175^{\circ} \text{ 1'}. \\ i: i = 120^{\circ} \quad -1: \frac{4}{3} \frac{4}{3} = 167^{\circ} \text{ 40} \end{array}$: 22=142° 2' $R: \frac{9}{8} \frac{9}{8} = 175^{\circ} \cdot 1' \cdot 11 = 167^{\circ} \cdot 40'$ $i: 3\frac{3}{2} = 154^{\circ} 55'$ i: 44=161° 31' i: i6=171° 33'

Cleavage: R, -1, and i very indistinct; sometimes effected by plunging a heated crystal into cold water. Twins: face of composition, o, (basal plane); plane truncating pyramidal edge, (f. 342); R, (f. 343 A, B, (Rose), opposite views of the same crystal). The two crystals in twins compounded parallel to o, some




times penetrate one another very irregularly, while the external planes are regular and even. Also f. 345, 346, metagenic twins, (p. 131). Figs. 188, 189, 193 represent distorted crystals. Also stalactic and mammillary forms. Often massive, either impalpable, or coarse granular. Sometimes coarsely tabular and reticulated.

H.=7. G.=2·5—2·8; 2·6413—2·6541, Beudant; 2·6701, Hauy. Lustre vitreous, sometimes inclining to resinous; splendent—nearly dull. Colorless, when pure; often various shades of yellow, red, brown, green, blue, black. Streak white, of pure varieties; if impure, often the same as the color, but much paler. Transparent—opaque. Fracture perfect conchoidal—subconchoidal. Tough—brittle—friable.

OLIGOCLASE. Soda Spodumene. Natron-spodumene, Berz. Unionite, Silliman, Jr.

Triclinic. I: I' about 120°, $O: \tilde{i} = 93^\circ$ 15′, $O: I' = 115^\circ$ 37′. Cleavage: O, \tilde{i} very distinct. Twins common.

			0				
ñ	iğ	I		ľ	$i \S'$	ñ	
28'			21	2'		21	
		1	11	1'			
Observed Planes.							



H.=6. G.=2.58—2.69. Lustre vitreous, vitreo-pearly or greasy. Color yellowish, grayish, reddish, greenish-white, white. Transparent, subtranslucent. Fracture conchoidal—uneven.

Composition.—R Si+Xl Si²—(R+Xl)Si⁸—Silica 62·3, alumina 23·5, soda 14·2=100.

Analyses: 1, 2, Berzelius, (Jahresb. iv, 14⁷, xix, 302); 3, Laurent, (Ann. Ch. Phys.lix, 108); 4, R. Hagen, (Pogg. xliv, 329); 5, Rosales, (Pogg. lv, 109); 6, Francis, (Pogg. lii, 470); 7, Chodnev, (Pogg. lxi, 390); 8, Wolff, (J. f. pr. Chem. xxxiv, 234); 9, Scheerer, (Pogg. lxiv, 153); 10, 11, Kersten, (J. f. pr. Ch. xxxvii, 173, Leonh. Jahrb. 1845, 653); 12, Deville, (Compt. Rend. xix, 46); 13, Forchhammer, (Skand. Nat. S. Stockholm, 1842); 14, L. Svanberg, (Œfv. K. V. Ann. Ferrh. iii, 111); 15, Rammelsberg, (Pogg. lvi, 617); 16, 17, 18, Delesse, (Ann. Ch. Ph. [3], xxiv, Bull. Geol. [2], vii, 310, Ann. d. M. [4], xix, 149); 19, Kerndt, (J. f. pr. Chem. xliii, 218); 20, Smith and Brush, (Am. J. Sci. [2], xv, 211, mean of 2 analyses); 21, Bodemann, (Pogg. lv, 110); 22, 23, Smith and Brush, (loc. cit., xvi, 44, each mean of 2 anal.); 24, Walterhausen, (Vulk. Gest., 26):

		S i	X l	Fe	Ċa	Мg	Ňа	ĸ
1.	Danvikszoll,	68.70	23.95	0.20	2.05	0.65	8.11	1.20=100.16, Berz.
2.	Ytterby,	61.55	23.80		3.18	0.80	9.67	0.38=99.38. "
3.	Arriége,	62.6	24.6	0.01	3.0	0.5	8.9	=99.4, Laurent.
4.	Arendal,	68.51	23.09		2.44	0.77	9.37	2·19=101·37, Hagen.
5.	Arendal, yelw.	62.70	23.80	_	4.60	0.02	8.00	1.05, $Fe0.62 = 100.79$ R.
6.	Ajatskaja,	61.06	19.68	4.11	2.16	1.05	7.55	3.91=99.52, Francis.
7.	Kimito, red,	63.80	21.31		0.47		12.04	1.98=99.60, C.
8.	Schlw. Holstein,	64.30	22.34		4.12		9.01	—=99·77, W.
9.	Sunstone fr. Tved	.61.30	23.77	0.36	4.78	_	8.50	1·29==100, Scheerer.
10.	Near Frieberg,	62.97	23.48	0.21	2.83	0.24	7.24	2.42=99.69, Kersten.
11.	Marienbad,	63.20	23.50	0.31	2.42	0.25	7.42	2·22==99·32, Kersten.
	Teneriffe,	62.97	22.29		2.06	0.54	8.45	8.69==100, Deville.
18.	Hafnefjordite,	61.22	23.32	2.40	8.82	0.36	2.56	tra.=98.68, Forch.
14.	* "	59.66	23.28	1.18	5.17	0.36	5.61	175, ign.1.02, und.0.82
								=98.85, Sv.
15.	Warmbrunn,	63.94*	23.71	tra.	2.52	tra.	7.66	2·17=100, Ramm.
16.	Mer-de-glace,	63.25	23.92	tra.	8.23	0.35	6.88	2.31, Mntra. = 99.91, D.
17.	Quenast,	6370	22.64	0.28	1.44	1.20	6.12	2.81,ign.1.22=99.69,D.
• Loss,								

Si Ca 1.21,ign.1.70=98.68,D. 18. Visembach, 63.88 22-27 0.21 3.45 tra. 6.66 3.08=,Mn0.40=100,K 19. Boden, 61-96 22.66 0.35 2.02 0.10 9.43 20. Unionville, Pa., 64.27 21.21 tra 0.81 0.58 10.94 1-36, ign.1-08=100-28 21. Schaitansk, Ural, 64.25 22.24 0.54 2.57 1.14 7.98 1.06=99.76, Bodenn. 68.76 22.56 tra. 3.09 tra. 9.72 0.55, ign. 0.26=99-94, 22. Danbury, Ct. 23. Haddam, Ct. 64·26 21·90 — 2·15 tra. 9·99 0·50 ign. 0·29, 8. d B. 24. Borodin, Finland, 63·20 18·41 0·20 0·11 0·87 0·52 14·41 "0·57=98·29, W. G. of No. 7, 2.63; 8, 2.651; 9, 2.656; 10, 2.65; 11, 2.631; 12, 2.59; 14, 2.69; 19, 2.65. Other analyses: Lory, (Bull. Geol. Soc. de Fr. [2], vii, 452); Damour, etc. (Ramm. 5th Supp. 178); Deville, (Et. Geol. Teneriffe, 1848).

B.B. fuses more easily than orthoclase, and quietly to a glass, either clear or enamel-like. Not acted upon by acids.

Occurs in porphyry, granite, syenite, serpentine, and basalt; with quartz and mica it forms the granite at Kimito, containing columbite. At Tenerific it occurs

in trachyte. Among its localities are Danvikszoll near Stockholm; at Arriège and Arendal, with calcite, crystals sometimes two or three inches long; at Schaitansk, Ural, greenish, in a gangue of quartz and mica and yellowish-white feldspar; at Clausthal in serpentine; at Lake Baikal; as sunstone at Christiana-fiord, Norway, the aventurine character of which is owing to minute particles of specular iron, according to Scheerer, (göthite according to Kengott).

In Iceland at Hafnefjord, (Hafnefjordite), Borodin, etc.
In the United States, at Unionville, Pa., (Unionite), with euphyllite and corundum, G.=2.61; also at Danbury, Ct., with othoclase and danburite; at Haddam, Ct., often transparent, with iolite and black tourmaline; at Mineral Hill, Delaware

Co., Pa., called Moonstone.

Named from olivos, little, and klaw, to cleave.


ALBITE, D. Cleavelandite, Brooke. Periklin, Breit. Tetartine. Kieselspath, Haus.

Triclinic. 0: ii=93° 36', over 2i=86° 24'. (B. & M.)

 $0: \frac{1}{4} = 150^{\circ} 5'.$ $ii: is' = 149^{\circ} 12'.$ I: 27=134° 32'. 0: I=115° 5'. O: I'=110° 51'. I: 27=138° 34'. 0:2%=133° 55'. $I: I'=122^{\circ} 15'$. ñ: I=117° 53'. ii: ii=148° 30'. O: 2%=137° 26'. ũ: I'=119° 52'. $O: 1i(adj.) = 127^{\circ} 23'.$ $ii: 1' = 120^{\circ} 27'.$ $O: 2i(ov, 1i) = 97^{\circ} 37'.$ $ii: 1 = 112^{\circ} 11'.$ 1: I=122° 32'. 1': I'=124° 53.

414

			0			
it	iš	I		ľ	i3'	it
211			21			21
			41			
	1	1	11	1'		
		+		#		
	_	Ohean	wad Di	-	1	




415

416

age: O very perfect; ii less so; I' imperfect. Twins: similar usually flattened parallel to ii; also similar, but with 1i and

me plane nearly, (f. 416); also parallel Also lamellar and granular: the laminæ es divergent; granular varieties occaquite fine, approaching to impalpable. ; some granular varieties 7. G.=2·59—612, Finbo, Eggertz; 2·619, Broddbo; ariety Pericline; 2·626, Peristerite. Lusrly upon a cleavage face; vitreous in irections. Color white; also occasionish, gray, reddish, greenish, and green; es having a bluish opalescence or colors on O. Streak uncolored. Transsubtranslucent. Fracture uneven. Brit-



ition.—NaŠi+ĀlŠi*=(Na+Āl)Ši*=Silica 687, alumina 195, soda 11.8=

s: 1, G. Rose, (Gilb. Ann. lxxiii, 173); 2, Stromeyer, (Untersuch. 300); ; (Ann. Ch. Phys. lx); 4, Thaulow, (Pogg. xlii, 571); 5 Abich, (Berg. u. Zeitg. 1 Jahrg.); 6, Erdmann, (Jahresb. xxi, 192); 7, Abich, (Pogg. li, & G. Gmelin, (Pogg. vii, 79); 9, Redtenbacher, (Pogg. lii, 468, mean of 3 0, Brooks, (Pogg. lxi, 392); 11, Kersten, (Leonh. Jahrb. 1845, 648); 12, and Weld, (Am. J. Sci. [2], viii, 390); 14, T. S. Hunt, (Phil. Mag. [4], i, Am. J. Sci. [2], xii, 212); 15, Diday, (Cryst. from Melaphyre of Agay, [5], ii, 184, 193); 16, Rammelsberg, (Pogg. lxxix, 305):

Ķ Ňа 0.68=97.84, G. Rose. 68.46 19.30 9.12 0.28 0.24=99.88, Stromeyer. erfield, 19.80 0.11 70.68 9.06 68.4 10.5 0.2=100, Laurent. 20.8 0.1 11:47 thard, cryst. 69 00 19.43 0.20=100.10, Thaulow. 68.45 18-71 0.27 0.65 0.50, Mg 0.18, Mn tr.= , cryst. 11.24100, A. tr., Mg, Mn tr.=1007, E. 1.26, Mg 0.51=99.83, Ab. 69.11 19.34 0.62 0.65 10.98 Pantellaria, 68-23 18:30 1.01 2.53 7.99 18.93 F 0.48 0·15, ign 0·36=100·26, G. 1·44, Mg 0·31=100·07, R. 67.94 2.41 8.88 ylvania, 67.20 19.64 1.57 9.91 thard, white, 67.39 19.24 6.77 6.28 0.31, Mg0.61 = 100.55, Bks.nbad. 68.70 17.92 1.18 11.01 0.24=99.77, Kersten. 2.05, Mg 0.52=99.42, B. 1.79, Mg 0.48, H 0.48= ster Co., Pa., 66.65 2079 9.36 21.89 878 wille, Pa., 66.86 100.27, W. lerite, 2.52, Mg 0.20, ign 0.6= 66:80 21.80 0.30 0.58 7.00 99 80, Hunt. 1.2, Mg 1.8=98.9, Diday. , cryst., 0.8 2.2 7.2 67.62 16.59 2.30 0.51 10.24 0.85, " 1.46=99.8, R. clerite, 5, G.=2.624; 11, G. 2.612; 12, G.=2.619; 15, G.=2.478; 16, G.=2.63 to

e feldspar, but colors the flame distinctly yellow. Acted on by hot acids, often replaces feldspar as a constituent of granite; in other instances it is with feldspar, as in Pompey's pillar, and then may be generally distiny its superior whiteness. The albite granites are often repositories of the granite minerals, tourmalines of different colors, beryls, allanite,

dence, (one fine crystal over 7 pounds in weight), in Chester Co.; very handsome at the Prince vein, Lake Superior, but now hardly obtainable as the mine is not worked; also very large fine crystals near Greensboro, N. C. Crystallized green quartz occurs in tale, at Providence, Delaware Co., Penn. Chalcedony and agates of moderate beauty are found in the same trap region; more abundantly about Lake Superior, the Mississippi, and the streams to the west; at Natural Bridge, Jefferson Co., N. Y.; about the Willamet, Columbia, and other rivers in Oregon; abundant and beautiful on N. W. shore of Lake Superior. Belmont's lead mine, St. Lawrence Co., N. Y., has afforded good chalcedony and chrysoprase, associated with calc spar. Red jasper is found on Sugar Loaf Mt., Maine, and in pebbles on the banks of the Hudson at Troy. Yellow jasper occurs with chalcedony at Chester, Mass. Heliotrope occupies veins in slate at Bloomingrove, Orange Co.

Quartz, chalcedony, prase, carnelian, hornstone, constitute many of the pseudomorphs formed by substitution. (see chapter on Chemical Mineralogy). Pseudomorphs, after hexagonal and scalenohedral crystals of calcite and cubes of fluor, occur at Westhampton, Mass.; after heavy spar, probably, in Rutherford Co., N. C. often filled with water. Petrified wood consists of quartz, and sometimes of chalcedony or agate, of

rare beauty.

Quartz crystals occasionally occur of enormous size. A group in the museum of the university at Naples, weighs nearly half a ton. A crystal, belonging to Sig. Rafelli of Milan, measures three and a quarter feet in length, and five and a half in circumference, and its weight is estimated at eight hundred and seventy pounds; another at Paris is three feet in diameter, and weighs eight hundred weight. About a century since, a drusy cavity was opened at Zinken, which afforded 1000 cwt. of rock crystals, and at that early period brought \$300,000. One crystal weighed 800 pounds. A group from Moose Mountain, New Hampshire, at Dartmouth College, weighs 1474 pounds, and contains 48 crystals; four of them are from 5 to

College, weighs 147½ pounds, and contains 48 crystals; four of them are from 5 to 5½ inches in diameter, ten from 4 to 4½ inches. A crystal from Waterbury, Vt., 2 feet long and 18 inches through, weighs 175 pounds.


Crystals often exhibit internal iridescences, owing to fissures or fractures. Foreign substances frequently penetrate or thoroughly permeate crystals of quartz. Oxyd of iron has already been alluded to as one of these permeating substances. Chlorite is sometimes so thoroughly intermingled, that the crystals appear to be composed entirely of this material; their hardness, however, shows their siliceous nature. Anthracite, asbestus, actinolite, tourmaline, silver and copper are other penetrating substances. Specimens containing acicular crystals of rutile are often very beautiful. The most interesting of the substances occurring in quartz are the fluids, which occupy small cavities in the interior of crystals; they are either water, peculiar resinous liquids, or mineral solutions. Mr. Allan describes a crystal of amethyst in his collection, having four cavities partly filled with a bituminous fluid; at 83° F., the fluids dilates and fills all the cavities, and on cooling reappears with ebullition. Silica is held in solution in the Geysers of Iceland and New Zealand, whose sol-

vent powers are due to their temperature, and a small quantity of alkali present.

It is also present in traces in ordinary waters, as alkaline silicates.

Several varieties of this species have long been employed in jewelry. The amethyst has always been esteemed for its beauty. Like most other stones, it is less brilliant by candle light; it appears to best advantage when surrounded with pearls and set in gold. The color of the amethyst is often irregularly diffused, as s well described by Pliny, "ad viciniam crystalli descendet albicante purpure defectu," purple, gradually fading into white. It was called amethyst, αμίθυστος, on account of its pretended preservative powers againt intoxication, from a, not, and petros, to intoxicate. This is not, however, the only amethyst of the ancients. The violet colored sapphire, the violet fluor spar, (scalpturis faciles, Plin. easily graven), and some other purple species, were designated by the same name; and it has been apposed that garnet was also included.

Cameos are in general made of onyx, which is well fitted for this kind of minia-ture sculpture. The figure is carved out of one layer, and stands in relief on another of different color. The most noted of the ancient cameos, is the Mantuan vase at Brunswick. It was cut from a single stone, and has the form of a cream pot, about seven inches high and two and a half broad; on its outside, which is of a brown color, there are white and yellow groups of raised figures, representing Cleavage: O perfect; ii less distinct; ii faint; also imperfect in the direction of one of the faces I. Twins: f. 424 and 425 face of composition, ii; f. 428 parallel to plane 2i; also parallel to O and ii. Often massive, cleavable, or granular; sometimes coarse lamellar.



```
0: i=145^{\circ} 47'.
                               O:-1=146^{\circ}30'.
                                                            ii:ii=150^{\circ}35'.
0:1i=129^{\circ}41'.
                              0:2=98^{\circ}4'.
                                                            ii: 42 = 142^{\circ} 25'.
0: 4i=116^{\circ} 33'.
                              0:is=77^{\circ}31'.
                                                            ii:-42=130^{\circ} 50'.
                              O: \frac{2}{3}i=161^{\circ} 36'.
                                                            ii: 3\hat{s} = 146^{\circ} 40'.
O: 2i=99^{\circ} 38'.
                              O: 2i=135^{\circ} 3'.
O: -2i = 139^{\circ}.
                                                             I: 2i=134^{\circ} 19'.
O: ii=116^{\circ} 7'.
                              0: ii = 90^{\circ}
                                                            I: 1i=110^{\circ} 40'.
Q: \frac{1}{2} = 150^{\circ} 52'.
                             O: I = 67^{\circ}44'.
                                                             1:1=126° 14'.
0:\bar{1}=124^{\circ}42'.
                              ii: ii=90^{\circ}.
                                                             -1:-1=142^{\circ}40'.
```

H.=6. G.=2·4—2·62. Lustre vitreous, sometimes inclining to pearly upon the face of perfect cleavage. Color white; often gray, reddish-white, flesh-red, greenish-white, green; streak uncolored. Transparent—translucent. Fracture conchoidal to uneven.

Composition.—KŠi+Al Ši²—(K+Al)Ši²—Silica 64.8, alumina 18.4, potash 16.8

Analyses: 1, Val. Rose, (Scheerer's J. viii, 244); 2, G. Rose, (Pogg. xxviii, 148); 3, Schnedermann, (Stud. Götting. v. b. Freunde, v. Hft. 1); 4, Delesse, (Ann. Ch. Phys. [3], xxv); 5, 6, 7, Abich, (Pogg. li, 528, and Berg. und hüttenm. Zeitg. Jahrg. 19); 8, Domeyko, (Ann. d. Mines, [4], ix, 529); 9, Brongniart and Malaguti, (Ann. Mines, [4], ii, 465); 10, Kröner, (Pogg. lxvii, 421); 11, Kersten, (J. f. pr. Chem. xxxvii, 162); 12, Plattner, (Pogg. xlvi, 299); 13, Evreinoff, (Pogg. xlvii, 196); 14, T. S. Hunt, (Phil. Mag. [4], i, 322, and Am. J. Sci. [2], xii, 212); 15, 16, Gmelin, (Pogg. lxxxi, 313); 17, J. D. Whitney, (Am. J. Sci. [2], xv, 440); 18, Rammelsberg, (4th Suppl. 71); 19, F. A. Genth, (Keller and Tied., iii, 486); 20—23, Smith & Brush, (Am. J. Sci., [2], xvi, 42); 24, Plattner, (Pogg. lxvii, 419);

	Si	Æì	₽e	Ĉa	Ŕ	Ňa
1. Lomnitz,		17.50				=98·25, V. Rose.
2. Sanidin, Vesuv.	65.52	19.15		0.60	1474,	with some Na, G. Rose.
8. Glassy, Dransfeld,	64.86	21.46	trace	trace	2.62	10.29=99.23, Schned.
4. Chamouni.	66.48	19.06	trace	0.68	10.52	2·30==98·99. Delesse.

tufa, in smooth and shining globular and botryoidal masses, which have a pearly Wood opal has a peculiar ligneous structure. Michaelite (from the island of St. Michaels, Azores) is a white fibrous pearly variety. Sp. gr.=1:88. Alumo-calcite is an impure opal, of a bluish milk-white color, containing 6 per cent. of lime. Some if not all the deposits of silicious earth formed of infusorial remains, consist of soluble silica, and the name Randanite has been applied to a variety, composed mainly of silica of this kind. (See analyses below).

composed mainly of since of this kind. (See analyses below).

Composition.—Silica in the soluble or gelatinizing state, but often combined with insoluble Silica; more or less hydrous, but the water is not considered essential. Analyses: 1, Klaproth, (Beit. iv); 2—6, Damour, (Bull. Geol. de France, 1848, 161); 7, Klaproth; 8, Forchhammer, (Pogg. xxxv, 331); 9, Stucke, (Rose, Bechreib, p. 78); 10, Damour, (loc. cit.); 11, Pattison, (Phil. Mag., [8], xxv, 495); 12, Damour, (loc. cit.); 13, G. J. Brush, (communicated); 14, Damour, (loc. cit.); 15, Klaproth, (Beit. iv, 156); 16, Mallet, (Phil. Mag., [4], v, 285); 17, Damour, (loc. cit.); 18, Schaffgotsch, (Pogg. Lyviii, 147); 19, Forchhammer, (loc. cit.); 20, Wrightson 18, Schaffgotsch, (Pogg. lxviii, 147); 19, Forchhammer, (loc. cit.); 20, Wrightson,

	(1) (2) (1) (2)		, , , , , ,
(An	n. Ch. Pharm. liv. 858):	-	and the second s
		S i	Ĥ
1.	Fire opal, Mexico,	92.00	775 Fe 0·25=100, Klaproth.
2.	Limpid, " G.=2.029,	91.12	8.88=100, Damour.
	Chatoyant, " 2.024,		10:10, and some combust., Damour.
4.	Geyserite, white, "	91.23	8.77=100, Damour.
5.	" gray opaque, 2 081,	92.59	7.41=100, "
6.	Silex resinite, Iceland, 2095,		7.97=100, "
7.	Menilite, Menil Montant,	85.50	11 00 Pe 0.5, Xl 1.5, Ca 0.5, Klaproth.
8.	Fire opal, Faroe,	88.78	7.97, K, Na 0.34, Ca 0.49, Mg 1.48 🛣
	•		0.99, Forch.
9.	Semi-opal, Hanau,	82.75	10 00, Fe 3 00, Ca 0 25, Al 3 50=99 50 8.
10.	Iceland, Geyser,	87 · 67	10.40, Xi, Fe 0.71, Ca 0.40, Na 0.82, K tr.,
	-		=100, Damour.
11.	Sil. incrust, N. Z. G.=1 968,	77:35	7.66, X1 970, Fe 372, Ca 174=100.17,
12.	Prec. opal, Hun., G=2.099,	93-90	6·10=100, Damour. [Pattison.
18.	Fire opal, Georgia, G.=207	, 91 ·89	5.84, \(\frac{1}{2}\) 1.40, Mg 0.92=100.06, Brush.
14.	Silex resinite, Mex., G .= 1.21,	, 95· 4 0	4.60=100, Damour.
	Yellow opal, (Pechopal) Telk		5.00, Fe 1.0, Klaproth. [=99.86, Mallet.
16.	Sil. incrust, N. Zeal.,	94.20	8.06, Xl 1.58, Fe 0.17, Ca tr., Cl Na 0.85
17.	Hyalite, Waltsch, Bohemia,	96-94	8.06, Damour.
18.	" Bohemia,	95.5	3 0, F e 0 8, Ca 0 2=99 5, Sch.
19.	Cacholong, Faroe,	95.32	8.47, K 0.07, Na 0.06, Ca 0.06, Al 0.2,
	-		Mg 0·4=:99·58, F.
20.	Semi-opal, Schiffenberg,	90.20	273, Fe 4·11, Mg 0·86, K 0·8, X 1·86,
	-		Na 0 9, S 0 31, W.
21.	" Kaschau,	92.16	H and C 5.75, Fe 2.00, Ca 0.28.
			· · · · · · · · · · · · · · · · · · ·

The precious opal of Hungary afforded Kobell 10.94 p. c. of water. A resin opal from Vourla, Smyrna, afforded Mr. G. J. Brush, 5.10 p. c. of water. G.=2.054. (This. Min. 3d edit. p. 691). Another from near Harmanjick, Asia Minor, contains, according to J. L. Smith, 3 per cent. of magnesia, besides 92 Si and 4.15 H. A hyalite, called water opal, from Pfaffenreith, afforded Schmitz 35 per cent. of water. For other analyses, see Schnabel and v. der Mark, Verh. nat. Ver. Rheinl. 1852, 377, 459, 561; Bickell, Ann. Chem. Pharm. lxx, 290.

The Randanite of Salvetat, (silice gelatineuse), corresponds to the formula Si'll when dried at 16° C. and Si'll when dried at 100° C. Fournet and Salvetat obtained, (Ann. Ch. Phys., [3], xxiv, 348):

- 1. Ceyssat, Sol. Si 87 20, H, C, and org. matters 10 00, Al and Fe 2 00, sand
- 9. Algiers, Sol. Si 80, H 9, insol. Si 648, Al 141, Fe 0.55, Ca 0.56, Na, K, and loss 2 00, S.

It occurs as a fine earth or in compact earthy masses, and consists mainly of the casts of infusoria.

The Michaelite afforded Kobell, Si 83.65, H 16.35.

B.B. opal is infusible, but gives out water and becomes opaque. Some varieties containing iron turn red.

Arenturine Feldspar is less pellucid, and has yellow and reddish internal relections.

Glassy Feldspar is a transparent variety found in trachytic and volcanic rocks, naving a perfect vitreous lustre. It has been called Sanidin, from savis, a board, the crystals being tabular; and according to Naumann, it has C=63° 55'. O: I=110°, O: F=115°. The name Ice Spar is sometimes given to a similar variety found in Vesuvian lavas; the term however includes pellucid varieties of other species of leldspar.

Other varieties are the Murchisonite of Levy, [named after Murchison, the Geologist], which is a yellowish-gray or flesh-red variety from Heavitree, near Exeter; Amazon stone, a verdigris-green variety colored by copper, from Lake Ilmen; the Leslite of Dr. Clarke, (the Hellefinia of the Swedes), which occurs at Gryphyttan in Sweden, with a peculiar waxy lustre, and deep flesh-red color; and the Vario-ite, a dark green variety, containing lighter globular particles, from river Drac in France.

Kaolin is a term applied to a clay resulting from the decomposition of feldspar. [See beyond.)

The Microcline [fr. μικρος, little, κλινω, to incline] of Breithaupt, is a variety of this species from Arendal, (Pogg. xlvii, 196). The Erythrite [fr. ερνθρος, red] of Thomson (Phil. Mag. xxii, 188, 1843) is a flesh-colored feldspar, containing three per cent. of magnesia, found in amygdaloid; G.=2.541. The Perthite of Thomson is from Perth, in Upper Canada.

Rhyacolite of Rose, (or Ryacolite), from Vesuvius, [named from praf, a lava stream], has the crystallization of feldspar, and resembles the glassy variety. G. Rose states (Kryst. Chem. Min. 88, 1852) that he suspects that in his analysis (Pogg. txviii, 143) some nepheline may have been mixed with the feldspar, as they often neeur together at the locality, and he therefore does not mention it as a distinct species in this recent work of his.

Feldspar in fine crystals is found at Carlsbad and Elnbogen in Bohemia, (twins, £ 424, 425). Ekatherinenburg in Siberia, Arendal in Norway, Baveno in Piedmont, Lomnitz in Silesia, Land's End, &c., are other localities. At the Mourne mountains in Ireland, fine specimens occur, associated with beryl and topaz. Glassy feldspar occurs in great abundance in the trachyte of the Drachenfels on the Rhine; also in the lavas which devastated the island of Ischia, near Naples, in 1302. Ice spar is found principally at Vesuvius; it may be obtained in profusion in the valley calls of Fossa Grande.

Fine crystallized feldspar occurs in New York, in St. Lawrence Co., at Rossie, two niles north of Oxbow; the crystals are white or bluish-white, and sometimes an nch across; also eight miles from Potsdam, on the road to Pierremont, where crystals a foot through are said to have been found; and near DeLong's mills in the two of Hammond, with apatite and zircon, where the Loxoclase is obtained; in Lewis Co., feldspar occurs both crystallized and massive in white limestone near Natural Bridge, with scapolite and sphene; in Orange Co., crystals near West Point; more abundant and interesting forms are found at Rocky Hill, in Warwick, with tourmaline and zircon; and at Amity and Edenville. In Saratoga Co., N. Y., at the Greenfield chrysoberyl locality, white translucent crystals, usually coated with silvery mica. In Connecticut at the gneiss quarries of Haddam and the feldspar quarries of Middletown, crystals a foot long, and six or eight inches thick; near Bradleysville, in the western part of Litchfield, crystals 2-3 inches long, abundant. In Massachusetts at South Royalston and Barre, in crystals often large; also at Three Rivers, in Palmer. The Acworth beryl locality, the tourmaline locality of Paris, Maine, are other localities of crystallized feldspar. In Pennsylvania, in crystals at Leiperville, Mineral Hill, and Chester, (chesterlite), Delaware Co.; a sunstone in Kennett Township; fine crystals of green feldspar occur on the islaud, Mt. Dessert, Me. Washington Mine, Davidson Co., N. C., in white and yellowish crystals, (anal. 19).

Massive feldspar is abundant at the above mentioned localities, besides many

Massive feldspar is abundant at the above mentioned localities, besides many others. An aventurine variety, with bright coppery reflections in spots, occurs at Leiperville. Pennsylvania. Adularia occurs at the Falls of the Yantic, near Nor-

3. Acid of the form RO2.

VI. TITANATES.

VII. CARBONATES.

4. Acid of the form $R^2 O^3$ $(RO^{\frac{3}{2}})$

VIII. OXALATES.

I. SILICATES.

I. Anhydrous.

[The different species of Silicates are widely varied in their characters through the mutual replacements of lime, potash, soda, magnesia, protoxyd of iron, and other protoxyds, represented by the general expression (B;) and also of the peroxyds, alumina, peroxyd of iron, etc. (B). The mere presence of one or another of these bases affords therefore no ground for distinctions in classification. The only general fact of a constant character is the almost total absence of magnesia from the feldspars, (and also the zeolites), and, in fact, from all those species in which the protoxyds and peroxyds are to one another in the ratio of 1:1, (1B:1B) that is, which have 1:3 for the oxygen ratio.

I divide the anhydrous silicates, as has been explained, into a few grand groups, dependent on the oxygen ratio for the oxygen of the bases and silica; these ratios being 1:3, 1:2, $1:1\frac{1}{2}$, 1:1, $1:\frac{3}{4}$ or less than $\frac{3}{4}$.)

The feldspars, although seemingly unconformable to this system, still have been shown to have the type-ratio 1:1, this occurring in Anorthite; the additional silica in the other species, being added without changing the crystallization or typical structure.

A general principle is here indicated which modifies the law of ratios, and which is exemplified also in the micas, scapolite, hornblende, and some other species.

It has been observed that while some species contain water, without its affecting the crystalline form, so there are silicates, not hydrous, in which there is an addition of accessory substances which do not modify the form, and which substances thus appear to be in a certain sense unessential. Thus Sodalite, Hauyne and Nosean, have each the ratio 1:3:4, and a common formula, with the addition of some Na Cl for Sodalite, Ca B for Hauyne, and Na S for Nosean. By considering these as ingredients essential to the type, the species would be widely separated from their congeners.

The above facts contain the principles upon which the anhydrous silicates are arranged. They are more fully developed in the chapter on Chemical

Mineralogy and Classification.

Besides the ordinary chemical formulas, which have the advantage of a familiar form and look, we add the condensed formulas, explained in our chapter on Chemical Mineralogy. There is little reason to doubt that the protoxyds and peroxyds replace one another, 3 parts of R replacing 1H; or generally that proportions of oxyds equal in amount of included oxygen are mutual substitutes in compounds. Thus R², H and R are equivalents. In this view, the complex silicates are simply silicates of a single complex base. Thus the general garnet formula is (R³, H) Si; under which the following are among the special formulas,

Garnet, $(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$, $(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$, Idocrase, $(\frac{1}{2} R^2 + \frac{1}{2} R) \overline{S}_i$, $(\frac{3}{2} R^2 + \frac{2}{2} R) \overline{S}_i$,

which differ from one another only in the ratio of R³ to H, it being 1:1 in Garnet, 1:2 in Epidote, 1:1 or 3:2 in Idocrase—the fractions within the brackets equaling together a unit and indicating this ratio. Such formulas give the constitution of the species with all the precision of the old formulas, exhibiting the exact relations of the constituents, without any hypothesis as to their atomic groupings.]

The following are the subdivisions of the Anhydrous Silicates.

- I. EDELFORSITE SECTION.—Oxygen ratio of bases and silica, 1:3.
- II. Augite Section.—Oxygen ratio, 1:2.
- III. EULYTINE SECTION.—Oxygen ratio, 1:12.
- IV. Garnet Section.—Oxygen ratio, 1:1.
- V. Mica Section.—Oxygen ratio in type, 1:1; Structure micaceous.
- VI. Feldspar Section.—Oxygen ratio in type, 1:1; Oxygen ratio of protoxyds and peroxyds, 1:3.
- VII. Andalustre Section .- Oxygen ratio 1 to less than 1.

I. EDELFORSITE SECTION.

EDELFORSITE. Neutral Silicate of Lime. Ædelforsite, Kobell.

Fibrous or feathery, and massive.

H.=6. (?) G.=2.58. Lustre shining. Color white or grayish.

Transparent.

Composition.—CaSi=Silica 62.2, lime 87.8. B.B. fuses to a white translucent glass. Gelatinized at Adalasa in Second of Adalasa in Second of Adalasa in Second of Adalasa in Second of Adalasa in Second of Adalasa in Second

Edelforsite is found at Aedelfors in Smaoland, Cziklowa in the Bannat, and at Gjelleback in Norway.

MANCINITE.

Plumose and shining, with two unequal cleavages inclined to one another, 92°. Color brown.

Composition.—Zn Si, probably, according to Jacquot, (Ann. d. Mines, [3], xix, 703). From Mancino near Leghorn. The species is a doubtful one.

II. AUGITE SECTION.

The oxygen ratio for the bases and silica in the Augite Section, is 1:2; varying in the species hornblende and acmite, to 1:2.

1. AUGITE GROUP. Crystallization monoclinic.

WOLLASTONITE, $\hat{C}a^{0}\hat{S}i^{2}$, Hornblende, $\hat{B}^{4}\hat{S}i^{2}=\hat{B}^{0}\hat{S}i^{2}$ Pyroxene, $\hat{B}^{0}\hat{S}i^{2}$, Acmite, $(\hat{B}+\hat{B})\hat{S}i^{2}=(\hat{B}^{0},\hat{B})\hat{S}i^{2}$ Rhodonite, $\hat{M}n^{0}\hat{S}i^{2}$ † Wichtyne, $(\frac{1}{2}\hat{B}^{0}+\frac{1}{2}\hat{B})\hat{S}i^{2}$ (†) Spodumene, $(\frac{1}{2}\hat{B}^{0}+\frac{1}{2}\hat{B})\hat{S}i^{2}$ † Sordawalite, $(\frac{2}{3}\hat{R}^{0}+\frac{2}{3}\hat{B})\hat{S}i^{2}$ (†)

- 2. BABINGTONITE GROUP.—Triclinic.
 Babingtonite.
- 8. BERYL GROUP.—Hexagonal.

Beryl, $(\frac{1}{2}Be+\frac{1}{2}\overline{A}l)\overline{S}i^2$ Eudialyte, $[(\frac{1}{2}B^2+\frac{1}{2}Zr)\overline{S}i^2]$.

WOLLASTONITE, H. Tabular Spar. Table Spar. Grammite. Schaalstein, W. Tafelspath, M.

Monoclinic. $C=69^{\circ}$ 48', $I: I=87^{\circ}$ 28', $O: 2i=137^{\circ}$ 48'; a:b:c:=0.4338:1:0.89789. Observed planes as in the annexed figure.

Rarely in distinct tabular crystals. Cleavage: O most distinct; ii less so; 1i and -1i in traces. Twins: composition-face ii. Usually cleavable massive, with the surface appearing long fibrous, fibres parallel or reticulated, rather strongly coherent.

H.=4.5—5. G.=2.78—2.9; 2.785—2.895, (United States), Thomson; 2.805, (Bannat), Haidinger. Lustre vitreous, inclining

Sideromelane is an amorphous ferruginous labradorite; formula R Si+R Si. Pélé's Hair (anal. 12) has the composition of an augite, (Rammelsberg).

ALTERED FORMS.—Feldspar may be altered through infiltrating waters carrying more or less carbonic acid in solution, (Forchhammer, Fournet, Bischof); also through the action of waters rendered acid by the decompositio nof pyrites, (Mitscherlich); also by ordinary waters holding traces of alkaline and other ingredients in solution, (Bischof).

The presence of pyrites, or a mineral containing protoxyd of iron, as some mica, garnet, &c., is often the first occasion of the change. The decomposition of the mineral with the attendant oxydation of the iron distributes ferruginous waters

through the rock, (or sulphate of iron, from the altered sulphuret), and thus by a disaggregating or decomposing action, prepares the way for other agencies.

When the infiltrating waters contain traces of carbonic acid, the feldspar acted on first loses its lime, if a lime feldspar, by a combination of the lime with this acid; next, its alkalies are carried off as carbonates, if the supply of carbonic acid continues, or otherwise as silicates in solution. The change thus going on, ends in forming Kaolin or some other hydrous silicate. The carbonate of soda or potash, or the silicate of these bases, set free, may go to the formation of other minerals—the production of pseudomorphic or metamorphic changes—and the supplying fresh and marine waters with their saline ingredients.

Kaolin is generally a simple hydrous silicate of alumina, expressed by the formula Il Si+2H=Silica 40.0, alumina 44.5, water 15.5; occasionally it corresponds to *ISi3+2H. Orthoclase in changing to the former loses 1K+3Si; or to the latter. 1K+8Si. Part of the silica set free may go off with more or less of the potash, or may form opal, quartz, siliceous sinter. The alumina also is often in part removed. The same explanation is readily applied to the change in albite or other feldspars. When the change is not carried on to the exclusion of the protoxyd bases, certain

zeolites may result, especially as Bischof states, when labradorite is the feldspar undergoing alteration, which species he describes as giving origin to the species mesolite. Massive nepheline or elæolite is a still more common source of zeolites.

When the waters contain traces of a magnesian salt—a bicarbonate or silicate the magnesia may replace the lime or soda, and so lead to a steatitic change, or to a tale when the alumina is excluded; and when augite or hornblende is present, it may give origin to chlorite.

The action of sulphurous acid from volcanic fumaroles produces often a complete destruction of the feldspar and other minerals present, giving rise to deposite or incrustations of silica, in some of its various forms, and also Halloysite, etc.

Steatite, Talc, Chlorite, Kaolin, Lithomarge, occur as pseudomorphs after orthoclase or albite; and Tin ore and Calcite also replace these feldspars by some process

of solution and substitution. Labradorite more rarely forms kaolin.

Orthoclase is also described as occurring altered to Albite. This has been mentioned as an example of paramorphism, the two species being dimorphous. But as these feldspars occur together in the same rock, and must have been formed under very similar circumstances, we can hardly suppose that either is liable to a change like that of a dimorphous compound to the form of the other.

The following are analyses of Kaolin. No. 1 to 28 are by Brongniart and Malaguti, who carefully separated the free silica and undecomposed feldspar. Their results are here reduced to 44.5 as constant for the alumina, this being the amount in the Kaolin of the formula, \$\frac{1}{A} \cdot \text{Si} + 2 \cdot \text{H}\$. G.=2.21—2.26. Analyses a, b, are from analyses by Ebelmen and Salvetat, (Ann. Ch. Phys. xxxi, 257). Analyses 1 to 17 and 21 give quite closely the theoretical formulas \$\frac{1}{A} \cdot \text{Si} + 2 \cdot \text{H}\$; 19, 20, have one quarter more of silica; 22, one half more; 26 and b, twice more.

STATE OF THE PARTY OF	Si	X 1	Ĥ	Si : Al
1. Limoges,	40.	44:5	15.5	1.0 : 1
2. Clos de Madame, Allier,	46.0	**	16.	1.15:1
3. Chabrol, Puy-de-Dome,	37.2	**	15.9	0.93:1
4. Plympton, Devonshire,	40.9		15.3	1.02:1
5. Piedmont,	36.5	"	15.5	0.91:1
6. Diendorf, Passau,	36.9	0 "	16.2	0.92:1
7. Rama, Passau,	43.8	16	15.4	1:09:1
8. Auerbach, Passau.	38.3	**	15.9	0.96:1

Named after the English Chemist, Wollaston; also tabular spar from its lamellar

Dr. Thomson has described under the name of Wollastonite, a mineral from Kilsyth, occurring in greenstone veins. It differs from tabular spar in containing some silicate of soda. Formula, Na Si+Ca*Si*, or near acmite. It is referred by J. D. Whitney, to Pectolite.

PYROXENE, Haüy. Augite. Coccolite. Diopside. Sahlite. Alalite. Mussite. Pyrgom. Fassaite. Pentaclasite. Jeffersonite, Keating. Asbestus, in part. Bronzite. Paulite. Green Diallage. Kokkolit, Baikilit, Omphazit, W. Pentaklasit, Haus. Malacolithe, Haüy. Funkite. Hudsonite, Beck. Polylite, Thom. Egerine, in part. Breislakite, Brocchi.

Monoclinic; $C=73^{\circ} 59'$, $I: I=87^{\circ} 5'$, $O: 2i=131^{\circ} 17'$; a:b:c=0.5412:1:0.91346.


- $0:1i=155^{\circ}51'$.
- $O: -1i = 148^{\circ} 35'$.
- $O: -3i = 109^{\circ} 31'$.
- $0: ii = 106^{\circ} 1'.$
- $0:1=146^{\circ}9'$.
- $0:2=130^{\circ}6'$.
- $O: -1 = 137^{\circ} 49'$.
- $O: -2 = 114^{\circ} 28'$.
- $0:1i=150^{\circ}20'.$
- $\theta: ii = 90^{\circ}$
- $2i: 2i(ov.O) = 82^{\circ}34'.$
- $ii: 1i=130^{\circ} 10'.$
- $ii:-1i=105^{\circ} 24'.$
- $ii:i2=152^{\circ}15'$.
- $ii: I=133^{\circ} 33'.$
- $ii: i_2 = 115^{\circ} 25'$.
- $ii:i3=107^{\circ}35'$.
- $i2:i2(ov.ii)=124^{\circ}30'.$
- $i\hat{2}: i\hat{2}(\text{ov}.ii) = 50^{\circ} 50'.$
- ii: 3i=143° 34'.
- $-1:-1=120^{\circ}$ 32′.
- $-2:-2=95^{\circ}30'$.
- $1:1=131^{\circ}24'$.
- $2:2=111^{\circ}10'$.

)	_		
16			1				14
			2				21
						25	
					38		
	100						41
ii	i8	i2	I	iù	ià		iù
		Œ,					44
1	=		-8				
-3 <i>i</i>				$-\frac{8}{3}$			
			-2				21
-1 <i>i</i>			-1	1-			10
-1i							

Observed Planes.

Cleavage: I rather perfect, often interrupted; ii and ii imperfect. Crystals usually thick and stout. Twins: face of composition ii, (f. 357). Often coarse lamellar, in large masses, parallel to O or ii. Also granular—particles coarse or fine; and fibrous, fibres often fine and long.

H.=5-6. G.=3.23-3.5. Lustre vitreous, inclining to resinous; some pearly. Color green of various shades, verging on one side to white or grayish-white, and on the other to brown and black. Streak white—gray. conchoidal—uneven. Brittle. Transparent—opaque.



Composition.—R*Si*, in which R may be lime, magnesia, protoxyd of iron or manganese, or even soda; and in some instances alumina enters into the composition without changing essentially the crystallization, and usually replaces silica. When R=(Ca, Mg), the color is white or light green; when R=(Ca, Fe), the color varies in shade of green to black, according to the proportion of oxyd of iron; if R=Mn, the color is flesh-red, and the mineral is manganese spar. It may also be (Ca, Mn), or (Ca, Mg, Fe), or (Fe, Mn), and when iron is abundant the mineral is very dark green or black.

There are other kinds arising from mode of crystallization, the species being sometimes in distinct crystals, sometimes thin foliated, sometimes granular, and often fibrous or asbestiform. The following are the prominent varieties:—

1 Diopside, White Augite, White Malacolite, Mussite.—Of white, grayish, or grayish-green color, either crystallized, lamellar or granular. The granular, when coarse and somewhat friable, is called white coccolite. Alalite is a diopside from Ala in Piedmont. Mussite has a grayish-green color, and is lamellar parallel to the Composition .- R'Si', in which R may be lime, magnesia, protoxyd of iron or man-

Ala in Piedmont. Mussite has a grayish-green color, and is lamellar parallel to the base, the lamellar sometimes contorted; it is from Mussa in Piedmont. These varieties contain the bases magnesia and lime, with little or no iron, and usually no

ricties contain the bases magnesia and lime, with little or no iron, and usually no alumina, (Ča, Mg)*Si². G.—3·23—3·26. Diopside is from δις, two-fold, and οψις, appearance; malacolite, from μαλακος and λιθος.

Sahlite resembles diopside, but has a dingy greenish color, and is coarse foliated, arising from composition parallel to O; from Sahla, Sweden. Baikalite is a green variety, from Lake Baikal. Pyrgom is a dingy variety of sahlite, (named from the Greek πυργωμα.) Omphazite is a foliated leek-green variety. The same constitution as above, but usually with some iron. G.=3·23-3·3.

Purosene (from πρ. fire and trees stranger)—Besides its general use this name is

Pyroxene, (from \$\pi\phi\$, fire, and \$\text{tronger}\$).—Besides its general use, this name is specially applied to the green or grayish-green crystals, often of large size Green Malacolite is another name for this variety. Fassaite is handsome grass-green or pistachio

green, with high lustre; from the Fassa valley, Piedmont. Green Coccolite is a granular friable variety, consisting of bright green shining granules, named from surres, a grain. Funkite is a green coccolite. Liberzolite has a deep green, or olivegreen color, and occurs both crystallized and lamellar; from Lake Lherz in the Pyrenees. Baikalite (from Lake Baikal) is an olive-green sahlite. These species contain the bases lime, magnesia, and protoxyd of iron, (Ca Mg, Fe) Si. G. 325

Jeffersonite is a dark-green crystallized foliated variety, from Mine Hill, Franklin, New Jersey: it has the same constitution and angles as the last, with some oxyd of zinc. (Ca, Fe, Mg, Zn)³ Si² G.=3.6. Named after Mr. Jefferson.

Augite (from suyn, lustre) includes the black and greenish-black crystals, common in basaltic and volcanic rocks. It contains the same bases as the last, together with alumina. (Ca, Fe, Mg)³(Si, Kl)³. G.=3.38—3.36; 8.359, Etna; 3.356, Riffel; 3.358, Fassa. Alumina is also contained at times in some of the above varieties. Ægirine of Brevig is a black or greenish-black to leek-green pyroxene; G .= 3.482 -8·504, (Pogg. lxxx, 815).

Breislakite occurs in wool-like forms at Vesuvius and Capo di Bove. Its crystallographic identity with pyroxene has been shown by Chapman, (Phil. Mag. xxxvii, 444, 1850). Named after Breislak, an Italian geologist.

Hedenbergite is a black pyroxene, containing largely of iron, little or no magnesia, and no alumina. (Ca, Fe)*Si². G.=3·5. Named after the Swedish Chemist, L. Hedenberg

Hudsonite, from Orange Co., N. Y., near the Hudson river, is black and cleavable like Hedenbergite, but differs in having a considerable part of the silica replaced by alumina, (Oa, Fe,) (Si, ±1). G.=3.5, Beck; 3.43—3.46, Brewer; streak green; often has a brown tarnish. It also contains at times some manganese. *Polylite* is the same compound.

A pure iron-augite analyzed by Grüner, (Anal. 47), has been called Grünerite. Diallage, (from διαλλαγη, difference, alluding to the dissimilar cleavage).—Thin foliated and easily cleavable; laminæ brittle; color various shades of green, gray, and brown, and sometimes bronze or pearly-metallic. G.—3:11—3:227. It includes Schiller spar (in part) and Bronzite. Bronzite has a greenish-brown or brownish color, and metalloidal lustre; it cleaves in three directions, two of which meet at an angle of 87°. G.=3·125. From Gulsen in Styria.

an angle of 87°. G.=3·125. From Gulsen in Styria.

Hypersthene, (from wasp and σθενος, very strong or tough), bears nearly the same relation to diallage that the dark varieties of pyroxene bear to the light. It contains a large proportion of iron and little lime, yet varies much in this respect, and some varieties, not distinguished by external characters, have the composition flearly of diallage. Its colors are grayish or greenish-black, and copper-red, with a bright metallic-pearly lustre. It cleaves easily, but not into as thin folia as the preceding. G.=3·3—3·6. The Paulite (G.=3·389) is from the island of St. Paul Labrador Hornblende and Metalloidal Diallage are here included. The Bronsite has alone brown and minchheck brown colors with a metallic-pearly lustre. clove-brown and pinchbeck brown colors, with a metallic-pearly lustre. G. = 3.2-3.5. Cleavage orthodiagonal, very perfect. Diaclasite of Hausmann (analysis 43) is between diallage and hypersthene in composition, but has the pale colors of diallage, passing into brass-yellow. Named from dianhaw, to cleave through.

Analyses: L-1, Nordenskiöld, (Schweig J. xxxi, 457); 2, H. Rose, (Schw. xxxv. 86); 3, T. Wachtmeister, (Schw. xxx, 334); 4, Hermann, (J. f. pr. Ch. xxxvii, 190); 5, Wackenroder, (Kastn. Archiv. xiii, 84); 6, Kussin, (Ramm. 4th Suppl. 12); 7, Reutersköld, (Jahresb. xxv, 362); 8, Richter, (Pogg. lxxxiv, 384).

II. 9, Seybert, (Am. J. Sci. iv, 340); 10-13, H. Rose, (loc. cit.); 14, Wolff, (J. f. pr. Ch. xxxiv, 236); 15, Hochstetter, (J. f. pr. Ch. xxvii, 375).

III. 16-20, Kudernatsch, (Pogg. xxxvii, 577); 21, Gmelin, (Leonh. u. Bronn, N. Jahrb. 1840, 549); 22, Delesse, (Ann. d. Mines, [4], xii, 293); 23, Rammelsberg, (Pogg. lxxxiii, 458); 24-26, Waltershausen, (Vulk. Gest. 107 to 110). IV. 27, T. S. Hunt, (Logan's Geol. Rep. 1853).

V. 28, 29, Smith and Brush, (Am. J. Sci., [2], xvi, 369); 80, Thomson, (Min. i, 495); VI. 31, 32, Köhler, (Pogg. xiii, 101); 33, Delesse, (Ann. d. M. [4], xvi); 34-36, Regnault, (Ann. des M. [3], xiii, 147); 37, Kobell, (J. f. pr. Ch. xxxvi, 303); 38, Schaf häutl, (Ann. d. Ch. u. Ph. li, 254); 39, Beck, (Min. N. Y., p. 310); 40, Seybert; 41, Muir, (Thom. Min. i, 202); 42, Damour, (Ann. des Mines, [4], v. 157; 43, Köhler, (loc. cit.); 44, T. S. Hunt, (communicated).

greenish, yellowish, grayish or reddish in color; H.=2.5—3, cutting like massive talc. G.=2.7—2.784. It is identical with some agalmatolite. Mr. Hunt regards it as an altered clay slate. It is from Canada.

Analyses; 1, Vauquelin, (Ann. de Ch. xlix, 88); 2, Klaproth, (Beit. v, 19); 3, Thomson, (Min. i, 343); 4, Karafat, (Pogg lxxviii, 575); 5, 6, T. S. Hunt, (loc. cit.);

7, 8, 9, Smith and Brush, (Am. J, Sci. [2], xvi, 50).

```
Fe Ca Mg
                    ₿i
                         ₩l
                                                      Ķ
  Agalmatolite, 56.
                                                     7.
                                                          5=100, Vauquelin.
2.
                  54.50 84.0
                                   075 -
                                                    6.25 4:=99.50, Klaproth.
                                  1.50 6.00 —
                  49.82 29.60 1.50 6.00 — 6.80 5.5=99.21, Thomson.
49.50 27.45 Fel.03 5.56 0.72 10.20 5.10, Mn tr.=99.56, Karafist.
                  48·50 27·50 "5·67 1·30 2·24 5·30 7·00, Na 1·91=99·42, Hunt.
48·42 27·60 "4·50 2·80 1·80 5·02 6·88, "2·78=99·80, Hunt.
  Parophite,
7. Dysyntribite, 44.80 84.90 Fe3.01 0.66 0.42 6.87 5.38, Na 8.60 Mn0.30=99.94,
                                                                            Smith & Brush.
                                   8.69 tr. 0.50 11.68 5.80,
                                                                  " tr. =98.88, S. & B.
                   4670 3101
                                  8.88 8.44 6.86 5.80 6.15, " tr. =100.13, S. & B.
                  44.94 25.05
```

The analyses by Hunt agree rather closely with 3 and 4 by Thomson and Karaflat. Karafiat's agalmatolite is in part the gangue of the Diaspore of Schemnitz; it is slightly greenish and somewhat greasy in lustre. H=2.5-3. G.=2.785.

Walmstedt and Lychnell have analyzed other so-called Agalmatolites from China which contain no alkali; Walmstedt obtained (Ofv. K. V. Ak. Förh., 1848, 111) Silica 65-96, £1 28-58, Fe 0-09, Ca 0-18, H 5-16=100-12. Some specimens called agalmatolite are steatite.

PETALITE. Castor, Breit.

Monoclinic? Massive, with three cleavages in one zone, affording the angles 117°, 142° and 101°; the cleavages inclined at 142°, the most perfect.

 $\mathbf{H} = 6 - 6.5$. G.=2.42, Arfvedson; 2.45, Dr. Clarke; 2.426, C. G. Ginelin. Lustre vitreous and glistening; pearly on the faces of perfect cleavage. Color white or gray, with occasionally a reddish or greenish tinge. Streak white. Translucent. Fracture imperfectly conchoidal.

Composition.—(Li, Na) Si4+4 Li Si4=(B+5 Li) Si4=(if Na: Li=1:6) Silica 77-9. **slumina 17-7**, lithia 3-1, soda 1-3=100.

Analyses: 1, Arfvedson, (Schw. J. xxii, 93); 2, Gmelin, (Gilb. Ann. lxii, 399); 3, 4, R. Hagen, (Pogg. xlviii, 361); 5, Rammelsberg, (Pogg. lxxxv, 553); 6, Waltershausen, (Vulk. Gest. 296); 7, 8, Smith & Brush, (Am. J. Sci. [2], xvi, 373); 9, Plattner, (Ann. Ch. Pharm. lxix, 448).

```
₩l
                                       Li
1. Uto,
                  79.212 17.225
                                     5.761
                                                    =102·198, Arfvedson.
                                                     Ca 0.32, ign. 2.17=99.23, Gmelin.
2.
                  74.17
                            17.41
                                           5.16
8.
                  77.812
                                      2.692 2.302=100, R. Hagen.
                            17.194
4.
                  77:067
                            18.000
                                      2.660
                                              2 273=100.
                                               1.19=100, Rammelsberg.
                  7779
                                      8.30
                            18.58
                                               _____, Fe0 08, Mn1 0, Mg1 0, H0 97=99 95, W. 0.48, Fe 0.62, K, Ca, tr., Mg 0.21, ign. 0.60=
    " reddish, 7674
                            18.66
                                      2.69
7. Bolton, Ms. 77-95
                            16.63
                                      374
                                                                        100.23, Smith & Brush.
                                      8:52 (0:58, "0:51 " tr., Mg0*26, ign. 0.70, 8 & B. 2.76 (with tr. K, Na)=100*24, Plattner. G.=2*892.
                            15.85
9. Castor,
                  78-01
                            18.86
```

The protoxyds in Castor are less than in Petalite, according to the analyses; but it is hardly possible that it can be a distinct species. Its cleavages are like those of Petalite, according to Rose.

VI. This for stell. Note 31 to 14 This tipe 34 to 17 December 38. Freedifferous Brownie 1, 40, a lead of Hopermone 1, 41, is special to 4, 40, a lead of Hopermone 1, 41, is special to 4, 40, a lead of Hopermone 1, 41, is special to 4, 40, a lead of Freedings. Richer, Lanata: 14 Depresente il Hamenman.

	3i	Ýε	i e	ŕ.	Ýз	基
M. Harz	5171	17.35	17:0	•	1:19	55年至174年176年, 区
32 Florence.	13 20	. 4):	4	* 7.	1:38	247. 宜 1 丁二1(0)-49. K.
12 Oders the spe	43 30	::4:	15 43	7.17	51	- 3 50. €r ⊕*00. ign. 0*%= 36.48. Delene
4 Fielmost	507-55		15 43	94		254. # 213=3951. Reg.
25. U.a.	52.40	14 43		: 43		3-27 1.53-23-3-3-3-
M. Ultenthal.	55 -4	3 . 3		10.79		100 110 = 10-90.
17. Green and	30.00	29 44		19-14		133=1 · 13. Kobell
38. Genoa, G. 125	49.50	1414	19 13	1 23	_	3 33, V 3 43, Na 3 75, B 1 77, S
38. Lake General.	45 45	1944	:4 33	11.40		
40. Wilmington.	32:17	11:33	29,730			4.1. fi : 1.=39 23, Seyb
41. Skye. Hypers.		1114				— 1==38 70, Muir
42 Latrair.	5: 34				131	T=1872 Pamour
43 Beste, Diani.		2510	4-73	11:51	.,-1:	1 34 E 3 75=1-0-40 Koh
44. Canada, Hup.	31 33		1 53	37.54		3 7% ign. 0-16 ==39-93, H
an iron-angite, w.	h the fo	enala f	`- ³ 5;2—	rii a s	74. př	esition of a diopside; 46 i coxylications 543; G.= 170 (water excluded)
45. Ziller hai.		3) 33	17.76	431	1-13	
46 Collobrieres.	43-1	1.1	93	52-2		1 9==99 % Gruner.
47. Staten I.i.	55-99	30.73		11-32		H 2-25=1 o. Beek

```
43. Tyrol.
43. Reichenstein.
                                          3-99
                                                 -- " 2 34=1:0 25. Scheerer.
                    57.50 23.19
                                 13:43
                                          5 22 31 - 56 - 2 15. Cu - 4 - 99 - 85, Re.
                          23 99 11 55
                    55-45
                    57-27 22-5
                                                     - * 243=1 + 24. Scheerer
30 Pock Cork.
                                 : 3 3 3
                                          4 37
```

Jeffermnite afforded Hermann, J. L pr. Chem. xlvii, 13, 1549 ::

Si 4091 Ca 1549 An 700 Zn 449 Fe 1053 Ei 100, Mg 5 10, ign. 1-30

Other analyses: by Lory, (Bull. Soc. Gool. Fr. [2], vii, 54°; Delesse, Ann. d. M. [4], xviii, 3°9, xx, 145°; A. Erlmann, (K. V. Ac. H. 184c, and Ramm., 5th Suppl., 80); Deville (Etudes, 1846); Brei lenstein, (Ramm. 5th Suppl., 6°). Frölich, (ib. 62.

B.B. the whitish or pale varieties fuse with some effervescence to a colorless glass; with borax afford a clear glass. Varieties containing iron afford an iron reaction, which is more intense the greater the proportion. The Hedenbergies and dark augites free readily to a shining black glass. Diallage vieles some water in a matrass, and becomes of a paier color: on charcoal it fuses with difficulty on the edges to a gray slag; with borax it forms a glass colored with iron. Brownie becomes of a paier color, but alone is infusible. Hypernihess generally fuses on charseal rather easily to a grayish-green glass, not clear. Hudsonite fuses with effervescence to a black magnetic head; with sods, a manganese reaction.

Pyroxene is principally confined to crystalline or volcanic rocks, and is associated at different localities with granite, granular limestone, serpentine, greenstone. basalt or lavas. Dialiage occurs generally in serpentine or greenstone; and hypersthene with feldspar and quartz forms hypersthene met, which occurs extensively in some districts of crystalline rocks.

Pyroxene, with labradorite or oligiocase, forms Greenstone or Diabase; and when the texture is very compact, it constitutes Melaphore, which is red-lish-brown With labradorite and magnetite, forms Dolerite or Basult, often crystalto like:k ine granular, and called basalt more especially when the texture is impalpable. Pyreasers is common in lavas, and is a constituent of Tufas.

Foreign localities are numerous and we mention but few.

Angite occurs at Anseig and Teplitz, in Bohemia in large crystals imbedded in basalt; and in small highly polished crystals in the lavas of Vesuvius, with nephe-line, idoerase, and mica. Diopside is met with in crystals at Ala, in Piedmont, asthe outer flame weak red and yellow at the point; the red color more distinct, on platinum, but less so than with petalite. With borax a colorless glass; with salt

of phosphorus, a silica skeleton.

Occurs in the cavities of a porphyritic amgydaloid, with chalcedony and quartz,

bear Weissig; also as a pseudomorph after a zeolite.

POLLUX, Breit., Plattner, Ann. d. Ch. u. Pharm. lxix, 489, 445.

Massive. Like quartz in appearance; traces of cleavage.

H.=6-6.5. G.=2.880. Colorless and transparent, with a vitreous splendent lustre. Fracture conchoidal. Refraction biaxial.

Composition.—Analysis by Plattner, (loc. cit.):

Si 46.200, £1 16.394, Fe 0.862, K 16.506, Na (and Li trace) 10.470, H 2.321=92.758.

The quantity analyzed was too small for a satisfactory result.

B.B. fuses to an enamel-like blebby glass, and tinges the flame orange. Dissolves easily with borax and forms a colorless glass. Glass with salt of phosphorus uncolored when cold. Decomposed completely in the acids.

Associated with castor at the island of Elba.

ISOPYRE, Turner. Ed. New Phil. J. iii, 268.

In compact masses, with cleavage.

H.=6-6.5. G.=2.9-3. Lustre vitreous. Streak light greenish-gray. Color grayish or velvet-black, occasionally spotted red, like Heliotrope. Opaque—subtranslucent. Fracture flat conchoidal. Brittle. Acts slightly on the magnetic needle.

Composition.—(Ca+(Al, Fe))Si' or essentially same as for Labradorite. Analysis by Turner, (loc. cit.):

Ĉa 15.43, Bi 47 09, Æl 13.91, Fe 20.07, Ču 1.94=98.44.

Part of the iron is supposed to be protoxyd, judging from the color of the mineral. B.B. fuses easily to a magnetic bead. On platinum colors the flame green. A silica skeleton, with salt of phosphorus. With the acids decomposed with difficulty and imperfectly.

From St. Just, near Penzance, in a quartzose granite with tourmaline and tin ore, in pieces two inches in diameter. Also in breccia, on the Calton Hill, Edinburgh,

with limonite.

SILICATE OF YTTRIA, Damour, L'Institut, 1858, 78.

H.=5-6; scratches glass. G.=4.391. Color brown. Probably a silicate of yttria. B.B. whitens, but infusible. Not soluble in salt of phosphorus. Sulphuric acid heated to 300°C decomposes it, leaving a siliceous residue.

From the Diamond sands of Bahia, Brazil.

POLYCHROILITE, P. C. Weibye.

Hexagonal? In 6-sided prisms of about 120°, with flat summits. Also massive. and reniform.

H .= 3-3.5. Lustre greasy. Color blue, green, brown, red, rarely white. Fracture splintery—subconchoidal to even.

Analysis by Dahl, (v. Leonh. 1846, 288). Si 52, Al 87, Mg 7, Fe 8, Ca, H; Scheerr found less alumina and 6 per cent. of water.

Found in gneiss at Krageröe, Norway.

Crystals of this species have been obtained by fusion, and are not unfrequent, of a black color, among the iron slags of Sweden. Mitscherlich and Beudant have formed white crystals by heating together silica, lime, and magnesia.

ALTERED FORMS.—Pyroxene undergoes alteration in different ways, as has been well explained by Bischof. When containing much protoxyd of iron, as in many varieties, the iron, if moisture is present, undergoes oxydation, becoming brown or brownish-red and hydrated, or of a red color and anhydrous; or is carbonated and becomes gradually removed and the result uncolored, if carbonic acid is present. In an early stage of alteration, crystals often develop a basal cleavage. The carbonic acid of influentian enterprise is present against of the limit bonic acid of infiltrating waters when lime is present, carries off the lime, leaving the most of the magnesia, as in the change to Rensselaerite; or by continuing its action, carries off the magnesia and gives origin, if the pyroxene is aluminous, to a hydrous silicate of alumina, like Cimolite; an addition of alumina may probably take place through the accompanying decomposition of associated feldspar. Acted on by sulphuric or sulphurous acid about volcanoes, the protoxyd bases are rapidly removed, and a hydrous aluminous silicate is left, and often a siliceous deposit or sinter. Acted on by alkaline carbonates in solution, a similar result is produced, but alkalies take the place of the removed bases, and an alkaline silicate of alumina or of iron and alumina is formed, as Green earth; or under different circumstances there is a change to mica. Acted on by waters containing traces of bicarbonate of magnesia in solution, magnesia is exchanged for the lime, and thus pyrallolite, hypersthere and hornblende, may be formed from Augite; and the removal of the lime entirely, and its replacement by magnesia, gives origin to serpentine, steatite, tale, saponite. Silicates of iron and magnesia may also proceed from the action of alkaline silicates or carbonates.

Tufas consist largely of altered augite, and are formed from augitic sands under the action of steam or heated waters, thus becoming a hydrous silicate of alumina, etc.; such, according to Bunsen, is the Palagonite of Waltershausen

The following are analyses and descriptions of some of the more prominent re-

sults of alteration.

1, 2, Waltershausen, (Vulk. Gest. 305); 3, Beudant; 4, Beck, (Min. N. York, 297); 5, Nordenskiöld, (Schw. J. xxxi, 386); 6, Köhler, (Pogg. xi, 192; 7, Rammelsberg. (3d Suppl. 106, and Pogg. xlix, 387); 8, Klaproth, (Beit., ii, 180, v, 22); 9, Svanberg, (K. V. Ac. H. 1840, and Pogg. lvii, 165); 10, 11, Smith & Brush, (Am. J. Sci. [2], xvi, 368); 12, Svanberg, (Pogg. liv, 267); 13, 14, Rammelsberg. (Pogg. xlix, 387); 15, Delesse, (Bib. Univ. Genève, June, 1848, 106); 16, 17, Waltershausen, (loc. cit., 301); 18, Rammelsberg, (loc. cit.); 19, Klaproth, (Beit., i, 291); 20, Ilimoff, (Ann. J. M. Russ., 1841, 336); 21, Rammelsberg, (loc. cit.):

1. CALCAREO-MAGNESIAN.-1. Hydrosilicite. 2. Ibid.

```
Ńа
                                                Ŕ
     Bi
             Æı
                      Mg Ca
                                                        13:21=100, Waltershausen.
14:48=100, Waltershausen.
1. 44-90
                     4.60
                          83.82
                                       2.11
                                                1.86
9 43-91
             8.14
                           2870
                                            1.70
                     8.66
```

II. MAGNESIAN.—3. Sahla, Pseudomorph. 4. Rensselaerite. 5. Pyrallolite. 6. Schiller Spar. 7. Ibid. 8. Saponite, Cornwall. 9. Ibid. 10. Thalite, Lake Superior. 11. Ibid. 12. Piotine.

```
₽e
                              Йg
                                             Ňа
                       Гe
                                    Ċa
                                                    Ŕ
                                                          Ħ
           Ξl
                                    4-97 Ún 0-78
                                                       - 4:38=100:16. Beud
                      4.18
                             25-20
 4. 5975 -
              - 3:40
                             32.90
                                    1.00
                                                      - 2:85=:99:90, Beck.
                             23-38
                                    5.58 Mn 0.99
                                                       - 3.58Bit and loss 6.38, Nor.
 5. 56·62 3·38 0·99
                             26.16
                                                       - 12:43 Er 2:37=100, Köhler.
 6. 48-08 178 -
                      10.91
                                    2.75
                                          " 0.57
                             27-24
                                                        10.13=101.95, Ramm.
                      16.61
 7. 41:48 6:49
                                                   075 18:00= 18:75, Klap.
                             2475
 8. 45-00 9-25 1-00
                                                        11-00=100-2, Svanb.
20-66=::884, S. and B.
                                     07
 9. 46 8 8 0 0 4
                             83.3
                                    1.07
                                                0.45
10. 45 60 4 87 2 09
                             24.10
11. 48-89 7-28 2-46
                             24.17
                                               0.81
                                                         15.66= 19.22, S. and B.
                             26.23
                                    0.78
                                                        10:5=100:15. Syanb.
12 50-89 9-40 2-06
```

III. ALEALINE.—13. Green Earth, Fassa. 14. Ibid 15. Green Earth, Mt. Baldo 16. Green Earth, Iceland. 17. Ibid.

100	Bi	Æl	Fe	Ѓе	Mg	Ča	Ňa	ĸ	Ĥ
13.	45.87	11:18	-	24.68	0.28	1:50	672		9.82=100, Ramm, 8.67=100, Ramm.
14	39.48	10.31	8.04	15.66	170	Ca C	15.24, alkali	and H	8.67=100, Ramm.
15.	51.25	7.25		20.72	6.16	-	1.92	6.21	6.49=100, Del.
16.	52.04	4.93	-	25.54	4.26	1.38	-		5·19=99·87, Walt.
17.	60.09	5.28	-	15.72	4.95	0.09	2.51	5.04	4.44=98.12, Walt.

IV. ALUMINOUS.-18. Bilin, Pseudomorph. 19. Cimolite, Argentiera. 20. Cimolite, Alexandrowski.

Si HI Mg Ca Ĥ 18. 60.63 23.08 4.21 0.91 1.28 9.12=99.23, Rammelsberg. 12.00=99.25, Klaproth. 19. 63.00 23.00 1.25 20, 63.52 23.55 12.00=99.07, Ilimoff.

V. Siliceous.—21. Vesuvius, Pseudomorph.

Ča X1 Fe Mg

21. 85.31 1.58 1.67 1.70 2.66 5.47=98.42, Rammelsberg.

Hydrosilicite, Waltershausen, (Analyses 1, 2).—Occurs amorphous or as a crust, at Palagonia and Aci Castello, in Sicily, associated or mixed with Herschelite, Phillippsite and Calcite. Formula R³ Si²+3H, or a hydrous augite.

Rensselaerite, Emmons, (Analysis 4) .- Compact steatitic, with an unctuous feel, fine compact texture, either gray, whitish, greenish, brownish, or at times black. H. =3-4, G. =2.87. Translucent. Has often the cleavage of pyroxene. On account of its softness, translucency and fine texture, it is worked in a lathe into inkstands and other forms. Occurs over large areas in Northern New York, in the towns of Fowler, Dekalb, Edwards, Russel, Gouverneur, Canton and Hermon, St. Lawrence Co.

Pyrallolite, Nordenskiöld, (Analysis 5).—Cleavable or granular massive, and like pyroxene. H.=3·5—4. G.=2·555—2·594. White, sometimes greenish; subtranslucent to opaque. Formula Mg³ Si² with water. B.B. at first blackens and then becomes white. From Storgord in Finland, in limestone, with pyroxene and

scapolite. Closely related to the Rensselaerite.

Schiller Spar, (Analyses 6, 7).—Cleavable, massive, like some pyroxene. H.=3.5

4. G.=2.5—2.76. Lustre metallic pearly, to subvitreous. Dark green, inclining to pinehbeck brown. Subtranslucent. B.B. fuses on thinnest edges. From Baste in the Hartz with serpentine. It is considered an altered augite by G. Rose. The name is from the German for a play of colors or lustre. Called also Bastite.

Saponite, Seifenstein, (Analyses 8-11).—Occurs like Green Earth in amygdaloidal cavities. It is soft, almost like butter, brittle on drying; white, yellowish, bluish, reddish,—not adhering to the tongue. B.B. fuses with difficulty on the edges. Wholly soluble in sulphuric acid. From Lizard's Point, Cornwall; amygdaloid of northern shore of Lake Superior Region, (Owen's Thalite, Proc. Acad. Philad. 1852, and Am. J. Sci., [2], xiii, 420, Anal. 10, 11); Svärdsjö in Dalarne, (Piotine of Svanberg, Pogg. liv, 267, Analysis 12).

Green Earth, (Seladonite).—Earthy or a minutely crystalline appearance, dark olive green, to celandine green, and quite soft, with an unctuous feel. It occurs in amygdaloidal cavities. The green earth from Mt. Baldo is nearly apple green; G.=2-907. That from Iceland where it occurs with zeolites, afforded a trace of vanadium; G.=2-677. Analyses of Green Earth Nos. 13 to 17; 13, 14, Fassa, 15, Mt. Baldo, 16, 17, Iceland.

Picrophyl according to Breithaupt is also altered Augita.

Cimolite, (Analyses 18-20).—Massive, earthy, very soft. G.=2·18-2·30. Color white, grayish. Lustre of steak greasy. Absorbs water but does not fall to proceed to the composition nearly to \$\frac{1}{4}\$ Si^2+3 (or 2) H. B.H. infinitely original Cimolite was from Cimolis, on the island of Argentiera, Greece. 18 is of a pseudomorph after augite from Bilin, identical in composition with Cimolite.

Acmite is considered by Bischof and Rose, pyroxene altered by the alkaline

process.

tesselated appearance, as shown in the following figures, from a memoir by Dr. C.T. Jackson, (Jour. Bost. Soc. Nat. Hist. i, 55). Figs. a and b are from opposite extrem-



ities of the same crystal; so also c and d, and e and f. h appears to be a twin

Composition.—Äl Ši =Silica 370, alumina 630. Perhaps in part Al Ši =Silica 403, alumina 597. Analyses: 1, Bucholz, (v. Moll's Ephemer. iv. 190); 2, Thomson, (Min. i, 332); 3, Kersten, (J. f. pr. Chem. xxxvii, 162); 4, Svanberg, (Jahresh. xxiii, 279); 5, Bunsen, (Pogg. xlvii, 186); 6, A. Erdmann, (Jahresb. xxiv, 311); 7, Bunsen, 8, Jackson, (Bost. J. Nat. Hist. i, 55); 9, Renou, (Expl. Sci. de l'Algerie, Paris, 1848, 58); 10, Hubert, (Jahrb. k. k. g. Reichs. i, 350):

		A 3 . Th.	THE REAL PROPERTY.	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
		Si	X 1	Fe
1.	Herzogau,	36.5	60.5	4.0=101.0, Bucholz.
2.	Tyrol,	35.30	60.20	-, Fe 1·32, Mg 1·0, H 2·03=99·86, Thomson.
3.	Munzig,	37.51	60.01	1.49, Ca 0.48, Mg 0.46=99.95, Kersten. G.=3.151
4.	Fahlun,	37.65	59.87	1.87, Ca 0.58, Mg 0.38=100.35, Svanberg.
5.	Lysens, Tyrol	40.17	.58.62	—, Mn 0.51, Ca 0.28=99.58, Bunsen.
6.		39.99	58.60	0.72, Mn 0.83=100.14, Erdm. G.=3.154.
7.	Chiast.Lanc.	39.09	58.56	—, Mn 0.53, Ca 0.21, ign. 0.99=99.38, Bunsen.
8.	44 44	33.0	61.0	4.0, H 1.5=99.5, Jackson.
9.	" Algeria,	36.6	61.9	-, 98.5, Renou; I: I=93° 30'. G.=3.1.
10.	Andal. Tyrol,	39.24	59.49	0.63, Mg 0.25, Ca 0.51=100.12, Hubert

B.B. alone infusible. When pulverized and mixed with borax, it fuses with artreme difficulty to a transparent colorless glass. With soda it swells up without


melting.

Andalusite occurs in crystalline schists, especially mica and clay slate. It was first observed in the province of Andalusia, in Spain. Occurs in the Lisens valley, in the Tyrol, in large crystallizations; at Bräunsdorf and Penig in Saxony; Goldesstein, in Moravia; in Bavaria; in Siberia; at Killiney Bay, Ireland, in mica slate; and near Balahulish, Argyleshire. Chiastolite at Jago di Compostella in Spain, Barèges in the Pyrenees, Bayreuth, and Cumberland in England.

At Westford, Mass., abundant both crystalline and massive, sometimes roccolored. Litchfield and Washington, Conn., fine crystals; also Mt. Abraham, Bangor, and Searsmont, Me. In Pennsylvania, near Leiperville, in large crystals; also at Marple; at lake St. Francis, Canada East, in flesh-red translucent crystals in a mica schist of Silurian age, the larger crystals sometimes chiastolite. Chiastolite is abundant in the towns of Lancaster and Sterling, Mass.; and at the former place occasionally in quartz, presenting all the essential characters of andalusite, (anal. 7, 8). Andalusite occurs also near Bellows Falls, Vermont; at the White Mountain Notch, N. H.; at Camden in Maine, and Charleston, N. H.

ALTERED FORMS.—Andalusite occurs altered to Kyanite. Hubert's analysis above, was of the interior of an Andalusite crystal, the exterior of which was changed in structure to Kyanite. The exterior afforded Si 36.67, Al 60.00, Fe 1.33, Ca 0.28=98.93. The analysis of the Andalusite affords the second formula above, while that of the Kyanite affords the first, which is that of all Kyanite. It is also found changed to tale, steatite and mica.)PAZ. Fluosilicate of Alumina, Thom. Physalite, Pyrophysalite, Hisinger.
Pycnite. Schorlartiger Beril, W. Stangenstein. Alumine Fluatée Siliceuse, H.

Trimetric. $I: I=124^{\circ} 19': O: 1i=138^{\circ} 3'; a:b:c=0.8987: 1.8932.$



Crystals usually hemihedral, the extremities being unlike. Reavage: basal, highly perfect. Also granular—coarse or ne.

H.=8. G.=3.4—3.65. Lustre vitreous. Color yellow, white, green, blue; pale. Streak uncolored. Transparent-subtrans-Fracture subconchoidal, uneven. Pyroelectric. Iucent.

Composition .- AlSit with one-seventh of the oxygen replaced by fluorine, Rammelsberg.

Analyses: 1—3, Berzelius, (Schweig J. xvi, 423, Afhand. iv, 236); 4, 5, Forchhammer, (J. f. pr. Ch. xxix, 195, xxx, 400); 6, Berzelius, (Schw. J. xvi); 7, Bucholz, (ib. i, 385); 8, Forchhammer, (J. f. pr. Chem. xxix, xxx):

	Si	X 1	F
1. Auerbach, Saxony,	34 24	57.45	14.99, Berzelius.
2. Brazil, yellow,	34.01	58:38	15.06, "
3. Finbo, pyrophysalite,	34.36	57 74	15.02, "
4. Monroe, Ct.,	35.39	55-96	17.35, Forchhammer.
5. Finbo, pyrophysalite,	35'66	55.16	17.79, "
6. Pycnite, Altenberg,	38.43	51.00	17.09, Berzelius.
7. "	35.0	48.0	16.5, Ca 0.5, Bucholz
8. " "	39.04	51.25	18.48, Forchhammer.

B.B. infusible alone on charcoal, but when strongly heated becomes covered with small blisters, which crack as soon as formed. Some varieties take a wine-yellow or pink tinge when heated. With borax forms slowly a diaphanous glass.

Pycnite is a massive subcolumnar variety; G. Rose has observed the prism 93° 15′-93° 20′, proving its identity with topaz. The formula £1Si with one-seventh of the oxygen replaced by fluorine, is proposed by Rammelsberg.

Physalite or pyrophysalite of Hisinger is a coarse, nearly opaque variety, found in yellowish-white crystals of considerable dimensions; it intumesces when heated, and hence its name from puraw, to blow. Minute crystals of three or four different kinds, and two or three kinds of fluids have been detected by Sir David Brewster in crystals of topaz.

Topaz occurs in gneiss or granite, with tourmaline, mica, and beryl, occasionally with apatite, fluor spar, and tin; also in talcose rock, as in Brazil, with euclase, ec, or in mica slate. With quartz, tourmaline, and lithomarge, it forms the topaz rock of Werner. Specimens of quartz crystal from Brazil, penetrated by topaz, are not

Fine topazes come from the Urals and Altai mountains, Miask in Siberia, and from Kamschatka, of green and blue colors; Villa Rica in Brazil of deep yellow color, either in veins or nests in lithomarge, or in loose crystals or pebbles; aky-blue crystals in Cairngorm, Aberdeenshire; Jameson mentions one which weighed 19 oz; the tin mines of Schlackenwald, Zinnwald, and Ehrenfriedersdorf, smaller crystals. tals also at Schneckenstein and Altenberg; the Mourne mountains, small limpid crystals with beryl, albite, and mica, in drusy cavities in granite. Physalite occurs in crystals of great size, at Fossum, Norway; Finbo, Sweden, in a granite quarry, and at Broddbo in a boulder; one crystal from this last locality, at Stockholm. weighed eighty pounds.

Pycnite is from Altenberg, Schlackenwald, Zinnwald, and Kongsberg.


Topaz occurs in the United States at Trumbull, with fluor and diaspore, at Middletown, Conn., and Crowder's Mountain, N. C. At Trumbull the crystals are abundant, but are seldom transparent, except those of small size; these are usually white, or with a tinge of green or yellow. The large coarse crystals are sometimes six or seven inches in diameter.

A variety of topaz from Brazil, when heated, assumes a pink or red hue resembling the Balas ruby. The finest crystals are brought from Minas Novas in Brazil. From their peculiar limpidity, topaz pebbles are sometimes denominated gouttes d'eau. The coarse varieties of topaz may be employed as a substitute for emery. The name topaz, is from romagios, an island in the Red Sea.

ALTERED FORMS.—Topaz is found altered both to Steatite and Kaolin or Lithomarge. It is possible that pycnite has lost part of its alumina by a process of change, and hence the excess of silica.

STAUROTIDE, Haily. Staurolite. Grenatite. Staurolith, W.

Trimetric. $I: I=129^{\circ} 20', O: 1i=124^{\circ} 38'; a:b:c=1.4478:$ 1: 2.11233. $O: \frac{3}{2}i$ (plane of composition, f. 440)=134° 12'; $O: \frac{3}{2}i$ (plane of composition, f. 441)=119° 23', $I:ii=115^{\circ} 20'$. Cleavage:



ii distinct, but interrupted; I in traces. Crystals thick, often cruciform, surface often rough. Massive varieties have not been observed.

H.=7-7.5. G.=3.5-3.75. Subvitreous, inclining to resinous. Color dark reddish-brown—brownish-black. Streak uncolored, grayish. Translucent—nearly or quite opaque. Fracture conchoidal.

Composition.—(XI, Fe)Si½=(if XI: Fe=2:1) Silica 29.3, alumina 53.5, peroxyd of iron 17.2. But the crystals from Airolo in St. Gothard and Polewskoi in the Ural and Brittany, if correctly analyzed, are irreconcilable with this formula; the first affording ₩Si², and the second ₩Si².

Analyses: 1-4, Jacobson, (Pogg. lxii, 419); 5, Marignac, (Ann. Ch. Phys. [3], xiv, 49); 6-11, Jacobson, (Pogg. lxviii, 414):

	Si	X 1	Fe	₩n	Mg
1. St. Gothard,	30.31	46.80	18.08	-	2.16 Ca 0.13=97.48, Jac.) G.=3797
2 "	30.91	48.68	15.37	-	1.33, Mn1.19=97.48, Jac. in pieces,
3. "	2972	54.72	15.69	-	1.85=101.98, Jac. 3.744
4. "	29.13	52.01	17.58	-	1.28=100, Jac. pulveriz
5. "	28.47	53.34	17.41	0.31	0.72=100.25, Marig.
6. Airolo,	33.45	47.23	16.21	-	1-99=99·18, Jac. G.=3·66-3·73.
7. "	32.99	47.92	16.65	-	1.66=99.22, Jac.
8. Brittany,	39.19	44.87	15.09	-	0.82, Mn 0.87=99.64, Jac. G.=3.528.
9. "	40.35	44.22	15-77	-	, Mn 0·10=100·44, Jac.
10. Polewskoi, Ura	138.68	47.43	15.06	-	2·44=103·61, Jac. G.=3·549-3·588.
11. " "	38.33	45.97	14.60	-	2·47=101·37, Jac. " "

B.B. alone darkens, but infusible; with borax forms with difficulty a dark green

Occurs imbedded in mica slate and gneiss, at St. Gothard, in Switzerland; at the Greiner mountain, Tyrol, in simple crystals associated with kyanite and sometimes appearing as a continuation of its crystals, parallel with them. Angle of prism in a crystal from Cheronice, Switzerland, according to Kengott 128° 42′. Large twin crystals occur in Brittany; also at Oporto and St. Jago de Compostella, &c.

pearly. Cross fracture vitreous. Color grayish green, passing into greenish white and grayish white, rarely faint reddish; streak uncolored. Translucent—subtranslucent. Fracture uneven.

Composition.—(] R²+4 B)Si²—Silica 64·5, alumina 29·3, lithia 6·2.

Analyses: 1, R, Hagen, (Pogg. xlviii, 361); 2, Thomson, (Min. i, 302); 3, 4, Rammelsberg, (Pogg. lxxxv, 544); 5–8, Smith and Brush, (Amer. Jour. Sci. [2], xvi, 372):

		S i	X 1	₽e	Li	Йa	Ča
1.	Utö,	66.136	27 024	0.821	3.836	2.683	——=100, Hagen.
2	Killiney,	63.812	28.508	Fe 0.828	5.604		0.728, H 0.36=99.84, Thom.
	Utö,	65-02	29.14	Fe trace.	5.47	0.46	0.50, K 0.14, Mg 0.15, R.
4.	Tyrol,	65.23	29.04	Fe 1:42	4.49	0.07	0.97, K 0.07, Mg 0.07, R.
5.	Norwich	641)4	27.84	0.64	5.20	0.66	0.97, K 0.177, Mg 0.07, R. 0.34 ign.0.50, K 0.16==99.38,
							8. & B.
6.	**	63.65		28-97	5-05	0.82	0.31 " 0.50=99.30, S. & B.
7.		63.90		28.70	4-99	0.80*	0.26 " 0.60=99.25, "
8.	Sterling,	64.50	25.30	2.55	5.65	1.10	0.48 " 0.80, Mg 0.06==99.89,
	O.						8. & B.

a With some soda; in 5, 6, 7, magnesia, trace.

In a specimen from Sterling, Mass., Hagen found \$\overline{8}\$i 65-247, \$\overline{A}\$l \$\overline{F}\$e 27-556; and in another from Tyrol, \$\overline{8}\$i 66-027, \$\overline{A}\$l 26-451.

B.B. loses translucency and color, intumesces and fuses to a glassy globule; gives the reaction of lithia.

Occurs on the island of Utö, in Südermanland, Sweden, with magnetic iron ore, quartz, tourmaline, and feldspar; also near Sterzing and Lisens in the Tyrol, and of a pale green or yellowish color, imbedded in granite, at Killiney Bay, near Dublin, and at Peterhead in Scotland.

It occurs in granite at Goshen, Mass., associated at one locality with blue tourmaline and beryl; also at Chesterfield, Chester, Norwich, and Sterling, Mass.; at Windham, Maine, near the bridge, along with garnet and staurotide; at Brookfield, Ct., a few rods north of Tomlinson's tavern, in small grayish or greenish white individuals looking like feldspar. At Norwich, Mass., it is associated with triphyline, mica, beryl, and albite; one crystal from this locality was 161 inches long, and 10 inches in girt.


Named from $\sigma\pi\sigma\delta\sigma_5$, ashes, because the mineral becomes ashy before the blowpipe. The following are the angles obtained with the common goniometer, from the Norwich crystals: $O: ii=69^{\circ} 40', ii: I=138^{\circ} 30', ii: i>=107^{\circ}, 2i: 2i (top)=80^{\circ}.$ ii: $2i=139^{\circ} 45', ii: 2i=103^{\circ}, ii: -2=116^{\circ}, ii: -1=100^{\circ} 30', ii: x=140^{\circ}, ii: -2=134^{\circ}, ii: -2=142^{\circ}, I: -2=144^{\circ}, -1: -1=117^{\circ}, -2: -2=32^{\circ}.$

ALTERED FORMS.—Killinite of Thomson (Min. i, 330) has the appearance of spodumene, and occurs with it at Killiney Bay. Mallet states that it affords by cleavage a prism of 135°, which is very nearly the angle between the diagonal and prismatic cleavage of spodumene, both of which are perfect. II.—4. G.—2.56. Lustre vitreous, weak. Color greenish-gray, brownish, or yellowish. Composition. According to Lehunt and Blythe (loc. cit.) and Mallet, (Raumelsberg's 5th Sup. 143):

```
Æl
               Fе
                    Ċз
                          Мg
                               Мn
                                      K
                                            Ħ
                                          10:00=100:43, L.
      30.60 2.27
                   0.68
                         1.08
                                     672
49.08
                                          10·00=39·30, BL
3·67, Li 0·46=99·92, M.
      31.04 2.33
                         0.46 1.25
                   0.72
                                     6.06
47.93
52·89 33·24 3·27
                   1.45
                                     4.94
```

HORNBLENDE. Amphibole. Green diallage. Actinolite. Actinote. Tremolite. Calamite. Pargasite. Smaragdite. Asbestus, in part. Amianthus. Amianthinite. Amianthoid. Lotalite. Strahlstein, Tremolith, Kalamit, Amiant, W. Grammatit. Byssolith, Haus. Carinthine, Anthophyllite, Schumacher. Cummingtonite, Dewey. Breislakite, Brocchi. Raphilite, Thom. Arfvedsonite, Brooke. Agirin, Tammau, in part. Kymatin, Breit. Diastatite, Breit.

Monoclinic. C=75° 2', I: I=124° 30', O: 1i=164° 10', a:b:c =0.5527; 1:1.8825. Crystals sometimes stout, often long and



bladed. Cleavage: I highly perfect; ii, ii, sometimes distinct. Lateral planes often longitudinally striated. Twins: face of composition ii, as in f. 362, a twin of the form represented in f. 361.

 $0: 1i=155^{\circ} 33'$. $ii: i_3=147^{\circ} 39'$. $0:-1i=149^{\circ}.$ i3: i3=115° 18'. 0: -2i=124° 56'. ii: 33=124° 14'. 0: ii=104° 58'. ii: -33=130° 15'. 0:1=152° 36'. 2i: 2i(ov. O)=120° 52'. O: -1=145° 35'. 1:1=154° 26'. 0: -2=121° 29'. 1:-1=148° 28'. O: 2i=150° 26'. -2:-2=131° 36'. 0: ii=90°. 33:33=1110 32'. O: I=103° 12'. -33:-33=99°30'.ii: i3=99° 57'.

0								
11	1							
12.00			100	21				
	10		33					
ii	i3	I	13	ii				
	-		-33					
-2 <i>i</i>		-2	-	21				
-1 <i>i</i>	CE S	-1		(
	Ohear	eved P	lanes					

Imperfect crystallizations: fibrous or columnar, coarse or fine, fibres often like flax; sometimes lamellar; also granular, coarse or fine, and usually strongly coherent; sometimes friable.

H.=5-6. G.=2.9-3.4. Lustre vitreous to pearly on cleavage faces; fibrous varieties often silky. Color between black and white, through various shades of green, inclining to black ih green. Streak uncolored or paler than color. Sometimes nearly transparent; usually subtranslucent-opaque. Fracture subconchoidal, uneven.

Composition.—R*Si*=R*Si *4=R*Si*+RSi.
Isomorphism leads to the same variations of constitution in hornblende, as in pyroxene, and R may be either lime, magnesia, protoxyd of iron or manganese. Alumina replaces silica, in some varieties. The prominent varieties are the following :-

H.=6-7.25. G.=3.559, white kyanite; 3.675, blue transparent; 3.661, Tyrol, Erdmann. Lustre vitreous-pearly. Color blue, white, blue with white margins; also gray, green, black. Streak uncolored. Translucent-transparent.

Kyanite is generally in bladed crystallizations, though occasionally in short prisms; and these prisms or blades are bounded by the planes it and it, with clearage parallel to the larger face. The prevalent color is pale blue, which is often deeper along the middle of the prisms. The crystals may often be easily scratched on the lateral surface while they are very hard on the extremities.

Composition.—ÄlSi[‡]—Silica 37.0, alumina 63.0.

Analyses: 1-3, Arfvedson, (K. V. Ac. H. 1821, i, 148, and Schw. J. xxxiv, 203);

4, Rosales, (Pogg. lviii, 160); 5, Marignae, (Ann. Ch. Phys. xiv, 49); 6, 7, A. Erdmann, (Jahresb. xxiv, 311); 8, Jacobson, (Pogg. lxviii, 416); 9, 10, 11, Smith and Brush, (Am. J. Sci. [2], xvi, 49, 371);

```
1. Rôraas, Norway, 36.4
                              63.8
                                            =100.2, Arfvedson.
                                        -=99.22,
 2. St. Gothard,
                       34.33
                               64.89
                       36.9
                               64-7
                                         -=101.6
 3.
                               63.11 1.19=100.97, Rosales.
62.66 0.84=100.60, Mariguac. G.=3.6.
                       36.67
 5.
                       36.60
                                       0.52, Cu 0.19=96.97, Erd. G.=3.124.
0.71=100.16, Erd. G.=3.661.
 6. Röraas,
                       34.40
                               61.86
                       37.36
    Tyrol,
 8. Greiner, Tyrol,
                       37.30
                                62.60 1.08=100.98, Jacobson. G.=3.678.
 9. Monroe, N. Y.,
                               59-02 2:08, ign. 1:03=99:33, Smith and Brush.
                       37.20
10. " 37.03 61.90 " 0.85=99.78,
11. Lincoln Co., N.C., 37.60 60.40 1.60 " —=99.60,
```

B.B. unaltered. With borax slowly fuses to a transparent colorless glass. With cobalt solution, a dark blue.

This species occurs principally in gneiss and mica slate. Transparent crystals occur at St. Gothard in Switzerland; at Greiner and Pfitsch (Rhætizite or white variety) in the Tyrol; also in Styria, Carinthia, Bohemia; at Pontivy, France; Villa Rica, South America.

In Massachusetts, at Chesterfield, it occurs with garnet in mica slate; Worthington and Blanford in good specimens. In Connecticut, at Litchfield and Washing ton and Blanford in good specimens. In Connecticut, at Litchfield and Washington in large rolled masses with corundum and massive apatite; at Oxford, near Humphreysville, in mica slate. In Vermont, at Thetford and Salisbury; in New York at Monroe, Orange Co., (Monrolite). In Pennsylvania, in fine specimens near Philadelphia, on the Schuylkill road near the Darby bridge; near the Schuylkill on the Ridge road, back of Robin Hood Tavern; at Leiperville; at East and West Branford and Darby, Chester Co.; at Morris's Ferry, Delaware Co. In Maryland eighteen miles north of Baltimore, at Scott's mill; in Delaware, near Wilmington In Virginia at Willis's Mt., Buckingham Co., and two miles north of Chancellorville, Spotsylvania Co. In North Carolina, on the road to Cooper's gap in Rutherford Co., near Crowder's Mtn. In short crystals at Bellows Falls, Vt., in gneiss, at Westfield, and Lancaster, Mass., and at Jaffrey on the Monadnock Mt., N. H. A black variety associated with rutile occurs in North Carolina.

Kyanite, when blue and transparent, and in sufficiently large pieces, is employed.

Kyanite, when blue and transparent, and in sufficiently large pieces, is employed a gem, and somewhat resembles sapphire. The name is from verses, blue. The name sappare arose from a mistake by Saussure in reading a label of this mineral on which it was called sapphire. Disthene is from eig, twice, or of two kinds, and even, strong, alluding to its unequal hardness and electric properties in two different

directions.

Bamlite, Erdmann, (J. f. pr. Ch. xxxi, 165), from Bamle, Norway, has the structure and appearance of some Kyanite, occurring in columnar somewhat plumose forms, silky in lustre, with one perfect cleavage. H.=5-7. G.=2.984. Greenish white or bluish green. The analysis by Erdmann (loc. cit.) gave Si 56.90, X1 40.73, Fe 1.04, Ca 1.04, F trace=99.71. There is an excess of silica. But according to cent observations by Mr. I. Sæmann, there are minute prisms of quartz among the fibres of the Bamlite, which fully account for this excess.

Xenolite of Nordenskiöld resembles kyanite as well as bucholzite; and the analysis differs no more from the accepted formula than some that have been made of each of these species. Komonen obtained (Act. Soc. Sci. Fenn., i, 372, Pogg. lvi, 643) Silica 47.44, alumina 52.54—Al Si. H.—5. G.—3.58. From Peterhoff, Finland.

ALTERED FORMS.—Warthite appears to be an altered or hydrous kyanite, which it resembles. H.=7.25; white and translucent. Hess obtained (Pogg. xxi, 73) Si 40.58, Ål 53.50, Mg 1.00, H 4.63=99.71. B.B. infusible. From near St. Petersburg. Hydrobucholzite of Thomson is probably of similar origin. Thomson obtained (Min. i, 237) Si 41.35, Ål 49.55, H 4.85, gypsum 3.12=98.87. Probably from Sardinia.


Kyanite has also been observed altered to tale and steatite.

SILLIMANITE, Bowen. Bucholzite, Brandes. Fibrolite, Bournon.

Triclinic. $I: P=98^{\circ}$, but varying to 110°, and larger when the faces are much striated; $O: P=105^{\circ}$, $O: m=133^{\circ}$ 30′, $P: m=120^{\circ}$ 30′, $O: a=130^{\circ}$, D., (but only approximations, as the terminal planes are respectively approximations, as the terminal planes.

minal planes were rough and uneven.) Cleavage: perfect, parallel with the longer diagonal, affording a brilliant surface. Also compact or loose fibrous; and columnar massive.

H.=6—7.25. G.=3.238, from Norwich, Dana, 3.232. ib., Brush; 3.259, Yorktown, Norton; 3.239, bucholzite of Chester, Del., Erdmann. Lustre vitreous, approaching subadamantine. Color hair-brown, grayish. Streak uncolored. Translucent—transparent.



Bucholzite and fibrolite are generally fibrous massive, sometimes approaching distinct prisms, like those of sillimanite; the lustre approaches adamantine as in sillimanite. The colors are grayish, whitish and pale brown.

Composition.—Al Sit, like Kyanite—Silica 37.0, alumina 63.0. Bucholzite and shrolite of Bournon afford the same, according to Silliman, Jr. Most analyses of bacholzite give Al Si=Silica 46.9, alumina 53.1. Erdmann's (No. 9) corresponds to Al Sit. Bowen's and Hayes's analyses of Sillimanite afford Al Sit Silica 42.3, alumina 57.7.

I, SILLIMANITE—1, Bowen, (Am. J. Sci. viii, 113); 2, Hayes, (Alger's Min. p. 601); 3, Connel, (Jameson's J. xxxi, 232); 4, Norton, (2d edit. of this work, 378); 5, Staaf, (Jahresb. xxv, 348); 6, Silliman, Jr., (Am. J. Sci. [2], viii, 386. II, BUCHOLZITE—7, Brandes, (J. de Pharm. xci, 237); 8, Thomson, (Ann. Lyc. N. York, iii, and Min. i, 235); 9, A. Erdmann, (K. V. Ac. H. 1842, 19); 10, B. Silliman, Jr., (Am. J. Sci. [2], viii, 386). III, FIBROLITE—11, 12, B. Silliman, Jr., (Am. J. Sci. [2], 8, 388); 13, Chenevix:

			Si	Æl	₽Fe .
1.	Chest.Ct., Sillin	nanite	,42.66	56.111	1.999, H 0.510=99.286, Bowen.
2	46	"	42.60	54.90	1·10, Ca 0·31, Mg 0·4=99·31, Hayes.
8.	"	"	36.75		0.9=96.68, Connell.
4	Fairfield, N.Y.	"	37.700	62.750	2·287==102·789, Norton.*
5.	Chester, Ct.,	"	87 ·362	58 ·62 2	2·174, Mg 0·398, H 0·428=98·984, Staaf

[•] Prof. Norton states that in his analysis the excess of alumina was probably owing to the presence of aluminate of potassa, which remained with the alumina after separating the peroxyd of iron by caustic potassa; subtracting this excess, the analysis corresponds to those by Silliman.

VI. Containing alumina, with iron and lime.

Si Mig Ca fe Min Al

32. Westmanland, 42:00 2:

4200 2-25 11:00 30:00 0:25 12:00, Ĥ 0:75, K, trace=

33. Fuldaischen,

47:00 2:00 8:00 15:00 --- 26:00, H 0:5==98:50,

VIL Containing alumina, with iron and magnesia.

34. Garpenberg, 53:50 11:35 4:65 22:52 0:35 4:40, H 0:6=97:10, His.

Cummingtonite is an anthophyllite variety containing largely of oxyd of iron resembling an asbestiform tremolite, often scopiformly arranged; color ash-gray, lustre silky. B.B. alone fuses with great difficulty. Formula, (‡ Fe+‡ Mg) Si, Smith and Brush, (Anal. 15, 16.)

The analysis by Thomson, (Ann. Lyc. Nat. Hist. New York, iii, 50), referred by Shepard to Boltonite, is shown by B. Silliman, Jr., (Am. J. Sci. [2], viii, 391), to pertain probably to an actinolite from Bolton. The Raphilite, according to Hunt, has the augite oxygen ratio 2: 1, (anal. 9).

The fluorine is name hornblendes is supposed to exist as fluorid of calcium, and this ingredient, according to Bonsdorff may constitute 1 part in 5 of the mineral.

B.B. the tremolite and pale varieties, containing no iron, fuse readily with intumescence to a glass nearly transparent to milk-white; and with borax form a transparent colorless glass. The lighter colored varieties containing iron, fuse alone with more or less difficulty to a dark yellowish glass, and with borax give a transparent glass, tinged with iron. The darker green varieties afford a deeper iron color. The hornblende, containing alumina and little iron, acts much like tremolite; but the black varieties fuse to a brilliant black lead, and the borax glass is tinged with iron. Anthophyllite fuses with great difficulty to a glass colored by iron. Articologic fuses readily with intumescence to a black magnetic globule.

Green or black hornblende is one of the constituents of syenite and greenstone, as well as hornblende rock and slate. Tremolite is most common in dolomite and granular limestone. Hornblende also occurs in granular limestone and in trachyte. Actinolite is found in the greatest perfection in talcose rocks. Asbestus often traverses serpentine rocks and granular limestones. Much of the so-called asbestus in serpentine is Chrysotile.

Aussig and Teplitz in Bohemia, Tunsberg in Sweden, and Pargas in Finland, afford fine specimens of the dark colored hornblendes. Actinolite occurs at Saltzburg and Greiner, in the Zillerthal; Tremolite at St. Gothard, in granular limestone or dolomite, the Tyrol, the Bannat, Gulajö in Sweden, &c. Calamite occurs at Normarken in Sweden, in prisms in serpentine. Asbestus is found in Savoy, Saltzburg, the Tyrol; also in the island of Corsica, where it is so abundant that Dolomieu employed it in packing his minerals. Rock cork is obtained in Saxony. Portsoy, and Leadhills, where also mountain leather occurs. Oisans, in France, affords a variety of amianthus, composed of fibres having some degree of elasticity; it is the amianthoide of Hany. Anthophyllite comes from Kongsberg, Norway, &c.

Arfredsonite was brought first from Greenland, where it is associated with soda-

lite. It occurs also at Fredericksvärn, in Norway.

In the United States, black crystals of hornblende occur at Franconia, N. H.; at Chester, Mass.; at Thomaston, Me.; at Moultonboro', Me., in Syenite; at Willsboro', N. Y., presenting interesting crystalline forms; also near the bridge at Potsdam, St. Lawrence Co., N. Y.; near Greenwood Furnace, and in Warwick, Orange Co., N. Y. (f. 365.) Crystals of a dark green color occur near Two Ponds, and also a mile north, two and a half miles north, and a mile south of Edenville, together with gray or hair brown crystals and tremolite, sphene, and chondrodite, in granular limestone. Near Amity, hornblende occurs of various forms and colors, and often in large and perfect crystals: in dark green crystals, with ilmenite, at the Stirling mines, Orange Co.; at Gouverneur, in short green crystals, sometimes two or three inches in diameter, along with apatite; in Rossie, two miles north of Oxbow, the variety pargasite in neat bright green crystals. Pargasite occurs also at Phipsburg and Parsonsfield, Me. Gray hornblende or tremolite in good crystals is found at Bryam, N. J., and other varieties at Franklin and Newton of the same State.

EUCLASE, H. Euklas, W.

[onoclinic. C=71° 7'; $I: I=115^{\circ}$ 0', $O: 1i=162^{\circ}$ 30'; i: c=0.49492: 1: 1.4852. Angles, (Schabus, Denks. K. Ak. n, vi, 57):

 $1:1=151^{\circ}43'$.

 $-1:-1=143^{\circ}42'$.

 $ii = 108^{\circ} 53'$. $1i = 158^{\circ} 10'$. $1i = 130^{\circ} 52'$. $-33:-33 (front)=156^{\circ} 14'$.

I=147° 30′. $3\hat{s}: 3\hat{s} \text{ (front)} = 105^{\circ} 49\frac{1}{3}'$.

 $i2=162^{\circ}\ 20'$. $-3\hat{s}:-3\hat{s}$ (front)=90° 56′. i2=144° 40'. $-2\hat{2}:2\hat{2}$ (front)=133° 29′.


 $-33=101^{\circ} 53'$. $3:3(front)=130^{\circ}16'$.

 $-3\frac{3}{2}=112^{\circ}50'$. $2i : 2i(top) = 115^{\circ} 32'$.

 $-4\frac{4}{3}$ =130° 17 $\frac{1}{3}$ ′. ii: 3i=127° 5′. vage: ii highly perfect; O and ii much

distinct.

.=7.5. G.=3.036, Mallet; 3.098, Haidr. Lustre vitreous. Color pale mountain-



						0						
$-\frac{1}{2}i$		Vi —										1/2
71					117	-1						
										-22		21
												51
	-32	-33		-33					4			
					1-	7						131
								$-4\frac{4}{3}$				41
ii		i3	i2	$i\frac{3}{2}$	i 4/3	I			$i\frac{3}{2}$			ii
					-	3	397				33	
11			= 1			1			= 3			

Observed Planes. Add i 10, i 12, i 18, i 18, i 32, Schabus.

m, passing into blue and white. Streak uncolored. ent; occasionally subtransparent. Fracture conchoidal. Very

mposition. – (1Be+1Al)Ši‡, G. Rose—Silica 48-2, alumina 32-6, glucina 24-2 2. Analyses: 1, Berzelius, (Schw. J. xxvii, 73); 2, Mallet, (Phil. Mag. [4], v,

. Bi	Æl	₽e	₿e	§n
1. 43.22	80.26	2.22	21.78	0.70=98.48, Berz.
9 44.18	21.27	1:31	91.43	0:85-99:14 Mallet

B. strongly heated intumesces and becomes white, throws out points, and melts white enamel, if the temperature is still further increased. Dissolves with a with effervescence to a clear glass. A silica skeleton with salt of phosphorus, mes electric by friction, and when once excited, retains this property for al hours. Not acted on by acids.


Occurs in Brazil, in the mining district of Villa Rica, in chlorite slate resting on sandstone. The crystallization of this species is elaborately detailed by Schabus in the Transactions of the Royal Academy of Vienna, vol. vi.

Euclase receives a high polish, but is useless as an ornamental stone on account of its brittleness. Named by Haüy from \$\vec{v}\$, casily, and \$\vec{v}\lambda \vec{v}\$, to break.

SPHENE. Titanite. Menakerz. Menachine Ore, Wern. Titane Silico-calcaire, H. Lederite, Shepard. Greenovite, Duf. Spinthère. Pictite, Saus. Arpidelite.

Monoclinic. C=60° 27'; $I: I=113^{\circ}$ 28', $O: 1i=159^{\circ}$ 34': a:b:c=0.5678:1:1.326.*

 $O(y): ii(P)=119^{\circ} 33'.$ $-1(l):-1(l)=133^{\circ}48'$. $-2(t):-2(t)=110^{\circ}$ 54'. $O(y): 1i(x)=158^{\circ} 55'$. $O(y): 14(x) = 138 - 33 \cdot .$ $O(y): 4i(s) = 123^{\circ} 52' \cdot .$ $O(y): I(r) = 114^{\circ} 21' \cdot .$ $O(y): 1(z) = 154^{\circ} 13' \cdot .$ $O(y): 2(n) = 141^{\circ} 36' \cdot .$ $22(e):22(e)=157^{\circ}12'.$ $12(w): 12(w)=164^{\circ} 32'.$ I(r): $I(r) = 113^{\circ} 28'$. 63 (u): $ii(b) = 140^{\circ} 26'$. $-3\hat{s}$ (m): $-3\hat{s}$ (m)= 76° 1'. $-3\hat{s}$ (m): i(b)= 141° 59'. $O(y): -1(l)=139^{\circ} 20'.$ $O(y): -2(t)=109^{\circ} 37'$. $ii(P): i3(o)=167^{\circ} 40'.$ $ii(P): ii(b)=90^{\circ}.$ $1(z)': 1(z)=149^{\circ} 38'.$ $2(n) : 2(n) = 136^{\circ} 4'$. 449



 Authors generally take P as the base of the fundamental prism, y as the plan replacing the front angle, and I as the lateral prismatic planes. Above, in figure

Cleavage: sometimes distinct parallel with I; orthodiagonal less so; parallel with -1, also very imperfect, and not easily obtained. Sometimes massive, compact, and rarely lamellar.

H.=5-5.5 $G = 3 \cdot 1 - 3 \cdot 56$. Lustre adamantine — resinous. Color brown, gray, yellow, green, and black. Streak white, slightly reddish in greenovite. Transparent—opaque. Brittle.

Composition.—The analyses afford 3Ca, 2 Si, 3 Ti=silica 30 45, titanic acid 41 33, lime 28:22=100, (which have been written 2Ca Si+CaTi².) The oxygen of the Ca and Ti is to that of the Silica as 3:2=1:3, and this leads to the formula (Ca+Ti) Sif or #Sif, (since Ca+Ti=RO+RO²=R²O³); so that sphene is a silicate of a peroxyd (Fi) in which part of the Fi is replaced by Ca. It is probable that there is the same kind of replacement by a protoxyd in much ilmenite, and also in Keilhauite, etc., and that there are properly no silico-titanates. The formula accords with the relation in form to Euclase.

Analyses: 1, Fuchs, (Ann. d. Ch. u. Pharm. xlvi, 319); 2, H. Rose, (Pogg. lxii, 253); 3, 4, Rosales and Brooks, (ib); 5, Marignac, (Ann. Ch. Phys. [3], xiv, 47); 6, Delesse, (Ann. d. Mines, [4], vi, 325): 7, T. S. Hunt, (Am. J. Sci. [2], xv, 442):

```
Тi
                                       Si
                                     32.52 43.21
                                                         24·18=99·91, Fuchs; G.=3·44.

    Schwarzenstein, yw.

                                                         26.61, Fe 0.96=101.44, Rose; G.=3.535.
22.25, Fe 5.06=99.43, Rosales.
25.00, Fe 3.93=102.12, Brooks.
27.65, Fe 0.76, Mn 0.76=100, Marignac.
24.3, Mn 3.6=100.3, Delesse.
2. Zillerthal, ywh. green,
                                     32.29
                                               41.58
   Arendal, brown,
                                     31.20
                                               40.92
   Passau,
                                     30.63
                                               42.56
5. Piedmont, Greenovite,
                                     32.26
                                               38.57
                                     80.4
                                               424)
7. Grenville, Lederite,
                                     31.83 40.00 28.31, ign. 0.40=100.54, Hunt. G.=3.5.
```

B.B. the yellow varieties are not altered in color; the others become yellow; they slightly intumesce, and fuse on the edges to a dark enamel. With borax they afford a clear yellowish-green glass. Imperfectly soluble in heated muriatic acid; and if the solution be concentrated along with tin, it becomes of a fine violet color.

This species was formerly divided into titanite and sphene; the former included

the brown or black variety, the latter the lighter colored and translucent.

Greenovite, from St. Marcel in Piedmont, was shown to be identical in crystallization with sphene by Breithaupt (Pogg. lviii, 257) and Descloizeaux, (Ann. Ch. Phys.

Sphene occurs in imbedded crystals, in gneiss, granite, mica slate, and granular limestone; also in syenite, beds of iron ore, and volcanic rocks. Found with pyroxene, in beds of iron ore, at Arendal in Norway; in granite in Greenland; in complicated compound crystals of a pale green color and transparent, at Graubinden in the Grisons, associated with feldspar and chlorite; in mica slate at St. Gethard, also at Mont Blane and clearly in the Alexand Small and the state of the state Gothard; also at Mont Blanc, and elsewhere, in the Alps. Small crystals occur in syenite at Strontian in Argyleshire, and Criffel in Galloway. Occasionally it is found among volcanic rocks, as at Lake Laach, and Andernach on the Rhine.

Occurs in Canada at Grenville, Elmsley, Burgess and Grand Calumet Island, in amber-colored crystals; in the trap of Montreal, Yemaska, Monnoir, and Brome Mts. In Maine in fine crystals at Sanford, also at Thurston. In Massachusetts, good crystals in gneiss, in the east part of Lee; at Bolton with pyroxene and scapolite in limestone; at Pelham. In Connecticut, at Trumbull. In New Jersey, at Franklin, of a honey-yellow color. In Pennsylvania, Buck's Co., three miles west

Fig. 450 represents an ideal crystal containing all known planes; it has both the old and new lettering.

^{450, 451,} y is made the base, and r the prismatic planes, a course recommended not only by the simplicity it gives to the view of the crystallization, but also by the fact that y is a common plane of composition in twins, and r is the direction of most distinct cleavage; moreover the analogy with Euclase is thus brought out. In Euclase $I:I=115^\circ$, $O:1i=158^\circ$ 10', $1:1=151^\circ$ 43', and the same angles in Sphene are 113° 28', 158° 55', 149° 38'.

leading to the formula (123+131) Si2. But the species is probably bad. It was named from raxes, quick, how, to dissolve or to fuse. A similar mineral from Sasebuhl near Dransfeld, afforded Schnedermann,

Bi 5574, 基l 12·40, Fe 18·06, Mg 6·92, Na 8·88, K 0·60, Mn 0·19, H 2·78—99·80.


B.B. melts easily with intumescence to a brown slag or opaque glass.

Occurs at Säsebühl in basalt and wacke, and resembles obsidian or gadolinite in external characters: also at Vogelsgebirge; sp. gr. of this variety, (called Hyalomelan [fr. valos, glass, pelas, black] by Hausmann), 27144. (Breithaupt, Kastner's Archiv. vii, 112. Gmelin, Pogg. xlix, 283).

On the north shore of Lake Superior occurs a mineral resembling Tachylyte; also

in a trap dyke at Johnsburg, Warren Co., New York

BABINGTONITE, Levy, Ann. Phil. 2d ser. vii, 275.



Triclinic. Observed planes as in the annexed figure, $O: I=92^{\circ}$ 34', $O: I'=88^{\circ}$, $O: \frac{1}{2}=150^{\circ}$ 25', $I: I'=112^{\circ}$ 30', $I: i'=132^{\circ}$ 15', $I': i'=115^{\circ}$ 15', $I': i'=155^{\circ}$ 25', $I: I'=155^{\circ}$ $i\bar{s}'=137^{\circ}5'$, $i\bar{i}:i\bar{s}'$ (over I)=90° 40′. Levy. H.=5·5—6. G.=3·35—3·5. Lustre vitreous, splendent. Color dark greenish-black;

thin splinters green in the direction of O, and brown transversely. Faintly translucent; large crystals, opaque, or faintly subtranslucent. Fracture imperfectly conchoidal.

Composition.—(Ca, Fe) Si. Analyses: I, Arppe, (Berz. Jahresb. xxii, 205); 2, R. D. Thomson, (Phil. Mag. xxvii, 128):


Bi	Мg	Ĉa	Fе	Йn	Ϫ 1
1. 54.4	2.2	19.6	21.3	1.8	0.3 ign. 0.9=100.5, Arppe.
9 47-48	2-21	14-74	16:81	10.16	6.48 jon 1.94=99.10 Thomson

Reckoning the alumina with the silica, the two analyses essentially agree; but the mineral requires further investigation. G. of No. 2=3.855.

B.B. fuses easily to a black magnetic bead. With borax affords a clear ame-

thystine globule, which becomes green in the reducing flame.

Babingtonite occurs in distinct crystals at Arendal, in Norway, associated with epidote and massive garnet, and in the Shetland Isles, imbedded in white quartz. It was named after Dr. Babington; it resembles some dark varieties of pyroxene.



In the United States it is said to coat crystals of feldspar, at Gouverneur, St. Lawrence Co., N. Y.

seldspar, at Gouverneur, St. Lawrence Ce., N. Y. Small black polished crystals coating mica slate, or micaceous gneiss, at Athol, Mass., (fig. annexed), have been referred here by Shepard. The author's measurements give the following approximate angles, $O: I=90^{\circ}-91^{\circ}, O: I'=85^{\circ}, O: \frac{1}{2}'=158^{\circ} 20', I: I=120^{\circ} 30'$ and 69° $80', I: I=129^{\circ}, I': I=120^{\circ} 30', O: -1=135^{\circ}$ $40', O: 1=135^{\circ}$ $30', O: I=135^{\circ}$ $30', I: \frac{1}{2}=95^{\circ}$ $30', I: \frac{1}{2}=95^{\circ}$ 30'.

BERYL. Emerald. Aquamarine. Smaragd. Emeraude, H. Davidsonite, Rick-ardson. Goshenite, Shepard.


Hexagonal. $O: 1=150^{\circ} 3': a=0.499.$

O: 3=139° 10′ O: 2=130° 58′. *O*: 12=116° 37′. $I: 33=142^{\circ} 11'$. $0:22=135^{\circ}4'$. $I: 8\frac{3}{7} = 165^{\circ} 30'$. $0:2\$=130^{\circ}58'.$ $0: I = 90^{\circ}.$ $I: I=120^{\circ}.$

Cleavage: basal imperfect; lateral, indistinct. Ocasionally coarse columnar and large granular.







H.=7.5-8. G.=2.732, emerald, Haidinger; 2.678, apple-green. Lustre vitreous; sometimes resinous. Color pale green, emeraldgreen, passing into light-blue, impure yellow and white. white. Transparent-subtranslucent. Fracture conchoidal, uneven. Brittle.

Composition.—(†Be+†Al) Ši²—Silica 66.9, alumina 19.0, glucina 14.1=100. Analyses: 1, Du Menil, (Schw. J. xxxix, 487); 2, Berzelius, (Schw. J. xvi, 265, 277); 3, Klaproth, (Beit. iii, 215); 4, Moberg, (Acta Soc. Sci. Fenn. ii, 81); 5, Schlieper, (Ramm. 2d Supp. 24); 6, Bornträger, (Jahrb. Min. 1851, 185); 7, J. W. Mallet, (Am. 1851, 180); J. Sci. [2], xvii, 180):

Si X1 Fe Be Siberia, Beryl,
 Broddbo, " 67-00 68:35 Emerald, 68.50 Finland, 67:359 16:465 1:497 S. Amer. 69:51 14:49 6. Beryl, Hirschgasse, 66.90 7. "Goshen, 66.97 17.22 2.03 12.91, Mn tr.=99.13, Mallet. 66-97

Other analyses: Mallet, (Ramm. 5th Suppl. 66); W. Mayer, (Jahrb. Min. 1851, 185, and Lieb. Kopp, 1851, 779); Müller, (J. f. pr. Ch. lviii, 180).

B.B. alone unchanged or becomes clouded; at a high temperature the edges are rounded, and ultimately a vesicular scoria is formed. Glass with borax, clear and colorless for beryl, a fine green for emerald. Slowly soluble with salt of phosphorus without leaving a siliceous skeleton. A yellowish variety from Broddbo and Finbo yields with soda, traces of tin.

Emerald and heryl are varieties of the same species the former in the

Emerald and beryl are varieties of the same species, the former including the rich green transparent specimens, which owe their color to oxyd of chrome, the latter, those of other colors. Fine emeralds are found in a vein of dolomite, which traverses a hornblende rock at Muzo, north of Santa Fé de Bogota. A perfect hexagonal crystal from this locality, two inches long, is in the cabinet of the Duke of Devonshire; it measures across its three diameters 21 in., 21 in., 11 in., and weighs 8 oz 18 dwts; owing to flaws, it is but partially fit for jewelry. A-more splendid specimen, though somewhat smaller, weighing but 6 oz, is in the possession of Mr. Hope, of London. It cost £500. Emeralds of less beauty, but much

^{*} M. Lewy states that the rock is a black limestone, some parts of which contain fossils.

larger, occur in Siberia. One specimen in the Royal collection measures 14½ inches long and 12 broad, and weighs 16½ pounds troy; another is 7 inches long and 4 broad, and weighs 6 pounds troy. Mount Zalora, in Upper Egypt, affords a less distinct variety, and was the only locality which was known to the ancienta Other localities are Canjargum in Hindostan, and Salzburg, where it is imbedded in mica slate.

Pliny speaks of the finest beryls as those "qui viriditatem puri maris imitantur,"—green like the sea,—and crystals of clear shades of sky-blue, or mountain-green, are hence termed aquamarine. This variety is found in Siberia, Hindostan, and Brazil. In Siberia they occur in the granite district of Nertschinsk, and in the Uralian and Altai ranges of Siberia. They have been obtained exceeding a foot in length, and are commonly striated longitudinally. The most splendid specimen of this variety of which we have any account, belongs to Don Pedro. It approaches in size, and also form, the head of a calf, and exhibits a crystalline structure only on one side; the rest is water-worn. It weighs 225 ounces troy, or more than 18½ pounds. The specimen is transparent, and without a flaw. Less clear crystals of beryl occur at the Mourne mountains, Ireland, county Down; rarely at Cairngorum in Aberdeeashire; at Limoges in France; Finbo and Broddbo in Sweden; Pfitscher-Jeck, Tyrol; Bodenmais and Rabenstein in Bavaria, tin mines of Schlackenwald, also in

Australia, and elsewhere.

Beryls of gigantic dimensions have been found in the United States, at Acworth and Grafton, N. H., and Royalston, Mass. One beryl from Grafton, N. H., weight 2900 pounds; it is 32 inches through in one direction and 22 in another transverse. and is 4 feet 3 inches long. Another crystal from this locality, according to Prof. Hubbard, measures 45 inches by 24 in its diameters, and a single foot in length. by calculation weighs 1076 lbs., making it in all nearly 2½ tons. At Royalston, ose crystal exceeded a foot in length. The smaller crystals are often limpid and a yellowish variety, forms a gem resembling chrysolite; the colors are mostly aquamrine, grass-green, and yellowish-green; one locality is in the southeast part of Royalston, near the school-house, on the land of Mr. Clarke; the best crystals are imbedded in quartz. A still better is situated 4 miles beyond the old one in South Royalston; some crystals of a sky-blue color in white quartz are beautiful. At Barre, Mass., there is a similar locality, though less remarkable; also at Pearl Hill, in Fitchburg, Goshen, and Chesterfield, Mass. At Compton, N. H. the beryls are as fine as at Royalston. Albany, in Maine, and Norwich, a few miles above Bethel, towards Waterford, afford fine large beryls with green and black tourmalines; crystals, often large, are also obtained at Streaked Mountain, with black tourmaline and mica; at Bowdoinham and Topham of a pale green or yellowish white color in veins of graphic granite; at Georgetown, Parker's Island, at the mouth of the Kennebec; at Wilmot, N. H.; with modified terminations, (f. 369), at Haddam, Conn., in a feldspar vein in gneiss, on the east side of the river; the crystals are limpid at the extremity for about a twelfth of an inch, as indicated by the dotted line in f. 369; the chrysoberyl locality affords less interesting specimens; also the Middletown feldspar quarry, and the granite of Chatham, near the cobalt mine. At Monroe, Conn., beryl occurs in a granite vein, and the crystals often consist naturally of several pieces separated by plates of quartz, (f. 194). Crystals, sometimes 10-12 in. long and 11 in. in diameter, occur with black tourmalines at Leip erville and Chester, Penn., Delaware Co.; also less interesting at Mineral Hill.

The emerald derives its color from the presence of a minute quantity of oxyd of

chrome, and beryl from oxyd of iron.

The species Dioptase and Pyrosmalite are homocomorphous with Beryl, and have the same oxygen ratio between the bases and silica, if the water and chlorine be excluded.

ALTERED FORMS.—Kaolin, Mica, Limonite and Quartz, occur as pseudomorphs after Beryl, the last two by substitution, the others by alteration. The change to Kaolin is the same essentially as in feldspar.

An altered beryl, from Tirschenreuth afforded H. Müller, (J. f. pr. Chem. lviji, 182), Si 58-8, Xl 24-7, Be 10-2, Fe 2-6, H 25

	,	.) xxxv,
K Li P F 1.80 1-22 0·10 2·41=100, 0·68 1·17 0·27 2·68=99·92, 0·21 0·48 0·27 2·47=100, 2·17 0·41 0·23 2·70=100.		Earlier Analyses; Sworton II, 27—80, Gmellin, (Schw. J., xxxi, 299, xxxviii, 514, Pogg. ix, 172); Sxcrnov III, 31, Hermann, (J. f. pr. Ch. xxxv, 282); Sxcrnov IV, 82, 88, Gmelin, (loc. cit.); 84, Hermann, (loc. cit.); Skrriov V, 85, 86, Gmelin, (loc. cit.); 87, 88, Hermann, (loc. cit.); Skrriov V, 85, 86, Gmelin, (loc. cit.); 87, 81, Hermann, (loc. cit.); Skrriov V, 85, 86, Gmelin, (loc. cit.); 87, 81, Hermann, (loc. cit.); Skrriov V, 85, 86, Gmelin, (loc. cit.); 87, 81, 41, 18, 816 11.11 7.77 5.99 0.98
Na 2.00 2.00 8.60 1.97	117, 25.44 119, 3°28 22, 2°94 22, 3°37 22, 3°37 26, 3°46	86. in 17 8. in 18 8.
3 § 2	17, 18, 28, 28, 28, 28, 28, 28, 28, 28, 28, 2	Character (V, 35, 17, 17, 17, 17, 17, 17, 17, 17, 17, 17
1.02 1.02 1.60 0.61		Secretary Secret
1.12 2.60 0.97 449	2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2	(i, 299, 1)
44.41 48.15 43.97 41.88	9, 8-26 10, 2-49 11, 2-72 12, 2-22 13, 2-05 14, 2-16 16, 2-31 16, 2-31	Mw. J., xxxi, 299 rmann, (loc. cit.) En Pe Fe 1:11 777 fr. 5:81 0:43 17:86 2:50 0:50 12:07 2:14 6:96 6:92 6:92 6:92 6:92 2:80 7:43 0:27 0:27 0:27 0:27
7.87 9.00 7.41 8.56	2) 20	elin, (Schw. 184, Herman El Herman El Herman 111 111 111 111 111 111 111 111 111 1
89.27 88.38 88.38 41.16	1. 8-19 2, 2-98 8, 8-50 4, 8-49 5, 3-32 7, 8-11 7, 8-11	Hmelin (Schw. J.); 84, Hermann H. H. H. H. H. H. H. H. H. H. H. H. H.
G. 8 022 8 019 8 082 2 998	. 10,88,4,00,00,00	Ei 27—30, Galain, (loc. cit., [loc. cit., [loc. cit., 2]] Ei 25 Ei
28. Red Elba, 8-022	Loss by ignition, in analysis	### Rarlier Analyses; Section I 282); Section IV, 82, 83, Gmel 27. Brown, St. Gothard, 83, 80. " Raringbricka, 83, 67een, Brazil, 82. Green, Brazil, 83. " Chesterfield, 84. " Totech. Gora, 44, 86. " Perm, 86. " Perm, 87. Achroite, Elba, 87. Achroite, Elba, 88. Red, Sarapulak, 88. " Red

In the United States, magnificent red and green tourmalines have been found at Paris, Maine, some crystals over an inch in diameter, transparent, ruby-red within, surrounded by green, or red at one extremity and green at the other; blue and pink varieties commonly imbedded in lepidolite, still to be found. Red and green, at Chesterfield, Mass., in a granite vein with albite, uranite, and pyrochlore; the crystals small and curved, nearly opaque, and fragile; green crystals often with distinct prisms of red color inside, especially when in smoky quartz; blue also at this locality. At Goshen, Mass., similar varieties occur, and the blue is met with in greater perfection. At Norwich, New Baintree, and Carlisle, Mass., good black crystals; also Alstead, Grafton, Sullivan, Acworth, and Saddleback Mt., N. H., and Streaked Mountain, Me.; Brattleboro', Vt.; large brownish black crystals abundant in steatite at Orford, N. H. Green and black crystals with beryl and feldspar at Albany, Me. Perfect dark brown crystals in mica-slate near Lane's Mine, Monroe, Conn.; sometimes two inches in length and breadth. At Haddam, Conn., in In the United States, magnificent red and green tourmalines have been found at roe, Conn.; sometimes two inches in length and breadth. At Haddam, Conn. interesting black crystals in mica slate with anthophyllite, also in granite with iolite, and also at the gneiss quarries, on the east side of the river. Near Gouverneur, N. Y., light and dark brown crystals, often highly modified, with apatite and scapolite in granular limestone, (f. 253, 254, p. 174); at Canton; in simple prisms in the same rock near Port Henry, Essex Co.; at Schroon, with chondrodite and scapolite; fine brown crystals at Crown Point, one mile south of village. Black crystals at the chrysoberyl locality near Saratoga, N. Y.; also at Alexandria, Jefferson Co.; at Kingsbridge, N. Y., brown, yellowish or reddish-brown crystals in dolomite; gray or bluish-gray and green in three-sided prisms occur near Edenville; short black crystals in the same vicinity, and at Rocky Hill, sometimes 5 inches in diamblack crystals in the same vicinity, and at Rocky Hill, sometimes 5 inches in diameter; a mile southwest of Amity, yellow and cinnamon colored crystals with spinel in calc spar; also near the same village a clove-brown variety with hornblende and rutile in granular limestone. At Franklin, Hamburgh, and Newton, N. J., black and brown crystals in limestone, with spinel. Good crystals in Pennsylvablack and brown crystals in limestone, with spinel. Good crystals in Pennsylvania at Newlin, Chester Co.; at London Grove and near Unionville, of a light yellow or brownish yellow, (f. 458), in limestone, and rarely white; at Parksburg; Aston; at Chester, fine black; Lieperville, Delaware Co., black; Marple, Lancaster Co., of a green color in tale; opposite New Hope, Buck's Co.; in New Garden township, Chester Co., in limestone, light brown to yellow and sometimes transparent. Near New Hope on the Delaware, large black crystals, in which the prismatic faces are sometimes almost obsolete. Also in Cheowee valley, South Carolina; Habersham Co., Georgia. In Canada, superb greenish-yellow crystals, 1 inch through, in limestone at G. Calumet, Id.; amber colored at Fitzroy, C. W.; transparent brown (f. 457) at Hunterstown, C. E., with idocrase and garnet; black at Bathurst and Elmsley, C. W., and St. Jerome, C. E. Bathurst and Elmsley, C. W., and St. Jerome, C. E. Figure 459 represents a crystal from northern New York; and 460 as well as 457

crystals from Canada, both of these last furnished the author for examination by

T. S. Hunt.

A green Tourmaline gave Brooke and Miller, from whom the above angles are cited, O: R=134° 2' 24"; a red, 133° 48'; a black from Modum, 133° 47' 12"; a light brown, 133° 56'; a white afforded Brooke, 134° 7'. A green gave Kupffer 134° 3', a

black 134° 6', a red 133° 58'.

ALTERED FORMS.—Tourmaline occurs altered to Mica, Chlorite, Steatite. The mica is lepidolite, a species which is related in composition to some tourmaline and is a frequent associate of the red and green varieties. It appears to take place through the addition of alkalies. Some rubellites and green tourmalines at these terfield are hollow, evidently from decomposition and removal of the interior; and in the cavities are occasionally observed small crystals of yellow uranite, (Teschemacher).

MELINOPHANE, Th. Scherrer, J. f. pr. Chem. lv. 449.

Dimetric or hexagonal; optically uniaxal, Descl. Massive, with a scaly and sometimes foliated structure. Cleavage in one direction. H.=3. G.=30, Richter. Lustre vitreous. Color sulphur, eitron, or honey-yellow. Not phosphorescent. Brittle.

Composition, according to an approximative analysis by R. Richter, (loc cit.):

Ŷę %a %a Ċa δi Вe En Fe Ŧı F Si, Zr, &c, Y. 448 2-2 124 14 1.1 **3**1-5 0-3 26 2-3 0-3-98 8.

This analysis gives for the ratio of the oxygen of the protoxyds, peroxyds, and

silies, if we suppose the fluorid as replacing protoxyds, 1½: 1: 3.

From the zircon-syenite of Norway, near Fredericksvärn, with elseolite, mics, fluor spar, and magnetic iron. An imperfect crystal in the cabinet of R. P. Greg, Eaq. gave him M: M'=133°, and edge M: M replaced by a rough plane, apparently not equally inclined to M and M'. The place of this species in the system is doubtful.

IV. GARNET SECTION.

Oxygen ratio for the bases and silica 1:1, varying to 1: \(\frac{3}{4}\), (Chondrodite), and 1:\(\frac{4}{3}\), (Scapolite).

1. CHRYSOLITE GROUP.—Trimetria.

Chrysolite, (fe, Mg)² Si, Tephroite, Mn² Si Monticellite, († Ca+†Mg)² Si, Knerelite, (fe, Mn)² Si Fatalite, fe ² Si, Crondrodite, Mg² Si

2. PHENACITE GROUP.—Hexagonal. R: R=115°-117°.

WILLEMITE, Znº Ši, PHENACITE, Be Ši.

2. GARNET GROUP.-Monometric.

Garnet, $(\frac{1}{2}R^2+\frac{1}{2}H)$ Si, Helvin, $(\frac{1}{2}R^2+\frac{1}{2}H)$ Si, in which R= (Mn, Fe, MnS.)

Pyrope, (18+18)Si

4. SCAPOLITE GROUP .- Dimetric.

Ziroon, Zr $\overline{S}i$, Meionite, $(\frac{1}{2}\hat{C}^{0}+\frac{1}{4}\overline{A}1)\overline{S}i$. Idocrase, $(\frac{1}{4}\hat{B}^{0}+\frac{1}{4}\overline{B})\overline{S}i$, Scapolite, $(\frac{1}{4}\hat{B}^{0}+\frac{1}{4}\overline{A}1)\overline{S}i$, " $(\frac{1}{4}\hat{B}^{0}+\frac{1}{4}\overline{A}1)\overline{S}i$. Saboolite, $(\frac{1}{4}\hat{B}^{0}+\frac{1}{4}\overline{A}1)\overline{S}i$, Mellilite, $(\frac{1}{4}\hat{B}^{0}+\frac{1}{4}\overline{B})\overline{S}i$.

Dipyre may belong here. Taking 2i of Scapolite as the plane 1, (to which there is no objection), then O:1 in Zircon and the Scapolite Group will equal 1379-1399. Idoerase diverges more widely, giving for the corresponding angle 1339 3'.

5. EPIDOTE GROUP.-Monoclinic.

Epidote, $(\frac{1}{2}\hat{B}^{2}+\frac{1}{2}\hat{B})\hat{S}i$, Zoisite, $(\frac{1}{2}\hat{B}^{2}+\frac{1}{2}\hat{B})\hat{S}i$.

" $(\frac{1}{2}\hat{B}^{2}+\frac{1}{2}\hat{B})\hat{S}i$.

Gadolinite, $\hat{B}^{0}\hat{S}i$.

4. AXINITE GROUP.-Triclinic.

DASHERRA

(Ca. B. St.

(P. B. B. Axesers,

7. IOLITE GROUP.-Trimetic. Oxygen ratio for the bases and silica 1:14, as in some Mica, and perhaps not belonging to this section. Related to the Micas in the primmatic angle near 120°.

LOLETZ,

(iP+1261

CHRYSOLITE Peridot, H. Olivine, Chusite. Limbelite, Sensoure. Krisolith, W. Hyalosiderite. Betrachite, Breit. Glinkite, Romanouski. Monticellite, Brooks.

Trimetric. $I: I=94^{\circ} 3$; $0: 1i=128^{\circ} 27'$; a:b:c=1-2594:1: 1-0733.

 $0:1\overline{2}=125^{\circ}45'$. $0:1\overline{1}=130^{\circ}27'$.

 $O: 1i=130^{\circ}\ 27'.$ $i\frac{3}{2}: i\frac{3}{2}=(ov.ii)108^{\circ}\ 50'.$ $1: 1(mac.)=107^{\circ}\ 46'.$ $i\frac{3}{2}: i\frac{3}{2}(ov.ii)=123^{\circ}\ 34'.$ 0:1=120° 9'.

 $0: \frac{3}{4} = 114^{\circ} 49$. $1: 1(br.) = 101^{\circ} 32$. $ii: 1\frac{1}{2} = 137^{\circ} 22$. $0: \frac{1}{4}i = 149^{\circ} 36$. $ii: 1i = 130^{\circ} 2$.

			0				
						įι	
11	14	12	1			11	
				3 ž	_		
						21	
il		iŽ	I	13	iž	ñ	
Observed Planes.							



Cleavage: ii rather distinct. Massive and compact, or granular; usual in imbedded grains.

H.=6-7. G.=3.33-3.5; 3.441 of chrysolite, Haidinger; 3.33 —3:345, olivine; 3:3514, chrysolite. Lustre vitreous. Color green—commonly olive-green, sometimes brownish, black in some iron chrysolites; rarely white. Streak uncolored. Transparent translucent. Fracture conchoidal.

Chrysolite includes usually the transparent crystals of paler color, while olivise, (so called from the clive-green tint), is applied to imbedded masses or grains of inferior color and clearness.

Composition.—B'Si, in which R may be Mg, Fe, Mn, Ca, alone or in combination. Common chrysolite is usually (Mg, Fe)Si. Analyses: 1, 2, Walmstedt, (K. V. Ac. H. 1824, ii, 259, and Schw. J. xliv, 25); 3, 4, Stromeyer, (Gött, gelehrt. Anz. 1824, 206; Pogg. iv, 192); 5, Walchner, (Schw. J. xxxix, 65); 6, W. v. Beck, (Verh. Russ, Min. Ges. St. Petersb. 1847); 7, Rammelsberg, (Pogg. li, 446); 8, Walmstedt, (ib.); 9, Waltershausen, (Vulk. Gest. 117); 10, Deville, (Et. Geol. Canaries); 11, Demeyko, (Ann. des. M. [4], xiv, 187):

Extensive beds of steatite occur in various part of the New England States, also in New Jersey, Pennsylvania, &c. A bed at Smithfield, R. I., affords a delicate green columnar variety of tale, and a crystalline limestone in the same region, a white granular variety. At Bridgewater, Vt., handsome green tale occurs, intermingled with a transparent massive dolomite; also at Dexter, Me.; Lockwood, Newton, and Sparta, N. J.; near Amity, N. Y.; on Staten Island, both common and indurated, near the quarantine; and four miles distant it occurs in detached masses made up of folia, of a snow-white color, (Beck); at Cooptown, Md., of green, blue, and rose colors; in South Mountain, ten miles south of Carlisle, Penn.; in Texas, Nottingham, and Unionville, Penn.

Steatite occurs in Vermont at Athens or Grafton, Westfield, Marlboro, and Newfane; in New Hampshire at Francestown, Pelham, Orford, Keene, and Richmond; in Massachusetts at Middlefield, Windsor, Blanford, Andover, and Chester; at Pot-

ton, Canada East, with green talc and magnesite.

Slabs of steatite are extensively employed as fire stones in furnaces and stoves. It may be turned in a lathe, or formed into tubes by boring. When ground, it is used for diminishing friction. It is also employed in the manufacture of some kinds of porcelain. Venetian tale is used for removing oil stains from woollen cloth, etc.

Hampshirite is a name applied by Hermann, to the steatite of steatitic pseudomorphs described and analyzed by Dewey, (Am. J. Sci., iv, 274, v, 249, vi, 334, 1822, 1823), who obtained Si 50 60, Al 0 15, Mg 28 83, Fe 2 59, Mn 1 10, H 15:00. But the constituents of pseudomorphs are seldom pure species, and without thorough investigation afford no sufficient ground for instituting a new species. These have mostly the form of quartz.

MEERSCHAUM. Magnesite. Sepiolite, Glocker.

Compact, with a smooth feel, fine earthy texture.

H.=2-2.5; impressible by the nail. Color grayish-white, white, or with a faint yellowish or reddish tinge. Opaque.

Composition.—Mg Si+H?=Silica 60.9, magnesia 26.1, water 12.0. Analyses: 1, Lychnell, (K. V. Ac. H., 1826, 175); 2-6, Scheerer and Richter, (Pogg. lxxxiv, 321); 7, Damour, (Ann. Chem. Ph. [3], vii, 316):

	Si	Йg	Ĥ
1. Asia Minor,	60.87	27.80	11.29, Fe and Al 0.09=100.05, Lychnell.
2. Turkey,	61.17	28.43	9.83, Fe 0.06, C 0.67=100.16, Scheerer.
8. "	61.49	28.13	9.82, Fe 0.12, C 0.67, Ca 0.60=100.83, Richter.
4. Greece,	61.30	28.39	9.74, Fe 0.08, C 0.56=100.07, Scheerer.
5. ———— 1	58.20	27.73	9·64, Ça 1·53, Ç 2·73=99·83, Richter.
6. —— i	60.45	28.19	9.57, Fe 0.09, C 1.74, Xl 0.11=100.15, Scheerer.
7. Morocco,	5500	28.00	10.35, Fe 1.40, $\frac{1}{K}$ l 1.20, Ca 1.01, K 0.52, sand 1.50
			=98°98 Demour

19 to 20 per cent. of water were found by Berthier in Meerschaum from Madrid and Coulommiers, (Ann. des M. vii, 313); and by Kobell in that of Greece, (J. f. pr. Chem. xxviii, 482), as follows:

```
1. Spain,
          Si 53.8 Mg 23.8
                      2. Coulommiers, 54.0
                 24.0
                        20.0
                            1:4=99:4,
```

48.0 20.06 19.6 trace, Fe 12.40=100.06, Kobell. 3. Greece,

Döbereiner also found 2 atoms of water (instead of 1) in the meerschaum of Asia Minor. Klaproth (Beit. ii, 172) found in the same 5 per cent. of carbonic acid, which proceeded from intermixed carbonate of magnesia.

Yields water in a matrass, blackens, and gives a burnt smell. B.B. on charcoal burns white and fuses on the thinnest edges. Dissolves readily in borax to a transparent glass A like color with cobalt solution.

The word Mecracham is German for froth of the sea, in allusion to its apparent

lightness and whitish color.

6. AXINITE GROUP.—Triclinic.

(Ca3, B) Si, (B', H, B)Si. DANBURITE, AXDUTE.

7. IOLITE GROUP.—Trimetic. Oxygen ratio for the bases and silica 1:14, as in some Mica, and perhaps not belonging to this section. Related to the Micas in the prismatic angle near 120°.

(1R°+1H)Si2.


CHRYSOLITE. Peridot, H. Olivine, Chusite. Limbelite, Saussure. Krisolith, W. Hyalosiderite. Batrachite, Breit. Glinkite, Romanowski. Monticellite, Brooke.


Trimetric. $I: I=94^{\circ}3'; O: 1\bar{\imath}=128^{\circ}27'; a:b:c=1\cdot2594:1$: 1.0733.

 $O: 1\overline{2} = 125^{\circ} 45'$. $O: 1\widetilde{i} = 130^{\circ} 27'$. $\widetilde{i}\widetilde{j}: \widetilde{i}\widetilde{j} = (\text{ov}.\widetilde{i}i)108^{\circ} 50'$. $O: 1 = 120^{\circ} 9'$. $1: 1(\text{mac.}) = 107^{\circ} 46'$. $\widetilde{i}\widetilde{i}: \widetilde{i}\widetilde{j} = (\text{ov}.\widetilde{i}i)108^{\circ} 34'$.

 $i\bar{\imath}: 1\bar{\imath}=137^{\circ} 22'.$

 $O: \frac{3}{4} = 114^{\circ} 48'$. $1: 1(br.) = 101^{\circ} 32'$. $O: \frac{1}{4} = 149^{\circ} 36'$. $is: is(ov.ii) = 130^{\circ} 2'$.





Cleavage: it rather distinct. Massive and compact, or granular; usual in imbedded grains.

H.=6-7. G.=3.33-3.5; 3.441 of chrysolite, Haidinger; 3.33 —3:345, olivine; 3:3514, chrysolite. Lustre vitreous. Color green—commonly olive-green, sometimes brownish, black in some iron chrysolites; rarely white. Streak uncolored. Transparent translucent. Fracture conchoidal.

Chrysolite includes usually the transparent crystals of paler color, while elimin, (so called from the clive-green tint), is applied to imbedded masses or grains of inferior color and clearness.

Composition.—R^aSi, in which R may be Mg, Fe, Mn, Ca, alone or in combination. Common chrysolite is usually (Mg, Fe) Si. Analyses: 1, 2, Walmstedt, (K. V. Ac. H. 1824, ii, 359, and Schw. J. xliv, 25); 3, 4, Stromeyer, (Gött, gelehrt. Anz. 1824, 208; Pogg. iv, 193); 5, Walchner, (Schw. J. xxxix, 65); 6, W. v. Beck, (Verh. Russ, Min. Ges. St. Petersb. 1847); 7, Rammelsberg, (Pogg. li, 446); 8, Walmstedt, (ib.); 9, Waltershausen, (Vulk. Gest. 117); 10, Deville, (Et. Geol. Canaries); 11, Domeyko, (Ann. des. M. [4], xiv, 187):

```
Mg
                                                          X1
                                                                  Mn
                                    50.04
 1. Iserwiese,
                          41.54
                                                8.66
                                                        0.06 0.25=100.55, Walmstedt.
     Mt. Somma,
                           40.08
                                     44.22
                                              15.26
                                                        0.18
                                                                 0.48=100.24,
                                                        0.22M0.09, Ni 0.32=99.68, Stromeyer.
0.19 "0.20, "0.37=99.51, "
     Orient chrys.
                          39.73
                                    50.13
                                                9.19
     Vogelsberg,
                                                8.17
                          40.09
                                    50.49
                                                        0 19 " 0 20, " 0 37 = 99 51,

2 21 " 0 48, K 2 69, Cr. trace, Walchner.

— — = 100 72, Beck.

— Ča 35 45, H 1 27 = 99 19, Ramm.

trace 0 29, Ča trace=100 39, Walmst.

0 64 — Ni 0 20, H 1 04=100 22, Walm.
 5. Hyalosiderite,
                                              28:49
                          31.63
                                    32.40
     Glinkite,
                          39.21
                                    44.06
                                              17.45
     Batrachite,
                          87.69
                                    21.79
                                                2.99
 8. Pallas meteorite 40.83
                                     47.74
                                              11.53
    Etna,
                          41.01
                                    47.27
                                               10.06
                                                                 2.27 Ca 5.12=99.35, Deville.
10. C. Verdes, Fog. 40:19
                                    3570
                                              15.27
                                                        0.80
11. Antuco, Chili, 40-7
                                    39.7
                                              19.6
                                                                    -=100, Domeyko.
```

Berzelius detected oxyd of tin in the olivine of the Pallas meteorite, and Rummler a trace of arsenous acid. Other recent analyses: E. E. Schmid, (Pogg. lxxxiv, 51, Atacama); Erdmann (K. V. Ac. H. 1848, 15, Tunaberg).

No. 5, Hyalosiderite is (1Mg+1Fe)*Si, with an excess of Mg Si. It occurs at Kaiserstuhl in yellowish and reddish-brown crystals; H.=5.5. G.=2.875.

Tautolite, Breith. From volcanic rocks near Lake Laach, resembles hyalosiderite. H.=6.5: G.=3.865. Forms trimetric.

Forsterite, (Levy), from Vesuvius, is a white or colorless translucent chrysolite, occurring in small crystals, (Scacchi, Quad. Cryst. 63). Monticellite of Brooke, (Ann. Phil. 1831) is also Chrysolite. It is the peridot blane of Scacchi. Formula (†Ca*+ Mg Si, Seacchi.

Glinkite is greenish chrysolite from a talcose slate, in Perm, Russia, and occurring also in gneiss at Tunaberg with augite and garnet, (Analysis No. 6).

Batrachite, from Rinzoni, Tyrol, has the formula of Monticellite; G .= 3 033. Said to have two cleavages meeting at 115° and 65°, and a third diagonal to them.

With the fluxes gives the reaction of iron. Scarcely attacked by muriatic acid, but easily gelatinizes with sulphuric acid. Berzelius says that it also forms a jelly iron chrysolites are fusible before the blowpipe; hyalosiderite forms a black magnetic bead. Others are infusible.

Chrysolite is found near Constantinople, at Vesuvius, and the Isle of Bourbon in lavas; imbedded in obsidian, at Real del Montein Mexico; among sand at Expailly in Auvergne, in pale green transparent crystals. Olivine is of frequent occurrence in basalt and lavas. Crystals several inches in length, in greenstone at Unkel, on the Rhine; spheroidal masses at Kapfenstein in Lower Styria; and at Heela and Vesuvius, and various volcanie regions. Olivine is common in the lavas and basalt of the Sandwich and other Pacific Islands. It occurs in imbedded grains, and in masses sometimes several inches through in boulders of coarsely crystallized basalt in Thetford and in Norwich, Vermont.

Crystals of this species are commonly very fragile, and therefore unfit for an ornamental stone. The word chrysolite is derived from χρυσος, gold, and λιθος, stone, in allusion to its color; hyalosiderite is from ψαλος, glass, and σιδηρος, iron.

FAVALITE, (Iron-chrysolite, Eisenperidot).—Fayalite is a pure iron-chrysolite. Color black, greenish or brownish, sometimes iridescent. Cleavage in two directions at right angles with one another. H .= 6.5. G .= 4.11-4.14; 4.006, Delesse.

Composition .- Fe'Si=Silica 29.55, protoxyd of iron 70.45. Analyses: 1, Klaproth, (Beit. v, 222); 2, Thomson; 3, Delesse, (L'Institut, 1854, p. 52); 4, Gmelin:

Fe Mn X1 0.25=99.75, Klaproth. 1. Vole. glass, 29.50 66 00 4.0 2. Slavearrach, Ireland, 29:60 68.73 1.78 29.50 63.54 5:07

-=100 11, Thomson. - Mg 0 30=98 41, Delesse. - Cu 0 60, FeS 2 77, Gmelin. 4. Fayal, 65.84 2.94 1.84

Fuses readily to a black globule which is magnetic. Easily attacked by acids. From the Mourne Mts., Ireland, in Pegmatite; also from volcanic rocks at Fayal.

The Obsidians or volcanic glass often approach Fayalite in composition.

Iron-chrysolite has been observed in crystals, as a furnace product, near Goalar.

ALTERED FORMS.—Alteration of chrysolite, often takes place through the oxydation of the iron; the mineral becomes brownish or reddish-brown and iridescent. It also splits into thin lamins as the change goes on, sometimes so as to resemble a mica. A basalt thus changed was once pointed out to the author as a mica alate, although no further change had taken place than that here mentioned. Chusite and Limbelite are chrysolite more or less altered. The process may end in leaving the cavity of the crystal filled with limonite or red oxyd of iron. Under the action of carbonated waters, the iron is often carried off instead of being peroxydized, and also some of the magnesia is removed at the same time; and thus may come sorp tine, picrosmine, villarsite, which often retain the crystalline form of chrysolite. A further change may produce steatite and other magnesian species.

TEPHROITE, Breithaupt.

Dimetric? Massive, with cleavage parallel to the sides of a square or rectangular prism; also granular.

H.=5.5-6. G.=4-4.12. Color ash-gray. Streak pale-gray.

Darkens, on exposure, to brown and black.

Composition.—Mn Si=Silica 29 8, protoxyd of manganese 70 2. Analyses: 1, Thomson, (Min. i, 514); 2, Rammelsberg, (Pogg. lxii, 145):

Mn 66.60 1. Franklin, Bi 29·64 Fe 0.92, Moisture 2.70=99.86, Themson. Fe 2.92=100.46, Rammelsberg. 2. Sparta, 28.66 68.88

B.B. fuses easily to a black scoria. Gelatinizes perfectly in muriatic acid without evolving chlorine.

From Stirling, N. J., with franklinite, and at Sparta. This species has the general formula of a chrysolite.

A black silicate of manganese from Klapperud, Dalecarlia, having a submetallic lustre and yellowish-brown streak, afforded Klaproth, (Beit. iv, 137), Si 250, Mn 558, H 1800=988=Mn Si+8H, agreeing with the Tephroite, excepting the water. Klaproth obtained 60 per cent. of Mn Mn, whence the above is deduced by Berze-

KNEBELITE.

Massive, with an uneven and cellular surface, and quite hard. G.=3.714. Lustre glistening. Color gray, spotted dirty-white. red, brown, and green. Opaque. Brittle. Fracture subconchoidal.

Composition.—(Fe Mn)² Si, Fe and Mn being in equal proportions. Analysis by Döbereiner, (Schw. J xxi, 49); Silica 32.5, protoxyd of iron 32, protoxyd of manganese 35, and thus appearing to be a ferruginous tephroite. With muriatic acid decomposed, the silica separating. Unaltered alone before the blowpipe. Fusee with however to a dark clina graces with borax to a dark olive-green pearl.

Locality unknown. Named by Döbereiner after Major von Knebel.

CHONDRODITE, d'Ohsson. Condrodite, H. Maclurite, Seybert. Brucite. Cleaveland. Humite, Bournon.

Trimetric; often hemihedral in octahedral planes, producing forms monoclinic in character. $I: I=94^{\circ} 26'$. Crystals of three types.*

^{*} Seacchi in Pogg. Ann. 1851, Ergänz ii, 161. The author adopts a modified view of these types and their axes. (See Am. J. Sci., [2], xiv, 175).

The numbers given for the planes of these figures on page 59, vol. I, are based

on a similar fundamental form, except that the longer lateral axis has twice the length here adopted.

APHRODITE. Berlin, K. V. Ac. H. 1840.

Soft and earthy like Meerschaum. G .= 2.21.

Composition.—Mg*Si²+2‡H. Berlin obtained Silica 51.55, magnesia 33.72, protoxyd of manganese 1.62, protoxyd of iron 0.59, alumina 0.20, water 12.32. From Longbanshytta, Sweden. The name is from αφρος, foam.

Delesse has analyzed another species, containing Silica 53.5, magnesia 28.6, alumina with trace of peroxyd of iron 0.9, water 16.4—nearly Mg 512+3 H. Occurs in serpentine, of a white or yellowish color, with a waxy lustre and somewhat translucent. G.=2.335.


QUINCITE.—The Quincite of Berthier is in light carmine red particles disseminated through a limestone deposit.

Composition.—Silica 54, magnesia 19, protoxyd of iron 8, water 17=98. From near the village of Quincey, France. Strong concentrated acids dissolve the magnesia and iron, and leave the silica in a gelatinous state.

PICROSMINE. Pikrosmin, Haidinger.

Trimetric. $I: I=126^{\circ} 52'$, $ii: I=153^{\circ} 26'$, $ii: 1i=121^{\circ} 6'$, 1i: 1i (over ii)=62° 11', adjacent 117° 49'. Cleavage: ii perfect; ii less so; traces parallel with 1i. Also fine columnar and granular.

H.=2.5—3. G.=2.596—2.68. Lustre of cleavage face pearly, elsewhere vitreous. Color greenish-white: also dark green, gray. Streak white. Subtranslucent—opaque. Odor bitter argillaceous when moistened.



Composition.—Mg³Si²+1¹H=Silica 55², magnesia 36⁶, water 8². Analysis by Magnus, (Pogg. vi, 53):

Si 54.886, Mg 34.348, Al 0.793, Fe 1.399, Mn 0.420, H 7.301=98.147.

Some ammonia was given off with the water. Yields water in a matrass, blackens, and has a burnt smell. B.B. on charcoal whitens without fusing. With borax slowly dissolves to a transparent glass; affords a glass with little soda, and an infusible slag if the soda be increased. A pale and indistinct red with cobalt solution.

Associated with magnetic iron ore near Presnitz in Bohemia. The fibrous variety resembles asbestus. The name is from πικρος, bitter, and οσμη, odor.

ANTIGORITE, Schweizer, Pogg. Ann. xlix, 595.

Trimetric. In foliated masses, laminæ easily separating.

H.=2.5. G.=2.622. Brownish-green in reflected light and leek-green in transmitted, with uncolored streak. Transparent in thin laminæ. Feel smooth, but not greasy.

Composition.—R'Si'+MgH, Sehw. Analyses by Schweizer, (loc. cit.):

	Si	Mg	Fe	X 1	Ĥ
1.	46.22	34.39	13.05	2.08	3 70=99 44.
2	46.18	85'19	12:68	1.89	8-70=99-64
			36		

Compound crystals parallel to 45 in the third type, and 25 in the second, the former sometimes producing stellate forms of six crystals, each hemihedral. Cleavage indistinct. Usually in imbedded grains or masses of a somewhat granular texture; sometimes in

small implanted crystals.

II.=6-6.5. G.=3.118, from New Jersey, Thomson; 3.199, Finland, Haidinger; 3.234, white crystal, Type I; 3.199, brown of Type III; 3.186, yellowish, Type III; 3.177, yellow of Type II; Scacchi. Lustre vitreous—resinous. Color white, yellow, pale yellow or brown; sometimes red, apple-green, black, gray. Streak white, or slightly yellowish or grayish. Transparent—subtranslucent. Fracture subconchoidal—uneven.

Composition.—Mg⁴ Si, with part of the oxygen replaced by fluorine, or 1 Mg⁴ Si, with 1¹/₂ 4(Mg F, Si F⁵) in chondrodite, 1/8 in Type II for humite, 1/2 in Type II, 1/8 in Type III, Rammelsberg. Analyses: 1, Seybert, (Am. J. Sci., v, 836); 2, 3, 4, Rammelsberg, (Pogg. liii, 180, and 1st Supp. 38); 5, W. Fisher, (Am. J. Sci., [2], ix, 85); 6, 7, 8, Rammelsberg, (Pogg. lxxxvi, 413):

```
Йg
 New Jersey, "yellow,
                   82.66
                          54.00
                                          2.88
                                                         HF 4-09, H 1-0, K 2-11, S.
                                                  7·60= 9977, Ramm.
                   88-06
                           55.46
                                   8.65
                   88.10
                                                  8 69=100 75, Ramm.
  Pargas, yellow,
                           56.61
                                   2.85
                   88.19
          gray,
                           54·50
                                   675
                                                  9-69=104-18, Ramm.
5. New Jersey, red, 88.85
                           58 05
                                   5.20
                                                  7.60= 99.50, W. Fisher.
                  84.80
                           80.09
                                   2.40
                                                  8.47=100.75, Ramm.
  Humite, type 1,
                  88-26
                          57.92
                                   2.30 Ca 0.74
                                                  5-04 Al 1-06=100-82, Ramm.
          type 2,
     "
          type 3,
                 86-67
                          56.88
                                  1.67
                                                  2.61= 97.78, Ramm.
```

B.B. on charcoal infusible, but becomes paler in varieties containing little iron, sometimes showing traces of fusion on the edges. With borax dissolves slowly but perfectly to a transparent glass slightly tinged by iron; if the glass is saturated it becomes cloudy by flaming. With salt of phosphorus in the open tube, affords fluorine.

Chondrodite occurs mostly in granular limestone. It is found near Abö, in the parish of Pargas in Finland, and at Aker and Gulsjö in Sweden; at Taberg in Wermland; in Saxony; on Loch Ness in Scotland; at Achmatowsk in the Ural, along with perofskite, and in the mines of Schischimsk with red apatite. The humite occurs at Somma, in ejected masses of a kind of granite rock, along with

white olivine, mica, and magnetite.

Abundant in the counties of Sussex, N. J., and Orange, N. Y., where it is associated with spinel, and occasionally with pyroxene and corundum. At Bryam, orange and straw-colored chondrodite, and also a variety nearly black, occurs with spinel; at Sparta, a fine locality of honey-yellow chondrodite; a mile to the north of Sparta is the best locality of this mineral in New Jersey. It also occurs at Vernon, Lockwood, and Franklin. Chondrodite is abundant in Warwick, Monroe, Cornwall, near Greenwood Furnace, and at Two Ponds, and elsewhere in Orange Co., N. Y. Fine specimens may be obtained on the land of Mr. Houston, near Edenville. It is obtained also at Chelmsford, Mass., along with scapolite; in Harry's quarry near Chaddsford, Ps., of yellow and orange colors and abundant. It occurs sparingly on the bank of Laidlaw lake in Rossie, N. Y.

Abundant in limestone at S. Crosby, Canada West, St. Jerome, St. Adèle, Gren-

ville, etc.

The name chondrodite is from Xordoss, a grain, alluding to its granular structure.

ALTERED FORMS.—Chondrodite altered to Serpentine, has been observed at Sparta,

N. J., with spinel and mica.

Metaxite, (in part). Chrysotile is fine asbestiform, of olive oil, yellowish or brownish color, and metallic or silky lustre. G.=2-219. It is the so-called asbestus or amianthus occurring in serpentine. Metaxite of Delesse does not differ in composition from Chrysotile.

Marmolite.—A thin foliated variety; folia brittle, separable. G.=241. Of a pale green color, sometimes nearly white. A lamellar variety in which the laminæ are not separable, is sometimes misnamed Kerolite.

Retinalite has a resinous appearance, honey yellow to oil green color, and is translucent. H.=3.5. G.=2.47-2.53. Bowenite resembles nephrite and has a hardness of 5.

Composition.—Mg°Si*+1;MgH°=Mg°Si*H°=Silica 43·64, magnesia 43·35, water 13·01. Analyses: 1, Hartwall, (Jahresb. ix, 204); 2, Hisinger, (Afhand. iv, 341); 3, Mosander, (K. V. Ac. H. 1825, 227); 4, 5, 6, Lychnell, (ib. 1826, 175); 7, Scheerer, (Pogg. Ann. lxviii, 328); 8, 9, Jordan and Marchand, (J. f. pr. Chem. xxxii, 499); 10, Hermann, (ib. xlvi, 227); 11, Ivanoff, (Ann. Mines Russ. for 1841, 333); 12, Garrett, (this Min. 3d edit., 692); 13, Lychnell, (loc. cit.); 14, Shepard, (Min. p. 292); 15, Vanuxem, (J. Ac. Sci. Phil. iii); 16, Beck, (Min. N. Y., 280); 17, Hermann, (J. f. pr. Ch. xlvi, 230); 18, Stromeyer, (Unters. 365); 19, Schaffgotsch, (Rose, Reise n. d. Ural, i, 245); 20, Rammelsberg, (3d Suppl. 107); 21, Kobell, (J. f. pr. Chem. ii, 297); 22, Thomson, (Phil. Mag. xxii, 193); 23, Delesse, (Thése An. 24); 24, Kühn, (Ann. Ch. u. Pharm. lix, 369); 25, G. J. Brush, (communicated to the author); 26–28, Hunt, (Logan's Rep. 1851, 41, and Am. J. Sci. [2], xii, 213); 29–31, Smith and Brush, (ibid. xv, 213); 32, Kersten, (J. f. pr. Ch. xxxvii, 167): (ibid., xv, 213); 32, Kersten, (J. f. pr. Ch. xxxvii, 167):

I. Massive Serpentine.

		Si	Mg	Ėе	Ĥ	X 1
1.	Snarum, crystallized,	42.97		-	12-02	0.87, Fe 2.48=100, Hartwall.
2	Fahlun,	43.07	40.37			0.25, Ca 0.50=97.81, Hisinger.
3.	Wermland,	42.84	44.20			-, 0.0.89=99.97, Mosander.
4.	Fahlun,	41.95	40.64	2.22	11.68	0.87, C and bitumen 3.42, L.
	Sjögrube,	41.58	42.41	2.17	11.29	trace," " 2.38=99.33, L.
	Massachusetts,	43.20	40.09			—=99.95, Lychnell.
	Snarum,	40.71	41.48			2·39=99·62, Scheerer.
8.	Fahlun, G.=2.53,	40.32	41-76			-=98.95, Jordan.
9.	ALCOHOLD CO.	40.52	42.05	3.01	13.85	0.21, Coaly subst. 0.3=99.94, M.
10.	L. Auschkal, crystals,	40.21	35.09	9.13	13.75	1.82=100, Hermann, G.=2.57.

II. Foliated varieties-including Marmolite.

11. Urals, G.=2.55,	40.80 40.50	2.2 12.02 3.02, Ča0.42, Mn0.2=99.16, L.					
I2. Hoboken,	42.32 42.28	1.28 13.80 0.66=100.29, Garrett.					
13. "	41.67 41.25	— 13.80 —-, Fe 1.64, C*1.37=99.73.					
14. Blandford,	40.00 41.40	2.70 15.67 —, Ca 0.93=100.70, Shep.					
15. Bare Hills, Md.,	42.69 40.00	1.16 16.11, Co.87=99.96, Vanuxem.					
16. Westchester Co., N. Y.,		— 21.00 —=99.50, Beck.					
17. Finland,	40.00 42.40	1.80 15.80 —=100, Hermann.					
The state of the s							

* With bitumen.

III. Fibrous varieties, (including Chrysotile, Metaxite in part, Baltimorite.)

```
18. Wermland, Picrolite, 41.66 37.16 4.05 14.72 - Mn 2.25=99.84, Strom.
19. Gornoschit,
20. Texas, Pa. G.=2:557,
                               43 73 37 72 6 11 11 63 0 81=100, Schaffgotsch.
                               43 79 41 03 2 05 12 47 -= 99 34, Rammelsberg.
21. Reichenstein, Chrysotile, 43:50 40:00 2:08 13:80 0:40=99:78, Kobell, 22. Bare Hills, Baltimorite, 40:95 34:74 10:05 12:60 1:50=99:80, Thomson.
23. Reichenstein, Metaxite, 42·1 41·9
24. " 44·48 40·60
                                               3.0 13.06 0.4=100, Delesse.
                                                2.34 12.35 -= 99.77, Kühn.
25. N. Haven, Ct., Chrysotile, 44.05 39.24 2.53 13.49 -=99.31, Brush. G.=2.49
```

IV. Retinalite-Williamsite-Bowenite.

		Si	Mg	Fe	Ĥ	X 1
26.	Retinalite, Grenville,	39.34	43.02	Fe1-80	15.09	-=99.25, Hunt. G.=2.494
27.		40.10	41.65	" 1-90	15.00	-=99.55, "
28.	" G. Calumet, I.					-==100.92, " G.=2.870.
29.	Williamsite,	41.60	41.11	3.24	1270	trace, Ni 0.50=99.15, S. & B.
30.		42.60	41.90		12.70	" " 0.40=99.22, S. & B.
31.	Bowenite,	42.29	42.29	1.21	12.96	" Cal-90=99.65", S. & B.
32.	Pseud. after Garnet,	41.50	40.34	4.10	12.87,	Mn 0.5, Na 0.42. Ca, Bit., tr.
						=99-78. Kersten.

. Mean of three analyses.

A Serpentine from Vermont afforded Dr. Jackson, (Am. J. Sci. xxxviii, 198). Si 45:80, Mg 33:41, H 7:70, Magnetic iron 2:00, Oxyd of Chromium 2:00. Lychnell detected 2:24 per cent. of protoxyd of cerium in one serpentine.

The Meerschaum of Taberg and Sala, Sweden, is a soft earthy serpentine.

The Marmolite, according to Hermann, differs in containing more water as well as in its foliated structure, and gives the formula Mg*Si*+2MgH*=Mg*Si*H*.

Delesse found for Chrysotile from the Vosges the composition of serpentine, (Ann. d. M. [4], xviii, 309). The pseudomorphs, anal. 32, were from Schwarzenburg, in

As serpentine is mostly a rock, the analyses must be expected to disagree, and every portion of alumina or water present, cannot in all cases be assumed to be an essential constituent.

Serpentine yields water in a matrass. B.B. on charcoal, fuses on the edges with difficulty. Dissolves readily in borax; with effervescence in salt of phosphorus. Gives usually an iron reaction. Soluble in muriatic and sulphuric acids.

Serpentine often constitutes mountain masses. Mixed with carbonate of lime, it forms verd antique marble, which occurs often in extensive beds. Chromie iron is often disseminated through it, giving it a mottled appearance, somewhat similar to the skin of a snake, whence the name serpentine or ophite. It is very commonly result of pseudomorphic (or metamorphic) changes. Hornblende, augite, chryslite, garnet, spinel, mica, and many other minerals, have thus been altered. Delesse says, that the Serpentine of Odern sometimes so graduates into feldspar to appear to have been formed at the expense of that mineral. Rose has found that some of the supposed crystals of serpentine are actually part chrysolite, the change not having been complete.

Crystals of serpentine occur in the Fassa valley, Tyrol; near Miask at Lake Auschkal, Barsovka, Katharinenberg, and elsewhere; in Norway at Snarum, (crystals). Fine precious serpentines come from Fahlun and Gulsjo in Sweden, the Isle of Man, the neighborhood of Portsoy in Aberdeenshire, Corsica, Siberia, and Sazony; in crystals at Lake Auschkal, in Miask, Borsovka, etc. Common serpen-

ony; in crystals at Lake Auschkal, in Miask, Borsovka, etc. Common serpentine occurs at Lizard's Point in Cornwall, and many other places.

In the United States, precious serpentine of a light-green color occurs at Phillipstown, in the Highlands, N. Y.; also at Port Henry, Essex Co.; at Antwerp, Jefferson Co., in crystals; at Syracuse, east of Major Burnet's, interesting varieties; in Gouverneur, St. Lawrence Co., in crystals, and also in Rossie, two miles north of Somerville; at Johnsburg in Warren Co.; Davenport's Neck, Westchester Co., affording fine cabinet specimens; in Cornwall, Monroe, and Warwick, Orange Co., sometimes in large crystals at Warwick; and from Richmond to New Brighton, Richmond County. In Massachusetts, fine at Newburyport; at Blanford with Schiller spar, and the marmolite variety; also at Westfield, Middlefield, Lynnfield, Newburyport, and elsewhere. In Maine, at Deer Isle. In Vermont, at New Fane, &c. In Rhode Island, at Newport. In Connecticut, near New Haven, at the verd antique quarries. In New Jersey, at Hoboken, with brucite, magnesite, &c., and the marmolite variety; also at Frankfort and Bryan; at Montville, Morris Co., silky fibrous, (chrysotile), and similar at New Haven, Ct. In Maryland, at Coopsilky fibrous, (chrysotile), and similar at New Haven, Ct. In Maryland, at Cooptown, Harford Co., with diallage; also in the north part of Cecil Co. In Penn sylvania, massive, fibrous and foliated, of various colors, purple, brown, green, and gray, at Texas, Lancaster Co.; also at Nottingham and West Goshen, Chester Co. and Mineral Hill, Delaware Co. Westchester, Chester Co., Pa., affords the serpen-

IV. Consisting of alumina and manganese-alumina-manganese garnet-or manganesian garnet.

V. Consisting of silicates of iron and lime-iron-lime garnet-including allo-

chroite, aplome, melanite and common garnet in part.

VI. Containing lime and chromic oxyd-lime-chrome garnet.

But these compounds pass into one another by imperceptible shades, as the following analyses show.

Composition.—R³ Si+# Si=(½R³+½H) Si. Analyses: 1, Arfvedson, (K. V. Ac. H. 1822, 87); 2, C. Gmelin, (Jahresb. v, 224); 3, 4, Klaproth, (Beit. iv, 319, v, 138); 5, T. Wachtmeister, (K. V. Ac. H. 1823); 6, 7, Karsten, (Karst. Arch. f. Min. iv, 388); 8, T. Wachtmeister, (loc. cit.); 9, Nordenskiöld, (Schw. J. xxxi, 380); 10, Croft, (G. Rose, Reise n. d. Ural, 132).

11, T. Wachtmeister, (loc. cit.); 12, Hisinger, (Schw. xxi, 258); 13, 14, Kobell, (ib. lxiv, 283); 15-17, Karsten, (loc. cit.); 17-20, T. Watchmeister, (loc. cit.); 21, Klaproth, (Beit. ii, 22, v, 131); 22, W. Watchtmeister, (Jahresb. xxv, 364); 23, Bahr, (Jahresb. xxv, 364); 24, A. Besnard, (Lieb. u. Kopp Jahresb. 1849, 745); 25, 26, Mallet, (J. Dubl. Geol. Soc. and Rammelsberg's 5th Supp. 125.)

27, H. Seybert, (Am. J. Sci. vi, 155, 1823); 28, Rammelsberg, (J. f. pr. Chem. lv. 487); 29, d'Ohsson, (Schw. J. xxx, 346); 30, Hisinger, (Jahresb. ii, 101); 31, Seybert, (Am. J. Sci. v, 118, where iron is made protoxyd); 32, Karsten, (loc. cit.); 33, 34, Bredberg, (K. V. Ac. H. 1822, i, 63); 35, Bucholz, (Scheerer's N. J. iv, 172); 36—41, Watchtmeister, (loc. cit.); 42, Thomson, (Ann. Lyc. N. York, 1829, iii, 9); 43, Vauquelin, (Jour. de Phys. Ann. viii, L. 94); 44, Klaproth, (Beit. v, 168, where the iron is made protoxyd); 45, Karsten, (loc. cit.); 46, Ebelmen, (Ann. des Mines, [4], vii, 19); 47, W. Fisher, (Am. J. Sci. [2], ix, 84); 48, Bahr (J. f. pr. Chem. liii, 312); 49, Weber, (Ramm. 5th Suppl., 193); 50, Baumann, (ib.); 51, Komonen, (Verh. min. Ges. St. Petersb. xxiii, 291); 52, Erdmann, (Jahresb. xxiii, 291);

I. Lime-Garnet.—Grossular.—Ca*Si+\(\frac{1}{4}\)\(\frac{1}{5}\)i=\(\frac{1}{4}\)\(\frac{1}{6}\)i=\(\frac{1}{4}\)\(\frac{1}{6}\)i=\(\frac{1}{4}\)\(\frac{1}{6}\)i=\(\frac{1}{4}\)i=\(\frac{1}{6}\)i=\(\frac{1}{4}\)i=\(\frac{1}{6}\) manzovite, topazolite, and succinite are names of varieties. Grossular or wiluite has a greenish color; G.=371. Succinite has an amber color, to which the name alludes. Topazolite has a topaz color. Romanzovite is brownish. Cinnamon stone or essonite (Kaneelstein, Germ.) has a clear cinnamon brown shade; G .= 3.5-3.6.

		Si	X1	Fe	Fe	Mn	Mg	Ča
1.	Malsjö, Cin.	41.87	20.57	3.93	_	0.	39	33.94=100.70, Arfved.
2.	Ceylon, "	40.01	23.00	3.67	-	-	-	30.57, K0.59, ign. 0.33, G.
3.	u u	38.80	21.20	6.20	-	-	-	31.25=97.75, Klaproth.
4.	Wilni, Gross.	44.00	8.20	12.00	-	trace		33.50=98, Klaproth.
5.	11 11	40.55	20.10	5.00		0.48	-	34.86=100.99, Wacht.
6.	"	38-25	19.35	7.33	-	0.50	2.40	31.75=99.58, Karsten.
	St. Gothard, Cin.		1970	5.95	-	0.12	4.15	31:35=99·12, Karsten.
8.	Tellemark, wh.	39.60	21.20	-	2.00	3.12	-	32·30=98·25, Wacht.
	Romanzovite,	41.21	24.08	7.02	-	0.	92	24 76, ign. & loss 1 98, N.
10.	Urals, white,	36.86	24.19	-	-	-	-	37·15=98·10, Croft.

II. Magnesia-Garnet.—(Mg, Fe)*Si+Xl Si=(\frac{1}{2}(Mg, Fe)*+\frac{1}{2}Xl)Si. Color deep coalblack. G.=3:157. Lustre somewhat resinous. B.B. easily fusible, intumescing and forming a dark grayish-green globule, which is not magnetic.

42.45 22.47 - 9.29 6.27 13.43 6.58=100.44, Wacht. 11. Arendal,

III. Iron-Garnet, or Almandine. Fe Si+XISi=(4Fe + 1XI)Si=Silica 36.3, alumina 20.5, protoxyd of iron 43.2.—Common Garnet, Precious Garnet.—Dark red, brownish-red to black. Allochroite is fine grained massive, of a dark dingy color. Precious garnet is deep red and translucent or transparent. Common garnet is dingy red. G. of these varieties 3.7—4.21. B.B. fuse rather easily with an iron reaction.

2, Brush, (communicated to the author); 3, Thomson, (Phil. Mag. 1843, 191); 4, Oellacher, (Zeits. geol. Ges., iii, 222); 5, Kobell, (Münch. gel. Anz., 1851, xxxiii, 1):

	Si	Mg	Ĉa.	Ĥ	₩1	Fe
1. Middlefield,	40.	40	-			-==100, Shepard.
2. Texas, Pa.,	48.15	35.95				=99·35, Brush.
3. Bare Hills, Md.,	40.16	36.00				1.16 =99.72, Thomson.
4. Tyrol,	40.40					0.38, Apatite 0.78=100, 0.
5. "	41.50	38.30	-	20.20	-	100 30, Kobell.

B.B. decrepitates, becomes opaque, and fuses with great difficulty on the edges; in powder with borax, a colorless transparent glass.

Occurs with serpentine at the localities above-mentioned. Named after Prof. Chester Dewey. The gymnite of Thomson named from yours, naked, in allusion to the locality at Bare Hills, Md., is the same species.

Thomson found in another mineral from the United States labelled Deweylite (6. =2.0964), Si 50.70, Mg 23.65, H 20.60, Al 3.55, Fe 1.70, (Am. J. Sci. xxxi, 173); and in another allied mineral, Si 41.42, Mg 23.53, Na 6.25, H 19.86, Al 4.47, Se 357, Fe tr.

HYDROPHITE, Svanberg, K. V. Ac. H. 1839, Pogg. li, 535. Jenkinsite, Sheperi Am. J. Sei. [2], xiii, 392. Eisengymnite.

Massive; sometimes fibrous.

H.=3.5. G=2.4—2.65. Lustre feeble, subvitreous. Color mountain-green to blackish-green. Streak paler. Translucent to opaque.

Composition.—R² Si+3H or (Mg, Fe)Si+Mg H²! Analyses: 1, L. Svanberg (loc. cit.); 2, 3, Smith and Brush, (Am. J. Sei. [2], xvi, 369):

Si Fe Mn Mg H1 V H

1. Hydrophite, of Taberg, 36·193 22·729 1·660 21·082 2·895 0·115 16·080=100.754,

Svanberg.

2. Jenkinsite, 38·97 19·30 4·36 22·87 0·53 H13·36=99·39, S. and B.

3. "37·42 20·60 4·05 22·75 0·98 "13·48=99·28, S. and B.

Smith and Brush find the oxygen ratio for the protoxyds, silica and water 3: 4: 21, and they mention the nearness to both Hydrophite and Serpentine.

B.B. blackens and becomes magnetic, and finally fuses to a black globule.

Hydrophite occurs at Taberg in Smaoland; also (Jenkinsite) at O'Neil's mine in Orange Co., N. Y., as a fibrous incrustation on magnetite. The name is from week, mater.

Nickel-Gymnite, Genth, (Keller and Tied. Nordamer. Monatsb., iii, 487). An amorphous reniform or stalactitic mineral from Texas, Lancaster Co., Pa. H.=3-4. G.=2.409. Lustre resinous. Color pale apple green, or yellowish. Streak greenish white. Opaque to translucent. Heated in a tube, yields water and blackens. BB the reaction of oxyd of nickel and silica. Soluble in muriatic acid, silica separating but not gelatinizing. Composition: Ši 35-36, Ni 30-64, Fe 0-24, Mg 14-60, Ca 0-26, H=19-09, corresponding to (Ni, Mg)² Si+3H. In other trials, 24-78 and 36-41 per cent. of oxyd of nickel were obtained.

G. Rose writes the formula (Mn, Fe)2 Si2+Be Si+Mn S, Mn O. If in this formula G. Rose writes the formula (Mn, Fe) Si²+Be Si+Mn S, Mn O. If in this formula Mn S be considered as replacing a portion of protoxyd, the oxygen ratio for the bases and silica is 8:9. The analyses correspond as well to the ratio 9:3=1:1, which is the garnet ratio; the formula may then be (\$\frac{1}{3}\cdot \frac{1}{3}\cdot \fra

Occurs in gneiss at Schwarzenberg in Saxony, associated with garnet, quartz, fluor, and cale spar; at Breitenbrunn, Saxony; also at Hortekulle, near Modum, in Norway. It was named by Werner in allusion to its yellow color, from ἡλιος, the sun.


ZIRCON, W. Hyacinth, Jargon. Zirconite. Silicate of Zirconia. Erdmannite. Ostranite, Breithaupt. Calyptolite, Shepard.

Dimetric. $0:1i=147^{\circ}21'; a=0.6407$. Observed planes as in f. 387, with also planes 2 and 3.

 $I: 1=132^{\circ}\ 10'$. $ii: 1=118^{\circ}\ 20'$. $ii: 44=155^{\circ}\ 8'$. $I: 2=151^{\circ}\ 6'$. $ii: 1i=122^{\circ}\ 39'$. $1i: 1i\ (pyr.)=135^{\circ}\ 11'$.

I: 3=159° 48'. ii: 33=148° 17'. 1:1 (pyr.)=123° 19'.

Cleavage: I imperfect; 1, less distinct. Also in irregular forms and grains.



H. = 7.5. G.=4.0-4.75; 4.505, Haidinger; 4.072 and 4.222, Stockholm, Svanberg; 4.599 and 4.610, Ilmen, ib.; 4.453, ib.; 4.681, Thomson, Svanberg; 4.721, Lowry; 4.03 from Lustre more or less perfectly adamantine. Color red, Tellow, gray, white. Streak uncolored. Transparent-Fracture conchoidal, and brilliant.

ZrSi=Silica 83.2, zirconia 66.8=100, the zirconia, being partly rin according to Svanberg. Analyses; 1, Berzelius, (K. V. Ac. H. 1824); (J. Acad. Sci. Philad. iii, 59); 3, W. Gibbs, (Pogg. lxxi, 559); 4, Henpr. Chem. xxxviii, 508); 5, T. S. Hunt, (Am. J. Sci. [2], xii, 214); 6, l, (Trans. Amer. Phil. Soc. x, 346, and Am. J. Sci. xv, 448);

Composition .- #2Si2+3H, from Siegert's analysis. Analyses: 1, Rammelsberg, (Pogg. xliii, 127); 2, Siegert, (Ramm. 5th Suppl., 230);

Ši	Fe	X 1	Mg	Ča	K	Ĥ
46.17	35.82	5.88	2.67	-	0.75	8.72=100, Ramm.
42.07 H	e 41.98	4.92	0.94	1.67	-	8.47=100.05, Siegert.

In a matrass yields water. B.B. fuses with some difficulty to a black shining globule; with the fluxes gives an iron reaction. Dissolves imperfectly in the acids Occurs at Obergrund, with calc spar and quartz, sometimes intermixed with pyrites and magnetic iron ore. Probably mixed with chlorite, according to Rammelsberg. Named from στιλπνος, shining, and μελας, black.

This species requires more investigation, and the same is true of the following.

EPICHLORITE. The Epichlorite of Rammelsberg, (Pogg. Ann. lxxvii, 437, 1849), is a fibrous or columnar mineral from Radauthal, between schiller spar and chlorite. H.=2-25. G.=276. Color dull leek-green. Streak white to greenish. Lustre greasy. In thin columns translucent and of a bottle green color.

Composition.—3R°Si+R°Si²+9H, Rammelsberg. Analysis; Si 40°88, Al 10°96, Fe 8°72, Fe 8°96, Mg 20°00, Ca 0°68, H 10°18=100°38. B.B. fuses only in thin fibres with difficulty. With the fluxes reaction of silica and iron.

GLAUCONITE.—The Green Grains of the green sand formation of Gay Head, contsin, according to Dr. S. L. Dana, (Hitchcock's Geol. of Mass., p. 93); of New Jersey, according to H. D. Rogers, (Geol. Rep. New Jersey, pp. 204 and 207); and W. Fisher, (Am. Jour. Sci., [2], ix, 83); of Germany, according to Berthier:

	Si	X 1	Fe	Mg	On	Ř	Na	Ĥ
1. Gay Head, Mass.	5670	13.32	20-10	1.18	1.62	1	-	
2. Cauley's Pits, Woodstown, N. J.,	48.45	6.30	24.31	-	trace	12.01	-	8·4099·47, B
3. Sculltown, N. J.,	51.50	6.40	24:30	trace	-	9.96	-	770=9986,B.
4. Poke Hill, Burlingt. Co., N.J.	50.75	6.50	22.14	-	-	12.96	_	7·50=99·85, R.
5. S. E. of Phil. in N. J.,	53.26	3.85	24.15	1.10	1.73	5.36	1.60	10-12=101-12,
6. Germany,	46.1	5.5	19-6	8.8	0.2	5.3	-	Fisher. 8-9, quartz, 11-5, Berth.

Van der Marck found in the Green Sand of Büderich near Werl in Westphalis, 25-9 per cent. soluble in muriatic acid (a), 33-1 insoluble ib. (b), and 41-0 of quarta Analysis afforded him, (Rammelsberg, 5th Suppl. 126),

a. Ca Č 19.7, MgČ 0.4, Ca° P 2.6, Fe 0.9, Ål 1-6, F trace=25.2. b. Si 19.3, Ål 3.3, Fe 6.2, Mg 1.1, K 1.1, Ĥ 2.1=33.1.

When first dug the grains are very soft, and the mass is sometimes adhesive, but on exposure they nearly equal gypsum in hardness.

Kirwanite. Fibrous; fibres diverging from a centre. H .= 2. G .= 2.941. Color

dark olive-green. Opaque.

Composition.—According to R. D. Thomson, Silica 40.5, protoxyd of iron 23.91, lime 19.78, alumina 11.41, water 4.35=99.95, whence Rammelsberg deduces the formula of 3R. Si+Al Si+2H. Blackens before the blowpipe and partially fuse. With soda or borax forms a dark brown glass. Occurs in basalt on the northest coast of Ireland. (Thomson, Min. i, 379).

MELANOLITE of Wurtz, (this Min. 3d edit., p. 679), has a chlorite like aspect. It is black and opaque with a striated surface and somewhat columnar structure; streat dark clive green. H.=2. G.=2.69.

H. Wurtz obtained Si 30.86, Al 3.92, Fe 20.25, Fe 21.97, Na 1.62, H 8.94, CaC

1277=100.33. It affords the oxygen ratio for the protoxyds, peroxyds, silica and water, 2:3:6:3; but it is probably not of constant composition. Rammelsberg observes that it is near Hisingerite.

From Milk Row Quarry, near Charlestown, Massachusetts, incrusting the sides of

a fissure.

III. CHLORITE SECTION.

1. General Formula—(R³, ₹)Si+Aq.

```
      R H Si H
      1:2:3:3
      \hat{F}e^3Si+2\hat{F}eSi+9\hat{H}
      =(\frac{1}{2}\hat{F}e^3+\frac{1}{2}\hat{F}e)Si+3\hat{H}

      THURINGITE,
      2:3:3:2
      \hat{F}e^3Si+Bi(Si,Al)+3\hat{H}
      =(\hat{F}e^3,Al)(\bar{S}i,Al)+1\frac{1}{2}\hat{H}

      EUPHYLLITE,
      1:8:9:2
      \hat{R}^3Si+8\hat{H}Si+6\hat{H}
      =(\frac{1}{2}\hat{R}^3+\frac{1}{2}\hat{H})Si+\frac{1}{2}\hat{H}

      Pyeosclerite(A) 4:2:6:4
      2\hat{R}^3Si+Al\hat{S}i+6\hat{H}
      =(\frac{1}{2}\hat{R}^3+\frac{1}{2}\hat{H})\hat{S}i+2\hat{H}
```

2. General Formula—(R, H)Bil+Aq.

```
Pyrosclerite(B) 6: 4: 7\frac{1}{2}: 5 3\hat{R}^3\hat{S}^{\frac{3}{2}} + 2\hat{H}\hat{S}^{\frac{3}{2}} + 7\frac{1}{2}\hat{\Pi}. =(\frac{3}{6}\hat{R}^3 + \frac{3}{6}\hat{H})\hat{S}^{\frac{3}{2}} + 1\frac{1}{2}\hat{\Pi}. Clinochlore, Chlorite, \frac{1}{6}\hat{R}^3 + \frac{3}{6}\hat{R}^3\hat{S}^{\frac{3}{2}} + 3\hat{H}\hat{S}^{\frac{3}{2}} + 12\hat{\Pi}. =(\frac{1}{6}\hat{R}^3 + \frac{3}{6}\hat{H})\hat{S}^{\frac{3}{2}} + 1\frac{1}{2}\hat{\Pi}. =(\frac{1}{6}\hat{R}^3 + \frac{1}{6}\hat{H})\hat{S}^{\frac{3}{2}} + 1\frac{1}{2}\hat{\Pi}. =(\frac{1}{6}\hat{R}^3 + \frac{1}{6}\hat{H})\hat{S}^{\frac{3}{2}} + 1\frac{1}{2}\hat{\Pi}.
```

8. General Formula—(R, H)Sit+Aq.

```
RIPHOLITE, 8: 3: 4: 3 R^3 \ddot{S} \dot{I}_{1}^{2} + 3\dot{\Pi}. = (\frac{1}{3}\dot{R}_{1}^{2} + \frac{1}{3}\dot{\Pi}_{1})\ddot{S} \dot{I}_{1}^{2} + 1\frac{1}{3}\dot{\Pi}_{1}. Aphrosiderite, 8: 3: 4: 2 \dot{F}e^{3}\ddot{I}_{1}^{2} + \dot{H}\ddot{S}\dot{I}_{2}^{2} + 2\dot{\Pi}_{2}. = (\frac{1}{3}\dot{F}e^{3} + \frac{1}{3}\dot{H}_{1})\ddot{S}\dot{I}_{2}^{2} + \dot{\Pi}_{2}. Clietonite, 8: 5: 2: 1 \dot{R}_{1}^{2}\ddot{S}\dot{I}_{2}^{2} + \dot{H}\ddot{S}\dot{I}_{2}^{2} + \dot{H}\ddot{S}\ddot{I}_{2}^{2} + \dot{H}\ddot{S}\ddot{I}_{2}^{2} + \dot{H}\ddot{S}\ddot{I}_{2}^{2} + \dot{H}\ddot{S}\ddot{I}_{2}^{2} + \dot{H}\ddot{S}\ddot{I}_{2}^{2} + \ddot{H}\ddot{S}\ddot{I}_{2}^{I}_{2}^{2} + \ddot{H}\ddot{S}\ddot{I}_{2}^{2} + \ddot{H}\ddot{S}\ddot{I}_{2}^{2} + \ddot{H}\ddot{
```

4. General Formula-(Ra, E)Sil+Aq.

```
      CHLORITOID (B)
      1:3:2:1
      \hat{R}^3\bar{S}^{\frac{1}{2}}+3\bar{A}|\bar{S}^{\frac{1}{2}}+3\bar{H}
      =(\frac{1}{4}\hat{R}^3+\frac{3}{4}\hat{L})\bar{S}^{\frac{1}{2}}+\frac{3}{4}\hat{H}

      CHRONSTEDTITE,
      1:1:1:1:1
      \hat{R}^3\bar{S}^{\frac{1}{2}}+3\bar{H}
      =(\frac{1}{2}\hat{R}^3+\frac{1}{4}\hat{H})\bar{S}^{\frac{1}{2}}+1\frac{1}{2}\hat{H}

      SIDEROSCHISOLITE,
      2:1:1:1
      \hat{R}^3\bar{S}^{\frac{1}{2}}+3\bar{A}^{\frac{1}{2}}\hat{H}
      =(\frac{1}{4}\hat{R}^3+\frac{1}{4}\hat{H})\bar{S}^{\frac{1}{2}}+1\frac{1}{4}\hat{H}

      MARGARITE,
      1:6:4:1
      (\hat{R}^3,\hat{H}^3)\bar{S}^{\frac{1}{2}}+3\bar{A}^{\frac{1}{2}}\hat{H}
      =(\frac{1}{4}\hat{R}^3,\hat{H}^3)+\frac{3}{4}\bar{A}^{\frac{1}{2}}\hat{S}^{\frac{1}{2}}
```

[The parallelism of the Andalusite and Chlorite sections of Silicates has been alluded to. In the former there are the formulas $\mathbf{B}\mathbf{S}i^{\frac{1}{2}}$, $\mathbf{E}\mathbf{S}i^{\frac{3}{2}}$, $\mathbf{E}\mathbf{S}i^{\frac{3}{2}}$, $\mathbf{E}\mathbf{S}i^{\frac{3}{2}}$, and they afford a key to the formulas of the latter section, for the same oxygen ratios are repeated with only the addition of water, as is illustrated in the above table.

Margarodite is a hydrous mica, and may belong near the species of this section, if not a mere alteration of common mica, without a subsequent reconstruction into a distinct form. In most of the species, following Pyrosclerite (A), if the oxygen of the water be added to that of the bases, the ratio between this sum and that of the silica is 2:1.]

SARCOLITE, Thomson. Sarkolith. Analcime carnea, Monticelli.

		9						
3	1							
2		23	2 i					
		63						
I	i2		ii					
Observed Planes.								

Dimetric; $O:1i=156^{\circ}5'; a=0.4435$. Hemihedral in the planes 23, only the alternate occurring. $O:2=128^{\circ}33', 2:2$ (over terminal edge) $132^{\circ}52', O:\frac{2}{3}=157^{\circ}19', I:2=141^{\circ}27'$. Crystals small.

H.=6. G.=2.545. Lustre vitreous. Color flesh-red, reddish-white. Transparent to subtransparent. Extremely brittle.


According to an imperfect analysis by Scacchi, (Quadri Crystallographici, Naplea 1842, p. 66), contains

Si 42 11 XI 24 50 Ca 32 43 Na 2 93=101 97,

corresponding nearly to the composition of idocrase, and formula (1 (Na, Ca)+12).

Bi. B.B. fuses to a white enamel. With acids gelatinizes. Of rare occurrence at Mt. Somma.

MEIONITE, H. Mizzonite, Scacchi.



Dimetric: $O: 1i=156^{\circ} 18'; a=0.439$. Observed planes, O, 13, I, 33, i3, 1i, ii; sometimes hemihedral in the planes 33, the alternate being wanting. $O: 1=148^{\circ} 10', 1:1$, pyr.=136° 11', basal 63° 40'.

Cleavage: ii and I rather perfect, but often interrupted.

II.=5·5—6. G.=2·5—2·74; 2·734—2·737, v. Rath. Lustre vitreous. Colorless to white. Transparent to translucent; often cracked within.

Composition.—Ca³Si+2Xl Si=(½Ca³+½Xl) Si=Silica 42·1, alumina 31·9, lime 260 Analyses: 1, L. Ginelin, (Schw. J. xxv, 36, xxxv, 348); 2, Stromeyer, (Untera. 378); 3, Wolff, (De Comp. Ekeberg. etc., Ramm., 2nd Suppl. 133); 4, v. Rath. (De Comp. Wern., Pogg. xc, and Ramm., 5th Suppl., 211):

		Si	æı	$\mathbf{F}_{\mathbf{e}}$	Ċa	Мg	Ňа		Ŕ
1.	Somma,								——, Fe 1.07=100-93, Gm.
2.	"		32.73					1.81	
8.	**	42.07	3171		22.43		0.45		0.31, ign 0.81 = 97-29, Wolf.
4.	"	42.55	30.89	0.41	21.41	0.83	1.25		0.93, " 0.19=98.46, Rath

a With some Li.

B.B. a colorless glass; a clear glass with soda. With acids does not gelatiniss, according to v. Rath., contrary to v. Kobell's statement.

Mizzonite, from Mt. Somma, afforded Searchi the angles 1: 1=135° 56' and 64°06'; B.B. does not intumesce as much as Meionite, and is less easily attacked by acids.

Occurs in small crystals in geodes, usually in limestone blocks on Monte Somma.

near Naples.

Meionite was named from perwe, less, the pyramid being less acute than in idocrass

EUPHYLLITE, Silliman, Jr. Am. J. Sci. [2], viii, 382.

Structure as in mica, but laminæ not as easily separable. Bi-

axial; angle between the optical axes 7110, Silliman.

H.=3.5-4.5. G.=2.963-3.008, Silliman. Lustre of cleavage surface bright pearly, inclining to adamantine. Color white to colorless; sides faint grayish sea-green or whitish. Transparent to translucent; at times opaque or nearly so. Laminæ rather brittle.

Composition.— $\hat{R}^{s}Si+8\tilde{H}Si+6\hat{H}=(\frac{1}{9}\hat{R}^{s}+\frac{8}{9}\hat{H})Si+\frac{1}{8}\hat{H}=(if Ca: K: Na=3:4:11),$ Silica 41.8, alumina 42.2, lime 1.4, potash 3.2, soda 5.8, water 5.5. Analyses: Smith and Brush, (Am. J. Sci. [2], xi, 209):

Si X1 Mg K Fe Na Ĥ 1. Unionville, 40·29 43·00 1·30 1·01 0·62 3·94 5·16 5·00=100·32, S. & B. 2. " 39·64 42·40 1·60 1·00 0·70 3·94 5·16 5·08= 99·52, " 40.21 41.50 1.50 1.88 0.78 3.25 4.26 5.91= 99.29, 40.96 41.40 1.30 1.11 0.70 3.25 4.26 6.23= 99.21,

In a matrass yields water. B.B. exfoliates, emits a strong light, and in the forceps

fuses on the edges. Gives traces of fluorine, but none of lithia.

Occurs associated with tourmaline and corundum at Unionville, Delaware Co., Pennsylvania. The impression of the crystals of tourmaline on the lateral surface of the euphyllite leaves a very smooth hard looking surface. Also in the same vicinity in aggregated laminæ, or scales, or compact masses.

Smith and Brush deduce the oxygen ratio 1:9:9:2, and give the formula

RSi+R'Si2+2H. 1:8:9:2 corresponds better with the analyses, giving the

above formula.

Dr. Smith refers here with a query, a mica found by him with the emery of Asia Minor, which afforded him the following results, (Am. J. Sci. [2], xv, 62):

Ča Mg Fe Si X1 Mn K, Na H 1. Gumuehdagh, 42.80 40.61 1.30 3.01 tra. tra. undet. 5.62 2. Kulah, 43.62 38.10 3.50 0.52 0.25 7.83 5.51 44 42.71 37.52 2.32 1.41 tra. tra. 4. Nicaria, 42.60 37.45 1.70 0.68 tra. tra. 976


They afford the mean oxygen ratio, excluding the water, 1:10:12.

PYROSCLERITE, Kobell. Chonikrite, Kobell. Kæmmererite, Nord. Rhodophyllite, Genth. Vermiculite, Webb. Tabergite, Rose. Rhodoehrome, Rose.

Hexagonal? $0: r = 95^{\circ} 31', 0: m = 93^{\circ} 58',$ O: n (another plane in same series) 109° 4', Kohscharov. Cleavage: basal perfect. Occurs foliated and massive; also fibrous.

H.=2.5-3. G.=2.6-2.74. Lustre weak, pearly. Color green, apple-green, grayish, reddish. Translucent. Fracture uneven and splintery.

Composition. -3R3Si4+2 XISi4+74H=(3R3+3XI) Si4 +14H=Silica 32.6, alumina 19.8, magnesia 34.6, water 13.0=100. In part, the same with Sid or Sid; in part 2R³ Si+XI Si+6H=(\(\frac{1}{2}\)R^3+\(\frac{1}{2}\)XI)Si+2H=Silica 37.6, alumina 14.2, magnesia 33.2, water 14.9; and the same with 1\(\frac{1}{2}\)H, for Tabergite.



Analyses: 1 Kobell, (J. f. pr. Ch. ii, 51); 2, Lychnell, (K. V. Ac. H., 1826); 3, Kobell, (loc. cit.); 4, Svanberg, (K. V. Ac. H., 1839, 155); 5, Hartwall, (Jahresb. xxiii, 266); 6, T. H. Garrett, (Am. J. Sci. [2], xv, 332); 7, Genth, (Proc. Acad. Nat. Sci. Philad. 1852, 121, mean of two analyses); 8, Hermann, (J. f. pr. Chem. liii, 1); 9, 10, Smith and Brush, (Am. J. Sci. [2], xvi, 47); 11, 12, Hermann, (loc. cit.); 13, Crossley, (this Min. 3d edit., 291); 14, T. S. Hunt, (Phil. Mag. [4], ii, 65);

```
Fe
                       Si
                             Al Gr Mg
                                                   Ča
                                                                     Ħ
 1. Pyrosclerite, 37.03 13.50 1.43 31.62 —
                                                            3.52 11.00=98.10, Kobell.
                                                            179 7.38, C & Bit. 6.28=9976,L
146 9.00=98.37, Kobell
6.34 11.76, Mn1.64, K 2.07, MgF,
                     35.28 13.73 - 35.35
 3. Chonikrite,
                     35.69 17.12 - 22.50 12.60
 4. Tabergite,
                     35.76 13.03 - 29.27
                                                                                 1-1=100-98, Sv.
                     37·0 14·2 1.0 31·5 1·5 1·5 13·0=99·7, Hartwall, 37·66 11·82 3·60 24·97 4·11 2·50 13·58, Ni 0·67=98·92, Gar. 33·20 11·11 6·85 35·54 trace Fel·43 12·95, Li, Na0·28, K0·1, G. 31·82 15·10 0·90 35·24 — "4·06 12·75, Ni 0·25=100·12, Her.
    Kammererite, 37.0 14.2 1.0 31.5
 6.
           11
                                                    - " 1.96 12.64, K, Na 0.35=9961,
 9.
                     33.26 10.69 4.78 35.93
                                                                                 Smith & Brush
                                                    - "1.60 18.25, K, Na 0.35=9975,
Smith & Brush
10.
                     33.30 10.50 4.67 36.08
                                                   - Fe3.32 12.05=100.33, Hermans.
                     30.58 15.94 4.99 33.45
11.
                                                   - Fe2.00 12.03=100.14, Hermann.
12. Rhodochrome, 34.64 10.50 5.50 35.47
                                                    -Fe10.02 10.30=99.92, Crossley.
13. Vermiculite, 35 74 16 42 - 27 44
14. Loganite,
                     32.49 13.18 - 35.77 0.95 Fe2.14 16.92 (Cincluded)=101.45
```

1, From Elba; 2, Aker, Sudermanland; 3, Elba; 4, Taberg; 5, Siberia; 6 to 10,

Texas, Pa.; 11, 12, L. Itkul; 13, Milbury, Massachusetts.

Nos. 6 to 10 are of similar character; 7 is rhodophyllite of Genth; 8 is chrom chlorite of Hermann. The varieties severally in a matrass yield water; and B.B. fuse with difficulty to a grayish glass; with borax form a chrome-green pearl. Wholly decomposed by concentrated sulphuric acid.

The oxyd of chromium varies in amount with the color, the paler varieties containing but little. Smith and Brush attribute the nickel to mixed sulphuret of

nickel. The Aker mineral (anal. 2) resembles serpentine in appearance.

Chonikrite occurs massive, of a white color, glistening lustre and weak translu-cence; found with pyrosclerite, at Elba. B.B. fuses with intumescence to a grayish

glass; soluble in muriatic acid, without gelatinizing.

Vermiculite has a granular scaly structure and greasy feel, and looks like steatite.

The scales when heated (to 500° or 600° F) open out into worm-like threads made up of separated laminæ of cleavage; and sometimes, as Dr. C. T. Jackson states, swelling to nearly a hundred times the original length; and if confined in a glass tube this expansion is so powerful as to break it with an explosion, and scatter the glass to a distance. G.=2.756. In the forceps a scale fuses readily to a yellowish-green glass; with soda an opaque brown bead; with borax or salt of phospheres easily a glass, yellow while hot and colorless when cold, or with the latter flux becoming somewhat milky-white on cooling. Decomposed by muriatic and sulphuric acids. In a matrass yields water which is somewhat alkaline. Crossley's analysis was made on the scales carefully separated from the mealy magnesian base with which it is associated. His formula is that of pyrosclerite.

Tabergite, called by Werner blue tale of Taberg in Wermland, is considered a distinct species by G. Rose, as it has but little resemblance to pyrosclerite.

Kammererite occurs in hexagonal prisms, of a reddish violet color like lepidolite. Cleavage basal, perfect. Sometimes plumose massive. H.=15-2. G.=276, Siberia; 2.617-2.62, Texas. Lustre pearly. Translucent. Sectile and flexible. Feel greasy. Found with chromic iron at Bissersk, Siberia; also at Texas, Lancaster Co. Pensylvania, with chromic iron in serpentine; the crystals are hexagonal or rhombic prisms, sometimes with the basal edges replaced; also crystallized at Haroldswick in Unst, Shetlands.

Rhodochrome has a greenish black color, but is peach-blossom-red in thin splinters. It occurs massive with a fine scaly structure, and a splintery fracture. H.=25-2. G.=2.668; 2.65, Hermann. B.B. strongly heated fuses on the edges to a yellow enamel. Affords a chrome-green glass with borax. Dissolves with difficulty in muriatic acid. From the island Tino, Greece, and from Bissersk and Kyschtimsk

Loganite, T. S. Hunt, from Calumet Island, on the Ottawa, Canada, has a weak begantie, 1. S. Hunt, from Calumet Island, on the Ottawa, Canada, has a weak subresinous lustre, pale or dark brownish color, and grayish streak; H.=3. G.=2.6 —2.64; sometimes in crystals with rounded angles, which appear to be pseudomorphs; one gave the angle 124°, near that of hornblende. Associated with serpentine, phlogopite, pyrites and apatite in crystalline limestone.

Hermann has found in blue Baltimorite, from Bare Hills, near Baltimore, Md., 33.26 per cent. of silica, 7.23 alumina, 4.34 chromic acid, with 2.89 Fe, 38.56 Mg, 12.44 H, 1.30 C; while Thomson, who instituted the species, obtained 40.95 of silica and


130 C; while Thomson, who instituted the species, obtained 40.95 of silica and 150 of alumina. Hermann's mineral may be impure pyrosclerite.

Delesse has analyzed a Serpentine-like mineral, remotely related to pyrosclerite, from the granular limestone of the Vosges, (Ann. des M. [4], xx, 155). It is soft, with a greasy or waxy lustre, grayish, bluish, and emerald-green color. G.=2.622. Analysis, in which the magnesia was determined by the loss, afforded Si 38.39, Ål 26.54, Gr trace, Fe 0.59, Mn trace, Ca 0.67, Mg (by diff.) 22.16 H 11.65=100.

The name pyrosclerite is from rep, fire, oxlnpes, hard, (refractory); chonikrite, from xwisia, fusion, xpiros, test, alluding to its differing from some allied minerals in its fusibility; Kammererite, after M. Kæmmerer; Rhodochrome, from pocos, rose, xpoya, color; Vermiculite, from vermiculus, a little worm, alluding to the blowpipe action.

CLINOCHLORE, W. P. Blake, Am. J. Sci. [2], xii, 339.

Trimetric and hemihedral; structure micaceous, and crystalline planes often equilateral triangles. Optically biaxial; apparent an-



5. Atheriastite,	∄i 38:00	Äl 24·10	Ča 22:64	Mg 2.80	Ňa.		Ĥ .95, Fe 4-82, M n
b. Athermatic,	50 00	24 10	22 01	200			=100 09. Berlin.
II. 6. Arendal, black,	29.52	1577	9.02	8.20		0.37	10.89a Fe 19.14, =98.45, v. Rath.
7. "epidote,	87-92	19:21	22.68	0.25			2·51, F e 15·55=
III. 8. Algerite, N. J.,	49.82	24.91		1.15		10.21	9874, v. Rath. 7.57, CaC 3.94
9 " "	49.96	24.41		5·18			==99.45, Hunt. 5.06, CaC 4.21,
10. " "	52-09	18·63b	1	undeteri	nined		1.48=100.27, Cr. CaO 4.41, Cal P
11. Yellow, Bolton,	49-99	28-01	8.35	178	0.35	7:09	8-22, Whitney. 4-23, OaO 7-80,
•					1	e 1.64:	=99 19, v. Rath.
12. <i>Red</i> , Arendal,	59·7 4	16.20	2.15	4.02	4.31	4.42	1·83, Pe 7·90=
							100.57, v. Rath.
18. Mica, "	44.49	24.91	2.14	0.36	1.11	671	
							99.11, v. Rath.
14. " _ "		° 27·87b			0.42		
15. " Pargas,	4875	26.15		1578	0.83	5.64	0.68=95.77, "
a With some bitumen.	b With a l	ittle pero	xyd of in	ron.	c By lo	ss and p	robably too high.

The altered scapolite of Franklin, N. J., (anal. 1, 2), is leek-green or yellowish-green, and has the forms of scapolite. H.=3.5. G.=2.78. Lustre subresinous or subvitreous. Very fusible. Occurs with quartz and calcite. The mineral from Diana, N. Y., (anal. 3), is in large crystals in calcite. with sphene, with the cleavage and appearance of scapolite. Color gray. H.=5.5. G.=2.74.

Stroganowite (Hermann) has a clear green color. H.=5.8. G.=279. Form and appearance nearly as in scapolite. Color light oil-green, yellowish green. Subvitreous, inclined to greasy. From near the Sludanka, a river in Dauria. Named

after M. Stroganow

Atheriastite, (Weibye), like scapolite in form and appearance. Green. Opaque.

From the mines of Arendal.

The Black scapolite of Arendal (anal. 6) is altered by a large addition of magnesia and iron. Color grayish-black; streak grayish-white. Rather soft. G.=2*837. No cleavage. B.B. edges rounded with difficulty.

The Epidote pseudomorph of the same locality, (anal. 7), has received still more largely of oxyd of iron, without magnesia. It gives the oxygen ratio of epidote

Algerite (Hunt) (anal. 8, 9, 10) occurs in slender square prisms, sometimes 2 or 8 inches long imbedded in calc spar. Yellowish to gray and usually dull. Brittle. H.=3-3.5; some crystals more altered, 2.5. G.=2.697-2.712 Hunt, 2.78, Crossley. From Franklin, Sussex Co., N. J. The varying results of analyses, and the presence of carbonate of lime, of magnesia, and the relations to known examples of altered scapolite, confirm the view derived from the form and appearances, that Alcontains an altered Scapolite. The yellow scapolite of Bolton examined by v. Rath (anal. 11) is a similar compound. It has H.=4.5, and G.=2.787; massive, with perfect rectangular cleavages. It is near to a mica in a composition, having received largely of potash in the change; oxygen ratio for R. R. Si, 1: 3.8: 8.9.

The Red scapolite of Arendal (anal. 12) has H.=5.

G.=2.852. Brownish or the change of th

brick red. Difficultly fusible. Oxygen ratio 1:2.4:7.5. In the change, Fe, mag-

nesis and potash have been introduced.

The Mica pseudomorphs of Arendal occur in quartz, and have the form according to v. Rath, of large crystals of scapolite, 6 inches long. The crystals are covered with mica externally, and within consist throughout of an aggregation of the same mica. The mica is greenish-white, translucent. H.=2-3. G.=2.833. Oxygen ratio, (from v. Rath), 1; 5.6: 10.5; perhaps 1: 6: 10\frac{1}{2}, giving 1: 1\frac{1}{2} for the oxygen of the bases and silica. The change from scapolite has consisted in the removal of lime, addition of Fe, and substitution of potash for sods. The Pargas mica pseudomorph is a magnesian mica

Sicatite pseudomorphs, formed by the substitution of magnesia, for other prot-

Cleavage basal, highly perfect. Crystals often tabular, crested. H.=2-2.5; sometimes 3 on lateral edges. G.=2.65-2.85; 2.673, Ala, Piedmont. Lustre vitreous when pearly. Color dull emerald-green, seen in the direction of the axis, and yellowish or hyacinth-red, at right angles with it: sometimes silver-white, Massive varieties olive-green. Transparent-subtranslucent. Laminæ not elastic.

Composition.— $5\hat{R}^{3}\tilde{S}i^{\frac{1}{4}}+3\tilde{A}l\tilde{S}i^{\frac{3}{4}}+12\hat{H}=(\frac{5}{8}\hat{R}^{3}+\frac{3}{8}\hat{R})\tilde{S}l^{\frac{3}{4}}+1\frac{1}{2}\hat{H}=Silica 32.6$, alumina 18-5, magnesia 36-0, water 12-9=100. Analyses: 1, Varrentrapp, (Pogg. xlviii, 185); 2, 3, 4, Kobell, (J. f. pr. Ch. xvi, 470); 5, Brüel, (Pogg. xlviii); 6, Delesse, (Ann. Ch. Phys. [3], ix. 396); 7, 8, Marignac, (Ann. Ch. Ph. [3]. x, 430); 9, 10, Hermann, (J. f. pr. Ch. xl, 13); 11, Schweizer, (Pogg. l, 526); 12, 13, 14, Marignac, (Ann. Ch. Ph. [3], x, 428):

		\overline{8}i	X 1	Mg		Fe	М'n	Ĥ
1.	Achmatowsk,	30.38	16-97			4.37		12.63=98.31, Varrentrapp.
2.		31.25	18.72	32.08				12.63=99.78, Kobell.
3.		31.14	17-14	34.40				12.20, insol.0.85=100.11,K.
4.	Schwarzenstein,	32.68	14.57	33.11		5.97	0.28	12·10, insol. 1·02=99·73, K.
5.	Zillerthal,	31.47	16.67	32.56		5.97	0.01	12:42=99:11, Brüel.
6.	Pyrenees, G .= 2.615,	32.1			2			12·1=100, Delesse.
7.	Ala, G.=2.673,	30.01	19.11	33.15	Fe	4.81	_	12.52=99.60, Marignac.
8.	Slatoust,							12.54=100.25, Marignac.
9.								12.30=98.82, Hermann.
	Leuchtenbergite,							12.50=99.51, Hermann.
11.	Zermath, Pennine,							12.58=99.08, Schweizer.
12.		33.36	13.24	34.21	F	5-93	_	12.80, Cr 0.20=99.74, M.
13.	" "							1274, " 0·15=100, M.
14.	Binnen, "	33.95	13.46	33.71	66	6.13	-	12·52, " 0·24=100, M.

Other analyses: A. McDonnell, (Proc. R. Irish Ac. v, 307); Delesse, (Ann. d. M.

[4], xviii, 309, loc. Col de Pertuis).

Yields water in a matrass. B.B. on charcoal fuses to a globule, at least on the edges; glass with borax colored with iron. Not dissolved with soda. Thin leaves are soluble in concentrated sulphuric acid.

Chlorite forms extensive beds in Plutonic regions, and is the characterizing ingredient of chlorite slate. Often occurs in quartz crystals, in vermiform crystal-lizations, and f. 467 is an enlarged view of a part of a specimen from New Hamp-shire, described by Professor Hubbard. Octahedral crystals of magnetic iron, and

shire, described by Professor Hubbard. Octahedral crystals of magnetic iron, and hornblende, are the most common minerals in chlorite and chlorite slate. Chlorite occurs at the above-mentioned localities and in various parts of the Eastern United States. The name is from $\chi \lambda \omega \rho o s$, green. Kokscharov, in a paper on the crystallization of chlorite, mentions numerous planes, and their angles. But the micaceous minerals vary so much by distortion that the angles are seldom trustworthy. (Verh. Min. Ges. St. Petersb., 1850-51, and Am. J. Sci., [2], xv, 437). Fig. 465 is from Kokscharov's paper.

Leuchtenbergite is from near Slatoust, in the Ural. Breithaupt considers it an altered chlorite: Komonen found but 8-62 per cent. of water. Kengott regards it as

a distinct species.

The Piklite of Sefstrom from Fahlun, is a doubtful species between tale and mica. The Tale Zographique of Hauy is a green earth,

A Chlorite-like mineral from Pressburg, Hungary, analyzed by von Hauer and described by Kengott, (Sitzb. xi, 609, 1853), is a hydrous biotite, affording the oxygen ratio for the protoxyds, peroxyds, silica and water, 1:1:2:1 and formula R² Si + HSi+3H or (½R²+½H)Si+1½H. Von Hauer obtained (loc. cit.) Si 38·13, Al 21·60, Fe 19·92, Mn 2·61, Mg (loss) 13·76, H 3·98.


Occurs near Mauleon in the Lower Pyrenees, with tale or chlorite, in an unctuous argillite. Named from $\delta\iota_i$, double, and $\pi\nu\rho$, fire, alluding to its both phosphorescing and fusing before the blowpipe.


Couzeranite of Charpentier. According to R. P. Greg, Jr., who has examined several crystals, couzeranite occurs in square prisms, giving I: I=90°, and I: i=185°. He suggests to the author that the species is Dipyre. It occurs in nearly the same region, (Couzeran in the Pyrenees), and resembles dipyre in appearance.


Composition, according to Dufrenoy, Si 52.37, Al 24.02, Ca 11.85, Mg 1.40, K 5.52, Na 3.96=98.55. B.B. nearly like Dipyre. It has been referred to labradorite, and according to Dufrenoy has an oblique form. The crystals are rough and may give varying measurements.

EPIDOTE, H. Zoisite, (in part.) Pistacite. Thallite. Withamite. Akanticon. Scorza. Delphinite. Arendalite. Bucklandite, Levy. Piemontischer Braustein, W. Eisenepidot. Manganepidot. Thulite. Puschkinite, Wagner. Achmatit, Hermann.

Monoclinic; $C=64\ 36'$; $I: I=63^{\circ}\ 8', O: 1i=125^{\circ}\ 4\frac{1}{2}^{\circ}$; a:b:e=0.8693:1:0.5514.







$$\begin{array}{llll} O: ii = 115^{\circ} \ 24'. & O: I = 102^{\circ} \ 59'. & -1: -1 \ (\mathrm{ib.}) = 96^{\circ} \ 10'. \\ O: 1i \ (\mathrm{adj.}) = 128^{\circ} \ 19'. \ ii: 1i = 116^{\circ} \ 17'. & \frac{1}{2}: \frac{1}{2} \ (\mathrm{ib.}) = 103^{\circ} \ 30'. \\ O: \frac{1}{2}i = 154^{\circ} \ 03'. & ii: \frac{1}{2}i = 90^{\circ} \ 33'. & 22: 22 \ (\mathrm{ib.}) = 96^{\circ} \ 41'. \\ O: 2i = 98^{\circ} \ 57'. & ii: 1 = 104^{\circ} \ 49'. & i2: i2 \ (\mathrm{ov.} \ ii) = 101^{\circ} \ 43'. \\ O: 1 = 110^{\circ} \ 59'. & ii: -1 = 117^{\circ} \ 49'. & \frac{1}{2}i: \frac{1}{2}i \ (\mathrm{ov.} \ O) = 109^{\circ} \ 6' \\ O: \frac{1}{2} = 134^{\circ} \ 55'. & ii: 22 = 128^{\circ} \ 5'. & 1i: 1i \ (\mathrm{ib.}) = 70^{\circ} \ 9'. \\ O: -1 = 130^{\circ} \ 11'. & 1: 1 \ (\mathrm{ov.} \ 1i) = 70^{\circ} 33'. \ ii: 1i = 75^{\circ} \ 44'. \end{array}$$

		0		
$\frac{1}{3}i$				
1i		+		1/2
16	= 3	1	12	11
3; 2				
2i	22	W.		
ii	i2	I		iì
-1 <i>i</i>		-1		19
				10

Observed Planes.

Crystals lengthened in the direction of the orthodiagonal, or parallel to ii. Cleavage ii perfect; O less so. Twins: plane of composition O; also ii. Also columnar, divergent, or parallel; also granular, particles of various sizes, sometimes impalpable.

II.=6—7. G.=3·25—3·5. Lustre vitreous, ii inclining to pearly or resinous. Color green, brown, or gray, sometimes red, white, black; green usually yellowish; less yellow in the direction of the vertical axis, than at right angles with it. Streak uncolored, grayish, reddish. Subtransparent—opaque: generally subtrans-

lucent. Fracture uneven. Brittle.

APHEOSIDERITE, Sandberger, (Ueb. Geol. Nassau). A ferruginous ripidolite, differing from the above in containing protoxyd of iron replacing the magnesia, and having less water. Occurs fine scaly granular.

Composition .- According to Sandberger, Si 26.45, Al 21.25, Fe 44.24, Mg 1.06, H 7-74=100-74=(1Fe3+1XI)Si3+H. From Weilburg.

METACHLORITE, List. Foliated columnar, like chlorite, vitreous to pearly in lustre, dull leek green color. H .= 2.5. Composition according to K. List:

Si X1 Fe Mg Ca K Na H 28-77 16-43 40-36 3-10 0-74 1-37 0-08 13-75=99-60.

Whence the oxygen ratio for R, H, Si, H, is 10.65: 7.67: 12.59: 12.22, which gives for the oxygen of the bases and silica the ratio 18:32: 12:59=3:2, as in Aphrosiderite; the formula is therefore 4R°Si +3HSi +14H=(47R°+3H) Si +2H. B.B. fuses on the edges to a dark enamel. Gelatinizes in the cold with muriatic acid.

CLINTONITE, Mather. Seybertite, Clemson. Holmesite, Thomson. Chrysophane, Breit. Xanthophyllite, Rose. Brandisite, Liebener.

Usually in tabular crystals, or foliated massive; sometimes lamellar radiate. Structure thin foliated, or micaceous parallel to the base.

H.=4-5. G.=3-3.1. Lustre pearly submetallic. Color reddish-brown, yellowish, copper-red. Streak uncolored, or slightly vellowish or grayish. Folia brittle.

Composition.—Meitzendorff's analyses give the oxygen ratio for R, R, Si, H, 8:5:2:1=3H3, 5H1, 2Si, 3H, whence, if 2Hl replace silica, we have the formula $\hat{R}^3\hat{S}i^{\dagger} + \hat{X}l(\hat{S}i, \hat{X}l)^{\dagger} + \hat{H} = (\frac{1}{2}\hat{R}^3 + \frac{1}{2}\hat{X}l)(\hat{S}i, \hat{X}l)^{\dagger} + \frac{1}{2}\hat{H}.$

Analyses: 1, Clemson, (Am. J. Sci. xxiv, 171); 2, Richardson, (Holmesite), (Rec. Gen. Sci. May, 1836); 3, 4, 5, Meitzendorf in Rose's labratory, (Xanthophyllite), (Pogg. lviii, 165); 6, Kobell, (the Disterrite), (J. f. pr. Chem. xli, 154):

Ča 5.0 Mg 1. Amity, Clint. 17:0 37:6 24:3 10-7 3.6=98.2, Clemson. 19.35 44.75 9.05 11.45 Fe 4.80 2. 4.55, Mn 1.35, Zr 2.05, HF0.9 =98.25, R. 3. Slatoust, Xant. 16·55 43·73 19·04 13·12 Fe 2·62 ign. 4·33, Ña 0·67=100·06, Meit.
4. " 16·41 43·17 19·47 14·50 2·23 " 4·45, Ña 0·62=100·85, M.
5. " 16·20 44·96 19·43 12·15 2·73 " 4·33, Ña 0·55=100·35, M.
6. Fassa, Dister. 20·00 43·22 25·01 4·00 Fe3·60 Ĥ 3·60, Ř 0·57=100, Kobell.

B.B. infusible alone, but whitens; with borax or soda forms a transparent pearl. In powder acted on by concentrated acids.

Occurs at Amity, N. Y., in limestone beds connected with serpentine, along with hornblende, spinel, pyroxene, and graphite. Also (the Xanthophyllite) in the Schisehimskian mountains, near Slatoust, in implanted globules about an inch and a half through, consisting within of the mineral; and in columnar and lamellar individuals, which sometimes contain within thin tabular crystals of a hexagonal form, secondary apparently to a rhombic prism. Also (the *Disterrite*, called also *Brandisite*) in the valley of Fassa, Tyrol, in hexagonal prisms. H. of base 5, of sides 6—6.5. G.=3.042—3.051.

```
Si
                    X1
                                Fe
                                                                   Mg
                                                                 Mg 1

3*80, Mn 1*36, Ĥ 8*70⇒97*79, Berr

3*44, Mn 3*40, Ĥ 5*36⇒98*72, "

0*01 29*81, Ĥ 4*59, K, Ña 0*61⇒99*96, B.

1*60 20*83, Ĥ 3*34, K, Ña 0*62⇒100, B.

0*86 1*91, Ĥ 0*52, Mn 0*85⇒100*08, Sch.

0*38 1*45, K 0*67, Ĥ 3*28⇒98*30, Scheer.

2*15, 0*59, Mn 0*39, Ĥ and some Ĉ 17*56
10. 36.25
                 14.00 11.42
                                       17.39
                                                        4.87
11. 32.00
                 14.80
                             12.44
                                        19:44
                                                        7.84
                   8.18
                              9.06
                                         4.98
                                                        5.48
12. 36'24
                                          4.56
13. 33.60
                 12.58
                             13.48
                                                        9.59
14. 34.93
                 14.26
                             14.90
                                       21.43
                                                      10.42
15. 33.81
                 13.04
                             15.65b 20.50
                                                       9.42
                              4.21 20.01
16, 32.93
                 15.54
                                                       6.76
                                                                                                                  =100.13, Br.
                                                                 1.58b, 1.18, ign. 1.24=99.71, Berlin.
4.94, 2.12, Mn 1.55, H 11.46, Č 6.71=
17. 33.05 15.29 16.64 20.55*
                                                      10.18
18. 27.59 16.14 16.01 11.75*
                                                       2.28
                                                                                                                  100.55, Bahr.
```

a Including oxyd of Lanthanum and Didymium. b Containing also manganese. c Undetermined.

IV. Uralorthite, G .= 3.4-3.647. From the Ilmen Mountains.

9·25 2·06, Mn 2·37, La 6·54, Ĥ 2=99·80, Herm 10·20 1·08, ĥe 8·24, La 7·66, Ĥ 1·56=100·03, U. 19. 35.49 18.21 13.03 10.85 20. 34.47 14.36 7.67 14.79

Rammelsberg has examined the orthite of Hitteroe, with special reference to its proportion of iron oxyds, (Pogg. lxxvi, 96), and corrects analysis 15 as follows: Si 33.81, Al 13.04, Fe 8.16, Fe 8.30, Ce 20.50, Y 1.45, Ca 9.42, Mg 0.38, K 0.67, H 3.38=99.11, which gives, excluding the water, the formula above. The water amounts to 1 H, with this formula. The same composition is derived from Her-

mann's analysis, No. 19.

B.B. Allanite fuses with intumescence, to a dark glass or slag, sometimes magnetic. Cerine fuses easily. Orthite fuses slowly to a black blebby glass. Reaction of iron with the fluxes, and with soda a manganese reaction. Uralorthite intumeses,

often very easily, and fuses on the edges to a black blebby glass.

Some allanites, and also some orthites, gelatinize with acids; others are imperfectly decomposed. Uralorthite is dissolved in acids, somewhat gelatinizing.

These varieties occur in albitic and common feldspathic granite, zircon-syenite, porphyry, and white limestone. Allanite occurs in Greenland, in granite; at John Fjeld in Norway, in a kind of porphyry, and at Snarum in albite, along with rutile and apatite; at Plauensche Gründ, near Dresden; in granite near Suhl in the Thüringerwald. The Allanite from Jotun Fjeld gelatinizes with acids, while that from Snarum is not affected by acids; Cerine occurs at Bastnäs in Sweden with hornblende and copper pyrites. Orthite occurs in acicular crystals sometimes a foot long at Finbo near Fahlun, and at Ytterby in Sweden; at Skeppsholm near Stockholm, in black vitreous masses disseminated through gneiss; also at Krageröe, Hitteroe and Fille Fjeld in Norway, at Miask in the Ural; at Dresden. The name is derived from optos, straight. Uralorthite occurs with small crystals of zircon in the bred foldeness at Miask in the Ural. flesh-red feldspar at Miask in the Ural.

In the United States in large crystals in Allen's vein at the gneiss quarries, Hadand, Conn.; in small crystals at the Bolton quarry, Mass.; at South Royalston in boulders; at Athol on the road to Westminster in gneiss; in a feldspathic rock in tabular crystals near West Point, and of similar character near Bay St. Paul, in Canada; in S. Mountain near Bethlehem, Pa., in crystals sometimes as large as the hand; in New Jersey, near Moriah, at Sandford ore bed. A massive pitch-black mineral from Monroe, Orange Co., N. Y.; a similar variety is found at East Bradford or bester Co. Par. G. 225 (Anal. S); at St. Pavil's Canada West.

ford, Chester Co., Pa.; G.=3.5, (Anal. 5); at St. Paul's, Canada West.
With Allanite belong probably Bodenite, (Breith. Pogg. lxii, 273, Kersten, ib. lxiii. 135, Kerndt, J. f. pr. Chem. xliii, 219), and Muromontite, (Kerndt, J. f. pr. Chem.

xliii, 228).

Bodonite occurs in long prismatic crystals, apparently rhombic, with I: I=110° -112°. H.=6-6.5. G.=2.523. Color brown, reddish-brown to nearly black and lustre somewhat greasy. Analysis by Kerndt, (loc. cit.): Si 26.12, 31 10.34 Fe 12.05, Y 17.43, Ce 10.46, La 7.57, Ca 6.32, Mg 2.34, Mn 1.62, K 1.21, Na 0.84, H 3.82=100. B.B. glows like gadolinite; in platinum forceps, fuses only on the edges after long heating, and gives to the flame the yellow color of soda in the outer flame. From Boden, near Marienberg, in the Saxon Erzgebirge, with oligoclase.

CRONSTEDTITE, Steinmann. Chloromelan, Naumann.

Rhombohedral. Occurs in hexagonal prisms, tapering towards the summit, or adhering laterally; also in diverging groups, reniform and amorphous. Cleavage: basal, highly perfect.

H.=2.5. G.=3.348. Lustre brilliantly vitreous. Color brownish-black. Streak dark leek-green. Opaque. Not brittle. Thin laminæ elastic.

Composition.— $\hat{R}^s\hat{S}^{\frac{1}{2}}+\hat{F}^s\hat{S}^{\frac{1}{2}}+\hat{R}^s\hat{H}=(\frac{1}{2}\hat{R}^s+\frac{1}{2}\hat{H})\hat{S}^{\frac{1}{2}}+1\frac{1}{2}\hat{H}$. Analyses: 1, Steinmann, (Schw. J. xxxii, 69); 2, same, as corrected by Kobell, (Schw. J. lxii, 196):

	S i	Fе	Йg	М́п	茁
1.	22.452	58.852	2.885	5.078	10-700=99-968, Steinmann.
2	22.452	27:112	2.885	5.078	10.700. Fe 35.850=108.577. Kobell.

B.B. froths and fuses on the edges, yielding, according to Kobell, a magnetic gray globule. With borax gives the reaction of iron and manganese. In powder gelatinizes in concentrated muriatic acid.

Accompanies hydrate of iron and cale spar, in veins containing silver ores, at Przibram in Bohemia. It occurs also at Wheal Maudlin in Cornwall, in diverging groups. Named after the Swedish mineralogist and chemist, Cronstedt.

SIDEROCHISOLITE, Wernekink, Pogg. i, 387.

Hexagonal or rhombohedral. Observed planes O, I, 1. Crystals minute and often hemispherically grouped. Cleavage: basal, perfect. Massive.

II.=2.5. G.=3-3.4. Lustre splendent. Color pure velvet-black when crystallized, dark greenish-gray. Streak leek-green, greenish-gray. Opaque.

Composition.—Fe*Si†+1H. Analysis by Wernekink, (on three grains of the mineral, loc. cit.):

B.B. fuses easily to an iron-black magnetic globule, according to Wernekink; infusible, Berzelius. Gelatinizes in muriatic acid.

Crystallized specimens occur in cavities of magnetic pyrites and sparry iron ore, at Conghonas do Campo in Brazil. Named from σιόπρος, iron, and σχιστος, cleavable, λιθος, stone.

Chamoisite, as analyzed by Berthier, (Ann. d. Mines, v, 393), has nearly the above composition, his result giving

Si 14.8, Fe 60.5, X1 7.8, H 17.4=100, with 15 per cent. of carbonate of lime.

It is considered a mixture of magnetic iron and a hydrous silicate of alumina. It occurs in beds of small extent in a limestone mountain abounding in ammonites at Chamoisin in the Valais. It has a black earthy appearance, and becomes red before the blowpipe.

heating 4.286—4.456, H. Rose; 4.35, from Hitteroe, Scheerer. Lustre vitreous, inclining to resinous. Color black, pitch-black. greenish-black. Streak greenish-gray. Subtranslucent—opaque. Fracture conchoidal.

Composition.—Approximately R²Si. Analyses: 1, 2, 3, Berzelius, (Afhand. iv, 148, 389); 4, Richardson, (Thom. Min. i, 410); 5, 6, Scheerer, (De foss. allanit, orthit, cerin, gadol. Berolini, 1840, and Pogg. Ivi, 479); 7, 8, 9, 10, Berlin, (Dissert. Gadol. Upsal. 1844, and Ofvers. af K. V. Ac. 1845, 86):

```
—— 45 00 16 69
 1. Pinbo,
               25-80
                                              10-26 — ign. 0-60=98-35, Berzeliu.
                                             1134 — ign. 0·60=98·93, Berzelius.

$\mathbf{F}\ 8.00 \ 3.15 \ \frac{1}{2}\text{m} \ 1.30, \ \hat{H}\ 5-20=99·53, B.

"14·55 — \hat{H}\ 0·50=100·55, R.
   Broddbo, 24.16
                             45-98
                                     16-90
                       200 4730 €840
   Korarfvet, 29.18
               24-65 11-05 45-20 "4-60
                                             4 14·55 —
                                              11.68 0.34 Ea 4.75,=100.71, Scheerer.
12.13 0.23 Ea 6.33=99.42, Scheerer.
L Hitteroe,
               2578 9.57 45-67 C1-81
               25.59 10.18 44.96
               "7-90
7. Ytterby,
10.
                             a With oxyd of Lathanum.
```


Of Berlin's analyses, the first two were of the glassy gadolinite; the others, excepting the last, did not present the glow of light when heated.

B.B. decrepitates and swells into cauliflower-like masses, but does not fuse into a

B.B. decrepitates and swells into cauliflower-like masses, but does not fuse into a bead; in the progress of the heat it exhibits a vivid glow, and the color becomes paler. With borax a dark glass deeply colored with iron, bottle-green in the reducing flame. Acted on by salt of phosphorus with great difficulty. A variety less glassy in appearance does not exhibit the glow on heating. Gelatinizes in muriatic acid.

Gadolinite occurs principally in the quarries of Korarfvet and Finbo, near Fahlun, in Sweden; also at Ytterby, near Stockholm; at each place indistinctly crystallized, and in rounded masses, which are often encircled with a yellow crust, and imbedded in coarse-grained granite. At Korarfvet crystals have been obtained four inches long. It has also been met with at Disko in Greenland; in trap near Galway, Ireland; imbedded in granite in Ceylon; at Finbo and Broddbo, and at Krageröe and Hitteröe in the southern part of Norway, crystals sometimes four inches across and twins at this last locality. Named after the Russian chemist, M. Gadolin.

DANBURITE, Shepard, Am. Jour. Sci. xxxv, 189.



Triclinic. Approximate angles, P: M 110° and 70°, M: T 54° and 126°, P: T 93° nearly, P: e 135°. Cleavage: distinct, parallel to M and P, less so parallel to T. Crystals imbedded, and often an inch broad. Also disseminated massive, without regular form.

H.=7. G.=2.95, Sillinan, Jr.; 2.957, Brush. Color pale yellow, whitish. Lustre vitreous, but usually rather weak. Translucent to subtranslucent. Very brittle.

Diphanite of Nordenskiöld (Bull. Acad. St. Petersburg, v, 17) is near Margarite. It occurs in hexagonal prisms with perfect basal cleavage. H.=5-5.5. G.=3.04-3.97. Color white to bluish. Formula 2P.Si+3×1.2Si+4\vec{H}. Analysis by Jeveinoff: Si 34.02, ×1 43.33, Ca 13.11, Fe 3.02, Mn 1.05, H 5.34=99.87. B.B. becomes opaque and fuses with intumescence in the inner flame to an enamel. With little soda, a blebby glass. From the emerald mines of the Ural with chrysoberyl and phenacite.

EPHESITE, J. L. Smith, Am. J. Sci. [2], xi, 59.

Lamellar, and resembles white kyanite. Cleavage difficult. Scratches glass easily. G.=3·15-3·20. Color pearly-white.

Composition.—Analyses by Smith, (loc. cit.):

	Si	æı	Ċa	Fe Ňa	and a little	ŔĦ
1.	31.54	57.89	1.89	1.34	4.41	8.12=100.19.
2.	30.04	56.45	2.11	1.00	4.41	8.09 = 97.07.

The oxygen ratio deduced for the protoxyds, peroxyds, silica and water, is 1:15:9:2. From the emery locality of Gumuch-dagh near Ephesus, on specimens of magnetite.

Probably related to Margarite, near which it is placed by Dr. Smith.

NON-MAGNESIAN HYDROUS SILICATES.

- 1. Oxygen ratio of bases and silica 1:1 to 1:3; of protoxyds and peroxyds, 1:1 to $1:2\frac{1}{2}$, rarely to 1:3.
- I. PYROPHYLLITE SECTION. Oxygen ratio between bases and silica, 1:8 to 1:2½.

PYROPHYLLITE,

表1 Si*+14A.

ANTHOSIDERITE,

Fe Si3+A.

II. PECTOLITE SECTION. Oxygen ratio between bases and silica augitoid, or 1: 2, varying to 1: $2\frac{1}{4}$.

APOPHYLLITE GROUP, II. APOPHYLLITE, !(Oa, Na, H) Si2+H.

LAUMONTITE GROUP, IV. PECTOLITE,

(Ĉa, Ña)⁴Si²+Ĥ.

OKENITE, !(Ča, Ĥ) "Ši"+1 } Ĥ.

Laumontite, $(\frac{1}{4}\mathring{C}a^3 + \frac{3}{4}\ddot{\Xi}l)\ddot{S}i^2 + 3\dot{\Pi} = (\mathring{R}^3, \frac{3}{4})\ddot{S}i^2 + 3\dot{\Pi}$.

[†]Cataplemte, (‡Ř³+‡Zr)Ši³+2Ĥ.

DIOPTASE GROUP, VI.

Dioptabe, Ču³Ši³+8Ĥ.

[Chrysocolla, Cu3Si3+6H.

Pyrosmalite, (fe, Mn) Si2+1(FeCl2+FeHe.


blende or magnetic iron ore in Normark in Sweden, and of a dark color, at the Botallack mine in Cornwall, where it also occurs massive, forming a peculiar kind of rock with garnet and tourmaline; also at Thum near Ehrenfriedersdorf in Saxony, and called Thumite and Thummerstein. It occurs with gray cobalt, near Coquimbo, Chili; at Phipsburg, Maine, with yellow garnet and idorrase; also at Wales, Maine. Axinite admits of a high polish, but is deficient in delicacy of color. It was named from after, an axe, in allusion to the form of the crystals.

IOLITE. Dichroite. Peliom. Steinheilite. Cordierite, H. Sapphire d'eau. Hard Fahlunite.

Trimetric. In stout prisms often hexagonal. $O:1i=150^{\circ}49'$, $O: 1=132^{\circ} 12'$, $I: I=60^{\circ} 50'$, and $119^{\circ} 10'$, $is: is=120^{\circ} 50'$.



Observed planes.



Cleavage: O and ii indistinct. Crystals often transversely divided, or foliated, parallel with O. Also massive, compact.

H.=7-7.5. G.=2.5969, Greenland, Stromeyer; 2.65-2.6643. Haddam, Thomson; Ostgothland 2.64, Südermanland 2.61, Schütz. Lustre vitreous. Color various shades of blue, light or dark, smokyblue; often deep blue along the vertical axis, and brownish-yellow or yellowish-gray, perpendicular to it. Streak uncolored. Transparent-translucent. Fracture subconchoidal.

Composition.—R² Si²+3H Si, Berz =(1 R²+1 H) Si²=Silica 49.6, alumina 33.6, magnesia 87, protoxyd of iron 79.

Analyses: 1, 2, 3, Stromeyer, (Unters. 329, 431); 4, 5, Schütz, (Pogg. liv, 565); 6, Scheerer, (Pogg. lxviii, 319, mean of two analyses); 7, Thomson, (Min. i, 278); 8, Jackson, (this Min. 2nd ed. 406, and Geol. Rep. New Hampshire, 184);

	₿i	Æl	Mg	$\mathbf{M}_{\mathbf{n}}$	Fe	H
1. Bodenmais,	48.35	31.71	10.16	0.33	8.32	0.59=99.46, Stromeyer.
2. Greenland.	49.17	33.11	11.45	0.04	4.34	1.20=99.31, Stromeyer.
8. Fahlun,	50.25	32.42	10.85		4.01	1.66, Mn ().68=99.87, Strom.
4. Ostgothland,	48.6	30.5	8.2	0.1	107.	1.5, undec. 0.2=100.8, S.
5. Südermannland	. 497	82.0	9.5	0.1		a 0.6, ign. 2.1, und. 0.6=100.6,8
6. Krageroe,	50.44	32.95	1276			I 1·02, Fe J·07, Ca 1·12=99·36.8
7. Haddam, Ct.	49.62	28.72	8.64	1.21	11.28	—, Ca 0.28=100.30, Thom.
8. Unity. Me.	48.15	32.50	10.14	0.58	7.92	0·50==99·49, Jackson.

B.B. fuses slowly on the edges to a blue transparent glass; with borax forms a clear bead. In powder attacked by concentrated acids, but not perfectly dissolved. Iolite is met with at Bodenmais, in Bavaria, occasionally in perfect crystals 11 in. thick. This variety has been called pelion, from its smoky-blue color, from zelies.

16H be added to the bases, we have 15R+10Si+10H=5R*Si*+10H=R*Si*+2H, which last is probably the true formula of the species, and seems to require that Apophyllite should be arranged in the Pectolite Section, where we

place it provisionally.

In Okenite the ratio of the oxygen of the bases and silica is 1:4, a ratio unknown in the Anhydrous Silicates, except in Petalite. The prismatic angle 122° 19' is so near that of Hornblende that we may suspect an approximation in form under the Monoclinic System. If 3H be considered as acting as a base, the formula is then of the Augite type, (ratio 1:2); and on this ground the species is placed near Pectolite. Rose recognizes the ratio 1:2 for the silicate of lime in his formula of Okenite, Ca "Si2+2H3Si.

Pyrophyllite has the ratio and probably the form of Tale, although different in containing no protoxyds; it pertains to a section parallel with that

of Talc in the Magnesian Series.

A considerable group of so-called species, related to Kaolin or Halloysite, might be here added. They are the direct result of the decomposition or alteration of other species, and have already been mentioned under the spe-

cies from which they are derived. They are as follows:

Under Pyroxene, Cimolite, (p. 165), Palagonite, (p. 166). Under Feldspar, Kaolin, (p. 249), Tuesite, Smelite, Lithomarge, Myelin, Melopsite, (p. 250), Pholerite, Halloysite, Smectite, Lenzinite, Samoite, (p. 251), Bole, Ochran, Collyrite, Pipestone, Agalmatolite, (p. 252).]

I. PYROPHYLLITE SECTION.

PYROPHYLLITE, Hermann.

Foliated like tale; often radiated lamellar.
H.=1. G.=2.7—2.8; 2.785, Berlin. Lustre pearly, inclined to greasy. Color white, apple-green, grayish and brownish-green, ochre-yellow. Subtransparent - subtranslucent. Thin laminæ flexible.

Composition.—AlSi*+1\frac{1}{2}H=Silica 67.7, alumina 25.6, water 6.7; or \frac{1}{2}Silica 65.2, alumina 29.6, water 5.2. Analyses: 1, Hermann, (Pogg. xv, 592); 2, Rammelsberg, (lxviii, 513); 3, 4, Sjögren, (Ofv. K. V. Ac. Förh., 1848, 110):

		Si	X 1	Fe	Mg	
1.	Siberia,	59-79	29.46	1.80	4.00	5.62, silver trace=100.67, Herm.
2.	Span,	66.14	25.87	-	1.49	5.59, Ca 0.39=99.48, Ramm.
3.	Westana, Sw.	67-77	25.17	0.82	0.26	5.82, Ca 0.66, Mn 0.50=101.00, Sj.
4.	11 11	65.61	26.09	0.70	0.09	7.08, Ca 0.69, Mn 0.09=100.35, Ber.

From Hermann's analysis comes the formula Mg Si2+9 Xl Si2+9 H.

B.B. alone swells up and spreads out into fan-like shapes, and increases to twenty times its former bulk. Infusible. With soda it forms a clear yellow glass. With cobalt solution it assumes a fine blue color. Partially soluble in sulphuric acid. Pyrophyllite occurs in the Uralian mountains, between Pyschminsk and Beresof; at Westana, Sweden, etc. It was considered a radiated tale. Also found in Cotton-

stone Mountain, Montgomery Co., N. C., in white stellate aggregations.

```
Mg
8·01
                                                                           Ĥ
                                      Æl
                               Вi
                                                                           173=99 86, Scheerer.
7-38, Mn 0-32, Pb, Cu, Ca,
Co, 0-50=98-62, Erdmann.
H and NH 3-20, Mn 0-63, Na
0-68, Zn 0-3=100-72, Wacht.
                             50.40 32.38
17. Krageroe, Asp.
18. Bräkke, Pras.
                                                                 1373
                             40-94 28-79
19. Fahlun, Weis.
                             58.69 21.70
                                                          4.10
                                                                   8.99
20. Helsingfors, Pyr. 43-93 28-93
                                                  5.30
                                                        1 05
                                                                  2.90b H15.47, Na 1.85=99.43, Nord.
                                                                 1 40 H C 4 49, Na 0 92 99 63, M

tr. 475°, Na 279, Ca

1 58=101 03, v. H.
21. Fleimser, Liebn. 44.66 36.51
                                                  175
                                                        9.90
                             44.45 38.75F7 2.26
                                                         6.45
22
```

b With magnesia. Reckoned as protoxyd by Erdmann.

Pinite includes the alkaline varieties of altered iolite, (analyses 1 to 9). In 6 or 12-sided prisms; cleavage often indistinct, sometimes basal; color gray to gray ish-green or brown. H.=2.5. Analysis 5 corresponds in formula to iolite+2H; 7, 8, 9, iolite +3H, Marignac; 6, to iolite +XI Si²+6H, Rammelsberg. B.B. whitens and fuses on edges. Occurs in Auvergne at the Puy-de-Dome, in decomposed feldspar porphyry; at Schneeberg in granite. Oosite related to pinite is from near Baden.

Fahlunite, Hisinger, (Anal. 10, 11), Bonsdorffite or Hydrous Iolite of Bonsdorff, Anal. 12), Esmarkite, Erdmann, (Anal. 13), Chlorophyllite, Jackson, (Anal. 14).— These are very similar, occurring often in large 6 and 12-sided prisms, the form of the original iolite, (sometimes 6 inches across), with basal cleavage usually perfect and sometimes micaceous. Folia brittle. Color gray or grayish-green, greenish brown, dark olive green. Lustre pearly. G. in Fahlunite 2:6—2:79; in Esmarkite 2:709; in Chlorophyllite, 2:705. B.B. fuse only on the thinnest edges. Bone-dorffite and Fahlunite correspond to Iolite+6H; Esmarkite, to Iolite+8H; Chlorophyllite to Iolite+2H; but the water is not constant, and the varieties are not distinct. Fahlunite occurs with iolite at Fahlun; Bonstorfite at Abo; Esmarkite is from near Brayig: Chlorophyllite from Unity Me, and Heddem Ct. is from near Brevig; Chlorophyllite from Unity, Me., and Haddam, Ct.

Gigantolite, Nordenskiöld, (Anal. 15, 16).—Forms and cleavage as in the last; H. about 3.5, but on cleavage surface 2; G.=2.862-2.878. Greenish to dark steelgray; between vitreous and waxy, approaching submetallic. Formula if part of the iron is peroxyd, (Fe 2 83, Fe 11 61), equivalent to Iolite +8H. B.B. fuses with intumescence to a light greenish slag. From Tamela, Finland, in a gneissoid granite. Crystals large.

Aspasiolite, Scheerer, (Anal. 17). In prisms like the preceding, but cleavage less distinct. II.=3.5. G.=2.764. Greenish gray to whitish. Lustre weak. Composition, Iolite + Al Si²+5II. B.B. infusible. From Krageroe in Norway, with quartz and iolite.

Prazeolite, Erdmann, (Anal. 18). In prisms with basal cleavage, like the above Green, with lustre greasy. Fracture flat-conchoidal and splintery. H.=3.5. G.=2754. Composition if the iron is peroxyd, Iolite+3H, Rammelsberg. B.B. fuses on thinnest edges only to a bluish green glass. From Brakke, near Brevig, Norway.

in granite.

Weissite, (Anal. 19). Similar to Fahlunite. Color blue, green. G.=2.8. Formula given, R'Si'+2BSi'. From Fahlun, occurring in chlorite state in masses as large as hazlenuts.

Tennant has analyzed a mineral from Canada East, (Rec. Gen. Sci., 1836, May, 832), which has the composition of Weissite, affording Si 5505, Al 2260, Mg 570, Fe 1260, Mn trace, Ca 140, H 225=9960. A relation to Weissite is doubtful.

Pyrargillite, Nordenskiöld, (Anal. 20). In prismatic forms; cleavage not distinct. =3.5. G.=2.5. Partly black, or bluish, liver-brown or dull red, and dull resin-

a red feldspar porphyry at Mt. Viesena, Fleimser Valley, in porphyry. Von Hauer states that his specimen had no appearance of alteration. The reference of this mineral here may not be correct.

Ca Ř H HF 52·13 24·71 5·27 16·20 0·82 (=4·82 Ca fluosil)=99·13, B. 1. Utö, 2. Faroe, Tesselite, 52.38 24.98 5.87 16 20 0.64 (=3.53 Ca fluosil)=99.57, B. 51.33 25.86 4.90 und. F 1.28, Ramm. 50.20 24.52 und. und. F 1.09, Ramm. 3. Andreasberg, Radauthal, G.=1.961, 52:44
 24:61
 4:75
 16:73
 Ca fluosil. 1:43 (=0:46 F.) R.
 Michigan, G. 2:305, 52:70
 23:35
 4:95
 16:00
 Ca F 1:85=98:85, Jackson. Nova Scotia, 52.60 24.88 5.14 16.67 F1.71=101, Reakirt. 8. L. Superior, G.=2.37, 52.08 25.30 4.93 15.92 0.96=99.19, Smith

Yields much water in a matrass, and in an open tube some fluorine. B.B. exfoliates, and ultimately fuses to a white vesicular glass; in an open tube usually some hydrofluoric acid. Melts easily with borax, and the saturated solution becomes milk-white on flaming. In nitric acid in powder it separates into flakes and becomes

imperfectly gelatinous and subtransparent.

The tesselite of Brewster, from Faroe, has a cubical form, and on optical examination, exhibits a tesselated structure. Oxhaverite is a pale green variety from the Oxhaver springs, near Husavick in Iceland, where it occurs on calcified wood; it is

generally indistinctly crystallized and translucent. Albin, of Werner, is a white, opaque variety, found at Aussig in Bohemia, associated with natrolite.

Greenland, Iceland, the Faroe Islands, Poonah and Ahmednuggar in Hindostan, afford fine specimens of apophyllite, coating cavities in amygdaloid, and associated with chalcedony, stilbite, chabazite, &c. At Andreasberg, in silver veins, traversing gray-wacke slate; in the Bannat, associated with Wollastonite; in Fifeshire, with magnetic iron; at Utö in Sweden; at Puy de la Piquette in Auvergne, in a ter-tiary limestone, near intruded basaltic rocks; at Dalecarlia, Sweden; in the Tyrol, near Frombach; Orawicza, Hungary; near Nertschinsk, Siberia; in New Holland; the Valencian Mines, Mexico.

In America it has been found at Peter's Point and Partridge Island, in the Basin

of Mines, Nova Scotia, both massive and crystallized, presenting white, reddish, and greenish colors, and associated with laumonite, thomsonite, and other minerals of trap rocks. Good crystals occur in greenstone at Bergen Hill, N. J., associated with analcime, pectolite, stilbite, datholite, &c. It is also found at Gin Cove, near Perry, Maine, with prehnite and analcime in amygdaloid; at the Cliff Mine, Lake Superior region, (f. 470.)

Apophyllite was so named in allusion to its tendency to exfoliate under the blowpipe, from απο and φυλλου, a leaf. Its whitish pearly aspect resembling the eye of a fish after boiling gave rise to the name lehthyophthalmite, from εχθυς, fish, and οφθαλμος, εγε.

XYLOCHLORE, Waltershausen, Vulk. Gest. 297. Dimetric and pyramidal, like apophyllite. Angle of pyramid about 96°. Cleavage basal, perfect, H.=6. G.=2.2904. Color olive green. Composition.—Analysis by Waltershausen, (mean of two analyses, loc. cit.), Si 52.07, Al 1.54, Ca 20.57, Mg 0.33, Fe 3.40, Na 0.55, K 3.77, H and O 17.14=99.37.

The mineral contains some carbonate of lime intermixed. From Iceland. The rystals are 1 to 11 millimeters long. Closely resembles apophyllite, and may be

that species.

GYROLITE.—The Gyrolite (or Gurolite) of Anderson, (Phil. Mag. [4], i, 101), from Skye, is very near Apophyllite. It occurs in spherical concretions having a lamellar radiate structure, white and pearly; H.=3-4; like Apophyllite before the blowpipe and with acids. Analysis afforded Si 50 70, Al 1 48, Ca 33 24, Mg 0 18, H 14 18=99 78; giving approximately CaSi+14H, (or more nearly 14H).

PECTOLITE. Pektolith, Kobell, Kastner's Archiv., xiii, 385, xiv, 341. Osmelite, Breit. Wollastonite, Thom.

Monoclinic, and near Wollastonite in angle, (Greg and Lettsom). Cleavage: orthodiagonal, perfect. Twins parallel to ii common. In aggregated acicular crystals, or fibrous massive, radiated or stellar.

Lustre of the surface of fracture G = 2.68 - 2.74H=5.39

I. Observations of Silliman, Jr.

1. American Muscovite and Lepidolite; Angle from 55° to 76°.

	•	
	Now York Taland Am Arm Older might man containing	Apparent Angle.
1.	New York Island, 4 m. from City, violet gray, containing	56° 20'-56° 40'
۵	black grains,	57° 30′
3.	Royalston, Mass., dark brown, fine crystal, ib. ib. ib. another,	58°-59°
	Pennsbury, Penn., smoky brown, striated,	590
5.	Philadelphia, Penn., greenish gray, banded,	60° 80′-61°
6.	ib. ib. near Fairmount, smoky brown; re-	
•	sembles No. 4,	60°-62° 80′
7.	Oxford, Maine, light brown,	62° 42'-63°
	Monroe, Conn., brown with patches,	64° 80'-65° 80'
9.	Royalston, Mass., violet brown; in thick plates,	650
10.	Local. ! greenish gray; in crystals,	65° 30'-66°
	Falls road, 21 m. from Baltimore, transparent brown,	65° 80′–65° 40′
12.	Near Ellicott's Mills, Md., ib. ib.,	66° 30′
13.	"Jones Falls," near Baltimore, blackish green; symmetri-	
	cally banded,	66° 15′-66° 80′
14.	Greenfield, Conn., greenish yellow,	66° 80′–67° 67°
10.	Haddam, Conn., (Quarry Hill), clear brownish green,	67° 30′
	Grafton, New Hampshire, light brown, transparent,	67°-67° 28′
	Unionville, Penn., white, Corundum locality,	67° 15′-67° 80′
19	Acworth, N. H., greenish gray, in granite, Grafton, N. H., another specimen, light brown, with	01 10 -01 80
10.	quartz and tourmaline,	68° 5'-68° 20'
20.	Templeton, Mass., transparent brown,	69° 30′-69° 40′
21.	Orange, Mass., ib. ib, beautiful crystals,	69° 30'-69° 40'
22.	Willimantic Falls, Conn., brownish green, transparent in	
	granite,	69° 30′-69° 5 0′
23.	Pennsbury, Penn., brown crystals; another locality.	69° 27′-70°
24.	Royalston, Mass., dark brown; 2d locality.	69° 40′-70°
	Grafton, N. H., light brown; 3d specimen,	69°-69° 80′
	Middletown, Conn., brownish, feldspar quarry,	700-700 301
27.	Chester, Hampden Co., Mass., greenish white,	70°-70° 30 ′
28.	Norwich, Mass., greenish yellow; Spodumene locality,	70° 80′
259.	Pennsbury, Penn., (3d local.), brownish green,	700-700 80'
3U.	Goshen, Mass., greenish yellow, with spodumene, Greenfield, N. Y., brownish; Chrysoberyl locality,	70°-70° 30 70° 45′-71′
91.	Haddam, Conn., brownish; in large plates,	700
	Gouverneur, N. Y., brownish-white, in boulder.	700
34.	Templeton, Mass., (2d spec.,) transparent brown.	70° 15′
85.	Leiperville, Del. Co., Pa., faint greenish, plicated,	700 30'-710
	Jefferson Co., N. Y., greenish; in a boulder.	71°-71° 30′
37.	Hebron, Maine, light brown, transparent,	71° 40′-71° 50′
3 8.	Norwich, Mass., yellowish green transparent;	71° 45′
39.	Haddam, Conn., ib. ib.; Columbite locality, E. Chester, Westchester Co., N. Y., yellowish green boulder,	71° 30′-71° 45′
40.	E. Chester, Westchester Co., N. Y., yellowish green boulder,	71° 30′-72°
41.	Paris, Maine, ib. ib.,	72° 15′-72° 3 0°
42.	_ ib. ib., ib.,	72° 30′
48.	ib. ib., Brunswick, Maine, whitish brown, silvery,	72° 37′-72° 50′
44.	Gouverneur, N. Y.? fair rose color; no lithia,	73°-78° 5′
	Paris, Maine, whitish green; with green tourmaline.	74°-74° 80′
4 6.	ib. ib. ib. another,	73°
4 7.	Orange, N. H., gray, with flattened tourmaline, quartz and	73° 74′
4 9	feldspar, Pannal Maine, nearly colonloss, lithic i mice	78° 74' 74° 50–75'
20.	Pounal, Maine, nearly colorless; lithia? mica.	14 00-19

LAUMONTITE, Hauy. Lomonite, W. Laumonite. Efflorescing Zeolite.

Monoclinic. C.=68° 40', I: I=86° 16', O: 1i=151° 9'; a: b: c=0.516:1:0.8727. In form related to augite. Observed planes, O, I, ii, 1, -1, -2i.

```
O: 1=148° 22'.
                 1:1=133° 26'.
                                     ii:-1=120° 17'.
O: I=104° 20'.
                 -1:-1=119° 26'.
                                     ii: -2i=125° 41'.
O: ii=101° 20'.
                 iì: 1=113° 17'.
                                     O: -2i=122° 59'.
```

Cleavage: ii perfect; also I. Also columnar, radiating, or di-

H.=3.5-4. G.=2.29-2.36. Vitreous, inclining to pearly upon the faces of cleavage. White, passing into yellow or gray, sometimes red; streak uncolored. Transparent-translucent; becomes opaque and usually pulverulent on exposure. Fracture scarcely observable, uneven. Not very brittle.

Composition.—Ca3Si3+3AlSi2+12H, Gerhardt=(+Ca3+4Al)Si2+3H=Silica 511, alumina 21.8, lime 11.9, water 15.2=100.

Analyses: 1, 2, Dufrénoy, (Ann. d. Mines, [3], viii, 503); 3, Connel, (Edinb. Jour. 1829, 282); 4, 5, Babo and Delifs, (Pogg. Ann. lix, 339); 6, Malaguti and Durocher, (Ann. d. Mines, [4], ix, 325); 7, N. J. Berlin, (Pogg. lxxviii, 415); 8, Scott, (Jameson's J., Oct. 1852, liii, 284):

	Si	X 1	Ča	Ĥ
1. Phipsburg, Me.,	51.98	21.12	11.71	15.05=99.86, Dufrénoy.
2. Cormayeur,	50.38	21.43	11:14	16·15=99·10, Dufrénoy.
3. Skye,	52.04	21.14	10.62	14.92=98.72, Connel.
4	52.30	22.30	12.00	14·2=100·8, Babo.
5.	51.17	21.23	12.43	15.17 (loss)=100, Delffs.
6. Huelgoet, G .= 2.290,	52.47	22.56	9.41	15.56=100, M. and D.
7. Red, Upsala,	51.61	19.06	12.53	14.02, Fe 2.96=100.18, Berlin.
8. I. Storr,	53-05	22.94	9:67	14.64=100.30, Scott.

B.B. intumesces and fuses to a frothy mass. With borax forms a transparent globule. Gelatinizes with nitric or muriatic acid, but not affected by sulphuric acid, unless heated.

Laumontite occurs in the cavities of amygdaloid, also in porphyry and syenite, and occasionally in veins traversing clay slate with calcite. It was first observed in 1785, in the lead mines of Huelgoet in Brittany, by Gillet Laumont, after whom

Its principal localities are at the Faroe Islands, Disko in Greenland, in Bohemia at Eule in clay slate, St. Gothard in Switzerland, the Fassa-thal in large masses exhibiting a radiated structure, Hartfield Moss in Renfrewshire, accompanying analcime, the amygdaloidal rocks in the Kilpatrick hills near Glasgow, and in several trap rocks of the Hebrides, and the north of Ireland.

Peter's Point, Nova Scotia, affords fine specimens of this species. It is there associated with apophyllite, thomsonite, and other species of this family. Also found in good specimens at Phipsburg, Maine, and the Charlestown quarries, Mass., in gneiss; also sparingly at Bradleysville, Litchfield Co., Conn., near a paper-mill, in narrow seams in gneiss; and at Southbury, Conn., a little east of the village, on the land of Mr. Stiles. Abundant in many places in the copper veins of Lake Superior in trap and on I. Royal; on north shore of Lake Superior, between Pigeon Bay and Fond du Lac. Found also at Bergen Hill, N. J., in greenstone, with datholite, apophyllite, &c.; sparingly at Phillipstown, N. Y., in feldspar with stilbite and at Columbia bridge, near Philadelphia.

II. Observations of Senarmont.

(1.) Micas whose optical azes are situated in the diametral plane of the longer diagonal.

```
    Odontchelon, Daouria; gangue dolomite and diopside; brown; cryst.
    Loc. — ! Hexagonal; transparent; brown, a little greenish,

          Loc. — ! Hexag.; transparent; clear brown,
Loc. — ! Hexag.; transparent; copper-colored,
Ceylon. Hexag.; transparent; clear green, nearly colorless,
Philadelphia. Transparent; clear clive-green,
Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Silvain and Sil
    8. Loc.
    4. Loc. -
    6. Philadelphia.
    7. Siberia, in white quartz. Silvery, imperf. transparent,
    8. Zillerthal, in albite. Silvery, imperf. transparent, 9. Arendal, in a feldspathic rock. Transparent; pale,
10. Loc. — † Transparent; gray, rhombs,
11. Loc. — † Hexag.; { outer parts grayish-brown, central parts colorless,
                                                                                                                                                                                                                     67°
                                               Transparent; clear brown,
                                                                                                                                                                                                                      58-59°
 12. Loc. -
13. Couzeran! Silvery, greenish-gray, with concave surface of cleavage, 14. St. Gothard, in quartzoec gneiss; hexag.; silvery; clear gray,
                                                                                                                                                                                                                     600
                                                                                                                                                                                                                     60°
16. Missk. Transparent; clear clive green,
18. Ekatherinenburg. Transparent; clear pale rose,
21. Schetank. Imperfectly transparent; rose-colored,
28. Brittany. Transparent, rhombic octahedrons; blond,
24. Kimito, Finland. Rhombic octahedrons; transparent; clear blonde,
                                                                                                                                                                                                                     69-63°
                                                                                                                                                                                                                      68-64°
                                                                                                                                                                                                                     67°
                                                                                                                                                                                                                     68°
                                                                                                                                                                                                                      67-68°
 25. Finland. Crystals, silvery; grayish green,
27. Aberdeen. Transparent; blonde,
                                                                                                                                                                                                                     67-684
                                                                                                                                                                                                                     68°
           Ekatherinenburg.
                                                                Rhombic prisms in feldspar; cryst; transparent;
                                                                                                                                                                                                                      69_70
                   nearly blonde,
                                    -! Colorless; but affords { a central region, an outer region,
                                                                                                                                                                                                                     70°
60°
 29. Loc. -
 82. American, probably; Lepidolite or rose mica,
83. Alençon. Hexag.; transparent; grayish blonde,
                                                                                                                                                                                                                     74-760
                                                                                                                                                                                                                     76-77°
           (2.) Micas with the optical axes in the diametral plane of the shorter diagonal.
 84. Lake Baikal. Hexag.; deep brown; transparent,
 85, 86, 87, 88 -micas of unknown locality,
49. Loc. —— ! Hexag.; deep bottle green,
40. Saxony. Hexag.; silvery, clear gray; transp., macled,
42. Zinnwald, with tin ore. Hexag.; silvery, greenish blonde by trp.
43. Loc. —— ! Hexag.; transparent; colorless;
                                                                                                                                                                                                                    150
                                                                                                                                                                                                                     44°
                                                                                                                                                                                                                      46-47°
                                                                                                                                                                                                                     50°
 44. Lepidolite; rhombic,
                                                                                                                                                                                                                     550
                                                                                                                                                                                                                     68°
 46. Piedmont. Rhombic; silvery reflection; grayish-green by trp.
                                                                                                                                                                                                                      65°
 48. St. Féréol, near Brives. Transparent; olive-green,
                                                                                                                                                                                                                     65°
 49. Milan. Hexag.; greenish-white; silvery; unctuous, not elastic,
                                                                                                                                                                                                                      66°
51. Fossum, Norway. Hexag.; clear olive-green,

52. Scotland. Brown; in large thick crystals,
54. Tarascon (Ariége). Rhombic; transparent; colorless,
55. Ural, in graphic granite; octahedrons in quartz; silver lustre; color

                                                                                                                                                                                                                     68°
                                                                                                                                                                                                                      690
                   blonde,
                                                                                                                                                                                                                     72-780
56. Utö. Rhombs; lustre silvery; yellowish blonde by trp.,
```

On examining different micas pressed between two plates of glass, and subjecting them to changes of temperature, Senarmont found no perceptible change in the optical axes.


Many of the micas that were reputed unaxial, and are properly biotite, were

^{*} The micas of doubtful locality in Senarmont's table are in general here omitted; but his numbering is retained.

DIOPTASE, Hauy. Emerald Copper, Phillips. Emerald Malachite. Achirite, Kupfer-Smaragd, W. Smaragdo-Chalcit, Br.

Rhombohedral; $R: R=126^{\circ} 24'$; $O: R=148^{\circ} 38'$; a=0.5281. Observed planes; rhombohedral, 1(R), 2, -2; hemi-scalenohedral on three alternate edges as in the figure, with also 2° ; also 1° ; prismatic i2, $i\frac{3}{2}$, $i\frac{4}{3}$, $i\frac{5}{7}$, the last three hemihedral.

```
O: 2=129^{\circ} 21'. i \frac{3}{3}: i2=165^{\circ} 44'. i2: i2=120^{\circ}. i \frac{3}{2}: i2=169^{\circ} 06'. 2: 2=95^{\circ} 54'. 1^{\circ}: i2=146^{\circ} 36'. 2: i2=132^{\circ} 3'. 2: R=137^{\circ} 57'. i2: R=126^{\circ} 48'.
```



Cleavage: R perfect. Twins: composition face R. H = 5. G = 3.278. 3.348. Lustre vitreous. St.

H.=5. G.=3·278, 3·348. Lustre vitreous. Streak green. Color emerald-green. Transparent—subtranslucent. Fracture conchoidal, uneven. Brittle.

Composition.—Cu²Si²+3H=Silica 38·3, oxyd of copper 50·3, water 11·4=100. Analyses: 1, 2, Hess, (Pogg. xvi, 860); 3, 4, Damour, (Ann. d. Ch. Phys., [8], x. 485):

```
1. Si 36·60 Cu 48·89 H 12·29 Fe 2·00=99·78, Hess.
2. 36·85 45·10 11·52 H 2·36, Ca 3·39, Mg 0·22=99·48, Hess.
3. 36·47 50·10 11·40 Fe 0·42, Ca C 0·35=98·74, Damour.
4. 38·93 49·51 11·27=99·71, Damour.
```

B.B. decrepitates, tinging the flame yellowish-green; in the outer flame becomes black, in the inner red, but does not melt. Fuses with borax to a green globule, and is finally reduced. Insoluble in nitric acid, but soluble and gelatinizing in muriatic.

Dioptase occurs disposed in well defined crystals on quartz, at Altyn Tübé, in the Kirghese Steppes of Siberia, whence it was first brought by a Bucharian merchant, Achir Mamed, after whom it was named Achirite. Also found in the Duchy of Nassau, between Oberlahnstein and Braubach.

The name dioptase is from dia, through, and 'ourrough, to see.

CHRYSOCOLLA. Kieselkupfer. Kieselmalachit. Copper-green. Kupfergrün, Cuivre hydrosilicieux, H.

Botryoidal and massive, incrusting or disseminated.

H.=2-3. G.=2-2·238. Lustre vitreous, shining, earthy. Color mountain-green, bluish-green, passing into sky-blue; often brown when impure. Streak white. Translucent—opaque. Fracture conchoidal. Rather sectile; translucent varieties brittle.

Composition.—Cu³Si³+6Ĥ=Silica 34.8, oxyd of copper 45.2, water 20.5; often mixed with carbonate and oxyd of copper. Analyses: 1, Ullmann, (Syst. tab. Uebers. 275); 2, Kobell, (Pogg. xviii, 264); 3, 4, 5, Berthier, (Ann. Ch. Phys. li, 395); 6, Bowen, (Am. J. Sci. viii, 18); 7, Beck, (Am. J. Sci. xxxvi. 111); 8, Scheerer, (Pogg. Ixv, 289); 9, C. T. Jackson, (Private communication); 10, Rammelsberg, (J. f. pr. Ch. lv, 488, Pogg. lxxxv, 300); 11, Kittredge, (ib.):

Twins: often observable by internal markings, or by polarized light; composition parallel to I. Folia sometimes aggregated in stellate, plumose, or globular forms; or in scales and

scaly massive.

H.=2-2.5. G.=2.75-3.1. Lustre more or less pearly. Color white, gray, pale-green, and violet-yellow, sometimes brown and dark olive-green; colors different in axial and diametral directions. Streak uncolored. Transparent—translucent. Thin laming flexible and elastic, very tough. Sectile. Biaxial; angle between the axes of polarization 45°-75°.

Composition.—(\mathbb{R}^2 , \mathbb{H}) \mathbb{S}^2 ; mostly $(\frac{1}{3}\mathbb{K}^3 + \frac{1}{4}\frac{3}{4}\mathbb{H})\mathbb{S}^2$. Analyses: 1, 2, H. Rose, (Schw. Jour. xxix, 282, and Gilb. Ann. lxxi, 13, and Pogg. i, 75); 3, Svanberg, (K. V. Ac. H. 1839, 155); 4, 5, 6, Rose, (loc. cit.); 7, Svanberg, (loc. cit.); 8, Schafhäutl, (Ann d. Ch. u. Pharm. xliv, 40):

```
Ši
                                        ₩n
                                                              0.56, H 2.63=101.59, Rose.
1.12, H 1.00=98.26, Rose.
                                3.20
                47.50
                        37:30
                                                       9.60
                                        0.90
2. Broddbo, 46·10
                        81.60
                                 8.65
                                        1.40
                                                       8.39
                                                              ___, F 0.72, Al 0.35, H 3.32, S 1.09, H 0.98, Ti trace=99.18, R
3.
                47.97
                        31.69
                                 5.37
                                        1.67
                                                       8.31
4. Fahlun,
               46.32
                                           2.11
                       34.52
                                6.04
                                                       8.22
                                                              0.71, H 1.84=99.52, Rosa.
0.29, H 4.07, Ca0.13=100.88,R
5. Kimito,
               46:36
                       36.80
                                4.53
                                           trace
                                                       9.22
  Ochotsk,
               47.19
                        33.80
                                4.47
                                           2.58
                                                       8.35
7. Abborf.
               39.45
                         9.27 35.78
                                                8.29
                                                                    F 0.29, Ca 0.32, Fe 145,
                                                       5.06
                                                                   Mn 2.57=90.59, Svanberg
                                                                  -, F 0 35, Er 3 95, Na 0 37,
8. Fuchsite, 47.95 34.45 1.80
                                               0.72 10.75
                                                                      Ca 0.42=100.76, Schal
```

In analyses 2 to 6 the oxygen of the protoxyds, peroxyds, and silica has the ratio 1: 12: 16; or as nearly 1: 12: 16;, which gives for the oxygen ratio for the bases and silica 4: 5, and affords the above formula.

The Abborforss mica (No. 7) gives closely the ratio 2: 9: 12.

Analysis No. 8 has nearly the ratio 1: 9: 12. The formula corresponding would be $(\frac{1}{10} R^3 + \frac{9}{10} R) \bar{S} i^3$.

B.B. fuses with some difficulty to a grayish-yellow blebby glass. easily with borax and salt of phosphorus, leaving with the last a silica skeleton.

The variety composed of scales arranged in plumose forms is called plumose

mica; and that with a diagonal cleavage, prismatic mica.

Mica is one of the constituents of granite, and its associate rocks, gneise, syenite. and mica slate. It also occurs in more recent aggregate rocks; also in imbedded crystals in granular limestone, wacke, trachyte, and basalt. Coarse lamellar aggregations often form the matrix of crystals of topaz, tourmaline, and other mineral species. The Fuchsite is a green mica from Schwarzenstein in the Tyrol.

Siberia affords laminæ of mica, sometimes exceeding a yard in diameter; and other remarkable foreign localities are at Finbo in Sweden, and Skutterud in Norway.

Fine crystallizations of mica occur in granite at Acworth, Grafton, and Alstead N. H., and the plates are at times a yard across and perfectly transparent; also at Paris and Streaked Mountain, Maine. In Massachusetts, at Chesterfield with tour maline and Albite. Barre and South Royalston, in two localities with beryl, and at Mendon and Brimfield; at Chester, Hamden Co., Mass., faint greenish. Agreen variety occurs at Unity, Me., on the estate of James Neal; and prismatic mics at Russell, Mass. In Connecticut, at Monroe of a dusky brown color, having internal hexagonal bands of a darker shade; in brown hexagonal crystal at the Middletown feldapar quarry; at Haddam, pale brownish, with columbite, and also similar a another locality with garnets. Six miles southeast of Warwick, N. Y., crystals and plates sometimes a foot in diameter, in a vein of feldspar; a mile northwest of Edenville in six-sided and rhombic prisms; silvery, near Edenville; in St. Lav rence Co., eight miles from Potsdam, on the road to Pierrepont, mica is found is plates seven inches across; town of Edwards in large prisms, six-sided or rhombic: Greenfield, near Saratoga, in reddish-brown crystals with chrysoberyl; on the

Composition.—(Fe, Mn)³Si³+‡(Fe²Cl³+FeH⁴). Analysis by Hisinger, (Afhand. i**v**, **3**17):

	S i	₽e	₩ n	Æl	HCl	Ħ
1.	35.40	32.60	23.10	0.60		6.50=98.20.
9.	85.85	85.48	23.44		2.91	undetermined, Oa 1:21=98:89.

As part of the iron is in the state of a basic chlorid, the second analysis becomes Si 85.85, Fe 21.81, Mn 21.14, Fe Cl 14.095, Ca 1.210, H and loss 5.895.

In the matrass yields water, and afterwards yellow drops of chlorid of iron. B.B. becomes reddish-brown on charcoal, and emits copious fumes; in a strong heat, fuses to a black slag, which at last becomes a round globule, attractable by the

magnet. With borax, fuses readily, and presents the appearances characteristic of iron and manganese. Dissolves perfectly in concentrated nitric acid.

Pyrosmalite occurs at Nya Kopparberg in Westmannland, and at Bjelkegruvan, one of the iron mines of Nordmark in Wermland, Sweden, where it is associated with calc spar, pyroxene, apophyllite, and magnetic iron. A hexagonal prism, in the museum at Stockholm, is nearly an inch in diameter and one and a quarter inches long, and weighs five and a half ounces.

The name pyrosmalite is derived from the said founces.

The name pyrosmalite is derived from wep, fire, and 'ooun, odor, and alludes to the

odor given off before the blowpipe.

PORTITE. Moneghini and Bechi.

Trimetric. In radiated masses; cleavage very distinct parallel to a rhombic prism of 120°.

H.=5. G.=2.4. Lustre vitreous. Color white. Opaque.

Composition.—Analysis by Bechi, (Am. J. Sci. [2], xiv, 63):

B i	Æì	Ċa	Йg	Ñа	Ŕ	Ĥ
58.12	27.50	176	4.87	0.16	0.10	7.92 = 100.48

If the protoxyds are not an essential part of the compound, the mineral corresponds to the formula Al Si*+2H, like Cimolite.

B.B. intumesces much and affords a milk-white enamel. Dissolves in acids even in the cold and gelatinizes.

From the gabbro rosso in Tuscany. Named after M. Porte of Tuscany.


III. CALAMINE SECTION.

TRITOMITE, Weibye and Berlin, Pogg. lxxix, 299, 1850.

Monometric: tetrahedral, f. 55. Cleavage indistinct. H.=5.5. G.=4.16—4.66. Lustre submetallic, vitreous. Color dull brown. Streak dirty yellowish-gray. Subtranslucent.

Composition. — I Si+2H! Analysis by N. J. Berlin, (loc. cit.), Si 20.13, Al 2.24, Ce 40.86, Ha 15.11, Y 0.46, Ca 5.15, Mg 0.22, Fe 1.88, Na 1.46, Mn, Cu, Sn, W, 4.62, loss by ignition, 7.86=99.44.

The species biotite was shown to be in part, at least, optically biaxial, by Silliman, Jr., and Blake, and this conclusion is confirmed by Senarmont, who takes the ground



Topsham, Maine.

that the species is not rhombohedral. annexed figure by Marignac, represents the rhombohedral aspect of a Vesuvian specimen, probably the same found to be biaxial by Silliman, Jr. Marignac gives the angles R: R= 62° 46′, R: a=99° 40′ (99° 45′ by calculation), a on o=102° 28', a on o'=98° 28', a on o''= 95° 37'.

The mica from Greenwood Furnace, Monroe, N. Y., analyzed by von Kobell, (anal. 4), occurs

in large and very regular rhombic prisms, (some-times 5 or 6 inches across), oblique from an acute edge; and also in tetrahedral pyramids; the faces of the pyramids inclined to the cleavage plane at 113° to 114°; Kobell gives for the angle R: R (faces of the pyramid) 71° to 72°. This is the same mica with that analyzed by Smith and Brush, (anal. 13, 14), as Mr. Brush has assured himself by an examination of von Kobell's specimens at Munich. It is the Rhombenglimmer of Kengott, (Pogg. lxxiii, 661). In composition it is true biotite. The Vesuvian biotite occurs in brilliant crystals, (Merozene). A brownish-green biotite with a waxy structure and soapy feel, (anal. 15), occurs in Putnam Co. N. Y. G.=2.80. One of the "uniaxial" micas of Biot is stated to have come from

ALTERED FORMS.—Rubellan is considered an altered biotite; it occurs in small hexagonal forms, of a red color, in a kind of wacks. Steatite is also a result of the alteration of this species, as in granite at Brünn and Thierscheim. Among the above analyses, several indicate incipient change, by the water and chlorine present. The mica of Putnam Co., N. Y., has even a soapy feel and is inelastic. Mica altered to Magnetite has also been observed in the Tyrol.

LEPIDOLITE. Lithia Mica. Lithion-glimmer. Lithionite, Kob. In part, Zinnwaldite, Haid.

Occurs often in oblique rhombic and hexagonal Trimetric. prisms of 119° to 120°; also in coarsely granular masses consisting of foliated scales. Cleavage: basal, highly eminent.

G.=2.84—3. Lustre pearly. Color rose-red, violet gray, yellowish, whitish. Translucent. Apparent angle of optical axes 70°-78°.

Composition.—According to Rammelsberg, the analyses afford the following for mulas, the fluorine replacing part of the oxygen :-

1. Ural, Chursdorf, Uto, Rozena, Zinnwald (Ramm.), Altenberg (Stein)

$$R\ddot{S}i + R\ddot{S}i = (\frac{1}{4}R^3 + \frac{1}{4}R) \ddot{S}i^{\frac{3}{2}}.$$

- 2. Zinnwald, Rozena, (Ramm. anal. 16), $2 R \vec{S}i + 3 \vec{R} \vec{S}i = nearly (\frac{1}{6} R^2 + \frac{5}{6} \vec{R}) \vec{S}i^{\frac{4}{3}}$.
- 3 RSi+2RSi[=(1R'+1R)Si 3.] 3. Juschakowa, (anal. 19, 20),
- $R^{3}\vec{S}i + 6R\vec{S}i = (\frac{1}{2}R^{3} + \frac{6}{2}R)\vec{S}i.$ 4. Altenberg, (Turner, anal. 11),

Ratio of fluorine to oxygen, in the Ural, Chursdorf, Uto and Rozena micas 1 :20:

Ratio of fluorine to oxygen, in the Ural, Chursdorf, Uto and Rozena micas 1:2; in the Altenberg, (Stein) 1: 80; in the Zinnwald, 1: 14, 1: 11, 1: 12; in the Juschakowa, 1: 8; in Turner's Altenberg 1: 25; in Rammelsberg's Rozena, (anal 16: 1: 12. The last is the prevailing ratio.

Analyses: 1, Klaproth, (Beit. i, ii, v); 2, Gmelin, (loc. cit.); 3, Kralowansky. (Schw. J. liv, 230); 4, 5, Gmelin; 6, Turner, (Edinb. J. Sci. iii, and vi, 61); 7, Klaproth; 8, Lohmeyer, (Pogg. lxi, 377); 9, Stein, (Ramm. 5th, Suppl., 119); 10. Rammelsberg, (ib., 119); 11—15, Turner, (loc. cit.); 16, Rammelsberg, (5th Suppl. 120); 17, 18, Regnault, (Ann. d. Mines, [3], xiii, 151,): 19, 20, Rosales, (Pogg. lviii, 154); 21, Stein, (J. f. pr. Chem. xxviii, 295):

Hermann's specimen was probably impure from mixture with carbonate of lime.

Kjerulf's analyses gives 14H.

In a matrass yields water. B.B. infusible alone; with borax in the outer flame forms a yellow globule, which becomes almost colorless on cooling; in the innerflame a weak iron reaction. With soda not dissolved, but fuses to a dark yellow

delaggy mass. Easily gelatinizes with muriatic acid, when in powder.


Occurs at Bastnäs, near Riddarhyttan, in Westmannland, Sweden, forming a bed in gneiss, and associated with mica, hornblende, copper pyrites, cerine, &c. It bears considerable resemblance to the red granular variety of corundum, but is readily

distinguished by its hardness.


Hermann has named the ore analyzed by Klaproth, Ochroite; but it is supposed. o have been cerite impure with mixed quartz. He deduces for it the formula Ces. Si²+3H=Silica 32.83, protoxyd of cerium 57.58, water 9.59.

CALAMINE, M. Siliceous Oxyd of Zinc. Hydrous Silicate of Zinc, Thom. Zinkglas, Haus. Zinkkieselerz, Berz. Kieselzinkerz, Kieselgalmey. Zinc Oxide Silicifère, H. Galmey, (in part).

 $I: I=103^{\circ} 54', 0: 1\bar{\imath}=148^{\circ} 29\frac{1}{3}';$ Trimetric; hemihedral. a:b:c=0.617:1:1.2776.



Observed Planes: add 11 and 71.



 $O: 2\bar{\imath} = 129^{\circ} 2'$. $i\tilde{2}: i\tilde{2} = 129^{\circ} 25'$. $0:1i=154^{\circ}13'$. $\bar{I}: \tilde{n}=128^{\circ} 3'.$ $O: 3\bar{\imath} = 118^{\circ} \ 23'$. $0:3i=124^{\circ}37'$.

Cleavage: I, perfect, O, in traces. Also stalactitic, mammillated, botryoidal, and fibrous forms; also massive and granular.

H.=4.5-5, the latter when crystallized. G.=3.16-3.9, 3.43 —3:49, from Altenberg. Lustre vitreous, O subpearly, sometimes adamantine. Color white; sometimes blue, green, yellow, or brown. Streak white. Transparent—translucent. Fracture uneven. Brittle. Pyroelectric.

Composition.—Zu²Si+14H—Silica 25·1, oxyd of zinc 67·4, water 7·5. Perhaps in some or all cases, one third more water, or Zu²Si+2H—Silica 24·86, oxyd of zinc 65·45, water 9·69. Analyses: 1, Smithson, (Nicholson's Journ. vi, 78); 2, Berzelius, (K. V. Ac. H. 1819, 141); 3, Berthier, (J. d. Mines, xxviii, 341); 4, Thomson, (Phil. Mag. 1840); 5, 6, Hermann, (J. f. pr. Ch. xxxiii, 98):

5. FELDSPAR SECTION.

Type ratio for oxygen of bases and silica 1:1, and varying from this by the addition of silica to the type. Oxygen ratio for protoxyds and peroxyds 1:3 or 1:4.

L LEUCITE GROUP.-Monometric.

```
Oxygen ratio 1:8:4+ (Na+X1)513[+1Na Cl]
SODALITE.
LAPIS-LAZULI.
                              1:8:4+ (Na+X1)Bi3[+10aB]
HAUYNE.
                              1:3:4+ (\hat{N}_a + \frac{1}{A})\hat{S}_i^{\frac{1}{2}}[+i\hat{N}_a\hat{S}]
NOSBAN.
                                           (於十基1)克ig
LEUCITE.
                              1:8:8
```

II. NEPHELINE GROUP.-Hexagonal.

Nepheline, Oxygen ratio 1:8:41 (Na, K+
$$\frac{1}{4}$$
1)Si³
Canozinite, "1:8:41+ (Na+ $\frac{1}{4}$ 1)Si³[+1(Na, Ca)O]

III. FELDSPAR GROUP.—Triclinic or Monoclinic.

```
(Ċa+<del>X</del>1)Si³
Anorthite, Oxygen ratio 1:8:4
                                                 (Ca, Na+X1)Si^{\frac{3}{3}}
                                  1:8:8
ANDESINE,
                                                  (Oa, Na+\frac{\pi}{4}l)Si^2
                                  1:3:6
LABRADORITE,
                                                  (Na, Ca+XI)Si<sup>3</sup>
                                  1:8:9
OLIGOOLASE,
                                                  (\hat{N}a + \frac{\pi}{4}l)\hat{S}i^4
ALBITE,
                                  1:8:12
                                                 (於十<del>基</del>1)系i*
                                  1:8:12
ORTHOCLASE,
```

IV. PETALITE GROUP.—Oxygen ratio for protoxyds and peroxyds 1:4.

Oxygen ratio 1: 4: 20 $(\frac{1}{K}B^3 + \frac{4}{K}E)$ Si⁴ PETALITE,

[The above formulas are a direct expression of the oxygen ratios, and present to the eye the prominent fact that the species vary in the proportion of silica. They might also be written like the formulas of the Garnet and Augite Sections; thus for Anorthite of the Feldspar group, (1R*+1A) \overline{\overl of the student than formulas like these last.

The species Leucite and Andesine are mutually dimorphous; so also Sodalite and Anorthite; also Orthoclase and Albite; which two species are besides closely homosomorphous. Again, the Anorthite ratio is supposed to recur in Scapolite Through Scapolite the Garnet and Feldspar sections osculate, and through Spokemene and Andesine the Augite and Feldspar sections. Leucite is essentially as

anhydrous analcime.]

Composition.—2 Ĉa®Ŝi+3¾lŜi+Ĥ®Ŝi Berz; or if 3Ĥ acts with Ĉa as base, (‡Ř³+ ‡¾l) Ŝi=Silica 43°8, alumina 24°8, lime 27°1, water 4°3=100. Analyses; 1, 2, Gehlen, (Schw. J. iii, 171); 3, 4, 5, Walmstedt, (Jahresb. v, 217); 6, 7, Thomson and Lehunt, (Min. i, 275); 8, Regnault, (Ann. d. Mines, [3], xiv, 154); 9, Amelung, (Ramm. 2d Supp. 118, Pogg. lxviii, 312); 10, 11, Leonhard, (Pogg. liv, 579); 12, Domeyko, (Ann. d. M. [4], ix, 3).

Fe Ca Si X1 Ħ Tyrol,
 Tyrol, Fassa,
 Mt. Blane, Kouph. 2.00 26.00 4.00, Mn 0.25=98.50, Geh. 43.00 23.25 200 26 00 4 00, Mn 0 25 = 98 35, Geh. 300 26 50 4 62, Mn 0 25 = 98 75, Geh. — 25 41 4 45, Mn 0 19, Fe 1 25 = 100, Walm. 6 81 26 28 4 43, Mn 0 15 = 100 20, Walm. 2 00 22 33 6 40 = 97 33, Thomson. 42.88 21.50 44-71 23-99 4. Dumbarton, 44.10 24.26 5. Edelfors, Edelite, 48.03 19.30 6. Glusgow, green, 43.60 23.00 43 05 23 06 2 26 16 4 60, Mn 0 42, K and Na 1 03, L 44 50 23 44 F 4 61 23 47 4 44=100 46, Regnault. 44 74 18 06 7 38 27 06 4 13, Na 1 03=102 40, Amelung. 42 50 30 50 0 04 22 57 5 00, K 0 02=100 64, Leonhard. 44 00 28 50 0 04 22 29 6 00, K 0 01=100 84, Leonhard. white. 8. Bourg d'Oisans, 9. Radauthal, Hartz, 10. Niederkirchen, pseudomorphs, -- 25.0 5.3, Fe 4.2=99.7, Domeyko. 43.6 21.6

B.B. on charcoal froths and melts to a slag of a light-green color. With borax a transparent bead. In dilute muriatic acid dissolves slowly after heating or fusing, without gelatinizing; before heating not perfectly soluble. Koupholite, which often contains dust or vegetable matter, blackens and emits a burnt odor.

Prehnite was first found at the Cape of Good Hope, by Colonel Prehn, after whom it was named by Werner. Occurs in granite, gneiss, and trap rocks, espe-

cially the last.

At St. Christophe, in Dauphiny, associated with axinite and epidote; at Ratschinges and the Fassa valley, Tyrol; in Salzburg; at Friskie Hall and Campsie in Dumbartonshire, and at Hartfield Moss; in Renfrewshire, in veins traversing trap, associated with analcime and thomsonite; also at Corstorphine Hill, the Castle and

Salisbury Crag, near Edinburgh; at Oisans in Dauphiny.

In the United States, finely crystallized at Farmington, Woodbury, and Middletown, Conn., and West Springfield, Mass., and Patterson and Bergen Hill, N. J.; in small quantities in gneiss, at Bellows Falls, Vt.; in syenite, at Charlestown, Mass., Milk Row quarry, often in minute tabular crystals, with chabazite; also at Palmer (Three River) and Turner's Falls, Mass., on the Connecticut, in greenstone, and at Perry, above Loring's Cove, Maine; on north shore of Lake Superior, between Pigeon Bay and Fond du Lae; in large veins in the Lake Superior copper region, often occurring as the most common veinstone of the native copper, sometimes including strings or leaves of copper; and at times in radiated nodules disseminated through the copper.

Handsome polished slabs of this mineral have been cut from masses from China. The formula (\frac{1}{2}\text{R}^2+\frac{1}{2}\text{Al}) \text{Si} is analogous to that of chrysolite in the ratio 1:1, and the two species appear to be homeomorphous, 2%: 2% in chrysolite=99° 7'.

Altered Forms.—Prehnite occurs altered to Green earth and Feldspar.

CHLORASTROLITE, C. T. Jackson. J. D. Whitney, Bost. J. Nat. Hist. v, 488.

Massive. Finely radiated or stellate in structure.

H.=5.5—6. G.=3.180. Lustre pearly. Color light bluishgreen. Slightly chatoyant on the rounded sides.

Composition.—(Ča, Ňa)° Ši+2 (Xl, ¥e) Ši+3 Ĥ=((†Ř°+‡Xl) Ši+Ĥ=Silica 37 9 alumina 25·1, peroxyd of iron 5·6, lime 18·7, soda 5·2, water 7·5=100.

Analyses by Whitney, (Rep. Geol. L. Sup. 1851, 97):

 Si
 Al Fe, little fe
 Ča
 Na
 K
 H

 1. 36:99
 25:49
 6:48
 10:90
 3:70
 0:40
 7:22=100:18.

 2. 37:41
 24:25
 6:26
 21:68
 4:88
 5:77=100:25.

Lapis Lazuli fuses to a white glass, and if calcined and reduced to powder, loses its color, and gelatinizes in muriatic acid; with borax it effervesces, and forms a colorless glass.

It is usually found in granite or crystalline limestones. It is brought from Perus, China, Siberia, and Bucharia; the specimens often contain scales of mica and disaminated pyrites. On the banks of the Indus, it occurs disseminated in a grayish limestone

The richly colored varieties of Lapis Lazuli are highly esteemed for costly vases and ornamental furniture; also employed in the manufacture of mosaics; and when powdered constitutes the rich and durable paint called *Ultramarine*. An artificial ultramarine equal to the native in color and permanency, and now extensively used in the arts, contains according to Varrentrapp,

Si 45-604, S 3-830, £1 28-804, Ĉa 0-021, Na 21-476, K 1-752, S 1-685, Fe 1-063, Cl trace=98.785.

A mineral from the Andes, occurring in large masses of a bright blue color with veins of carbonate of lime is referred to Lapis Lazuli by Mr. F. Field. He obtained (Quart. J. Chem. Soc. iv, 381), Si 87.60, £1 11.21, S 1.65, Fe 0.08, Mg 0.36, Na 9.66, O 15.05, Ca 24.10=99.71.

· HAUYNE. Auina, Monticelli. Berzelin, Necker. Marialite, Ryllo.

Monometric. In dodecahedrons, (f. 14, 16, 18, 43). dodecahedral, sometimes distinct. Commonly in crystalline grains. H.=5.5. G.=2.4-2.5.Lustre vitreous to greasy. bright blue, occasionally asparagus-green. Streak bluish-white. Subtransparent to translucent. Fracture flat-conchoidal—uneven.

Composition.—Na'Si+3XISi+2CaS=(Na+XI) Si4+1CaS, from Whitney's analysis of Haüyne of Mt. Albano=Silica 32.1, alumina 27.3, lime 9.9, soda 16.5, sulphuric acid 14-21. Analyses: 1, Gmelin, (Schw. J. xiv, 325, xv, 1); 2, Varrentrapp, (Pogg. xlix, 515); 3-5, J. D. Whitney, (Pogg. lxx, 431):

- 8 Χì 8i Ċa \$5.48 12.39 78.87 12.00 15.55 -. Fe1·16,HS and loss 3·45,G. 1. Marino, 9·12, Fe 0·17, Cl 0·58, S 0·24, H 2. Niederm'g, 35-01 12-60 27-41 12-55 6.2=98.84, Varrentrapp. 7.50 28-07 88.90 12.01
- 12.18 84.88 28.51 7.23 5. Mt. Albano, 82.44 12.98 27.75 2.40 14.24=99.77, Whitney. 9.96

The Hauyne from Niedermendig gives the formula, according to Whitney, $\hat{N}a^{3}\hat{S}i + 8\hat{A}\hat{S}i + \hat{N}a\hat{S}, 2(\hat{N}a^{3}\hat{S}i + 8\hat{A}\hat{S}i + 2\hat{O}a\hat{S}),$

corresponding to a compound of 1 Noscan and 2 of the Albano Hauyne.

B.B. Hauyne decrepitates and fuses slowly to an opaque white or greenish-blue blebby glass. With borax effervesces and forms a glass which is yellow on cooling. Gelatinizes with muriatic acid.

Hauyne occurs in the Vesuvian lavas, on Somma; in basalt at Niedermendig, near Andernach on the Rhine.

NOSEAN. Nosin. Spinellane. Hauyne, in part.

Monometric, like Haüyne; in dodecahedrons. Often granular massive.

G = 2.25 - 2.3H.=5.5.Color grayish, bluish, brownish; sometimes black. Translucent to nearly opaque.

Composition.—Na°Si+3XiSi+NaS=(Na+Xi) Si3[+iNaS=Silica 86°3, sulphuric acid 8°0, alumina 30°9, soda 24°8=100. Analyses: 1, 2, Bergmann, (Bullet. des Sci. 1823, iii, 406); 3, Varrentrapp, (Pogg. xlix, 515); 4, 5, J. D. Whitney, (Pogg. lxx, 515); 4, J. D. Whitney, (Pogg. lxx, 515); 4, J. D. Whitney, (Pogg. lxx, 515); 4, J. D. Whitn 431):

IV. ZEOLITE SECTION.

I. ANALCIME GROUP. Monometric.

Oxygen ratio. R H Si H 1:8:8:2

Analcine,
Pioranalcine,

GLOTTALITE,

ITTNERITE, 1:8:4:2

II. CHABAZITE GROUP. Hexagonal.

CHABAZITE, 1:3:8:6 (or 5)

" 1:3:9:6

GMELINITE, 1:3:6:4

III. GISMONDINE GROUP. Dimetric.

Gismondine, $1:3:4\frac{1}{2}:4\frac{1}{2}$

Edingtonite,

FAUJASITE, 1:8:9:9

IV. THOMSONITE GROUP. Trimetric; I: I=90°-92°. Rarely monoclinic, d homocomorphous with the trimetric species. No perfect cleavage.

HARMOTOME, 1:8:9:5
PHILLIPSITE, 1:8:9:5
THOMSONITE, 1:8:4:21
NATROLITE, 1:8:6:2
SCOLECITE, 1:8:6:8
SLOANITE, 1:6:8:4(f)

V. STILBITE GROUP. Monoclinic or trimetric, with a pearly diagonal cleaves: $I: I=130^{\circ}-138^{\circ}$.

Epistilbite, 1:8:9:5

Heulandite, 1:8:12:5

Brewsterite, 1:3:12:5

Stilbite, 1:8:9:6

Caporgianite, 1:8:8:8

The Leucitic lava of the neighborhood of Rome has been used for the last two thousand years at least, in the formation of mill-stones. Mill-stones of this rock have lately been discovered in the excavations at Pompeii.

Named from howes, white, in allusion to its color; and because its form is similar to a common variety of garnet, it has been designated white pernet.

ALTERED FORMS.—Feldspar and Kaolin occur with the form of Leucite, as a result of its alteration. Leucite changed to glassy feldspar has been observed at Mt. Somma by Scaechi.

Bernzeline, Neckar. Occurs in octahedrons and cubo-octahedrons, and in twins like £ 200; faces often uneven or rounded. Cleavage: cubic, tolerably perfect. Also massive. Colorless, gray, white, vitreous; H.=S. G.=2727—2428, Graelin. B.B. fuses with difficulty to a blebby glass; with borax a clear glass. In marriatic seid soluble, and heated forms a jelly. Said to be near leucite in composition.

Occurs in peperino at Mt. Albano and Marino, near Rome.

MEPHELINE, H. Sommite, P. Nefelina, Monticelli. Cavolinite, Mont. Davyne, Mont. Beudanite, Covelli. Pseudo-nephelin. Elssolite. Fettstein, W. Pierre

the form 42, and prisms, I, i2, i3. $O: 42=120^{\circ} 54'$, $I: i3=160^{\circ}$ 53'. Cleavage: I distinct, O imperfect. Also massive, compact; also thin columnar.

H.=5.5-6. G.=2.5-2.64, Nepheline and Elæolite. Lustre vitreous-greasy; little opalescent in some varieties. white or yellowish; also when massive, dark green, greenish or bluish-gray, brownish and brick-red. Transparent—opaque. Fracture subconchoidal.

Nepheline includes the crystallized varieties from Vesuvius; Electite the coarse massive varieties having a greasy lustre.

Composition.—(Ña, K)² Si+2 Āl Si—(Ña, K+Āl)Si⁴ —(if Ña: K=5: 1) Silica 44·4, alumina 33·6, soda 16·9, potash 5·1=100.

Analyses: 1, Arfvedson, (Jahresb. ii, 97); 2, 3, 4, Scheerer, (Pogg. xlvi, 291, xlix, 359); 5, Gmelin, (Neph. im Dolerit, &c., Heidelberg, 1822); 6, Heidefreim, (J. f. pr. Chem. l, 500); 7, Monticelli and Covelli, (Prod. min. Vesuv. 375, and Pogg. xi, 470); 8, 9, 10, Scheerer, (Pogg. xlvi, 291, xlix, 359); 11, 12, Bromeis, (Pogg. xlviii, 577); 18, Smith and Brush, (Am. J. Sci., [2], xvi, 371):

L. Nepheline.

			Bi ⊼ l	æe	Ca	Na	ĸ	Ĥ	
1.	Vesuvius,	- 44	·11 887			20.46		0.62=98.92, Arfved	
2	44	44	08 83-2	8 0.65	• 177	15.44	4.94	0.21=100.32 Schoot	
8.	44	44	29 83-0	4 0.89	* 1·82	14.98	472	0.51=99.40 "	
4.	Odenwald,	48	70 828	1 1.07	0.84	15.83	5.60	1.39=100.74 "	
5.	44	48	*86 88.4	9 1.50	0.90	18.86	7.18	1:39=101:19 Claustin	
6.	Löbau,	48	·50 82 ·3	8 1.42	8.55	14.18	5 08	0.82, Mg 0.11=100.39,	
7.	Davyne,	42	91 88-2				7· 4 8	—=96·89, M. & C.	
	* With ₩n.								

GLOTTALITE, Thomson. Monometric; cube with angles truncated. Vitreous. Colorless or white. H.=3-4. G.=2·18. Composition.—3Ca³Si²+Xl³Si²+24H. Analysis: Si 87·01, Al 16·31, Fe 0·50, Ca 23·93, H 21·25=99. From greenstone near Port Glasgow on the Clyde in Scotland.

ITTNERITE.

Monometric. Cleavage dodecahedral. Occurs granularly massive.

H.=5.5. G.=2.37-2.40. Color dark bluish or ash-gray, smoky gray. Lustre resinous. Translucent. Fracture imperfectly conchoidal.

Composition.—Essentially (Na, Ca)*Si+3\(\frac{1}{4}\)\(\frac{1}{6}\)\(\frac{1}{4}\)\(\frac{1}{6}\)\(\frac{1}{4}\)\(\frac{1}{6}\)\(\frac{1}{4}\)\(\frac{1}{6} (Pogg. lxx, 442):

Si S Xl Ca Na K 1. 84·02 2·86 28·40 7·27 12·15 1·56, Fe 0·62, HCl 0·75, H and HS 10·76—98·36, G. 2. 35.69 4.62 29.14 5.64 12.57 1.20, Cl 1.25, H (loss) 9.83=100, Whitney.


Yields much water in a matrass, in which it differs from the allied species. B.B. fuses easily with strong intumescence and evolution of sulphurous acid to a blebby opaque glass. A clear glass with borax. Gelatinizes perfectly in acids.

From the dolerite of the Kaiserstuhl near Freiberg; at Sasbach in basaltic dole-

rite; at Endingen in phonolitic dolerite, with pyrites, titanic iron, and apatite.

CHABAZITE. Chabasie, P. L. and H. Schabasite, W. Chabasin, Haid. Levyne. Mesolin. Hydrolite, De Dree. Sarcolite, Vaug. Phacolite, Breit. Ledererite, Jackson. Acadiolite, Alger and Jackson. Haydenite, Cleveland.

Rhombohedral; $R: R=94^{\circ}46', O: R=129^{\circ}15'; a=1.06$. Usual forms rhombohedrons. Observed planes as in f. 474, 475, with 3° replacing the edges $R: -\frac{1}{2}$. $R: -\frac{1}{2} = 137^{\circ} 23', -\frac{1}{3}: -\frac{1}{2} = 125^{\circ} 13';$



 $R: -\frac{1}{2}$ (over -2)=83° 31°, $R: -2=119^{\circ}$ 42', $R: \frac{3}{2}2=155^{\circ}$ 15'. Twins: Composition parallel with O; also parallel to R. Cleavage rhombohedral, rather indistinct.

H.=4-4.5. G.=2.08-2.17, Tamnau. Lustre vitreous. Color white, flesh-red; streak uncolored. Transparent—translucent. Fracture uneven. Brittle.

```
Ċ۵
                                               5.
                        Z;
                                                                          =100-27, G. Rose.
                                       7:16 17:36
                                                             6:38
L Ural,
                       40-59
                               28-29
                                                      ₩57
                                                                   282, En, Fe 086=
                       40-26
                               28 34
                                       6-54
                                              17.66
                                                      0-33
                                                             6:38
3. Litchfield, yellow, 37:42 27:70
                                      3-91
                                                      0-67
                                                             5-95
                                                                            100.31, Whit.
            greenish, 37-20 27-59 5-26 20:46 0-50 5-92 3-28, Min, Pe 0-27, V

1 Mts. 38-33 28-55 4-24 20-37 — (C&H) 8-51=100, v. Str.
                                                                           In, Pe 0-27, W.
5. Turkinsk Mts.
```

Whitney found a trace of chlorine in his analyses. The red color of the Miask cancrinite is due to disseminated grains of specular iron, according to Kengott, who also found calcite in microscopic grains, and suggests that this may be the source of the carbonic acid of cancrinite.


B.B. loses color and fuses easily with intumescence to a white blebby glass. Ef-


fervesces with muriatic acid and forms a jelly on heating, but not before.

Cancrinite is found at Miask in the Urals; also of citron-yellow color in the Turkinsk Mts., 400 wersts west of Irkutsk, in a coarse granite with zircon, calcite and magnetite; and also in crystals and massive at Litchfield, Maine, with sodslite and zircon.

ANORTHITE, Rose, 1828. Amphodelite, Nord. Latrobite, Brooke. Indianite, Bour. Christianite, Mont. Biotina, Mont. Diploite, Nord. Linseite, Komonen. Thiorsauite, Genth.

Triclinic. $O: \tilde{n}=85^{\circ} 48', O: I=114^{\circ} 22', O: I=110^{\circ} 57'.$ $O: \frac{2}{4}i = 145^{\circ} 12'$. $O: 42' = 98^{\circ} 37'$. $0:2i=133^{\circ}13'$. $O: 1=121^{\circ} 50'$. $\tilde{n}: I'=122^{\circ} 2'$. $0:2i'=137^{\circ}22'.$ 0:1i (adj.)=128° 27′. $0:1'=125^{\circ}38'$. $\tilde{n}:I=117^{\circ}28'$. $O: 2i \text{ (ov. } 1i) = 98^{\circ} 29'. \quad O: 2 = 94^{\circ} 53'.$ $I: I'=120^{\circ} 30'$. (Angles from Brooke and Miller). 411





Cleavage parallel with O and it perfect. Structure often granular, columnar, or coarse lamellar.

H.=6-7. G.=2.66-2.78; 2.762, (massive), Rose; 2.763, Amphodelite; 2.668, Indianite, Silliman. Lustre of cleavage planes GMELINITE, Brooke. Soda Chabazite. Natron-Chabasit. Hydrolite. Herschelite, Levy.

Hexagonal. Observed planes as in the figure, with sometimes

the pyramidal and prismatic edges truncated; 1:1 (pyram.) 142° 26'; (basal)=80° 8', Brewster, 80° 54', G. Rose, 80° 6', Dufrénoy, 79° 44', Breithaupt, 80° 8', Brooke and Miller. 0: 1=139°56', 0: 12=143° 56'. Cleavage: parallel to the faces of a 6-sided prism, perfect, G. Rose, (Kryst. Chem. Min., 1852, 100).

H.=4.5. G.=2.04—2.12. Lustre vitreous. Colorless, yellow-



ish-white, reddish-white, flesh-red, translucent. Brittle.

Composition .- Like that of chabasite, the compound therefore being dimorphous,

according to G. Rose. The Herschelite affords the same excepting 15 H.

Analyses: 1, Connell, (Edinb. New Phil. J. 1838); 2, 3, Rammelsberg, (Pogg. xlix,
211); 4, 5, Damour, (Ann. Ch. Phys. [3], xiv, 99); 6, Waltershausen, (Vulk. Gest. 261):

Al Ca Na K Ĥ 48.56 18.05 5.13 3.85 0.39 21.66, Fe 0.11=98.75, Connell. 1. Glenarm, 46.40 21.09 3.67 7.29 1.60 20.41=100.47, Rammelsberg. 46.56 20.19 3.89 7.09 1.87 29.41=100.02, Rammelsberg. Herschelite, Etna, 47.39 20.90 0.38 8.33 4.39 17.84=99.23, Damour. " 4746 20:18 0:25 9:35 4:17 17:65—99:06, Damour.
" 46:46 19:21 4:75 5:27 2:88 17:86, Mg 0:42, Fe 1:14—97:99, W.

B.B. like chabasite. Gelatinizes with muriatic acid. Waltershausen found a trace of phosphoric acid and supposed it combined with the Fe. Occurs in amygdaloidal rocks at Montecchio Maggiore, and at Castel in the Vicentine, at Glenarm, and the Island Magee.

and the Island Magee.

Gmelinite is usually considered rhombohedral, and the crystals as twins, secondary to a rhombohedron of 86° 18′. Tamnau makes R: R as in chabasite, and the pyramidal faces the form ½? The hexagonal cleavage observed by Rose separates it widely from chabasite. It was named after Prof. C. Gmelin, of Tübingen.

Herschelite is from Aci Castello, Etna, Sicily, along with Phillipsite. The crystals are colorless hexagonal prisms and tables, and are generally aggregated like those of Prehnite; bases convex with traces of a flat rhombohedron. Damour's analyses give (Na, K)² Si²+3¾l Si²+15¾, making it a distinct compound from the above. The angles of the pyramidal edges are 124° 45′, and the base makes with the pyramidal faces 132° nearly. H.=5·5. G.=2·06.

Ledererite of Jackson, from Cape Blomidon, Nova Scotia, has the form of Gmelinite. It has the same formula with one third the amount of water. Analysis by Hayes: Si 49·47, ¾l 21·48, Ča 11·48, Ña 3·94, № 0·14, Ħ 8·58, P 3·48=98·57, (Am. J. Sci., xxv, 78). G.=2·169. Named after Baron Lederer, formerly Austrian Consul at New York.

LEVYNE, Brewster.

Rhombohedral: $R: R=106^{\circ}4'; O: R=136^{\circ}1'; a=0.83583.$ Observed planes as in the annexed figure, with also -3; 2:2=79° 29', 0:3=109° 3', O: 2=117° 23'. Cleavage, R, indistinct. Twins compounded parallel to O. Crystals often striated; often in druses.

H.=4-4.5. G.=2.09-2.16. Lustre

Bi 45.80, ±1 26.15, Ca 16.25, Mg 2.95, Fe 4.70, Loss by ignition 2.00=97.85. Rosile or Rosellan, (Svanberg, K. V. Ac. H., 1840, Pogg. liv, 268, and lvii, 170, and Polyargite, Svanberg), is stated by G. Rose, (Kryst. Chem. 89), to be altered anorthite.

Latrobite, Brooke, (Diploite, Breit.), is referred to anorthite by Hermann and others. It is pale rose-red and closely resembles the Amphodelite. It is from Amitok island, coast of Labrador, where it is found with feldspar, mica, and calcita

ANDESINE, Abick, Berz Jahresb. i, 167. Pseudoalbit.

Triclinic. Like albite in crystalline forms and twins; but distinct in cleavage, and surfaces of cleavage more uneven and edges

ss sharp. Also fine granular. H.=6. G.=2.65—2.74; from the Andes, 2.7328: of Saccharite, 2.668; from the Vosges, 2.65—2.68; 2.668, Canada, Hunt Color white, gray, greenish, yellowish, flesh-red. Lustre subvitreous, inclining to pearly.

Composition.—R*Si+3KiSi*—(Ca, Na+Ki)Si\$ Analyses: 1, Abich, (Pogg. li, 523); 2, 3, 4, Delesse, (Mem. Soc. d'Emulation du Doube); 5, Schmidt, (Pogg. lxi, 285); 6, Waltershausen, (Vulk. Gest., 24); 7, 8, Rammelsberg, (5th Suppl., 48); 9, T. S. Hunt, (private communication):

		Bi	Χì	₽e	Ĉa.	Ĥg	ĸ	Ña
1.	Andes,	59.60	24 ·18	1.28	5-77	1.08	1.08	6·58==99·92, Abich.
2.	Vonges, white,	58.92	25.05		5.64	0.41	2.06	7-20, H 1-27=99-55, D.
8.	" red,	58.91	24.59	0.99	4.01	0.89	2.54	7.59, " 0.98=100, D.
4.	Chagey,	29.92	24.18	1.05	5.65	0.74	0.81	5·89, " 2·28=100, D.
5.	Baocharite,	58.98	28.20	1.27	5.67	0.26	0.02	7·42, Ni 0·39, H 3·21=
								100, 8.
6.	Iceland, crystals,	60.58	28.75	8.51	6.58	0.64	0.87	5.70=100.75, Walt.
7.	Marmato,	60.26	25.01	tr.	6.87	0.14	0.84	7.74=100.86, Ramm.
8.	"	58.32	26.52	tr.	8.18	0.11	2.86	5.27 ign0.60=101.36,R.
9.	Canada,	28.80	25.89	0.60	7.78	0.11	1.00	5·14=99·82, Hunt.

Other analyses: Delesse, (Ann. d. M. [5], iii, 374, Vosges).

Andesine fuses in thin splinters before the blowpipe. Saccharite melts only on thin edges; with borax forms a clear glass. Imperfectly soluble in acids.

Andesine occurs in the Andes, at Marmato, in the rock called Andesite, a whitish syenite; also in the syenite of Alsace in the Vosges. G.—2-683, white of Servanes; 2.651, red of Coravillers; and also in the porphyry near Chagey, Haute Saône; G. =2.786; at Vapnefiord, Iceland, in honey-yellow transparent crystals, (anal. 6, G. =2.65). Saccharite is a granular mineral, having traces of cleavage in one direction, occurring in veins in serpentine at the chrysoprase mines near Frankenstein, in Silesia. In North America, found at Chateau Richer, Canada, (anal. 9), forming with hypersthene and ilmenite a wide spread rock; color flesh-red; G.=2.668.

BARSOWITE, G. Rose, Pogg. xlviii, 567, 1889.

Massive of a granular texture, with a nearly perfect cleavage in one direction. H.—5.5—6. G.—2.74—2.752. Lustre more or less pearly. Color anow-white, subtranslucent. Fracture granular or splintery.


Composition.—Ca Bi +8 Al Bi=(Ca+Al) Bi =Silica 48.8, alumina 33.2 line 18.0. Analyses by Varrentrapp, (Pogg. xlviii, 568):

	Bi	Æì	Ôa.	Úg
1.	49.01	88 85	15 ·46	1.55=99.87.
2.	49.05	88-78	15.80	1.42=98.56.
8.	48.07	84-06	15.10	1.65==96.90.

EDINGTONITE, Haid. Brewster's Edinburg Jour. Sci. iii, 316. Antiedrit, Breit.

Dimetric; hemihedral. $0:1i=145^{\circ}$ 59'; a=0.67473. Observed planes as in the annexed figure. $0:1=136^{\circ}20\frac{1}{2}'$, $I:1=133^{\circ}39\frac{1}{2}'$, $I:\frac{1}{2}=115^{\circ}26'$, 1:1, over summit, $92^{\circ}41'$, $\frac{1}{2}:\frac{1}{2}$ ib. $129^{\circ}8'$. Cleavage: I perfect.

H.=4-4.5. G.=2.7-2.75. Lustre vitreous. Grayish-white. Streak uncolored. Translucent. Brittle.



Composition.—3Ba Si+4\(\frac{1}{4}\) Si+12\(\text{H}\). Analysis by Mr. Heddle, (Greg and Lettsom's Brit. Min.):

Si 37.263, #1 23.751, Ba 26.514, H 12.462=100.

At a high heat, before the blowpipe, it fuses to a colorless mass, having first given off water, and become white and opaque.

Edingtonite occurs in small crystals, with datholite in the Kilpatrick hills.

FAUJASITE, Damour.

Dimetric. $0:1i=127^{\circ}15'; a=1.315$. In octahedrons; 1i:1i (pyr.)=111° 30′, (bas.)=105° 30.′

H.=5. G.=1.923. Colorless—brown. Fracture vitreous and uneven.

Composition.—RSi+Al Si2+9H=(R+Al)Si2+9H=Silica 46, alumina 17, lime 5, soda 5, water 27.

Analysis by Damour, (Ann. des Mines, [4], xiv, 67):

Si 46·12, Al 16·81, Ca 4·79, Na 5·09, H 27·02=99·83.

In a matrass yields water. B.B. intumesces and fuses to a white blebby enamel. Soluble in muriatic acid.

Occurs with black augite in mandelstein at Kaiserstuhl in Baden. It was named

by Damour, in honor of Faujas de Saint Fond.

From the above dimensions, $O: 1=118^{\circ}$ 16', which is near a corresponding angle in apophyllite, etc.; also as near O: 2 in Zircon, Rutile, etc., or O: 4i in Scapolite and Mellilite.

HARMOTOME, H. Baryt-Harmotome. Staurolite, Kirwan. Andreolite. Andreasbergolite. Kreuzstein, W. Morvenite, Thom.

Trimetric: $I: I=91^{\circ}$ 46', $O: 1\bar{\imath}=144^{\circ}$ 24'; a:b:c=0.716:1: 1.031. Observed planes as in figures, with also 14, 1 and 14.

 $O: 1=135^{\circ} 4'$. $O: 2\%=125^{\circ} 45'$. $1\%: 1\% \text{ (top)}=110^{\circ} 26'$. $O: \%=90^{\circ}$. $1: 1 \text{ (mac.)}=121^{\circ} 6'$. $2\%: 2\% \text{ (top)}=71^{\circ} 30'$.

0: 11=145° 13'. 1:1 (brach.)=119° 4'. 14: 14 (brach.)=163° 16'.

Cleavage: in and in imperfect, the latter a little the most distinct. Twins: (fig. 481), composed of four individuals, face of composition I; common. Rarely massive.

```
₽e
                                                                  Мg
                              Æl
                       $i
                                              Ċa Na
                                                          179
 5. Dalarne,
                     52.15
                             26.82 1.29
                                              9.14 4.64
                                                                 1 02, ign. 1 75=98 60, Sv.
 6. Faroe,
                     52.52
                             80.08
                                     1.72
                                             12.58 4.51
                                                                  0·19=101·55, F.
 7. Egersund,
                     52·30
                             29.00
                                     1.95
                                             11.69 4.01
                                                           0.50 0.15=99.60, Karst.
                                                           0.60 0.16=99.66, Karst.
0.47 1.35=99.21, Schlieper.
                             29.85
                                     1.00
                                             11.70 3.90
                     52.45
 9. Maui, Pacific,
                     53.98
                                             8.65 6.06
                             27.56
                                     1.14
                                                                    -, H 1 07=99 88, Nor.
10. Scolexerose,
                     54.13
                             29.23
                                             15.45
                                                                     -, Fe 4·0, H 0·6=100·2,
11. Silicite,
                             28.4
                                             12.4
                     54.8
                                                                                   Thomson.
12. Greece,
                     53.20
                             27.31
                                      1.03
                                              8.02 3.52 3.40 1.01, H2.51=100.63, D.
                                                                0.93, " 0.95=100, Del
— H.0.4=99.35, H.
13. Tyrol,
                     53.23
                             27.73
                                                     7.38
                                      1.20
                                              8.28
                                            11 42 2 44 0 33, — H 0 4=99 35, H.
11 25 3 80 Mg 0 15, ign. 0 4=100, H.
14. Drummond, C. 54.70
                             29.80
                                     0.36
15. Morin,
                     54.20
                             29.10
                                      1.10
                                             11.69 4.00 0.54 "0.52, ign. 0.95=100.48,
Waltershausen.
16. Etna, Cryst.
                      53.56
                              25.82
                                      3.41
                                            10·49 3·52 0·83 " 0·74=100·35, Walt.
9·58 1·25 7·53 " 0·47, H 0·62=101·25,
      **
                     55.83
                             25.31
                                      3.64
18. Labrador.
                     53.75 27.06 0.99
                                                                             Waltershausen.
```

No. 7, brown massive variety; 8, with blue opalescence; 9, glassy colorless crystals; 14, from a boulder.

G. of 6, 2:68; 7, 2:71; 8, 2:72; 11, 2:666; 14, 2:697; 15, 2:69; 16, 2:618; 17, 2:633; 18, 2:646. Other analyses: Delesse, (Ann. d. M. [4], xvi, 239, 324, 342, 512); Damour, (Bull. G. Soc. de Fr., [2], vii, 88); Metzger, (Leonh. Jahrb. f. Min. 1850, 683); Deville, (Et. Geol. 1848). See also Ramm., 5th Suppl., 155.

B.B. on charcoal, acts like feldspar, and fuses with a little less difficulty to a colorless glass. With oxyd of nickel and borax affords a blue pearl. When pulverized, entirely dissolved by heated muriatic acid, which does not attack either feldspar or albite.

Labradorite is a constituent of some lavas, as those of Etna and Vesuvius; of many porphyries, as the oriental verd antique of Greece, (analysis 12), and other varieties; of dolerite; certain hornblende rocks, granites, and syenites; of some porphyritic greenstones, as at Campsie, Scotland; of melaphyres, as in the Tyrol, (analysis 13). On the coast of Labrador, whence it was originally brought, it is associated with hornblende, hypersthene, and magnetic iron ore. It has been found in place at Mille Isles, Canada, also in Morin, Abercrombie and elsewhere. It occurs abundantly at Essex Co., N. Y. Large boulders are met with in the towns of Moriah, Newcomb, M'Intyre, Westport, and Lewis, N. Y.; also occasionally in Orange, Lewis, St. Lawrence, Warren, Scoharie, and Green counties. In Pennsylvania, at Mineral Hill, Chester Co., and opposite New Hope, Bucks Co.

The Scolexerose and Anhydrous Scolecite are from Pargas, Finland; the Silicite is from Antrim, Ireland. Scolexerose has been referred to scapolite.

Labradorite receives a fine polish, and owing to the chatoyant reflections, the specimens are often highly beautiful. It is sometimes used in jewelry.

Vosgite of Delesse (Ann. d. M. [4], xii, 284) appears to be a Labradorite rendered hydrous by partial alteration, as stated by Rammelsberg. Color whitish, with sometimes a shade of green or blue; lustre greasy or pearly. G.=2.771. Analysis by Delesse, (loc. cit.), \$\overline{Si}\$ 49.32, \$\overline{A}\$1 30.07, \$\overline{F}\$e 0.70, \$\overline{M}\$n 0.60, \$\overline{C}\$a 4.25, \$\overline{M}\$g 1.96. Na 4.85, \$\overline{K}\$ 4.45, \$\overline{H}\$ 3.15=99.35. Delesse deduces the oxygen ratio 1: 3: 5, but by adding the water to the bases; excluding the water, it gives 0.96: 3\overline{\overline{A}}: 6. It constitutes the porphyry of Ternuay, in the Vosges.

Composition.—(Ca, K) Si+\(\frac{1}{4}\)Si^2+5\(\hat{H}\), G. Rose=(\hat{R}+\(\frac{1}{4}\))Si^2+5\(\hat{H}=\)Silica 51.3, alumina 19.4, lime 6.4, potash 5.9, water 17.0=100; or R'Si^2+3\(\hat{A}\)Si^2+12\(\hat{H}=\)Silica 50.2, alumina 21.3, lime 7.0, potash 6.5, water 15.0=100; or the last with 15\(\hat{H}=\) Silica 48.4, alumina 20.6, lime 6.7, potash 6.3, water 18.0=100.

Analyses: 1, 2, Gmelin, (Leonh. Zeits. f. Min. 1825); 3, 4, Köhler, (Pogg. xxxvii); 5, Connel, (Edinb. Phil. J. xxxv, 1843, 375); 6, Marignae, (Ann. Ch. Phys. [3], xiv, 41); 7, 8, Damour, (Ann. d. M. [4], ix, 336); 9, Genth, (Ann. Ch. Pharm. lxvi, 272); 10, 11, Waltershausen, (Vulk. Gest. 263):

Si Hl Ca Fe H 48.51 21.76 6.26 6.33 48.02 22.61 6.56 7.50 0.99 17.23=100.38, Gmelin. 0.18 16.75=100.62, " 1. Marburg, - 16·82=99·49, Köhler. 50.45 21.78 6.50 3.95 48-22 23-33 7-22 3-89 --- 17.55=100.22, 5. G. Causeway, 47.35 21.80 4.85 5.55 Na 3.70 16.96=100.21, Connel. G. 2.17. — 15.05=100.35, Marignae, — 15.60=100.73, Damour. 6- Vesuvius, 48.64 24.89 6.92 10.85 48.41 22.04 8.49 6.19 7. Iceland, 48·53 19·88 2·92 3·82 " 6·18 14·76, "2·64, Mg1·60=100·34, W. 48·37 21·07 3·24 6·15 " 3·41 14·54, "0·71, " 1·42=98·91, W. 9. Marburg, 10. Aci Castello, 11. Palagonia,

a Probably as phosphate.

B.B. intumesces somewhat, and fuses like other zeolites. Pulverized, dissolves very easily in muriatic acid and gelatinizes.

In large translucent crystals in amygdaloid, in the Giant's Causeway in Ireland, and in sheaf-like aggregations at Capo di Bove, near Rome; also in long crystals in radiating masses, at Aci Castello and elsewhere; among the Vesuvian lavas; at Stempel, near Marburg; Habichtswalde near Cassel; Annerode near Giessen; in Iceland. Named after the English mineralogist, J. Phillips.

The name Christianite was given by Descloizeaux to the Marburg harmotome and crystals from an amygdaloid in Iceland.

To phillipsite, Brooke has referred the zeagonite and gismondine, from Capo di Bove near Rome.

OMSONITE, Brooke. Mesotype, (in part), Hawy. Needle Zeolite, (in part), Werner. Comptonite, Brewster. Chalilite, Thom. Triploklas, Br. Ozarkite, THOMSONITE, Brooke. Shepard.

Trimetric. $I: I=90^{\circ} 40'; O: 1\bar{\imath}=144^{\circ} 9';$ a: b: c=0.7225: 1: 1.0117. Observed planes, as in the annexed figure. $0:2i=125^{\circ}$, ii:I=134° 40'. Cleavage: ii and ii easily obtained. Also columnar, structure radiated; also amorphous.

H.=5-5.5. G.=2.35-2.4; 2.35-2.38, Comptonite, Zippe. Vitreous, inclining to pearly. Snow-white: impure varieties brown. Streak Transparent—translucent. uncolored.

ture uneven. Brittle.



Composition.—(Ca, Na) Si+3 KlSi+7H, (6H, Waltershausen)=Silica 37.4, alumina

21.8, lime 18.0, soda 4.8, water 13.0.

Analyses: 1, Berzelius, (Jahresb. ii, 96); 2, Rammelsberg, (J. pr. Chem. lix, 349); 3, Retzius, (Jahresb. iv, 154); 4, Zippe, (Verh. Ges. Mus. Böhm., v. 1836, 39); 5, 6, Rammelsberg, (Pogg. xlvi, 288); 7, Melly, (Bib. Univ. N. S. xv, 193); 8, Rammelsberg, (J. f. pr. Chem. lix, 348, mean of results); 9, 10, Smith and Brush, (Am. J. Sci. [2], xvi, 50); 11, 12, Walterhausen, (Vulk. Gest. 272, 277);

1-21,ign,1-70=98-68,D. 3-08=,Mn0-40=100,K 68-88 22-27 0.21 8·45 tra. 6-66 18. Visembach, 9.48 61.96 22-66 0.82 2-02 0.10 19. Boden. 20. Unionville, Pa., 64.27 21.21 0.81 0.58 10.94 1.36, ign.1.06=100.26, tra 8. & B. 21. Schaitansk, Ural, 64.25 22.24 0.54 2.57 1.14 7.98 1.06=99.76, Bode 9-72 0-55, ign. 0-26---99-94 22. Danbury, Ct. 68.76 22.56 tra. 8.09 tra. 28. Haddam, Ct. 64.26 21.90 2.15 tra. 9.99 0.50 ign. 0-29, S. & B. 24. Borodin, Finland, 68:20 18:41 0:20 0:11 0:87 0:52 14:41 "0:57=98:29, W. G. of No. 7, 2-68; 8, 2-651; 9, 2-656; 10, 2-65; 11, 2-681; 12, 2-59; 14, 2-69; 18, 2-65. Other analyses: Lory, (Bull. Geol. Soc. de Fr. [2], vii, 452); Damour, etc. (Ramm. 5th Supp. 178); Deville, (Et. Geol. Teneriffe, 1848).

B.B. fuses more easily than orthoclase, and quietly to a glass, either clear er enamel-like. Not acted upon by acids.

Occurs in porphyry, granite, syenite, serpentine, and basalt; with quarts and mica it forms the granite at Kimito, containing columbite. At Tenerific it corus in trachyte.

Among its localities are Danvikszoll near Stockholm; at Arriège and Arendal, with calcite, crystals sometimes two or three inches long; at Schaitanak, Ural, greenish, in a gangue of quartz and mica and yellowish-white feldspar; at Claubhal in serpentine; at Lake Baikal; as sunstone at Christians-fiord, Norway, the aventurine character of which is owing to minute particles of specular iros,

according to Scheerer, (göthite according to Kengott).

In Iceland at Hafnefjord, (Hafnefjordite), Borodin, etc.
In the United States, at Unionville, Pa., (Unionite), with cuphyllite and corundum, G.=2.61; also at Danbury, Ct., with otherlase and danburite; at Haddam, Ot., often transparent, with iolite and black tourmaline; at Mineral Hill, Dalaware , Pa., called Moonstone.


Named from eliyes, little, and shaw, to cleave.

ALBITE, D. Cleavelandite, Brooks. Periklin, Breit. Tetartine. Kieselspath, Haus.

Triclinic. 0: 12=93° 36′, over 21=86° 24′. (B. & M.)

 $0: I=115^{\circ} 5'.$ $0:\frac{1}{4}=150^{\circ}5'$. $I: 2\bar{\imath}=134^{\circ} 32'$. $ii : ii' = 149^{\circ} 12'$. $O: I'=110^{\circ} 51'$. $I: 24=138^{\circ} 34'$. $I: I = 122^{\circ} 15'$. $0:21=133^{\circ}55'$. $\tilde{n}: I=117^{\circ} 53'.$ $ii: ii = 148^{\circ} 30'.$ $O: 2\lambda' = 137^{\circ} 26'$. $\tilde{u}: I = 119^{\circ} 52'$. $0:1i(adj.)=127^{\circ}23'.$ ₩: 1'=120° 27'. 1 : I=122° 32'. $O: 2\bar{\imath} (ov, 1\bar{\imath}) = 97^{\circ} 37'$. $\bar{\imath} : 1 = 112^{\circ} 11'$. 1': I'=124° 58.'

0 iĭ. $i\tilde{3}$ 13' 21 21 21 31 11 1'




NATROLITE, W. Soda Mesotype. Feather Zeolite. Bergmannite, Spreustein. Radiolite. Fäserzeolite, W. Natron-Mesotyp, R. Lehuntite, Thom. Brevieite,

Trimetric. $I: I=91^{\circ}, \ 0: 1i=144^{\circ} \ 23';$ a: b: c=0.7165:1:1.0176; $\frac{1}{2}:\frac{1}{2}$ (mac.)=143° 20′, (brach.)=142° 40′, $I:\frac{1}{2}=116°$ 40′. Crystals usually slender, often acicular; frequently interlacing, divergent, or stellate. Also fibrous, radiating, and massive.

H.=5-5.5. G.=2.17-2.24. Lustre vitreous, sometimes inclining to pearly, especially in fibrous varieties. Color white, or colorless; also grayish, yellowish. Streak uncolored. Trans-

parent-translucent.



Composition .- NaSi+AlSi+2H=Silica 47.4, alumina 26.9, soda 16.2, water 9.5. Analyses: 1, Klaproth, (Beit. v, 44); 2-4, Fuchs, (Schw. J. viii and xviii); 5, Thomson, (Min. i, 317); 6, Kobell, (J. f. pr. Chem. xiii, 7); 7, Riegel, (Jahrb. Pharm. xiii); 8, 9, 10, Scheerer, (Pogg. lxv, 276); 11, Thomson, (Min. i, 338); 12, C. G. Gmelin, (Pogg. lxxxi, 311); 13, C. Bergemann, (Pogg. lxxxiv, 491); 14, Souden, (Pogg. xxxiii, 112); 15, 16, Körte, (G. Rose's Mineral System, 1852, 96):

		Si	X 1	Pe	Ňa	Ĥ
1.	Högau,	48.00	24.25	1.75	16.50	9.00=99.50, Klaproth.
2.	11	47.21	25.60	1.35	16.12	8.88=99.16, Fuchs.
3.	Auvergne, cryst.	47.76	25.88	-	16.21	9:31=99:16, Fuchs.
4.	Tyrol, massive,	48.63	24.82	0.21	15-69	9.60=98.95, Fuchs.
	Antrim, cryst.	47.56	26.42	0.58	14.93	10-44, Cal 4=101-33, Thomson.
	Greenland, massive,	46.94	27.00	-	14-70	9.60, Cal.8=100.04, Kobell.
7.	Högau,	48.05	25.80	2.10	15.75	9.00=100.70, Riegel.
8.	Bergmannite, red,	47.97	26:66	0.73	14.07	9.77, Ca 0.68, K tr.=99.88, S.
9.	" white,	48.12	26.96	0.22	14.23	10.48, Ca 0.69, K tr.=100.7, S.
	Radiolite,	48.38	26.42	0.24	13.87	9.42, Ca0.44, K1.54=100.31, S.
	Lehuntite,	47.33	24.00	_	13.20	13.60, Cal.52=99.65, Thomson.
12.	Laurvig, Natrolite,	48.68	26.37	-	16.00	9.55, K0.36=100.96, Gmelin.
13.	Iron Natrolite,	46.54	18.94	7.49	14.04	9.37, Fe 2.40, Mn0.55=99.33B.
14.	Brevicite,	43.88	28.39	_	10.32	9.63, Ca 6.88, Mg 0.21, Souden.
15.	**	48.32	26.24	-	15.97	9.47, Ca tr.=100.00, Körte.
16.	44	48.50	26.05	-	16.49	9.29, Ča tr.=100.33, Körte.
			a With	a Httle	potash.	

B.B. natrolite becomes opaque and is often phosphorescent; it fuses quietly to a

glassy globule. Gelatinizes readily with acids, even after ignition.

This species occurs in cavities in amygdaloidal trap, basalt, and other allied rocks; and sometimes in seams in granite or gneiss. It is found in the graustein of Aussig in Bohemia; in Auvergne; the trap rocks of Kilmalcolm in Renfrewshire, and Glenarm in the county of Antrim and elsewhere. The Radiolite is from Brevig. Bergmannite is a red or white natrolite, from Zircon syenite near Brevig. Lehuntite

is from Glenarm, and if Thomson's analysis is correct it contains 3H like the scolecites, although a soda-mesotype. Kengott finds the angle I: I=91°.

The Iron-natrolite (anal. 13, Eisennatrolith) occurs along with the brevicite of Brevig, and is in dull green opaque prismatic crystals and semicrystalline plates.

H.=5. G.=2.353. It has one fourth of the alumina replaced by peroxyd of iron.

In North America, natrolite occurs in the trap of Nova Scotia; sparingly at Cheshire, Ct.; also at Copper Falls, Lake Superior, in crystals, sometimes on native copper.

&c. It is associated with pearl spar in the Tyrol, where it occurs in large transparent crystals; with epidote and garnet at Arendal; with eudialyte and horablende in Greenland. It is frequently one of the constituents of syenite and


In Massachusetts, U. S., at Chesterfield, with red and blue tourmalines in lamellar masses, (Cleavelandite), slightly bluish, and also fine granular, and rarely in small crystals. Contains the same minerals at Paris, Maine, and at Goshen, Mass., at Acworth and Alstead, N. H. At Haddam, Conn., accompanies chrysoberyl, beryl, columbite and black tourmalines. Fine transparent or translucent crystals at the Middletown feldspar quarry, (fig. 419; gave the author for $O: \tilde{u}, 92^{\circ}$ 40' and 87° 20'). At Granville, Washington Co., N.Y., white transparent crystals. At Monroe, Conn. a fine granular variety containing beryl. In Delaware Co., Pennsylvania, at Unionville, a granular variety is the matrix of the corundum, (see analyses 12 and 13), having the hardness of quartz, (7—725). It had been taken for Indianite. A similar variety equally hard is found with Idocrase at Sandford, Maine.

The name Albite is derived from albus, white, in allusion to its color, and was given the species by Gahn and Berzelius in 1814.

Hyposclerite of Breithaupt, analyzed by Hermann, (J. f. pr. Ch. xlvi, 396), with the resulting ratio for the protoxyds, peroxyds and silica 1:2:6, is shown by Ram melsberg to be probably albite mixed with augite. G.=2:6—2:66. From Arendal. Named from νπο, under or less, and σκληρος, hard.

ORTHOCLASE. Feldspar. Potash-Feldspar. Ice-spar. Felsite. Adularia Murchisonite. Leelite. Amausite. Amazonstone. Sunadin. Moonstone. Napeleonite. Necronite. Pegmatolite. Mikroklin, Breit. Valencianite, Breit. Feldstein, Haus. Feldspath, H. Eispath, W. Erythrite, and Perthite of Thomson.

Monoclinic; (Diclinic?) $C=63^{\circ} 53'$, $I: I=118^{\circ}48'$, O: 1i=153° 28'; a:b:c=0.844:1:1.5183.





Observed Planes.

A

I. Scolecite, or Lime-mesotype.

27.4

	DI	ZXI	Ua	TAR	п
1. Iceland,	48.94	25.99	10.44	_	13.90=99.26, Fuchs and Gehlen.
2. Faroe, cryst.	46.19	25.88	13.86	0.48	13.62=100.03, " "
3. Staffa, feathery,	46.75	24.82	14.20	0.39	13.64=98.80, " "
4. Auvergne,	49.00	26.50	15:30	-	9.00=99.80, Guillemin.
5. Niederkirchen,	48.16	23.50	14.50	0.30	13.50=99.96, Riegel.
6. Iceland,	46.72	25.90	13-71	10000	13.67=100, Gibbs.
7. "	46.76	26.22	13.68	-	13.94=100.6, Gülich.
8. Chili,	46.3	26.9	13.4	-	14.0 =1006, Domeyko,
9. Mull, Scotland,	46.21	27.0	1345	-	13.78=100.44, Scott.

II. Mesolite or Lime-and-sodo

		ra. Autobi	20000, 01	The state of the	Mete-one	a-most ypo.
10.	Faroe,	46.80	26.50	9.87	5.40	12:30=100:87, Berzelius.
11.	" cryst.	47.00	26.13	9.35	5.47	12.25=100.20, Fuchs & Gehlen.
12,	Iceland, feathery,	46.78	25.66	10.06	4.79	12.31=99.60, " "
13.	the state of the state of	47.46	25.35	10.04	4.87	12.41=100.13, " "
14.	Tyrol,	46.04	27.00	9.61	5.20	12.36=100.21, " "
15.	Niederkirchen,	46.65	27.40	9.26	4.91	12.00=100.22, Riegel.
16.	Giant's Causeway,	48.88	26.36	7.64	4.20	12.32, Mg2.46=101.86, Thomson.
17.	Iceland,	45.78	27.53	9.00	5.03	12.38, K 0.31=100.03, Breid.

An analysis by Walterhausen, Vulk. Gestein, 260.

B.B. scolecite curls up like a worm, (whence the name from σκωλης, a worm), and finally melts to a bulky shining slag, which in the inner flame becomes a vesicular

Slightly shining bead.

Occurs in the Berufiord, Iceland, where the crystals often exceed two inches in length, and are occasionally a quarter of an inch thick. It has also been met with in amygdaloid, at the Faroe Islands, Staffa; the Vendayah mountains, Hindostan; in Greenland; at Pargas, Finland; in Auvergne; also in veins in the Kilpatrick hills.

Poonahlite of Brooke has the angle I: I=91° 49′, Kengott. Ginelin obtained in an analysis, (Pogg. xlix, 538), Si 45°12, Xl 30°44, Ca 10°20, Na and trace of K 0°66, H 13°39=99°81. From Poonah, Hindostan. Brooke and Miller refer it to this

Antrimolite of Thomson (Min. i, 326) occurs in white silky fibrous stalactites, about as large as the finger, in cavities in amygdaloid at Antrim, four miles east of the Giant's Causeway. Fibres divergent from the axes; angle of prism, according to Kengott, 92° 13′, and the outer edges beveled by a prism of 150° 30′. H.=3'75. G.=2'096. Thomson's analyses afforded Si 43'47, Al 30'26, Ca 7'50, K 4'10, Fe 0'19, Cl 0'098, H 15'32. B.B. forms a white enamel without intumescence. Gelatinizes with muriatic acid.

A scolitic mineral from Saspach in Kaiserstuhl, afforded J. Schill (v. Leonh. 1846, 452) Si 51-50, Kl 16-51, Ca 6-20, K 6-82, Mg 1-93, H 17-00=99-96. Occurs in tufts of fibres and concretions; G.=1-465. H.=4-5; white or colorless; lustre silky

to vitreous. Easily soluble in muriatic acid.

SLOANITE, Meneghini and Bechi.

Trimetric. I: I=105°. Cleavage: I very distinct. In radiated masses, and often a fracture transverse to the radiation. H.=4.5. G.=2.441. Lustre pearly. White. Opaque.

Composition.—(Ča, Mg)⁸ Si²+5 Xl Si+9H=Silica 42.9, alumina 34.8, lime 11.3, water 11.0=100. Analysis by Bechi, (Am. J. Sei., [2], xiv, 64):

Si 42·19, £1 35·00, Ča 8·12, Mg 2·67, Na 0·25, K 0·30, H 12·50=100·76. B.B. fuses without intumescence to a white enamel. Dissolves in the acids even in the cold, and gelatinizes.

From the Gabbra rosso of Tuscany.

		≅ i	Æl	₽e	Ċn	Ŕ	Ν̈́a
5.	Adul. St. Gothard,	65.69	17.97		1.34	18.99	1 01=100, Abich.
6.	Baveno, green,	65.72	18.57		0.34	14.02	1.25, Mg 0.1=100, Ab.
	Siberia, green,	65.82	17.89	0.30	0.10	13.05	2.81, Mg 0.09, Mn 0.19,
	, ,						Cu trace=9975, Ab.
8.	Chili, rose,	65.37	20.47		2.60	6.80	4 00=98 74, Dom.
9.	Moonstone, Ceyl.	64.00	19.43		0.42	14.81	, Mg 0-2, H & loss
	. •						1·14, B. & M.
10.	Marienberg,	66.48	17.03	0.49	1.08	13.96	0·91==99·85, Krön.
11.	Saxony,	65.52	17.61	0.80	0.94	12.98	1.70=99.55, Kersten.
12.	Valencianite,	66.82	17.58	0.09		14.80	
18.	Microcline,	65.76	18:31	trace	1.20	14.06	=99 83.Evreinoff
14.	Perthite,	66· 44	18:35	1.00	0.67	6.37	5 56, Mg 0 24, ign 0 40
							==99·03, H
15.			19:46	0.44	0.28	6.22	6·14,ign0·12=98·89,G.
16.	" Freder'v'n, blh.	. 65·19	19.99	0.63	0.48	7.03	7·08, "0·38=100·78,G.
17.	" L. Superior,	66.70	18	·68	0.30	9.57	3·58, H 0·70=99·58, W.
18.	" Auerberg,	66.26	16.98	0.81	0.43	14.43	0·20, H 1·29, Mg 0·11,
19.	" Davidson Co.,	,					=100, Ramm
10.	N. C.,	85·30 6	20.20	tr.	0.02	14.85	0.79, Mg tr.=100.69.
		,					Genth.
2 0.	Chesterlite,	64.76	17.60	0.20	0.65	14.18	1.75, Mg0.80, ign 0.65,
							=100·89, S. & B.
21.	"	65·17	1770	0.20	0.26	13.86	1.64, Mg 0.25, ign 0.65
	_						=100 83, 8. 4 B.
22.	Loxoclase,	65· 4 0	19:48	1.25	2.26	2.76	7.23, Mg 0.20, ign 0.76
							=99·84, S. & B.
28.	"	66.31	18.23	0.67	1 09	4.85	7.81, Mg(+80, ign 0.20
						.	=98.96, 8. & B
24.	16	63.20	20.29	0.67	3·2 2	8.08	876, Mg tr. SiFH 1-23
							=1007, Plattner.

G. of No. 5=2.5756; of 6, 2.55; of 7, 2.58; of 8, 2.596; of 10, 2.44; of 15, 16. 2.59; of 19, 2.547.

Analyses: Diday, (Ann. d. M. [5], ii, 181); Delesse, (ib., iii, 372, 388, 406); Dechen, (of Sanidin, Verh. nat. Ver. Rheinl. 1852, 836); Avdeeff and Moss, (Pogg. lii, 465); Moll, (Ramm. 4th Suppl., 69).

B.B. fuses with difficulty, and only on the edges, to a semi-transparent blebby glass. With borax forms slowly a transparent glass, and with soda a vesicular glass. Not acted on by the acids. With cobalt solution, becomes blue only on the fused edges.

Difference of color and lustre has given rise to distinct names for several varieties of this species.

Common Feldspar or Orthoclase [is. ορθος, straight or rectangular, and κλαω, to eleave] includes the subtranslucent varieties, the common constituent of granite.

Loxoclass, Breit, has the composition of orthoclase as shown by Smith and Brush, and does not differ essentially in cleavage; the basal and clinodiagonal being much the most distinct; I: I about 120°; G.=2.6-2.62, Plattner.


Necronite [fr. serpos, a corpse] gives off a fetid odor when struck.


Adularia is a transparent or translucent variety, found in granitic rocks. The erystals are often large, and occur of great perfection in the high districts of Savoy; the name is derived from Adula, one of the highest peaks of St. Gothard. The Valencianite of Breithaupt is a variety of adularia; the name is from the Mexican mine Valenciana.

Moonstone is a variety of adularia, presenting, when polished, chatoyant or pearly reflections. Sunstone is a similar variety, containing minute scales of oxyd of iron, or Göthite, (Kengott), disseminated through it. The opalescence is seen in the direction of a plane replacing the edge $I\colon I$ somewhat obliquely. But neither of these are exclusively common feldspar. A Siberian sunstone has been shown by Schercer to be oligoclase; and the moonstone of Mineral Hill, Delaware Co., Pa., is of the same species.

O: 2i=116° 20'. 2i: -2i=129° 40'. ii: I=111° 58'. $0:-2i=114^{\circ}$. $ii:-1=106^{\circ} 32'$. -1:-1=146° 56'.

Cleavage: clinodiagonal (ii) eminent. Also in globular forms; also granular.





H.=3.5—4. G.=2.2, Haidinger; 2.195, Faroe Islands, Thomson, 2.175, Iceland. Lustre of ii pearly; of other faces, vitreous. Color various shades of white passing into red, gray, and brown. Streak white. Transparent—subtranslucent. Fracture subconchoidal, uneven. Brittle.

Composition.—Ča Ši+XlŠi°+5Ĥ, Damour=Silica 59·3, alumina 16·8, lime 9·2. water 14·7.

Analyses: 1, Thomson, (Min. i, 347); 2, Rammelsberg, (Handw. i, 302); 3, Damour, (Compt. Rend. xxii, 956, Ann. M. [4], x, 207); 4, Waltershausen, (Vulk. Gest. 252).

X1 Ca Ĥ 1. Farce, 59·15 17·92 7·65 15·40 —=100·12, Thomson.
2. Iceland, 58·20 17·60 7·20 16·00 —=99·00, Rammelsberg.
3. " 59·64 16·33 7·44 14·33 —, K·0·74, Na·1·16=99·64, D.
4. Berufiord, 58·90 16·81 7·38 14·33 0·12, "1·63, "0·57, Mg 0·29=100·04, W.

B.B. intumesces and fuses, and becomes phosphorescent. Dissolves in muriatic acid, affording slimy silica, without gelatinizing. Heulandite occurs principally in amygdaloidal rocks. Also in gneiss, and occasion-

ally in metalliferous veins.

The finest specimens of this species come from Iceland and the Farce Islands, and from the Vendayah mountains in Hindostan. Red varieties occur at Campsie in Sterlingshire, with stilbite of the same color, and brown in ore beds, at Arendal. It also occurs in the Kilpatrick hills, near Glasgow, on the I. of Skye, in the Fassa Valley, Tyrol, in the Hartz and elsewhere; abundant in the amygdaloid of Abyssinia.

At Peter's Point, Nova Scotia, it occurs in trap, presenting white and flesh-red colors, and associated with laumontite, apophyllite, thomsonite, &c.; also at Cape Blomidon, and other places in the same region, in crystals an inch and a half in

In the United States with stilbite and chabazite on gneiss, at Hadlyme, Ct., and Chester, Mass., and with these minerals and datholite, apophyllite, &c., in amygdaloid at Bergen Hill, New Jersey; sparingly at Kipp's Bay, New York Island, on gneiss, along with stilbite; in a fissure in hornblende rock, a few miles southwest of Philadelphia, sparingly; on north shore of Lake Superior, between Pigeon Bay and

Also in minute crystals, seldom over half a line long, with haydenite, at Jones's Falls, near Baltimore, on a syenitic schist. Levy has described these crystals, under

wich, Conn., at Brimfield, Mass., with iolite, and at Parsonfield, Me.; and sunstone at Lyme, Conn. (Some of these may be oligoclase). Kaolin occurs at Andover, Mass, and abundantly in New Milford, Kent, and Cornwall, Conn., and in the counties of Essex and Warren, New York; also in New Garden, Chester Co., Pa., abundant. Necronite is found at Roger's Rock, Essex Co., and at Thomson's quarry, near 196th street, New York.

Chesterlite (anal. 20, 21) is shown by Smith and Brush to have the constitution of Orthoclase. It occurs in crystals sometimes 1½ inches broad, implanted often and dolomite. Faces not polished; I: I'=121°—127°. O: it=90° as shown by twins; O: I and O: I' unequal, (as also 2i on I and 2i on I'), but not constant, and the difference may be an irregularity. Cleavage parallel to O and it, perfect. Twin common parallel to O: also a peculiar twin, in general form rectangular, made by composition parallel both to O and it, the latter composition shown by the meeting of strim along the middle of O, and the former by a similar meeting on it; but it is singular that in the two specimens observed by the author (free O, and one it; on the other plane O the strime is seen on only one of the plane O, and one it; on the other plane O the strime extend across, parallel to the intersection of O with one of the planes I, a fact that indicates a diclinic rather than monoclinic form. The crystals normally would have 4 planes I at one extremity: but the specimens are partly broken and only two are present on one side, one above the other.

Feldspar enters into the composition of a great number of rocks.

Granite consists of feldspar, quartz, and mica, crystallized promiscuously togeth.

The feldspar constitutes ordinarily about 40 per cent., but varies very widely; while the quartz is usually 30 to 40 per cent. Ordinary granite contains about 72.3 silica, 15.3 alumina, 7.4 of alkalies, 5.0 of lime, magnesia, and oxyd of irea,—a composition near that of petrosilex. Pegmatite is graphic granite.

Grains has the same ingredients as granite, but with traces of lamination.

Mica slate is similar in constitution, with a distinctly foliated structure.

Beresite is a fine grained granite, containing pyrites, from near Beresof, in the Ural Syenite consists of feldspar, hornblende, and quartz, and otherwise recemble granite. These rocks pass into one another by insensible gradations. Protognals a tale granite.

Dolerine is a gneissoid rock in the Alps consisting of tale and feldspar.

Granulite, Eurite, or Leptynite, (Weissstein), is a granular compound of feldsper and quartz, with sometimes garnet.

The Hornfels of the Germans is a massive compound of quartz and feldspar breaking with a smooth flinty fracture. The Cornubianite is similar.

Pyroxenite consists of feldspar and lamellar pyroxene.

Pyromeride is a granitoid rock containing spherules thickly disseminated. Similar spherules sometimes occur in porphyry, trachyte, curite, diorite, and occasionally granite. Delesse has shown that rocks containing these spherules have an excess of silica. The spherules are feldspathic, but contain mixed quartz which is most abundant in the exterior coats or at the centre.

Miascite, a granular slaty rock consisting of orthoclase, mica, and elseolite, with

sometimes quartz, albite, and hornblende.

Porphyry consists of a compact feldspathic base, (cornite or porphyrite, viz crystals of feldspar, (often orthoclase or oligoclase); it may be green with blotcheref paler green or white, or red with white blotches or specks, besides other shades of color; the blotches of a polished surface are the feldspar crystals. When distite feldspar crystals are scattered through granite it is called *porphyritic* granite. The feldspar of porphyry is often also the species labradorite, as is the case in the ancies: verd antique porphyry of Greece, quarried from rounded hills on the plains of Helosin, Laconia. In the porphyry of Ternuay in the Vosges it is the species vegite. It is often quartzose or globuliferous.

Clinkstone or phonolite is a compact feldspathic rock of grayish colors and smooth fracture, clinking under the hammer when struck somewhat like a metal. G =25

-2.6.

Trachyte is a rock of similar constitution and color with clinkstone, but having a rough surface of fracture. Domite is a grayish earthy variety from Puy-de Dome Pumice (Bimsstein, German) is a porous feldspathic scoria from volcanoes; the pores are fine and linear and often barely visible without a glass. G .= 2-2-24

488

H.=3.5-4. G.=2.094-2.205: 2.161, Haidinger. Lustre of ii, pearly; of other faces vitreous. Color white; occasionally yellow, brown, or red. Streak uncolored. Subtransparent-translucent. Fracture uneven. Brittle.

Composition .- CaSi+XISis+6H=Silica 57.6, alumina 16.3 Composition.—CaSi+HiSi+6H.—Silica 5/3, alumina 1: lime 8.9, water 16.3. Analyses: 1, Fuchs and Gehl (Schw. J. viii, 253); 2, Hisinger, (ib. xxiii, 63); 3, Retzi (Jahresb. iv, 153); 4, Moss, (Pogg. lv, 114); 5, Riegel, f. pr. Chem. xl, 317); 6, Hermann, (Bull. Soc. Nat., Mosc. 1848, 318); 7, Münster, (Pogg. lxv, 297); 8, 9, Sjögr (Ofv. K. V. Ak. 1848, 111); 10, Waltershausen, (Vulk. G. 254); 11, Kerl, (B. u. H. Ztg. 1853, No. 2); 12, R. Web (ib.); 13, Beudant, (Traitè de Min. ii, 119, 120).

len zius (J	
ow	
ren	
est	
ber	, (Y-1)
	-1
	Ĥ
	19.30=100.04,F. & G.
-	16.40=99.70, Hisinger.
-	18.35=100.77, Retzius.
32	17.79=100.58, Moss.
-	14.50, Fe0.26=98.53, R.
-	17.75, Fe, Mn1.0=100H.
-	17 05, Mg alk. 3 07, Fe0 5
)4	16.60, Mgtra.=101.40,S.
	10.00 M- N- 0.00

		Si	XI	Ca	Ňa	K	Ĥ
1.	Iceland,	55.07	16.58	7.58	1	5	19.30=100.04,F. & G.
2.		58:00	16.10	9.20	-	-	16'40=99'70, Hisinger.
3.	Faroe,	56.08	17.22	6.95	2.17	-	18.35=100.77, Retzius.
4.	"	57.18	16.44	7.74	1.11	0.32	17.79=100.58, Moss.
5.	Niederkirchen,	58.33	16.66	7.16	1.62	-	14.50, Fe0.26=98.53, R.
	Ilmen Mts.; G.=2.19,		16.25	7.66	1.03	-	17.75, Fe, Mn1.0=100H.
	Christiana; G .= 2.203	,58.58	15.73	7.02	-	-	17.05, Mg alk. 3.07, Fe0.5
	Gustafsberg,	57.41	16.14	8.97	1.21	1.04	16.60, Mgtra.=101.40,S.
9.	Barbro, Norway,	58.41	16.56	7.89	-	-	16.53, Mg, Mn 0.59=
							99·93, S.
10.	Iceland; G.=2.134,	57.40	16.23	7.71	0.60	0.34	16.68,Mg0.13=99.09,W.
11.		56.8	15.9	7.4	-	0.6	17.6, Fe 1.8=99.1, Kerl.
	Berufiord, Iceland,	58.02	14.94	8.33	-	1.30	17.71=100.30, Weber,
13.	Spharostilbite.	55-91	17.61	9.08	0.68	-	17:84=100:07 Bendant

B.B. intumesces and yields a milk-white bead. With acids yields slimy silica, excepting Beudant's sphærostilbite, which forms a jelly.

Stilbite occurs mostly in cavities in amygdaloid or trap. It is also found in some

Stilbite occurs mostly in cavities in amygdaloid or trap. It is also found in some metalliferous veins, and in granite and gneiss.

Abundant on the Farce Islands, in Iceland, and on the Isle of Skye, in trap; at Andreasberg in the Hartz and Kongsberg and Arendal in Norway, with iron ore; in the Vendayah Mts., Hindostan, in large translucent crystals, having a reddishtinge; in fine crystals of a brick-red color, in porphyritic amygdaloid, near Kilpatrick in Dumbartonshire; a brown variety on granite, at the copper mines of Gustafsberg, near Fahlun in Sweden; at Andreasberg, Kongsberg, etc.; at Partridge Island, at Nova Scotia, this species forms a perpendicular vein from three to four inches thick, and from thirty to fifty feet long, intersecting amygdaloid; its colors are white and flesh-red. are white and flesh-red.

are white and flesh-red.

In the United States, sparingly in small crystals at Chester and the Charlestown syenite quarries, Mass; at the gneiss quarry, Thachersville, Conn., in crystals lining cavities, in coarse granite; at Hadlyme in radiated forms or gneiss, associated with epidote, garnet, and apatite; at Phillipstown, N. Y., in crystals or fan-like groups; opposite West Point, in a vein of decomposing bluish feldspar, intersecting gneiss, in honey-yellow crystals; in the greenstone of Piermont, in minute crystals; in scopiform crystals of a dull yellow color, near Peekskill, N. Y.; and at Bergen Hill, New Jersey, in small but bright crystals; also at the Michipicoten Islands, Lake Superior. Lake Superior.

The name stilbite is from στιλβη, lustre.

ALTERED FORMS.—Stilbite has been observed changed to quartz. Hypostilbite of Beudant from Faroe, is considered a partially altered stilbite. Beudant obtained (loc. cit) Si 52:43. Al 18:32, Ca 8:10, Na 2:41, H 18:17=99:96. Two specimens of stilbite analyzed by Thomson, (Min. i, 345), approach hypostilbite.

Petrosilex (Adinole, Beudant) is compact impure feldspar, like the base of porphyry. It differs from jasper, which it often resembles, in being fusible before the blowpipe. G.=2-606. A greenish-gray specimen from Brittany afforded Berthier, Silica 75.4, alumina 15.5, potash 3.8, magnesia 1.4, oxyd of iron 1.2. The results are varying, as the species is rather a rock than a pure mineral. Thomson's Leelite, which falls here, consists of Silica 81.91, alumina 6.55, potassa 8.88, protoxyd of iron 6.42.

Obsidian or volcanic glass is sometimes an impure feldspar in a glassy state; and in other cases it is a mixture of feldspar and augite with chrysolite and much iron, or of augite and chrysolite or labradorite, &c., the materials varying with the lavas of a volcano; for any lava will become glassy, and thus make obsidian, by rapid

cooling. G.=2.25-2.8.

Pitchstone has the lustre of pitch rather than glass; pearlstone has a pearly lustre, and is sometimes in spherules, (spherulite), or consists of spheroidal concretions. G.=2·3-2·4. The spherules of pyromeride, porphyry, etc., are quite similar. The siliceous character of these spherules is mentioned on page 246; see also Delesse on Globuliferous Rocks, Trans. Geol. Soc. France, 1853, and Am. Jour. Sci. [2]. xvii. 168.

[2], xvii, 168.

Krablite, Forchhammer, or Baulite, appears to be a siliceous feldspathic mineral, related to these concretions. It forms the basis of the trachyte, obsidian and pitchstone of Iceland. According to von Waltershausen, it occurs also in triclinic crystals; and he deduces the oxygen ratio 1:3:24=(B+X1)Si*. B.B. fuses only in thin splinters; in acids insoluble. H.=6. G.=2:656, Forch., 2:572, Walt.

The following are analyses of pumice, obsidian, spherulite, krablite, etc.: 1, Berthier, (Ann. d. Mines, [3], v, 543); 2, Vauquelin, (N. allg. J. d. Chem. v, 230); 3, 4, Erdmann, (J. f. techn. Chem. xv, 32); 5, Thomson; 6, Trommsdorf, (N. J. d. Pharm. iii, 301); 7, Erdmann, (loc. cit.); 8, Ficinus, (Schw. J. xxix, 136); 9, Erdmann, (loc. cit.); 10, Klaproth, (Beit. ii, 62, iii, 262); 11, Berthier, (Ann. d. Mines, vii); 12, 13, B. Silliman, Jr., (Dana's Geol. Rep. p. 200); 14, Waltershausen, (Vulk. Gest. p. 211); 15, Delesse, (Bull. Geol. Fr. [2], ix 175); 16, Forchhammer, (Skand. Nat. Samm. i. Stockholm); 17, Genth, (Ann. Ch. u. Pharm. lxvi, 271):

```
Йø
                                                           Ňα
  1. Obsidian, Pasco, 69:46
                               2.60
                                      2.60
                                                                 7·12, H3·00=100, Berth.
                                             7.54
                                                   2.60
                                                          5.08
                                                                 -Mn 1·6=98·6, Vauq.
6·40, Mn 1·31=99·80, E
              Mexico, 78
                               10.
                                       2.
        " Telkiban, 74.80
                               12:40
                                      2.03
                                             1.96
  3.
                                                   0.90
                                                             2.77
  4. Pitchstone, Meis. 75.60
                               11.60
                                      1.20
                                             1.35
                                                    6.69
                                                                    \Pi 473=103-95, E.
                              12.74 F3.80
  5.
               Arran 63:50
                                             4.46
                                                          6.22
                                                                     , ign.8.0=98.71,Th.
        " bk. Dresdn. 74:00
  6.
                               17·00 £2·75
                                             1.50
                                                                     , Li 3чи),—98-25,Tг.
                                                              6·13 H 8 0=98·20, Erd.
     Pcarlstone, Hun. 72.87
                               12.05
                                     175
                                             1.30
                                                    1.10
                      79.12
                               12.00
                                      2.45
                                                   1:10
                                                              3.58 H 1.76=100.01, F.
  8.
  9. Spherulite, "
                      77.20
                                      2.27
                                             3.34
                                                             4.27 =100.28, Erdmann.
                               12:47
                                                    073
10. Pumice, Lipari, 77:50
                               17:50
                                      1.75
                                                              3.00=99.75, Klaproth.
                      70.00
                               16 00
                                      0.20
                                             2.50
                                                                6.50, H 3.00=98.50, B
12. Pélé's Hair, } 51'19
Hawaii, volc.glass, } 39'74
 12. Pélé's Hair,
                                                  18.16
                                                                    -, Fe 30 26=99 61, S.
                               10.55
                                             274
                                                   2.40 21.62
                                                                    -, Fe 22·29, H 0·33=
                                                                     99.67, Silliman, Jr.
                                                             1 1·12=100, Waltersh.
2·53 H 0·84=100, Del.
                       49.25
                               15.18 20.23
                                             9.61
                                                    2.10
                                                         2.51
14. Sideromelane,
15. Spher. in pyrom. 88:09
                               6.03
                                      0.58
                                             0.28
                                                   1.65
16. Krablite, Iceland 74.83
                               13:49
                                                          5.56
                                                                 tra.=100.43, F. G.=
                                      4.40
                                             1.98
                                                   0.17
                                                                                    2.389
17.
                       80.23
                              12.08
                                             0.95
                                                          2.26
                                                               4.92=100.44, Genth.
```

Other analyses of obsidian, Deville, (Bull. Geol. [2], viii, 427); of pumice, ib; also Schäffer, (J. f. pr. Chem. liv, 16):

apophyllite, some anhydrous silicate, (nepheline?) that gelatinizes with acida. Phonolite from Abstrode, analyzed by C. Gmelin, according to him, consists of mesotype, or some allied mineral, and a feldspar containing both soda and feldspar; but the proportions vary much in different phonolites, and some are but slightly attacked by acids. See further, Ramm. Handw. 76, etc., and Suppl. i to v.

Trimetric and hemihedral, Brooke and Miller. I: I=115° 26', $0:1i=153^{\circ}\ 26';\ a:b:c=0.5:1:1.5829.$

```
0:2i=135^{\circ}.
```

O: 67=108° 26'.

0:65=108° 4'.

O: 33=123° 11'.

 $0:4\overline{2}=115^{\circ}\ 27'$.

0:1=1530 26'.

 $O: \frac{1}{3} = 141^{\circ} 45'.$ $O: 2 = 130^{\circ} 13'.$ $O: 4 = 112^{\circ} 55'.$

O: 22=141° 9'.

O: 8½=107° 15'. O: 24=145° 49'.

O: 36=135° 35'.

O: 21=147° 43'.

O: 4%=128° 22'.

63: 63(mac)=157° 23'.

33: 33 " =160° 8'. 2: 2 " =131° 52'.

 $\frac{4}{3}$: $\frac{4}{3}$ (ov.ii)=141° 24′. ii2 : ii2 " =76° 44′.

용한 4 17 1 43 $\frac{4}{3}$ 27 2 29 24 38 31 47 49 4 41 40 47 55 63 68 82 12 13 12 iĭ

0

Observed Planes.

Cleavage: 12 and 17 indistinct. Crystals small and glassy. Also botryoidal and globular, having a columnar structure; also divergent and radiating; also massive.

H.=5-5.5. G.=2.989, (from Arendal), Haidinger. Lustre vitreous, sometimes subresinous on a surface of fracture; color white; sometimes grayish, pale green, yellow, red, or amethystine, rarely dirty olive-green or honey-yellow. Streak white. Translucent. Fracture uneven, subconchoidal. Brittle.

Composition.—(Ca*,H*,B)Si*, in which H*: Ca*: B=1: 2: 3=Silica 37.7, boracic acid 21.8, lime 34.9, water 5.6. 2Ca*Si+B*Si*+3H, Rammelsberg. Botryolite, a variety occurring in botryoidal concretions, is supposed to afford more water, but more analyses are needed to show that this is constant. The species is related in

formula as well as form to Euclase and Sphene.

G. Rose writes the formula for Datholite 3(ČaB+ČaŠi)+Ĥ*Ši, and the same for Botryolite, except Ĥ*Ši for the last term. He also states that the formula of the former may be 2Ča*Ši*+3Ĥ B, equivalent to two atoms of Wollastonite and three of Sassolin. But the boracic acid appears to be a base in all the silicates in which it occurs, as elsewhere observed.

Analyses: 1, Stromeyer, (Pogg. xii, 157); 2, Du Menil, (Schweig. J. lii, 364); 3, 4, 5, Rammelsberg, (Pogg. xlvii, 175); 6, Whitney, (Am. J. Sci. [2], xv, 435):

		Si	Ca	В	H
1.	Datholite, Andreasberg,	37.36	35.67	21.26	5.71=100, Stromeyer.
2.	" "	38.21	35.59	21.34	4.60=100.04, Du Menil.
3.	11 11	38.477	35.640	20:315	5.568=100, Ramm.
4.	" Arendal,	87.648	35.407	21.240	5.705=100, Ramm.
5.	Botryolite, "	36.085	85-215	19.340	8.635=99.275, Ramm.
6.	Datholite, I. Royal,	87.64	84.68	21.88(10	oss)5.80, Mntr.=100, Whitney.

	g Si	Æl	Ĥ	Bi: XI
9. Seilitz, near Meissen,	41.2	44.5	15-7	1 08 : 1
10. Aue, near Schneeberg,	44.6	"	14-5	1.11:1
11. Morl, near Hall,	42.9	**	14.8	1.07:1
12. Munschoff, Carlsbad,	457	"	14.9	1.14:1
18. Bornholm, Scandinavia,	400	66	158	10:1
14. Oporto, Portugal,	37.4	"	14.8	0.93:1
15. Newcastle, Delaware,	85.3	"	15.5	0.86:1
16. Galicia,	43.8	"	15· 2	1.09;1
17. Near Cherbourg.	51.5	"	15-6	1-29:1
18. Kaschna, near Meissen,	49.1	"	17-4	1-23:1
19. Zetlitz, Carlsbad,	41.1	"	16-0	1.08:1
20. Elba,	607	"	15-8	1.52 : 1
21. Wilmington, Delaware,	26.1	"	15.4	0.65:1
22. Cornwall,	83.8	"	16.1	2.09;1
28. Schletta, near Meissen,	82.	**	15.5	2.05:1
24. Hungary,	75 ·5	"	15-2	1.89:1
a. China,	78.4	"	14.4	1.81:1
ð. "	807	"	120	201:1

Ebelmen and Salvetat found in the last 1; 1 per cent. of potash, 2 of peroxyd of iron, and 27 of soda.

The following are other analyses in which the free silica and undecomposed mineral was not separated. Analyses c to l reduced to the same standard as the above, give 13 to 16:5 for the water. c to g are by Brongniart and Malaguti; &, i, R. D. Thomson and Richardson, (Thom. Min. i, 244); k, Rammelsberg, (3d Supp. 117); l, Dumenil (Chem. Anal. i, 1825, p. 35); m, Rammelsberg, (Pogg. Ixii, 152); a Glocker, (J. f. pr. Chem. xxxv, 39); o, W. S. Clarke, (Ann. Ch. Pharm. lxxx, 123):

		* .	·	٠.		``L		
		Si	Æl	н	Ċa,Mg,K	Ca,Mg,	Na	
C.	Newcastle,	29.73	25.59	8.94		Ře	eidue not arg	illac. 34 -99
d	Wilmington,	82-69	35.01	12.12	1.14	072	"	22.81
e.	Limoges,	42.07	84.65	12.17	1.33		"	976
f.	Devonshire,	44 26	36-81	12.74			"	4-30
g.	China,	2372	9.80		K 3 08		**	68-15
À.	Tuesite,	44.30	40.40	13.50	Ca075 M	Ig 0·50=9	9.45, Thoms	on.
Ĺ	"	48.80	40.10	14.21	" 0.64	" 0.55 Fe	0.94 = 100.23	, R.
k.	Schlackenwald,	48.46	41.48	13.49	" 1·20 N	Ta 0:37=	100, Ramm.	
l.	Clausthal,	43.00	40.25	15.50	" 0·47 F	e 0.48=	99 70, Dumei	nil.
171.	. Zorge,	49.75	29.88	5.48	" 0.43 N	Ig1 47, F	[6·35 F e6·61=	=99 -9 7, R
Ħ.	Smelite,	5 0·0	32 ·0	1301	Na2·1 Fe	2.0=99.1	, Glocker.	
0.	Schneckenstein,	4675	39.581	Mg 0.93	3 H 18·42:	=100.68	, W. S. Clark	. G.=26.

No. m contains still considerable potash, and was but partially decomposed. The Smelite is from a trachytic porphyry near Telkibanya, Hungary; it is rather tough; H.=2.5. G.=2.168; grayish-white, bluish. Named from σμηλη, scap. The Schneckenstein Kaolin often surrounds the crystals of topaz. Appears

The Schneckenstein Kaolin often surrounds the crystals of topaz. Appears under the microscope to consist in part of rhombic scales. B.B. becomes brownish but does not melt. Formula deduced Al³Si⁴+6H.

Many localities of Kaolin are already given in the above table. The name is a corruption of the Chinese Kauling, meaning high-ridge, the name of a hill near Jauchau Fu, where this mineral is obtained. The petuntze (peh-tun-taz) of the Chinese, with which the Kaolin is mixed in China, for the manufacture of porcelain, is a quartzose feldspathic rock, consisting largely of quartz.

The name Lithomarge (Steinmark) is often applied to a Kaolin material; the color may be white, yellow, or red, the latter color due to exyd of iron. A variety from Rochlitz analyzed by Klaproth (Beit. vi, 285) is red, and is called Carnet by Breithaunt. Analyzes h to I have been referred to Lithomarge.

Breithaupt. Analyses A to l have been referred to Lithomarge.

Myelin of Breithaupt (Talksteinmark) is from Rochlitz, and is of a yellowish or reddish color. Kersten obtained in an analysis Si 37.62, Al 60.50, Mg 0.82, And 63. Pe trace=99.57.

Melopsite of Breithaupt is a yellowish or greenish white Lithomarge from Neudeck in Bohemia. H.=2-3. G.=2.5-2.6. Feel greasy; adheres a little to the tongue.

Pholerite does not differ much from Kaolin in composition, but occurs in soft nacreous scales of a white color. G.=2.35—2.57. Infusible. Formula given Al Si+2 H. Analyses 1, 2, 3, Guillemin, (Ann. d. M. xi, 489); 4, 5, J. L. Smith, (Am. J. Sei. [2], xi, 58):

		Si	Al	H
1.	Fins,	41.65	43.35	15.00=100, Guillemin.
2.	a	42.93	42.07	15.00=100, "
3.	R. de Gier,	40-75	43.89	15.36=100, "
4.	Naxos,	44.41	41.20	13.14, Ca 1.21=99.96, Smith.
5.	Schemnitz.	42.45	42.81	12.92. Ca Mg tr .= 98.18. "

From Fins in the Dept. of Allier, and Rive de Gier, Dep. de la Loire, in France, filling fissures in nodules of iron ore in the coal formation. Also from Cache-Après, at Mons in Belgium; with emery and margarite at Naxos, and with diaspore at Schemnitz.

Halloysite. With a higher percentage of water (mostly about 24) the aluminous material is called Halloysite, Berthier, Lenzinite, John, etc. The composition corresponds mostly either to \(\frac{1}{4}\) \(\tilde{S}i + 3\) \(\tilde{H}\) or \(\frac{1}{4}\) \(\tilde{S}i^{\frac{3}{4}} + 4\) \(\tilde{H}\); the last—Silica 41.5, alumina 34.4, water 24.1.

Halloysite has a waxy lustre, a shining streak, white or bluish shade of color, and is subtranslucent, or becomes so in water; also adheres to the tongue. G.=

1.8-2.1.

Analyses: 1, 2, Berthier, (Ann. Chim. Phys. xxxii, 332, Ann. des Mines, [3], ix, 500); 3, Boussingault, (ib. v, 554); 4, 5, Dufrénoy, (ib. iii, 393); 6, Oswald, (J. f. pr. Chem. xii, 173); 7, Monheim, (Verh. d. Nat. Ver. d. preuss. Rheinl. v. 41 in Ramm. 4th Suppl. 221); 8, Sauvage (Ann. M. [4], x, 77); 9, ib. (ib. [3], xx, 204); 10, Salvetat, (Ann. Ch. Phys. [3], xxxi, 102):

Si X1 44.94 39.06 16.00=100, Berthier. 1. Anglar, 46.7 36.9 16.0=99.15, Dufrénoy 2. Housscha, 45.0 40.2 14.8=100, Boussingault. 3. New Granada, 40·66 33·66 24·83=99·15, Dufréuoy. 43·10 32·45 22·30, Mg 1·70=99·55, Dufrénoy. 40·25 35·00 24·25, Mg 0·25=99·55, Oswald. 40·31 33·23 23·69, Zn 1·23=98·46, M. 44·7 32·9 17·9, Mg and Alk, 14·5=100, Sauvage. 4. La Vouth, 5. Thiviers, Upper Silesia,
 Altenberg, 8. Milo, 42: 34: 24:0=100, Sauvage. 43:0 32:5 21.7, Fe 1:02, Mg 0:3, K, Na 0:4, Si gel. 1:5= 9. Ecogne, 10. Conde, Smectite, 11. Lenzinite, Eifel, 37.5 37.5 25.0=100, John. " Chanteloube, 36 36 36 00 21 50, Fe 1 95, Mg 0 18, K Na 0 50, Si gel. 20,

quartz 1 64=100·13, Sal.

The Halloysite of Househa is derived from graphic granite; that of Milo is from a pumiceous tufa, and it contained 29·3 per cent. of quartz. The mineral from Conde, near Houdan, France, is called Smectite by Salvetat, and he gives the formula Al Si²+7½H; it is greenish, and in certain states of humidity appears transparent and almost gelatinous. For his Lenzinite, Salvetat writes the formula Al Si+3H; the mineral is from the pegmatite of La Vilate, near Chanteloube, (Haute Vienne); it is clear brown, tender, not plastic. B.B. becomes reddish, but does not fuse; decomposed by heated sulphuric acid; at 100° C, the water is reduced to 16·5 per cent.

Samoite is related to the above, but contains more water. Moreover it is much harder than the other aluminous silicates that are here described as results of alteration. It forms stalactites three or four inches broad, and half as long, in a cavern in lava, island of Upolu of the Navigator group. The structure is lamellar; color whitish; lustre a little pearly. H.=4-4.5. G.=1.7—1.9. Analysis by Silliman, Jr. (Dana's Geol. Rep. Exp. Exp.):

Si 31 25, Xl 37 21, Ĥ 30 45, Mg 4 06, ĈaĈ 0 01, Ña 0 06=99 04. corresponding to Xl Si+5Ĥ. In another analysis he obtained Si 35 19, Xl 31 95, Ĥ 30 80, etc.

Bole.—The material so-called is closely related to Halloysite in its appearance, and prominently in its large per centage of water; but it is more varying in character. It is subtranslucent to opaque, has a shining streak, a brown, yellowish er reddish color, a greasy feel, and adheres to the tongue. Some varieties contain considerable oxyd of iron, from the decomposition of other minerals associated with the feldspar. Rock soap, (Bergseife), Bolus of Sinope, and Ockran of Orawitza, are of similar character. The following are analyses:

1, 2, Löwig, (Leonh. Oryk.); 3, Wackenroder, (Kast. Arch. xi, 466); 4, Zellner, (Leonh. N. Jahrb., 1835, 467); 5, Rammelsberg, (Pogg. xlvii, 180); 6, 7, Salvetat, (Ann. Ch. Phys. [8], xxxi, 102); 8, Smith & Brush, (Am. J. Sci. [2], xv, 211); 9, Bucholz, (Gehlen's, N. J., iii, 597); 10, Berthier, (Ann. d. M. [8], xi. 479); 11, Klaproth, (Beit. iv, 345); 12, Kersten, (Schw. J. lxvi, 31):

```
Bi Al Fe Ca Mg A

1. Ettingshausen, 42404 2404 1003 052 043 2473=10175, Löwig.

2. C. de Prudelles, 4175 2573 809 045 050 2402=9914, Löwig.

4179 209 122 — 249 = 999, Wackenroder.
 4. Striegau,
                          42:00 20:12 8:53 2:81 2:01 24:00, K 0:5=99:97, Zellner.
                          45-92 22:15 trace 3-90 trace 24:86=97:83, Ramm.
47:55 22:60 1:05 1:66 0:30 26:20, K Na 0:1, Si gel. 1:04, qtz
 5. Stolpen,
 6. Thiviers.
                                                                                          1 04=99 46. 8
                                            1.35 0.83 0.09 26.70, Na 0.93=99.35, Salvetat.
— 7.75 22.39 K, Na Mn tr.=99.64, Smith
                          45.44 24.00
 8. Unionville, Pa., 44.50 25.00
    Bergseife, Thu. 410
"Plomb., 440
                                             8.0 0.8
                                   26.5

    20.5=99.5, Bucholz.

                                                        - 20 250, Sand 60=990, Berth.
                                   220
10.
11. Bolus, Sinope, 32-0
                                           21 0 H17 0 NaCl 1.5=98 0, Klaproth.
                                   26.5
12. Ochran, Oraw., 31.3 430
                                            1.2 "21.0 and trace of B=96.5, Kersten.
```

The first two analyses give the formula H'Si'+9H, and 7 to 10 nearly AlSi'+6H. The Unionville mineral occurs with euphyllite; H .= 2.25; G .= 2.2; yellowishwhite; brittle; crumbles to pieces in water.

The Thiviers mineral which Salvetat calls Halloysite, has a rose-red color and is unctuous to the feel. No. 7 is similar. He writes for the formula of these #Si*+7#.

Clays are mostly derived from the decomposition of feldspathic rocks. Common clay consists ordinarily of about 1 part of alumina to 2 of silica, besides water; and often there are other ingredients present, as carbonate of lime, oxyd of iron and some magnesian compounds; and when iron is present it burns red. Acids attack the clay but slightly, showing that the water present is not to any great amount in chemical combination forming hydrous silicates of alumina; and thus they differ from the Halloysites and related compounds.

Cattinite of Jackson, (Am. J. Sci. xxxv. 388), is a variety of reddish clay stone, from the Coteau de Prairies, west of the Mississippi; and Pipestone, (pfeifenstein) is also a variety of clay slate or argillite. A variety from Northern Oregon, of a grayish color, has been analyzed by Thomson, (Min. i. 287).

Such clays or clay-slates have often been altered through infiltrating waters and heat. Of this nature are Agalmatolite, Dysyntribite of Shepard, and Parophite of Hunt. The alteration they have undergone has been dependent not properly upon a The alteration they have undergone has been dependent not properly upon a kaolinising process, but on the action and addition of alkalies, through the infiltration of solutions containing alkaline silicates or carbonates, which ingredients the decomposition of feldspar produces on a large scale.

Agalmatolite (Figure stone, Bildstein, Pagodite, Lardite, Fun Shih or Powder

stone of the Chinese) occurs massive, with a greasy feel and is rather soft. H .= 2-G.=2.8-2.9. Colors white, greenish, grayish, brownish, sometimes mottled Found in China, Saxony, at Nagyag, and Schemnitz. B.B. fuses only on the thin-

nest edges.

Dysyntribite of Shepard, (Am. J. Sci. [2], xii, 209), is massive or slaty and tough, and looks somewhat like serpentine; H.=3-3.5. G.=2.76-2.81. Color mottled, usually greenish, sometimes mottled with red. The composition varies widely, as Smith and Brush have shown. It is from Diana and other places in St. Lawrence Co., Northern New York. B.B. fuses in thin fragments.

Parophite of Hunt, (Logan's Rep. Canada, 1852, 95, Am. J. Sci. [2], xvii, 127), has the same serpentine aspect, and to this its name alludes; it is massive or slaty;

WOLCHONSKOITE.

Amorphous. Dull-shining. Color bluish-green, passing into grass-green. Streak bluish-green and shining. Feel resinous. Polished by the nail. Fracture subconchoidal. Adheres slightly to the tongue. Very fragile.

Composition.—Considered an impure hydrated silicate of chrome. Analyses: 1, Berthier, (Mem. ii, 263); 2, Kersten, (Pogg. xlvii, 489); 3, Ilimoff, (Ann. Jour. Mines de Russie, 1842, 366); 4, Bechi, (Am. J. Sci. [2], xiv, 62):

	Si	ër	Fe	₹1	Min	Mg	Ĥ
1.	27.2	34.0	7.2	-	-	7.2	23·2=98·8, Berthier.
2	37.01	17.93	10.43	6.47	1.66	1.91	21.84, Pb 1.01, K trace=98.26, Kers.
3.	30.06	31.24	9.39	3.09	_	6.50	12.40, Ca 1.90, Pb 0.16=100.74, Ilim.
4.	28.36	8.11	-	41.33	-	-	22.75=100.55, Bechi.

Gelatinizes with hot concentrated muriatic acid, in which half the chromium is dissolved, the rest remains in union with silica. Ilimoff gives 94.74 as the sum of his results. Should 6.50 Mg be 0.50 Mg? From Okhansk in Siberia; and a related compound (analysis 4) from Volterra, Tuscany.

CHROME OCHRE.

A clayey material, containing some oxyd of chrome, allied to the preceding. Occurs earthy of a bright green shade of color.

Analyses: 1, Drappier; 2, Duflos, (Schw. J. lxii, 251); 3, Zellner, (Isis, 1834, 637); 4, Wolff, (J. f. pr. Chem. xxxiv, 202);

Er Al Fe H - Ĉa and Mg 2.5=100, Drappier. 1. Creuzat, Fr. 64.0 10.5 23.0 57.00 5.50 22.50 3.50 11.00=99.50, Duflos. 58.50 2.00 30.00 3.00 6.25=99.75, Zellner. 46.11 4.28 30.53 3.15 12.52, K3.44, Na0.46=100.49, W. G.=2.701. 2. Halle, 3. Silesia,

4. Halle,

The formula (Al, Cr Fe)Si² corresponds nearly to the composition. Wolff's analysis, (No. 4), gives (Al, Cr)³Si⁴+4H, which is the constitution of a kaolin. It is probably not a true chemical compound.

Chrome ochre occurs at the localities above mentioned; also on Unst in Zetland, Mortenberg in Sweden, and elsewhere.

Miloschin, Herder. Serbian, Breit.—Another chromiferous compact mineral, probably a mechanical mixture. Color indigo-blue to celandine-green. H.=2. G.= 2.13.

Composition.—Approaches (XI, Er)*Si*+9H. Analysis by Kersten, (Pogg. xlvii, 485): Si 27:50, XI 45:01, Er 3:61, Ca 0:30, Mg 0:20, H 23:30=99:92.

In a matrass yields water. B.B. infusible. Partly dissolved in muriatic acid.

From Rudniak in Servia, associated with quartz and brown iron ore.

PIMELITE, Karsten. Alizite, Glocker.

Massive, or earthy. H.=2.5. G.=2.23-2.3: 2.71-2.76, Baer; 1.44—1.46, (alizite), Schmidt. Lustre weak, greasy. Color applegreen. Streak greenish-white. Translucent to subtranslucent. Feel greasy. Does not adhere to the tongue.

Composition .- Analyses: 1, Klaproth, (Beit. ii, 134); 2, Schmidt; 3, W. Baer, (J. f. pr. Ch. lv, 49);

Gently heated, it emits a blue phosphorescent light. B.B. on charcoal becomes glassy, subtransparent, and white, and melts only the edges; gives the reaction of lithia. With borax, it forms a clear, colorless glass. Not acted on by acids.

Petalite occurs at the iron mine of Utö, accompanying lepidolite, tourmaline, spodumene, and quartz; near York on the north coast of Lake Ontario; at Bolton, Mass., with scapolite; on Elba (Castor) in attached crystals.

Lithia was first discovered in this mineral by Arfvedson. The name petalite is

from strakov, a leaf.

ZYGADITE, [fr. ζογαόην, in pairs] Breithaupt, Ann. d. Ph. u. Chem. Ixix, 429. Plattner in a qualitative analysis found silica, alumina, and lithia, without water.

Form thin tabular rhombic prisms; only seen in twins, and like albite. G.=2-511. Lustre like glass. Color red and yellowish white. Feebly transparent. Occurs with quartz and stilbite at Andreasberg in the Hartz.

Appendix.

CYCLOPITE, von Waltershausen.

Triclinic; in small crystals resembling those of Anorthite and Labradorite.

H.=6. Lustre vitreous. Color white. Transparent.

Composition.—R°Si+2HSi=:1R°+3H)Si, or same as for Meionite. Analysis by Waltershausen, (Vulk. Gest., 292):

Si 41·45, Xl 20·88, Fe 2·20, Ca 20·83, Mg 0·66, Na 2·32, K 1·72, H 1·91=100·92. In dolerite of the Cyclopean Islands near Catania.

SAUSSURITE. Jade tenace, Feldspath tenace, H. Lemanit. Magerer Nephrit.

Probably oblique. Cleavage in two directions parallel to the lateral faces of a rhombic prism of 124° nearly. Composition often granular, impalpable; strongly coherent.

H.=5.5-6. G.=3.256, Piedmont; 3.642, Pays de Vaud. Lustre pearly, inclining to vitreous upon the faces of cleavage; also resinous in some specimens, particularly the massive. Color white, passing into greenish-white, mountain-green or ash-gray. Streak white. Fracture uneven, splintery. Subtranslucent. Extremely tough.

Joseph Composition.—(1R³+1H)Si† Analyses: 1, Klaproth, (Beit. iv, 278); 2, Saussure, (J. d. Mines, xix, 205); 3, 4, Boulanger, (Ann. d. Mines, [3], viii, 159):

		S i	æı	₽e	₩n	Ċa	Ňа	K	Йg
		49.00	24.00	6.20		10.20	5.50		3 75=99.25, Klap
2.	"	44 00	30.00	12.50	0.05	4.00	ი.00	0.722	=96.80, Saua
8.	Mt. Genèvre,	44.6	30.4			15.2	7.5	_	2.5=100.5, Boul
4.	Corsica,	43.6	32.0			21.0	-	1.6	2.4=100.6. "

B.B. fuses with great difficulty to a greenish-gray glass. Not acted on by scids. Saussurite occurs in regions of crystalline rocks, and with hornblende and angite constitutes the rocks called gabbro and euphotide. It was first found on the borders of the lake of Geneva, by Saussure, Senior, whose name it hears. It also occurs at Monte Rosa and its vicinity, in Corsica, in Greenland, at Madras, and elsewhere. as a constituent of the above rocks. This species has been considered an impure Labradorite.

WEISSIGITE, G. Jenzsch, N. Jahrb., 1853, 396.

Monoclinic. Crystals very small and indistinct. Cleavage unequal in two directions, parallel to the vertical axis, and meeting at 118°; also in the direction of a hemidome inclined 106° to the brachydiagonal. Sometimes in twins. Also massive II.=6.5. G.=2.538-2.546. Lustre vitreous. Color white to pale rose-red. Streak white.

Composition. - Contains silica, alumina, soda, lithia, and no water, and near petalite. B.B. fuses easily on the edges to a white somewhat blebby enamel and tinges

UNARRANGED SILICATES CONTAINING TITANIC ACID.

The species here included, may perhaps be arranged in some of the groups of silicates, when their composition is better understood. In sphene, a silicate of the same kind, we have pointed out a close relation to the ordinary silicates, the titanic acid acting as a base. The same appears to be true in Keilhauite, which may prove, as we show, to be related to sphene. The other species may have similar relations to some of the anhydrous silicates. The following are suggested as probably the general formulas under which the species fall.

1. Keilhauite,	(ų, ∄)Ši³ (like sphene).				
2. Tscheffkinite,	(Ř ³, ∰) Ši³ "				
8. Schorlomite,	(Ř³, X) Ši ¹ ⁄2.				
4. Mosandrite,	$(\mathbf{\hat{R}^3}, \mathbf{\hat{H}})$ Si+aq.				
5. Wöhlerite,	(Ř³, ₩) Ši.				

KEILHAUITE, A. Erdmann, K. V. Ac. H. 1844. Yttrotitanite, Scheerer, Pogg. lxiii, 459.

Trimetric $I: I=122^{\circ} 30'$, Greg. Cleavage: I, perfeet. Also massive.

H.=6.5. G.=3.69. Lustre vitreous to resinous. Brownish-black; in splinters brownish-red and translucent. Streak-powder grayish-brown.

Composition.—Analyses by Erdmann, (loc. cit.):

Si	Ti	Æl	₽e	₩n	₽e	Ĉa	Ÿ
1. 30.00	29.01	6.09	6.85	0.67	0.82	18.92	9.62=100.98.
2 29:45	28.14	K-90	8.48	0.88	0.68	19.69	0.64-00.00

The oxygen ratio between the bases and silica (reckoning Ti with the former, as in sphene) is very closely 3:2, the sphene ratio; and the formula may consequently be $\mathbb{H}Si^{\frac{3}{2}}$ or $(\mathbb{R}^3,\mathbb{R})Si^{\frac{3}{2}}$. The lime (Ca) united with the Ti is equivalent to a peroxyd (that is $TiO^2 + CaO = \mathbb{R}^3O^3 = \mathbb{R}$). Erdmann writes the formula $3Oa^3Si^2 + \mathbb{R}Si + \mathbb{Y}Ti^3$, which the three members have the widely unlike owners ratios $Oa^3Si^3 + \mathbb{R}Si + \mathbb{Y}Ti^3$.

(that is TiO²+CaO=R²O³=R). Erdmann writes the first equivalent to a prioxyd in which the three members have the widely unlike oxygen ratios, 2: 1, 1:1, 1:8. B.B. fuses with intumescence easily to a black shining slag. Yields an iron-colored glass with borax, which in the inner flame becomes blood-red. With salt of phosphorus gives an iron color and a silica skeleton, and in the inner flame a violet pearl. Reaction of manganese with sods. In powder wholly dissolved in muriatic acid.

Occurs about one and a half miles from Arendal, Norway, in a feldspathic rock. R. P. Greg, Jun., has a non-terminated crystal two inches long.

TSCHEFFKINITE, G. Rose, Reise n. d. Ural.

Massive, amorphous.

H.=5.5. G.=4.508—4.549, G. Rose; 4.5296, H. Rose, and in powder 4.615. Lustre vitreous. Color velvet-black. Streak dark brown. Subtranslucent to opaque.

VII. ANDALUSITE SECTION.

Oxygen of the bases exceeding in amount that of the silica.

1. GEHLENITE GROUP .- Dimetric.

GEHLENITE.

(1 R3+ ##) Si3.

2. ANDALUSITE GROUP.—Trimetric.

ANDALUSITE,

El Sis; also Sis.

TOPAE,

Il Si (F in place of some O).

STAUROTEDE.

(X1, Po)Si 1.

! LIEVRITE,

(R + 2 + 2 + 1) Si 2.

8. KYANITE GROUP .- Triclinie.

KYANITE.

₩1 813.

SILLIMANITE,

Al Si3; also Si3, Si6, Si !

4. EUCLASE GROUP .- Monoclinic.

EUCLASE.

(Be. X1)Si 3.

SPHENE,

 $(Ca+Ti)Sis^2=RSis^2$.

5. TOURMALINE GROUP.—Hexagonal.

TOURNALINE,

(R, H, B)Si.

[Euclase and sphene are homœomorphous, and probably dimorphous with Tourmaline. (See Am. J. Sci., [2], xvi, 96, xvii, 216). Through and alusite. kyanite and sphene, the compound #Si3 is trimorphous; and including gehlenite, it is tetramorphous. Datholite, although hydrous, is related to sphene and euclase both in form and formula.]

GEHLENITE, Fuchs. Stylobite.

Dimetric. Usual in short square prisms, sometimes tabular.

Cleavage: basal, imperfect; lateral in traces. H.=5.5—6. G.=2.9—3.067. Lustre resinous, inclining to vitreous. Color different shades of grayish green to liver-brown; none bright. Faintly subtranslucent—opaque. Fracture uneven -splintery. Streak white-grayish-white.

or reddish-brown. Streak-powder grayish-brown. Thin splinters translucent, bright red by transmitted light.

Composition .- Analysis by Berlin, (Pogg. 1853, 156):

Ti Ce, La D Fe Mg Oa 19.07 29.93 9.90 1.83 0.52 2.87 8.90=100.33.

There is some In with the Fe. Reckoning the Ti with the bases, as forming part of a peroxyd, as in Sphene and Keilhauite, the oxygen ratio of the protoxyds, peroxyds, and silica, is nearly 1: 2: 3, or of bases and silica 1: 1 (precisely 16:57: 15:86); affording the formula R*Si+2RSi+4H, or (\frac{1}{3}R^2+\frac{3}{2}R)Si+1\frac{1}{2}H. This excluding the water is the formula of epidote, to which the species may be related.

WÖHLERITE, Scheerer, Pogg. lix, 327, 1843.

Trimetric. $I: I=90^{\circ} 54', O: 1i=144^{\circ} 1', Descl.; a:b:c=$ 0.7261:1:1.01583.

494

 $0:\frac{1}{2}i=160^{\circ}3'$

 $0: \frac{7}{16}i = 153^{\circ} 29'.$ $0: \frac{17}{4}i = 116^{\circ} 37'.$

 $0:12=141^{\circ}18'$. in: i2=116° 56'.

in: I=135° 27'.

iz: iz (ov. ii)=126° 9'.

is: is (ov. ii)=142° 34'.

 $\frac{1}{2}i : \frac{1}{2}i \text{ (ov. } O) = 140^{\circ} 6'.$

In tabular crystals and prisms: Cleavage: distinct in one direction. Also granular.

H.=5.5. G.=3.41. Lustre vitreous, inclining to resinous. Color light-yellow, wine-, honey-, resin-yellow, brownish, grayish; Transparent — subtranslucent. streak-powder yellowish-white. Fracture more or less conchoidal-splintery.

Composition.— $6\dot{R}^2\ddot{S}i+3Zr\ddot{S}i+\ddot{C}b\ddot{S}i=(\frac{6}{10}\dot{R}^3+\frac{3}{10}Zr+\frac{1}{10}\ddot{C}b)\ddot{S}i=(if\dot{C}a:\ddot{N}a=7:2).$ Silica 31·2, columbic acid 14·3, zirconia 18·9, lime 27·0, soda 8·6=100. Scheerer writes the formula $Zr^3\ddot{C}b+5(\ddot{N}a\ddot{S}i+\ddot{C}a^3\ddot{S}i)$ which is hardly as near the analyses, and has for its three members the unlike oxygen ratios 1:1, 1:3, 3:1.

If in the above, the $\ddot{C}b$ be united with the peroxyds, the ratio of \ddot{R}^2 to \ddot{R} will be

3:2 and the formula will be essentially that of some Idocrase and Allanite. Scheerer obtained in his analysis,

Si 30.62, Cb 14.47, Zr 15.17, Fe 2.12, Mn 1.55, Ca 26.19, Na 7.78, H 0.24=98.14,

with perhaps traces of cerium, and 0.4 of magnesia.

Dissolves easily when heated in strong muriatic acid, with a separation of the silica and columbic acid. B.B. in a strong heat fuses to a yellowish glass. With the fluxes, gives the reaction of manganese, iron, and silica.

Wöhlerite occurs with elæolite in zircon syenite, on an island of the Langesund-

fjord, near Brevig, in Norway. Some crystals are nearly an inch long.

EUROLITE, Scheerer, Jahresb. xxv, 375, and Pogg. Ann. lxxii, 561). In reniform masses. Color brown. Resembles wöhlerite. G.=2-01.

Composition.—Analysis by Scheerer, (loc. cit.): Si 47.85, met. acids and some Zr 14.05, Fe 8.24, Ca 12.06, Ce 2.98, Na 12.31, Mn 1.94, Mg trace. H 0.94=100.37. Scheerer considers it a wöhlerite, in which the zirconia is replaced by peroxyd of iron. From Rödkindholm near Fredericksvärn, Norway; also near Brevig.

tesselated appearance, as shown in the following figures, from a memoir by Dr. C. T. Jackson, (Jour. Bost. Soc. Nat. Hist. i, 55). Figs. a and b are from opposite extrem-

ities of the same crystal; so also c and d, and e and f. A appears to be a twis crystal.

Composition.—Al Si = Silica 370, alumina 630. Perhaps in part Al Si = Silica 403, alumina 597. Analyses: 1, Bucholz, (v. Moll's Ephemer. iv, 190); 2, Thomson, (Min. i, 332); 3, Kersten, (J. f. pr. Chem. xxxvii, 162); 4, Svanberg, (Jahresb. xxiii, 279); 5, Bunsen, (Pogg. xlvii, 186); 6, A. Erdmann, (Jahresb. xxiv, 311); 7, Bunsen, 8, Jackson, (Bost J. Nat. Hist. i, 55); 9, Renou, (Expl. Sci. de l'Algerie, Paris, 1843, 58); 10, Hubert, (Jahrb. k. k. g. Reichs. i, 350):

1. Herzogau, 86.5 60.2 4 0=101 0, Bucholz. Tyrol, Munzig, 2 85.80 60.20 8. 87.51 60-01 Fahlun, 87.65 59.87 Lysens, Tyrol40.17 " 89.99 5. 58.62 0.72, \$\frac{\pm}{\text{km}} 0.88 = 100.14, \text{ Erdm.} \quad \text{G.} = 3.154. \\
--, \frac{\pm}{\text{km}} 0.53, \text{ Ca 0.21, ign.} 0.99 = 99.38, \text{ Bunsen.} 58.60 Chiast.Lanc. 89'09 58.56 88.0 610 4·0, H 1·5=99·5, Jackson. " Algeria, 36.6 , 98.5, Renou; I: I=98° 80'. G.=3.1. 61.9 10. Andal. Tyrol, 39.24 0.63, Mg 0.25, Ca 0.51=100.12, Hubert. 59.49

B.B. alone infusible. When pulverized and mixed with borax, it fuses with extreme difficulty to a transparent colorless glass. With sods it swells up without melting.

Andalusite occurs in crystalline schists, especially mica and clay slate. It was first observed in the province of Andalusia, in Spain. Occurs in the Lisens valley, in the Tyrol, in large crystallizations; at Bräunsdorf and Penig in Saxony; Goldenstein, in Moravia; in Bavaria; in Siberia; at Killiney Bay, Ireland, in mica slate; and near Balahulish, Argyleshire. Chiastolite at Jago di Compostella in Spain, Barèges in the Pyrenees, Bayreuth, and Cumberland in England.

At Westford, Mass., abundant both crystalline and massive, sometimes reserved.

At Westford, Mass., abundant both crystalline and massive, sometimes rescoolored. Litchfield and Washington, Conn., fine crystals; also Mt. Abraham, Bangor, and Searsmont, Me. In Pennsylvania, near Leiperville, in large crystals; also at Marple; at lake St. Francis, Canada East, in flesh-red translucent crystals in a mica schist of Silurian age, the larger crystals sometimes chiastolite. Chiastolite is abundant in the towns of Lancaster and Sterling, Mass.; and at the former place occasionally in quartz, presenting all the essential characters of and alusite, (anal. 7, 8). Andalusite occurs also near Bellows Falls, Vermont; at the White Mountain Notch, N. H.; at Camden in Maine, and Charleston, N. H.

ALTERED FORMS.—Andalusite occurs altered to Kyanite. Hubert's analysis above, was of the interior of an Andalusite crystal, the exterior of which was changed in structure to Kyanite. The exterior afforded Si 36:67, Al 60:00, Fe 1:33, On 0:98—98-93. The analysis of the Andalusite affords the second formula above, while that of the Kyanite affords the first, which is that of all Kyanite. It is also found changed to tale, steatite and mics.

VAUQUELINITE, (Ĉu, Pb)*Ōr*.

MELANOCHROITE, Pb* Ōr*.

DECHENITE, Pb V.

VANADINITE, Pb*V+‡Pb Cl.

VOLBORTHITE, (Ĉu, Ĉa)*V+Ĥ.

AREOXENE,

PEROFSKITE, G. Rose, Pogg. xlviii, 558.

Monometric. Observed planes: O, I, 1, 2, $i\frac{3}{2}$, $i\frac{3}{4$

H.=5.5. G.=4.017. Lustre metallic-adamantine; less bright on a cleavage face. Color grayish to iron-black. Opaque—subtranslucent. Streak uncolored, grayish.

Composition.—ĈaTi=Titanic acid 59.4, lime 40.6=100. Analyses: 1, Jacobson, (Pogg. lxii, 596); 2, Brooks, (ib.):

Ti Öa Mg
1. 58.96 39.20 trace
2. 59.00 36.76 0.11 " " 4.79=100.07, Brooks.

B.B. alone infusible. With salt of phosphorus and borax, the pulverized mineral forms a clear glass colored with titanium; with the former in the inner flame the globule, as long as it is heated, is grayish-green, but becomes of a violet-blue on cooling; in the outer flame, it is greenish-white while hot, and clear and colorless on cooling; slightly acted on by the acids.

Perofskite occurs in crystals or druses of crystals, the largest yet seen not over six lines in length. The forms have been studied by Descloizeaux, (Ann. Ch. Phys. xiii, 1845, 338). It is associated with crystallized chlorite, and magnetic iron in chlorite slate, at Achmatovsk, near Slatoust in the Ural. It is named in honor of you Perofski of St. Petersburg.

of von Perofski of St. Petersburg.

In Sphene, as has been shown, (Ca+Ti) is equivalent to a peroxyd; and in this view, Perofskite may be considered as related to Martite and Iserine, which are mo-nometric.

PYROCHLORE. Brewst. Jour. vi, 358. Microlite, Shepard. Hydrochlore and Fluochlore, Hermann.

Monometric. Observed planes 1, I, 22, 33, O. In octahedrons; f. 11, 19, 41. Cleavage: octahedral, sometimes distinct, especially in the smaller crystals.

H.=5-5.5. G.=3.802, from Brevig, Berzelius; 4.32, from Miask, Rose; 4.203, Miask, Hermann; 4.203-4.221, from Fredericksvärn, Hayes. Lustre vitreous or resinous. Color pale honeyyellow, brown, dark reddish or blackish-brown. Subtranslucent—opaque. Fracture conchoidal.

H.=8. G.=3·4—3·65. Lustre vitreous. Color yellow, white, green, blue; pale. Streak uncolored. Transparent—subtransfucent. Fracture subconchoidal, uneven. Pyroelectric.

Composition.—AlSit with one-seventh of the oxygen replaced by fluorine, Rammelsberg.

Analyses: 1—3, Berzelius, (Schweig J. xvi, 423, Afhand. iv, 236); 4, 5, Forchhammer, (J. f. pr. Ch. xxix, 195, xxx, 400); 6, Berzelius, (Schw. J. xvi); 7, Bucholz, (ib. i, 385); 8, Forchhammer, (J. f. pr. Chem. xxix, xxx):

		Ši	Æl	F
1. Aue	rbach, Saxony,	34 24	57.45	14-99, Berzelius.
2. Bra	zil, yellow,	34-01	58 38	15-06, "
3. Finl	oo, pyrophysalite,	34 ·36	57 74	15-02, "
	roe, Ct.,	35.39	55-96	17:35, Forchhammer.
5. Fin	bo, pyrophysalite,	35.66	55.16	17-79, "
	nite, Altenberg,	38.43	51 00	17 09, Berzelius.
		350	480	16.5, Ca 0.5, Bucholz
8. 4	44	39-04	51-25	18:48. Forehhammer.

B.B. infusible alone on charcoal, but when strongly heated becomes covered with small blisters, which crack as soon as formed. Some varieties take a wine-yellow or pink tinge when heated. With borax forms slowly a diaphanous glass.

Pyraite is a massive subcolumnar variety; G. Rose has observed the prism 93° 15′—93° 20′, proving its identity with topaz. The formula ÆiSi with one-seventh of the oxygen replaced by fluorine, is proposed by Rammelsberg.

Physalite or pyrophysalite of Hisinger is a coarse, nearly opaque variety, found in yellowish-white crystals of considerable dimensions; it intumesces when heated, and hence its name from puraw, to blow. Minute crystals of three or four different kinds, and two or three kinds of fluids have been detected by Sir David Brewster in crystals of topaz.

Topaz occurs in gneiss or granite, with tourmaline, mica, and beryl, occasionally with apatite, fluor spar, and tin; also in talcose rock, as in Brazil, with euclase, &c.. or in mica slate. With quartz, tourmaline, and lithomarge, it forms the topaz rock of Werner. Specimens of quartz crystal from Brazil, penetrated by topaz, are not uncommon.

Fine topazes come from the Urals and Altai mountains, Miask in Siberia, and from Kamschatka, of green and blue colors; Villa Rica in Brazil of deep yellow color. either in veins or nests in lithomarge, or in loose crystals or pebbles; sky-blue crystals in Cairngorm, Aberdeenshire; Jameson mentions one which weighed lyoz; the tin mines of Schlackenwald, Zinnwald, and Ehrenfriedersdorf, smaller crystals also at Schneckenstein and Altenberg; the Mourne mountains, small limpid crystals with beryl, albite, and mica, in drusy cavities in granite. Physalite occurs in crystals of great size, at Fossum, Norway; Finbo, Sweden, in a granite quarry, and at Broddbo in a boulder; one crystal from this last locality, at Stockholm, weighed eighty pounds.

Pycnite is from Altenberg, Schlackenwald, Zinnwald, and Kongsberg.

Topaz occurs in the United States at Trumbull, with fluor and diaspore, at Middletown, Conn., and Crowder's Mountain, N. C. At Trumbull the crystals are abundant, but are seldom transparent, except those of small size; these are usually white, or with a tinge of green or yellow. The large coarse crystals are sometimes ix or seven inches in diameter.

A variety of topaz from Brazil, when heated, assumes a pink or red hue, resembling the Balas ruby. The finest crystals are brought from Minas Novas in Brazil. From their peculiar limpidity, topaz pebbles are sometimes denominated gouttes deam. The coarse varieties of topaz may be employed as a substitute for emery. The name topaz, is from rowafies, an island in the Red Sea.

ALTERED FORMS.—Topaz is found altered both to Steatite and Kaolin or Lithomarge. It is possible that pycnite has lost part of its alumina by a process of change, and hence the excess of silica.

the oxydating flame becomes opaque. With salt of phosphorus (in the same proportion) in the inner flame gives a clear glass, and when reduced, the glass is green; but in the outer becomes yellow. With a little more of assay, the glass remains clear. With soda (12 parts to 1 of assay) dissolves; some clear portions are seen in the globule while hot, but on cooling, opacity precedes the crystallization of the globule; finally a gray-brown slag remains, which cooled from the outer flame, has a green color indicating oxyd of manganese. Decomposed by much soda, and the resulting mass heated with nitric acid, gives a heavy white insoluble powder, which with boiling water takes a white floculent form; the powder exhibited all the characters of columbic (niobic) acid. The acid solution, when mixed with carbonate of ammonia, remains clear; heated, some oxyd of iron falls, and the fluid is light yellow; with oxalic acid, a white earth separates, which, heated with substantial acid disclorers which, heated with substantial to exhibit the carbonate of the fluid is a substantial to exhibit the second of the fluid forms with substantial to exhibit the second of the fluid forms with substantial to exhibit the second of the fluid forms with substantial carbonates. phuric acid to destroy the oxalic acid, dissolves, and the fluid forms with potash before complete neutralization, a white double salt, which has the characters of that from zirconia, but may also contain oxyd of cerium. The oxalate when first formed did not afford when heated the cinnamon-brown color characteristic of deutoxyd of cerium. The extremely small amount of the mineral under examination forbids the expression of certainty respecting the base. Although inclining to the opinion of the existence of cerium in the mineral from the red color of the crystals, Mr. Hayes observes that he obtained no positive proof on this point.

SCHEELITE, Leona. Tungstate of Lime. Tungsten. Scheelin calcaire, H. Schwerstein, W.

Dimetric; hemihedral in planes 12 and 33. $O: 1i=123^{\circ} 59';$ a = 1.4835.


```
O: 1=115^{\circ} 29'. 1:1 (pyr.)=100° 40′. 1i:1i(bas.)=112° 2′. O: 33=102^{\circ} 2′. 1:1 (bas.)=129° 2′. 1:1i=140° 20′.
```

$$Q: 33=102^{\circ} 2'$$
. $1:1$ (bas.)=129° 2'. $1:1i=140^{\circ} 20'$.

$$O: 12=121^{\circ} 5'$$
. $1i: 1i \text{ (pyr.)} = 108^{\circ} 12'$. $12: 1i=157^{\circ} 21'$.

Cleavage: 1, most distinct, 1i, interrupted, O traces. Twins: planes of composition I and ii. Also reniform with columnar structure; and massive granular.





H.=4.5-5. G.=6-6.076. Lustre vitreous, inclining to adamantine. Color white, inclining to yellow and brown; sometimes Streak white. Subtransparent—transalmost orange-yellow. lucent. Fracture uneven. Brittle.

Staurotide is very abundant throughout the mica slate of New England. At Franconia, Vt., large brownish-red opaque crystals, often compound; also brownish black. At Windham, Me., near the bridge, the mica slate is filled with large crystals; also at Mt. Abraham, Hartwell, and Winthrop, Me. In New Hampshire, at Lisbon, abundant in mice slate, and on the shores of Mink Pond, loose in the soil; at Grantham, two miles from Meriden, of a gray color. In Vermont, at Cabot At Chesterfield, Mass., in fine crystals; also at Bolton, Vernon, Stafford, and Telland, Conn. Small crystals at the Foes ore bed in Dover, Duchess Co., N. Y.; also three and a half miles from New York city, on the Hudson, Reddish-brown crystals abundant on the Wissahiccon, eight miles from Philadelphia.

If we make I the plane is, then the faces of composition have simple expressions, being It and 1; I: I=109° 14', O: 11=124° 38', O: 11=134° 12'. The only difference between this form and the above is that the longer lateral axis is ease third shorter. If we halve a and c the axes are nearly identical with those of andalusite.



Dr. C. T. Jackson has described a variety of staure town, N. H., as represented in the accompanying figure. He states that the staurotide macles pass by insen shades into andalusite macles, where the mica slate passes into argillaceous slate.

Staurotide and Staurolite are derived from every, & CTOSS.

ALTERED FORMS.—Staurotide crystals occur altered to steatite.

LIEVRITE, W. Yenit. Ilvait.


Trimetric. $I: I=111^{\circ} 12', O: 1\bar{\imath}=146^{\circ} 20'; a:b:c:=0.6643$: 1 : 1.46.


 $O: 3i=116^{\circ} 35'. \ O: 2i=137^{\circ} 37'.$ 1i: 1i=112° 40'.

 $O: 1=141^{\circ} 5'$. $1: 1 \text{ (mac.)}=138^{\circ} 26'$. $ii: iii: (brach.)=107^{\circ} 44'$. $O: 1i: 167^{\circ} 9'$, $1: 1 \text{ (brach.)}=117^{\circ} 34'$. $I: ii: 160^{\circ} 32'$.

Lateral faces usually striated longitudinally. Cleavage: paral-

lel to the longer diagonal, indistinct. Also columnar or compact massive.






H.=5.5—6. G.=3.8—4.2; 3.994, Haidinger; 3.9796, Stromeyer; 3.825—4.061, Lelievre. Lustre submetallic. Streak black, inclining to green or brown. Color iron-black, or dark grayishblack. Opaque. Fracture uneven. Brittle.

B.B. melts and gives off vapors of lead, leaving a dark colored submetallic crystalline globule, having a pale-gray streak. Soluble in nitric acid with a yellow

Scheeletine occurs at Zinnwald in Bohemia, with quartz and mica; at Bleiberg in Carinthia, accompanying molybdate of lead; in Chili, probably near Coquimbo.

WULFENITE, Haid. Molybdate of Lead. Gelb-bleierz, Wern. Yellow Lead Ore. Bleigelb, Haus. Bleimolybdat.

Dimetric: sometimes hemihedral in 1, 1i, and $i \frac{3}{2}$. O: 1i =**126°** 26'; a=1.574. In modified square tables and octahedrons. $O: 1=114^{\circ} 12'.$ $1: 1 \text{ (bas.)}=131^{\circ} 35'.$ $\frac{2}{3}i: \frac{2}{3}i \text{ (bas.)}=92^{\circ} 43'.$ $1: 1 \text{ (pyr.)}=99^{\circ} 40'.$ $1i: 1i \text{ (pyr.)}=106^{\circ} 44'.$ $\frac{1}{3}i: \frac{1}{3}i \text{ (bas.)}=76^{\circ} 23'.$



Cleavage: 1 very smooth; O and 1 much less distinct. Also

granularly massive, coarse or fine, firmly coherent.
H.=2.75—3. G.=6.3—6.9. Lustre resinous or adamantine. Color wax-yellow, passing into orange-yellow; also siskin and olive-green, yellowish-gray, grayish-white, brown. Streak white. Subtransparent—subtranslucent. Fracture subconchoidal. Brittle.

Composition.—PbMo=Molybdic acid 38.5, oxyd of lead 61.5. Analyses: 1, Göbel, (Schw. J. xxxvii, 71); 2, Melling, (Raminelsberg, 1st Supp. 59); 3, 4, Parry and J. Brown, (Proc. Phil. Soc. Glasgow, April, 1847); 5, C. Bergemann, (Pogg. lxxx, 400):

1.	Carinthia,	M o 40·5	Pb 59·0=99·5, Göbel.
2.	"	40.293	61.903=102.196, Melling.
3.	"	89.30	60 35=99 65, Parry.
4.	"	89.19	60.23=99.42, Brown.
5.	Zacatecas.	37.65	62:85=100. Bergemann.

A red variety contains a trace of chromic acid.

B.B. decrepitates briskly and becomes darker, and afterwards on cooling, the color disappears. On charcoal it fuses and is absorbed, leaving behind globules of metallic lead. With borax in the exterior flame, it fuses readily to a slightly colorat once dark and opaque. Melts readily with salt of phosphorus, producing a green glass, when the proportion of the mineral is small, but black and opaque, if large. This species occurs in veins in limestone with other ores of lead, at Swarzenbach,

Bleiberg, and Windisch-Kappel in Carinthia. It is also met with at Retzbanya in Hungary, and at Moldawa in the Bannat, where its crystals are red and have

considerable resemblance to chromate of lead.

H.=6-7.25. G.=3.559, white kyanite; 3.675, blue transparent; 3.661, Tyrol, Erdmann. Lustre vitreous—pearly. Color blue, white, blue with white margins; also gray, green, black. Streak uncolored. Translucent—transparent.

Kyanite is generally in bladed crystallizations, though occasionally in short prisms; and these prisms or blades are bounded by the planes it and it, with cleavage parallel to the larger face. The prevalent color is pale blue, which is often deeper along the middle of the prisms. The crystals may often be easily scratched on the lateral surface while they are very hard on the extremities.

Composition.—AlSi =Silica 37.0, alumina 63.0. Analyses: 1-3, Arfvedson, (K. V. Ac. H. 1821, i, 148, and Schw. J. xxxiv, 203); 4, Rosales, (Pogg. lviii, 160); 5, Marignac, (Ann. Ch. Phys. xiv, 49); 6, 7, A. Erdmann, (Jahresb. xxiv, 311); 8, Jacobson, (Pogg. lxviii, 416); 9, 10, 11, Smith and Brush, (Am. J. Sci. [2], xvi, 49, 371):

```
=100·2, Arfvedson.
 1. Röraas, Norway, 86-4
                               63-8
 2. St. Gothard,
                       34.33
                               64.89
                                           ---99-22,
                       86-9
                               647
                                           =101.6
                                      1·19=100·97, Rosales.
0·84=100·60, Marignac.
          "
                       86-67
                               63.11
          "
                                                                   G.=3.6.
 5.
                       36.60
                               62.66
                                      0.52, Cu 0.19=96.97, Erd. G.=3.124.
0.71=100.16, Erd. G.=3.661.
 6. Röraas,
                       84.40
                               61 86
                       87-36
 7. Tyrol,
                               62-09
 8. Greiner, Tyrol,
                      37.30
                               62.60 1.08=100.98, Jacobson. G.=3.678.
 9. Monroe, N. Y.,
                       37<del>2</del>0
                               59-02 2-08, ign. 1-08=99-33, Smith and Bru
                       87-03
                                   61.90
                                                085=9978,
11. Lincoln Co., N.C., 37-60
                               60.40 1.60 "
                                                     -=99 60,
```

B.B. unaltered. With borax slowly fuses to a transparent colorless glass. cobalt solution, a dark blue.

This species occurs principally in gneiss and mica slate. Transparent crystals occur at St. Gothard in Switzerland; at Greiner and Pfitsch (Rhœtizite or white variety) in the Tyrol; also in Styria, Carinthia, Bohemia; at Pontivy, France; Villa Rica, South America.

In Massachusetts, at Chesterfield, it occurs with garnet in mica slate; Worthington and Blanford in good specimens. In Connecticut, at Litchfield and Washington in large rolled masses with corundum and massive apatite; at Oxford, near Humphreysville, in masses late. In Vermont, at Thetford and Salisbury; in New York at Monroe, Orange Co., (Monrolite). In Pennsylvania, in fine specimens near Philadelphia, on the Schuylkill road near the Darby bridge; near the Schuylkill on the Ridge road, back of Robin Hood Tavern; at Leiperville; at East and West Branford and Darby, Chester Co.; at Morris's Ferry, Delaware Co. In Maryland eighteen miles north of Baltimore, at Scott's mill; in Delaware, near Wilmington. In Virginia at Willis's Mt., Buckingham Co., and two miles north of Chancellorville, Spotsylvania Co. In North Carolina, on the road to Cooper's gap in Ruther-ford Co., near Crowder's Mtn. In short crystals at Bellows Falls, Vt., in gneisa, at Westfield, and Lancaster, Mass., and at Jaffrey on the Monadnock Mt., N. H. A black variety associated with rutile occurs in North Carolina.

Kyanite, when blue and transparent, and in sufficiently large pieces, is employed as a gem, and somewhat resembles sapphire. The name is from sures. Since. The name sappare arose from a mistake by Saussure in reading a label of this mineral on which it was called sapphire. Disthene is from sis, twice, or of two kinds, and strong, alluding to its unequal hardness and electric properties in two different directions.

Bamlite, Erdmann, (J. f. pr. Ch. xxxi, 165), from Bamle, Norway, has the structure and appearance of some Kyanite, occurring in columnar somewhat plumose forms, silky in lustre, with one perfect cleavage. H.=5-7. G.=2.984. Greenish-white or bluish green. The analysis by Erdmann (loc. cit.) gave Si 56.90, £1 40.73, Fe 1.04, Ca 1.04, F trace=99.71. There is an excess of silica. But according to recent observations by Mr. L. Semann, there are minute prisms of quartz among tha fibres of the Ramilia — bit fully account for this area. the fibres of the Bamlite, which fully account for this excess.

Xenolite of Nordenskiöld resembles kyanite as well as bucholzite; and the analysis differs no more from the accepted formula than some that have been made of each of these species. Komonen obtained (Act. Soc. Sci. Fenn., i, 372, Pogg. lvi, 643) Silica 47.44, alumina 52.54=Al Si. H.=5. G.=3.58. From Peterhoff, Finland.

ALTERED FORMS.—Wærthite appears to be an altered or hydrous kyanite, which it resembles. H.=7.25; white and translucent. Hess obtained (Pogg. xxi, 73) Si 40.58, Ål 53.50, Mg 1.00, H 4.63=99.71. B.B. infusible. From near St. Petersburg. Hydrobucholzite of Thomson is probably of similar origin. Thomson obtained (Min. i, 237) Si 41.35, Ål 49.55, H 4.85, gypsum 3.12=98.87. Probably from Sardinia.


Kyanite has also been observed altered to tale and steatite.

SILLIMANITE, Bowen. Bucholzite, Brandes. Fibrolite, Bournon.

Triclinic. $I: I'=98^{\circ}$, but varying to 110°, and larger when the faces are much striated; $O: I'=105^{\circ}$, $O: m=133^{\circ} 30'$, $I': m=120^{\circ} 30'$, $O: a=130^{\circ}$, D., (but only approximations, as the ter-

minal planes were rough and uneven.) Cleavage: perfect, parallel with the longer diagonal, affording a brilliant surface. Also compact or loose fibrous; and columnar massive.

H.=6-7.25. G.=3.238, from Norwich, Dana, 3.232. ib., Brush; 3.259, Yorktown, Norton; 3.239, bucholzite of Chester, Del., Erdmann. Lustre vitreous, approaching subadamantine. Color hair-brown, grayish. Streak uncolored. Translucent—transparent.



Bucholzite and fibrolite are generally fibrous massive, sometimes approaching distinct prisms, like those of sillimanite; the lustre approaches adamantine as in sillimanite. The colors are grayish, whitish and pale brown.

Composition.—Al Si[‡], like Kyanite=Silica 27.0, alumina 63.0. Bucholzite and fibrolite of Bournon afford the same, according to Silliman, Jr. Most analyses of bucholzite give Al Si=Silica 46.9, alumina 53.1. Erdmann's (No. 9) corresponds to Al Si ½. Bowen's and Hayes's analyses of Sillimanite afford Al Si =Silica 42.3, alumina 57.7.

I. Sillimanite.—1, Bowen, (Am. J. Sci. viii, 113); 2, Hayes, (Alger's Min. p. 601); 3, Connel, (Jameson's J. xxxi, 232); 4, Norton, (2d edit. of this work, 378); 5, Staaf, (Jahresb. xxv, 348); 6, Silliman, Jr., (Am. J. Sci. [2], viii, 386. II, Becholzite.—7, Brandes, (J. de Pharm. xci, 237); 8, Thomson, (Ann. Lyc. N. York, iii, and Min. i, 235); 9, A. Erdmann, (K. V. Ac. H. 1842, 19); 10, B. Silliman, Jr., (Am. J. Sci. [2], viii, 386). III, Fireclite.—11, 12, B. Silliman, Jr., (Am. J. Sci. [2], 8, 388); 13, Chenevix:

			Si	X 1	Fe
1.	Chest.Ct., Sillim	anite,	42.66	56.111	1.999, H 0.510=99.286, Bowen.
2.	100	"	42.60	54.90	1·10, Ca 0·31, Mg 0·4=99·31, Hayes.
3.			3675	58.94	0.9=96.68, Connell.
4	Fairfield, N.Y.	48	37 700	62.750	2.287=102.739, Norton.*
5.	Chester, Ct.,	15	87.362	58.622	2·174, Mg 0·398, H 0·428=98·984, Staaf

Prof. Norton states that in his analysis the excess of alumina was probably owing to the presence of aluminate of potassa, which remained with the alumina after separating the peroxyd of iron by caustic potassa; subtracting this excess, the analysis corresponds to those by Silliman.

```
to the tentage of
                                                                                                                                                                                                                                                                                                                                                                                                       or Comment of the comment
                                                                                                                                                                                                                                                                                                                                                                                             CHEST THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF THE STATE OF
                                                                                                                                                                                                                            .-..
                                                                                                                                                                                                                                7-4
                                                                                                                                                                                                                                                                                                                                                                                             - As is expensed tillings
á١
                                                                                                                                                                                                                                                                                                              نيذ ها
                                                                                                                                                                                                                                                                                                            12 15
                                              والمصرفين والماء والمراج المايات
                                                                                                                                                                                                                                                                                                                                                                                                                     - 42 -- ==
                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       - en en Hillman
                                                                                                                                                                                                                                                                                                                                                                                                                     ......
                                                                                                                                                                                                                                                                                                                                                                                             Teneral Beneral
                                                                                                                                                                                                                              . ب. سوئ
                                                                                                                                                                                                                                                                                                              ي...و
```

23 more displayed. With some mowing fines to a transparent colories give. #The inhalt of tunes buttering

favore control of the favorest and streams indisting the favorest parts as a control product of the favorest control of the fa seen Control Control presentation with this tier towns and honester. Printed table med a function or secuentially not with. It was secure in the town if Time Sown West, water to Told shout ten illes northeast if ring ring, near the residency force of the decides to I tentown Post, then associated with monagate, resiokke sad magnet i om i me imperale bet betidet blik ikken min klimagit kle

Problems who is greatly increment from Faces in the Tyrol. A similar variety secret at the content from the Leavising near the Queenshirty force of Commont and Similar variety force of Commont and Similar variety force of Commont and Similar variety. It is Humphreys the common Wirelester, Mass.; in Assa. and Leapers of Faces appropriately the relimination.

The commonte was caused after First relimination.

None In this art advisor of this work, the author placed together Equatic and Sourceaute. The angles I. I are approximately alike, and if polished prisms if the father minoral could be found, they might prove to be much nearer. The terminal planes orangered and so cough that were other points of identity made out, we should not sely upon town as an denne of a real difference. But the two minerals, as G Rose whates (Kryst Coem. p. 20). differ strikingly in appearance, and widely in specify gravity, and they make not seen found accordated together although both occur in the same class of rocks. We therefore alopt the view of Rose, and make them for the present distinct species

SAPPHIRINE, Stromeyer

Trimetric? Shows colors with polarized light, hence not monometric. Occurs granular massive.

II. 7 8. G. 3:42 3:48. Lustre vitreous. Color pale blue or green. Translucent.

Composition. Contains 2 Mg, 4 Al, 1 Si, which, if a portion of the alumina equal to the adea (or 1A1) acts as acid, becomes Mg* (Si, A1)2+3 Al·Si, A1;2=(1Mg+ (A)ySi, A) → Silica 14%, alumina 657, magnesia 195. Some relation in composition to clintonite and chloritoid.

Analysica 1, Stromeyer, (Untersuch. i, 391); 2, 3, Damour, (Bull. Soc. Gool d. Fr. 1849, 817):

```
Ri
                 Мg
                        Ċъ
                             ۴e
1 11 61
        63:11
               16.85
                      0.38 8.92
                                  ign. 0:49=9978, Stromever.
 II -NN
         63:31
                19:06
                       --- 2:09
---- 1:90
                                   =99.34, Damour.
8 14 81 63:20
                19.50
                                  =99.44,
```

Il B alone and with borax infusible, unaltered. Associated with mica and asthophyllite at Fiskenses, in Greenland. The name alludes to the sapphire color.

[·] One of Hournon's own specimens, received by Col. Gibbs (from whom the Yale Cubinet was obtained) from Count Bournon himself.

ad the whole heated, the color becomes green and it fuses to a clear globule, of a

Wolfram is often associated with tin ores; also with galena, in veins traversing graywacke; also in quartz, with native bismuth, tungstate of lime, pyrites, galena, blende, &c. It occurs at Cornwall, much to the detriment of the tin ores; in fine blende, &c. Schlaebenwald Schneeberg. Gever, Freiberg, Altenberg, Ehrenfrieders. dorf, Zinnwald, and Nertschinsk, and other places mentioned above; at Limoges, in France; near Redruth in Cornwall; in Cumberland, (both varieties, the first at Lochfell, the second at Godolphin's Bale); and on the island of Rona, one of the Hebrides. The crystals of Zinnwald are remarkable as hemitropes.

In the United States it occurs at Lane's mine, Monroe, Conn., in quartz, associated with native bismuth, and the other minerals above mentioned, often pseudomorphous after tungstate of lime; also reported from near Mine La Motte, Missouri; in small quantities in Trumbull, Conn., at the topaz vein; massive and in crystals on Camdage farm, near Blue Hill Bay, Me.

This species is shown to be isomorphous with columbite by G. Rose, (Pogg. lxiv, 171). Descloizeaux found in the angles of Wolfram, some evidence that the crystals were monoclinic. But G. Rose shows from the twins that the form is trimetric, and not oblique.


A mineral from Schlackenwald, occurring with fluor spar and apatite, in fine meedles of a brownish-red color, and G.=6.45, probably an altered wolfram, afforded Rammelsberg on analysis, (Ramm. 3d Supp. 127),

₩ 67 05, Fe 6 72, Mn 19 78, Ca 3 02, **X**l 1 01, Si 0 08, P and F 0 61, ign. 0 78=100.


ALTERED FORMS.—Wolfram occurs altered to Scheelite, by a substitution of lime for iron.

COLUMBITE, Hatchett. Tantalite, (in part). Tantale Oxidé, H. Niobite, Haid. Baierine, Beud. Torrelite, Thom.

Trimetric. $I: I=100^{\circ} 40', 0: 1\bar{\imath}=133^{\circ} 22\frac{1}{3}'; a:b:c=1.0584$: 1 : 1.2059.



Bodenmais



Middletown, Conn.

```
O: 10^{\circ} 34'.
                             1:1(\text{brac.})102^{\circ}\ 58'.\ i_{2}:i_{2}(\text{mac.})134^{\circ}\ 58'.
                             1: 1(\text{mac.})117^{\circ} 53'. ii: I(ib.) 140° 20'.
0: i=144° 48'.
                             1:1(bas.) 107° 56′.
                                                          ii:ii=158^{\circ}6'.
0:1=126^{\circ}2'.
0:18=136^{\circ}36'.
                             18: 18 (brac.) 150° 17'. is: is (brac.) 136° 12'.
                             26: 26 (ib.) 160^{\circ} 29'. ii: 18 = 104^{\circ} 52'.
O: 26 = 119^{\circ} 11'.
                             21: 21 (top) 59° 20′.
                                                          \tilde{u}: 1=121^{\circ} 3\frac{1}{2}'.
0:21=119^{\circ}40'.
i : i (top) 141° 8'.
                             ii: ii = 157° 29′.
                                                          \tilde{u}: 1\tilde{s} = 129^{\circ} \ 36'.
$i : $i (ib.) 109° 35'.
```


Occurs in Brazil, in the mining district of Villa Rica, in chlorite slate resting on sand-tone. The crystallization of this species is elaborately detailed by Schabus in the Transactions of the Royal Academy of Vienna, vol. vi.

Euclase receives a high polish, but is useless as an ornamental stone on account of its brittleness. Named by Hally from st. costly, and chapt to break.

SPHENE Titanite Menakerz Menachine Ore, Wern Titane Silico-calcaire, E. Lederite, Shepard Greenovite, Dur. Spinthère Pictite, Saua Arpidelite.

Monoclinic. $C=60^{\circ} 27'$; $I: I=113^{\circ} 25'$, $\theta: 1i=159^{\circ} 34'$; a:b:c=0.5678:1:1.326.*

 $O(y): iii(P) = 119^{\circ} 33$. $-1(l_1:-1(l_2=133°45')$. $(Ay): 10(x)=155^{\circ} 55^{\circ}.$ $-2(t):-2(t)=110^{\circ}$ 54'. $(hy): 4v = 123^{\circ} 52'$. 22(e): 22(e)=157° 12'. $12(w): 12(w) = 164^{\circ} 32'.$ $O(y): I(r)=114^{\circ} 21'.$ $O(y): 1(z) = 154^{\circ} 13'$. $I(r) \cdot I(r) = 113 \cdot 25'$. $O(y): 2(n)=141^{\circ} 36$. $O(y): -1(l)=139^{\circ} 20$. $63 (u) : ii(b) = 140^{\circ} 26'.$ $-33(m):-33(m)=76^{\circ}1'$. $O(y): -2(t) = 109^{\circ} 37$. $1(z): 1(z) = 149^{\circ} 38$. -33 (m): $n(b)=141^{\circ}59$. $ii(P): i3(o)=167^{\circ} 40'.$ $ii(P): ii(b)=90^{\circ}.$ $2(n): 2(n)=136^{\circ} 4'.$ 449



* Authors generally take P as the base of the for dancertal prismagase the plan replacing the front angle, and l as the lateral prismatic planes. Above, in figure

L. Mitchill stated (Med. Repos. vol. viii) that it was taken from a spring at New London, Conn. No locality has since been detected at that place. But the rediscovery of it at Haddam, first published by Dr. Torrey, (Amer. J. Sci. iv, 52), has led to the belief that the latter was its original locality. It has since been discover-

ed more abundantly near Middletown.

At Haddam it occurs in a granite vein, with chrysoberyl, beryl, and automolite; also two miles from the chrysoberyl locality, (anal. 14); also at the iolite locality. Finer crystals come from a feldspar quarry near Middletown, along with albite; figure 503, represents one with brilliant faces three quarters of an inch long; another described by Professor Johnston, (Amer. J. Sci., xxx, 387), weighed before it was broken, fourteen pounds; and the part figured about six inches in length and breadth, weighed 6 lbs. 12 oz.; it exhibits the faces ii, ii, i2, I, i3, ½, and another imperfect plane, which appears to be 13. Chesterfield, Mass., has afforded some fine crystals, associated with blue and green tournalines and beryl in granite; also Acworth, N. H., but this locality is now apparently exhausted. It has also been observed at Beverly, Mass.; at Plymouth, N. H., with beryl; at Greenfield, N. Y., with chrysoberyl.

Rdefonsite.—A columbite from Ildefonso, Spain, with a submetallic vitreo-adamantine lustre, and I: I=121° 46', nearly the angle of the prism 2% above; G.=7.416,

Haidinger.

SAMARSKITE, H. Rose. Uranotantal, G. Rose. Yttroilmenite, Herm.

Trimetric: angle of prism i_2 , 135° to 136°, (whence $I: I=100^{\circ}$ 40′ to 101° 40′, near columbite). Usually in flattened grains.

H.=5.5—6. G.=5.614—5.68, Uranotantalite; 5.398—5.45, Yttroilmenite; 5.45—5.69, North Carolina. Lustre of surface of fracture shining and submetallic. Color velvet-black. Streak dark reddish-brown. Opaque. Fracture subconchoidal.

Composition.—Analyses: 1, 2, 3, Peretz, under the direction of Rose, (Pogg. lxxi, 157); 4, Hermann, (his latest results, J. f. pr. Chem. 1, 178); 5, T. S. Hunt, (Am. J. Sci. [2], xiv, 341):

	Met. acids.	U(#1)	Fe	Y	Mg	Ca & Mn
1.	56.38	14.16	15.48	9.15	0.80	0.92=96.84.
2.	56.00	16-70	15.90	11.04	0.75	1.02=101.41.
3.	55.91	. 16.77	15.94	8.36	0.75	1.88=99.61.
4.	56.36	U16.63	8.87	13.29		La 2.85 Mn 1.20, 33=100.03, Herm.
5. N. Carolina,	Ĉb 54·81 €	317-08	14.07	11.11	De, La 3.95	, ign. 0.24=101.21,

The acid is the columbic with some tungstic, according to Rose. Hermann's name yttroilmenite alludes to the supposed new metal ilmenium, alledged to exist in this species; in his recent analysis he makes the acid columbic with a little

ilmenic acid.

Heated slightly in a glass tube, it decrepitates, disengages sometimes a little moisture, and glows like gadolinite, becoming of a brownish-black color. In the platinum forceps it melts on the edges to a black glass. On platinum wire with borax the pulverized mineral fuses easily, and forms in the inner flame a yellowish glass, and in the outer a yellowish-green glass; with muriatic acid forms with difficulty a green solution.

Uranotantalite occurs in reddish-brown feldspar, with crystallized æschynite, in the Ilmen mountains, near Miask in the Ural. The largest pieces met with were of

the size of hazel-nuts.


If the occurring prism of Samarskite is i3 instead of i2 (as in Mengite), then I: I becomes 100° 57' to 102° 20'.

Families is also seek and the end of the and products. In The Ending Engage End of the complete of the content of the end

English of the control of the contro

টি TEVACTE দি ও চিন বিচন কৈ বিচন কৈ একুমান একুমান দি জি মানা টি সামান একুমান ভিতৰত দিন এই

Est with Level of Section 1. Set with the residence of the mention of the set of the section of the set of the section of the



POLYCRASE. Polykras, Scheerer, Pogg. lxii, 480.

Trimetric. $I: I=95^{\circ}, O: 1i=134^{\circ} 15'; a:b:$ a=1.02655: 1: 1.0913. Observed planes as in the figure.

 $0:2i=118^{\circ}.$ $1:1(\text{mac.})=112^{\circ} 32'$. $O: 1=125^{\circ} 41\frac{1}{6}'$. $1:1(brac.)=106^{\circ} 24'.$


 $O: 18=139^{\circ} 59'$. $i\vec{3}$: $i\vec{3}$ (ov. $i\vec{i}$)=140°.

 $1 \tilde{s}$: $1 \tilde{s}$ (mac.)= $96^{\circ} 40'$. $i \tilde{s}$: $1 \tilde{s}$ = 160° .

 $18:18(brac.)=152^{\circ}.$

i.

Crystals thin linear. Cleavage none. H.=5.5. G.=5.09—5.12. Lustre bright. Color black; in splinters brownish. Streak grayish brown. Fracture conchoidal.



Composition.—Near Polymignyte, but containing in addition columbic acid, pro-**Soxyd of uranium, and but little lime with no manganese. B.B. decrepitates, glows and becomes brown, but infusible. Yields with borax a glass which is yellow in the outer flame and brown in the inner. With soda on platinum gives a weak reaction of manganese. Dissolves imperfectly in muriatic acid, and perfectly in heated sulphuric.

From Hitteroe, Norway, in granite with gadolinite and orthite; crystals 1 to 11 inches long. Named from molos, many, and spaces, mixture. On crystallization of Polycrase, see Am. J. Sci. [2], xviii, 46, 47.

ÆSCHYNITE, Berzelius, Jahresb. ix, 195.

Trimetric. $I: I=90^{\circ}$ 34', $O: 1\bar{\imath}=145^{\circ}$ 58'; a:b:c=0.675: 1:1.01. Observed planes, $I, i\bar{\imath}, 2\bar{\imath}, 1\bar{\imath}, i\bar{\imath}: i\bar{\imath}=127^{\circ}$ 19', (Rose), 2 $\bar{\imath}: 2\bar{\imath}(top)=73^{\circ}$ 34', $1\bar{\imath}: 1\bar{\imath}(mac.)=136^{\circ}$ 36', (brach.) 83° 4', (basal), 112° 52'. Cleavage: $i\bar{\imath}$ in traces. Crystals usually striated and imperfect.

H.=5-6.G = 4.9 - 5.14Lustre resinous — submetallic, nearly dull. Color nearly black, inclining to brownish-yellow when translucent. Streak gray, or yellowish-brown, almost black. Subtranslucent—opaque. Fracture small subconchoidal.

Composition.—Analyses: 1, Hartwall, (Pogg. xvii, 483, Jahresb. ix, 195); 2, Hermann, (new anal. J. f. pr. Chem. l. 198):

- 1. Ti 560, Zr 200, Ce 150, Ca 88, Fe 26, Sn 05=979, Hartwall.
- 2. Ti 25.90, Ob 33.20, Ce 22.20, Ce 5.12, Fe 5.45, La 6.22, Y 1.28, H 1.20=100.57, H.

In a matrass yields water, and in an open tube traces of fluorine. B.B. on charcoal swells and becomes yellow, but does not fuse, though forming a black slag on the edges. With borax readily forms a dark-yellow glass, which is colorless on cooling, and with tin in the inner flame becomes red; with salt of phosphorus yields a transparent colorless bead, which with more of the salt appears yellow and clouded. Affords some tin.

From Missk in the Ural, in feldspar with mica and zircon. Named from according to the inability of chemical science, at the time of its discovery, to separate the two unlike substances, titanic acid and zirconia.

I. Maynesia Tourmaline. (4,E.11—1847); mean 1846.

			•												
		=	Ŧ.	<u></u>		ź	şi	÷	Ň	ć	ź	Æ	ج	<u>-</u>	
_	. Brown, Gouverneur,	0.00	N. X.	:	H		-		=	2	¥:-	Ð.:. 0		ź. :	<u> </u>
=1		-	XTX	-	=		=		=======================================	9 =	: H	-	<u>::</u>	<u>-</u>	Ξ
	Greenin	180.1	: ':	ĭ	ž		¥.		: e	X	7	E: 0		- -	==
•	4. Hrown, Critord, N. H.,	X.O.O.		9	=======================================		7.51	=======================================	CH.C.	(.)	<u>-</u>	Ë	7::0	ē.	100 15.
•		K9:1	9.68	==	<u> </u>	•	=	HG. C	3	ž	×	-		#	Ē
•	Black,	3 064	Fab. 2.80	XC. A	33 63		2	1.15-0	91.01	S S	== ;;	7K-0	<u>7</u> .	90.5	100
		=	. Iron m	minen	II. Iron magnesia Tourmaline,- G. 3106-312; moun 3-11.	dine.	: ::	## 99		3.11.					
7	Mack, Geenland,	:/0	::	9 :: ::	=		50.7	47.0	14 2	99	9.5	: :	=	F.	je Je
æ.		=======================================	:= :::	=	- F	20 01	E		Ξ	T., u	80 :-	R /, O	<u> </u>	<u> </u>	Ē
æ.	Brownish black, St Gothard,	3.455	3	: :			:: ::	Ξ	<u>,</u> ,,,,,,	==	=	XC	7 <u>1</u> 2	= = =	Ξ
Ę		5. I s	9		t,>: 01;		=======================================	90.1	00. N	=	9.	R.), O	E	<u>z</u>	100
=	:	:: ::	346.345		Ξ.		HO =	3	ų. K	ž	÷.	×		: -	Ë
<u>:</u>	" I nity, Me.,	10.1	36 70	- - -	₹		N	¥1:-::	EH: 0	:: -	Ξ	3		3.	<u></u>
			•	11 11 11	A One las Punerba.	=	h Chryschmy; health	herally							
		Ξ	. Iran 7	ourma	III. Iron Tourmaline; Mack.		E	g ==	nin nin men nin	и·10,					
<u> </u>	Bovey Travey,	305.8	37, 00	5	80 53		E		#4.	Q.0		0.48	-	3-	100
Ξ	14. Alabaschka Cral,	:- :- :-	4. ':		9 TK		7:01	9. N	1.76	SH.C	- -	23.0		=	100
2	Sonnenberg, Hartz,	<u> </u>	36.51		N. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1.	====	, =- :x		¥	7. J. O	5.	74.0		÷	Ξ
Ξ	Krumman, Bohemin,	9:138	:: :::		971E		¥5.5		¥.	7-0	ij	SK. 0		<u> </u>	100
		IV. Iru	. Manga	1.	IV. Jeon Manganon Lither Tourmaline,(L: 294-2011; mean Book)	urmalis	r(1,	<u>-</u>	11.18	menn B	.OM33,				
11	Bluish black, Surapulsk, Ural,	3.163	38.30	2	316-17	2	9::0	¥. ::	19.0 19.0	1,7.0	7.8.4	=======================================	3	1.70	0.00
ž		:: 6.::	 	<u>-</u>	98.00	<u> </u>	<u>-</u> :	•	2:3	 	3	¥.:	•	9.3	Ξ
<u> </u>	(Jeen)	=======================================	£	=	21 AS	Ţ.,	-	,	£.	ž	9.7 7.	<u>:</u> :	1.1.0	- 311 %	-100
8	: :	690.		: :	\$0.0\$	1.7X	NO.S	•	<u>=</u> ;	C.KK	7.310	VH. 0	=	5.7	Ë
2 2	· Strayl, · · · (thustortheld Mass	3.107			01. HR	H-1	X 1.0	00.7	# / ₋ 0	7		78.0	2.5	20.7	200 - 100
*				2	-	5	10.7	Ž.					*	•	

YTTRO-TANTALITE. Tantale Oxidé Yttrifère, H.

Three varieties; the black, yellow, and brown or dark. Black: indistinct traces of crystallization in four- or six-sided irregular prisms and plates. H.=5.5. G.=5.395, Berz., 5.67, Rose, and 6:40 after heating. Lustre submetallic. Color ironblack. Streak gray. Opaque.

Yellow: not crystalline, and occurring in laminæ in the fissures of feldspar. H.=5. G.=5.882, Ekeberg. Lustre resinous on the surface, vitreous in the fracture. Color yellowish-brown—

greenish. Streak white. Opaque.

Brown: occurs with the yellow in thin plates, or rarely grains presenting no trace of crystallization. H.=4.5-5. Lustre vitreous, inclining to resinous. Color black, with a very light shade of brown, slightly yellow when in thin plates by transmitted light; streak white.

Composition.—Ř*(Ta, W, ♥). Analyses: 1—4, Berzelius, (Afhandl. iv, 268, 272, and Schw. J. xvi, 461); 5, H. Rose, (Pogg. lxxii, 155):


	Ta	Ŵ	₽	Ť	Ĉa.	₽e
 Yellow, Y ³ (Ta, ₹), 	60.12	1.04	6.62	29.78	0.20	1.16=99.28.
0 "	59.50	1.25	3.23	29.90	8.29	2.72==99.89.
8. Black, (Y, Ca, Fe) (Ta, W),	57 ·0 0	8.25	0.20	20.25	6.25	3·50 == 95·75.
4. Brownish-black, (Y, Ca) ² Ts 5. Black (after ignition),	,51.82	2.59	1.11	88.52	8-26	0.55=97.85.
5. Black (after ignition),	58.65	0.60	8·94	21.25	7.55F	e6 29, Mg 1 40,
, , ,					ີກາ ()•4()	=100:08. Rose.


Loss in analysis 5 by ignition, 8.9—5.54 per cent.; the specimen was from Ytterby. B.B. infusible alone, but decrepitate and assume a light color. The black variety froths and fuses with carbonate of soda. They dissolve in borax, but are not acted on by acids.


These varieties of yttro-tantalite occur in Sweden at Ytterby, in red feldspar, and at Broddbo and Finbo, near Fahlun, imbedded in quartz and albite, associated with garnet, mica, and pyrophysalite.

CROCOISITE, Kobell. Chromate of Lead. Red Lead Ore. Krokoit, Breit. Rothbleierz. Plomb Chromaté. Lehmannite.

		(9		
					1è
11		ri (1		11
2i			-1		21
41		11	4		
ii	<i>i</i> 2	$\frac{3}{2}$	I	12	it
	-22				24
-1 <i>i</i>	-		-1		12
			7		11







Monoclinic, $C=78^{\circ}$ 1'; $I: I=93^{\circ}$ 44', $O: 1i=137^{\circ}$ 31'; a:b: c=0.9773: 1: 1.044.

Cleavage: I tolerably distinct; O and ii less so. Surface I streaked longitudinally; the faces mostly smooth and shining. Also imperfectly columnar and granular.


H.=2·5-3. G.=5·9—6·1. Lustre adamantine—vitreous. Color various shades of bright hyacinth-red. Streak orange-yellow. Translucent. Sectile.

Composition.—Pb Ör=Oxyd of lead 68.7, chromic acid 31.3. Analyses: 1, Pfaff. (Schw. J. xviii, 72); 2, Berzelius, (ib. xxii, 54):

Blackens in the blowpipe flame, and decrepitates if quickly heated, but may be fused to a shining slag, containing globules of lead. It undergoes a partial reduction in glass of borax, at the same time coloring it green. Dissolves with effercencence in nitric acid, and produces a yellow solution. With soda yields easily metallic lead.

Occurs at Nischne Tagilsk in the Ural, and in narrow veins, traversing decomposed gneiss, and associated with gold, pyrites, galena, quartz, and vauquelinite; in Brazil, at Congonhas do Campo, in fine crystals in decomposed granite; at Retbanya in Hungary, at the mine of St. Anthony; at Moldawa in the Bannat; on Luzon, one of the Philippine Islands.

VAUQUELINITE. Chromate of Lead and Copper, Phil.



Monoclinic. Crystals usually minute, irregularly aggregated. Twins: annexed figure; face of composition a plane on the acute solid angle: O:O (of the two individuals)=134° 30′; O:ii=149° nearly. Also reniform or botryoidal, and granular; amorphous.

H.=2·5—3. G.=5·5—5·78. Lustre adamantine to resinous, often faint. Color dark-green to brown, sometimes nearly black. Streak siskin-green or brownish. Faintly translucent—opaque. Fracture uneven. Rather brittle.

Composition.—Ču²Ör²+2Pb²Ör²=(Ču, Pb)°Ōr²=Oxyd of lead 61.2, oxyd of copper 10.9, chromic acid 27.9. Analysis by Berzelius, (Afhandl. vi, 246):

Pb 60 87, Ou 10.80, Or 28.33=100.

B.B. on charcoal slightly intumesces and fuses to a gray submetallic globule, yielding at the same time, small beads of lead. With borax or salt of phosphorus affords a green transparent glass in the outer flame, which in the inner after cooling is red to black, according to the amount of mineral in the assay; the red color is more distinct with tin. Partly soluble in nitric acid.

Occurs with erocoisite at Beresof in Siberia, generally in mammillated or amorphous masses, or thin crusts; also at Pont Gibaud in the Puy de Dome; and with the crocoisite of Brazil.

At the lead mine near Sing Sing, it has been found by Dr. Torrey in green and brownish-green mammillary concretions, and also nearly pulverulent.

John describes a greenish or brownish chromo-phosphate of lead and copper, from Beresof, Siberia, as occurring in small crystalline concretions, having the surface covered with capillary prisms; H.=2-3; opaque to subtranslucent; fracture uneven; powder dull greenish. Analysis afforded (v. Leonh. 1845, 67) Pb, Cr 450, Pb 190, Cu 11 20, P 4 10, Cr 7 50, manganese tr., H 1 78, impurities 11 42. To a large extent soluble in nitric or muriatic acid.

MELANOCHROITE, Hermann. Phonikochroite, Glocker. Subsesquichromate of Lead, Thom. Phonicite.

Trimetric? Crystals usually tabular, and reticularly interwoven.

Cleavage in one direction perfect. Also massive.

H.=3-3.5. G.=5.75. Lustre resinous or adamantine, glimmering. Color between cochineal and hyacinth-red; becomes lemon-yellow on exposure. Streak brick-red. Subtranslucent-opaque.

Composition .- Pb2 Cr2=Chromic acid 23.3, protoxyd of lead 76.7. Analysis: Hermann, (Pogg. xxviii, 162):

> Protoxyd of lead 76.69=100. Chromic acid 23.31,

The same result was obtained by G. Rose, (Leonh. 1889, 575).

B.B. on charcoal fuses readily to a dark mass, which is crystalline when cold. In the reducing flame on charcoal, lead is sublimed. Gives the reaction of chrome

Occurs in limestone at Beresof, in the Ural, with crocoisite, vauquelinite, pyromorphite, and galena. Named from pelas, black, and xpoa, color.

DECHENITE, C. Bergemann, Pogg. lxxx, 393.

In small botryoidal masses; texture crystalline. Some appearances of a rhombohedral cleavage.

H.=4. G.=5.81. Lustre of fresh fracture greasy. Color when purest dull-red; also yellowish. Streak yellow.

Composition .- PbV=Vanadic acid 45.34, oxyd of lead 54.66. Analyses, by C. Bergemann, (loc. cit.):

	V	Pb
1. Dull-red,	47.164	52.915=100.079.
2.	46.101	53-717=99-818.
3 Vellominh	49.97	50.57 =99.84

B.B. alone fuses easily to a yellowish glass; on charcoal does not decrepitate, but forms a yellowish-green pearl which yields a slag containing some grains of lead. Sometimes traces of arsenic with more of the assay. With soda a white enam-

el containing grains of lead.

From the Lauter Valley in Rhenish Bavaria, near Nieder-Schlettenbach, where it

occurs in the variegated sandstone.

DESCLOIZITE, A. Damour, Ann. Ch. Phys, 1854.

Trimetric. $I: I=100^{\circ} 28', O: 1i=$ 143° 14'; a:b:e=0.747:1:1.2052. Angles (Descloizeaux):

源: 鴻=122° 6'.

1i: 1i (top)=116° 25'. 12: 12 (adj.)=127° 10′. 12: 12 (ov. 1i)=115° 10'.

12: 1%=147° 35', 0:1%=148° 124'.



sometimes bright green, perpendicular to cleavage surface, and brown and less translucent at right angles to this direction. Streak usually white; of dark-green varieties, lighter than the color. Subtransparent—subtranslucent. Sectile in a high degree. Thin laminæ flexible, but not elastic. Feel greasy.

Varieties.—Foliated Talc.—Purest crystalline talc, consisting of easily separated folia, having a greasy feel, and presenting light-green, greenish-white, and white colors. G.=2:55-2:78.

Bospetone or Steatite, (Specketein of the Germans).—Coarse gray and grayishgreen massive varieties, generally granular. Also of fine texture, and grayishgreen to white, occasionally yellowish or reddish; sometimes lamellar, but usually compact. Very greasy to the feel, or like soap. G.=265—28 The Briançon variety is milky-white with a pearly lustre. Pot stone or Lapis ollaris includes the coarser granular specimens of dark color, and more or less impure. Some Agelmatolite is of this nature.

Indurated Talc.—An impure slaty tale, with a nearly compact texture, and se-

perior hardness to common talc.

Tulcose Slate.—A dark slaty rock, having a somewhat greasy feel, consisting largely of tale, mixed intimately with more or less feldspar and quarts.

Composition.—Mg^a Si^a+2Ĥ—Silica 62·14, magnesia 32·92, water 4·94—100. The more recent analyses give 4 to 5 per cent. of water. Analyses: 1, 2, Kobell, (Kasta. Arch. xii, 29); 3, 4, Delesse, (Rev. Scientif. etc.); 5, Marignac, (Bib. Univ. de Gan. 1844); 6, 7, Scheerer, (Pogg. lxxxii, 321, Am. J. Sci. xiv); 8, Tengatröm, (Jahresh. iv, 156); 9, 10, 11, Lychnell (Pogg. xxxviii); 12–17, Scheerer and Richter, (loc. cit. where are also other anal.); 18, Kersten, (J. f. pr. Ch. xxxvii, 164):

```
Si Mg Fe H <del>A</del>l
62.8 82.4 1.6 2.8 1.0=100.1, Kobell.
   Fol. Talc, Greiner,
 2
                Katherinen., 62-8
                                       81.92 1.10 —
                                                          0.60, Ca 1.92=98.84, Kob.
 8.
                Zillerthal,
                                63.0 83.6 tr. 3.4
                                                                =100, Delesse.
 4.
5.
        "
                R. Island,
                                6175 8168 170 8.88
                                                               =98 96, Delesse.
        "
                Chamouni,
                                62:58 35:40 1:98 0:04
                                                                =100, Marignac.
6. " Tyr
7. " Rör
8. Steatite, Abo,
                                62:38 31:19 1:42 4:73 — Ni 0:20=99:92, Seh.; G. 2:69. 61:98 30:41 1:59 5:04 0:04=99:06, Seh.; G. 2:78.
                Tyrol,
Röraas,
                                63 95 28 25 — 271 078, ign. 8 94 Fe 0 6=100 23, T.
 9.
              Sala,
                                68:13 84:80 2:27 ---
                                                           ----99.70, Lychnell.
10.
              Mt. Caunegou, 66 70 80 23 2 41
                                                               ==99 34, Lychnell.
11.
              Scotland,
                                64.53 27.70 6.85
                                                               -=99 08, Lychnell.
        "
              Wunsiedel,
                                62 03 31 44 1 88 4 96 -
                                                              -=100·31, Scheerer.
12.
              Parma, 62:18 30:46 2:53 4:97 tr. =100:14, Richter.

Pseudomorph, 62:07 31:13 1:69 4:83 0:39=100:11, Scheerer.
18.
        "
14
15. Indur'd, Gloggnitz,
                                62.47 32.08 0.47 4.78 0.18=99.93, Scheerer; G. 2.78 61.96 31.02 1.47 4.92 —=99.37, Scheerer; G.=2.78
16. Sparry, Piedmont,
                                                               -=99.37, Scheerer; G.=279.
                                62:30 31:32 1:62 4:89 0:06=100:19, Scheerer.
17. Agalmat. China,
18. Lardite, Voigtsberg,
                                66 02 31 94 0 81 0 2 -
                                                              -Na, K tr. 075=9972, Kers.
```

Stromeyer found 0.4 Ni in the tale of Röraas, and 0.48 Ni in that of Sell.

A steatite from Göpfersgrün in which Klaproth found but 59.5 per cent. of silics.

has been called Hydrosteatite.

B.B. talc loses color, not fusing, or rarely with difficulty on the edges. With borax it intunesces, and forms a clear glass, sometimes colored with iron. Not attacked by the acids.

This species is very generally diffused, and in some of its varieties especially common tale, potstone, and steatite, forms extensive beds in regions of crystallise rocks, which often contain rhomb spar, dolomite, (var. bitter spar), magnetic iron, and actinolite.

Apple-green tale occurs in the island of Unst, one of the Shetland isles; also in the Greiner mountain in Saltzburg, and in the Vallais, etc. Other foreign localities of potstone are, the Vallais and Grisons, and Wald, in Styria.

H.=3-3.5. G.=3.459-3.860, Credner, the first green, the other a gray variety. Lustre pearly to vitreous. Color olivegreen; also gray. Streak clear yellowish-green, nearly yellow. Thin splinters, translucent.

Composition.—A variety analyzed by Credner afforded (Ču, Ča)*V+H; and when Ču to Ča=5: 2, (analysis 1)=Vanadic acid 37.5, oxyd of copper 45.9, lime 13.0, water 3.6,=100; when 3: 2, (analyses 2, 3)=Vanadic acid 38.3, oxyd of copper 39.4, lime 18.5, water 3.7=100. Analyses of specimens from Frederichsrode, by Credner, (Pogg. lxxiv, 546):

		V	Ču	Ča	Mg	Йn	Ĥ		
1.	Green,	86.58	44.15	12.28	0.50	0.40	4.62, p	gangu	e 0·10=98·63.
2.	Gray,	39.02	38.27	16.65	0.92	0.52	5.05	11	0.76=101.18.
3.	**	36.91	38.90	17:40	0.87	0.53	4.62	46	0.77=100

The green mineral has a perfect cleavage in one direction; streak greenish yellow. The gray variety is fine crystalline granular; powder brownish yellow. H.=3.5. B.B. in a glass tube gives off some water, and blackens, without further change. On charcoal fuses readily without intumescence, and finally forms a graphite-like slag, which does not fuse to a globule. Affords a chrome-green globule with borax. With salt of phosphorus and a little of the mineral, on platinum, forms a pearl

which is yellow in the oxydation flame, and green in the reduction flame.

Volborthite was first discovered by Volborth, with copper ores, in the collection of Dr. Rauch, and occurs at Syssersk and Nischne Tagil, also in the Permian formation (Kupfersandstein) at several mines in the districts of Jugowskoi and Motowil-

icha. Also found at Fredericksrode in Thuringia.

A vanadate of copper (=CuV) has been reported as occurring in the Ural at Wosskressensk with native copper, copper glance, and malachite. It is pearly, of a citron-yellow color, foliated in structure, and occurring either reniform or pulver-

VANADATE OF LEAD AND COPPER, Domeyko, Ann. des Mines, [4], xiv, 150.—This ore has a dark brown or brownish-black color, and has been observed only in an earthy state, looking much like a ferruginous clay or earth. It occurs in cavities in an arseno-phosphate of lead along with amorphous carbonates of lead and copper. B.B. fuses easily and affords a black pearl, a little blebby; gives a clear green pearl with salt of phosphorus or borax and a globule of lead containing copper on charcoal. In nitric acid easily soluble.

Composition.-Pb°V+Cu°V. Analyses by Domeyko, (loc. cit.):

 V
 As
 P
 Cu
 Pb
 Pb
 Cl
 Fe, H
 Si
 H

 13.5
 4.6
 0.6
 14.6
 54.9
 0.3
 0.5
 3.5
 1.0
 2.70, clay
 1.0=97.2.

 13.33
 4.68
 0.68
 16.97
 51.97
 0.37
 0.58
 3.42
 1.38
 2.70,
 "
 1.52=97.55.

Considering the arsenic and phosphoric acids as combined with lead constituting the arsenophosphate with which the mineral is associated, the analysis affords very closely the above formula.

This ore occurs at the silver mine called Mina Grande, or Mina de la Marqueza, in

This ore occurs at the siteer innecated mina Grande, or mina de la Marqueza, in Chili, till recently worked for copper and silver.

Vanadate from the Lake Superior Copper Region.—An ore similar in color and clayey appearance to Domeyko's mineral, has been announced by J. E. Teschemacher among specimens from the Cliff Mine, in the Lake Superior Copper Region. The presence of vanadium was ascertained by both blowpipe and acid tests. The color is a dark chocolate, and also a bright yellow. The exact state of composition of the vanadic acid is doubtful. There is no oxyd of lead in the ore, and the brown variety is mixed with an earthy oxyd of iron; when carefully separated from the gangue, it was found to contain no copper.

ARÆOXENE, von Kobell, J. f. pr. Ch. 1, 496.

Massive; imperfectly crystalline, with traces of a columnar structure. II.=3. Color deep red, with a brownish tinge: streak pale yellowish

Composition.—Contains according to Kobell (loc. cit.), 487 p. c. of oxyd of lead, and 1632 of oxyd of zinc, along with vanadic acid. The oxyds of lead and zinc are nearly in equal equivalents, and the oxygen of the bases at least equals that of the acid, as in vanadinite and volborthite, and unlike dechenite.

B.B. on charcoal fuses with intumescence, yielding an arsenical odor and a globule of lead; more lead if sods be added; with borax a bright green glass in the reduction flame, light olive-green and then clear yellow in the oxydation flame, and pale greenish on cooling. In powder decomposed easily in heated concentrated muriatic acid, the liquid first yellow, then brownish, and after giving out chlorine emerald-green. On adding spirits of wine, heating it, and pouring off from the solution the separated chlorid of lead, it is still green; concentrating it with a vapor bath and diluting it with water, takes a fine sky-blue color: in this characteristic it is like other vanadium compounds.

From Dahn in the Palatinate, associated with galena. Resembles crocoisite, bet

color darker.

III. SULPHATES.—SELENATES.

I. ANHYDROUS SULPHATES OR SELENATES.

1. CELESTINE GROUP. Trimetric.

GLASERITE,	Ŕ 3 .	Anhydrite,	Ċa S.
Thenardite,	Ńа 🕏.	Anglesite,	₽ ь 5 .
Barytes,	Ba 3.	Almagrerite,	2n 8.
CELESTINE,	Šr 3.	Leadhillite,	Pb 8+8Pb C.
"	(Ba, Sr)S.		

Appendix.—CALEDONITE.

2. DREELITE GROUP. Rhombohedral.

Dreelite, $\hat{C}a \bar{S}+3\hat{B}a \bar{S}=(\frac{1}{4}\hat{C}a+\frac{1}{4}\hat{B}a)\bar{S}$.

Subannite, Pb S+8Pb C.

3. GLAUBERITE GROUP. Monoclinic,

Glauberite, Ña Š+Ĉa Š=(Ña, Ĉa)Š.

LANAREITE, Pb 3+Pb 0.

Appendiz.—Connellite. Selenate of Lead. Reussin.

[The compounds of sulphates and carbonates, or sulphato-carbonates, have the crystallization of the sulphates, the carbonic acid being wholly subordinated, as regards the form produced, to the sulphuric, the more powerful acid. Thus Leadhillite is homeomorphous with Anglesite, Celestine, etc., Susannite with Dreelite, and Lanarkite with Glauberite; and these species are here arranged accordingly.]

GLASERITE, Hausm. Aphthitalite. Sulphate of Potash. Arcanite, Haidinger. Aphthalose, Beudant. Vesuvian Salt, Lond. Phil. Trans., 1813. Kalisulphat, Naum.

Trimetric. $I: I=104^{\circ} 52', O: 1i=119^{\circ} 46'; a:b:c=1.749: 1:1.3.$ Observed planes $O, 1\bar{\imath}, \frac{1}{3}\bar{\imath}, i\bar{\imath}, 1, 2\bar{\imath}, 1\bar{\imath}, \frac{1}{3}\bar{\imath}, i\bar{\imath}, O: \frac{1}{3}\bar{\imath}=149^{\circ} 46', O: \frac{1}{3}\bar{\imath}=146^{\circ} 4', 1\bar{\imath}: 1\bar{\imath} \text{ (basal)}=120^{\circ} 29', 1\bar{\imath}: 1\bar{\imath} \text{ (ib.)}=106^{\circ} 46', \frac{1}{3}\bar{\imath}: \frac{1}{3}\bar{\imath} \text{ (ib.)}=60^{\circ} 28', \frac{1}{2}\bar{\imath}: \frac{1}{3}\bar{\imath}=67^{\circ} 52'.$ Occurs in thin tables and in blades made up of aggregated crystals; also massive, or imperfectly mammillary, and in crusts.

imperfectly mammillary, and in crusts.

H.=3-3.5. G.=1.731. Lustre vitreous, inclined to resinous.

Color white, sometimes tinged with blue or green. Transparent to translucent or opaque. Taste saline and bitter, disagreeable.

Composition.—KS=Potash 54·1, sulphuric acid 45·9. A specimen from Vesuvius contained sulphate of potash 71·4, sulphate of soda 18·6, chlorid of sodium 4·6, chlorid of ammonium, copper, and iron 5·4=100, (Phil. Trans, 1813). Fuses before the blowpipe, without intumescence.

Found at Vesuvius, upon lava, in delicate crystallizations and also in masses

Found at Vesuvius, upon lava, in delicate crystallizations and also in masses often an inch or more in thickness.

THENARDITE, J. L. Casaseca, Ann. Ch. Phys. xxxii, 311. Anhydrous Sulphate of Soda.

Trimetric. $I: I=103^{\circ} 26', O: 1i=120^{\circ} 36', \text{ Hausmann}; a:b: c=1.6905:1:1.267, O: 1i=126^{\circ} 51', 1i:1i (top)=73^{\circ} 42', (basal)=106^{\circ} 18'.$ Cleavage: basal, nearly perfect.

H.=2-2.5. G.=2.73. Lustre vitreous. Color white. Translucent. Covered with a white powder on exposure to the air.

Composition.—NaS=Soda 56.3, sulphuric acid 48.7; analysis by Casaseca, (loc. cit.), Anhydrous sulphate of soda 99.78, carbonate of soda 0.22; by A. Dick of a specimen from Tarapaca, (Phil. Mag. [4], v, 373), \$55.11, Na 42.37, insol. 2.19=99.67. Wholly soluble in water. Colors the blowpipe flame deep yellow.

Occurs at Espartinas in Spain, 5 leagues from Madrid, and 21 from Aranjuez.

Occurs at Espartinas in Spain, 5 leagues from Madrid, and 2½ from Aranjuez. The water exudes during winter from the bottom of a basin, and becoming concentrated in the summer season, deposits crystals of thenardite. Also at Tarapaca, with Glauberite and Hayesine, the crystals of which locality give some of the angles nearly of Trona, according to H. J. Brooke, (loc. cit.)

PICROPHYLL, Svanberg, Pogg. 1, 662.

Massive and foliated fibrous. Color deep greenish-gray. H.= 2·5. G.=2·75.

Composition.—(Mg, Fe) 58i3+2H. Analysis by Svanberg:

Si 49-80, Mg 30-10, Fe 6-86, Mn trace, Ca 0-78, Xl 1-11, H 9-88-98-48.

Yields water in a matrass. B.B. like Picrosmine. From Sala, Sweden. The name is from muspes, bitter, and police, leaf. May be altered augite.

KEROLITE, Breithaupt.

Massive, reniform, compact or lamellar.

H.=2-2.5. G.=2-2.4. Vitreous or resinous. White or green. Streak uncolored. Transparent—translucent. Feel greasy. Fracture conchoidal. Does not adhere to the tongue.

Composition.—Mg°Si°+44Ĥ. Analyses: 1, 2, Kühn, (Ann. d. Ch. u. Ph. lix, 363); 3, Melling, (Ramm. First Sup. p. 79):

Si Mg 29∙84 Ĥ =98-22, Kühn. 1. Silesia, 47.84 21 04 =99·4**4**, 2. Zöblitz, 46.96 81-26 21-22 47.128 86.128 11.500 2.922 2.570=100.248, Melling.

Pfaff found 37-95 silica, and 12-18 alumina, with 18-02 magnesia, and 31-00 water, in a Silesian specimen; and Delesse in one from Zöblitz, Silica 58.5, magnesia 284, alumina and peroxyd of iron 0.9, water 16.4=99.4. Maak obtained from his analysis of a Frankenstein specimen, the formula Mg Si²+Al Si+15H=Silica 388, alumina 12.2, magnesia 19, water 32. B.B. blackens but does not fuse.

From Zoblitz in Saxony and Frankenstein in Silesia, associated with serpentiae Two or three minerals or mixtures are indicated by the analyses. The name Kerolite is from κηρος, wax, and λιθος.

DERMATIN, Breithaupt. Massive, reniform or in crusts on serpentine, of a resinous lustre and green color. Feel greasy; odor when moistened, argillaceous.

Composition, according to Ficinus, (Min. Ges. zu Dresden, ii, 215):

Йg Fе ₩n Ħ, Ö Æl Čа Ñα

1. 85.80 28.70 11.83 2.25 25.20 0.42 0.88 0.50 = 100.08

2. 40·17 19·33 14·00 1·17 22·00 0·83 0·83 1·33, \$ 0·48=100·10.

Formula (Mg, Fe)*Si*+6H? B.B. blackens and cracks.
From Waldheim in Saxony. The name is from deput, skin, alluding to its occurrence as an incrustation.

MONRADITE, Erdmann, K. V. Ac. H. 1842, p. 108.

Massive, granular; also foliated, with one distinct and another imperfect cleavage, inclined 130°.

H. nearly 6. G.=3.2673. Color pale yellowish, verging on red. Lustre vitreous.

Composition.—(Mg, Fe)2Si2+4H. Analysis by Erdmann:

Ši 56·17, Mg 81·68, Fe 8·56, Ĥ 4·04=100·40.

Yields water when heated. B.B. infusible alone; with borax affords a glass colored by iron, and with salt of phosphorus a silica skeleton. From Bergen in Norway. Named after M. Monrad.

Streak white. Color white; also inclining to yellow, gray, blue, red, or brown. Transparent to translucent-opaque. Sometimes fetid, when rubbed.

Composition .- BaS = Sulphuric acid 34.33, and baryta 65.67. Oxyd of iron, silica, carbonate of lime, and alumina, occur sometimes as impurities, and sulphate of strontian is a common ingredient. E. Riegel obtained from a crystalline variety, (Jahrb. pr. Pharm. xxiii, 348), BaŠ 93-92, SrŠ 0-86, Ši 3-75, Fe 0-64, Ĥ 0-50=99-67. Freisleben found 8 per cent. of silica in a variety from Nassau; and Rammelsberg 15-12 per cent. of sulphate of strontia in another from Görzing; G.=4-488. The Allomorphite, Breith. from near Saalfeld, according to Gerngross, contains 1.9 per cent. of sulphate of lime as impurity; but von Hauer found none, (Jahrb. k. k. geol. cent. of sulphate of time as impurity; but von Hauer found none, (Jahrb. R. R. geot. R. 1853, 152). Hepatite is an impure spar affording a fetid odor on friction. The Calstronbaryte contains according to Heidingsfeld, (Ramm. 5th Supp. 206), 9BaS, 1SrS, 1CaS, the analysis affording S 36-91, Ba 54-58, Sr 4-01, Ca 2-52, Fe 1-83=99-85. Decrepitates before the blowpipe, and is difficultly fusible, or only on the edges. In the inner flame is reduced to a sulphuret, and the globule, when moistened, smells slightly hepatic. Not acted upon by the acids. Does not tinge the flame red like strontian when tested with muriatic acid and alcohol.

Heavy spar occurs commonly in connection with beds or veins of metallic ores. It is met with in secondary limestones, sometimes forming distinct veins, and often

in crystals along with calcite and celestine.

At Dufton, England, large transparent crystals occur; one of them of a tabular form, has been described as weighing forty-two pounds, and measuring ten inches form, has been described as weighing forty-two pounds, and measuring ten inches across its basal plane. Some of the most important European localities are at Felsöbanya and Kremnitz, at Freiberg, Marienberg, Clausthal, Przibram, and at Roya and Roure in Auvergne. At Freiberg in Saxony, a variety occurs composed of indistinct prismatic crystals, and having a pearly lustre; this is the Stangenspath of Werner. Rounded masses, composed of diverging columnar particles, occur at Mount Paterno, near Bologna, which have hence been called the Bologness stone. At Stanfordshire and Derbyshire is found an opaque massive variety, of an earthy appearance and dirty-white color; this variety has been called cawk.

In Cheshire, Conn., large crystals, sometimes transparent, (f.512 and simpler forms), occur in veins of red sandstone with vitreous copper and green malachite. Other similar localities are at Berlin, Farmington, and Southington, of the same State. Formerly found, but now exhausted, at Pillar Point, opposite Sackett's Harbor,

similar localities are at Berlin, Farmington, and Southington, of the same State. Formerly found, but now exhausted, at Pillar Point, opposite Sackett's Harbor, N. Y., constituting a vein two to three feet thick, in compact limestone. Large slabs, when polished, are often quite beautiful. Earthy and foliated varieties and delicate crystals are found at the Perkiomen lead mine, in Pennsylvania. At Scoharie, N. Y., a fibrous variety occurs with carbonate of lime, and the two are often mechanically mingled. In St. Lawrence Co., N. Y., fine tabular crystals occur in De Kalb, at Fowler with specular iron, at the Parish ore bed, and on the farm of J. Morse, in Gouverneur, with calc spar and specular iron, and on the banks of Laidlaw lake in Rossie; the crested barytes is found at Hammond, with crystals of iron pyrites. At Wolcott, Wayne Co., near the stratum of lenticular iron ore, and on the south side of the Mohawk, opposite Little Falls, are other localities of some interest; also at Hatfield and Leverett in Massachusetts; Piermont, N. Hampshire; Brown's Creek and Haysboro', near Nashville, Tennessee, localities of some interest; also at Hatfield and Leverett in Massachusetts; Piermont, N. Hampshire; Brown's Creek and Haysboro', near Nashville, Tennessee, and at the lead mines of the west; also at Eldridge's gold mine, in Buckingham Co., Virginia, (£ 513); three miles S. W. from Lexington, in Rockbridge Co.; a beautiful white variety is found on the plantation of J. Hord, Esq., Fauquier Co., Virginia; in large veins in sandstone on the west end of I. Royale, L. Superior, and on Spar Id., north shore, one vein, (containing also calcite), fourteen feet wide, sometimes in crystals; in trap of north shore, veins numerous. There is a vein twenty-seven inches wide at Landsdown, Canada West, affording fine crystals.

The white varieties of heavy spar are ground up and employed as a white paint, either alone or mixed with white lead.

ALTERED FORMS.—Heavy Spar occurs altered to Calcite, Spathic Iron, Cerusite, Quartz, Limonite, Red Iron Ore, Pyrites, Psilomelane, Göthite.

In a matrass yields water. B.B. fuses on thin edges to a yellowish-brown ename. With borax forms easily a glass colored by iron. Decomposed with some difficulty by concentrated muriatic acid, affording a greenish solution.

From the Antigorio valley to the north of Domo d'Ossola, Piedmont; also reported from Mount Albrun between Oberwallis and Piedmont, where masses 5 inches long and over 2 thick are said to have been obtained.

SAPONITE. Steatite. Soapstone. Seifenstein. Pierre de Savon, H.

Massive. Soft, almost like butter, but brittle on drying. Lustre greasy. G.=2.26. Color white, yellowish, blui h, reddish. Does not adhere to the tongue.

Composition. $-2\dot{M}g^2\Xi^{\dagger}+\dot{A}1\Xi^{\dagger}+10\dot{H}$ (or 6 \dot{H}). Analyses: 1, Klaproth, (Beit. ii, 180, v, 22); 2, Svanberg, (K. V. Ac. H., 1840, and Pogg. lvii, 165); 3, 4, Smith and Brush, (Am. J. Sci. [2], xvi, 368); 5, Svanberg, (Pogg. liv, 267, lvii, 165):

		δi	Æì	₽e	Ŵg	Ňa	Ķ	Ĥ
1.	Cornwall,	45 THI	9.52	144)	24 75		0.75	18-00=98-75, Klaproth.
2.	••	46.8	84)	0.4	33· 3		_	11 0, Ca 0.7=100.2, Svanberg.
3.	Thalite,	45 60	4.87	2410	24.10	0	· 4 5	20.66. Ca 1.07=98.84, S. & B.
4.	••	4.89	7-28	2.46	24:17	0	81	15-66=99-22, S. & B.
5.	Piotine,	50.89	9.40	2116	26.52			10.50, Ca 0.78=100.15, Svan.


B.R. gives out water and blackens; thin splinters fuse with difficulty on the edges. Wholly soluble in sulphuric acid.

Occurs at Lizard's Point, Cornwall; in the geodes of datholite at Roaring Brook, near New Haven, Ct.; in the trap of the north shore of Lake Superior. (Thalite of Owen, J. Acad. Nat. Sci. Philad. 1852'; at Svärdsjö in Dalarne. Sapo-

nite is from sapo, soap; and Piotine, from viers, fat.

A Saponite-like mineral from Morocco, afforded Damour the composition of Meerschaum.

SERPENTINE, Linn., Weener. Marmolite of Nuttal. Silliman's Journal, iv. 18
Og. 78. Ophitis, Vetrurius. Picrolite, Hausmann. Baltimorite, Thom. Kyphelite, Breit. Chrysotil, and Schillernder Asbest. Kolell. Metaxite, (in part)



Supposed to be Trimetric: but the crystals. like the annexed, are probably pseudomorphs of Chrysolite. Usually massive, granular to impalpable; also fibrous and foliated.

H = 3-4, rarely 5. G = 2.507-2.591; some fibrous varieties 2:2-2:3. Lustre resinousgreasy; low degrees of intensity. Color leekgreen and blackish-green; occasionally, oil and siskin-green; none bright; sometimes nearly white. On exposure, becoming yellowishgray. Streak white, slightly shining. Translucent-opaque. Fracture conchoidal or splintery. Sectile.

VARIETIES. Precious or Noble Serpentiue.-Translucent and massive, with a rich

collegreen color, of pale or dark shades.

Common Serpentine.—Opaque or nearly so, and often of dark shades of green. Domotitutes extensive hede

Picrolife, Hausmann.—A fibrous variety of a dark green color, somewhat re-mbling asbestus. Baltimorite is an allied variety, and so also Chrysotile and

Stelly, at Girgenti and elsewhere, affords splendid groups of crystals along with sulphur and gypsum. Fine specimens are met with at Bex in Switzerland, and Conil in Spain; at Dornburg, near Jena; in the department of the Garonne, France; in the Tyrol; Retzbanya, Hungary; at Norten, in Hanover. A fibrous variety of a blue color occurs in clay, at Dornburg, near Jena. Also found at Aust Ferry, near Bristol; in trap rocks near Tantallan, in East Lothian; at the Calton Hill, Edinburg; near Knaresborough, in Yorkshire; at Popayan, New Grenada. Specimens, finely crystallized, of a bluish tint, are found in compact limestone about Lake Erie, particularly on Drummond's island. Schoharic and Lockport, N.Y., Depeauville and Stark, (farm of James Coill), New York. A blue fibrous celestine occurs near Frankstown, Logan's Valley, Huntington Co., Pennsylvania, associated Sicily, at Girgenti and elsewhere, affords splendid groups of crystals along with

occurs near Frankstown, Logan's Valley, Huntington Co., Pennsylvania, associated.

with pearl spar and anhydrite.

The celestine of Drummond's Island, Lake Erie, contains sulphate of barytes, and gave Hugard the angle 103° 30'. That of Kingston, C.W., (baryto-celestine of Thomson), is pure celestine, according to T. S. Hunt, as the specific gravity 3.921 would indicate. The same is found at Sydenham, C. W.

ANHYDRITE. Cube Spar, Muriacite, W. Karstenite, Haus. Vulpinite. Anhydrous Sulphate of Lime.

Trimetric: $I: I=102^{\circ} 56', O: 1\bar{\imath}=120^{\circ} 42\frac{1}{2}', a:b:c=1.684:$ 1:1.256. Observed planes as in the annexed figure.

O: 31=131° 42'. O: 11=126° 19'. $ii: n(\frac{6}{4}) = 143^{\circ} 37'$ 0: 41=134° 25'. $ii: o(\frac{3}{4},\frac{9}{8}) = 124^{\circ} 10'. ii: f(\frac{9}{4},\frac{27}{8}) = 153^{\circ} 50'.$

Cleavage: O very perfect; ii also perfect; ii somewhat less so.

Also fibrous, lamellar, granular, and sometimes
impalpable. The lamellar and columnar varieties

often curved or contorted.

H.=3-3.5. G.=2.899-2.957. Lustre: Oand it somewhat pearly; it vitreous, in massive varieties, vitreous inclining to pearly. white, sometimes a grayish, bluish or reddish tinge; also brick-red. Streak grayish-white. Fracture uneven; of finely lamellar and fibrous varieties, splintery.



Composition.—CaS=Lime 41.2, sulphuric acid 58.8. B.B. whitens, but does not exfoliate, and is finally covered with a friable enamel. With borax, dissolves with effervescence to a transparent glass, becoming yellow or brownish-yellow on cool-

Anhydrite has been variously denominated muriacite, anhydrite, tripe stone, (gekrosstein), according to its structure; the first, when crystallized in broad lamellæ; the second when granular; and the third when composed of contorted plates. Vulpinite is a siliceous variety, containing 8 per cent. of silex, and having the hardness 3.5. Pseudomorphs in cubes, imitative of rock salt, have been de-

the hardness 3.5. Pseudomorphs in cubes, imitative or rock sair, have occurs scribed by Haidinger.

Crystallized anhydrite occurs at the salt mines of Bex in Switzerland, and at Salzburg near Hall in the Tyrol. At Aussee, both crystallized and massive, the latter brick-red. Also at Sulz on the Neckar, in Würtemberg; at Bleiberg in Carinthia; at Lüneberg, Hanover; at Lauterberg in the Hartz; at Kapnik in Hungary; at Ischl in Upper Austria; and at Berchtesgaden in Bavaria. The variety gekrösstein has been found principally at Wieliczka in Poland. The Vulpinite, from Vulpino, Italy, admits of being cut and polished for ornamental purposes.

In the United States, at Lockport, N. Y., fine blue, in geodes of black limestone, accompanied with crystals of calcareous spar and gypsum. In Nova Scotia it forms


extensive beds at the estuary of the Avon and the St. Croix river, also near the Five Islands, and elsewhere, associated with gypeum, in the carboniferous forms


ALTERED FORMS.—Absorbs moisture and changes to gypsum. Extensive beds at sometimes thus altered in part or throughout, as at Bex, in Switzerland, where by digging down 60 to 100 feet, the unaltered anhydrite may be found. Sometime specimens of anhydrite are altered between the folia or over the exterior.


ANGLESITE, Bend Sulphate of Lead Lead Vitriol. Bleivitriol. Vitriolbleiers, W.


Trimetric: $I: I=103^{\circ} 38'$, $(103^{\circ} 43\frac{1}{2}')$, Kokscharov, Pogg. r., 158), $O: 1\bar{\imath}=121^{\circ}\ 21'; \ a:b:c=1.641\bar{5}:1:1.2715.$

 $o: 1 = 127^{\circ} 45'$. $1 : 1 : (top) = 75^{\circ} 29'$. $1: 1 : (mac.) 112^{\circ} 13'$. $\frac{1}{4} : \frac{1}{4} : (top) = 101^{\circ} 15'$. $1: 1 : (brac.) 89^{\circ} 41'$. $1: 1 : (bas.) 128^{\circ} 54'$. $O: 140^{\circ} 37'$. $O: \bar{1}=115^{\circ} 33'.$ $O: \frac{1}{2} = 133^{\circ} 44'.$ $O: \frac{1}{2} = 123^{\circ} 9'.$









Cleavage: I, O, but interrupted The planes I and ii, often vertically striated, and it horizontally. Also lamellar, and massive granular.

H.=2·75—3. G.=6·259—6·299. Lustre highly adamantine in some specimens, in others inclining to resinous and vitreous. Color white, tinged yellow, gray, green, and sometimes blue. Streak uncolored. Transparent—opaque. Fracture conchoidal. Very brittle.

Composition. —PbS=Sulphuric acid 26.4, oxyd of lead 78.6=100. Analyses: 1, Klaproth, (Beit. iii, 162); 2, Stromeyer, (Unters. 226); 3, Thomson, (Min. i, 559):

	•	8	Pъ	₽e³Ĥ³	Ĥ
1.	Wanlockhead,	25.75	70 ·50		2·25=98·50, Klaproth.
	Zellerfeld,	26.09	72.47	0.09	0·51. M n 0·07=99·23, Strom.
3.	Leadhills,	25.65	74-05		0.30=100, Thomson.

Decrepitates in the flame of a candle, and frequently becomes slightly reddish. B.B. in powder, melts to a bead which cools milk-white; and in the inner flame af-

fords metallic lead by the addition of soda.

This ore of lead results, in many instances, from the decomposition of galena. At Leadhills it frequently occurs, occupying the cubical cavities of galena, or disposed on the surface of this ore. This locality, and also Wanlockhead, afford large and beautiful crystals of this mineral, some of which are transparent, of a tabular form, and several inches in diameter; occurs also at Pary's mine in Anglesea, Mellanoweth, in Cornwall, Derbyshire in large crystals, Clausthal, Zellerfield and Giepenbach, in the Hartz, near Siegen in Prussia, at Schapbach in the Black Forest, Badenweiler in Breisgau, and on Sardinia. Small, but extremely perfect transparent crystals, have been brought from Fondon in Granada. The massive varieties are met with in Siberia, Andalusia, and Alston Moor in Cumberland.


In the United States, it occurs in large crystals at Wheatley's mine, Phenixville, Pa., (f. 517, 518, 519); in the Missouri lead mine; at the lead mine of Southampton, Mass.; at Rossie, N. Y., with galena at the Walton gold mine, Louisa Co., Va.


ALTERED FORMS.—Anglesite occurs altered to cerusite (PbC.)


Almagrerite. Anhydrous Sulphate of Zinc, Breit.—According to Breithaupt, this sulphate occurs at the mine of Barranco Jaroso in the Sierra Almagrers, Spain, in crystals isomorphous with Anglesite and Heavy Spar. G.=4.331. (B. u. H. Ztg., 1852, No. 7; Ramm. 5th Suppl., 26).

LEADHILLITE. Sulphato-tricarbonate of Lead, Brooke, Ed. Phil. Jour. iii, 117. Rhomboidal Carbonate of Lead. Bleisulphotricarbonat, Ramm. Ternärbleierz.

Trimetric, Brooke and Miller. $I: I=103^{\circ}$ 16', $O: 1\bar{\imath}=120^{\circ}$ 10'; a:b:c=1.7205:1:1.2632. Observed planes as in f. 521, with also $i\bar{\imath}$ replacing edge between I and $i\bar{\imath}$. Hemihedral in I and some other planes; hence monoclinic in aspect, or rhombohedral when in compound crystals.








 $O: 150^{\circ} 10'.$ $O: 150^{\circ} 11'.$ $ii: 150^{\circ} 11'.$

 $ii : \frac{4}{3}i = 156^{\circ} \ 27'.$ $ii : \frac{2}{3}i = 128^{\circ} \ 14'.$ $ii : \frac{1}{3} = 111^{\circ} \ 30'.$

 $\vec{u}: I=128^{\circ} 22'.$ $\vec{u}: \vec{i_2}=111^{\circ} 36$ $\vec{u}: \vec{i_1}=90^{\circ}.$ Cleavage: ii very perfect; ii traces. Twins, f. 523, 524, (drawn with it as top plane), consisting of 3 crystals; face of composition It, (see f. 525); also parallel with I.



H.=2.5. G.=6.2-6.5. Lustre of it pearly, other parts resinous, somewhat adamantine. Color white, passing into yellow, green or gray. Streak uncolored. Transparent—translucent Conchoidal fracture scarcely observable. Rather sectile.

Composition .- Pb S+3PbC=Sulphate of lead 27:44, carbonate of lead 7254 Analyses: 1, Berzelius, (Jahresb, iii, 184); 2, Stromeyer, (Gött. gel. Anz. 1825, 118):

> Pb Ö 71 0=99 7, Berzelius. 727=100, Stromeyer. Pb S 28.7 28.3

B.B. intumesces at first, and then turns yellow; but white on cooling. Easily reduced on charcoal. Effervesces briskly in nitric acid, and leaves a white precipitate. This ore has been found principally at Leadhills, associated with other ores at lead; Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho, Grenada is also stated to be a locality of it, and the island of Serpho is the interpretation of

lead; Grenada is also stated to be a locality of it, and the island of Serpho, Grecian Archipelago. The crystals seldom exceed an inch in length, and are commonly smaller. Reported by C. U. Shepard, (Am. J. Sci. [2], xv. 446), from Newberg District, South Carolina, but there is some doubt as to the locality.


Brooke and Miller, who show that the form of Leadhillite is trimetric, make the prism \$\frac{1}{4}\$ (of \$120^\circ 20'\$), the fundamental vertical prism, and appear to regard the species as related to Aragonite. The fact that the twins are not formed parallel to the faces of this prism, (as they should be if the prism \$\frac{1}{4}\$ were homologous with the Aragonite prism), and the close approximation in angle to Anglesite, shown above, besides other reasons, have led the author to adopt the position of the crystal here given, which exhibits the Anglesite relation. Susannite (rhombohedral) and Leadhillite (trimetric) are mutually dimorphs, and so also are Dreelite and Anglesite. Now Susannite and Dreelite are nearly identical in angle; and therefore Leadhillite and Anglesite must be equally related. Since in Susannite the sulphuric acid dominates over the carbonic acid and impresses on the lead salt its character, (or the form of the sulphate), the same should be the case with its correlate Leadhillite—this species being the very same chemical compound. (See on this Leadhillite—this species being the very same chemical compound. (See on the subject, Am. J. Sci. [2], vol. xviii). The hemihedrism of the species gives origin to the peculiar rhombohedral aspect of the twins. The angles of these twins are new those of Susannite.

CALEDONITE, Beud. Cupreous Sulphato-Carbonate of Lead, Brooks, Ed. Phil. Jour. iii, 117. Halbazurblei, Ramm.

Trimetric. $I: I=95^{\circ}, 0: 1i=123^{\circ}9'; a:b:c=1.5314:1:1.0913.$ Observed planes as in the annexed figure. $O: 1\bar{i}=125^{\circ}\ 29',\ O: 2\bar{i}=108^{\circ}\ 5',\ O: \frac{2}{3}=125^{\circ}\ 50',\ O: 1=115^{\circ}\ 43',\ I: \bar{ii}=132^{\circ}\ 30',\ 1: 1\ (pyr.)=105^{\circ}\ and\ 96^{\circ}\ 45'.$ Cleavage I and O indistinct, \bar{ii} more obvious. Crystals sometimes large, usually minute, and occasionally in bunches diverging from a point.

H.=2·5—3. G.=6·4. Lustre resinous. Color deep verdigris or bluish-green; inclining to mountaingreen if the crystals are delicate. Streak greenish-white. Translucent. Fracture uneven. Rather brittle.

Composition.—Analysis by Brooke, (Ed. Phil. J. iii, 119):



Pb S 55·8 Pb C 82·8 Cu C 11·4=100, Brooke.

B.B. easily reduced. Soluble in nitric acid, with slight effervescence. Occurs at Leadhills, Scotland, accompanying other ores of lead, in crystals with Linarite, at Roughten Gill in Cumberland; also reported from Tanné in the Hartz, and from Mine la Motte, Missouri.

DREELITE, Dufrénoy, Ann. de Ch. et de Ph. lx, 102.

Rhombohedral. $R: R=93^{\circ} \text{ or } 94^{\circ}$. Cleavage: rhombohedral, in traces.

H.=3.5. G.=3.2—3.4. Lustre pearly; splendent on a surface of fracture. Streak and color white.

Composition.—CaS+3BaS. Analysis by Dufrénoy, (loc. cit.):


BaS 61-78 CaS 14-275 CaC 8-05 Si 9-71 Al 2-405 Ca 1-52 H 2-81=100.

In small unmodified crystals, disseminated on the surface, and in the cavities of a quartzose rock, at Beaujeu, France, Dep. of the Rhone; also at Badenweiler, (Baden). It was named by Dufrénoy in honor of M. de Drèe, a liberal patron of science.

Thomson has analyzed another compound of the sulphates of baryta and lime, (Min. i, 106), consisting of 71.9 of the former to 28.1 of the latter; it was from Harrowgate in Yorkshire.

SUSANNITE, Haidinger.

30'. Cleavage O easily obtained. H.=2.5. G.—6.55. Lustre resinous—adamantine. Color white, green, yellow, brownish-black. Streak uncolored.



Composition.—Same as for Leadhillite. Analysis by Brooke, (Edinb. Phil. J., New Series, iii, 117, 138), Sulphate of lead 27.5, carbonate of lead 72.5.

Composition.—BET+3H, from Siegert's analysis. Analyses: 1, Resmabber. (Pogg. xliii, 127); 2, Siegert, (Ramm. 5th Suppl., 220):

S i	Że	3	Ėg	Ca	ĸ	宜
	35-62				0-75	8-72-100, Ress.
42 V7 📱	e 41 36	4-93	0.94	1-67		8-47:100-06, Siegurt.

In a matraes yields water. B.B. frees with some difficulty to a black chining globule; with the fluxes gives an iron reaction. Disselves imperfectly in the acid. Occurs at Obergrund, with cale spar and quartz, sometimes intermined with pyrites and magnetic iron era. Probably mixed with chlorite, according to Bassachberg. Named from evolutes, admining, and pales, black.

This species requires more investigation, and the same is true of the following

Erschloster. The Epichlerite of Resemblery, (Pogg. Ann. luxvii, 437, 1869), is a fibrous or columnar mineral from Redusthal, between schiller spar and chlorite. H=2-25. G.=276. Color dull leck-green. Streek white to greenish. Laste greeny. In this columns translacent and of a bettle green color.

Composition.—32.51+257+9H, Resembleberg. Analysis: Si 40-88, 32 10-96, 76 8-72. Fe 8-96, Mg 20-96, Ca 0-68, M 10-18=100-28. R.R. fences only in this fibres with difficulty. With the fluxes reaction of silice and iron.

GLACOSSITE.—The Green Grains of the green sand formatists of Gay Head, contain, according to Dr. S. L. Duna, (Hitchcock's Gool. of Mass., p. 93); of New Jersey, secording to H. D. Rogges, (Gool. Rep. New Jersey, pp. 206 and 207); and W. Fashe, (Am. Jour. Sci., [2], ix, 43); of Germany, according to Berthier:

	轰	33	Pe	± g	Ca.	Ì	Ża.	H
1. Gay Head, Mass.	5670	13-33	20-10	1-18	1-62	_		D
	40-45	6-20	24-51		tress	1 2-01		***-**********************************
2. Sculitowa, S. J.,	51 -5 0	6-40	24 30	from		3-96		770 -198 ,2
4. Poke Hill, Burlingt. Co., N.J. 5 S. E. of Phil. in N. J.,	50-75	65)	22-14			12-76		7-50
& S. E. of Phil in N. J.	23-36							25-1
6. Germany,	46-1	5-5	19-6	3-3	_	5-3		59, quartz,

Van der Marck found in the Green Sand of Båderich near Werl in Westphalia, 259 per cent soluble in muriatic acid ich 25'l insoluble il. (\$1, and 41 % of quarte Analysis afforded him, (Rammelsberg, 5th Suppl. 126).

a. Ca C 197, MgC 04, Ca' P 24, Fe 09, H 14, F trace=252. A. Si 192, H 32, Fe 62, Mg 1-1, K 1-1, H 2-1=33-1.

When first dug the grains are very soft, and the mass is sometimes adhesive, but on exposure they nearly equal gypsum in hardness.

KIRWANIE Fibrous; fibres diverging from a centre. H = 2 G. = 241 Color

dark olive-green. Opaque.

Composition.—According to R. D. Thomson, Silica 40-5, protoxyd of iron 23-91, lime 19-78, alumina 11-41, water 4-35-39-35, whence Rammelsberg deduces the formula of 3R Si+H Si+2H. Blackens before the blowpipe and partially funs. With soda or borax forms a dark brown glass. Occurs in basalt on the northeast coast of Ireland. (Thomson, Min. i, 579.

MELAVOLPE of Wurtz, (this Min. 3d edit., p. 679), has a chlorite like aspect. It is black and opaque with a stricted surface and somewhat columnar structure; struk dark olive green. H.= G.= +**

H. Wurtz obtained Si 30:36. Al 3:22. Pc 21:25. Fc 21:27. No 1:32. H 3:24. CaC 12:77=100:32. It affords the carygen ratio for the protoxyda, peroxyda, silica and war, 2:3:6:3; but it is probably not of constant composition. Rammelsburg serves that it is near Hisingerite.

m Milk Row Quarry, near Charlestown, Massachusetts, increasing the sides of

H.=2-2.5. G.=6.3-7. Lustre of the cleavage face pearly; other parts adamantine, inclining to resinous. Streak white. Color greenish-white, pale-yellow or gray. Transparent—translucent.

Composition.—PbS+PbO=Sulphate of lead 58.15, carbonate of lead 46.85. Analysis by Brooke, (loc. cit.); Thomson, (Phil. Mag. 1840, Dec. 402):

Carbonate of lead 46.9, sulphate of lead 53.1=100.
" 46.04, " 48.96=100, G.=6.3197.

B.B. fuses to a globule, which is white on cooling. Dissolves in nitric acid without perceptible effervescence.

At Leadhills, Scotland. Massive in Siberia and at Tanné in the Hartz; at Biberweier, Tyrol.

Appendix to the Anhydrous Sulphates, etc.

REUSSIN, Karsten.

In white, flat, six-sided crystals, and also acicular, in radiating groups. Also a mealy efflorescence. Color white. Taste saline and bitter.

Composition.—Analysis by Reuss, (Crell's Anal. 1791, ii, 18);

ÑaS 66 04, MgS 31.85, CaCl 2.19, Gypsum 0.42. From the neighborhood of Seidlitz in Bohemia.

SELENATE OF LEAD. Selenbleispath, Kersten, Pogg. xlvi, 277.

In small spheres and botryoidal masses. Cleavage distinct in one direction.

Color sulphur-yellow. H = 3 - 4. Lustre greasy—vitreous. Streak uncolored. Brittle. Fracture fibrous.

According to Rose's examination, it consists of selenic acid and oxyd of lead, with a small proportion of oxyd of copper. On coal it fuses readily to a black slag, giving off a strong selenium odor, and is finally reduced to a metallic globule. With borax it fuses and forms a yellowish-green pearl, which is of the same color on cooling. With soda, on charcoal, metallic lead is obtained.

Occurs with seleniuret of antimony and lead, malachite, etc., at the Friederichs-blick mine near Hilburghausen and at Fiefeld.

glück mine, near Hilburghausen, and at Eisfeld.

CONNELLITE. Sulphato-chlorid of Copper, Connel, Proc. Brit. Assoc. for 1847.

Hexagonal. In hexagonal prisms with truncated edges. Lustre vitreous. Color fine blue. Translucent.

Composition.—From trials by Connel, supposed to be a compound of a sulphate and chlorid of copper. Associated with arsenate of copper in Cornwall.

Analyses: 1 Kobell, (J. f. pr. Ch. ii, 51); 2, Lychnell, (K. V. Ac. H., 1826); 3, Kobell, (loc. cit.); 4, Svanberg, (K. V. Ac. H., 1839, 155); 5, Hartwall, (Jahresh xxiii, 266); 6, T. H. Garrett, (Am. J. Sci. [2], xv, 332); 7, Genth, (Proc. Acad. Nat. Sci. Philad. 1852, 121, mean of two analyses); 8, Hermann, (J. f. pr. Chem. liii, 1); 9, 10, Smith and Brush, (Am. J. Sci. [2], xvi, 47); 11, 12, Hermann, (loc. cit.); 13, Crossley, (this Min. 3d edit., 291); 14, T. S. Hunt, (Phil. Mag. [4], ii, 65);

```
Йg
                                                        Рe
                      Ŗί
                           Æl
                                  æ.
                                                Ċа
                                                                Ħ
 1. Pyrosclerite, 87.03 13.50 1.48 31.62
                                                        3.52 11.00=98.10, Kobell.
                                                        179 7:38, Ö & Bit. 6:28=99.76,L
1:46 9:00=98:37, Kobell.
                    35·28 13·73 — 35·35
35·69 17·12 — 22·50
     Chonikrite,
 8.
                    85.69 17.12
                                      - 22.50 12.60
    Tabergite,
                    85.76 13.08 -
                                    -- 29:27
                                                        6 34 11 76, Mn1 64, K 2 07, Mg P,
                                                                            1·1=100-98, 8v.
    Kæmmererite, 37 0 14 2 1.0 31 5
                                                1.5
                                                        1.5 13.0=997, Hartwall.
                                               4·11 2·50 18·58, Ni 0·67=98·92, Gar. trace Fel·48 12·95, Li, Na0·28, Ko·1, G.
                    87.66 11.82 8.60 24.97
 6.
                                               4.11
 7.
                    88.20 11.11 6.85 35.54
                                                — " 4 06 1275, Ni 0 25=100-12, Her.
 8.
                    81.82 15.10 0.90 35.24
                                                    - "196 12.64, K, Na 0.35=9961,
 9.
                    88-26 10-69 4-78 35-93
                                                                            Smith & Brush
                                                   - "1 60 18 25, K, Na 0 35 = 99 75,
Smith & Brush.
10.
                    83.80 10.50 4.67 36.08
                                                   - Fe3·32 12·05=100·33, Hermans.
- Fe2·00 12·03=100·14, Hermans.
                    80.58 15.94 4.99 88.45
11.
12. Rhodochrome, 34.64 10.50 5.50 85.47
                   35·74 16·42 — 27·44
32·49 13·18 — 35·77
18. Vermiculite,
                                                   -Fe10:02 10:80=99:92, Crossley.
14. Loganite,
                                               0.95 Fe2.14 16.92 (Cincluded)=101.45
```

1, From Elba; 2, Aker, Sudermanland; 3, Elba; 4, Taberg; 5, Siberia; 6 to 10,

Texas, Pa.; 11, 12, L. Itkul; 13, Milbury, Massachusetts.

Nos. 6 to 10 are of similar character; 7 is rhodophyllite of Genth; 8 is chromechlorite of Hermann. The varieties severally in a matrass yield water; and B.B.
fuse with difficulty to a grayish glass; with borax form a chrome-green pearl.
Wholly decomposed by concentrated sulphuric acid.

The oxyd of chromium varies in amount with the color, the paler varieties containing but little. Smith and Brush attribute the nickel to mixed sulphuret of nickel. The Aker mineral (anal. 2) resembles serpentine in appearance.

Chonikrite occurs massive, of a white color, glistening lustre and weak translu-cence; found with pyrosclerite, at Elba. B.B. fuses with intumescence to a grayish

glass; soluble in muriatic acid, without gelatinizing.

Vermiculite has a granular scaly structure and greasy feel, and looks like steatite. The scales when heated (to 500° or 600° F) open out into worm-like threads made up of separated laminæ of cleavage; and sometimes, as Dr. C. T. Jackson states, swelling to nearly a hundred times the original length; and if confined in a glass tube this expansion is so powerful as to break it with an explosion, and scatter the glass to a distance. G.=2.756. In the forceps a scale fuses readily to a yellowish green glass; with soda an opaque brown bead; with borax or salt of phosphorus easily a glass, yellow while hot and colorless when cold, or with the latter flux becoming somewhat milky-white on cooling. Decomposed by muriatic and sulphuric acids. In a matrass yields water which is somewhat alkaline. Crossley's analysis was made on the scales carefully separated from the mealy magnesian bese with

which it is associated. His formula is that of pyrosclerite.

Tabergite, called by Werner blue talc of Taberg in Wermland, is considered a distinct species by G. Rose, as it has but little resemblance to pyrosclerite.

Kammererite occurs in hexagonal prisms, of a reddish violet color like lepidolite. Cleavage basal, perfect. Sometimes plumose massive. H.=15-2. G.=276, Siberia; 2.617-2.62, Texas. Lustre pearly. Translucent. Sectile and flexible. Feel greasy. Found with chromic iron at Bissersk, Siberia; also at Texas, Lancaster Co., Pennsylvania, with chromic iron in serpentine; the crystals are hexagonal or rhombic prisms, sometimes with the basal edges replaced; also crystallized at Haroldwick in Unst, Shetlands.

Rhodochrome has a greenish black color, but is peach-blossom-red in thin splinters. It occurs massive with a fine scaly structure, and a splintery fracture. H. =2.5-1. G. =2.668; 2.65, Hermann. B.B. strongly heated fuses on the edges to a yellow enamel. Affords a chrome-green glass with borax. Dissolves with difficulty is PISSOPHANE,

LINARITE, IV.

BROCHANTITE, III.

LETTSOMITE, MEDJIDITE.

PbS+CuH.

ČuŠ+3ČuH.

Cu68+318+12H.

MISENITE, A. Scaechi, Mem. Geol. sulla Campania, 1849, p. 98.

In silky fibres of a white color. Soluble; in taste, acid and bitter.

Composition.-KS+HS. Analysis by Seacchi, (loc. cit. and J. f. pr. Ch. lv, 54): ₩ 0.38, 并 6.12=100. S 56.93, Ř 36.57.

Fuses easily in the flame of a spirit lamp. Occurs in a hot tufa cavern, near Misene.

POLYHALITE,

Trimetric. A prism of 115°, with acute edges truncated. Usually

in compact fibrous masses.

H.=2.5-3. G.=2.7689. Lustre resinous or slightly pearly. Streak red. Color flesh or brick-red, sometimes yellowish. Translucent-opaque. Taste bitter and astringent, but very weak.

Composition.—RS+1H, in which R=K, Mg, Ca in the ratio 1:1:2, (analyses 1 to 3), or 1:1:4, (anal. 5). Analyses: 1, Stromeyer, (Unters. i, 144); 2, Rammelsberg, (Pogg. lxviii, 512); 3, C. A. Joy, (Inaug. Dissert., 49); 4, 5, von Hauer, (Sitz Wien. xi, 385):

Cas MgS KS Fe NaCl H

- 44.47 0.34 5.95=98.94, Strom. 1. Ischl, 20.03 27.70 0.19
- 5.24, Si 0.2=100, Ramm. 6.41, NaS0.75=90.21, Joy. 5.58=100, v. Hauer. 2. Aussee, 45.43 20.59 28.10 0.11 0.33
- 3. Gmund, 42.78 19.85 28.11 175 FeS0-36 4. Hallstatt, 56.41 11.04 14.81 12.16
- 0.23 Fe 0.41 6.05=100.52, v. Hauer. 5. Ebensee, 61.18 13.53 19.12

Becomes opaque in the flame of a candle, and of a brownish color. B.B. fuses instantly. But slightly soluble in water.

Occurs at the mines of Ischl, Aussee, Hallstatt and Ebensee, in Austria, with common salt, gypsum, and anhydrite; at Berchtesgaden in Bavaria.

The name Polyhalite is derived from πολές, many, and ἀλξ, salt, in allusion to the process of salts in the constitution of the mineral salts.

number of salts in the constitution of the mineral.

The specimens from Vic in Lorraine, analyzed by Berthier, are supposed to be glauberite mixed with rock salt.

GYPSUM. Sulphate of Lime. Alabaster. Selenite. Satin Spar. Gyps. Plaster of Paris. Schaumkalk. Γέψος.

Monoclinic. C=66° 14', I: I=138° 28', 1i: 1i=128° 31'; a:b:c=0.9:1:2.4135. Angles from B. and M.

O: I=67° 52'. 0: ii=66° 14'. 0: 4i=126° 12'.

O: 1i=127° 44'. 0:2=98° 46'. 1:1=143° 42'.

O: 3i=87° 58'. 0:1=88° 8'. 2i:2i=111° 42'.

O: 1=125° 35'. 0: 2i=145° 41'. 1: I=122° 17'. gle between the axes 84° 30', for 30° to 86°; plane of the axes, perpendicular to cleavage surface, but the two unequally inclined to this surface, one at about 54°, the other 30°. In large crystals and plates. Often compounded, the crystals giving a second pair of optical axes, making of, with the other. Crystals have usually a rhombohedral aspect, as in £ 464.

 $HL=2-2^{2}25$. $G.=2^{2}714$, but probably too low, as the specimens could not be obtained wholly free from air, (Blake). Lustre somewhat pearly. Color olive-green. Transparent, unless in thick plates. Somewhat elastic.

Composition. $-5R^4Si^{\frac{3}{4}}+3\overline{A}ISi^{\frac{3}{4}}+12\overline{H}=\frac{5}{3}R^2+\frac{3}{4}B_1Si^{\frac{3}{4}}+14\overline{H}-Silica 32.6, alumina 18.5, magnesia 26.0, water 12.9=100. Perhaps <math>R^2:\overline{H}=7:4$, instead of 5:3, which gives Silica 32.6, alumina 17.9, magnesia 26.6, water 12.9=100, corresponding closely with von Kobell's analysis.

Analyses: 1, 2, W. J. Craw, (Am. J. Sci. [2], xiii, 222); 3, Kobell, (Gel. Anaeig.

Analyses. ., ., No. 43 Ap. 10, 1854): Si

Pe Æı 1. Chester Co., Pa., 31-34 17-47 3-85 1-69 33.44 12.60=100.39, Craw.

8178 2271 38-64, 12-60=100-73, Craw. 8. Bavaria, 33.49 15.37 2.30 0.55 32.94 11.50, Pe 4.25=100.40, K.

B.B. like chlorite; shows traces of fusion on the edges. Abundant with serpe tine in large crystals and plates at Westchester, Chester Co., Pa.; at Unionville, Pa.; at Leugast, Bavaria.


A line between the apparent optical axes is a perpendicular to one side of the

triangular plates of the mineral.

HELMINTH, (G. H. Otto Volger, Entw. Min. 142). A chlorite occurring in feld-spar and quartz, and resembling f. 467, but the prisms trimetric or monoclinie. I: I nearly 120°; the rhombic prisms with the acute edges truncated by a striated plane unlike I. O: I nearly 90°. No analysis is given; and it may be elinochlore.

CHLORITE, Werner. Leuchtenbergite, Komonen. Ripidolite, Kobell.

Rhombohedral. $R: R=75^{\circ} 22\frac{1}{2}', \theta: R=113^{\circ} 58'; a:1.948.$



(): $2=102^{\circ}32'$, $2:2=64^{\circ}34'$, $\frac{6}{5}:\frac{6}{5}=71^{\circ}24'$, $\frac{12}{5}:\frac{12}{5}=63^{\circ}14\frac{1}{5}'$, (Pennine). Usually massive granular, also foliated.

being formed from the sulphuric acid generated, and the lime afforded by the decomposing lavas—lime being contained in augite and labradorite. It is also produced by the decomposition of pyrites when lime is present; and often about sulphur springs where sulphuretted hydrogen is emitted, this gas changing through reaction with vegetable matter into sulphuric acid. Gypsum is also deposited on the

evaporation of sea-water and brines

Fine specimens are found in the salt mines of Bex in Switzerland; at Hall in the Tyrol; in the sulphur mines of Sicily; in the gypsum formation, near Oçana, in Spain; in the clay of Shotover Hill, near Oxford; and large lenticular crystals have been met with at Montmartre, near Paris. Derbyshire affords the fibrous varieties. Alabaster occurs at Castelino, 35 miles from Leghorn, whence it is taken to Florence for the manufacture of vases, figures, &c. Gypsum also occurs in acicular crystals in most volcanic regions.

This species occurs in extensive beds in several of the United States; and more particularly New York, Ohio, Illinois, Virginia, Tennessee, and Arkansas, and is usually associated with salt springs. Also in Nova Scotia, Peru, &c.

usually associated with salt springs. Also in Nova Scotia, Peru, &c.

Handsome selenite and snowy gypsum occur in New York, near Lockport, (occasionally f. 582), in limestone along with pearl spar and anhydrite; also near Camillus, Onondaga County, occasionally crystals are met with in the vicinity of Manlius In Ohio, large transparent crystals, have been found at Poland and Canfield, Trumbull County; in Maryland, large grouped crystals on the St. Mary's in clay; also near the mouth of the Patuxent; in Iowa, in perfect crystals in the shales of the coal measures on Cedar river, a branch of the Des Moines, and elsewhere on the latter river. Selenite and Alabaster occur in Davidson County, Tennessee, and large beds of gypsum with rock salt in Washington County, Virginia, eighteen miles from Abingdon. In the Mammoth Cave, Kentucky, it presents singular imitations of vines, flowers, and shrubbery.

tions of vines, flowers, and shrubbery.

Plaster of Paris, or gypsum which has been heated and ground up, is used for making moulds, taking casts of statues, medals, &c., for producing a hard finish on walls; also in the manufacture of artificial marble, as the scagliola tables of Leg-

horn, and in the glazing of porcelain.

The fibrous variety when cut en cabochon, and polished, resembles cat's eye.

Gypsum is related in form to heulandite, a fact brought out in the view above taken of the crystallization, (Am. J. Sci. [2], xvii, 85). To the table of observed planes the lettering of Brooke and Miller for the planes is added. Plane I of f. 534 would be situated on f. 533, between 2i and 3i below, or the back 2i and 3i above. Kengott obtained from an English crystal 2i: 2i=111°-14′, (Sitz. Wien. Ak. xi).

Note.—The gypsum of East River, Pictou, Nova Scotia, according to Prof. W. R. Johnson, and that of Southern Virginia, according to Prof. W. B. Rogers, (Am. J. Sci. [2], v. 113, 1848), contain 1 atom of water to 2 of sulphate of lime, (2CaS+H). The passage of anhydrite into gypsum is exemplified on a large scale in many places, as at the Canaria valley and at Bex in Switzerland, (Blum, Pseud, p. 24; Am. J. Sci. xlviii, 69), and the compound here described may have been formed in the course of the transition.

ALTERED FORMS .- Gypsum occurs altered to calcite.

ASTRAKANITE, Rose.

In imperfect prismatic crystals, whitish and translucent.

Composition.—MgS+NaS+4H=Sulphate of magnesia 35.9, of soda 42.5, water 21.6. Analysis by Göbel:

NaS 41.00, MgS 35.18, H 21.56, Mg Cl 0.33, Gypsum and sand 1.75.

From the salt lakes east of the mouth of the Volga. Rammelsberg suggests that this species may be the same as Blödite. The Blödite of John from Isehl afforded John, MgS 36-66, NaS 33-34, MnS 0-33, NaCl 0-33, H 22-00=92-66, with 0-34 sulphate of peroxyd of iron.

MASCAGNINE. Maskagnin, Karsten, Reuss. Sulphate of Ammonia.

Trimetric. $I: I=107^{\circ} 40', O: 15=122^{\circ} 56', a:b:c=1.5437:$ 1:1.3680. Cleavage: ii perfect; O imperfect.

DELESSITE, Naumann. Chlorite Ferrugineuse, Delesse. Kisenchlorit.

Massive, with a short fibrous or scaly feathery texture. H.=2.5. G.=2.89. Color olive-green to blackish-green.

Composition.—B'Si3+BSi3+8H=(1B3+1B)Si3+11 H. Analysis by Delesse, (Ann. des M. [4], xvi, 520):

Bi 29.45 Al 18.25 Pe 8.17 Fe 15.12 Mg 15.82 Ca 0.45 H 12.57=99.33.

In a matrage yields water and becomes brown. B.B. fuses with difficulty on the

edges. Easily soluble in scids, affording a deposit of silica.

Occurs in the amygdaloidal porphyry of Oberstein and Zwickau.

The Grongesite of Hisinger from Grengesberg in Dalecarlia is referred here. G.

21. Color dark green. According to Hisinger, it contains Si 27.01, 31 1431, 32 218, Fe 25.63, Mg 14.81, H 12.53.

RIPIDOLITE, G. Ross. Chlorite, in part.

Hexagonal. Cleavage: basal, eminent. Crystals from Tyrol in double pyramids, pyramidal edges 132° 40′, basal 106° 50′, Descloizeaux.

H.=1-2. G.=2.78-2.96. Translucent—nearly transparent. Lustre pearly. Color green, olive-green; across the axis, by transmitted light, red. Streak uncolored or greenish. Laminæ flexible, not elastic.

Composition.—R*Si\$+XlSi\$+8H=({R\$+{Xl}}Si\$+1{H=(if Mg : Fe=1 : 1) Silica 27.2, alumina 28.1, magnesia 18.5, protoxyd of iron 24.2, water 12.1=100.

Analyses: 1, Varrentrapp; 2, 3, 4, Kobell, (J. f. pr. Ch. xvi); 5, 6, Marignae, (Ann. Ch. Phys. xiv, [3], 59); 7, Hermann; 8, J. L. Smith, (Am. J. Sci., [2], xi, 65):

```
Æι
                                                         Гe
                                                                Min H
                                                        2879 — 8.96=9870, Varr.
15.00 — 12.00=98.15, Kobell.
1. St. Gothard,
                             25.87 18.50 17.09
2. Zillerthal, G.=2.78, 26.51
8. "G.=2.88, 27.32
                                      21.81 22.88
                                      20.69 24.89
                                                        15.28 0.47 12.00=100.60,
                                      18:47 14:69
17:52 13:84
4. Rauria, G.=2.9,
                                                        26.87 0.62 10.45, gan. 2.24=29.40, K.
                             26-06
                             26.88
5. Dauphiny,
                                      17.52 13.84 29.76 — 11.83=99.33, Marignae.
19.19 16.78 24.76 — 11.50=99.37, "
22.21 80.96 Fe 5.00 — 18.43, 2.25 undec., H.
                             27.14
7. Miask,
                              25.60
8. Gumuch-dagh,
                             27:20 18:62 17:64 Fe23:21 - 10:61=98:28, Smith
```

Analyses 2, 8, are of the Lophoite of Breithaupt; R: 0=105° 14'. Analyses 4 is of his Ogcoite.

B.B. like chlorite. Rammelsberg makes the St. Gothard ripidolite (anal. 1) to contain 16 89 Fe and 13 22 Fe, and finds reason for changing other analyses correspondingly

Ripidolite occurs at the localities above-mentioned, and also in Scotland; at Gemuch-dagh, in Asia Minor, with Emery, etc. The name ripidolite is from pares, effea.

The "chlorite" of Traversella has all the characters of a hexagonal chlorite, occurring in rather large hexagonal plates regularly grouped. But Marignac considers it a mixture of tale and chlorite. His analyses obtained, (Ann. Ch. Phya. [3], xiv, 60):

Bi 3845 五1175 Fe 12.82 Mg 28·19 **拍 8:49=997**0. 89-81 12.56 11.10 28-41 779=99-67. 11.42 10.09 29.67 7-66=100-18.

It has the greasy feel of tale.

of different shades. Streak uncolored. Subtransparent—translu-Taste metallic and nauseous. Somewhat brittle.

Composition.—CuS+5H=Sulphuric acid 32·1, oxyd of copper 31·8, water 36·1.

B.B. on charcoal with soda affords metallic copper. Soluble in water. A polished plate of iron introduced into the solution causes the copper to be deposited

Blue vitrol is found in waters issuing from mines, and in connection with rocks containing copper pyrites, by the decomposition of which it is formed. Its foreign localities are the Rammelsberg mine near Goslar in the Hartz, Fahlun in Sweden, also Anglesea, and Wicklow; also Rio Tinto mine, Spain. The waters of the Rio Tinto mine have yielded annually 1800 cwt. of copper, consuming 2400 cwt. of iron. At Wicklow about 500 tons of iron were laid in the pits at one time, and in about twelve months the bars were dissolved, and every ton of iron yielded a ton and a half to two tons of a reddish mud, which was oxyd of copper, each ton affording 16 cwt. of pure copper. Found at the Hiwassee copper mine in Polk Co., Tennessee, 30 miles from Cleveland.

When particular it is evenly add in dwaing connections, and in the printing of cetters.

When purified, it is employed in dyeing operations, and in the printing of cotton and linen, and for various other purposes in the arts. It is manufactured mostly

from old sheathing copper, copper trimmings, and refinery scales.

ALUNOGEN, Beudant. Feather Alum, in part. Hair Salt, in part. Neutral Sulphate of Alumina. Davyt. Federalaun. Halotrichite, Glocker. Haarsalz, Werner. Thonerde Schwefelsaure.

Usually in delicate fibrous masses or crusts; also massive. H.=1.5-2. G.=1.6-1.8. Lustre vitreous-silky. Color white, or tinged with yellow or red. Subtranslucent-subtransparent. Taste like that of common alum.

Composition.—XIS+18H=Alumina 15:42, sulphuric acid 35:99, water 48:59. Analyses: 1, 2. Boussingault, (Ann. Ch. Ph. xxx, 109); 3, Mill, (Quart. Journ. 1828, p. 382); 4, Hartwall, (Jahresber. x, 178); 5, H. Rose, (Pogg. xxvii, 317); 6, 7, 8, 9, Rammelsberg, (Pogg. xliii, 180, 399); 10, Herapath, (Chem. Gaz. 1846, p. 422):

	0, 1, 00	-	-				-	NODYNEED AND PROPERTY.
		A 1	S	H	Fe	Mg	Ca	Si
1.	Saldana,	16.00	36.40	46.60	0.004	0.004	0.00	2=99.010, Bouss.
2	Pasto,	14.98	35.68	49.84	-		18	=100.00, "
3.	Chioachi, Davyte,	15.00	29.00	51.80	1.20	_	_	-=Earthy 3.0=
	The second second							100-00, Mill.
4.	Milo,	14.98	40.31	40.94	-	0.85	_	1 13, Na 1 13, K 0 26,
	China Piline							HCl 0'40=100, Hart.
5.	Copiapo,	14.63	36.97	44.64	2.58	0.14	_	1.37=100.33, Rose,
6.	Kolosoruk,	15.57	85:82	48.61	-	-	-	-==100, Ramm.
7.	Friesdorf,	14.87	37:38	45.16	-	-	0.15	K0.22, Fe2.46=100.24, R.
8.	Potschappel,							Ko 32, Feo 67, Mn1 02, R.
9.	Freienwalde,	11.23	35.64	48.84	_	1.91	0.45	Si 0.43, Fe 0.72, K 0.47,
	AND DESCRIPTION OF THE PARTY OF							Mn 0.31=100, Ramm.
10.	Adelaide, N. S. W.,	17.09	35'63	46.70	_	Cu0.04	and	earthy substance 0.50, H.

a And loss.

B.B. intumesces and fuses easily. Very soluble.

This species, a hydrous sulphate of alumina, results both from volcanic action and the decomposition of pyrites in coal districts and alum shales, and occurs at the localities above mentioned, besides many others. It is found as an efflores-cence in numerous places in the United States.

A salt of allied composition from Ararat, analyzed by Göbell, (Schw. J. lx, 401), afforded alumina 3875, sulphuric acid 58 58, sulphate of protoxyd of iron 278=

100.11=\(\frac{1}{4}\)\(\frac{1}{8}\)\sigma; the water was not determined.

The clintonite was discovered over twenty years since, and thus named by Mesur. Fitch, Mather, and Horton, in honor of the Hon. De Witt Clinton. It was subsequently analyzed by Clemson and named Septertite. Dr. Thomson's Helmenite was based on the same mineral. Breithaupt makes the crystallization monoclinic, and gives the angle between the lateral planes 94°.

CHLORITOID, Chloritspath, Fiedler. Barytophyllit, Breit. Masonite, C. T. Jackson.

Coarsely foliated, massive, folia often curved or bent, and brittle; sometimes also a transverse cleavage.

H.=5.5—6. G.—3.557, chloritoid; 3.450, masonite; 3.52, Hermann, (anal. 6). Color dark gray, greenish-gray, greenishblack. Streak uncolored, or slightly greenish. Lustre weak. pearly.

Composition.—R'Si\$+2AISi\$+3H=(\B'+\AI)Si\$+H=Silica 27.6, alumina 31.2, protoxyd of iron 32.9, water 82=100. Whitney obtained one third less water.

Also for the chloritoid of Asia Minor and Bregratten, R'Si+3AlSi+4H=(1R' +#BSi+#H=Silies 240, alumina 40.5, protoxyd of iron 28.4, water 7.1. Bregratten mineral contains one third less water, (‡H in the last formula).

Analyses: 1, Bonsdorff, (G. Rose, Reise n. d. Ural, i, 252); 2, J. D. Whitney, (Proc. Bost. S. N. Hist. 1849, 100); Delease, (Ann. Ch. Phys. [3], ix, 385); 4, Kobell, (J. f. pr. Ch. lviii, 40); 5, J. L. Smith, (Am. J. Sci. [2], xi, 64); 6, Hermann, (J. f. pr. Ch. hii, 18); 7, Kobell, (Gel Anz. Ap. 1854):

	Bi	Æı		Йg	Ħ
 Chloritoid, 	27.48	35-57	27 05	4-29	6-25, Mn 0-30=101-64, Bonsd
2. Masonite,	28-27	32 ·16			5-00=99-28, Whitney.
3. Bismondine,	24.1	43-2	23.8	_	7 v, Ti tr. = 98 7, Delesse.
4 "	2575	37:50	21 100	6.50	7:80, undec. 0:5=08:75, Kobell
5. Asia Minor,	23-91	39.52	28 05		7-08=98-56, Smith.
6. Katharinenburg,	24.54	8072	17:30	3.75	6.38, Fe 17.28=99.97, Hermann.
7. Bregratten.					5.50, " 6.00=100:40, Kobell,

In a matrass yields water. B.B. infusible, but becomes darker and magnetic. Wholly dissolved by sulphuric acid. The masonite fuses with difficulty to a dark

Occurs at Koroibrod near Katharinenburg in the Ural, associated with mica and kyanite; at Bregratten in the Tyrol. The masonite occurs in compact argillite, near

Natic village, Rhode Island.

A related mineral found on the Corundum of North Carolina has been called Corundophilite by Shepard, (Am. J. Sci. [2], xii, 211). Shepard mentions some angles which are nearly those of common mica. It is dark green, lamellar, brittle. No analyses given except one with 20 per cent. loss.

The Sismondine of Delesse occurs at St. Marcel, in chlorite slate, and resembles chloritoid, agreeing in composition, according to von Kobell, with the Bregratten mineral; color dark grayish or blackish green; structure foliated; G .= 3.565; H.=5.5.

B.B. nearly infusible and forms a blackish glass; after heating, magnetic. Yields water; with borax dissolves and affords the reaction of iron; not dissolved in strong muriatic acid, but attacked by sulphuric after long heating.

CHLORITE SPAR -A mineral from the Ural, referred to chloritoid and resembling it, afforded Erdmann (J. f. pr. Chem. vi, 89) no water. He obtained Si 24-90. Al 46-20, Fe 28-89, which is equivalent to Si *Al *Fe *. or Fe *Al + 2Al Si.

CRONSTEDTITE, Steinmann. Chloromelan, Naumann.

Rhombohedral. Occurs in hexagonal prisms, tapering towards the summit, or adhering laterally; also in diverging groups, reniform and amorphous. Cleavage: basal, highly perfect.
H.=2.5. G.=3.348. Lustre brilliantly vitreous. Color brown-

ish-black. Streak dark leek-green. Opaque. Not brittle. Thin

laminæ elastic.

Composition.—R*Si\(\frac{1}{2}\)+\(\frac{1}{2}\)H*\(\frac{1}\)H*\(\frac{1}\)H*\(\frac{1}{2}\)H*\(\frac{1}{2}

	Si	Fe	Mg	Mn	Ĥ
1.	22.452	58.852	2.885	5.078	10.700=99.968, Steinmann.
2.	22.452	27.112	2.885	5.078	10.700, Fe 35.350=103.577, Kobell.

B.B. froths and fuses on the edges, yielding, according to Kobell, a magnetic gray globule. With borax gives the reaction of iron and manganese. In powder gelatinizes in concentrated muriatic acid.

Accompanies hydrate of iron and calc spar, in veins containing silver ores, at Przibram in Bohemia. It occurs also at Wheal Maudlin in Cornwall, in diverging groups. Named after the Swedish mineralogist and chemist, Cronstedt.

SIDEROCHISOLITE, Wernekink, Pogg. i, 387.

Hexagonal or rhombohedral. Observed planes O, I, 1. Crystals minute and often hemispherically grouped. Cleavage: basal, perfect. Massive.

H.=2.5. G.=3-3.4. Lustre splendent. Color pure velvetblack when crystallized, dark greenish-gray. Streak leek-green,

greenish-gray. Opaque.

Composition.-Fe3Si1+1H. Analysis by Wernekink, (on three grains of the mineral, loc. cit.):

> Fe Fe 75.5, Si 16.3, ·Al 4·1, H 7.3=103.2, Wernekink.

B.B. fuses easily to an iron-black magnetic globule, according to Wernekink; infusible, Berzelius. Gelatinizes in muriatic acid.

Crystallized specimens occur in cavities of magnetic pyrites and sparry iron ore,

at Conghonas do Campo in Brazil. Named from σιδηρος, iron, and σχιστος, cleavable, λιθος, stone.

Chamoisite, as analyzed by Berthier, (Ann. d. Mines, v, 393), has nearly the above composition, his result giving

Si 14-3, Fe 60-5, Al 7-8, H 17-4=100, with 15 per cent, of carbonate of lime.

It is considered a mixture of magnetic iron and a hydrous silicate of alumina. It occurs in beds of small extent in a limestone mountain abounding in ammonites at Chamoisin in the Valais. It has a black earthy appearance, and becomes red before the blowpipe.

MARGARITE Parks Periginance L. Emergine Smith Commission and Class

Trimetrie: Lemihedral, with a monoclinic aspect, like Muscovite. $I: I=119^{2}-129^{2}$, $\theta: r=152^{2}-153^{2}$, $\theta: t=144^{2}-145^{2}$. $\theta: i=120^{\circ}-134^{\circ}, \ \theta: ii=00^{\circ}$. Lateral planes horizontally stria-



teil Cleavage: basal eminent. Usually in intersecting or aggregated lamings, sometimes compact massive, with a somewhat scaly structure.

H.=3·5—4·5. G.=3·032—2·99. the latter for Margarite, Hermann: 2:995 Emery-

lite. Silliman, Jr. Lustre of base pearly, laterally vitreous. Color grayish, reddish-white, yellowish. Translucent-subtranslucent. Laminæ rather brittle.

Composition - BSi+831Si+1H=Silve 3 1. alumina 51 2. lime 11 5, sois 24.

water 42. Or, making the water tasic, 22. H Si2-34-54.

Analyses: 1-7. J. L. Smith. Am. J. Sci. [2], xi. 52. and xv. 2.5 : 1-12. W. J. Craw. 10. viii, 27c : 14. B. Silliman. Jr., this Min. Sci. edit., 362); 13. W. J. Craw. (ibid. : 16. C. Hartshorne in Laboratory of J. C. Booth. (ibid. : 56: : 17. Hermann. J. f. pr. Chem. IIII, 1 : 15. 12. J. L. Smith and G. J. Brush. Am. J. Sci. [2], xv. 279:

```
Ξi
                                 ₹ı
                                               Ča Ng K. Na
                          2976 5 35
                                      175
                                              18 50 5
                                                           15 341.J. L Selts.
 1. Gan ich-iach.
                         25 - 0.

0. - 22 49 - 67 - 2 - 0.

29 - 67 4 5 4 5 - 1 6 0.

0. - 21 4 - 62 - 1 6 5 0.

0. - 21 4 - 62 - 0. 67
                                      1:55 11:57 truce
 2 Island of Nivaria.
                                                           231 342. J. L. Smith
                                                           236 462 J. L SERE
                                             1. A trace
                                             1 32 45
   Island of Naxes
                                                           125 557.3.1. 52.5
 4
                                              miet 5: 5. J. L Smith
                                                                 4 521. J. L. Smith
4 51. J. L. Smith
                                       70.50
                                                           ..
                                             915A 11
 7. Gunneh-dagh.
                          Sime: 45ml mml
                                                           281 072 Ma : race.
                          5175 4rm 15.
                                              9.41
                                                                          L Salah
                         1945 - 517 2 1479 1275
4191 4044 — 1046
                                                                 5-4. J. L. Smith
S. Sileria.
                                       221 (27, W. J. Cras
10. Village Green, Pal.
                                             10%6 030
                                                           127 - 727, W. J. Craw
122 - 427, W. J. Craw
                          8106 5120
11.
12
                          $126 5160
                          30:15 31:40
                                                           277 452, W. J. Craw

    Buncombe Co., N. C. 29:17 48:40.

                                              9:57 1:24
                                                           6.12
                                                                Francis J.
                                                          247 744 W. J. Caw.
15. Unionville. Pal.
                          2279 50-57
                                            1151 062
                                                         mden ( %). Harrahame
1768 4 4=1 s do.Her
                          $2:15 54:25 trace 11:56 65:5
16.
17. Margarite.
                          5246 4915
                                      . 54
                                              742 8-21
                                                          157 5 = 2 2 . S.
200 47 = 100 . T
16.
                          28:47 50:24 1:65 11:50 0:70
19.
                          25764 51766
                                             1275 065
```

• 5 of this is K trace of K.

The specimens of Margarite analyzed by Smith and Brush, were from Sterring. the original locality, and leave no doubt of the identity, as observed by Smith. The early analyses of Margarite were wide from the truth. Cornad-like and Clingman see were based on an incorrect determination of the silica in the analyses.

Margarite occurs in chlorite at Sterzing in the Tyrol; at the different localities of emery in Asia Minor, and the Grecian Archipelago, as discovered by Dr. Smithwith corundum at Village Green, Delaware Co., Pa.; at Unionville, Chester Co., Pa., (Corundellite : at the corundum locality in Bunconde Co., North Carolina, (Clingmaniter; with the corundum of Katherinenburg, Urals. It occurs massive in Pennsylvania. Also found at Greinerberg, Zillerthal, with chlorite.

COPPERAS. Green Vitriol. Melanterite, Boud. Eisen-Vitriol, Hous. Sulphate of Iron.

Monoclinic. $C=75^{\circ} 40'$; $I: I=82^{\circ} 21'$, $O: 1i=123^{\circ} 44'; a:b:c=1.310:1:0.8474.$

 $0: ii = 104^{\circ} 20'$. $O: I = 80^{\circ} 37'$


 $O: -1i = 136^{\circ} 13'$. $0:1i=123^{\circ}44'.$

 $0:-159^{\circ}6'$.

 $-1:-1=101^{\circ}32'$.

Cleavage: O perfect, I less so. Generally massive and pulverulent.

H.=2. G.=1.832. Lustre vitreous. Color, various shades of green, passing into white; becoming yellowish on exposure. Streak un-colored. Subtransparent—translucent. Taste sweetish, astringent, and metallic. Fracture conchoidal. Brittle.



Composition.—FeS+7H=Sulphuric acid 28.8, protoxyd of iron 25.9, water 45.3. B.B. becomes magnetic; yields a green glass with borax. Soluble in twice its weight of water, and the solution is blackened by a tincture of nut galls. Exposingly the solution is blackened by a tincture of the solution is blackened by a tin ed to the air, becomes covered with a yellow powder, which is the sulphate of the peroxyd of iron

This salt usually proceeds from the decomposition of iron pyrites, which readily affords it, if occasionally moistened while exposed to the atmosphere. Occurs near Goslar in the Hartz, and also at Hurlet near Paisley, and in several of the Saxon and Hungarian mines. Usually accompanies iron pyrites in the United States, occurring as an efforescence; at Copperas Mt., a few miles east of Bainbridge, Ohio, it is associated with alum and pyrites. It is employed in dyeing and tanning and in the manufacture of ink and Prussian blue.

BIEBERITE, Haid. Cobalt vitriol. Red Vitriol. Sulphate of Cobalt. Kobalt-vitriol. Rhodalose, Beud.

Monoclinic. Usually in stalactites and crusts, investing other minerals. Lustre vitreous. Color flesh and rose-red. Subtransparent—translucent. Friable. Taste astringent.

Composition.—(Co, Mg)S+7H, from Winkelblech's analysis. Analyses: 1, Kopp, (Gehlen's J. [2], vi, 157); 2, Winkelblech, (Ann. d. Pharm. xiii, 265); 3, Beudant; 4, 5, Schnabel, (Ramm. 4th Suppl. 118):

Co 41.55=100, Kopp. 1. Bieber, 19.74 3871 29:053 19.909 46 830. Mg 3 864=99 656, Winkelblech. 2 .. 41.2, Fe 0.9, Beudant. 28-7 80.2 45.22, Ca 0.43, Mg 0.88, Cl 0.09, earthy subst. 1.14 Siegen, 28.81 28.30 =100·12, Schn. 88·13, Ca tr., Mg tr., Cl 0·05, earthy, 24·04=100, S. 20.84 16.50

In a matrass yields water, and when strongly heated, sulphurous acid. Communicates a blue color to glass of borax.

In the rubbish of old mines at Bieber, near Hanau, and at Leogang in Saltsburg

III. CALAMINE SECTION. Oxygen ratio between bases and silica, 1:1.

TRITOMITE GROUP, L. TRITOMITE, #Si+2H.

THORITE GROUP. THORITE, Th'Si+3H.

CERITE, (Če, La)³Si+3H.

CALAMINE GROUP, IIL CALAMINE, ZnºSi+14H(or 2H).

PREHNITE, (1(R, H)3+1-1-1)Si.

Appendiz. Chlorastrolite, Savite, Schneiderite, Carpholite.

- 2. Oxygen ratio of protoxyds and peroxyds, 1:3.
 - IV. ZEOLITE SECTION.—[For enumeration of species see beyond.]
 - 3. Oxygen ratio of bases and silica, 1 to less than 1.
- V. DATHOLITE SECTION.

[Among the Non-magnesian Hydrous Silicates, a large group—the Zeolite Section—corresponds with the Feldspar Section of Anhydrous Silicates, in having the oxygen of the protoxyds and peroxyds as 1:3; and to some extent there are analogies in crystallization as well as formula. Thus Analcime is related to Leucite, and Ittnerite to Sodalite, both in form and formula: while Heulandite and Orthoclase are each monoclinic, with a like oxygen ratio, 1:3:12. Still these analogies are not to be too closely pressed. Gismondine is regarded as more nearly related to the Scapolite Group; and Chabazite, excluding the water, has the oxygen ratio of Beryl, and Eudialyte, as well as of Pyrosmalite and Dioptase, besides being related in angles.

Another section, including Datholite, corresponds with the Andalusite Section of Anhydrous Silicates, the oxygen of the silica being less than that of the bases; another section (II) has the augite ratio; another (III) the garant ratio

In view of these and other considerations, the above prominent subdivisions are adopted.

The ratios on which the divisions are based, are, as with the magnesian species, for the most part independent of the water present in the compound. Thus in the Pectolite Section, excluding the water, Pectolite has an augite ratio (Frankenheim) as well as augite form. The same is true of Laumontite. So also Dioptase and Pyrosmalite have the form and ratio of the Beryl Group. Again, in the Calamine Section, Calamine and Prehnite are homocomorphous with one another, besides being each pyro-electric: and as written above, they have analogous formulas, (ratio 1:1), if the water of Calamine is excluded and that of Prehnite is basic.

On the other hand, if part of the water in Apophyllite be regarded as acting as a protoxyd base, the formula may be R*Si*+2H. The ratio of ingredients afforded by the analyses is 10Si, 8Ca, 1K, 16H; and if 6H out of the

Composition.—NaS+10H=Soda 19.3, sulphuric acid 24.8, water 55.9. Beudant's

Exanthalose from Vesuvius contains but two of water, (2H).

Occurs at Ischl and Hallstadt in Austria, also in Hungary, Switzerland, Italy, Spain, &c. Abundantly deposited at the hot springs at Carlsbad. At Kailus, on Hawaii, Sandwich Islands, abundant in a cavern, and forming from the action of volcanic heat and gases on salt water; effloresces with other salts on the limestone below the Genesee Falls, Rochester, N. Y.; also near the Sweetwater river, Rocky Mountains


The artificial salt was first discovered by a German chemist by the name of

Glauber, and hence its name.

Taking the plane 1i as 2i, the axes are nearly those of pyroxene, becoming a:b:c=0.55445:1:0.8962.

BOTRYOGEN. Red Iron-vitriol. Neoplase, Beud. Rother Vitriol. Fer Sulfaté Rouge, Duf.

Monoclinic. $C=62^{\circ}\ 26', I: I=119^{\circ}\ 56',$ $O: 1i=152^{\circ} 1\frac{1}{2}$; a:b:c=0.9188:1:1.5334. Observed planes as in the figure, with also 1i (on acute solid angle of base), 1 (on acute edge of base), and ii. O: I=113° 37′, O: 1i=125° 31′, O: 1=121° 4′, striated. Cleavage parallel to I. Crystals usually small. Often in reniform and botryoidal shapes, consisting of globules with a crystalline surface.



H.=2-2.5. G.=2.039. Lustre vitreous. Color deep hyacinth-red; massive varieties sometimes ochre-yellow; streak ochre-yellow, a little shining. Translucent. Taste slightly astringent.

Composition.—Fe'S'+3FeS'+8EH, Berz.—(1Fe'+1Fe)S'+9H—Sulphate of protoxyd of iron 190, ib. of peroxyd 483, water 327=100. Analyses by Berzelius, (Afh. iv, 807):

	FeS	FeFeS	Mg₹	ĊaB	Ĥ and loss.
1.	6.77	35.85	26 ·88	2.22	28·28=100.
2.	6.85	89.92	17.10	6.71	81·42=1 00.

B.B. intumesces and gives off water, producing a reddish-yellow earth, which, by using the reduction or oxydizing flame, is changed to protoxyd or peroxyd of iron. Remains unaltered if kept dry, but in a moist atmosphere it becomes covered with a dirty yellowish powder. Partly soluble in boiling water, leaving an ochreous residue.

Occurs at the copper mine of Fahlun, in Sweden, coating gypeum or pyrites. Named from Borpus, a bunch of grapes.

COPIAPITE, Haid. Yellow Copperas. Basisches Schwefelsaures Eisenoxyd.

In small grains, sometimes consisting of delicate hexagonal tables; angles undetermined. Cleavage: basal, perfect. Also fibrous and incrusting.

Lustre pearly. Color yellow. Translucent.

ANTHOSIDERITE Hausmann.

In tufts of a fibrous structure, and sometimes collected into feathery flowers. Resembles Cacoxene.

 $H_{c}=6.5$. $G_{c}=3.6$. Color ochre-vellow and vellowish-brown, somewhat gravish. Opaque or slightly subtranslucent. Gives sparks with a steel. Tough.

Composition.—FeSi⁴+H=Silica 60.4, peroxyd of iron 35.6, water 4.0=100. Analysis by Schnedermann, (Pogg. lii. 292): Si 60.08, Fe 34.99, H 3.59=98.66.

B.B. becomes reddish-brown, then black, and fuses with difficulty to a black


magnetic slag. Dissolves in muriatic acid.

From the province Minas Geraes, in Brazil, where it is associated with magnetic iron. Named from ares, flower, and sicapes, iron.

IL PECIOLITE SECTION.

APOPHYLLITE. Pyramidal Zeolite, J. Tesselite, Brevster. Oxhaverite, Breuster. Ichthyophthalmite. Albin, Wern. Mesotype Epointée, H.

Dimetric. $O: 1i = 128^{\circ} 38'; a = 1.2515$. Observed planes: 0, ii, i2, i3, 1, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$, $\frac{1}{3}$; $\frac{1}{3}$, $\frac{1}{3}$; $0: 1 = 119^{\circ} 30', O: \frac{1}{3}i = 147^{\circ} 58', 1: 1 \text{ (pyr.)}$ = $104^{\circ} 2'$, (bas.) = 121° , $ii: i3 = 161^{\circ} 34'$, $ii: i2 = 153^{\circ} 26'$. Crys



tals sometimes nearly cylindrical or barrel-shape. Cleavage: O highly perfect; Iless so. Also massive and lamellar.

H = 4.5 - 5.G = 2.335Haidinger, a variety from Iceland; 2.359, Thomson; 1.961, from Radauthal, R. Lustre of O pearly; of the other faces vitreous. Color white, or grayish; occasionally with a shade of green,

yellow, or red. Streak white. Transparent—opaque. Fracture uneven. Brittle.

Composition.—(R) Si3+2H, (in which R3=Ca, K, H, in the proportions 8:1:6) able proportion of fluorine in the mineral, but its relation to the compound is not clearly made out. Analyses: 1, 2, Berzelius, (Afhand. vi, 181); 3, 4, 5, Rammelsberg, (2d Supp. 16, and 3d Supp. 18); 6, C. T. Jackson, (this Min. 3d edit., p. 249); 7, E. L. Renkirt, (Am. J. Sci., [2], xvi, 84); 8, J. L. Smith, (private communication): reddish. Streak white. Transparent—subtranslucent. Fracture flat conchoidal, uneven; of massive varieties, splintery; and sometimes earthy. Brittle.

Composition.—KS+3XIS+6H=Alumina 37·13, sulphuric acid 38·53, potash 11·34, water 13·00. Analyses: 1, 2, Cordier, (Ann. des M. iv, 205, and v, 203, and Ann. Ch. Phys. ix, 71); 3, Descotils, (Ann. d. Mines, i, 319); 4, Berthier, (Ann. d. Mines, [4], ii, 459); 5, Sauvage, (ib. [4], x, 85):

	± 1	В	K	#re	н	Silica
1. Mt. Dor,	81.80	27.00	5.80	1.44	3.72	28.40==98.16, Cord.
2. Tolfa, cryst.,	39·6 5	35.49	10.02		14.88	(and loss), Cord.
8. Tuscany,	40.0	35.6	13.8		10.6	=100, Desc.
4. Hungary,	260	27.0	7.3	4.0	8.2	26 5=100, Berth.
4. Milo,	3 0 -0	81.0	9.40		10.6	19=100, Sauv.

The silica, which is an impurity, amounts to 60 per cent. in some varieties. B.B. decrepitates, and is infusible both alone and with sods. With borax, forms a colorless globule. In a matrass yields water, and finally sulphate of ammonia. When

pulverized, soluble in sulphuric acid.

Met with in crystals at Tolfa, near Civita Vecchia, in the neighborhood of Rome; also at Musay and Bereghszasz in Hungary; on Milo, Argentiera, and Nevis, Grecian Archipelago; and at Pic de Sancy, France, Dep. Puy de Dome. It occurs with volcanic rocks. The compact varieties from Hungary are so hard as to admit of being used for millstones. Alum is obtained from it by repeatedly roasting and lixiviating, and finally, crystallizing by evaporation.

JAROSITE, Breithaupt, Berg. u. Hüttenm. Ztg. 1852.

Rhombohedral. $R: R=88^{\circ} 58'; O: R=124^{\circ} 32'; a=1.2584$. Cleavage: basal. G.=3.256. Color yellowish.

Composition.—Perhaps KS+4FeS+6H[+FeH] Ramm; KS+4FeS+9H, Gelbeisenerz, Ramm. Analysis: 1, Richter, (loc. cit); 2, Rammelsberg, (Pogg. xliii, 132); 3, Scheerer, (Pog. xlv, 188):

```
₽e
                   8
                                             Ķ
1. Jarosite,
                          52.5
                                    17
                                            67-
                                                           9.2=98.9, Richter.
                  28.8
2. Gelbeisenerz,
                 32·111 46·736 Cn 0·643
                                           7.882
                                                           13.564 (tr. of Am.)=
                                                                100.986, Ramm.
3. Soda-Copperas, 32.42
                                                   4.08
                                                           18·13=99·55, Scheer.
                         49.87
                                a With little soda.
```

The potash-copperas (Gelbeisenerz, Vitriolgelb) from Bohemia is recognized by Rammelsberg as related to the Jarosite, though perhaps not identical with it. The soda-copperas is similar.

From Baranco Jaroso in the Sierra Almagrera, Spain. May be isomorphous with alunite.

WEBSTERITE, Levy, Duf. Aluminite. Hallite. Subsulphate of Alumina.

Reniform, massive; impalpable.

H.=1-2. G.=1.6606. Lustre dull, earthy. Color white. Opaque. Fracture earthy. Adheres to the tongue, and is meagre to the touch.

		X 1	B	Ĥ
1. H	alle,	20.263	23.365	46.372=100, Stromeyer.
2.	**	29.23	23.25	46 34, Ca 1 18=100, Schmid.
3. M	lorl,	30.98	23.68	45.34=100, Strom.
4 N	ewhaven,	29.87	23.37	46.76=100, Strom.
5. L	unel Vieil,	2972	23.45	46'80=99 97, Dufrénoy.
6. A	uteuil,	30.00	23.00	47:00=100, Dumas.
7. E	pernay,	89.70	30.06	39.94, CaS 0.30=100, Lassaigne.
8. S.	of Halle,	39.50	11.45	48.80=99.75, Marchand.
9.	#	37-71	12.22	49.18, ČaČ 1.00=100.11, Backs
10.	"	38.81	12.44	47.07, CaC 1.68=100, Wolff.
11.	"	36.00	17.00	47.2=100.2, Marchand.
12.	**	35.96	14.04	50.00=100, Märtens.
13.	11	36.17	14.54	49.03=99.74, Schmid.

The formula of the analyses 1 to 6, (true websterite), is \$\frac{18}{418} + 9\hat{H}\$. The others are either different compounds or impure websterite. Rammelsberg writes their constitution as follows, putting W for the above formula:

No. 7, 2W+Xl(fH). Nos. 8-10, 2W+3XlH°, (=Xl°S°+36H, Marchand). No. 11, 3W+2XlH°, H (=Xl°S°+36H, Marchand). Nos. 12, 13, W+XlH°, (=Xl°S+15H, Marchand).

A variety from Huelgoet, analyzed by Berthier, corresponds to 2W+3XIH.

Fuses with difficulty. Easily soluble in acids without effervescence. Absorbs water, but does not fall to pieces. At 100° C. gives up half its water.

It occurs at Newhaven, Sussex, in reniform and botryoidal concretions, imbedded in ferruginous clay, which rests on the chalk strata; also under similar circumstances at Epernay, in Lunel Vieil, and Auteuil, in France, and in plastic clay, with gypsum, at Hallé and Morl in Prussia.

PISSOPHANE, Breithaupt. Garnsdorffite.

Amorphous, or stalactitic.

H.=1.5. G.=1.93—1.98. Lustre vitreous. Color pistachio-, asparagus-, or olive-green. Transparent. Very fragile. Fracture conchoidal.

Composition .- Erdmann (Schweig J. lxii, 104) obtained :

S 1. Green. 35-155 9.788 12.700 41.690 gangue and loss, 0.717=100. 35.301 9.799 12.487 41.700 0.709=100. 3. Yellow, .55 6.799 40.060 11.899 40.131 1-111=100.

Probably not a simple mineral. Perhaps Nos. 1 and 2, R*S+15H, and No. 3, R*S+15H. The relation in the former is more exactly R*S*+30H. For the most part insoluble in water. Easily soluble in muriatic acid. B.B. becomes black. In a glass tube gives alkaline water.


Occurs at Garnsdorf, near Saalfeld, and at Reichenbach, Saxony, on alum slate.

LINARITE, Brooke. Cupreous Anglesite. Cupreous Sulphate of Lead, Brooks.

Bleilasur. Kupferbleispath. Linarit.

Monoclinic. $C=77^{\circ}$ 15'; $I:I(\text{over }ii)=61^{\circ}, O:1i=140^{\circ}$ 5', a:b:c=0.4927:1:0.5745. Observed planes, as in the annexed figure, with also \$i, \$i, \$i and 2i, on the acute edge between O and ii, and the lateral plane ii (B. & M.) 0: ii=102° 45', ii: 1i=105° 35', $ii: 2i=128^{\circ} 6', ii: \frac{2}{3}i=96^{\circ} 18'$. Twins: composition face iicommon; $O: O'=154^{\circ} 30'$. Cleavage: 541

very perfect parallel to ii; less so to O. $\dot{H} = 2.5 - 3$. G. = 5.2 - 5.5. Lustre vitreous or adamantine. Color deep azure blue. Streak pale blue. Translucent. Fracture conchoidal.



Composition.—PbS+CuH=Sulphate of lead 757, oxyd of copper 198, water 4.5. Analyses: 1, Brooke, (Ann. Phil. [2], iv, 117, 1822); 2, Thomson, (Phil. Mag. 1840, Dec. 402):

Pb\$ 75.4 Ču 180 H 4.7=98.1, Brooke. 1. Wanlockhead, 5.5=100, Thomson; G.=5.2137. 2. 197

In the blowpipe flame, it affords indications of copper and lead. This mineral occurs at Leadhills; also at Roughten Gill, in Cumberland, in crystals sometimes an inch long; at Linares in Spain, and near Ems.


ALTERED FORMS. - Linarite occurs altered to Cerusite, a change like that of Anglesite to Cerusite.

BROCHANTITE. Brochantit, Levy. Konigine, Levy. Krisuvigite, Forchhammer.

Trimetric. $I: I=104^{\circ} 10', O: 2\bar{\imath}=147^{\circ} 14\frac{1}{2}'; a:b:c=0.3232:$ 1:1.2838. Observed planes as in the annexed figure, with $\tilde{\imath_2}$. $i\vec{\imath}$: $i\vec{\imath}$ (ov. $i\vec{\imath}$)=114° 36′, $1\vec{\imath}$: 1 $\vec{\imath}$ (ov. $i\vec{\imath}$)=28° 8′, $i\vec{\imath}$: 1 $\vec{\imath}$ =104° 4′, $2\vec{\imath}$: 2 $\vec{\imath}$ (ov. 0)=114° 29′, $i\vec{\imath}$: $i\vec{\imath}$ =90°. 542

Cleavage: ii very perfect; I in traces. Also massive; reniform with a columnar structure.

 $H_{.}=3.5-4$. $G_{.}=3.8-3.91$. Lustre vitreous. Color emerald-green, blackish-green. Streak paler green. Transparent—translucent.



Composition.—CuS+8CuH[=Cu4 S H3]=Sulphuric acid 177, protoxyd of copper 70.3, water 12.0. Analyses: 1, 2, Magnus, (Pogg. xiv, 141); 3, Forchammer, (J. f. pr. Ch. xxx, 396); 4, Berthier, (Ann. Ch. Phys. 1, 360):

	3	Ču	Źn	Рb	Ĥ
1. Retzbanya,	17.182	62-626	8.181	0.080	11.887=99.856, Magnus.
2. "	17:426	66-985	8.145	1.048	11.917=100.471, Magnus
8. Krisuvigite,	18.88	67.75			12.81=99.44, Forchhammer.
▲ Mexico,	16.6	66·2			17.2=100, Berthier.

The last from Mexico, corresponds to Cu⁴S H⁴.

Rivot found in crystals of brochantite of a fine green color, which afforded a slight effervescence with acids, S 19 4, Cu 57 9, H 18 5, with Cu 5 0, C 1 2, H 1 2= 982. The mineral had undergone partail alteration, as shown by the carbonate of copper present, (Delesse's Extr. de Min., Ann. d. M. [5], iii, 740).

B.B. fuses on charcoal and yields metallic copper.

Occurs in small but well defined crystals, with malachite and native copper, at

Katherinenburg in Siberia; the Konigine was found at the same locality; also in

The rapid change to which this mineral is liable, may be prevented by dipping the specimen in a thin solution of gum Arabia. The change consists in a loss of 1 to 2 per cent of water. Some varieties do not undergo this change. Dufrinoy makes $I: I=64^{\circ}$ VI.

The Edelforsite of Retzius, or the Red Zeolite of Edelfors, is referred here by N. J. Berlin, who considers it impure from mixed silies quartzy and related to the red zeolite of Upsala analyzed by him. It afforded Retzius Si 60-28. Ed 15-42 Ca 6-15, Fe 4-16. Mg and Min 6-42 H 11:05—59-53. A similar mineral from Fahlus yielded Hisinger Si 60-66. Ed 15-6. Fe 1-5. Ca 6-6. H 11:25—5-36. We then be obtained for the Edelfors zeolite Si 53-76. Ed 16-47. Fe 4-52. Ca 10-50. H 11:25—5-28.

LEONHARDITE, Blum.

Monoclinic. $I: I=83^{\circ} 30'$, and $96^{\circ} 30'$; $O: I=114^{\circ}$. Cleavage parallel with I very perfect, basal imperfect. Also columnar and granular.

H.=3-3.5. G.=2.25. Lustre of cleavage face pearly, elsewhere vitreous. White, sometimes yellowish, seldom brownish. Usually whitens on exposure like Laumonite.

Composition.—3CaSi+4AlSi²+15H—Silica 54⁴0, alumina 22³3, lime 9⁻¹1, water 14⁴6. Equally near the analyses and analogous to the formula of Laumontite, if written R*Si²+3AlSi²+9H, in which B consists of Ca and H in the proportion of 3:1. More probably the oxygen ratio for the bases and silica is 4:9, as in horablende, which (taking 12H,—silica 56⁻²2, alumina 22⁻⁷7, lime 9⁻²2, water 11⁻⁹2.

Analyses: 1, Delffs, (Pogg. lix, 336, 239); 2, Babo, (ibid); 3, 4, G. O. Barnes, under the direction of J. D. Whitney, (Am. J. Sci. [2], xv, 449);

	Si	X 1	Ċa	Ŕ
1.	56:128	22-980	9~251	11.641=100, Delffs.
2	5540	24-36	16:50	12:30=102:16, Babo.
3.	55-95	21:04	16:49	11-93==99-42, Barnes.
4.	55-04	22-34	10%4	11-93=29-95, Barnes.

Delffs' analysis was made after drying the mineral at 100° cent.; dried at the ordinary temperature it gave 13:547—13:8:7 water, which corresponds to the above formula. B.B. exfoliates, froths, and easily melts to an enamel. Dissolves in acids. From a trachytic rock at Schemnitz in Hungary. Also at Copper Falls, Lake Superior Region, a variety which does not alter on exposure.

CATAPLEIITE. Katapleiit, Weibye and Sjögren, Pogg. lxxix, 299.

In imperfect prismatic crystals with perfect basal cleavage.

H. near 6. G.=28. Lustre nearly dull, weak vitreous on surface of fracture. Color light yellowish-brown. Streak isabella-yellow. Opaque.

Composition. — $R^9\ddot{S}i^9+2Zr\ \ddot{S}i^9+6\dot{H}=(\frac{1}{4}\dot{R}^9+\frac{1}{4}Zr)\ddot{S}i^9+2\dot{H}$. Analyses by Sjögren. (loc. cit.):

B i	\mathbf{z}_{r}	Æl	Ñа	Ĉa	Гe	Ĥ
1. 46.83	29.81	0.45	10.88	8.61	0.68	8-86==101-02.
2 46.52	29·3 8	1.40	10.06	4.66	0.49	9.05=101.55.

B.B. in the platinum forceps fuses easily to a white enamel; with borax a clear colorless glass; blue with cobalt solution. Easily soluble in muriatic acid without gelatinizing.


From the island Lamö near Brevig, Norway, along with zircon, leucophane, mosandrite and tritomite.

BORATES. 393


BORACITE, Werner. Borate of Magnesia, P. Borazit. Magnésie boratée, H.

Monometric; tetrahedral. Figs. 1, 53, 54, and the following. Observed planes as in the figures, with also 22 and 5\frac{4}{3}.

Cleavage: octahedral, in traces. Also amorphous.



544



H.=7. G.=2.974, Haidinger; 2.9134, massive, Karsten. Lustre vitreous, inclining to adamantine. Color white, inclining to gray, yellow and green. Streak white. Subtransparent—translucent. Fracture conchoidal, uneven. Pyro-electric, even when massive.

Composition.—Mg*B4—Boracic acid 70.0, magnesia 30.0. Stromeyer, (Gilbert's Annalen, xlviii, 216), Arfvedson, (K. V. Ac. H., 1822, p. 92), and Rammelsberg, (Pogg. xlix, 445), obtained:

Boracic acid, 67 69.6 69.252 Magnesia, 38=100, St. 30.3=100, Arf. 30.748=100, Ramm.

A compact boracite from Stassfurth, afforded Karsten, (Pogg. Ann. lxx, 557), Magnesia 29.48, boracic soid 69.49, with 1.03 of carbonate of iron and manganese, and hydrated oxyd of iron. H.=4.5, G.=2.91.

B.B. intumesces, and forms a glassy globule, crystalline and white on cooling. Observed in beds of anhydrite, gypsum or salt: in crystals at Kalkberg and Schildstein in Lüneberg, Hanover; at Segeberg near Kiel in Holstein; at Luneville, La Meurthe, France: massive or as part of the rock of the Salt Mine at Stassfurth, Prussia.

RHODIZITE, G. Rose, Poggendorff's Annalen, xxxiii, 258.

Monometric and tetrahedral, like boracite; planes 1 smooth and shining, i often uneven. H.=8. G.=3·3—3·42.

B.B. in the platinum forceps, fuses with difficulty on the edges to a white opaque glass, tinging the flame at first green, then green below and red above, and finally red throughout. With borax and salt of phosphorus, fuses to a transparent glass.

Supposed to be a lime boracite. It was found by G. Rose in minute crystals on red tourmalines from near Mursinsk, Siberia, and named from 'pobiçue, in allusion to its tinging flame red. The largest crystals seen were two lines in diameter.

HYDROBORACITE, Hess. Hydrous Borate of Lime and Magnesia.

Resembles fibrous and foliated gypsum. H.=2. G.=1.9-2. Color white, with spots of red from iron. Thin plates translucent.

Composition.—Ca*B*+Mg*B*+18H=Boracic acid 47*7, lime 14*3, magnesia 10% water 27*7. Analyses by M. Hess, (Pogg. xxxi, 49):

B Ca Mg H 1. 49 922 13 298 10 430 26 330 = 100. 2. 49 22 13 74 10 71 26 33 = 100.

B.B. fuses to a clear glass, tinging the flame slightly green, and not becoming opaque. In a matrass affords water. Somewhat soluble in water, and yielding a slightly alkaline reaction. Dissolves easily in muriatic and nitric acids.

Sightly alkaline reaction. Dissolves easily in muriatic and nitric acids.

Hydroboracite was first observed by Hess, in a collection of Caucasian minerals. The specimen was full of holes filled with clay, containing different salts. It may be mistaken for gypsum, but is readily distinguished by its fusibility.

HAYESINE. Borate of Lime, Hayes. Borocalcite. Borsaurerkalk. Hydroborocalcit. Tiza.

In masses having a globular form, consisting of interwoven fibres. Opaque, snow-white, silky, and having a peculiar odor.


Composition.—CaB²+6H, Hayes=Boracie acid 45.98, lime 18.45, water 35.57. Analyses: 1, A. A. Hayes, (Am. Jour. Sci. [2], xviii, 95); 2, Bechi, (ib. xvii, 129):

B Ca H
1. Peru, 46:11 18:89 35:00=100.
2. Tuscany, 51:135 20:850 26:250=100.

Hayes observes in Am. J. Sci. xviii, 95, July, 1854, that the pure mineral domestic contain soda, and the soda in the following analyses he attributes to impurities. Ulex obtained, (Ann. Ch. u. Pharm. 1xx, 49), Boracic acid 49.5, lime 15-2, soda 88, water 25-8; and A. Dick, (Phil. Mag. [4], vi, 50), Boracic acid (by loss) 45-46, lime 14-32, soda 8-22, potash 0-51, sulphuric acid 1-10, NaCl 2-65, sand 0-32, I and P trace. Ulex gives the formula Na, 2Ca, 5B+10H. (Named Ulexie in last edition of this work, on the ground of a supposed difference in composition from the Hayesine). Occurs over the dry plains near Iquique in Southern Peru, in white reniform

Occurs over the dry plains near Iquique in Southern Peru, in white reniform masses, from the size of a hazlenut to that of a potato, where it is called tiza; the masses consist of interwoven silky fibres which rapidly absorb water, and have a slightly saline taste. It is associated with Pickeringite. The mineral analyzed by Professor Bechi forms an incrustation at the Tuscan lagoons.

BORAX. Tincal. Pounxa. Swaga. Zala. Borate of Soda.



Monoclinic. $C=73^{\circ}\ 25'$, $I:I=87^{\circ}$, $O:2i=132^{\circ}\ 49'$; a:b:c=0.4906:1:0.9095. Observed planes as in the annexed figure, with also 4i. $O:I=78^{\circ}\ 40'$ and $101^{\circ}\ 20'$, $O:1=139^{\circ}\ 30'$, $O:2=115^{\circ}\ 53'$, $O:4i=114^{\circ}\ 51\frac{1}{2}$, O:i=90', $ii:I=133^{\circ}\ 30'$. Cleavage: ii perfect; I less so; ii in traces. Plane of composition $ii:0:0:146^{\circ}\ 50'$.

H.=2—2.5. G.=1.716. Lustre vitreousresinous; sometimes earthy. Color white; sometimes grayish, bluish or greenish. Streak white-Translucent — opaque. Fracture conchoidal. Rather brittle. Taste, sweetish-alkaline, feeble-

Composition.—NaB*+10H=Boracic 36.58, soda 16.25, water 47.17. B.B. pure up, and afterwards fuses to a transparent globule, called the glass of borax. It is soluble in water; the solution changes vegetable blues to greens. With fluor spar and bisulphate of potash, it colors the flame around the powder a clear green.

BORATES. 395

Borax was originally brought from a salt lake in Thibet. The borax is dug in masses from the edges and shallow parts of the lake, and in the course of a short time the holes thus made are again filled. This crude borax was formerly sent to Europe under the name of tincal, and there purified. It is now extensively made from the boracic acid of the Tuscan lagoons, by the reaction of this acid on carbonate of soda. It has also been found at Potosi in Peru, and in Ceylon. It occurs in solution in the mineral springs of Chambly, St. Qurs, &c., Canada West, (Hunt, Logan's Geol. Rep. 1853).

This salt is employed in several metallurgical operations as a flux, is sometimes used in the manufacture of glass and gems, and extensively in the process of

soldering

Prof. Bechi has analyzed a borate occurring as an incrustation at the Tuscan lagoons, which afforded B 43.56, Na 19.25, H 87.19=100, giving the formula NaB³+6H, (Am. J. Sci., [2], xvii, 128).

LAGONITE.

An earthy mineral of an ochreous yellow color.

Composition.—FeB*+3A=Boracic acid 49.5, peroxyd of iron 37.8, water 12.7=100. Analysis by Prof. Bechi, (Am. J. Sci. [2], xvii, 129):

B 47.95, Fe 36.26, H 14.02, Mg, Ca and loss 1.77.

Occurs as an incrustation at the Tuscan lagoons.

LARDERELLITE, Bechi.

Very light, white and tasteless. Appearing under the microscope to be made up of minute oblique rectangular tables; M:T=110°, Amici.

Composition.—NH40B4+4H. Analysis by Prof. Bechi, (Am. J. Sci. [2], xvii, 180): B 68.556, NH40 12.784, H 18.325.

Dissolves in hot water, and is transformed into a new salt, represented by the formula NH40B⁸+9H.

Occurs at the Tuscan lagoons.

WARWICKITE, Shepard, Am. J. Sci., xxxiv, 313, xxxvi, 85.—Enceladite; T. S. Hunt, ib., [2], ii, 30.

Monoclinic $I: I=93^{\circ}-94^{\circ}$. Usual in rhombic prisms with obtuse edges truncated, and the acute beveled, summits generally rounded; surfaces of larger crystals not polished. Cleavage: macrodiagonal perfect, affording surface with vertical striæ and traces of oblique cross cleavages.

H.=3—4. G.=3·188, Hunt. Lustre submetallic pearly on cleavage surface to subvitreous; often nearly dull. Color dark hairbrown to dull black, sometimes a copper-red tinge on cleavage surface. Streak bluish-black. Fracture uneven. Brittle.

Composition.—Essentially a borotitauate of magnesia and iron, with over 20 per cent. of boracic acid, Smith and Brush, (Am. J. Sci., [2], xvi, 293).

Yields water. B.B. alone infusible, but becomes lighter in color; with borax a

		B i	Za	H
1. Retzbanya,		2510	68-3	4·4 ==97·7, Smithson.
2. Limburg.		26-23	66-37	7-40==100, Bernelius.
2. Breisgau.		25-5	64.2	10-0 = 100, Berthier.
4. Leadhills.	G.=3·164.	23-2	66-8	10-8 =100-8, Thomson.
5. Nertschinsk.	G.=3871.	25-38	62-85	9-07. Pb 2-70=100, Hermans.
	G.=3·435,	25-96	65-66	8-38=100, Hermann.

Other analyses: K. Monheim, J. f. pr. Ch. xlix, 319; R. Schmidt, (ib. li, 267).
When pulverized, it dissolves in heated sulphuric or muriatic acid, and the selection of the sel tion gelatinizes on cooling. In a matrass yields water. B.B. decrepitates, less its transparency, intumesces, and emités green phosphorescent light; fusible with difficulty on the edges on charcoal; with borax melts to a clear glass, which does not become opaque on cooling. Swells up with sods and affords with difficulty funes of zinc; with cobalt solution becomes at first green, then light blue on the edges, and shows signs of fusion, while the blue color extends into the unfused resting and shows signs of fusion, while the blue color extends into the unfused portion.

Calamine and Smithsonite are usually found associated in veins investerated.


rocks accompanying ores of blende, iron, and lead, as at Aix la Chapelle, Raibe, Bleiberg, Iserlohn, Tarnowitz, Olkucz, Miedzanagora, Retzbanya, and Mendip Hills


&c. Pseudomorphs imitative of calcareons spar are common in Derbyshire, and also at Schemnitz in Hungary. Large crystals have been found at Nertschinsk. In the United States, it occurs with calamine in Jefferson county, Missouri; also at the Perkiomen lead mine, and in a lower Silurian rock two miles from Bethlehem, at Friedersville, in Saucon valley, abundant and extensively worked; on the Saccardance of the the Susquehanna, opposite Selimsgrove; abundantly at Austin's mines in Wythe Co. Virginia.

ALTERED FORMS.—Calamine is sometimes found altered, by substitution, to quarte

PREHNITE, Werner. Koupholite. Edelith. Chiltonite, Emmons.

Trimetric. $I: I=99^{\circ}$ 56', $O: 1i=146^{\circ}$ $11\frac{1}{2}'; a:b:c=0$ -66963: $1:1\cdot19035$. $O: 2i=153^{\circ}$ 20', $O: 3i=134^{\circ}$ 52 $\frac{1}{2}'$, $O: 2=119^{\circ}$ 45', $O: 6=100^{\circ}$ 47', $O: 6i=106^{\circ}$ 30', $I: ii=130^{\circ}$ 2'. Cleav-





age: basal, distinct. Tabular crystals often united by O, making broken forms, often barrel-shaped. Reniform, globular, and stalactitic with a crystalline surface. Structure imperfectly columnar or lamellar, strongly coherent; also compact granular or impalpable.

 $\Pi = 6 - 6.5$. G = 2.8 - 2.953. Lustre vitreous; O pearly. Color light green, passing into white and gray; often fades on exposure. Subtransparent—translucent; streak uncolored. Fracture uneven. Somewhat brittle. Pyroelectric.

```
      O: \frac{1}{2} = 157° 5'.
      O: \frac{3}{2} = 110° 3'.
      O: \frac{4}{2} = 108° 51.

      O: \frac{1}{2} = 120° 36'.
      O: \frac{1}{2} = 143° 47'.
      I: \frac{3}{2} = 149° 37'.


      O: \frac{4}{2} = 105°.
      O: \frac{2}{2} = 124° 30'.
      1: \frac{1}{2} \text{ (pyr.)} = 142° 20'.
```

Descloizeaux makes $1:1=142^{\circ}$ 15', and $0:1=139^{\circ}$ 45'. Cleavage: O, imperfect; I, more so. Also globular and reniform, with a fibrous or imperfectly columnar structure; also massive, structure granular.

		0		
1				
1				12
2		24/3		22
			$3\frac{3}{2}$	
		443		42
I	$i\frac{5}{4}$		$i\frac{3}{2}$	i2

3

3



Observed Planes.

H.=5, sometimes 4.5. G.=3.25. Lustre vitreous, inclining to subresinous. Streak white. Color usually sea-green, bluish-green; often violet blue; sometimes white; occasionally yellow, gray, red, and brown; none bright. Transparent—opaque. A bluish opalescence sometimes in the direction of the vertical axis, especially in white varieties. Cross fracture conchoidal and uneven. Brittle.

Composition.—Ca*P+{Ca(Cl, F)=Phosphoric acid 42-26, lime 50-0 fluorine 3-77, calcium 3-97; or phosphate of lime 92-26, and fluorid of calcium 7-74, with Ca Cl sometimes replacing part of the fluorid. According to G. Rose, (Pogg. ix):

	Snarum, Norway,	Cabo de Gata Spain.	Arendal, Norway.	Greiner, Tyrol.	St. Gothard, Tyrol.
Phosphate of lime,	91.13	92.066	92.189	92.16	92.81
Chlorid of Calcium,	4.28	0.885	0.801	0.12	trace
Fluorid of Calcium,	4.59	7:049	7.01	7.69	7.69
G.	-8·174	G.=3·235 (3.==8·194 G	3.==8.175	G.==8·197

Other analyses: 1, Rammelsberg; 2, Weber, (Monatsb. Preuss. Akad. 1851, 173); 3, C. A. Joy, (Inaug. Diss., 45); 4, T. H. Henry, (Phil. Mag):

```
      P
      Ca
      Ca
      Cl
      F

      1. Schwarzenstein, 42:58
      49:66
      40:6
      0:07
      3:63, Rammelsberg.

      2. Snarum, 3. Faldige, 48:01
      55:24
      —
      2:66
      † Fe, Ge, Ý 1:79, Weber.

      3. Faldige, 48:01
      55:24
      —
      0:05
      † Fe 0:09, Joy.

      4. Huel Franco, 41:34
      53:38
      —
      —(loss) 2:32, Fe, Mn, 2:96, Henry.
```

Weber's analysis corresponds to 90.66 per cent. Ca. P., 4.17 Ca Cl., 3.07 Ca F. Bischof has found magnesis in some apatites. The Eupyrchroits of Emmons (a compact concretionary subfibrous variety) afforded C. T. Jackson the constituents of apatite, with only the impurities Fe 2.00, CaC 2.77, H 0.50. G. 3.058.

B.B. infusible alone except on the edges; gives the test of phosphoric acid, With biphosphate of soda or borax fuses without difficulty to a glass, which on cooling, has a crystalline structure; also fuses if mixed with carbonate of iron; dissolves slowly in nitric acid, without effervescence. Some varieties are phosphorescent.

Apatite usually occurs in crystalline rocks. It is often found in veins in gneiss

or mica slate, and particularly those containing tin and iron ore; also in grandler limestone. It is sometimes met with in serpentine, and occasionally, as in Spila

in ancient volcanie rocks.

Among its localities are Ehrenfriedersdorf in Saxony, Schwarzenstein and Pfitsch in the Tyrol; Amberg in Bavaria; Zinnwald and Schlacken wald in Bohema; Caldbeck Fell in Cumberland, Devonshire; St. Gothard in Switzerland. The green ish-blue variety, called moroxite, occurs at Arendal in Norway, and Pargas, Finland. The asparagus stone or spargetstein variety, which is obtained at Zillerthal in the Tyrol, and Villa Rica, Spain, is translucent, and has a wine yellow-color; it is inbedded in tale. The phosphorite or massive radiated varieties are mostly obtained from Estremadura in Spain, and Schlackenwald in Bohemia.

Large crystals of apatite are found in St. Lawrence County, New York in white limestone, along with scapolite, sphene, &c. One crystal from Robinson's farm in Hammond, was nearly a foot in length, and weighed eighteen pounds. The prisms are frequently well terminated. Also in crystals about a mile southeast of Gouverneur, and two miles north; and also in Rossie, with sphene and pyroxene, two miles north of the village of Oxbow. Also on the bank of Vrooms lake, Jefferson Co., in white limestone, fine green prisms from half to five inches the property of the prisms from half to five inches the property of the prisms from half to five inches the property of the prisms from half to five inches the property of the prisms from half to five inches the property of the prisms from half to five inches the prisms from hal long; Sanford mine, East Moriah, Essex Co., in magnetic iron ore, which is often thickly studded with six-sided prisms; also at Long Pond, Essex Co.; near Edesville, Orange Co. in prisms from half an inch to twelve inches long, of a bright asparage green color, imbedded in white limestone; and in the same region, blue, grayish green, and grayish white crystals; two miles south of Amity, emerald and blue green crystals; at Long Pond, Essex Co., with garnet and idocrase; at Greenfeld Saratoga Co., St. Anthony's Nose, and Corlaer's Hook, less interesting; fibres mammillated (Eupyrchroite) at Crown Point, Essex Co., about a mile south of Hamiltonian Company of the control of th mondsville; at Hurdstown, Essex Co., where a shaft has been sunk and the apalite monosyme; at Hurdstown, Issex Co., where a snart has been sunk and the apality mined; masses brought out weigh occasionally two hundred pounds, and some cleavage prisms have the planes three inches wide. In New Hampshire, crystal often large, are abundant, four miles south of the north village meeting-how Westmoreland, in a vein of feldspar and quartz, in mica slate, along with molybdenite; some fine crystals at Piermont, N. H., in white limestone on the land of Mr. Thomas Cross. In Maine, on Long Island, Blue-hill Bay, in veins ten inches wide intersecting graphic. In Masseshuetts are stated as a s wide, intersecting granite. In Massachusetts, crystals occasionally six inches long are obtained at Norwich, (northeast part), in gray quartz; at Bolton abundant, the forms seldom interesting; also sparingly at Chesterfield, Chester, Sturbridge Hinsdale, and Williamsburgh. In Pennsylvania, at Leiperville, Delaware Co., in Bucks Co., three miles west of Attleboro. Apatite has also been found near Balting and Co., three miles west of Attleboro. Morris Canal, near Suckasuny, N. J., of a brown color, in massive magnetic pyrits;

Phosphate of lime in nodules occurs in Silurian rocks in Canada and elsewhere which are supposed to be coprolites; at Burgess, C. W., in large green crystals; a Grand Calumet in calcite, in delicate blue crystals; in trap of St. Norbert, C. E. is transparent amethyst, rose, or colorless crystals, some one inch long, and one-sixth in diameter.

Apatite was named by Werner from anaraw, to deceive, in allusion to the mistate

of the older mineralogists with regard to the nature of its many varieties.

The Pseudoapatite is an impure apatite; analysis by Rammelsberg, J. pr. Chem. lv, 486.

The tale-apatite of Hermann, (J. f. pr. Ch. xxxi, 101), is from chlorite elate in the Schischimskian mountains near Slatoust. It contains Lime 37:50, magnesia 774 phosphoric acid 39 02, sulphuric acid 2 10, chlorine 0 91, fluorine and loss 2 3, oxyd of iron 1 00, insoluble 9 50=100, whence the formula 3 Ca P+Mg P. Bet from the variety of its constituents and the large per-centage of insoluble ingredents, Berzelius suggests that the magnesia may possibly come from the gangue. 6.= 2.70—2.75. In six-sided crystals, grouped or single.

ALTERED FORMS.—The Osteolite of Bromeis is supposed to be apatite which has ATTRICE POINTS.—Ine Osteotte of Promess supposed to be apartic which has become earthy in appearance, and lost its fluorine and chlorine, (Ann. Ch. Pharm. lxxix, 1). It has a compact texture like lithographic stone, or else is earthy, and adheres to the tongue. G.—2'89. Composition, Ca² P. Analyses: 1, Bromes, compact part, (loc cit.); 2, Rütz, earthy, (ib.); 3, Ewald, intermediate part, (ib.); 4, G. Besanez, (Ann. Ch. Pharm., lxxxix, 221):

```
13
                   Ca
                                               K
                                                     Na
                                                          O
                                                                Ĥ
1. Hanau,
           36.88 49.41 4.50 1.85
                                  0.93 0.47 0.76 0.62 1.81 2.28= 99.51
                                                    0.46
           37.41
                  49.24
                        2.75
                              278
                                   1.25
                                         0.79
                                              0.81
                                                         2.34
                                                               3.45=101.28
    11
           37.16
                 48.20
                        2.03
                              2.31
                                   trace
                                         1.85
                                              0.73
                                                    0.43
                                                         2'55
                                                               3.63= 98.80
4. Amberg, 42.00 48.16 4.97
                              1:56
                                         0.75 0.04 0.02
                                                         2.21
                                                               1.31=101.02
```

From near Hanau between Ostheim and Eichen, and also from Amberg in the Erzgebirge. Occurs in altered dolonite.

CRYPTOLITE, Wöhler, Götting. gel. Anzeig. 1846, 19, and Poggendorff's Annalen, lxvii, 424.

In acicular hexagonal prisms. G. about 4.6. Wine-yellow, transparent.

Composition .- Ce P, in which the cerium is part didymium=Protoxyd of cerium 69.4, phosphoric acid 30.6. Analysis by Wohler, (loc. cit.):

Oxyd of cerium 73.70, protoxyd of iron 1.51, phosphoric acid 27.37=102.58.

The excess is owing as supposed to a change of the protoxyd of cerium to peroxyd. Soluble in concentrated sulphuric acid. Not altered by a moderate calcination.

Occurs in the green and red apatite of Arendal, and distinguished on putting the apatite in dilute nitric acid; constitutes 2 or 3 per cent. of the mass; it was found especially in the red apatite, or in reddish points of the green, and associated with particles of magnetic iron, hornblende, and another cerium ore of a hyacinth-red color, supposed to be monazite. This mineral was looked for in the yellowish apatites of Snarum without success. Occurs also with apatite in the Tyrol. (?) Named from κρυπτος, concealed.

It has been suggested that Cryptolite is a cerium apatite.

Phosphocerite, H. Watts, Quart. J. Chem. Soc. July 1, 1849, ii, 131.—The phosphocerite, as recognized by Mr. Watts, has the composition essentially of the cryptolite, but is said to differ in crystalline form. According to Watts and Chapman, (loc. cit. p. 154), the form is probably dimetric; yet as the crystals of both this species and the cryptolite are microscopic, the two, as observed by Chapman, may yet be brought together. They occur as a grayish yellow powder along with the cobalt ore of Tunaberg, and are associated with dark purple crystals of another kind and dodecahedral form, (FeSt), which are strongly magnetic. The crystalline forms most common in the powder are an octahedron and a square or rectangular forms most common in the powder are an octahedron and a square or rectangular prism, terminating in a four-sided pyramid parallel with the lateral planes, resembling fig. 382, under zircon. G.=478. H.=5.0—5.5. Colorless or pale sulphuryellow. Lustre vitreo-resinous or adamantine.

Composition.—(Ĉe, La, Ď) P. Analysis by Watts, (loc. cit.): Protoxyd of cerium, lanthanum, didymium 67.38, phosphoric acid 29.66, oxyd of iron 2.95=100.

The oxyd of iron and a little cobalt detected are probably impurities. B.B. according to Chapman, it vitrifies partially on the edges, tinging the flame at the same time slightly green. Affords the reaction of phosphoric acid and also of cerium. rium, producing however with borax and salt of phosphorus a glass which is pale violet blue when cold, either due to the presence of didymium, or a minute portion of cobalt ore.

[The analysis of cryptolite gives more nearly the oxygen proportion of 2: 3, corresponding to 10 of Ce and 3 of P.]

ZWIESELITE, Breit. Phosphate of Iron and Manganese. Eisenapatit, Fuchs.

Hexagonal? Supposed to be isomorphous with Apatite. Occurs in crystalline masses. Cleavage: distinct in three directions, but imperfect.

H.=5. G.=3.97. Lustre greasy, color clove-brown. Streak grayish-white. Fracture uneven or imperfect conchoidal.

1F15ATER Cabiert W Cabaire Brait Smalaine &

Monometric. In responsioners, i. 3h. also i. 37. 39. Clearage: enhic in vaces. Also massive granular.

H=1-1-1. G=1-100. Hadinger: 1-17. Thomson Incre victions. Color white: sometimes colorless: occasionally gravish greenish, 7-ilawish or reddish-white. Streak white. Transporent nearly scarne. Fracture subconcionidal uneven. Britise

Composition. No. 51 - 12:51 - 12:51 - 13:51 - 14:51 - 14:51 - 15:51 br. 187 ; 4 7. Liogei, L. 2 pr. Chem. zi. 117; thus min. Li affit, ; 4, Walts (Vulk. Gest. 204);

```
3
                                      $a
                                ù
L Famethal, 25-13 12-19
2 Biografia, Cubaica 57-24 12-59
                                     13-53
                                            THE R
                               1-15 II-16
                                            1-10-12 Connei
                  MY.
2. Kilpatrick.
                         *****
                                      13:17
                                            THE SHEETS Thomas
4 Grant Fam
                17.54 Ph
                        12 (6)
                                     14.10
                                     1422 128 E Ca presentite 24. Ard.
                  wie ww
& Benrie,
& Seiderhirchen,
                  राजा सन्दर्भ सन्दर्भ
                                      4-45 - 4-46, Fr 1-10-100-40, Bingel
4-45 - 5-40, Fr 1-12-1-10-54, Bingel
                   到位 地侧 红色
&Cycl.Lin.G == 234.5172 34-18 1-28
                                      792 95). Be 1-96. E 4-46-39-51. Wat.
```

B.B. fisse on charcoal, without intumerence, to a clear biology given. Geletinian with difficulty in nurristic scirl. Tinges fame yellow.

The Cubric of Benithamps (L T., has a granula gray enter, with distinct class-G=294-291

age. 4:—2:24—2:25.

The Cyclopean Islands, near Catania, Sinity, affect pellunist crystals. (f. 37); also the Tyrol; trapezahedral crystals occur in Duminartenshire, the Kilpatrick Hills.

The Tyrol; trapezahedral crystals occur in Duminartenshire, the Kilpatrick Hills. Gles Farz, generally spaque, and sometimes three or four inches through Other localities are the Farze Islands, besignd; the Vincentine, where it occurs in any Saloid, bessit, and trap, with preinite managine apoptylite &c. At Armela n Norway it comes in both of iron ore; and at Antreasberr in the Harry in give Now Jersey; in gness, near Youkers, Westchester Co., N. Y., of Dr.; at Perry. Maine, with apophylitte, in greenstone; abundant in fine crystale, with prehain. datholite, and case spar in the Lake Superior region ; in the rangue of the copper, a Copper Palls and northwestern mines, and at Michippecoter Island, form 24. sad also at other mines not now worked.

The name Analoise is from source, weak, and alludes to its weak electric power when heated or raphed.

Reduphite of Weibye, von Borek and Berlin, (Poez, basis, 185), has the our praction of Analoime, and although described as trimetric, two of the angles given d d and d s, are 1900, as in the descenhedron, d: 0=1200. H=5.5. G==7. Mean of two analyses, by von Borek, and Berlin, Si 5500, El 2426. Na 1446. H = 21

It was found in white and grayish crystals with leucophane and mosandrite on the island Lamb, Norway, in syenite. Named from releases, obscurity.

The Cluthalite of Thomson, Min. i, 339,) occurs in flesh-red vitreous crystals in amygdaloid at the Kilpatrick Hills. H=35. G.=2166. Opaque or subtranslucent Fragile. Analysis afforded: Si 51 266, Al 23 560, Fe 73 6, Na 5 130, Mg 1253. H 117552=99748.

ALTERED PORMA.—The Picronalcime of Meneghini and Bechi is probably analcime altered by the magnesian process. It occurs in geodes in the Gabbro rosso of Tweany, and also in the steatitic paste of a metalliferous dyke; forms trapezohedross and cules-trapezohedrons with distinct cubic cleavage. H.=5. G.=2257; Color. flesh red to colophonite-red; lustre vitreous. Composition, according to mean of two analyses by M. Bechi, (Am. J. Sci. [2], xiv, 62); Si 59:11, Al 22:08, Mg 10:12. Na 0:45, K 0:02, H 7:67=99:45. Formula Mg² Si³+3AlSi²+6H. Bechi, or more nearly Mg Si²+3H Si²+2H, Rammelsberg. Associated with calcite, caporcianite, and Green Lead Ore, Arsenate of Lead. Grünbleierz, W. Traubenblei, Haus. Kampylite, Breit. Hedyphane. Mimetite.

Hexagonal. $O:1=139^{\circ}$ 6'; a=0.7491. Observed planes as in pyromorphite. $O:2=120^{\circ}, O:22=123^{\circ}41$. Cleavage: 1, imperfect. H.=3.5. G.=7.19—7.25, Mimetene; 5.3—5.5, Hedyphane; 6.8—6.9, Kampylite. Lustre resinue. Color pales, passing the control of the c into brown; sometimes orange-yellow (kampylite) from the presence of chromate of lead; sometimes whitish when containing much phosphate of lime, (hedyphane). Streak white or nearly so. Subtransparent—translucent. Sectile.

Composition.—(Pb, Ča)*(Ās, P)+1Pb Cl. Analyses: 1, Wöhler, (Pogg. iv. 167); 2, 3, Dufrénoy, (Traité, iii, 46): 4, Kersten, (Schw. J. lxii):

Pb3As Pb3P PbCl

1. Johanngeorgenstadt, 82 74 7 750 9 60 = 99 84, Wöhler.
2. Horhausen, 86 70 2 15 10 40 = 98 25, Dufrénoy.
3. Cornwall, 84 55 4 50 9 05 = 98 10, Dufrénoy.
4. Longbansh., Hedyphane, 60 10 — 10 29 = , Ca P 15 51, Ca As 12 98 = 98 88, K.

A Zacatecas ore afforded C. Bergemann, (Pogg. lxxx, 401), Ås 23 065, Cl 2 445, Pb 74 961=100 471, corresponding to Pb Ås+iPbCl=Arsenic acid 23 2, oxyd of lead 67 5, chlorid of lead 9 3=100. Analysis by Rammelsberg, Pogg. xci, 316. Dissolves easily in nitric acid, especially if heated. B.B. fuses to a brownish-yellow mass; and on charcoal gives out copious arsenical fumes and affords a

globule of lead.

Occurs at Huel Unity, near Redruth, in Cornwall, and at several other of the Cornish mines; also at Beeralston in Devonshire, and Caldbeckfell in Cumberland. At St. Prix, in the Department of the Saone, in France, in capillary crystals; at Johanngeorgenstadt, in fine yellow crystals; at Nertschink, Siberia, in reniform masses, brownish red; also at Zinnwald and Badenweiler.

The Hedyphane is from Longbanshyttan in Sweden, usually in amorphous masses, and subadamantine or resinous in lustre. Kampylite occurs at Alstonmoor and

Badenweiler.

Domeyko has analyzed an impure ore related to mimetene from Chili, Maria Grande, east of the silver mines of Arqueros. Its color is dirty yellow, with an earthy or slightly resinous appearance. B.B. fuses with intumescence to a gray metallic scoria, giving a bluish tint to the flame.


Composition .- According to Domeyko, (Ann. d. M. [4], xiv, 145):

PbCl 9.05, Pb 58.31, Cu 0.92, As 11.55, P5.13, V 1.86, Ca 7.96, Al, Zr? Fe 1.10, clay It is associated with a vanadate of lead and copper. [2·00, ign. 1·12=99·00.

XENOTIME. Phosphate of Yttria. Phosphorsaure Yttererde. Ytterspath.

Dimetric. $0:1=138^{\circ} 45'; a=0.6201.$ Observed planes as in the annexed figure. 1:1 (pyram.) 124° 26′, (basal) 82° 30′, I: 1=131° 15′. Cleavage: I, perfect.

H.=4-5. G.=4·39-4·55. Lustre res-Color yellowish-brown, reddishbrown, hair-brown, flesh-red; streak pale brown, yellowish, or reddish. Opaque. Fracture uneven and splintery.



Composition.—(Ĉa, Ña, Ř)²Ši²+3ĂiŠi²+18Ĥ=(Ř², Ħ)Ši²+4ੈĤ; for the Parebre and Gustafaberg chabazite, and also the acadiolite, (Ĉa, Ña, K)Ši+ĀiŠi²+5Ĥ. Anslyses: 1, 2, 3, Hofmann, (Pogg. Ann. xxv, 495); 4, Berselius, (Afh. i Fya. vi, 190); 5, Rammelaberg, (Handw. i, 149); 6, Thomson, (Min. i, 334); 7, Connell, (Edinh J. 1829, 262); 8, Durocher, (Ann. d. Minea, [3], xix, 585); 9, Genth, (Ann. d. Ch. u. Pharm. lxvi, 274, 1848); 10, Rammelaberg, (2d Supp. p. 34); 11, Engelhardt, (Ann. d. Ch. u. Pharm. lxv, 372); 12, 13, A. A. Hayes, (Åm. J. Sci. [2], i, 122); 14, 14, Rammelaberg, (Pogg. lxii, 149); 16, Anderson, (Jameson's Jour. 1843, 23):

		S i	₹ı	Ča	Ña	Ŕ	甘
1.	Paraboro, N. S.,	51.46	17-65	8-91	1-09	0.17	19-66, Fe 0-85==99-79, Hel
	Fassathal,	48-63	19.52	10-22	0.56	0-28	2070=99-91, Hofman.
1		48.18	19-27	9.65	1.54	0-21	21·10=99·95, Hofman.
4.	Gustafsberg,	50-65	17-90	9-37	_	170	19 90=99 52, Bernelina
	Aussig.	48-36	18-62	978	0.25	2.56	(20.47)==100, Rammelsberg.
6.	Kilmalcolm,	4876	17:44	10.47		1.55	21 72=99 93, Thomson.
7.	66	50.14	17:48	8.47		2.28	20-8 3==99 -50, Connell.
8.	Farce,	4775	20.85	574	2-84	1.65	21-30==99-68, Durocher.
9.	Annerode,	47-00	1971	10.63	0.65	0.33	22-29, Pe 0·15-100-76, G.
10.	Parsboro,	52-14	19.14	7.84	0.71	0-98	19.19=100, Rammelsberg.
11.	Giessen,	48.31	19:47	11-01		1.17	19-65, Mg 0-26, Engelbard
12.	Acadiolite,	52·02	17.88	4-24	4-07	8-08	18-30=99-54, Hayes.
18.	"	52 ·2 0	18 -2 7	6.58	2.	12	20.52=99.69, "
14.	Leipa, Phacolite,	46.46	21.45	10.45	0-95	1-29	1940=100, Rammelsberg.
15.	ัน้ำ แ	46.50	22.30	10.34	1.	77	19 05, Mg0 34=100, Rama.
16.	ee 66	45.63	19.48	18.30	1-68	1-31	17-98, Mg 0-14, Fe 0-43=
							99-96, Anderson

B.B. intumesces and fuses to a blebby glass, nearly opaque. Dissolves in muristic acid, when pulverized.

The Acadiolite is a Nova Scotia chabazite of a flesh red color; form £ 474, with the scalenohedron of £ 475, also the simple rhombohedral form of chabazite; the color is red, though passing into white. In some crystals the color is arranged in a tesselated manner, the angles being nearly colorless.

Haydenite is a yellowish chabazite from Jones's Falls, Maryland. Levy made the form an oblique rhombic prism with $I: I=98^{\circ} 22'$, $0: I=96^{\circ} 5'$. The form is setually a scalenohedron (f. 475) differing but slightly from the rhombohedron; it is apparently the same scalenohedron that occurs in the Nova Scotia chabazite; angle of edge X=97-98°, of edge Y, about 176°. The crystals are often in twins parallel to R, and they are incrusted with chlorite, and sometimes consist of this mineral, unlike the accompanying heulandite, (heaumontite). Delesse obtained in a analysis of the haydenite (Revue Sci. xxv, 107), Si 49.5, Al, Fe 23.5, Ca 270, Mg frace, K 2·50, H 21·0=99·2.

Chabazite occurs mostly in trap, basalt, or amygdaloid, and occasionally in gades.

syenite, and mica slate.

Occurs at the Faroe Islands, Greenland, and Iceland, associated with chlorite and stilbite; at Aussig in Bohemia, in a kind of greenstone, (the graustein of Werner); at Annerode near Giessen; at the Giant's Causeway, Kilmalcolm, Renfrewshire, Isle of Skye, &c. In Nova Scotia wine-yellow or flesh-red (the last, the acadiolite). associated with heulandite, analcime, and calcite. Phacolite occurs at Leips is Bohemia.

Both massive and incrusted, at the Paugatuck stone-quarry, Stonington, Cons., with scapolite, sphene, and apatite; also yellowish-red in North Killingworth, on the Essex turnpike; at Hadlyme, Conn., on gneiss; in syenite at Charlestown, Mass; also at Chester, Mass., in amygdaloid; at Bergen Hill, N. J., in small crystals; in the same rock at Piermont, N. Y. Phacolite has been reported from New York

The name Chabazite is from χεδαζιος, an ancient name of a stone. Phacelite is from φακος, a bean, and λιθος; and Acadiolite from a former name of Nova Scotia.

Composition.—(Ce, La, Th) P. Analyses: 1, Kersten, (Pogg. xlvii, 385); 2, Hermann, (J. f. pr. Chem. xxxiii, 90):

13 Ċe Th La Sn Mn Ca 1.68, K and Ti trace=101.49. 1.46, Mg 0.80, Fe trace=99.59. 1. 28-50 26.00 23.40 17-95 2.10 1.86 2 28.05 37.36 27.41 175 trace

The presence of thoria in this mineral is considered certain, notwithstanding Her-

The presence of thoria in this mineral is considered certain, notwithstanding Hermann's result. Tin was detected in this species by Rose, with the blowpipe.

B.B. infusible, becoming gray or greenish-yellow. With borax, slowly dissolves and forms a globule, which is bright yellowish-green, or yellowish-red while hot, and colorless when cold. Decomposed by muriatic acid.

Monazite was first brought by Fiedler from the Ural. It occurs near Slatoust in granite, along with flesh-red feldspar. In the United States it is found in small crystals from one sixteenth to three fourths of an inch long, with the sillimanite of Norwich, and sparingly with the same mineral at Chester, Ct. A few minute crystals (the eremite of Shepard) were found in a boulder of albitic granite, containing also a few minute zircons and tourmalines, in the northeastern part of Watertown, Ct. Good crystals are obtained with the sillimanite of Yorktown, Westchester Co., N. Y.; also near Crowder's Mountain, N. C.

Ct. Good crystals are obtained with the sillimanite of Yorktown, Westchester Co., N. Y.; also near Crowder's Mountain, N. C.

The crystal affording the author the above angles (f. 552) was a fine one with polished faces, well calculated for accurate measurements.* Hermann gives the angle I: I 92° 30′; Breithaupt 94° 35′; Descloizeaux 93°.

Monasitoid, Hermann, J. f. pr. Chem. xl, 21. This mineral is monazite in crystallization and external characters. H.=5. G.=5°281. Hermann states that the brown color is distinct. Hermann obtained in his analysis,

P 17°94, Ce 49°35, La 21°30, Ca 1°50, H 1°36, subst. like tantalum 6°27, Mg, Fe, a trace=97°72. B.B. infusible. With the fluxes like monazite.

WAGNERITE, Fuchs. Pleuroclase. Tale Phosphorsäurer. Fluophosphate of Magnesia, Thom. Magnésie Phosphatée.

			0			
	-			+		弘
	48					
16	THE REAL PROPERTY.	12	-	1	12	11
	100	761	-61			31
10				100	200	21
ii		i 2	13	I	12	
				-2		
			1	-1	-12	-

Monoclinic. C=71° 53', I: I= 95°25′, O: 1i=144°25′ (B. & M.); a:b:c=0.78654:1:1.045. $0: \frac{1}{2}i = 160^{\circ} 19'$. $0:1i=135^{\circ}18'$. 0: ii=108° 7'. 0: I =

ii: 1i=116° 35'. 1:1 (front)=112° 6'. -1:-1 " =127° 32'. 66 12:12 =142° 48'. 66 $=138^{\circ} 54'$. 1 : 1 12:12 " =106° 4'. -12:-12 " =119° 0'.

i2:i266 =131° 4'. i2: i2 (side) = 122° 25'.

Most of the prismatic planes deeply striated. Cleavage: I, and the orthodiagonal, imperfect; O in traces.

H. = 5-5.5. G. = 3.068 transparent crystal, and 2.985 untransparent, Rammelsberg. Lustre vitreous. Streak white. Color

See article by the author, Am. J. Sei. xxxiii, 1838, 70. Figure 3, in that article is zircon, and not monazite.

DECRIPTIV MINERALOGY.

vitreous. Colorless, white, reddish, yellowish. Transparent to translucent.

Composition.—CaSi+AlSi+4H=(Ca+Al)Si²+4H, from Damour's analyses, which contain less silica than the others. Berzelius's analyses gives the formula of chabasite. Analyses: 1, 2, Berzelius, (Jahresb. iii, 146, v, 216); 3, Council, (Phil. Mag. v. 50); 4, 5, Damour, (Ann. d. M. [4], ix, 333):

Ca Na 8-35 2-86 Bi Æı Ĥ 0-11 1930, Mg 0-1-9932, Berz. — 18:19-9979, Berz. 1-26 19-51, Fe, Mn 0-96-102-67, C. 1. Faroe, Levyne, 48 00 20 00 2 " Mesolin, 47 50 21 40 8. Skye, Levyne, 46 80 22 47 7-90 4-80 9-72 1.55 4. Iceland, Levyne, 45 04 21 04 9 73 1 42 1 63 17 42 99 34, Damour. 5. " 45 76 28 56 10 57 1 36 1 64 17 33 = 100 22, Damour.

B.B. fuses to a blebby glass nearly opaque. Soluble in acids when pulverised, without gelatinizing

Found in amygdaloid at Glenarm; Hatfield Moss, Renfrewshire; at Dalsnypes. Faroe; at Godhavn, Disco Island, Greenland; at Skagastrand in Iceland. Named after the English Mineralogist, Mr. Levy.

GISMONDINE, Bond. Abrasite, Breislak.

Dimetric. In octahedrons, either separate or clustered into mammillated forms with a drusy surface; basal angle 92° 30', pyramidal 118° 30', Marignac.

H.=4.5. G.=2.265. Bluish white, grayish, reddish. Lustre splendent. Transparent to translucent.

Composition.—(Ca, K) Si+2XISi+9H. Analysis by Marignac, (Ann. Ch. Phys. [**8]**, xiv, 41):

Si 35-88 Al 27-23, Ca 13-12, K 2-85, H 21-10=100-18.

Easily dissolves in acids and gelatinizes. At 100° C. yields one third of its water.

R.B. whitens, intumesces much, and melts to a milky glass.

Occurs at Capo di Bove near Rome, associated with Phillipsite, and often the latter is involved in the grouped crystallizations of the former. The crystallize surfaces of the octahedrons are not even, and afforded Marignac very variable angles; angle at the base from 93° 30' to 89°, and pyramidal edges from 117° to 122°. The faces of the crystals never have the strike of those of Phillipsite, and the manmillated specimens are not columnar within; moreover Phillipsite does not lose asy of its water below 100°. Kobell analyzed the mineral called Gismondine or zeagonite, with a different result, (J. f. pr. Chem. xviii, 105). (See below.)

Brooke considers them cruciform twins of Phillipsite. Kengott makes them

distinct and dimetric, stating that they have an octahedral cleavage.

ZEAGONITE. Occurs in trimetric crystals, the angles of the fundamental octahedres being according to Kengott, 121° 44′, 120° 37′, 89° 13′, which are near those of Phillipsite. G.=2·218, Kengott, or same as for Phillipsite. Kobell obtained in an analysis of this mineral, (J. f. pr. Ch., xviii, 105), Si 42·60, £l 25·50, Ca 7·50, K 6·80, Ĥ 17·66=100·06. But it has been supposed that the specimen was a mixture of Phillipsite and Gismondina. Zeagonite and Phillipsite (p. 324) appear to be correctly regarded as one species. Seacchi reports both to the same species, and mentions Somma as a locality.

H.=5-6. G.=3.057, Fuchs; 3.067-3.121, Prüfer; 3.122, Smith and Brush. Lustre vitreous. Color azure-blue; commonly a fine deep blue, viewed along one axis, and a pale greenish-blue, along another. Streak white. Subtranslucent-opaque. Fracture uneven. Brittle.

Composition.—2(Mg, Fe)*P+XI*P*+5H, Smith and Brush=Phosphoric acid 43*88, alumina 31*77, protoxyd of iron 8*90, magnesia 9*89, water 5*56. From other analyses, 2(Mg, Fe)*P+XI*P*+6H=phosphoric acid 46*79, alumina 27*10, protoxyd of iron 7*10, magnesia 11*87, water 7*12. Perhaps (R+XI)P+H.

Analyses: 1, Fuchs, (Schweig. J. xxiv, 378); 2, R. Brandes, (ib. xxx, 385); 3 to 8, Rammelsberg, (Pogg. lxiv, 260); 9, 10, Smith and Brush, (Am. J. Sci. [2], xvi, 370);

		P	X 1	Mg	Fe	Ča	Ĥ
1.	Rädelgraben,	41.81	35.78	9.34	2.64	-	6.06, Si 2.1-87.68, F.
2.	Krieglach,	43.32	34.50	13.56	0.80	0.42	0.50, Si 6.5=99.6, Br.
3.	Gratz, G.=3.11,	42.41	29.58	10.67	10.60	1.12	5.62=100, Ramm.
4.		43.84	33.09	9.00	6.69	1.44	5-94=100, "
5.		46.99	27.62	11.19	6.47	2-12	5.61=100, "
6.	Krieglach, G .= 2.02,	40.95	36.22	12.85	1.64	1.42	6.92=100, "
7.	" "	47.36	30.05	12.20	1.89	1.65	6.85=100, "
8.		47.73	27.48	12.16	1.91	4.32	6.40=100, "
9.	North Carolina,	43.38	81.22	10.06	8.29	-	5.68,Si1.07=99.70,S.B.
10.	a a	44-15	89-17	10:02	8:05	-	5.50 Sil.07=100.96 "

In a matrass yields water and loses its color. B.B. on charcoal, intumesces slightly and at a high heat assumes a blebby, glassy appearance, but does not fuse. With borax, yields a clear colorless globule. Forms a fine blue with cobalt solution. Rammelsberg found more or less silica as impurity which is excluded in the results above given.

Occurs both massive and crystallized in narrow veins, traversing clay slate, in the torrent beds of Schladming and Rädelgraben, near Werfen in Saltzburg, with spathic iron; in Gratz, near Vorau, and elsewhere, and in Krieglach, in Styria. From the locality at Vorau it has been called voraulite. Also at Tijuco in Minas Geraes, Brazil. It is abundant at Crowder's Mt., Lincoln Co., N. C.

The name lazulite is derived from an Arabic word azul, meaning heaven, and al-

ludes to the color of the mineral.

TURQUOIS. Calaite. Agaphite. Johnite. Kalait and Türkis. Birousa of the Persians. Callais (probably) of Pliny.

Reniform, stalactitic or incrusting. Cleavage none.

H.=6. G.=2.6-2.83; 2.621, Hermann. Lustre somewhat waxy, internally dull. Color a peculiar bluish-green. Streak white. Feebly subtranslucent-opaque. Fracture small conchoidal.

Composition. - Contains, according to John, (Ann. des Mines, [2], iii, 231), Zellner (Isis, 1834, 637), and Hermann, (J. f. pr. Ch. xxxiii, 282):


```
P
                                                                   Ĥ
                                                                                Ou
1. Silesia, 44.50 30.90 19.00 3.75 Fe 1.80=99.95, John.
2. " 54.50 38.90 1.00 1.50 Fe 2.8=98.70, Zellner.
3. Blue Oriental, 47.45 27.34 18.18 2.02 "1.10, Mn 0.50, CaP 3.41=100, H.
```

Formula from the first and last analyses, \(\frac{\text{Al}^2P}{+5H} = \frac{\text{Al}}{46.9}, \(\frac{P}{2}\) 32.6, \(\text{H}\) 20.5. The green Oriental turquois afforded Hermann only 5.64 per cent. of phosphoric acid, and is evidently a mechanical mixture, containing but little turquois. Specific gravity of the last 2.621.

Berzelius obtained in his analysis, phosphate of alumina, phosphate of lime, sili-

ca, oxyd of iron, and copper.

H.=4.5. G.=2.39-2.498. Lustre vitreous. Color white: passing into gray, yellow, red, or brown. Streak white. Sti-



transparent—translucent. Fracture uneven, imperfectly senion-dal. Brittle.

(Composition — NaSt-ElST-III — Na-ElST-III — Silva 44), armina 164 baryta 548, water 145 — 170, Analyses 1 i.E. Kinler. Fings execut 561 c. Barminelsberg, Handwig 190 (18. Control Ed N Finl 2 177 1801 18 c. 6. Iw mount Ann des M [4] in 365, and Compo Rend with 141 (17. 6. Iwanship and 2 Mines, 4) in 565.

SS of the process, makes with the commenced of the element of the CD. The equipment when the configuration is the configuration to the second mass that have been also

Sample and south in an ingrise in and in groups and in the addition as readblement and in any problem in an ingrise in and the sample and in a treatment as read-Source and in any properties of many took and the sample and in a treatment of the ages, on the improve and those are the transplant of the ansatz and a treatment of an international treatment of greats with a transmitted in the antiquation of a limitation and the animal problem.

all to it will be provided.

Name of the above to be and made to the althought the interest of the interest that we are also the continuous terms of the about the continuous terms.

There is no not to be Southern, and a distinguished to the first of the filless. There is a first of the factorish of the fill of the factorish of the fill of the

PERCENTISCHE LAND, SAND, Phil. Salver v. 1982. Linne Harrick inc. — Carrennalia Percentagna

Transcript Stanges and magnated constant for the months were. I have the left see and the see Alampian Lin see 125 18 and military for the first and military for the first and military for the first and military.

aguar annaennis soner, print romain l'ince de l'établique :

Triphyline occurs at Bodenmais in Bavaria; and f. 550, is from a large somewhat distorted Bavarian crystal in the cabinet of R. P. Greg, Jr.; it has the appearance of being altered. Named from τρις, three, and φυλη, family, in allusion to its con-

taining three phosphates.

Tetraphyline, (or Perowskine), a similar compound, is from Keiti, in Finland. In the analysis below, the excess is supposed to be due to an incorrect determination of the lithia. It differs in physical characters from the preceding, in presenting a yellow color on its surface of fresh fracture, which by degrees becomes black. It afforded Berzelius and Nordenskiöld, (Jahresb. xv, 211), P 426, Fe 386, Mn 121, Li 8·2, Mg 1·7=103·2.

ALTERED FORMS.—Triphyline and Triplite undergo alteration, by taking up water, the protoxyds passing to peroxyds, and the former losing also its alkalies. The following compounds are supposed to have thus originated. Analyses: 1, Fuchs, (J. f. pr. Chem.); 2, Delffs, (Blum's Lehrb. d. Orykt. 2 Aufl. 537); 3, Dufrénoy, (Ann. Ch. Phys. xli, 342); 4, Rammelsberg, (Pogg. lxxxv, 439); 5, Dufrénoy, (loc. eit. p. 337); 6, Damour, (Ann. d. M. [4], xiii, 341); 7, 8, W. J. Craw, (Am. J. Sci. [2], xi, 99); 9, J. W. Mallet, (ib., xviii, 33):

			P	Fe	Min	Fe	Mn	Ĥ	Si	
1.	Bodenma	is,	85.70	48-17	8.94	-	-	5.30	1.40=99	51, F.
2.	**	Pseudotriplite,	35-71	51.00	8.07	-	-	4.52	-, ins	ol. 0.70=
		SALES PLE								o, Delffs.
3.	Limoges,	Heterosite,	4177	-	-	34.89	17.57	4'40	0.22=98	8'85, Duf.
4.	a	"								00, Ram.
5.	Limoges,	Hureaulite,								·95, Duf.
6.	"	Alluaudite,	41.25	25.62	1.06	-	28.08	2.65	0.60, N	a 5.47=
										Damour.
7.	Norwich,	Mass.,	41.35	27.36						2.27, Ca
		The same of the sa								1, Craw.
8.	"	"	44.64	26'02						2.20, Ca
										4, Craw.
9.	44		43.04	29.50	22.59,	Ca O	09, Mg	0.73,		H 2.05=
									99.79	Mallet.

No. 1, Fuchs regards as altered Triphyline.

Pseudotriplite corresponds to the formula (Fe. Mn)*P*+2H.

Heterosite, by Rammelsberg's analysis, gives H'P*+6H; but reckoning it as an anhydrous protoxyd compound, the formula becomes, according to Rammelsberg, R*P+R*P. It is of a brownish violet color, to greenish gray. Dufrenoy gives G.=

P+RP. It is of a brownish violes color, to globals and the second of the

Alluaudite has 3 cleavages at right angles with one another, one more perfect than the others. H above 4; G.=3.468. Color clove-brown. Streak yellowish. Lustre dull. Subtranslucent to opaque. Fracture shining, scaly. Formula from analysis R*P+FeP+H, or reckoning the iron as all protoxyd, R*P*+H. From Chanteloub, near Limoges.

The Norwich mineral (Massachusetts) is found only in crystals, some an inch long and wide, associated with spodumene in quartz. The crystals vary much in their angles; the faces are smooth but hardly polished. The following angles were obtained by the author from eight crystals, (the right hand is is here accented).

1	11	Ш	IV V	VI	VII	VIII
ig: ig' 128°	1810-1820	127°-1304°	13010 1260	1340	1280	130°
ig: il		113	113	108	108	
1g: 1t	1211-122			120	115	118-119
O: 18	181	129-132				
ig: 11	1011-102					
12: 11	1131	110	110-112			
ia (or ia'): I 159	162					
O: obtuse edge of I	94-97		90	93	100	90
U: obtuse edge of 1	86-87	86	86		80	90
I:I	-	93				

```
Æl
                                      Ca Na K H
 1. Kilpatrick,
                        88.30 80.70 13.54 4.58
                                                     - 13·10=100·17, Berzelius
                        88-09 81-62 12-60 4-62
                                                       13:40=100:20, Rammelab
 2. Dumbarton.
 & Farce,
                                              8:11 13:40, Fe 0:5=101:84, Retail
                        89·20 30·05 10·58
                        38·25 32·00 11·96 6·58 -
                                                      - 11.50=100.24, Zippe.
 4. Seeberg, Compt.,
                        38 73 80 84 13 43 3 85 0 54 13 10=100 49, Ram
                        88 77 81 92 11 96 4 54 12 81=100, Ramm.
 6.
                                                     - 12·24=99·16, Melly.
 7. Elbogen,
                        87-00 81-07 12-60 6-25 -
                                                     - 18:30=99:48, Ramm. G. 2:357.
                        39-63 31·25 7·27 8·03 -
 8. Hauenstein,
                        36-85 29-42 13-95 3-91 — 13-80, Fe 1-55=99-88, S. & R. $7-08 31-13 13-97 3-72 — 13-80=99-70, Smith & Brush. $9-28 29-50 12-38 4-09 0-38 13-23, Mg0-13, Fe 1-49=100-48, W.
 9. Ozarkite,
10.
11. Carphostilbite,
12. Thomsonite,
                        89-86 81-45 13-33 5-30 1-00 11-39=102-33, Waltershaus
```

B.B. intumesces, becoming white and opaque; the edges merely are rounded a high heat. When pulverized it gelatinizes with nitric or muriatic acid.

Thomsonite occurs near Kilpatrick, and Lochwinnoch, Scotland, in smygdalaid.

Comptonite is met with in the lavas of Vesuvius; in baselt at the Pflasterkaute Saxe Weimar, at Seeberg and elsewhere in Bohemia in the cavities of clinkstone; in the Cyclopean islands, Sicily, with analcime and phillipaite; in Farce; in pheolite at Hauenstein, (called Mesolite of Hauenstein.)

Long alender prismatic crystallizations of a grayish white color are obtained a Peter's Point, Nova Scotia, where it is associated with apophyllite, mesotype, larmontite, and other trap minerals.

Ozarkite, as Smith and Brush show, is an amorphous or fibrous radiated Thesonite. It occurs at the Ozark Mts., Arkansas, with elselite, and appears to have resulted from its alteration; it is often mixed with apatite in colorless sleads prisms. In analysis 10 some Fe is included with the Al.

Chalilite of Thomson may be an impure massive thomsonite. It afforded Thom (Min. i, 324), and v. Hauer, (Jahrb. Geol. Reicha. 1853):

Ca 10-28 Fe 9-28=10170, I Bi 36.56 No 272 Ĥ 16 66 <u>₹1 26-20</u> **M**g 6.85 38.56 2771 1201 14-32 tr.==99 45, H

From the Donegore Mountains, in the county of Antrim. Color deep reddish brown.

According to Kengott, Chalilite includes two species. The one analyzed, is many sive, with a splintery fracture, subtranslucent to opaque; streak vellowish and s little greasy; B.B. fuses with intumescence; in a tube yields water, and blacked The other is flesh-red; H.=5, G.=2.24; B.B. fuses with more difficulty than the receding to a white blebby glass; it appears to contain but little water. (Sizurg Wien. Akad., x, 179).

Scoulerite of Thomson is near thomsonite in composition, but contains less alum a and water, and 64 per cent. of soda. It comes from Port Rush in Ireland, Phi-Mag. Dec. 1840, 402.)

Carphortilbite from Berufiord, Iceland, is straw-yellow, and columnar; it give e oxygen ratio for B: H: Si: H=1: 3: 44: 25. G.=2362. the oxygen ratio for B . H : Si : H=1 : 3 : 44 : 25.

e oxygen ratio for B: H: Si: h=1; s; +2.20 Si.— [2], xiv. 631.—This speed Picкотном sourk.—Meneghini and Bechi, (Am. J. Sci., [2], xiv. 631.—This speed 121. Thomsonita in form and near it in composition. The soda is replaced by is like Thomsonite in form and near it in composition. magnesia, and it is possibly the result of alteration. It occurs in radiated masses laminated in structure, and cleaving with equal case parallel to two sides of a rectangular prism. H=5. G=278. Lustre pearly. White Transparent in section 1. fragments. Very fragile.
Composition.—(Ca. Mg/Si+2;HiSi+1;H. Analysis:

Żę Ŧı Ċĸ 2.2 Ĥ 40-36 6-26 31-25 10-99 0-29 1079-99-94

B.B. fuses to a white enamel, with intumescence. Dissolves in cold acids and elatinizes. Occurs with caporcianite in the Gabbro rosso of Tuscany. The name om super, bitter, and Thomsonite, aliudes to the magnesia present.

NATROLITE, W. Soda Mesotype. Feather Zeolite. Bergmannite, Spreustein. Radiolite. Fäserzeolite, W. Natron-Mesotyp, R. Lehuntite, Thom. Brevieite,

Trimetric. I: I=91°, O: 1i=144° 23'; $a:b:c=0.7165:1:1.0176; \frac{1}{2}:\frac{1}{2} \text{ (mac.)}=143^{\circ}$ 20', (brach.)=142° 40', $I:\frac{1}{2}=116^{\circ}$ 40'. Crystals usually slender, often acicular; frequently interlacing, divergent, or stellate. Also fibrous, radiating, and massive.

H.=5-5.5. G.=2.17-2.24. Lustre vitreous, sometimes inclining to pearly, especially in fibrous varieties. Color white, or colorless; also grayish, yellowish. Streak uncolored. Transparent-translucent.



Composition.-NaSi+AlSi+2H=Silica 47.4, alumina 26.9, soda 16.2, water 9.5. Analyses: 1, Klaproth, (Beit. v, 44); 2-4, Fuchs, (Schw. J. viii and xviii); 5, Thomson, (Min. i, 317); 6, Kobell, (J. f. pr. Chem. xiii, 7); 7, Riegel, (Jahrb. Pharm. xiii); 8, 9, 10, Scheerer, (Pogg. lxv, 276); 11, Thomson, (Min. i, 338); 12, C. G. Gmelin, (Pogg. lxxxi, 311); 13, C. Bergemann, (Pogg. lxxxiv, 491); 14, Souden, (Pogg. xxxiii, 112); 15, 16, Körte, (G. Rose's Mineral System, 1852, 96);

		Si	X 1	Fe	Ña	Ĥ
1.	Högau,	48.00	24.25	1.75	16.50	9.00=99.50, Klaproth.
2.	11	47.21	25.60	1.35	16.12	8.88=99.16, Fuchs.
3.	Auvergne, cryst.	4776	25.88	-	16.21	9.31=99.16, Fuehs.
4.	Tyrol, massive,	48.63	24.82	0.21	15.69	9.60=98.95, Fuchs.
5.	Antrim, eryst.	47.56	26.42	0.58	14.93	10.44, Cal.4=101.33, Thomson.
6.	Greenland, massive,	46.94	27.00	-	14.70	9.60, Cal 8=100.04, Kobell.
7.	Högau,	48.05	25.80	2.10	15.75	9.00=100.70, Riegel.
8.	Bergmannite, red,	47.97	26.66	0.73	14.07	9-77, Ca 0.68, K tr.=99.88, S.
9.	" white,	48.12	26.96	0.22	14.23	10.48, Ca 0.69, K tr.=100.7, S.
10.	Radiolite,	48.38	26.42	0.24	13.87	9.42, Ca0.44, K1.54=100.31, S.
11.	Lehuntite,	47.33	24.00	-	13.20	13.60, Cal.52=99.65, Thomson.
12.	Laurvig, Natrolite,	48.68	26.37	-	16.00	9.55, K0.36=100.96, Gmelin.
13.	Iron Natrolite,	46.54	18.94	7.49	14.04	9.37, Fe 2.40, Mn0.55=99.33B.
14.	Brevicite,	43.88	28.39	-	10.32	9.63, Ca 6.88, Mg 0.21, Souden.
15.	н	48.32	26.24	-	15.97	9.47, Ca tr.=100.00, Körte.
16.	44	48.50	26.05	-	16.49	9.29, Ca tr.=100.33, Körte.
			a With	a little	potash.	The second secon

B.B. natrolite becomes opaque and is often phosphorescent; it fuses quietly to a

glassy globule. Gelatinizes readily with acids, even after ignition.

This species occurs in cavities in amygdaloidal trap, basalt, and other allied rocks; and sometimes in seams in granite or gneiss. It is found in the graustein of Aussig in Bohemia; in Auvergne; the trap rocks of Kilmalcolm in Renfrewshire, and Glenarm in the county of Antrim and elsewhere. The Radiolite is from Brevig.

Bergmannite is a red or white natrolite, from Zircon syenite near Brevig. Lehuntite

Bergmannie is a red or white natrolite, from Zircon syenite near Brevig. Lehantie is from Glenarm, and if Thomson's analysis is correct it contains 3H like the scolecites, although a soda-mesotype. Kengott finds the angle I: I=91°.

The Iron-natrolite (anal. 13, Eisennatrolith) occurs along with the brevicite of Brevig, and is in dull green opaque prismatic crystals and semicrystalline plates. H.=5. G.=2353. It has one fourth of the alumina replaced by peroxyd of iron. In North America, natrolite occurs in the trap of Nova Scotia; sparingly at Cheshire, Ct.; also at Copper Falls, Lake Superior, in crystals, sometimes on native copper.

Occurs at Chursdorf and Arnsdorf, near Penig in Saxony, where it is associated with tourmaline and garnet in granite; also at Arendal, Norway.

The name is from σμόλυς, blunt, and γονο, angle.

HERDERITE, Haid. Allogonit, Breit.



Trimetric. $I: I=115^{\circ} 53'$, $O: 15=145^{\circ} 51'$; a:b:c=0.6783:1:1.5971. Observed planes as in the annexed figure, with also 3, 4 and 6 \tilde{i} .

O: 1=141° 19′. 1: 1 (mac.) 141° 17′. O: 3=112° 35′. 1: 1 (brach.)=116° 3′. O: ¾=147° 30′. O: I=90°.

Cleavage: I interrupted. Surfaces I and 1 very smooth, and delicately lined parallel to

their edge of intersection.

H.=5. G.=2.985. Lustre vitreous, inclining to subresinous Streak white. Color various shades of yellowish and greenish white. Translucent. Fracture small conchoidal. Very brittle. Index of refraction 1.47.

Composition.—Probably, according to trials by Turner and Plattner, an anhydrous phosphate of alumina and lime with fluorine. B.B. fuses with difficulty to a white enamel; becomes blue with cobalt solution. Dissolves when finely powdered in muriatic acid.

Very rare at the tin mines of Ehrenfriedersdorf in Saxony. Resembles the sparagus variety of apatite,

Named after Baron von Herder, director of the Saxon mines.

CARMINITE. Carmine Spar. Carminspath, Sandberger, Pogg. lxxx, 391.

Trimetric? In clusters of fine needles; also in spheroidal forms with a columnar structure. Cleavage parallel to the faces of a rhombic prism.

H.=2.5. Lustre vitreous, but cleavage pearly. Color carmine to tile-red; powder reddish-yellow. Translucent. Brittle.

Composition.—Probably an anhydrous arsenate of lead and iron.

B.B. on charcoal fuses easily to a steel-gray globule, giving out arsenical vapors; with soda, a globule of lead, and with borax an iron reaction. Heated in a glast tube, no change. Soluble in nitric acid.

From Horhausen in Saxony, with Beudantite in quartz and brown iron ore.

THE RESERVE THE PERSON NAMED IN COLUMN TWO IS NOT THE OWNER.

ROMEINE, Damour, Ann. des Mines, [3], xx, 247, [5], iii, 179. Romeit.

Dimetric. In octahedrons; basal angle, according to Dufrénoy, 110° 50′—111° 20′; angle over the summit 68° 10′—69° 10′. Occurs in groups of minute crystals.

Scratches glass. G. in grains 4.714; in powder 4.675. Color

hyacinth or honey-yellow.

Composition.—R³, SbO³, SbO⁴ Damour. Analysis by Damour, (loc. cit.): O 15-82. Sb 62-18, Fe 1-31, Mn 1-21, Ca 16-29, Si sol 0-96, insol. 1-90=99-67, or Sb O 40-79, Sb O 86-82, Fe 1-70, Mn 1-21, Ca 16-29, Si 0-96, insol. 1-90=99-67.

B.B. fuses to a blackish slag. With borax affords a colorless glass in the inner flame, a violet in the outer. In acids insoluble.

Romeine was found at St. Marcel in Piedmont, in small nests or veins in the gangue which accompanies manganese, consisting in part of feldspar, epidote, quartz, brown iron ore, and greenovite. It is named after Romé de l'Isle.

2. HYDROUS PHOSPHATES AND ARSENATES.

The hydrous phosphates are arranged in the order of the oxygen ratio, commencing with the species which have proportionally the most acid.


Among them, two groups may be recognized:
1. VIVIANITE GROUP.—Containing Vivianite, Cobalt Bloom, and probably Symplesite and Köttigite, (oxygen ratio 3:5), with also Pharmacolite, (oxygen ratio 2:5), which is homeomorphous with Vivianite. Monoclinic, with perfect clinodiagonal cleavage.

2. OLIEVNITE GROUP.—Containing Olivenite and Libethenite. Trimetric,

(oxygen ratio 4:5).

Тивомволить,			P,		Ĥ 8	Ĉu³ 1º -+6Ĥ.
STERCORITE,	•					Na NHOP+9H.
Struvite,						Mg³ NH⁴O P+ 12 H .
Haidingerite,	2	:	5	:	4	Ĉa³Ã•+4Ĥ.
Pharmacolite,	2	:	5	:	6	Ċa³Ās+6Ĥ.
VIVIANITE,	8	:	5	:	8	∱ e 'P +8 Ĥ .
Erythrine,	8	:	5	:	8	Ċo³Ãs+8Ĥ.
NICKEL GREEN,	8	:	5	:	8	Ñi³Ās+8Ĥ.
Коттівіта,	8	:	5	:	8	ذĀs+8Ĥ.
Symplesite.						
Scorodite,	8	:	5	:	4	₽ eÃe+4Ĥ.
Libethenite,	4	:	5	:	1	Ċu P+ £.
OLIVENITE,	4	:	5	:	1	Ċu4(Ās,P)+Ĥ.
CONICHALCITE,	4	:	5	:	11	Ř4(Äs,P)+1 ; Ĥ.
EUCHBOITE,	4	:	5	:	7	Ôu⁴Ãs+7Ĥ.
Arseniosiderite,						Ās, F e, Ca, Ĥ。
Pharmacosiderite,	4	:	5	:	6	Fe³Ãs+Fe³Ãs³+18Ĥ.
BEUDANTITE,						
Wavellite,	4	:	5	:	6	和中 +18用+1AIF*。

KPISTILBITE, G. Rose, Pogg. vi, 183, and Brewster's Jour. iv, 283. Monophan, R.



Trimetric. $I: I=135^{\circ} 10', O: 1i=144^{\circ}$ 53'; a:b:c=1.422:1:2.4242. Observed planes, as in f. 484, with 22 replacing edge planes, as in 1. 404, with 22 replacing edge $I: 1i: 1i: 1i: (top)=109^{\circ} 46', 1i: 1i: (top)=147^{\circ} 40', I: 1i=122^{\circ} 9', 1i: 1i=141^{\circ} 47'.$ Cleavage: ii, very perfect: indistinct in other directions. Face I mostly uneven. Occasionally in twins parallel to I. Also granular.

H.=3·5-4. G.=2·249-2·363. Lustre pearly upon the cleavage face: upon I vitreous. Color white, bluish or yellowish-white. Transparent—subtranslucent. Fracture uneven.

Composition.—(Ca, Na)Si+XISi³+5H=Silica 59.8, alumina 16.8, lime 9.2, water 14.7, which is identical essentially with the formula of brewsterite, and also with heulandite, taking Damour's formula; it differs from that of stilbite in containing 1 atom less of water. Analyses: 1, 2, G. Rose, (loc. cit.); 8, Dr. Limpricht, (Waltersh. Vulk. Gest. 248); 4, Waltershausen, (ib.):

		Si			Ñа	Ħ
1.	Berufiord,	58.59	17.52	7.56	178	14·48==99·98, Rose.
2.	"	60.28	17.36	8.32	1.52	12.51 (loss)==100, Rose.
3.	"	58.99	18.21	6.92	2.35	14.98=101.44, Limpricht.
4.	"	59.22	17.23	8.20	2.46	18-90=101-01, Waltershausen.

B.B. intumesces, and forms a vesicular enamel. Borax dissolves a great part of it, and forms a clear globule. Soluble in concentrated muriatic acid without gelat-

Occurs with scolecite at the Berufiord in Iceland; in Farce; at Poonah in India; in small flesh-colored crystals at Skye; reported as occurring with stilbite, apo-

This species exhibits but one system of rings in polarized light, according to Dr. Brewster, while heulandite has two. The double refraction of heulandite is also much greater than that of epistilbite. Yet the angle I: I in this species is near that of heulandite.

Ehrenbergite of Nöggenrath (Lieb. Kopp, 1852, 867) is a pale rose-red amorphous mineral, almost gelatinizing with acids, from trachyte in the Steinbruch. Bischof and Schnabel obtained for it,

HEULANDITE. Foliated Zeolite, J. and W. Stilbite, (in part). Stilbite anamorphique, Haus. Blättriger Stilbit, Haus. Blätterzeolit, W. Euzeolith. Lincoln phique, Hauy. Blättriger Stilbit, Hite, Hitchcock. Beaumontite, Levy.

Monoclinic. $C=88^{\circ} 35'$, $I:I=136^{\circ} 4'$, $O:1i=156^{\circ} 45'$; a:b:c=1.065:1:2.4785. Observed planes as in the annexed figures.

STERCORITE, Herapath. Microcosmic Salt. Salt of Phosphorus.

In crystalline masses and nodules. G. = 1.6151. Lustre vitreous. Color white, stained yellowish-brown. Transparent. Fragile. Not efflorescent. Easily soluble in hot and cold water.

Composition.—Na NH40 P+9H=P34.05, NH4012.40, Na 14.92, H 38.63. Analysis by T. J. Herapath, (Quart. J. Chem. Soc. April, 1849):

P 84.325, Am 7.680, Na 15.752, H 42.248=100.

Mixed with about 9 per cent. of impurities, consisting of organic matters along with chlorid of sodium, carbonate of lime, carbonate of magnesia, phosphate of lime, sand, &c. B.B. intumesces, blackens, and gives off water and ammonia, and after-


wards fuses to a transparent, colorless glass, soluble in boiling water.

Found in guano at the island of Ichaboe on the western coast of Africa.

This species is identical with the *Salt of Phosphorus*, used as a flux in blowpipe

STRUVITE, Ulex, Afv. K. V. Ac. Förh. iii, 32, Ann. Ch. Pharm. lxvi, 41. Guanite, E. F. Teschemacher, Phil. Mag. [3], xxviii, 546.

Hemihedral, two opposite sides having unlike planes. $I: I=101^{\circ} 42', O: 1\bar{\imath}=132^{\circ} 32'; a:b:c=1\cdot0900:1:1\cdot2283.$ Observed planes as in the annexed figure. $O: 1\bar{\imath}=138^{\circ} 25', O: \frac{1}{4}\bar{\imath}=151^{\circ} 25', O: \bar{\imath}=90^{\circ}, i_2: i_2^{\circ} (\text{ov. } i_1^{\circ})=63^{\circ} 8', 1\bar{\imath} 1\bar{\imath} (\text{ov.} O)=96^{\circ} 50', \frac{1}{4}\bar{\imath}: \frac{1}{2}\bar{\imath} (\text{ov. } i_1^{\circ})=57^{\circ} 10'.$ Cleavage: O, perfect. Twins: face of composition i_1° .



H.=2. G.=1.65—1.7. Color slightly yellowish to brown; white. Lustre vitreous. Translucent; sometimes opaque. Brittle. Tasteless, being but very slightly soluble.

Composition.—NH'O Mg² P+12H=Phosphoric acid 29'9, magnesia 16'3, NH'O 10'6, water 44'0=100. Ulex obtained, (v. Leonh. 1851, 51):

P Mg Fe Min Am, H 28:56 13:46 8:06 1:12 53:76

B.B. falls to powder, giving off water and ammonia, and fuses to a colorless glass which becomes an enamel on cooling. Dissolves readily in acids

which becomes an enamel on cooling. Dissolves readily in acids.

Found in guano from Saldanha Bay, coast of Africa, imbedded in patches of crystals; also under an old church in Hamburg, where quantities of cattle dung existed in the soil, above a bed of peat which contained the crystals. This salt forms when a tribasic phosphate and a salt of ammonia are dissolved together, and a salt of magnesia is added to the mixture.

The dimensions of the crystals are nearly those of barytes, if 11 be taken as 11.

HAIDINGERITE, Turner, Brewster's Journal, iii, 808.


Trimetric. $I: I=100^{\circ}$ (80° over ii), O $1i=148^{\circ}$ 16'; a:b:c=0.595:1:1.1918. $\frac{1}{2}i:\frac{1}{2}i$ (top)= 146° 53', $1i:1i=126^{\circ}$ 58', $I:ii=140^{\circ}$, $I:ii=130^{\circ}$. Cleavage ii highly perfect. Mostly in minute crystals aggregated into botryoidal forms and drusy crusts.

H.=1.5-2.5. G.=2.848. Lustre vitreous. Streak white.

the name of Beaumontite, as modified square prisms. The difference in the lustre of O and ii, the two faces of the prism, shows that these planes are dissimilar, and that the form cannot be a square prism. In physical and other characters they rescrible Heulandite, and the angle I:2i, according to Levy, equals 145° 18', which is near the same angle in this species. Levy makes $I: I=132^\circ$ 28'; but the author finds $135\frac{1}{2}^\circ$ to $136\frac{1}{2}^\circ$ by reflected light. Delesse's analysis afforded silies 642, alumina 141, protoxyd of iron 12, lime 43, magnesia 17, loss and so in 04, water 134; but it is probable that the specimen was not pure. G.=234, (Ann. Ch. Phys. 131, ix. 385). [3], ix, 385). Named after the English Mineralogist, Mr. Heuland.

Parastilbite. Von Waltershausen thus names (loc. cit. p. 251) a specimen from Borgarfiord, which afforded on analysis, Si 61 67, H 17 83, Ca 7 32, Na 2 32, K 178, H 9 20=100, for which he writes the formula R Si + H Si + 3H. It resembles Epistilbite, but he states that the angles are somewhat different. It may be Heulandite.

BREWSTERITE, Brooke, Edinb. Phil. Jour. vi, 112 Diagonite, Breit.



Monoclinic. $C=86^{\circ}20', I: I=136^{\circ}, 0: 1=157^{\circ}$ 14'; a:b:c=1.038:1:2.47. $0:ii=93^{\circ}.40', 0:$ $ii=90^{\circ}$, $O: \frac{1}{6}i=176^{\circ}$, $\frac{1}{6}i: \frac{1}{6}i=172^{\circ}$. Cleavage iihighly perfect.

H.=4.5-5. G.=2.12-2.432; the latter according to Thomson. Lustre of ii pearly; of other faces, vitreous. Color white, inclining to yellow and gray. Streak white. Transparent-translucent. Fracture uneven.

Composition. —(Sr. Ba)Si+AlSi2+5H=(if Ba: Sr=1: 2) Silica 537, alumaina 152, baryta 7-6, strontia 10-2, water 13-3; but gives too little alumina. Analyses by Connel and Thomson, (Min. i, 348):

Si Al Ba Sr Ca H Fe

1. Strontian, 53.67 17.49 6.75 6.32 1.35 12.58 0.29=100.45, Conneil.

2. " 53.04 16.54 6.05 9.01 0.80 14.73 —=100.17, Thomson.

B.B. parts with its water and becomes opaque; then froths and swells up. but fuses with difficulty. Leaves a silica skeleton when fused with salt of phosphorus. Dissolves in the acids with a separation of the silica, and according to Kobell, gelatinizes.

Brewsterite was first observed at Strontian in Argyleshire, associated with cale spar. Occurs also at the Giant's Causeway, coating the cavities of amygdaloid; in the lead mines of St. Turpet; near Freiburg in the Brisgau; in the department of the Isere in France, and in the Pyrenees

This species was named after Sir David Brewster.

STILBITE, H. Desmine, Breit. Radiated Zeolite, J. Foliated Zeolite. Strahlseolith, W. Blättrich strahliger Stilbite, Haus. Garbenstilbit. Sphærostilbite, B. Hypostilbite, B.

Monoclinic? Breit. $I: I=94^{\circ} 16'$ (whence $i_2: i_2=130^{\circ} 12'$, analogue of I: I in Heulandite); $1:1(front)=119^{\circ}16'$, $ii:ii=90^{\circ}$. Brooke and Miller make 0:ii or $ii=90^{\circ}$, $ii:1=123^{\circ}$, $ii:1=120^{\circ}$ 22'. Cleavage: ii perfect, ii less so. Twins of a cruciform character are rarely met with. Common in sheath-like aggregations; globular, divergent, and radiated forms; also thin lamellar and columnar.

the Vosges; at Andreasberg in the Hartz, and at Riechelsdorf and Bieber in Hessia;

at Glücksbrunn in Thuringia; at Josehinstahl in Bohemia.

This species was named, in allusion to its containing arsenic, from φαρμακον, poison.

The Picropharmacolite of Stromeyer from Riechelsdorf, (Gilb. Ann. lxi, 185), contains, Lime 24 646, arsenic acid 46 971, magnesia 3 223, oxyd of cobalt 0 998, water 23 977=99 815, affording the formula (Ca, Mg) As +12H, Ramm.; but it is probably

This species, viewing the form as above, is remotely homœomorphous with cobalt

bloom and vivianite.

VIVIANITE. Phosphate of Iron. Blue Iron Earth. Mullicite, Thom. Fer Phosphaté, H. Blaue Eisenerz, Wern. Eisenblau. Fer azuré, H. Glaukosiderit, Eisenphyllit.

Monoclinic. $C=71^{\circ} 25'$, $I: I=111^{\circ} 12'$, $O: 1i=145^{\circ} 33'$; a:b:c=1.002:1:1.3843.

ii: 1i=125° 47'. ii: i3=167° 7'. ii: 1i=90°.

ii: -1i=144° 20'. 1:1 (front)=119° 10'. i3: i3=154° 14'.

ii: I=145° 36'. 1:1i=149° 35'. $\frac{1}{2}$: $\frac{1}{2}$ (front)=140°52′.

Surface ii smoth, others striated. Cleavage ii highly perfect; ii and 1/2 in traces. Often reniform and globular. Structure divergent, fibrous or earthy; also incrusting.

H.=1.5-2. G.=2.661. Lustre, ii pearly or metallic-pearly; other faces vitreous. Color blue to green, deepening by exposure; usually green when seen perpendicularly to the cleavage face, and blue transversely; the Observed Planes; add 83.

two colors mingled, producing the ordinary dirty blue color. Streak bluish-white, soon changing to indigo-blue; color of the dry powder, liver-brown. Transparent-translucent; opaque on exposure. Fracture not observable. Thin laminæ flexible. Sectile.

1i 1 12 12 13 I 22 ii ii 13 I 44 11 12 -1

Composition.—Fe³P+8H=Phosphoric acid 28³3, protoxyd of iron 43³0, water 28³7, when colorless, being isomorphous with Cobalt Bloom; but changes readily, owing to oxydation of part of the iron; analysis afforded Rammelsberg 6 (Fe³P+8H)+(Fe³P²+8H)

Analyses: 1, Vogel, (Gilb. Ann. lix, 174); 2, Stromeyer, (Unters. 274); 3, 4, Rammelsberg, (Pogg. lxiv, 410); 5, Brandes, (Schw. J. xxxi, 77); 6, Thomson, (Min. i, 452); 7, W. Fisher, (Am. Jour. Sci. [2], ix, 84):

		P	Fe	Fe	Ĥ
1.	Bodenmais,	26.4	41.0	1000	31.0 =9.84, Vogel.
2.	St. Agnes, Cornwall,	31.18	41.23	-	27:48=99:89, Stromeyer.
8.	N. Jersey, Mullicite,	28.40	33.91	12.06	27:49 Ramm, *Undetermined.
4.	ii ii	-	33.98	12.06	27:49 Kamm, Undetermined.
5.	Hillentrup,	30.32	43.78	Plant I	27.49 Ramm, "Undetermined. 25.00, \$\frac{1}{8}10.7, \$\text{Si 0.02}=99.82, B.
6.	Mullicite,	26.06	46.31	-	27·14=99·51, Thomson.
7.	Delaware,	27.17	44.10	-	27-95 Silica 0·10=99·32, Fisher.

CAPORCIANITE, Savi.

Monoclinic, according to Meneghini, resembling heulandite and near that species in its angles; $2i:-2i=131^{\circ}$, $2i:I=150^{\circ}$. Cleavage: ii very easy, and also parallel to 2i; easy parallel to -2i. Faces 2i minutely striated. Also in twins. Also imperfectly radiated foliaceous. H.=2.5. G.=2.470. Color flesh-red. Lustre pearly.

Composition.—Ca'Si'+8\(\frac{1}{4}\) \(\frac{1}{8}\) \(\frac{1}{4}\) \(\frac{1}{8}\) \(\frac{1}\) \(\frac{1}{8}\) \(\frac{1}{8}\) \(\frac{1}{8}\) \(\frac{1}{8

Fe Ca Mg K 0·1 11·3 0·4 1·1 •∡l Ñа Bi 18·1=100-7, Anderson. 21.7 1. 52.8 1.1 0.2


13·17=100·17, Bechi.

2. 52.02 22.83 9.68 1.11 1.11 0.25 B.B. fuses to a white enamel without intumescence. Dissolves easily in acids, and forms a jelly even in the cold.

Occurs in geodes with calcite in the Gabbro rosso of Monte de Caporciano st L'Impruneta and other places in Tuscany. It is sometimes accompanied by native copper.

V. DATHOLITE SECTION.

DATHOLITE. Borate of Lime, P. Borosilicate of Lime, Thom. Datolith, W. Esmarkite, Haus. Humboldite, Levy. Botryolite, Haus. Chaux Boratée Esmarkite, Haus. Siliceuse, H.



H.=1.5-2.5; the lowest on *ii*. G.=2.948.

Lustre of *ii* pearly; other faces, adamantine, inclining to vitreous; also dull and earthy. Color crimson and peach-red, sometimes pearl or greenish-gray; red tints incline to blue, perpendicular to cleavage face. Streak a little paler than the color; the dry powder deep lavender-blue. Transparent—subtranslucent. Fracture not observable. Thin laminæ flexible in one direction. Sectile.

Composition.—Co³Ās+8Ĥ=Arsenic acid 38'43, oxyd of cobalt 37'55, water 24'02; Co often partly replaced by Fe, Ca or Ni. Analyses: 1, Bucholz, (Gehlen's Jour. [2], ix, 308): 2, Laugier, (Mem. d. Mus. d'hist. n. ix, 283); 3, 4, 5, Kersten, (Pogg. ix, 251):

		Жs	Co	H
1.	Riechelsdorf,	37 ·	3 9·	22. =98 Bucholz.
2.	Allemont,	40.0	20.5	24.5, Ni 9.2, Fe 6.1=100.3, Laugier.
8.	Schneeberg	38.48	86.52	24.10, Fe 1.01=100.06, Kersten.
4.	"	38.8 0		24 08, " 4 01=99.81, Kersten.
5.	"	88.10	29.19	23.90, Ca 800=99.19, Kersten.

Yields water alone in a matrass and becomes bluish or green. B.B. on charcoal, gives an arsenical odor, and fuses in the inner flame to a dark-gray bead of arsenical cobalt. With the fluxes a cobalt reaction. Dissolves easily in the acids.

The earthly cobalt bloom, of a peach blossom color, (Kobaltbeschlag), is shown by Kersten to be cobalt bloom, with some free arsenous acid. He obtained,

	Ās	Xs	Òо	Fе	Ĥ
1. Schneeberg,	51.00	19.10	16.60	2.10	11.90-100.70
2. Annaberg.	48.10	20.00	18.30		12.13=98.53.

with a trace of nickel, lime, and sulphuric acid, (Pogg. lx, 262).


Occurs at Schneeberg in Saxony, in micaceous scales, stellularly aggregated. Brilliant specimens, consisting of minute aggregated crystals, are met with at Saalfeld in Thuringia; also at Riechelsdorf in Hessia; Wolfach and Wittichen in Baden; Modum in Norway. The earthy peach-blossom varieties have been observed at Allemont in Dauphiny, in Cornwall, and at the lead mine of Tyne Bottom, near Alston, in Cumberland. A perfectly green variety occurs at Platten in Bohemia, and sometimes red and green tinges have been observed on the same crystals. Occurs also on the north shore of Lake Superior at Prince's Mine on calcite.

Cobalt bloom, when abundant, is valuable for the manufacture of smalt.

ROSELITE.—The Roselite of Levy is probably a variety of cobalt bloom; and Kersten suggests that it may be identical with the variety in the third of his analyses above, which contains lime, an element detected by Children in Roselite. The form is given by Levy as here figured. Haidinger makes it a twin with composition parallel to it.

Trimetic; I: I=132° 48'. O: 11=158° 2'. Cleav-

Trimetic; I: I=132° 48'. O: 11=158° 2'. Cleavage distinct and brilliant, parallel to it. It is deep rose-red, with the lustre vitreous, and H.=3.



Its only known locality is at Schneeberg in Saxony, where it has been found in small quantities on quartz.

LAVENDULAN, (Breithaupt, J. f. pr. Chem. x, 505).—Amorphous, with a greasy lustre, inclining to vitreous. H.=2·5-8. G.=3·014, Breithaupt. Color lavender blue. Streak paler blue. Translucent. Fracture conchoidal.

Contains, according to Plattner, Arsenic and the oxyds of cobalt, nickel and copper, with water. Fuses easily before the blowpipe, coloring the flame deep blue,

In a matrace affords water; becomes friable in the flame of a candle. B.B. on

In a matrass affords water; becomes friable in the flame of a candle. B.R. en charcoal becomes opaque, intumesces, and melts to a glassy globule, coloring the flame more or less green. Dissolves readily with borax to a clear glass, and leaves a siliceous skeleton with salt of phosphorus. With cobalt solution affords a blue glass. Dissolves readily and gelatinizes with nitric said.

Datholite is found in amygdaloid and gnesis; sometimes also in beds of iron ere in primitive rocks. In the latter situation both varieties are found in Arendal is Norway; in agate balls at the Seisser Alp, in the Tyrol. Datholite is most with also in the valley of Glen Farg, Perthshire and Salisbury Craigs; at Utō, Sweden, at Andreasberg, near Wolfstein in Rhenish Bavaria. At Mount Catini, Tuncany, and Toggiana in Modena, carratal large and transparent.

at Andreasberg, near Wolfstein in Rhenish Bavaria. At Mount Catini, Tascany, and Toggiana, in Modena; crystals large and transparent.

Occurs crystallized and massive at the Rocky Hill quarry, Hartford, Coma, in the northeast part of Southington, near Mr. Hamlen's, in amygdaloid, both in crystals, fibrous and massive; also in Berlin, near Kensington; in the northwest part of Meriden and at Middlefield Falls, Conn. The best specimens in Connecticut come from Roaring Brook, fourteen miles from New Haven, where the crystals (£ 489, 493) are sometimes half an inch long, and nearly pellucid; the author obtained from a transparent crystal of this locality I: I=115° 12', giving by calculation for \$\frac{1}{2} \cdot 76° 28'. The plane s, is not quite even, and is often unpolished. B replaces edge 21: I; its intersections with 63 and 4 are not parallel, nor is the intersection with 63 parallel to that of 63 and 61, hence it is probably the plane \$2\$ and \$60\$ the Roaring Brook crystals are unpolished. The angles of the form \$\frac{1}{2}\$ \$\frac{1}{2}\$ Planes \$2\$ and \$60\$ the Roaring Brook crystals are unpolished. The angles of the form \$\frac{1}{2}\$ \$\frac the form 16 I are X=189° 26', Y=57° 8', Z=141° 82'. Bergen Hill, N. J., has afforded fine specimens, and Patterson, specimens of less interest. Occurs sparingly at Piermont, N. Y. At the hill near Copper Falls, south shore of Lake Superior, it occurs in amygdaloid, and the crystals often include native copper, and are sometimes amethystine in color; also on the south shore of Isle Royal in fine crystals; fig. 490, 491 are from crystals in the cabinet of J. E. Teschemacher; plane () gives approximately O (bottom plane), on t,=140°-142°, it; t=109° 80°, which are near the angles of plane; but the 22 intersections of t with 2 and 21 are not parallel, although those with \$ and 4 are parallel.

The crystallization of Datholite was shown to be trimetric by Brooke and Miller,

a conclusion which the author's observations confirm.

ALLOPHANE, Stromeyer. Riemannite.

Reniform and massive; sometimes presenting traces of crystallization on the surface; occasionally almost pulverulent.

H.=3. G.=1.852—1.889. Lustre vitreous or resinous; splendent and waxy internally. Color pale-blue; sometimes green, brown, yellow, or colorless. Streak white. Translucent. Fracture conchoidal and shining. Very brittle.

Composition.—Analyses: 1, Stromeyer, (Unters. 308, and Gilb. Ann. liv, 120); 2, Walchner, (Schw. J. xlix, 154); 3, Guillemin, (Ann. Ch. Ph. xlii, 260); 4, Bassen, (Pogg. xxxi, 53); 5, Berthier, (Ann. des M. [8], ix, 498); 6, B. Silliman, Jr., (Am. J. Sci., [2], vii, 417):

1.	Grafenthal,	Ši 21·92	X 1 82·20	Ĥ 41·30	Ôu ——Ĉu Ö 3-06, Ĉa 0-78, Gyps. 0-52, Fe ² . 0-27==99-88, Stro
	Gersbach,	24.11			2.88=100.95, Walchner.
8.	Fermi,	2376	89·68	85.74	0.95=99:88, Guillemin.
4	Friesdorf,	21.05	8 0.37	40.28	—, CuC 2:39, Fe 2:74, MgC 2:06, B.
5.	Beauvais,	21.90	29-2 0	44.20	—, Clay 47=100, Berthier.
6.	Richmond, Ms.	22.65	8877	85.24	—. Mg 2 88=99 49, Silliman, Jr.

The formula from analyses 2, 3, and 6, is \overline{A} ! \overline{S} i*+15 \overline{H} =Silica 24-22, alumina 40-39, water, 85 39; from 1 the same except 20H in place of 15H.

561

iì ĭž


sometimes between leek and mountain-green. Streak bluish-white. Subtransparent to translucent.

Composition.—Supposed to be an arsenate of the protoxyd of iron. Heated in a glass tube, it turns brown, and loses 25 per cent. of water. On charcoal it gives off an alliaceous odor, turns black without melting, and is then magnetic. Occurs at Lobenstein in Voigtland, with cobaltic pyrites and spathic iron.

SCORODITE. Neoctese, Beud. Martial Arseniate of Copper, P. Cupreous Arseniate of Iron, Bournon. Skorodit, Breit.

Trimetric. $I: I=98^{\circ}2', O: 1i=132^{\circ}20'; a:b:$ c=1.0977: 1: 1.1511. Observed planes as in the annexed figure, with also I, and another pyramid $\frac{1}{4}$. **114°** 34' and 103° 5', (bas.)=110° 58', $\frac{1}{2}$: $\frac{1}{2}$ (pyr.)= 134° 38' and 127° 18', (bas.)=72° 2'. Cleavage: $\frac{1}{2}$ imperfect, $\frac{1}{2}$ and $\frac{1}{2}$ in traces.

H.=3.5-4. G.=3.1-3.3.Lustre vitreoussubadamantine and subresinous. Color pale leekgreen or liver-brown. Streak white. Subtransparent



	Хs	₽e	Ĥ	P.
1. Brazil, Neoctese,	50.78	34.85	15.55	0.67, Cu trace=101.85, Berzelius
2. Popayan,	49.6	84.3	16.9	, Pb 0.4=101.2, Boussingault.
3. Vaulry, gn. cryst.	50.95	31.89	15.64	,=98.48, Damour. G.=3.11
4. Cornwall, blue cryst.	51.06	82.74	15.68	,=99.48, "
5. Saxony, bluish,	52.16	33.00	15.28	,=100·74, "
6. Brazil, Neoctese,	50.96	83.20	15.70	——.=98·86. " G.=3·18

B.B. on charcoal gives out an alliaceous odor, and fuses to a reddish-brown or black scoria, which acts upon the magnet when all the arsenic is expelled. No action

with nitric acid, cold or hot; but easily dissolved with muriatic acid.

A brown variety occurs in the granitic mountains of Schwarzenberg in Saxony, associated with arsenical pyrites, and at Löling, near Huttenberg in Carinthia, along with leucopyrite; also at Chanteloube, near Limoges. A leek-green scorodite is found in the Carinth mines continue agents against a formula in the Carinth mines continue agents. found in the Cornish mines, coating cavities of ferruginous quartz. Minas Geraes, in Brazil, and Popayan have afforded some fine specimens.

The Neoctese, from Brazil, is shown by Descloizeaux and Damour to be identical

with Scorodite, (Ann. Ch. Phys. [3], x, 403).

Occurs in minute crystals and druses of leek-green, grass-green, and greenish-white colors, near Edenville, N. Y., with arsenical pyrites, iron sinter, &c., in white lime-

Named from excepcion, garlic, alluding to the odor before the blowpipe.

An Iron-sinter, (Eisensinter, Arsenik-sinter), from Nertschinsk, analyzed by Hermann, is an amorphous scorodite. Hermann obtained, (J. f. pr. Ch. xxxiii, 95), As 48 05, Fe 36 41, H 15 54=100.

It forms an ochreous crust upon beryl, topaz, and quartz crystalse ALTERED FORMS.—Scorodite occurs altered to Limonite.

```
      Si
      Fe
      Al
      Mg
      H

      5. Montmort, Nontronite, 41:31
      35:69
      3:31
      —
      18:63, Ča 0:19, Ču 0:9=100:3, J.

      6. Andreasberg, "41:10
      37:30
      —
      21:56=99:86, Biewend.

                                                47·1 35·75·7·15 tr. 10·00=100, Müller.
47·59 42·49 0·18 9·79=100, Uricoechea.
7. Tirschenreuth, "
     Wolfenstein, Pinguite, 36.90 29.50 1.80 0.45 25.10, Fe 6.10 In 0.15=100, Kent.
                                                              a With some potash.
```

Kobell found, after expelling the water,

```
Si 52·10 Fe 40·60 Al 3·00 Ca 1·60 Mg 1·08—98·38.
1. Haar,
2. Hungary,
              52.33
                        43.34
                                 2.82
                                          0.93
                                                   073-99-65.
```

The chemist does not consider all the water in chemical combination.

B.B. infusible, but becomes black and then brown. With the fluxes gives as i ron reaction. Partially dissolved in muriatic acid. Nontronite gelatinizes.

From Hungary. Described as breaking readily into a kind of parallelopiped, the upper end and two adjoining lateral edges of which have the opposite magnetic pole from the lower end and the other two edges.

The Pinguite affords the formula Fe Si+Fe Si*+15H. It has a greasy feel. G=

A mineral from Ceylon, resembling chloropal, afforded Thomson, (Min. i, 464): Si 53.00, **F**e 26.04, Æl 1.80, Mg 1.40. H 1800=100-24.

COLLYRITE. Kollyrite, Freisleben. Scarbroite.

Collyrite is a clay-like compound, white, with a glimmering lustre, gressy feel and adhesive to the tongue. G.=2-2·15. H.=1-2. B.B. infusible. Gelatinizes with nitric acid. From Ezquerra in the Pyrenees, in porphyry near Schemnitz, Hungary, near Wessenfels, Saxony. Scarbroite from the coast of Scarborough is related to Collyrite. G.=1·48. Does not fall to pieces in water or increase in

Analyses: 1, Klaproth, (Beit. i, 257); 2, Berthier, (Ann.d. M. ii, 476); 3, Kerten, (Schw. J. lxi, 24); 4, Vernon, (Phil. Mag. and Ann. v, 178):

		Si	₩l	₽e	Ħ
1.	Collyrite, Schemnitz,	14.0	450		42.0=101, Klaproth.
2.	" Ezquerra,	150	44.5		40.5=100, Berthier.
3.	" Saxony,	23.3	42.8		347=1008, Kersten.
4.	Scarbroite.	10.20	42.50	0.25	46.75=100. Vernon.

The formula X1°Si+15H has been written for Collyrite.

Dillnite is a related substance, white and firm, (H.=3.5), or earthy, (H.=1.8-2), G.=2.574-2.835. It is the gangue of the disspore of Schemnitz. Analyses by Hutzelmann and Karafiat, (Pogg. Ixxviii, 575):

```
Si 22.40 Al 56.40 Ca tr. Mg 0.44 H 21.18, Fe, Mn, alk. tr.=100.37. H.
  28.53
            53.00
                      0.88
                               176
                                        20-05=99-22, Karafiat.
```

The analyses correspond to the formula \(\frac{1}{2}\)\(\frac{1}{2 H 21:38. Dr. J. L. Smith obtained a very different result for a similar material from the same Schemnitz locality, as given under Pholerite, (q. v.)

Composition.—Cu'(As,P)+H (the arsenic to the phosphoric acid as 8:1)=Arsenic soid 31.7, phosphoric acid 6.6, oxyd of copper 58.4, water 3.3=100, and isomorphous with libethenite. Analyses: 1, Kobell, (Pogg. xviii, 249); 2, 3, Richardson, (Thom. Min. i, 614); 4, Hermann, (J. f. pr. Ch. xxxiii, 291); 5, Damour, (Ann. Ch. Phys. [3], xiii, 404); 6, Thomson, (Min. i, 615); 7, Hermann, (loc. cit.):

	•			Жs	P	Ču	Ĥ
1.	Cornwall,	cryst		36.71	3.36	56.48	3.50=100, Kobell.
2.	"	ĩ,		89.9		56.2	8.9=100, Richardson.
8.	**	**		39.80		56.65	3.55=100, Richardson.
4.	**	**	G.=4·135,	83.20	5.96	56.38	4·16=100, Hermann.
5.	66	"	G.=4.378,	34.87	3.43	56.86	3.72=98.88, Damour.
6.	" 1	ibrou					4.41=100, Thomson.
7.	"	"	G.=8.918,	40.50	1.00	51.08	8.83, Fe 3.64=100, Hermann.

The fibrous is the wood-arsenate, (Holzkupfererz), a variety from Cornwall, pre-

senting a soft velvet-like surface, and a siskin or greenish-gray color.

B.B. in the forceps affords a brown crystalline bead; on charcoal fuses with a kind of deflagration, and yields arsenical fumes and a white brittle metallic globule, which, as it cools, becomes covered with a red scoria. Dissolves in nitric acid, and also in ammonia.

The crystallized varieties occur disposed on, or coating, cavities of quartz, at the Cornwall mines; also in inferior specimens at Alston Moor, in Cumberland. Found at Camsdorf and Saalfeld in Thuringia, in the Tyrol, the Bannat, in Siberia, Chili, and other places.

CONICHALCITE. Konichalcit, Breit. and Plattn., Pogg. Ann. lxxvii, 189.

Reniform and massive.

ir. Ç

> Color pistachio-green, inclining to eme-H.=4.5. G.=4.123. rald-green; streak the same. Subtranslucent. Brittle. Fracture splintery.


> Composition.—(Cu, Ca)4 (P, As)+11H, with some vanadic acid replacing (!) part of the phosphoric, the copper and lime in equal proportions, the arsenic to the other acids as 2:1. Closely allied to olivenite and volborthite. Analysis by Fritzsche, (loc. cit):

P 8.81, Ÿ 178, Ču 8176, Ca 21.36. Ĥ 5·61. Probably from Hinajosa de Cordova, in Andalusia, Spain.

EUCHROITE, Breithwupt.

Trimetric. $I: I=92^{\circ} 8', 0: 1\bar{\imath}=148^{\circ} 40';$ a:b:c=0.6088:1:1.038. Observed planes as in the annexed figure. $1i:1i=117^{\circ}20'$, $ii: 1\bar{\imath} = 121^{\circ} \ 20', \ i\bar{\imath}: 3\bar{\imath} = 132^{\circ} \ 24', \ i\bar{\imath}: 2\bar{\imath} = 140^{\circ} \ 36\frac{1}{2}', \ 2\bar{\imath}: 2\bar{\imath} \ (\text{ov. } i\bar{\imath}) = 101^{\circ} \ 13'.$ Cleav-

age: I and 12. Faces 12 vertically striated. H.=3·5—4. G.=3·389. Lustre vitreous. Color bright emerald or leek-green. Transparent - translucent. Fracture small conchoidal—uneven. Rather brittle.



Composition.—Cu'Ās+7Ĥ=Arsenic acid 84·15, oxyd of copper 47·15, water 18·70 =100. Analyses: 1, Turner, (Edinb. Phil. J. iv, 801); 2, 3. Kühn, (Ann. d. Ch. u. Pharm. li, 128); 4, Wöhler, (ib. 285):

 Si
 Ni
 Mg
 Fe
 Ca
 Hi
 H

 1. Chrysoprase earth, 35:00 15:63 125 4:58 0:42 5:00 38.12, Klaproth.

 2. Alisite, 54:63 32:66 5:89 Fe1:18 0:16 0:30 5:23=100, Schmidt.
 35-80 278 14-66 Fe2-69 23 04 31 03=100, Baer. 3. Hard Pimelite,

.The second corresponds nearly to the oxygen ratio, for the protoxyds, silica and water: 1:3:4; the third for the protoxyds, peroxyds, silica and water. :1:2:3:3.

From Silesia and elsewhere.

MONTMORILLONITE, Salvetat.

Rose-red; fragile. From Montmorillon; Confolens in Charente; and near St. Jes. de Colle, in Dordogne.

Smectite, Breithaupt, is from Cilley in Lower Styria, and Zeug in Croatia. Supposed formula Al Si +6H.

Malthacite of Breithaupt, (J. f. pr. Ch. x, 510). In thin plates and massive; soft like wax. G.=199—201; white or yellowish, and translucent. From basels at Steindorfel, and greenstone near Bersun in Bohemia. Analyses: 1, Damour, (Bull Soc. Geol. de Fr. [2], iv, 464); 2, L. A. Jordan, (Pogg. lxxvii, 591); 3, Meissner. (J. f. pr. Ch. x, 510):

Ĉa. Ŵg Æl ₽e 1. Montmorillonite, 50.04 20.16 0.68 1.46 0.23 1.27 26.0=99.84, Demour. 27 89, Jordan. 85 8, Meissner. 2. Smectite, 51-21 12-25 207 2.13 4-89 0-2 3. Malthacite, 3.1 50-2 10-7

Razoumofakia of John, is another clayey or halloyaite-like substance from Komuth in Silesia. Zellner obtained Si 54 50, Al 27 25, Ca 2 00, Mg 0 37, Fe 725. Ĥ 14-25=98-62

ERDMANNITE, Berlin, Pogg. lxxxviii, 160.

In imbedded grains and folia: with no traces of crystallization. G.=3.1. Lustre vitreous. Color dark-brown. In thin splinters. Translucent.

Composition.—Analysis by Blomstrand, of half a gramme, (loc. eit.):

Si Ox Ced La Al 31-85 34-89 11-71 Ŵп Y H and loss Ċa Ėе 6.46 8-52 0.86 143 4-28

From the island Stoko in the Langesundfiord, near Brevig. Named in honor of M. Erdmann.

BARALITE

Massive, and cellular.

H.=4. Lustre glimmering. Color greeenish-black. Opaque Streak gravish-green.

mposition.—Contains silica, alumina, peroxyd of iron, lime, magnesia and water B.B. alone infusible; with borax, a glass colored by iron; with soda partly solved. Wholly soluble in muriatic acid. In a tube yields pure water, and ie comes brownish.

11

ii

H.=2.5. G.=2.9-3. Lustre adamantine, not very distinct. Color olive-green, passing into yellowish-brown, bordering sometimes upon hyacinth-red and blackish-brown; also passing into grass-green and emerald-green. Streak olive-green—brown, yellow, pale. Subtranslucent. Rather sectile. Pyroelectric.

Composition.—Fe³ Ås+Fe³Äs²+18Ĥ=(Fe³,Fe)*Äs²+18Ĥ=Arsenic acid 40.4, peroxyd of iron 28.1, protoxyd of iron 12.6, water 18.9; according to G. Rose probably Fe¹Äs²+18Ĥ. Analysis by Berzelius, (K. V. Ac. H. 1824, p. 354):

As P Fe Ĉu Ĥ 18.61, gangue 1.76=102.95. 40.20 2.53 0.65 39.20

Exposed to a gentle heat, it becomes red; a higher temperature causes intumescence, but drives off little or no arsenic, and leaves a red powder. B.B. copious arsenical fumes are emitted on charcoal, and a metallic scoria is obtained in the reducing flame which acts on the magnetic needle.

Cube ore was formerly obtained at the mines of Huel Gorland, Huel Unity, and Carharrack in Cornwall, coating cavities in quartz, with ores of copper; now found in quartz at Burdle Gill in Cumberland, in small brilliant crystals; also in Australia; at St. Leonard in France; and at Schneeberg and Schwarzenberg in

BEUDANTITE, Levy. This mineral from Horhausen, Nassau, has been referred to Cube ore, but Brooke gives reason for believing it distinct. Form according to Levy, rhombohedral; R: R=86° 30', but faces not even. Black and opaque. Percy obtained in two imperfect analyses, (Phil. Mag. [3], xxxvii, 161):

Äs	P	S	Fe	Pb	Ĥ
9.68	1.46	12.31	42.46	24-47	8.49
13.60	undet.	12:35	87.65	29.52	8.49

Unless containing largely of impurities, it must be distinct from the above. Rammelsberg deliuces the formula Fet As+8H.

ALTERED FORMS. - Cube ore has been observed altered to Psilomelane, Limonite, (Fe°H'), Red Iron Ore, (Fe).

WAVELLITE. Subphosphate of Alumina. Devonite. Alumine Phosphatee, H. Lasionite, Fuchs.

Trimetric. $I: I=126^{\circ}\ 25',\ O: 1\bar{\imath}=143^{\circ}\ 23';$ a: b: c=0.7431:1:1.4943. Observed planes as in the annexed figure, with also 1, 22 and i 1: I=129° 47', 1:1 (mac.) 146° 28', (brach.) 110° 20' and (bas.) 79° 34′, 22 : 22 (pyr.) 117° 53′, 118° 33′, (bas.) 93° 7', $ii:i\frac{3}{3}=123^{\circ}57'$. Cleavage: I rather perfect: also brachydiagonal. Usually in hemispherical or globular concretions, having a radiated structure.

H.=3·25—4. G.=2·337, (Barnstaple), Haidinger; 2·3616, (Irish variety), Richardson. Lustre vitreous, inclining to pearly and resinous. Color white, passing into yellow, green, gray, brown, and black. Streak white. Translucent. Index of refraction 1.52.

Composition. - (X14P3+18H)+1 Al F=Alumina 33.8, phosphoric acid 34.9, alumi-

nium I.5, fluorine 3·1, water 26·6=100. Sonnenschein's analysis corresponds nearly to Al-P2+12H.

Analyses: 1, 2, Fuchs, (Schweig. xxiv, 121); 3, Berzelius, (Schw. J. xxvii, 63), 4

—7, Erdmann, (Schweig. lxix, 154); 8, Hermann, (J. f. pr. Chem. xxxiii, 288); 9, Sonnenschien (J. f. pr. Chem. liii, 344):

	∓ 1	P	Ħ	HF	₽e
1. Devonshire,	87.20	85.12	28.00		-=100.32, Fuchs.
2. "	87.16	34.84	28.00		—=100 Fuchs.
8. "	85.35	83.40	26.80	2.06	1-25, Ca 0-50-99-39, Bermin
4. Strigis, blue,	36.60	34.06	27.40	trace	1 00=99 06, Erd.
5. " green, yellow,					2.69=99.46, Erd.
6. " brown,	84.90	81.55	24.01	trace	2·21. Si 7·30=99·97, Erd.
7. " black,	35.39	32.46	24.00	trace	1.5 Si 6.65=100, Erd.
8 Zbirow,	36.39	34.29	26.34	F 1.69	1.20=98.91, Herm.
9 Allendorff,	85-76	32.16	28.32	trace (1 20=98 91, Herm. Ca 0 86, Si 2 70=98 80, Sonn.
•					•

a With peroxyd of Manganese.

Hermann obtained much less fluorine than Berzelius, and gives a different formula But Berzelius remarks that this ingredient may easily fall short.

B.B. whitens and intumesces, but is infusible; gives the reaction of phosphora. In a matrass yields water, and acts on glass from the hydrofluoric acid present. Reduced to powder, and heated with sulphuric acid, it gives off a vapor which or rodes glass.

Wavellite was first discovered in a tender clay slate near Barnstaple, in Deveshire, by Dr. Wavell. It has since been found at Clonmel and Cork, Ireland; is the Shaint isles of Scotland, at Zbirow in Bohemia; at Frankenberg and Langustriegis, Saxony; Diensberg near Giessen, Hesse Darmstadt; on brown iron ore is the Jura limestone at Amberg in Bavaria, (the Lasionite of Fuchs); in a Manganese mine at Weinbach near Weilburg in Nassau, (Genth); at Villa Rica, Minas Gersa Brazil.

In the United States reported as found near Saxton's River, Bellows Falls, N. H.: also at the slate quarries of York Co., Pa., near the Susquehannah; found at Washington mine, Davidson Co., N. C., with actinolite, pyrites and native silver.

A Wavellite containing oxyd of lead occurs at Rosières in stalactites, as detected by Berthier.

CACOXENE. Kakoxen, Steinmann.

Occurs in radiated tufts of a yellow or brownish yellow color. II.=3—4. G.=3.38. Becomes brown on exposure.


Composition.—Supposed to be an iron-wavellite. (Fe, \(\frac{\mathbb{H}}{2}\)) Ps+18\(\text{H}\), but doubtful. Analyses: 1, Steinmann, (Leonh. Orykt. 750); 2, Holger, (Baumg. Zeits. viii, 129); 8, Richardson, (Thomson's Min., i, 476):

₽e P Ċа Si H and HF 17.86 0.15 8.90 25.95=99.19, Steinmann. 1. Zbirow, 10.01 86.32 8.30 18.98, with Mg 7.58, Zn 1.23, \$11.29,H. 86.88 9.20 2. 11.29 1.1 20.5 30.2, with Mg 0.9=97.9, Rich. 48.1 2.1

The differences are supposed to be due to impurities. Steinmann's analysis of wavellite was made on a specimen from Zbirow, and has the composition of true cacoxene. B.B. acts like wavellite, except that it affords the reaction of iron.

It occurs at the Hrbeck mine, near Zbirow in Bohemia, along with an earthy brown iron ore, in the graywacke formation.

CHILDRENITE, Levy.



Trimetric. $I: I=111^{\circ} 54', O: 1i=136^{\circ} 26'; a:b:c=0.9512:1:1.4798.$ Observed planes as in the annexed figure, with also $\frac{3}{2}\frac{3}{2}$. $O: 2i=127^{\circ} 53', O: 1=131^{\circ} 4', O: \frac{3}{2}=142^{\circ} 35', O: 3i=90^{\circ}, 1:1 \text{ (mac.) } 130^{\circ} 4', \text{ (brach., or } 130^{\circ} 4', \text$

over 2), 102° 41', (bas.) 97° 52', 21 : 21 (ov. 0)=75° 46', B. and M. Cleavage : 41, imperfect.

H.=5. G.=3.18-3.24; 3.184, Kengott. Lustre vitreous, inclining to resinous. Color yellow and pale yellowish-brown, also vellowish-white, and brownish-black. Streak white, yellowish. Translucent. Fracture uneven. In a matrass much water.

Composition.—(R³, X1)⁶ P³+15H, with the protoxyds to the alumina as 4:3=Phosphoric acid 27.8, alumina 14.4, protoxyd of iron 31.3, protoxyd of manganese 8.9, water 17.6=100. In the formula, the oxygen ratio for the bases and phosphoric acid is 15: 15; Rammelsberg's analysis, (Pogg. lxxxv, 435), which follows, affords 14-4: 15.

P 28-92 X114-44 Fe 30-68 Mn 9-07 Mg0-14 H16-98=100-23, Rammelsberg.

B.B. color of flame bluish-green; with the fluxes reactions of iron and manganese.

Soluble in muriatic acid after long ignition.

Occurs in crystals and crystalline coats, on spathic iron, pyrites or quartz, and sometimes with apatite near Tavistock in Devonshire; on slate at Crinnis in Corn-

If the dome 27 be made the fundamental vertical prism, then I: I=104° 14', 15; 1% (top)=73°, 1%: 1% (ib.)=87° 14'; the cleavage macrodiagonal; a: b: c=1.3514: 1:1.2853.

ERINITE, Haid.

In mammillated crystalline groups, concentric in structure and fibrous, and rough from the terminations of very minute crystals; the concentric layers compact, and often easily separable. Traces of cleavage in one direction.

H.=4.5-5. G.=4.043. Lustre almost dull, slightly resinous. Color fine emerald-green, slightly inclining to grass-green. Streak green, paler than the color. Subtranslucent—nearly opaque. Brittle.

Composition.—Ču^aĀs+2Ĥ=Arsenic acid 347, oxyd of copper 599, water 54=100. Analyses, (approximative), by Turner, (Ann. Phil. [2], 1828, iv, 154):

Ås 33 78, Ču 59.44, Ĥ 5.01, ₹1 177=100.

Erinite occurs associated with other arsenates of copper, in the county of Lim-


erick. Ireland, whence its name.

CORNWALLITE.—Zippe thus names an arsenate of copper from Cornwall, which afforded Lerch, as mean of two analyses, (Ramm. 4th Supp. 122): As 30·21, P 2·16, Cu 54·61, H 13·02=100, leading to the formula Cu* As+5H. G.=4·166; H.=4·5. It occurs amorphous of a blackish or verdigris-green color, and is associated with olivenite.

PHOSPHOCHALCITE, Kobell. Pseudomalachite. Hydrous Phosphate of Copper Dihydrite, Herm. Kupferdiaspore, Kühn. Lunnite, Bernhardi.

Trimetric; hemihedral, producing monoclinic forms. I: I=109° 28', O: 1i=146° $18\frac{1}{2}$; $a:b:c=\sqrt{2}:1:0.6667$. Observed planes as in the annexed figure. $i_2:i_2=141^\circ$ 4' and 38° 56', 1: 1=117° 49', $0:\frac{1}{2}i=166^\circ$ 34', $1i:12=168^\circ$ 46'. Cleavage: ii imperfect. Also reniform or massive; indistinctly fibrous, and having a drusy surface.

H.=4.5-5. G.=4-4.4. Lustre adamantine, inclining to vitreous. Color dark eme-



II. TANTALATES, COLUMBATES,* TITANATES,* TUNG-STATES, MOLYBDATES, VANADATES, CHROMATES.

I. PYROCHLORE GROUP. Monometric. Oxygen ratio 1: 2.

Perofskite, Ča Ti.

PYRRHITE.

Pyrochlore, Rº Ta2.

II. SCHEELITE GROUP. Dimetric. Oxygen ratio of bases and acid, 1: 3.

Scheelite,

Ċa W.

WULFENITE,

Pb Mo.

Scheeletine, Pb W.

AZORITE.

III. FERGUSONITE GROUP. Dimetric. Oxygen ratio of bases and acid. 2:1.

FERGUSONITE, (Y, Ce) Ta.

IV. TANTALITE GROUP. Trimetric. I: I=100°-102°.

TANTALITE,

(Fe, Mn) (Ta, Cb).

SAMARSKITE.

WOLFRAM,

(Fe, Mn)W.

MENGITE.

Columbite, $(\hat{\mathbf{f}}\mathbf{e}, \hat{\mathbf{M}}\mathbf{n})^3 \hat{\mathbf{C}}\mathbf{b}^2$.

V. POLYMIGNITE GROUP. Trimetric. I: I=90° 80' to 95°

POLYMIGNYTE,

ÆSCHYNITE.

POLYCRASE,

Appendix,

EUXENITE,

RUTHERFORDITE.

VI. YTTROTANTALITE GROUP. Oxygen ratio 1: 1.

YTTROTANTALITE,

ſ₹³(Ta, W, ♥).

VII. VANADATES, CHROMATES.

CROCOISITE,

Pb Cr.

^{*} The metal of the American Columbite was early named Columbium, by Hatchett, (in 1801); and as it is the same which Rose has since called niobium, Hatchett's name is here restored. See Phil. May. [41, vii. 46]. June 1854.

name is here restored. See Phil. Mag. [4], vii, 461, June 1854.

† The relation of the Titanates to the Columbates, etc, are so close, and at the same time so imperfectly understood and the acids are so often combined in the same mineral, that the species are here arranged together, instead of making a separate head for the Titanates.

to sky-blue. Streak a little paler. Translucent-subtranslucent. Fracture not observable. Very sectile. Thin laminæ flexible.

Composition.—Ču^aĀs+10 Ĥ+ČaČ(!)=Arsenic acid 25.4, oxyd of copper 43.8, water 19.8, carbonate of lime 11.0=100. The carbonate of lime may be an impurity. Analysis by Kobell, (Pogg. xviii, 253):

Falkenstein, Tyrol, Ās 25.01 Ča 43.88 Ĥ 17.46 ČaČ 13.65=100.

B.B. decrepitates briskly, throwing off fine fragments which tinge the flame green, blackens, and fuses to a steel-gray globule, not crystalline on its surface. On charcoal emits moisture quietly, and after a long continuance of the blowpipe heat, swells a little from the extrication of the vapor of arsenic. With soda, an imperfectly fluid mass is obtained, which contains a white metallic nucleus. Soluble in acids evolving carbonic acid.

This mineral usually occurs in the cavities of calamine, ealc spar, or quartz, accompanied by other ores of copper, appearing in small aggregated and diverging fibrous groups of a pale-green color, and possessing a delicate silky lustre. It has been observed in the Bannat; at Posing and Libethen in Hungary; Nertschinsk in Siberia; Falkenstein and Schwatz in the Tyrol; Saalfeld in Thuringia; Riechels-

dorf in Hessia; Schneeberg in the Erzgebirge.

Rammelsberg suggests that this species may be related to Aurichalcite; the latter has a yellowish-green color and may thus be distinguished.

DELVAUXENE, Dumont. Delvauxit.

Massive and earthy, with a yellowish-brown, brownish-black, or reddish color.

H.=2.5. G.=1.85. Waxy; dull. Opaque to translucent on the edges.

Composition.—FeT+24 H=Phosphoric acid 15.9, peroxyd of iron 35.8, water 48.3=100. FeT+18H, Delvaux. Analyses: 1, 2, Dumont, (L'Institut, No. 276); 3, Delvaux, (Bull. Acad. Brux. 1838, 147):

1.	Reddish brown,	P 16:04	Fe 34.20	Ĥ 49-76=100.
2.	Brownish black,	16.57	36.62	46.81=100.
2	and the same of th	18-90	40.44	41-13-00-77

B.B. changes color, decrepitates, and fuses to a gray magnetic globule.

From Berneau, near Visé in Belgium. It is supposed to be a mechanical mix-

Beraunite, Breit., is supposed to be a hydrous phosphate of peroxyd of iron. Occurs foliated and radiated, with one perfect cleavage and one imperfect; hyacinth-red or reddish-brown; streak reddish ochre-yellow. B.B. fuses and colors the flame bluish-green. Soluble in muriatic acid. Found in limonite near Beraun in Bohemia; also near Kertsch, Crimea. It is altered Vivianite, (Breit.)

DUFRENITE, Brongn. Green Iron Ore. Kraurite, Br. Grüneisenstein, M.

Trimetric. I: I about 123°. Cleavage: brachydiagonal. Radi-

ated fibrous, with a drusy surface.
H.=3.5—4. G.=3.2—3.4. Lustre silky, weak. Color dull leek-green, blackish-green; alters on exposure to yellow and brown. Streak siskin-green. Subtranslucent.

Composition.—Fe'P+21H=Phosphoric acid 28.0, peroxyd of iron 63.1, water 8.9 =100. Analyses: 1, Karsten, (Arch. f. Bergb. u. Hütt. xv, 243); 2, Vauquelin, (Ann. Ch. Phys. xxx, 202):

Composition.—Analyses: 1, from Miask, 2, Bravig, 3, Fredericksvärn, Wöhler, (Peg. xlviii, 83); 4, 5, Miask, Hermann, (J. f. pr. Chem. xxxi, 94,1, 188, 192); 6, 7, Fredericksvärn, A. A. Hayes, (Am. J. Sci., xlvi, 164); 8, Microlite, Shepard, (Am. J. Sci., xxxii, 888); 9, ib. Hayes, (ib. xlvi, 158):

Ti Mn Fe Ca Y Ce H

tr. 0-15 1-29 10-98 0-81 18-15 1-16, Nas-98,F3-23,Sn, Mg == 102-06, W.

tr. 1-69 1-83 9-88 — 5-16 7-06, F-4-60, Sn, Mg, Na tr. == 97-30, W.
62-75 2-75Fe2-16 12-85 — 6-80 4-20, U5-18, Sn 0-81, alk. tr. == 97-25, W.
2-28 tr. 5-11 18-54 0-70 3-09 0-50, La 2-00, Zr 5-57, K, Na, Li 3-72,

F 3-0=101-71, Hermann. 1. 67.88 2. 67-02 4 62.25 4-90 — 2-28 9-80 0-94 15-23° — Mg 1-46, K 0-54, Na 2-49, F 2-21= 100-83, Herman. **5.** 60·88 6. 58·10 20·20 — \$\frac{\pi}{2}\cdot 85 & 19·45, oxyds of U, Mn, Pb, Sn, 1·20, ign. 0·80=\$7·10, H.
7. 59·00 18·88 — 16·78, \$\frac{\pi}{2}\cdot end \$\frac{\pi}{2}\cdot etc. 0·70, \$\frac{\pi}{8}\sigms 680=101·19, H.

8. 75 70 WY U 7 42, Ca 14 84, H 2 04=100, Shepard. Microlite.
9. 79 60 Fe 0 99, ox. of U and Mn 2 21, Ca 10 87, Pb 1 60, Sn 0 70=95 97, Hayaa

a With oxyd of Lanthanum. b With some Lime and Titanic acid. c With Therin. d Percuyd of Carlum.

B.B. becomes pale brownish-yellow or lemon yellow, but retains its lustre, and fuses with great difficulty. With borax forms a reddish-yellow transparent globule in the oxydating flame, which, on flaming, becomes opaque; with more of the borax, becomes a white enamel. With salt of phosphorus dissolves completely, and at first, with some effervescence, forming a glass which in the outer flame is yellow while hot, but becomes grass-green on cooling.

Pyrochlore occurs imbedded in syenite at Fredericksvärn and Laurvig in Norway, associated with zircon, polymignite, and phosphate of vitria; also at Bravie with

associated with zircon, polymignite, and phosphate of yttria; also at Brevig with

thorite, and at Ilmengebirge near Miask in Siberia.

Named by Berzelius, in allusion to its becoming yellowish-green under the blow-

pipe, from τυρ, fire, χλωρος, green.

Microlite (from the albite vein, Chesterfield, Mass., associated with red and green tourmaline) resembles pyrochlore closely, and is here referred by J. E. Teschemscher, (Am. J. Sci. xliii, 38). It presents the forms of f. 11, 19, and 41. H.=53. G.=5405, Hayes. Colors pale-yellow to brown. The light colored crystals appear to be nearly pure columbate of lime.

PYRRHITE, G. Rose, Pogg. xlviii, 502.

Monometric; in octahedrons. Cleavage not observed. H. = 6. Lustre vitreous. Color orange-yellow. Subtranslucent.

Infusible. Small splinters blacken and color the flame deep yellow. it dissolves easily in borax or salt of phosphorus; adding largely of the fluxes, it forms a clear glass, which, with still more of the flux, becomes yellowiah-green; with less, the glass remains colorless.

Pyrhite was found by von Perofski of St. Petersburg, at Alabaschka, near Mursinsk, where it occurs in drusy feldspar cavities, containing also tables of lithis mica, crystals of albite, and white topas. The largest crystal was but three lines long. The name is from **repos*, yellow.

With this species J. E. Teschemacher identifies small orange-yellow octahedross found with albite at the Azores. The crystals are a half to two lines long, and those of minute size are transparent.

According to chemical and blowpipe trials by A. A. Hayes, on specimens furnished him by Mr. Teschemacher, these crystals consist of columbate of zircomia, colored

apparently by oxyds of iron, uranium, and manganese.

B.B. in the forceps, on the first impulse of the heat, becomes darker, and the first orange color returns on cooling, even if the heat has been high; at the meltirg point of cast iron, in the reduction flame, the flame becomes permanently darker and brown. With borax (6 parts to 1 of assay) it dissolves and affords a clear colorless glass, which becomes instantly opaline or opaque on flaming; transferred to

plane is sometimes triangularly striated. Also foliated massive, and in druses.

H.=2. G.=2·4—2·66. Lustre: of O pearly; of other faces, vitreous or subadamantine. Color emerald or grass-green to verdigris-green. Streak somewhat paler than the color. Fracture scarcely observable. Sectile.

Composition.—Cu⁶Ās+12Ĥ, Damour—Arsenic acid 24·9, oxyd of copper 51·7, water 28·4. From Chenevix's analysis, Cu⁶Ās+12Ĥ—Arsenic acid 21·31, oxyd of copper 58·71, water 19·98.—From Hermann's analysis, Cu⁶Ās+23Ĥ—Arsenic acid 18·02, oxyd of copper 49·61, water 32·37.—Analyses: 1, Chenevix, (Phil. Trans. 1801); 2, Hermann, (J. f. pr. Ch. xxxiii, 294); 3, 4, Damour, (Ann. Ch. Phys. [3], xiii, 404):

			Āв	Ču	Ħ
1.	Cornwa	ll,	21.	58 ·	21=100, Chenevix.
2.	"	G.=2·485,	17.51	44.45	31·19, Fe 2·92, Al and P 8·98=100, H.
8.	"	G = 2.659	19.85	52 ·92	28.94, 1 1.80, 1 1.29=99.80, Dam.
4.	46	44	21.27	52.30	22.58, X 1 2.13, P 1.56=99.84, "

B.B. decrepitates, loses color and transparency; on charcoal emits arsenical fumes, and fuses to a black globule, after forming a black spongy scoria; with soda affords copper. Soluble in acids and ammonia.

copper. Soluble in acids and ammonia.

The copper mines of Tingtang, Huel Gorland, and Huel Unity, near Redruth, are its principal localities in Cornwall. Occurs also crystallized in iron ore, at Sayda in Saxony; in minute crystals at Herrengrund in Hungary; Moldawa in the Bannat.


Taking $\frac{1}{2}$ R as the fundamental rhombohedon, then $R: R=88^{\circ}$ 46', and a=17768. ALTERED FORMS.—Found altered to Chrysocolla.

LIROCONITE. Octahedral Arseniate of Copper. Linsenerz, Wern. Linsenkupfer, Haus. Cuivre Arseniaté Octaèdre Obtus, H. Chalcophacite, Glocker.

Trimetric. $I: I=119^{\circ}20'; 119^{\circ}9', Descl.; 1i:1i=72^{\circ}22'.$ Observed planes as in the annexed figure. Cleavage lateral, but obtained with difficulty. Rarely granular.

H.=2—2.5. G.=2.882, Bournon; 2.926, Haid.:

H.=2—2.5. G.=2.882, Bournon; 2.926, Haid.: 2.985, Hermann; 2.964, Damour. Lustre vitreous, inclining to resinous. Color and streak skyblue—verdigris-green. Fracture imperfectly conchoidal, uneven. Imperfectly sectile.



Composition.—25 Cu, 5 $\frac{1}{4}$ l, 6 ($\frac{5}{4}$ As + $\frac{1}{4}$ P), 75 $\frac{1}{4}$; [=5 Cu⁵As + $\frac{1}{4}$ P+75 $\frac{1}{4}$ P, Analyses: 1, T. Wachtmeister, (K. V. Ac. H. 1832, 80); 2, Hermann, (J. f. pr. Ch. xxxiii, 296); 3, 4, Damour, (Ann. Ch. Phys, [8], xiii, 404):

```
As P Cu Al H

1. Cornwall, 20.79 3.61 85.19 8.03 22.24, Fe 3.41, Si 4.04, gangue 2.95=100.26,

2. " 28.05 3.73 86.38 10.85 25.01, " 0.98=100, Hermann. [Wacht.

8. " 22.22 8.49 87.40 10.09 25.44=98.47, "
```


The above constitution, as far as the proportion of the bases and acids is concerned, is deduced by Rammelsherg from Wachtmeister's and Damour's analyses. Hermann's gives 20 Cu, 5 XI, 6As, 60 H.

B.B. loses color and transparency, emits arsenical fumes, and on charcoal becomes

a black, friable scoria, containing some metallic globules. With borax a green globule, and a partial reduction. Dissolves in nitric acid without effervescence.

Crystals occasionally an inch in diameter; usually quite small. Occurs with various ores of copper, pyrites, and quartz, at Huel Gorland and Huel Unity, in Corp. wall; also in minute crystals at Herrengrund in Hungary, and in Voigtland.

URANITE. Uran Mica. Uranglimmer. Uranoxyd, Haus. Urane Oxydé, H. Uranphyllit.



Dimetric. $0:1i=128^{\circ}35':a=1.2534$. Observed planes as in the annexed figure: $0:\frac{1}{2}i=147^{\circ}\ 56',\ 0:\frac{2}{3}i=140^{\circ}\ 7',\ 0:2i=111^{\circ}\ 45'.$ Cleavage: basal, highly perfect. Surface O smooth, ii rough.

Lustre of O pearly, of other faces sub-adamantine. Transparent—subtranslucent Fracture not observable. Sectile. Lami-

næ brittle and not flexible.

VAR. 1. URANITE. Lime-Uranite. Kalk-Uranit. Autunite.

H.=2-2.5. G.=3.05-3.19. Color citron to sulphur-yellow.

Composition.—Ca^{*}P+E^{*}P+16Ĥ=:Phosphoric acid 15.7, oxyd of uranium 627, lime 6.1, water 15.5=100. Analysis by Berzelius, (Jahresb. xxii, 212):

P Ca Mg and Mn Ba 0.20 1.57 61.78 5.88 1548=100:12 15.20

B.B. fuses to a blackish mass like pitchblende. A yellow solution in nitric seid.

Uranite is found with other ores of uranium, associated with silver, tin, and iros

Occurs in the Siebengebirge in the hornstone of a trachytic range; at Johann-georgenstadt and Eibenstock; at Lake Onega, Wolf Island, Russia; also near Limoge georgenstadt and Elbenstock; at Lake Onega, woll island, Russia; also near Limoge and at St. Symphorien near Autun. Occurs sparingly at the Middletown feldspar quarries, associated with columbite and pitchblende, in minute tabular crystals and thin scales of light green and lemon yellow colors; also in minute crystals at Chesterfield, Mass., on the quartz or albite, and sometimes in the red centres of tournal lines, and at Ackworth, N. H., straw-yellow and light green; also in a gneiss quarry on the Schuylkill near Philadelphia, about a quarter of a mile above the suspension bridge.

VAR. 2. CHALCOLITE. Copper-Uranite, Kupfer-Uranit. Torberite.

H.=2-2.5. G.=3.5-3.6. Color emerald and grass-green, and sometimes leek, apple, and siskin-green. Streak somewhat paler than the color.

Composition.—Cu²P+C⁴P+16H, or same as above, with copper in place of lime—Phosphoric acid 15·1, oxyd of uranium 61·2, oxyd of copper 8·4, water 15·2=100 Analyses: 1, Berzelius, (loc. cit): 2, Werther, (J. f. pr. Ch. xliii, 334):


P Ču 15-05=100-45, Berzelius. 15-39, Si 0-49, Earthy substance 0-41, Werther. 61-29 1. 15.57 8.44 2. 14.34 59.08 8-27

B.B. melts and gives off vapors of lead, leaving a dark colored submetallic crystalline globule, having a pale-gray streak. Soluble in nitric acid with a yellow

Scheeletine occurs at Zinnwald in Bohemia, with quartz and mica; at Bleiberg in Carinthia, accompanying molybdate of lead; in Chili, probably near Coquimbo.

WULFENITE, Haid. Molybdate of Lead. Gelb-bleierz, Worn. Yellow Lead Ore. Bleigelb, Haus. Bleimolybdat.

Dimetric: sometimes hemihedral in 1, 1i, and i = 0: 1i = 0126° 26'; a=1.574. In modified square tables and octahedrons. $\begin{array}{lll} O: 1 = & 114^{\circ} \ 12'. & 1: 1 \ (\text{bas.}) = & 131^{\circ} \ 35'. \ \frac{2}{3}i: \frac{2}{3}i \ (\text{bas.}) = & 92^{\circ} \ 43'. \\ 1: 1 \ (\text{pyr.}) = & 99^{\circ} \ 40'. & 1i: 1i \ (\text{pyr.}) = & 106^{\circ} \ 44'. \ \frac{1}{2}i: \frac{1}{2}i \ (\text{bas.}) = & 76^{\circ} \ 23'. \end{array}$



Cleavage: 1 very smooth; O and 1 much less distinct. Also

granularly massive, coarse or fine, firmly coherent.

H.=2.75-3. G.=6.3-6.9. Lustre resinous or adamantine. Color wax-yellow, passing into orange-yellow; also siskin and olive-green, yellowish-gray, grayish-white, brown. Streak white. Subtransparent—subtranslucent. Fracture subconchoidal. Brittle.

Composition.—PbMo=Molybdic acid 38.5, oxyd of lead 61.5. Analyses: 1, Göbel, (Schw. J. xxxvii, 71); 2, Melling, (Rammelsberg, 1st Supp. 59); 3, 4, Parry and J. Brown, (Proc. Phil. Soc. Glasgow, April, 1847); 5, C. Bergemann, (Pogg. lxxx, 400):

> Carinthia, Mo 40.5 Pb 59.0=99.5, Göbel. 2. 40.293 61.903=102.196, Melling. 60.35=99.65, Parry. 60.23=99.42, Brown. ** 3. 89.30 39.19 5. Zacatecas, 62.35=100, Bergemann. 37.65

A red variety contains a trace of chromic acid.

B.B. decrepitates briskly and becomes darker, and afterwards on cooling, the color disappears. On charcoal it fuses and is absorbed, leaving behind globules of metallic lead. With borax in the exterior flame, it fuses readily to a slightly colored glass; in the interior flame, the glass is transparent, but on cooling becomes all at once dark and opaque. Melts readily with salt of phosphorus, producing a green

glass, when the proportion of the mineral is small, but black and opaque, if large.

This species occurs in veins in limestone with other ores of lead, at Swarzenbach,
Bleiberg, and Windisch-Kappel in Carinthia. It is also met with at Retzbanya in
Hungary, and at Moldawa in the Bannat, where its crystals are red and have

considerable resemblance to chromate of lead.

HYDROUS PHOSPHATE OF ALUMINA AMD LIME, Damour,

Compact, of a pale or dark brick-red color. Scratches glass feebly. G .= 3-194. Composition .- Supposed by Damour to be a hydrophosphate of alumina and lime. B.B. in a tube gives considerable water; and in a platinum crucible at a red heat loses 1270 per cent. of water.

Found in rolled pebbles with the diamond sand of Bahia. L' Institut, 1853, 78.

CASTELNAUDITE, Damour, L' Institut, 1853, 78.

Trimetric? In imperfect crystals, and irregular grains. A pyramid observed, the two larger opposite faces of which meet at 96° 35′, the two smaller at 98° 20′, and adjacent faces mutually inclined 124° 23½′, Descloizeaux. Cleavage in two directions, affording a rectangular prism, but whether oblique or not, not ascertained. H. above fluor. Scratched by a steel point. Lustre greasy, adamantine. Color grayish-white to pale yellow.

Composition.—Probably a hydrous phosphate of yttria.

B.B. whitens, but infusible; with borax dissolves, and gives a colorless pearl, which becomes white and opaque in the oxydating flame; dissolves with extreme slowness in salt of phosphorus, giving a colorless globule unless the glass is saturated, when it becomes milky. Soluble in heated concentrated sulphuric acid. From the diamond sands of Bahia, Brazil.

PITTICITE, Haus. Iron Sinter. Diarsenate of Iron. Eisensinter. ter. Eisenpecherz. Gänseköthigerz. Chenocoprolite. Arsen eisenain-

Reniform and massive. H.=2-3. G.=2.2-2.5. Lustre vitreous, sometimes greasy. Color yellowish and reddish-brown, blood-red and white. Streak yellow-white. Translucent-opaque

Composition.—Analysis affords varying results. 1, Stromeyer, (Gilb. Ann. Iri. 181); 2, Laugier, (Ann. Ch. xxx, 325); 3, Kersten, (Schw. J. hiii, 176); 4, 5, Rammelsberg, (Pogg. lxii, 139); 6, ib. (5th Suppl. 102):

	Äs	B	Fe	₩n	H
1. Freiberg,	26.06	10:14	33.10	0.64	29.26=99.09, Stromeyer.
2, "	20.	14.	35	trace	80 = 99, Laugier.
3. "	30:25		40.45	-	28.50=99.20, Kersten.
4. Seiglitzstollen,	24.67	5.20	54.66	-	15:47=100, Ramm.
5.	28.45	4.36	58.00		12.59=100, Ramm
6. Schwarzenberg,	26.70	13.91	84.85		24.54=100, Ramm,

Stromeyer's analysis corresponds to Fe²Ās²+FēS̄²+30Ĥ; No. 4, gives b̄FēĀs +3FēS̄+40Ĥ, Rammelsberg; 6 gives Fe²S̄²+2FeĀs+24Ĥ, Rammelsberg. Acts before the blowpipe like scorodite.

Occurs in old mines near Freiberg and Schneeberg in Saxony, and elsewhere. An ore on Hopkins' farm near Edenville, N. Y., is referred by Beck to this species. Ganseköthigers (Chenocoprolite, or Ganomatite) has been shown to be an impure iron sinter, containing some silver and arsenate of cobalt; it is a result of decomposition, and not a distinct mineral.

position, and not a distinct mineral.

433

NITRATES.

DIADOCHITE, Breit., J. f. pr. Chem. x, 508. Phosphoreisensinter, Ramm.

Reniform or stalactitic; structure curved lamellar.

H.=3. G.=2.035. Lustre resinous, inclining to vitreous. Color yellow or yellowish-brown. Streak uncolored. Fragile; fracture conchoidal.

Composition.—Fe²P²+2FeS²+36H=Phosphoric acid 13:90, sulphuric acid 15:62, peroxyd of iron 38:94, water 31:54=100. Analyses by Plattner, (Ramm. 1st Supp. 45): P 14:811, S 15:145, Fe 39:690, H 30:344=100.

Considered by Rammelsberg as near Iron Sinter, (Pitticite), with phosphoric acid in place of arsenic acid. In a matrass yields much water. B.B. colors the flame green, intumesces and fuses on the edges to a black scoria somewhat magnetic. With the fluxes gives the reaction of iron.

From alum slate near Gräfenthal and Saalfeld in Thuringia.

3. NITRATES.

NITRE. Nitrate of Potash. Saltpetre. Kalisalpeter.

Trimetric. $I: I=118^{\circ} 50', O: 1\bar{\imath}=130^{\circ} 8'; a:b:c=1\cdot1861: 1:1\cdot692.$ 1 $\bar{\imath}:1\bar{\imath}$ (top)=109° 57', 2 $\bar{\imath}:2\bar{\imath}$ (ib.)=71° at 19° C, and 71° 44' at 100° C, B. and M. Generally in thin crusts, silky tufts, and delicate acicular crystallizations.

II.=2. G.=1.937. Lustre vitreous. Streak and color white. Subtransparent. Brittle. Taste saline and cooling.

Composition.—KN=Potash 46.6, nitric acid 53.4. Klaproth obtained for an African specimen, (Beit. i, 317), Nitrate of potash 42.55, sulphate of lime 25.54, chlorid of calcium 0.20, carbonate of lime 30.40=98.60.

Deflagrates vividly on burning coals, and detonates with combustible substances.

Dissolves easily in water; not altered by exposure.

Found generally in minute needle-form crystals, and crusts on the surface of the earth, on walls, rocks, &c. It forms abundantly in certain soils in Spain, Egypt and Persia, especially during hot weather succeeding rains. Also manufactured from soils where other nitrates (nitrate of lime or soda) form in a similar manner, and beds called nitriaries are arranged for this purpose in France, Germany, Sweden, Hungary, and other countries. Refuse animal matter, also, putrified in calcareous soils gives rise to the nitrate of lime. Old plaster, lixiviated, affords about 5 per cent. of nitre. In India it is obtained in large quantities for the arts.

In Madison county, Kentucky, it is found scattered through the loose earth, covering the bottom of a large cave. Also in other caverns in the western part of the United States.


NITRATINE, Haid. Nitrate of Soda. Soda Nitre. Soude Nitratée, H. Natron Salpeter, Leonh.


Rhombohedral. $R: R=106^{\circ} 33'$; a=0.8276. Cleavage: rhombohedral, perfect. In efflorescences; also massive, granular.

H.=1.5—2. G.=2.09—2.29; 2.290, (Tarapaca), Hayes. Lustre vitreous. Color white; also, reddish-brown, gray, and lemonH.=5.—5.5. G.=7.1—7.55. Lustre submetallic. Color dark grayish or brownish-black. Streak dark reddish-brown. Opaque. Sometimes weak magnetic.









Composition.—(Fe,Mn)W; either 2FeW+3MnW, or 4Fe W+MnW.

Analyses: 1, 2, Schaffgotsch, (Pogg. lii, 475); 8, Ebelmen, mean of two analyses.
(Ann. Ch. Phys. [3], viii, 505); 4, Kussin, (Ramm. 3d Supp. 127); 5—10, Kerak,
(J. L. pr. Chem. xlii, 81); 11, R. Schneider, (J. f. pr. Chem. xlix, 322); 12, 13, Schaffgotsch, (loc. cit.); 14, Ebelmen, mean of 5 analyses, (loc cit.); 15, Rammelsberg, (Misupp. 175); 16—19, Keradt, (loc. cit.); 20—22, R. Schneider, (loc. cit.):

J. Formula, 2FeW+8Mn W.

		G	Ŵ	Рe	Йn
1.	Zinnwald,	7·191	75-38	9-55	15·12=100, Schaffgotsch.
2.	"	7·191	75-66	9.49	14-85==100, "
8.	"		75-99	9.62	13-96, Ca 0.48=100-05, Ebelmen.
4.	46		75-92	9.38	14 04=99 84, Kussin.
5.	44	7 -22 8	76.34	9-61	14-21=100-16, Kerndt.
6.	"	7 -28 1—7 -2 2	75.62	9.55	14-85=100-02, "
7.	Lane's Mine,	7:411-7:486	75.47	9.53	14-26=99-26, "
8.	"	7-208-7-269	75-96	974	14.50==100.00, "
9.	Schlackenwald,	7.482-7.585	75.68	9.56	14-30=99-54, "
10.	Altenberg,	7.198-7.189	75.44	9.64	14-90=99-98, "
11.	Zinnwald,		76-01	9.81	18-90, Ca 1-19=100-91, R. Sehn.

II. Formula, 4FeW+Mn W.

12. Ehrenfriedersde	orf,	76-10 19-16	474=100, Schaffgotsch.
Is. Chanteloup,	7·487	76.00 18.33	5·67=100. "
14. Limoges,		76-20 19-19	4.48, Mg 0.80=100.67, Ebelmen.
15. Harzegerode,	7·148	75.56 20.17	8.54=99.27, Rammelsberg.
16. "	7-28	75·90 19·25	4.80=99.95, Kerndt.
17. Monte Video.	7.5-7.518	76-02 19-21	475=99.98, "
18. Nertschinsk,	7.5	75-64 19-55	4-81=100-00. "
19. Chanteloup,	7.48-7.51	75.88 19.32	4-84==99-99, "
20. Hartz, Glasebac	h,	76-04 19-61	4-98, Ca 0-28, Mg tr.=100-92, Sch.
21. "Pfaffenbe		76-21 18-54	5-28, " 0-40, " 0-86=100-74, "
22. " Meiseber	g,	76-25 20-27	8-96, " 0-28, " 0-15=100-91, "

Sp. gr. of the second group generally greater than that of the first.

B.B. decrepitates, and melts at a high temperature to a magnetic globule, where surface is covered with crystals, having a metallic lustre. With borax forms a green bead. With but little salt of phosphorus in the inner flame, if tin be added

2. ARAGONITE GROUP .- Trimetric. I: I=1160-1190.

Aragonite,	Ċa Ö.	Beomlite, (†Ĉa+†Ba)Ĉ
WITHERITE,	Ba Ö.	Manganocalcite, Mn C.
STRONTLANITE,	Ŝr Ō.	Cerusite, Pb C.


8. BARYTOCALCITE GROUP.—Monoclinic.

BARYTOGALGITE,


(10a+1Ba)0.

CALCITE. Calcareous Spar. Carbonate of Lime. Marl, Agaric Mineral, Anthraconite, Aphrite, Argentine, Chalk, Inolite, Marble, Oolite, Ostroccolla, Peastone, Slate Spar, Travertine, Tufa. Kalkspath. Kohlensäurer Kalk. Chaux carbonatée, Prunnerite. Strontiano-calcite, Genth.

Rhombohedral. $R: R=105^{\circ}5', O: R=135^{\circ}28'; a=0.8543.$



The secondary planes or forms include thirty-six different rhom bohedrons, seventy-nine scalenohedrons, seven pyramids, and four



Observed Planes: Add (!) is, if, it.

Twins: face of composition %. Cleavage: ii and ii, the former most distinct. Occurs also rarely massive.

H.=6. G.=5.4—6.4; 5.469—5.85, Connecticut; 5.7—6.39, Bavarian. Lustre submetallic; a little shining. Color iron-black, brownish-black, grayish-black; often iridescent. Streak dark red to black. Opaque. Fracture subconchoidal, uneven. Brittle.

Composition.—Essentially protoxyd of iron and of manganese with columbic acid=:(Fe, Mn)*Cb*. Analyses: 1, Wollaston; 2, Schlieper, (Pogg. lxiii, 317); 3, 4, 5, 6, H. Rose, (ib.); 7, Avdejev, (ib.); 8, Jacobson, (ib.); 9, Hermann, (J. f. pr. Chem. xxxviii, 121); 10, Bromeis, (Pogg. lxxi, 157); 11, 12, Damour, (Comptes Rend. xxviii, 353); 13, Hermann, (J. f. pr. Chem., xliv, 207); 14, T. S. Hunt, (Am. J. Sci., [2], xiv, 340); 15, H. Müller, (J. f. pr. Ch. lviii, 183):

		G.	Съ	Гe	Йn	S n	Ċu			
1.	Connecticut,		80.	15.	5.					llaston.
2.	Middletown,	5.469-5.495	78.83	16.66	471					Nio-22=101 -23
8.	"	5.708	79.62	16.87	4.44	0.47	0.06,	Ca tr		=100.96, Rose.
4.	Bodenmais,	6.39	81 07	14.80	3.85	0.45	0.18,			=98·80, Ross.
5.	"		81.34	18.89	877	0.19	0.10,			==99-29, Ross.
6.	"	57	79.68	15.10	4.65	0.13	0.12,	"	"	=99.67, Ross.
7.	" .	6.02—6.08	80.64	15.33	4.65	0.1	10	"	0.51	=100 93, Avd
8.	"	5.976								Jacobson.
9.	Ilmen Mts.	5·43— 5·78	80.47	8.20	6.09,	Ý 2·0	Mg 2	44, C	J 0.1	50=100, Herm.
10.	"	5.461								0.56, Cu trace=
11.	Limoges,	5·65·727	78.44	14.96	6.52=	=99.9	2, Dan	our.	[1	100.17, Bromeis
12.	"	"					55, Da			
18.	Middletown,	5.8	78.22	14.06	5.63,	Mg 0	·49, Sn	0.4,	w (.26=99·06,Ha
14.	Haddam,	5.85	80.60	15.57	8.25,	Cu 0	·50, Sn	tr.=	=99	92, Hunt.
15.	Tirschenreuth	,	73.6	25.1	5.2, }	n 07	=104	6, M i	ülle	r.

a Includes Yttria.

Damour finds in a Limoges variety 78.74 columbic acid, Fe 14.50, Mn 7.17=100.41 (Ann. des M. [4], xiv, 423). The yttria and uranium of the Ilmen columbite, Hermann attributes to a mixture with Samarskite.

Specimens of the highest specific gravity at Bodenmais, give a black powder, and others of less gravity a dark reddish brown. The Limoges specimens (analysis 11, 12) resemble those of Bavaria, in streak; and Damour has proposed for this variety the name Baierine; but Rose has shown that the metal pelopium, supposed to distinguish the variety, is identical with Columbium, (Rose's niobium).

Wollaston's analysis was made on four grains of the original specimen in the British Museum, sent out from Connecticut by Governor Winthrop to Sir Hams Sloane.

B.B. alone, on charcoal, infusible. With borax, in powder, fusion takes place slowly but perfectly, forming a blackish-green glass.

Columbite of Bodenmais, in Bavaria, on the Rabenstein, near Zwiesel, occur in granite. In the United States it occurs both in feldspathic and albitic granite. The occurrence of columbite in America was first made known by Mr. Hatchett's

The occurrence of columbite in America was first made known by Mr. Hatchett's examination of a specimen, sent by Governor Winthrop to Sir Hans Sloane, then President of the Royal Society, which was labeled as found at Neatneague. Dr. S.

ANGLES OF RHOMBOHEDRONS:

R is a face of the fundamental rhombohedron 1R; R' the particular rhombohedron below in each line; O the basal plane:

	Term. Edge.	O:R	R:R'	Term. Edge	O:R	R:R'
	0 1	0 ,	0 /	0 ,	• ,	0 /
1	156 2	166 9	149 14	- y 71 18	110 14	114 23
4	142 55	158 28	156 55	$-\frac{5}{2}$ 73 15	112 5	112 32
Į.	134 57	153 45	161 48	-12 74 9	112 56	111 41
T	129 40	150 35	164 48	- 9 76 9	116 16	110 21
i <i>R</i>	105 5	135 23	180	-2 (f. C) 78 51	116 52	107 45
Ŧ	82 56	120 5	164 42	$-\frac{1.3}{8}$ 85 26	121 58	102 39
Ĭ	73 15	112 5	156 42	-₩ 86 36	122 49	101 58
3	69 24	108 40	153 7	-3 88 18	124 6	100 2
1,3	68 25	107 20	151 57	$-\frac{7}{3}$ 90 55	125 58	98 39
4 (f. 57	3E) 65 50	104 17	148 54	$-\frac{5}{4}$ (f. D) 95 28	129 2	95 35
1.7°*	65 6	103 24	148 1	$-\frac{6}{3}$ 97 10	130 11	94 48
2	64 42	102 42	147 19	$-\frac{8}{7}$ 99 14	131 35	9 3 2
13 (f. F	7) 60 36	94 27	139 4	-1 111 13	139 12	85 25
16`	60 20	93 38	138 15	$-\frac{1}{5}$ 115 7	141 48	82 54
-11	60 50	95 19	129 18	$-\frac{2}{3}$ 123 10	146 40	. 77 57
-8	61 33	97 48	127 25	$-\frac{3}{4}$ 127 39	149 23	75 14
-5	63 51	101 28	123 9	$-\frac{1}{2}$ (f. B) 134 57	153 45	70 52
-4	65 50	104 17	120 20	$-\frac{1}{4}$ 156 2	166 9	58 3 8
-7	67 26	106 9	118 28	$-\frac{1}{8}$ 160 42	168 50	55 47


ANGLES OF SCALENOHEDRONS:

I	onge	er E.	Short	er E.	Mid.	E.	l	Long	er E.	Short	er E.	Mid.	E.
	•	,	•	,	0	,		•	,	0	,	0	,
107 113	154	37	145	55	61	36	15	134	28	109	1	150	44
Įŭ	130	16	121	14	131	19	1 3	132	41	110	3	154	5
1 ³ (f. 577)	159	24	138	5	64	54	17	130	10	111	39	158	53
į ⁵ `	146	10	128	15	93	20	19	127	50	113	21	163	30
į,	164	1	130	37	67	41	111	126	26	114	24	166	28
3 3	152	40	123	35	90	20	1"	125	47	114	50	167	35
13	166	57	125	53	69	16	1 ¹³	125	30	115	12	168	32
42	169	5	122	37	69	45	<u>5</u> 13	165	59	95	27	105	24
	170	29	120	14	71	5	77	170	0	91	34	103	21
1 67	172	30	116	59	72	1	<u>1</u> 3	142	53	100	55	145	28
i	171	43	102	55	88	16	23	142	30	99	58	149	21
17	168	1	102	21	94	1	Ļ۴°	153	2	91	12	137	48
13	165	33	102	6	97	57	4°	152	54	90	46	139	12
15	161	53	101	55	103	52	85 4	146	31	95	12	147	38
1,	160	13	101	56	106	34	38	143	50	97	28	151	51
1:	159	17	101	57	108	7	43	162	23	80	10	133	19
1*	155	50	102	11	1/13	45	42	152	29	88	57	144	29
11	15 l	7	102	52	121	34	43	141	51	98	40	155	39
13(f.574A)	144	24	104	38	132	58	Y 11 9	157	14	83	55	140	40
113	136		107	48	146	28	10% ?	134	3	66	44	125	4

[•] From Rossie Crystals, St. Lawrence Co., N. Y.

MENGITE, G. Rose. Ilmenite, Brooke, Phil. Mag. x, 1831.

Trimetric. $I: I=100^{\circ} 28', O: 1i=133^{\circ} 42'; a:b:c=1.0463: 1:1.2071.$



 $O: 1\S = 136^{\circ} 50', \quad i\S: i\S(adj.) = 136^{\circ} 20'.$ $I: i=140^{\circ} 14'. \quad 1\S: 1\S(mac.) = 151^{\circ} 26'.$ $i: i\S = 111^{\circ} 50'. \quad 1\S: 1\S(brac.) = 101^{\circ} 10'.$

Occurs in short prisms often terminated by four-sided pyramids. No distinct cleavage.


H.=5—5.5. G.=5.48. Lustre submetallic, splendent, of surface of fracture subvitreous. Color iron-black. Streak chestnut-brown. Fracture uneven.

Composition.—Contains, according to G. Rose, (Reise, n. d. Ural. ii, 1842, 83). Zirconia, peroxyd of iron, and titanic acid. B.B. infusible, but becomes magnetic. With salt of phosphorus, in the outer flame, gives a greenish yellow clear glass; in the inner, a yellowish red, which is deepened by adding tin. With soda a manganese reaction.

Occurs in granite veins in the Ilmen mountains. The crystals are imbedded is albite, and the largest are but two or three lines long.

Brooke's name *Ilmenite* being preoccupied, was changed by Rose to Mengite. The mengite of Brooke is monazite.

POLYMIGNYTE, Berzelius, K. V. Ac. H. 1824, p. 838.



Cleavage: \tilde{u} and O in traces. Crystals generally slender and thin, and striated longitudinally.

H.=6.5. G.=4.77—4.85. Lustre submetallic, but brilliant. Color black. Streak dark brown. Opaque. Fracture perfect conchoidal, presenting, like the surface, a brilliancy almost metallic.

Composition.—Analysis by Berzelius, (K. V. Ac. H. 1824, ii, 839),

Ti 46·30, Zr 14·14, Fe 12·20, Ca 4·20, Mn 2·70, €e 5·00, Y 11·50=96·04, with a trace of potent regression silice and over of tip.

with a trace of potash, magnesia, silica, and oxyd of tin.

B.B. alone unchanged. With borax yields easily a glass colored by iron; with tin the bead becomes reddish, inclining to yellow. Not easily dissolved by salt of phosphorus to a glass, which is reddish in the reducing flame.

phosphorus to a glass, which is reddish in the reducing flame.

Occurs at Fredericksvärn in Norway, imbedded in feldspar and zircon syenite.

Its crystals sometimes exceed an inch in length. It has been reported by Prof. C.

U. Shepard as occurring at Beverly, Mass.

a loose friable variety, deposited from waters containing carbonate of lime in solution; it is found about lakes whose waters are impregnated with lime; also in fissures in limestone and in limestone caverns; it is called calcarcous tufa, if so hard as not to be friable. Prunnerite is grayish violet, from Faroe. Marble includes all the imperfectly crystalline and earthy varieties which admit of a high polish. The Stinkstone, Swinestone, or Anthraconite, which is found columnar, granular, and compact, of various shades, emits a fetid odor when struck with a hammer. Stalactites are pendant masses of limestone, formed in limestone caverns by the percolation of water, holding lime in solution, through their rocky roofs; the water which drops to the floor from the roof also evaporates, and forms a layer of limestone over the floor, which is called Stalagmite; and both stalactites and stalagmites when polished are often called Alabaster in France. Argentine possesses a silvery-white lustre, a slaty structure, and contains a little silica. Slate spar and aphrite are similar varieties. Marl is a mixture of clay and carbonate of lime. The Fontainbleau Limestone is an aggregate of secondary rhombohedrons, containing, mechanically mingled, a large proportion of sand. A similar variety is found on the African coast between Saudanha Bay and Ichaboe Island, in great quan-

tities in the sand; they contain fifteen to twenty per cent. of sand.

Strontianocalcite of Genth., (Proc. Ac. Phil. vi, 114), is opaque, white, and crystallizes like calcite; form uneven, globular, the globules terminating in acute rhombohedrons, (4R, 65° 50'), H .= 3.5. A crimson flame before the blowpipe and

affords some strontia.

Granular limestone includes common statuary and architectural marble, having a texture something like loaf sugar. Compact limestone has a compact texture,

usually an even surface of fracture, and dull shades of color.

Hydraulic limestone is an impure limestone. The French varieties contain two or three per cent. of magnesia, and ten to twenty of silica and alumina, (or clay). The varieties in the United States contain twenty to forty per cent. of magnesia, and twelve to thirty per cent. of silica and alumina. A variety worked extensively at Rondout, N. Y., afforded Professor Beck (Min. N. Y., p. 78) Carbonic acid 34 20, lime 25:50, magnesia 12:35, silica 15:37, alumina 9:13, peroxyd of iron 2:25. Oxyd

of iron is rather prejudicial to it than otherwise.

The Cipolin marbles of Italy are white with shadings or zones of green tale. The Bardiglio is a gray marble having a whitish basis with crowded dark cloudings; from Corsica. The Sienna is yellow with cloudings, and Brocatello di Sienna has clouds of bluish red or purplish shades. Portor is a Genoese marble of deep black color with veinings of yellow; the best is from Porto-Venese. Bird s-eye marble is a compact limestone with crystalline points disseminated through it. Ruin marble is yellowish with brown shadings or lines representing castles, towers, and cities in ruins; the markings are due to infiltrated oxyd of iron or manganese. Shell marble contains scattered fossil shells; crinoidal or encrinital includes joints of encrinites of a disk-shape; madreporic marble is made up of fossil corals, and bas a stellate surface when polished. Fire marble or lumachelle is a dark brown shell marble, having brilliant fire or chatoyant reflections from within. Languedoc marble is of a light red color, with lighter spots due to corals. The marble of Sarancolin in the Pyrenees is deep red mixed with gray and yellow, and some transparent spots. Alabaster has been brought largely from Chili and Algiers.

Marl contains often forty to fifty per cent. of lime.

This species, in some form, is very generally diffused. England and France contain extensive strata of chalk. Italy, from her Carrara beds, and Greece, from the Pentelican quarries, have provided the world with statuary marble. The greater part of the middle and western sections of the United States are underlaid with strata of limestone, and white or granular limestone occurs in various portions of the Eastern States.

Andreasberg in the Hartz is one of the best European localities of crystallized calcite; there are other localities in the Tyrol, Styria, Carinthia, Hungary, Saxony, Hesse Darmstadt (at Auerbach), Hesse Cassel, Norway, France, and in England in Derbyshire, Cumberland, Cornwall, Scotland; in Iceland. In Iceland a single rhombuhedron (R) over six yards long and three high has been observed.

The most interesting localities of calcite in the United States, both as regards

size of crystals and form, exist in St. Lawrence and Jefferson Counties, N. Y., especially at the Rossie lead mine; the crystals are highly modified, (f.575, $\frac{4}{7}$: (o'), i (a), $\frac{17}{4}$ (a"), $\frac{85}{32}$ (o"), 1^{3} (e), and are often transparent even when large; one gigantic

EUXENITE, Scheerer, Pogg. 1, 149, and luxii, 561.

Trimetric? Form a rectangular prism (ii, ii) with lateral edges replaced by I, and a pyramid at summit, also with two domes, one parallel to each diagonal; I:I about 120° , $i:I=150^{\circ}$, angle (mac.) of pyramid 100° , $i:I=150^{\circ}$, angle (mac.) of pyramid 100° , $i:I=150^{\circ}$, $i:I=150^{\circ}$, $i:I=150^{\circ}$, angles may be in error several degrees, R. P. Greg. Commonly massive, without any traces of cleavage.

G.=4.6—1.76. Lustre metallic, greasy. brownish-black; in thin splinters a reddish-brown translucence lighter than the streak. Streak-powder reddish brown. Fracture subconchoidal.

Composition .- Analyses by Scheerer, (loc. cit.):

								Jölst	er. G.	-440, 1	voicestrand, G413-416
Titanie and m	etalli	e aci	ds,		-		-		-	57-60	58-64
Yttria,	-			•		-		-		25-09	28-97
Protox. uraniu	m		-		-		-			6.34	7.58
Protox. ceriun		lantl	anı	um,		-		-		8.14	2-91
Protox. iron,	-		-	,	-		-		-		2.60
Lime.				-		-				2.47	
Magnesia,	-		-		-		-		-	0.29	
Water,	•	•		-		-		-		8-97	4-0499-74

* Protoxyd of cerium 2-18; ib. lanthanum 0-96.

Scheerer has ascertained'that the mineral contains columbic acid in place of tantalic The Jölster euxenite contains the most titanic acid; yet Scheerer does not doubt

the identity of the two minerals.

B.B. infusible. With borax in the oxydation flame becomes yellow or brownish. yellow, and the same after cooling; by flaming, forms a yellowish enamel; color but little changed in the reduction flame. With salt of phosphorus dissolves in the oxydation flame, forming a yellow pearl, which on cooling becomes colorless.

Euxenite comes from Jölster in Norway, where it was obtained by Prof. Keilhau:

also near Tvedenstrand. Named by Scheerer from cofcros, a stranger, in allusion to the rarity of its occurrence.

RUTHERFORDITE, Shepard, Amer. Assoc. iv, 811, Am. J. Sci. [2], xii, 209.

In crystals and grains, without cleavage. Monoclinic, with $I: I=93^{\circ}$, according to Shepard.

II.=5.5, Hunt. G.=5.58-5.69, Shepard, 5.55, Hunt. Lustre of fracture shining vitreo-resinous, and color blackish-brown: opaque, but thin fragments translucent and smoky orange-brown by transmitted light. Streak and powder yellowish-brown, near fawn-color. Fracture conchoidal. Brittle.

Composition.—According to Shepard contains titanic acid, oxyd of cerium and possibly oxyd of uranium and yttria; according to some unfiniahed trials by T. S. Hunt, (Am. J. Sci. [2], xiv, 344), it contains probably 58.5 per cent. or more of titanic acid, with 10 per cent. of lime, with other ingredients undetermined.

Occurs at the gold mines of Rutherford Co., North Carolina, along with rutile.

brookite, zircon, and monazite.

by carbonated waters, and silicate of zinc replacing it, or by incrustation of the calcite before its removal by carbonic acid or otherwise; to Malachite through a solution of sulphate of copper, which forms carbonate of copper and sulphate of lime; to Gypsum or Anhydrite through the action of sulphuric acid, which acid is produced by the oxydation of sulphuretted hydrogen or otherwise, thus forming sulphate of lime; to Quartz by waters containing alkaline silicates, which afford free silica; to Fluor, Limonite, and other species, by the removal of the CaC by waters which hold carbonic acid or alkaline silicates, and at the same time contain the ingredients forming the replacing mineral. Limonite or Red Iron Ore might result from the decomposition of pyrites in the vicinity.

MAGNESITE. Carbonate of Magnesia. Baudisserite. Brounnerite. Rhomb Spar... Giobertite, Beudant. Talkspath, Hartmann.

Rhombohedral. $R: R=107^{\circ} 29', O: R=136^{\circ} 56'; a=0.8095$. Cleavage: rhombohedral, perfect. Also massive; granular, or fibrous, and sometimes in radiating groups; also very compact.

H.=3.5-4.5. G.=2.8-3. Lustre vitreous; fibrous varieties sometimes silky. Color white, yellowish or grayish-white, brown.

Transparent-opaque. Fracture flat conchoidal.

Composition.—MgC=Magnesia 47 6, carbonic acid 52 4. Analyses: 1, 2, Stromeyer, (Untersuch. 119); 3, Rammelsberg, (Handw. 397); 4, 5, Scheerer, (Nyt. Mag. f. Nat. iv, 342, and Pogg. lxxx, 313):

47.89 0.28=100.00, Str. 51.83 -1. Salem. 2. Baumgarten, Giobertite, 48.36 50.22 1.39 Mn 0.21=99.18, Str. 48·004 51·996 —— 46·93 52·57 —— =100.00, Ramm. Fe 0.87=100.37, Scheer. 3. Frankenstein, 4. Arendal, G .= 3.068, 47.296 51.447 0.470 Fe 0.786=100, Scheerer.

Guyton Morveau found fourteen per cent. of silica in the magnesite of Castellamonte. T. S. Hunt found in the magnesite of Sutton, C. E., Mg C 83.35, Fe C 9.02, mixed silica 8.03=100.40, (Logan's Rep. Canada, 1848, 88). Other analyses, Brunner, (Pogg. lxv, 292); C. v. Hauer, (Jahrb. der k. k. Reichs. iii, 154, Lieb. and K. Jahres.

Dissolves slowly, with little effervescence, in nitric or dilute sulphuric acid. Infusible before the blowpipe.

Magnesite is found with serpentine and other magnesian rocks. It occurs at Hrubschitz in Moravia, at the Gulsen mountains in Styria, at Baumgarten in Silesia, at Baudissero in Piedmont, and at Valecas in Spain. In the United States at Bolton, Mass., in indistinctly fibrous masses, traversing white limestone; at Lynnfield, Mass. coating serpentine; at Barchills, near Baltimore, Md.; in Pennsylvania, in crystals at West Goshen, Chester Co., and near Texas, Lancaster Co.; in talcose slate, in Sutton and Bolton, Canada East; in Canton Upata, Venezuela, near Mission Pastora, looking like porcelain in the fracture, as observed by N. S. Manross.

DOLOMITE. Bitter Spar. Pearl Spar. Magnesian Limestone. Gurhofite, Gur-hofian. Brown Spar. Bitterkalk, Bitterspath, Braunspath, Rautenspath. Miemite. Conite. Tharandite. Ankerite.

Rhombohedral. $R: R=106^{\circ} 15', O: R=$ 584 136° $8\frac{1}{2}$; a=0.8322. Observed planes: O, R, 4, -2, $-\frac{1}{2}$, i2, 1, 1, 0 (hemihedral). $0:i2=90^{\circ}$, $0:4=104^{\circ}$ 35′, $0:2=117^{\circ}$ 29′, $0:\frac{1}{2}=154^{\circ}$ 20′, $\frac{1}{2}:\frac{1}{2}=135^{\circ}$ 57′, $2:2=79^{\circ}$ 36′. R:0 R varies between 106° 10' and 106° 20'. R varies between 106° 10' and 106° 20'. An increase of 100° C diminishes the angle 4'. Cleavage: R perfect. Monoelinie, $C=75^{\circ}$ 1'; $I: I=93^{\circ}$ 44', $O: 1i=137^{\circ}$ 31'; a:b: c=9.9773: 1: 1.944.

0:1=131° 45'. 0:2i=115° 35'. 1:1=118° 58'.

 $0: I=95^{\circ} 43'$. $i2: i2=129^{\circ} 45'$. $-1: -1=107^{\circ} 54'$. $0: ii=101^{\circ} 59'$. $i2: i2=123^{\circ} 50'$. $-22: -22=131^{\circ} 38$.

Cleavage: I tolerably distinct; O and ii less so. Surface I streaked longitudinally; the faces mostly smooth and shining. Also imperfectly columnar and granular.


H.=2.5—3. G.=5.9—6.1. Lustre adamantine—vitreous. Color various shades of bright hyacinth-red. Streak orange-yellow. Translucent. Sectile.

Composition.—Pb Cr=Dxyd of lead 657, chromic acid 312. Analyses: 1, Pfd. (Schw. J. xviii, 72); 2, Berzelius, ib. xxii, 54):

Blackens in the blowpipe flame, and decrepitates if quickly heated, but may be fused to a shining slag, containing globules of lead. It undergoes a partial reduction in glass of borax, at the same time coloring it green. Dissolves with effervenence in nitric acid, and produces a yellow solution. With soda yields easily metallic lead.

Occurs at Nischne Tagilsk in the Ural, and in narrow veins, traversing decomposed gneiss, and associated with gold, pyrites, galena, quartz, and vauquelinite; in Brazil, at Congonhas do Campo, in fine crystals in decomposed granite; at Retbanya in Hungary, at the mine of St. Anthony; at Moldawa in the Bannat; at Luzon, one of the Philippine Islands.

VAUQUELINITE. Chromate of Lead and Copper, Phil.



Monoclinic. Crystals usually minute. irregularly aggregated. Twins: annexed figure; face of composition a plane on the acute solid angle: O:O (of the two individuals)=134° 30′; O:ii=149° nearly. Also reniform or botryoidal, and granular; amorphous.

II.=2.5—3. G.=5.5—5.78. Lustre adamantine to resinous, often faint. Color dark-green to brown, sometimes nearly black. Streak siskin-green or brownish. Faintly translucent—opaque. Fracture uneven. Rather brittle.

Composition.—Cu²Cr²+2Pb²Cr²=(Cu, Pb)²Cr²=Oxyd of lead 61·2, oxyd of copper 10·9, chromic acid 27·9. Analysis by Berzelius, (Afhandl. vi, 246):

Pb 60 87, Cu 10·80, Cr 28·38=100.

B.B. on charcoal slightly intumesces and fuses to a gray submetallic globule, yielding at the same time, small beads of lead. With borax or salt of phospherus affords a green transparent glass in the outer flame, which in the inner after cooling is red to black, according to the amount of mineral in the assay; the red color is mone distinct with tin. Partly soluble in nitric acid.

Occurs with crocoisite at Beresof in Siberia, generally in mammillated or amorphous masses, or thin crusts; also at Pont Gibaud in the Puy de Dome; and with the crocoisite of Brazil.

At the lead mine near Sing Sing, it has been found by Dr. Torrey in green and brownish-green mammillary concretions, and also nearly pulverulent.

```
No. 23, (Ankerite), gives the formula CaC+($\frac{1}{2}$ [Fe, Mn]+$\frac{3}{2}$ Mg) C. No. 24, """ CaC+($\frac{1}{2}$ Fe+$\frac{1}{2}$ Mg) C. No. 25, """ CaC+(Mg, Fe) C. No. 27, """ CaC+(Mg, Fe, Mn), C.
```

A reddish bitter spar from Przibram afforded Gibbs (Pogg. lxxi, 564) 4 to 5 per cent. of oxyd of cobalt, as follows:

```
1. C 45·12 Ca 31·72 Mg 16·63 Co 5·17 Fe 1·36=100,
2. 45·37 31·86 17·37 4·34 1·16=100.
```

affording the formula CaC+(Mg, Fe, Co) C. G.=2-921.

Soluble in the acids, but more slowly than calcite. B.B. acts like calcite; some varieties darken and increase in hardness.

The name Dolomite is applied to white crystals, and to the granular varieties. Pearl-spar includes rhombohedral crystallizations with curved faces and a pearly lustre. When the crystals are not curved, and have a brown or reddish-brown color, they are called Brown spar: this variety contains 5 to 10 per cent. of oxyd of iron or oxyd of manganese. Ankerite contains still more iron; R: R=106° 12′. Gur-kofan is a compact snow-white subtranslucent variety, so named from a locality of it at Gurhof, in Lower Austria. The Traversella dolomite (anal. 28) has been called Brossite: R=106° 20′.

Granular dolomite constitutes extensive beds in various regions. Crystalline and compact varieties are often associated with serpentine and other magnesian rocks. Pearl spar occurs in geodes in compact limestones and other stratified rocks. Rhomb spar is found in Salzburg, the Tyrol, and at Miemo in Tuscany, whence the name Miemite was derived. Brown spar and Pearl spar are obtained at Schemnitz in Hungary, Kapnik in Transylvania, at Freiberg in Saxony, in the lead mines at Alston in Derbyshire, and at other places in Devonshire. The Ankerite is from Styria and elsewhere.

Roxbury, Vt., affords large yellow transparent crystals of the rhomb spar variety imbedded in talc. A coarse cleavable variety occasionally presenting perfect crystals is associated with white talc in calc spar, at Smithfield, R. I. White hexagonal crystals (f. 584) occur at Hoboken, N. J. The pearl spar variety is abundant in geodes at Lockport, Niagara Falls, and Rochester, N. Y., accompanying calc spar, celestine, and gypsum; also at Glen's Falls. Massive dolomite forms extensive beds in Litchfield Co., Conn., in the southwestern towns of Massachusetts, in Vermont, in various parts of New York, Pennsylvania, New Jersey, Maryland, &c. Crystallized dolomite occurs in rhombohedrons at the quarantine, Richmond Co., N. Y., and at Hoboken, N. J. Brown spar occurs at Warwick, N. Y. and at the Parish ore bed, St. Lawrence County, N. Y. A variety resembling Gurhofite is found on Hustis's farm, Phillipstown, N. Y. It has a semi-opaline appearance, and a fracture nearly like porcelain.

Dolomite is generally supposed to be injurious as a manure for soils, on account of its magnesia; but this is not so, unless used after calcination, before it is fully airslaked. The lime it affords when burnt, makes a more durable cement than common limestone. The rock is generally less firm or more friable than pure granular limestone, and therefore not as good for building stone. This species was named in honor of Dolomieu.

ALTERED FORMS.—Dolomite occurs altered to Spathic Iron, Calamine, Steatite, Limonite, Red Iron Ore, Göthite, Pyrolusite, and Quartz, and by processes similar to those explained under Calcite:

BREUNNERITE, Haid. Bitter Spar and Brown Spar, in part. Mesitine Spar. Talkspath. Magnesitspath. Mesitinspath. Pistomesite.

Rhombohedral. $R: R=107^{\circ}23', O: R=136^{\circ}52'; a=0.81135.$ Observed planes: $R, -\frac{1}{2}$. $\frac{1}{2}: \frac{1}{2}=136^{\circ}54'$. Cleavage: rhombohedral, perfect. Crystals often imbedded. Also massive, granular, and fibrous.

H.=4-4.5. G.=3-3.63. Colorless, whitish, yellowish, often brown on exposure. Transparent to subtranslucent. Brittle.

Composition.—(Mg, Fe, Mn) C. MgC+FeC=Carbonate of magnesia 42.0, carbonate of iron 58.0. Analyses: 1, 2, Stromeyer, (Gött. gel. Anz. 1827, and Schw. J. ii); 3, Brooke (Ann. Phil. N. Ser. v, 382): 4, 5, Stromeyer, (loc. cit.); 6, Fritzsche (Pogg. lxx, 146); 7, Stromeyer; 8, Fritzsche, (loc. cit.); 9, Gibbs, (Pogg. lxxi, 566); 10, v. Hauer, (Jahrb. k. k. geol. Reichsanst. iii, 1852, 154):

			MgO	FeO	MnC
1.	Hall, Tyrol,	10:1	89.70	8.02	2.44 C 0.11=100.27, Stromeyer.
2.	St. Gothard,	10:1	87.78	10.54	0-90=99-22, Stromeyer.
3.	Tyrol,	8:1	86.05	13.15	=99.20, Brooke.
4.	Zillerthal,	8:1	84.79	13.82	0.69=99.30, Stromeyer.
5.	Fassathal,	6:1	82.89	16.97	0.78=100.64, "
6.	Pistomesite, G=341	5, 1:1	44.98	55.27	-==100.23, Fritzsche.
7.	Mesitine, Piedmont,	1:1	4272	57.24	- 99.96, with some MnC, Strong
8.	*	2:1	58.68	39.38	CaC 2:30=100:36, Fritzseba
9.	" Piedmont,	2:1	56.14	43.36	— ČaČ 0-29=99-89, Gibbs.
10,	Semmering, white,	10:1	89.22	5.10	CaC 3.89, Si 1.29, v. Hauer.

In the above the proportion of the magnesian carbonate to the rest, is given in the first column. Other analyses by A. Patera, (Fr. d. Nat. ii, 227 and 227, R: h= 107° 20'), Völkel, (v. Leonh. 1849, 701); Joy, (Rammelsberg's 5th suppl., 161). The mesitine spar occurs in lenticular forms, and the first five above in the primary rhombohedron with the faces not curved.

B.B. gives an iron-reaction, becoming black, and sometimes magnetic. Disselves


very slowly in muriatic acid, when pulverized.

Occurs in chlorite slate at St. Gothard; also at the Zillerthal, and at Hall and elsewhere in the Tyrol. The mesitine is from Traversella in Piedmont. Include much of the so-called brown spar.

CHALYBITE, Gl. Spathic Iron. Carbonate of Iron. Sparry Iron. Siderite, Beil.
Siderose, Beud. Brown Spar. Stahlstein. Sphærosiderite. Clay Iron Stone.
Eisenspath and Spatheisenstein. Junkerite, Dufrénoy. Oligonspath.

Rhombohedral. $R: R=107^{\circ}, O: R=136^{\circ} 37'; a=0.81715.$ Observed planes: rhombohedral 1, 4, -5, -2, $-\frac{1}{2}$; scalenohedral 1'; pyramidal $\frac{4}{3}$ 2; prismatic I, i2; and basal O. The faces often curved, as below.

$$O: 2=117^{\circ} 53'$$
. $\frac{1}{2}: \frac{1}{2}=136^{\circ} 34'$. $4: 4=66^{\circ} 18'$. $O: \frac{4}{3}2=132^{\circ} 30'$. $i: R=133^{\circ} 23'$. $i2: 1^3=155^{\circ} 45'$.





586

Cleavage: rhombohedral, perfect. Twins: plane of composition -1. Also in botryoidal and globular forms, (spharosiderite), occasionally in silky fibrous masses; often cleavable massive with

cleavage planes undulate; also coarse or fine granular.

H.=3.5-4.5. G.=3.7-3.9. Lustre vitreous—pearly. Streak white. Color ash-gray, yellowish-gray, greenish-gray, also brown, and brownish-red, rarely green; and sometimes white. Translucent-subtranslucent. Fracture uneven. Brittle.

Composition .- FeC=Carbonic acid 37.93, and protoxyd of iron 62.07. But often

Composition.—FeC—Carbonic acid 37 vs, and protoxyd of from 6207. But often containing some oxyd of manganese, magnesia, and also lime, or equivalent to (Fe, Mn, Ca, Mg,) C.
Analyses: 1—6, Karsten, (Karst. Arch. ix, 220); 7, Stromeyer, (Untersuch.); 8, 9, 10, Berthier, (Ann. d. Mines, viii, 887); 11, Thomson, (Min. i, 445); 12, Magnus, (Pogg. x, 145); 13, Klaproth, (Beit. vi, 315); 14, Stromeyer, (Untersuch.); 15, Schnabel, (Ramm. 3d Supp. 112):

			Ö	Ėе	Mn	Mg	Ča	
	1.	Babkowsky, black,	36.61	57.91	1.51	trace	0.59	gangue 0.60=97.22, K.
	2.	Styria, white,	34.62	50.23	2.54	1.60	0.83	" 9.78=99.55, K.
	3.	Hackenburgh, white,	38.64	50.41	7:51	2.35	-	" 0.32=99.23, K.
	4.	Siegen, yellowish,	38.90	50.72	7.64	1.48	0.40	" 0.48=99.62, K.
	5.	" "	88.85	47.20	8:34	3.75	0.63	" 0.95=99.72, K.
	6.	Müsen, white,	39.19	47.96	9.50	3.12		=99.77, Karsten.
		Stolberg,	38.22	48.20	7.07	1.84		H 0.25=96.25, Stromeyer.
	8.	Allevard, Isère,	41.8	42.8	-	15.4	-	=100, Berthier.
		Autun,	40.4	45.2	0.6	12.2		=98.4, Berthier.
		Vizelle, Isère,	42.6	43.6	1.0	12.8		=100, Berthier.
		Durham, Eng.,	35:90	54.57	1.15			Aq. 2.63=97.43, Thomson.
1	12.	Ehrenfried. Oligon,	38.35	36 81	25.31	-	-=	=100.47, Magnus.
	13.	THE RESERVE AND ADDRESS OF THE PARTY.	34.00	-	0.75			=98.75, Klaproth.
	14.	4 4	-	59.63	1.89			=99.91, Stromeyer.
	15.	Siegen,	38-22	43.59	17.87	0.24	0.08=	=100, Schnabel.

a With some water.

Of the above, Nos. 9 and 10, from Autun and Vizelle, correspond to the formula 2 Fe Č+Mg Č; that from Ehrenfriedersdorf, No. 12, (called Oligon Spar by Breithaupt), 2 Mn Č+3 Fe Č; that from Stolberg, (No 7)=4Fe Č+Mn Č.

A green variety from Altenberg afforded F. Monheim, (J. f. pr. Chem. xlix, 318), Fe Č 64.04, Mn Č 16.56, Ča Č 20.22, Ši 1.10=101.92, corresponding to 8 Fe Č+2 Mn Č+3Ča Č; it resembles the calamine called Kapnite.

In a brownish-black crystallized spathic iron from Wolch, Rosengarten found,

(Ramm. 3d Supp. 112):

Fe 11.30, Fe 43.83, Mn 7.31, Mg 2.44=100. C with H 35.12.

The spathic iron of Plymouth, Vt., according to T. G. Clemson, (Am. J. Sci. xxiv, 170), and another from Neudorf, according to Peischel, (Ramm. 1st Supp. 139), contained

FeÖ 74-28 Mg Ö 16-40 Mn Ö 6-56 Fe 0-30 undec. 1-40=98-94, Clemson.
79-34 Ca Ö 5-43=101-06, Peischel.

B.B. blackens, giving off carbonic acid, and ultimately an oxyd of iron is obtained, which is attractable by the magnet. Alone infusible. Colors borax green; dissolves with difficulty in nitric acid, and scarcely effervesces, unless previously pulverized. Exposure to the atmosphere darkens its color, rendering it often of a blackish-brown, or brownish-red color.

Chalybite occurs in many of the rock strata, in gneiss, mica slate, clay slate, and in connection with the coal formation. It is often associated with metallic ores. At Freiberg it occurs in silver mines. At Cornwall it accompanies tin. It is also found accompanying copper and iron pyrites, galena, vitreous copper, dc. In New York according to Beck, it is almost always associated with specular iron. Occasionally it is to be met with in trap rocks as spherosiderite.

ARÆOXENE, son Kobell, J. f. pr. Ch. 1, 496.

Massive; imperfectly crystalline, with traces of a columnar stree ture. II.=3. Color deep red, with a brownish tinge: streak pake vellowish

Composition.—Contains according to Kobell (loc. cit.), 487 p. c. of oxyd of last and 16.32 of oxyd of zinc, along with vanadic acid. The oxyds of lead and zinc are nearly in equal equivalents, and the oxygen of the bases at least equals that of the acid, as in vanadinite and volborthite, and unlike dechenite.

B.B. on charcoal fuses with intumescence, yielding an arsenical odor and a globule of lead; more lead if soda be added; with borax a bright green glass in the aduction flame. Eight olive-green and then clear vellow in the covariation flame.

me or lead; more lead it sods be added; with borax a bright green glass in the reduction flame, light olive-green and then clear yellow in the oxydation flame and pale greenish on cooling. In powder decomposed easily in heated concentrated muriatic acid, the liquid first yellow, then brownish, and after giving of chlorine emerald-green. On adding spirits of wine, heating it, and pouring of five the solution the separated chlorid of lead, it is still green; concentrating it with a vapor bath and diluting it with water, takes a fine sky-blue color: in this characteristic it is like other vanadium compounds. teristic it is like other vanadium compounds.

From Dahn in the Palatinate, associated with galens.

Resembles crocoisite by

color darker.

III. SULPHATES.—SELENATES.

I. ANHYDROUS SULPHATES OR SELENATES.

1. CELESTINE GROUP. Trimetric.

GLASERITE,	Ŕ <u>\$</u> .	Anhydrite,	Ĉa 3.
THENARDITE,	Ńа З.	Anglesite,	Р ь 3 .
Barytes,	Ba 3.	Almagrerite,	2n 8.
CELESTINE,	Šr 3.	Leadhillite,	Pb \$+8Pb C.
44	(Ba, Sr)3.		

Appendix.—Caledonite.

2. DREELITE GROUP. Rhombohedral.

Ca \$\frac{1}{2} + 3 Ba \$\frac{1}{2} = (\frac{1}{2} Ca + \frac{1}{2} Ba) \$\frac{1}{2}\$. DREELITE.

Pb 5+3Pb C. SUBANNITE,

8. GLAUBERITE GROUP. Monoclinic,

 $\hat{N}a \vec{S} + \hat{C}a \vec{S} = (\hat{N}a, \hat{C}a)\vec{S}$. GLAUBERITE.

PbB+PbC. LANARKITE.

Appendix.—Connellite. Selenate of Lead. Reussin.

The compounds of sulphates and carbonates, or sulphato-carbonates, have the crystallization of the sulphates, the carbonic acid being wholly subordinated, as regards the form produced, to the sulphuric, the more powerful acid. Thus Leadhillite is homocomorphous with Anglesite, Celestine, etc., Susannite with Dreelite, and Lanarkite with Glauberite; and these species are here arranged accordingly.]

GLASERITE, Hausm. Aphthitalite. Sulphate of Potash. Arcanite, Haidinger. Aphthalose, Beudant. Vesuvian Salt, Lond. Phil. Trans., 1813. Kalisulphat, Naum.

Trimetric. $I: I=104^{\circ} 52', O: 1i=119^{\circ} 46'; a: b: c=1.749: 1: 1:3.$ Observed planes $O, 1\bar{\imath}, \frac{1}{3}\bar{\imath}, \tilde{\imath}i, 1, 2\bar{\imath}, 1\bar{\imath}, \frac{1}{2}\bar{\imath}, \tilde{\imath}i.$ $O: \frac{1}{3}\bar{\imath}=149^{\circ} 46', O: \frac{1}{2}\bar{\imath}=146^{\circ} 4', 1\bar{\imath}: 1\bar{\imath} \text{ (basal)}=120^{\circ} 29', 1\bar{\imath}: 1\bar{\imath} \text{ (ib.)}=106^{\circ} 46', \frac{1}{3}\bar{\imath}: \frac{1}{3}\bar{\imath} \text{ (ib.)}=60^{\circ} 28', \frac{1}{2}\bar{\imath}: \frac{1}{2}\bar{\imath}=67^{\circ} 52'.$ Occurs in thin tables and in blades made up of aggregated crystals; also massive, or imperfectly mammillary, and in crusts.

H.=3-3.5. G.=1.731. Lustre vitreous, inclined to resinous. Color white, sometimes tinged with blue or green. Transparent to translucent or opaque. Taste saline and bitter, disagreeable.

Composition.—KS=Potash 54.1, sulphuric acid 45.9. A specimen from Vesuvins contained sulphate of potash 71.4, sulphate of soda 18.6, chlorid of sodium 4.6, chlorid of ammonium, copper, and iron 5.4=100, (Phil. Trans, 1813). Fuses before the blowpipe, without intumescence.

Found at Vesuvius, upon lava, in delicate crystallizations and also in masses

often an inch or more in thickness.

THENARDITE, J. L. Casaseca, Ann. Ch. Phys. xxxii, 311. Anhydrous Sulphate of

Trimetric. $I: I=103^{\circ} 26', O: 1i=120^{\circ} 36', \text{ Hausmann}; a:b:$ c=1.6905:1:1.267, 0:1=126°51', 1i:1i(top)=73°42', (basal)=106° 18'. Cleavage: basal, nearly perfect.

H.=2-2.5. G.=2.73. Lustre vitreous. Color white. Translucent. Covered with a white powder on exposure to the air.

Composition.—NaS—Soda 56'3, sulphuric acid 43'7; analysis by Casaseca, (loc. cit.), Anhydrous sulphate of soda 99'78, carbonate of soda 0'22; by A. Dick of a specimen from Tarapaca, (Phil. Mag. [4], v, 373), \$55'11, \$\times 42'37\$, insol. 2'19=99'67. Wholly soluble in water. Colors the blowpipe flame deep yellow.

Occurs at Espartinas in Spain, 5 leagues from Madrid, and 24 from Aranjuez. The water exudes during winter from the bottom of a basin, and becoming concentrations of the parality.

trated in the summer season, deposits crystals of thenardite. Also at Tarapaca, with Glauberite and Hayesine, the crystals of which locality give some of the angles nearly of Trona, according to H. J. Brooke, (loc. cit.)

Fine specimens of Smithsonite are obtained at Nertschinsk in Siberia; one variety has a dark brown color, and contains cadmium; another is of a beautiful bright green. Other localities are Dognatzka in the Bannat of Temeswar in Hungar; Bleiberg and Raibel in Carinthia; Altenberg, near Aix la Chapelle. Concentre botryoidal groups are met with in the Mendip hills and at Wanlockhead, in Dum-

In the United States, Smithsonite is found occasionally at the lead mines of Missori, and Wisconsin, though the ore is mostly silicate of zinc. Mine Hill, near the Franklin furnace, New Jersey, the Perkiomen lead mine, Pennsylvania, and the lead mine at Brookfield, Conn., afford it in small quantities. At Franklin it occurs only in a pulverulent form, and results from the decomposition of red zinc ore.

ALTERED FORMS .- Smithsonite changes though the action of alkaline silicates, to Calamine (Zna Si+1H); or becomes incrusted with silica and forms quartz pseudo morphs. It is also sometimes replaced by Limonite or Göthite.

ARAGONITE. Eisenbluth, W. Igloite. Flos ferri. Needle Spar. Tarnovitel. Aragonspath.


Trimetric. $I: I=116^{\circ} 10', O: 1i=130^{\circ} 50'; a:b:c=1.1571$: 1:1.6055.


O: 17=130° 50'. $0:25=118^{\circ}25'$. 2%: 2i=110° 30'.

 $O: 1=126^{\circ} 15'$. $O: \frac{1}{2}i=160^{\circ} 11'$. $O: 1\frac{1}{2}=137^{\circ} 15'$. $O: 1\frac{1}{2}=144^{\circ} 13'$. 1%: 1%=71° 34'. I: ii=121° 55'.









Cleavage: I, imperfect; it distinct, 11 imperfect. Twins: plane of composition I; hexagonal prisms, and also f. 227, 236, 237, p. 149, 151, and f. 588. Also globular, reniform, and coralloidal shapes; sometimes columnar, composed of straight or divergent fibres.

H.=3.5-4. G.=2.931, Haidinger; 2.927, Biot; 2.945-2.947, small crystals, and others when pulverized, Beudant. Lustre vitreous, sometimes inclining to resinous on surfaces of fracture Color white; also gray, yellow, green, and violet; streak uncolor ed. Transparent—translucent. Fracture subconchoidal. Brittle

Composition.—CaC, like calcite, = Carbonic acid 44.0, lime 56.0. Analyses: 1-4. Stromeyer; 5, 6, Nentwich, (Versamml. ung. Naturf., Neusohl, 1846); 7, Böttger, (Pogg. Ann. xlvii, 497); 8, Stieren, Arch, f. Pharm., [2], lxii, 31):

		CaC	SrC	PbC	Ĥ	Fe2H3
1.	Brisgau,	97.0963	2.4609	_	0.4102	=99.9674, St.
2.	Nertschinsk,	97.9834	1.0933	_	0.2578	=99·3345, St.
3.	Eschwege,	96.1841	2.2390	-	0.3077	0.2207=98.9515, St.
4.	Aussig,	98-00	1.0145	-	0.2139	0·1449=99·3733, St.
5.	Herrengrund, G .= 2.93	, 98.62	0.99	_	0.17	e 0·11=99·89, N.
6.	Retzbanya, G .= 2.86	99.31	0.08	-		u Ö 0·19=99·89, N.
7.	Tarnowitzite,	95.940	-	3.859		=99·956, B.
8.	Papenberg.	97.39	2.22			H 0.39=100, S.

Delesse finds in the aragonite of Herrengrund, near Neuschl, Hungary, no strontia, and 0 13 per cent. of water. A Thurnberg variety afforded E. Riegel, (Jahrb. pr. Pharm. xxiii, 348), 2.2 per cent. of carbonate of strontian. A fibrous variety from Dufton in Cumberland, afforded 4.25 per cent. of Mn C.

When aragonite is heated, it falls to powder. It is phosphorescent on red hot

iron, and soluble with effervescence in nitric and muriatic acid.

The most common repositories of aragonite are beds of gypsum, beds of iron ore, (where it occurs in coralloidal forms, and is denominated flos-ferri, 'flower of iron'), basalt, and trap rock; occasionally it occurs in lavas. It is often associated with copper and iron pyrites, galena, and malachite. It is forming at an old mine in Monte Vasa, Italy, at a temperature below the boiling point of water.

This mineral was first discovered in Aragon, Spain, (whence its name), at Molina and Valencia, near Migranilla, in six-sided prisms, with gypsum, imbedded in a ferruginous clay. It has since been obtained in compound hexagonal prisms at Bilin, in Bohemia, in a vein traversing basalt; at Breisgau in Baden; at Baumgarten and Tarnowitz in Silesia; at Leogang in Salzburg, Austria; in Waltsch, Bohemia, and many other places. The flos-ferri variety is found in great perfection in the Styand many other places. The flos-ferri variety is found in great perfection in the Styrian mines, coating cavities and even caves of considerable extent, and associated with spathic iron. At Dufton, a silky, fibrous variety, called satin spar, occurs traversing shale in thin veins, generally associated with pyrites. In Buckinghamshire, Devonshire, &c., it occurs in stalactitic forms in caverns, and of snowy whiteness at Leadhills in Lanarkshire. The variety tarnowitzite (analysis 7 above) corresponds to plumbocalcite, under calcite. Kersten found in another specimen 2.19 of carbonate of lead. An aragonite deposited in stalactites, etc., at the Carlsbad Springs, called Sprudelstein, contains 0.69 per cent. of fluorid of calcium and a trace of arsenic.

Aragonite in fibrous and other forms occurs in Serpentine at Hoboken, (it has

been called magnesite).

Flos-ferri occurs sparingly at Lockport, N. Y., coating gypsum in geodes; at Edenville, N. Y., lining cavities of mispickel and cube ore; at the Parish ore bed, Rossie, N. Y.; and at Haddam, Conn., in thin seams between layers of gneiss. A coralloidal aragonite occurs at New Garden, in Chester Co., Pennsylvania.

ALTERED FORMS.—Aragonite may undergo similar changes with calcite. It also passes to calcite, through paramorphism. Pseudomorphs of copper after aragonite are reported from Bolivia.

WITHERITE, Werner. Withering, Phil. Trans. 1784, p. 293. Carbonate of Barytes. Barolite.

Trimetric. $I: I=118^{\circ} 30', \ 0: 1\overline{\imath}=128^{\circ} 45'; \ a:b:c=1.246:$ 1:1.6808. Observed planes, I, $\frac{1}{4}$, $\frac{1}{2}$, I, $\frac{3}{2}$, 2. O:1=124° 35 $\frac{1}{2}$, I:1=145° 24 $\frac{1}{2}$, I:2=160° 58 $\frac{1}{2}$, I: $\frac{3}{2}$ =155° 18 $\frac{1}{2}$, I: $\frac{1}{2}$ =125° 57 $\frac{1}{2}$, I: $\frac{1}{4}$ =109° 55 $\frac{1}{2}$, I:1 (mac.)=130°13′, (brach.)=89°57′, (bas.) 110° 49'. Twins: all the annexed figures, composition parallel to I, (probably, as represented in f. 234 or 237, p. 151); reëntering angles sometimes observed. Cleavage: I distinct; also in globular, tuberose, and botryoidal forms; structure either columnar or granular: also amorphous.


 $H_{-3}-3.75$. $G_{-4.29}-4.35$. Lustre vitreous, inclining to


extensive beds at the estuary of the Avon and the St. Croix river, also near the Five Islands, and elsewhere, associated with gypsum, in the carboniferous forms tion

ALTERED FORMS.—Absorbs moisture and changes to gypsum. Extensive beds are sometimes thus altered in part or throughout, as at Bex, in Switzerland, where, by digging down 60 to 100 feet, the unaltered anhydrite may be found. Sometimes specimens of anhydrite are altered between the folia or over the exterior.


ANGLESITE, Bend Sulphate of Lead Lead Vitriol. Bleivitriol. Vitriolbleiers, W.

Trimetric: $I: I=103^{\circ} 38'$, (103° 43½', Kokscharov, Pogg. xc, 158), $O: 1\bar{\imath}=121^{\circ} 21'$; $a:b:c=1.641\bar{5}:1:1.2715$.





Observed Planes.



Cleavage: I, O, but interrupted The planes I and ii, often vertically striated, and $\frac{1}{2}i$ horizontally. Also lamellar, and massive granular.

H.=2.75—3. G.=6.259—6.2%. Lustre highly adamantine in some specimens, in others inclining to resinous and vitreous. Color white tinged yellow, gray, green, and sometimes blue. Streak uncolored Transparent—opaque. Fracture conchoidal. Very brittle.

even faces of fracture. Color asparagus green, apple-green; also white, gray, yellow, and yellowish-brown. Streak white. Transparent—translucent. Fracture uneven.

Composition.—ŜrĈ=Carbonic acid 29.81, and strontia 70.19.

Thomson found the two varieties from Strontian to contain 6 to 8.64 per cent. of Thomson found the two varieties from Strontian to contain o to 8 be per cent. of CaC; and another from the United States, named by him *Emmonite*, in honor of Prof. Emmons, affords 12.5 per cent. of CaC. Similar specimens come from Clausthal, and from Hamm in Westphalia. Schnabel found in the latter 7.89 per cent. equivalent to 1 CaC to 8 SrC. (Ramm. 4th Suppl, 215; also 5th Suppl, 231). The former contains five to eight per cent. of CaC.

B.B. melts on the edges and then swells out, emitting a brilliant light, and in the advance of the state of the same a raddish tings: assay gives an al-

reducing flame strongly heated gives the flame a reddish tinge: assay gives an al-

kaline reaction.

Effervesces with nitric and muriatic acids. Paper wet with the solution in these

acids and dried, burns with a red flame.

Strontianite occurs at Strontian in Argyleshire, in veins traversing gneiss, along with galena and heavy spar, in stellated and fibrous groups, rarely in perfect crystals. Yorkshire, England; Giant's Causeway, Ireland; Clausthal, in the Hartz; Bräunsdorf, Saxony; Leogang in Saltzburg, Austria, are other localities.

In the United States it occurs at Scoharie in granular and columnar masses, and also in crystals, forming nests or geodes often large in the hydraulic limestone, associated with heavy spar, iron pyrites, and calc spar. At Muscalonge Lake a massive and fibrous variety of a white or greenish-white color, is sometimes the matrix of fluor spar. Chaumont Bay and Theresa, in Jefferson Co., N. Y., are other localities. Massive strontianite has been found by Mr. James Heron, at Warwick, N. Y.

Barystrontianite from Stromness, in Orkney, consists of

BaS 27.5, ŠrČ 62·6, CaC 2.6, and oxyd of iron 0.1.

It is supposed to be a mechanical mixture.

ALTERED FORMS.—Strontianite is altered to Celestine in the same way as Witherite to Heavy Spar.

BROMLITE, Johnston, Phil. Mag. vi, 1, and xi, 45. Thomson, ibid. x, 373, and Rec. of Gen. Sci. i, 373. Delesse and Descloizeaux, Ann. Ch. Ph. [3], xiii, 425. Alstonite, Breithaupt. Bicalcareo-carbonate of barytes, Thomson.

Trimetric. $I: I=118^{\circ} 50' \text{ (Descl.)}, O: 1\bar{\imath}=128^{\circ} 39; a:b:c$ =1.2504:1:1.6920. Observed planes: octahedrons 1, 2; domes, = 12504:1:170520. Observed planes: octahedrons 1, 2, unless, 15, 25; with $I. O:15=143^{\circ} 32\frac{1}{2}', 15:15$ (bas.)= $72^{\circ} 55', 25:25$ (bas.)= $111^{\circ} 50', 1:1$ (mac.)= $130^{\circ} 27', 1:1$ (brach.)= $89^{\circ} 40'$. Twins: double six-sided pyramids, with angles $122^{\circ} 30'$, and 142° ; reëntering angle $178^{\circ} 51'$. Cleavage: I and O rather indistinct.

H.=2.5. G.=3.718, Thomson; 3.706, Johnston. Lustre vitre-Color snow-white. Translucent. Fracture granular and uneven.

Composition.—BaC+CaC, like Barytocalcite=Carb. baryta 66.8, carb. lime 837:

	ВаĈ	ĈaĈ	Šr Ö	ЙnÖ	S i	М́п
1.	60.63	30.19		9.18		—=100, Thomson.
2.	62.156	80.290	6.641			
3.	65.31	82 ·90	1.10		0.20	0·16==99·67, Delesse.

Discovered by Johnston in the lead mine of Fallowfield, near Hexham, Northumberland; and afterwards at Bromley Hill, near Alston, whence the name Bromlite, given by Thomson.

MANGANOCALCITE, Breit.

In rhombic prisms like Aragonite, and closely related to that species. Cleavage lateral, also brachydiagonal.

H.=4-5. G.=3.037. Lustre vitreous. Flesh-red to dull reddish-white. Translucent.


Composition.—Same general formula as Diallogite. Analysis by Rammelsberg (Pogg. lxviii, 511):

Mn C 67.48, Fe C 3.22, Ca C 18.81, Mg C 9.97=99.48.

THOMAITE.—This name has been given to a carbonate of iron, said to have a prismatic form. G.=:3:10. Lustre pearly. An analysis by Meyer afforded 03349, Fe 5372, Mn 0:65, Mg 0:43, Ca 1:52, Al 4:25, Si 6:04=100. From the Siebesgebirge. Leona. u. Bronn's Jahrbuck, 1845, 200.

CERUSITE, Haid. White Lead Ore. Carbonate of Lead. Ceruse. Weissbleier. Iglesiasite. Bleierde, Worn.

Trimetric. $I: I=117^{\circ} 13', O: 17=130^{\circ} 9\frac{1}{2}': a:b:c=1\cdot1852:1:1\cdot6388.$



Observed Planes.

O: 1=125° 46'.
O: 1=149° 21'.
O: 1=144° 8'.

 $O: 2\% = 124^{\circ} 40'.$ $I: \% = 121^{\circ} 24'.$

 $\tilde{\mathbf{A}}: 2\tilde{\mathbf{A}} = 145^{\circ} \ 20'.$ $\tilde{\mathbf{A}}: \frac{1}{4}\tilde{\mathbf{A}} = 109^{\circ} \ 53'.$

2i : 2i (bas.)=110° 40'.


1i: 1i (bas.)=71° 44′. $\frac{1}{1}$ i: $\frac{1}{1}$ i (bas.)=39° 45′.


is: is (ov. ii)=122° 43'.


1:1 (mac.)=130°. 1:1 (brach.)=92° 19′.

1 · 1 (box)—1/109 001

 $1:1 \text{ (bas.)}=108^{\circ} 28'.$







Cleavage: I often imperfect; 2i hardly less so. Twins: f. 233, 598, often stellated; plane of composition I. Rarely fibrous; often granularly massive and compact.

H.=3-3.5. G.=6.465-6.480; some earthy varieties as low as 5.4. Lustre adamantine, inclining to vitreous or resinous; sometimes pearly; sometimes sub-metallic, if the colors are dark. Color white, gray, grayish-black, sometimes tinged blue or green by some of the salts of copper; streak uncolored. Transparent—subtranslucent. Fracture conchoidal. Very brittle.

Composition .- Pb C=Carbonic acid 16.5, oxyd of lead 88.5=100. Analyses: 1, Bergemann, (Chem. Unters. Bleib. 167, 175); 2, J. A. Phillips, (Qu. J. Ch. Soc. iv, 175); 3, 4, John, (Schw. iv, 227, xxxii, 114, 117); 5, Bergemann; 6, Kersten:

O 1. Eifel, 16.49 83.51=100, Bergemann.

2. Durham, 1605 83:56=99:61, Phillips.
2. Eschweiler, earthy, 16:62 81:34 1:75, Ca and Fe 0:29=100, John.
4. Kall, earthy, 15:81 77:07 6:32 " 0:80=100, John.
5. " red, Pb C 94:233, H 2:566, quartz 1:07, Fe and Kl 2:2, Berg.
6. Sardinia, Iglesiasite, " 92:10, Zn C 7:02, Kersten; G.=5:9.

B.B. decrepitates, becomes yellow, then red, and finally, with care, on charcoal a globule of lead may be obtained; dissolves readily, and with effervescence, in dilute

Occurs at Leadhills and Wanlockhead in Scotland, with other ores of lead in Silurian slate; in beautiful crystals at Johanngeorgenstadt; at Nertschinsk and Beresof in Siberia; near Bonn on the Rhine; at Clausthal in the Hartz; at Bleiberg in Carinthia; and at Mies and Przibram in Bohemia; in England, at Alston Moor, Keswick, and particularly in Cornwall, where, in the mine of St. Minvers, it occurs in exceedingly delicate crystals; in heart-shaped macles at Seven-Churches, Wick-low Co., Ireland; in pseudomorphs, imitating Anglesite and Leadhillite, at Leadhills.

Fine crystals have been obtained in Pennsylvania, at Phenixville; also at the Perkiomen lead mines, near Philadelphia. Also occurs at Valle's Diggings, Jefferson Co., Missouri, and in other mines of the West; at Brigham's mines, near the Blue Mounds; as an incrustation, at Southampton, Mass.; sparingly at the lead mines of St. Lawrence Co., N. Y.; fine crystals are obtained at Austin's mines, Wythe Co., Virginia, and especially at King's Mine, in Davidson Co., N. C.

ALTERED FORMS.—Cerusite occurs altered to pyromorphite, or phosphate of lead; probably through the action of waters holding phosphate of lime in solution; also to Galena (PbS) through the action of sulphuretted hydrogen, and Minium by oxydation: also to Breunnerite, Malachite and Chrysocolla.

BARYTOCALCITE, Brooke, Ann. Phil. viii, 114, 1824.

Monoclinic. C=73° 52', I : I=106° 54' O : 1i=149° a:b:c=0.81035:1:1.29583. $O: 1i=147^{\circ} 34', O: ii=106^{\circ} 8', ii: 1i=138^{\circ} 34', ii: ii=124^{\circ}, 2i: 2i (over 6i)$ =95° 8′, 6è : 6è (adj)=146° 6'. Cleavage: I, perfect, O, less perfect; also massive.


H.=4. G.=3.6363-3.66. Lustre vitreous, inclining to resinous. Color white, grayish, greenish, or yellowish.

599 600 ii 66 66 22 22

Streak white. Transparent-translucent. Fracture uneven.

In attached crystals at Leadhills in Scotland, and at Moldawa in the Bana Formerly referred to Leadhillite, the compound crystals of which it resembles. The rhombohedron R of Susannite, as it is assumed by Haidinger, equals very nearly -2 of Dreelite, which it is here made. (The minus sign is omitted in the figure).

GLAUBERITE, Brongniart, J. des Mines, xxiii, 5. Brongniartin, c. Leon



(116° 18'—116° 52'), -33: -33=135° 20'. Cleavage: O perfect H.=2.5—3. G.=2.64—2.85. Lustre vitreous. Color pale yellow or gray. Streak white. Fracture conchoidal; brittle. Taste slightly saline.


Composition.—(1Na+1Ca)S=Sulphate of soda 51:1, and sulphate of lime 48:1.

Kobell obtained from a specimen from Berchtesgaden, (v. Leonh. 1846, 840), Sulphate of soda 48:6, sulphate of lime 51:0. Crystals from Atacama gave Hayea, (Jour. Bost. Nat. Hist. Soc. iv, 498), Sulphuric acid 67:22, soda 21:32, lime 20:68, iron 014:99:56

Ulex found in the Peruvian mineral, Ca 19.6, Na 21.9, S 55.0, B 3.5=100, the boracic acid being due to mixture. Kengott obtained from an Ischl specimes, (Sitz Wien, Akad), S 57.52, Ca 20.37, Na 21.60, Na 0.20, Cl 0.31. In water it loss transparency, and is partly dissolved. On long exposure it absorbs moisture and falls to pieces. Before the blowpipe it decrepitates and melts to a clear glass. On charcoal, it first whitens, then fuses to a transparent bead, opaque on cooling. In crystals in rock salt at Villa Rubia, near Ocana in New Castile: also at Australia.

In crystals in rock salt at Villa Rubia, near Ocana in New Castile: also at Aussee, in Upper Austria, in Bavaria; and at the salt mines of Vic, in France. (0: 1= 104° 11′, Duf.) Province of Tarapaca, Peru, with the Hayesine, (affording the above figure and Senarmont's angles.)

LANARKITE, Beud Dioxylite. Sulphato-Carbonate of Lead, Brooke, Ed. Phil Jour. iii, 117.



Monoclinic. $I: I=85^{\circ} 48'$. $i_{1}: i_{2}$ (front) 49° 50′, Greg. $O: -1i=12^{\circ} 45'$. Plane i_{2} usually rounded, and the crystals aggregated lengthwise, and seldom distinct. Cleavage: O perfect: -1i less perfect. Laminæ flexible as in gypsum.

THERMONATRITE, Haid.

Trimetric. In rectangular tables, with beveled sides. One vertical prism of 83° 50′, another of 121° 56′, and a brachydome of 107° 50′. Usual as an efflorescence.

H=1-1.5. G=1.5-1.6. Lustre vitreous. Colorless.

Composition.-NaC+H=Soda 50.0, carbonic acid 35.5, water 14.5. Beudant obtained in two analyses:

Ñαδ NaCl and other ingredients. ÑaÜ Ħ 1. Debreczin, 78.6 13.8 10.4 $2 \cdot 2 = 100$ 2. Egypt, 747 13.2 7.8 8.1, Earthy matter 4.1=100.

This is the more common salt in nature, natron changing to it, on efflorescing. It occurs at the various localities of natron.

NATRON. Carbonate of Soda. Soude Carbonatée. Natürliches Mineral Alkali, W.

Monoclinic: $C=58^{\circ}$ 52, $I: I=76^{\circ}$ 28', $O: 1i=140^{\circ}$ 9½'. Cleav-

age O distinct; ii imperfect; I in traces.
H.=1-1.5. G.=1.423. Vitreous to earthy. White, sometimes gray or yellow, owing to impurities. Taste alkaline.

Composition.—NaC+10H=Carbonic acid 26.7, soda 18.8, water 54.5. Wackenroder found in the Debreczin Natron, NaC 89.84, NaCl 4.34, NaS 1.63, NaP 1.46, KS 0.08, MgC 0.24, CaC 0.24, Fe and Si 0.42, NaSi 1.61, S 0.15.—Effervesces strongly with nitric acid.

Occurs at the soda lakes of Egypt, at Debreczin in Hungary, at Vesuvius, Etna, and in various parts of Africa, Asia, and America. This is the nitre of the Bible.

GAY-LUSSITE, Boussingault.

Monoclinic. $C=78^{\circ}\ 27', I: I=68^{\circ}\ 50'.$

 $0:2i=130^{\circ}21'.$ $O: I = 96^{\circ} 30'$. $1i: 1i=109^{\circ} 30'$.

 $0: ii = 101^{\circ} 33'.$ $0:1i=125^{\circ}15'$. $1:1=110^{\circ} 30'$.

 $O: 1=136^{\circ} 39'$.

Cleavage: I perfect; O less so.

H=2-3. G=1.92-1.99. Lustre (obtained by fracture) vitreous. Streak grayish. Color yellowish-white. Translucent. Exhibits double refraction. Fracture conchoidal. Extremely brittle. Not phosphorescent by friction or heat.


Composition. - NaC+CaC+5H=Carbonate of soda 35.9, carbonate of lime 33.8, water 30.3=100. Analysis by J. B. Boussingault, (Ann. Ch. Phys., vii, [3], 488, 1848),

ĈaĈ 33·6, H 30.4, · Clay 1.5=100.

Heated in a matrass, the crystals decrepitate and become opaque. With the fluxes it behaves like carbonate of lime; dissolves in nitric acid, with a brisk effer-vescence; partly soluble in water, and reddens turmeric.

This mineral is abundant at Lagunilla, near Merida, in Maracaibo. Its crystals are disseminated at the bottom of a small lake, in a bed of clay, covering urac. The natives call it claves or nails, in allusion to its crystalline form. It was named by Boussingault, in honor of Gay-Lussac. Also found near Sangerhausen in Thuringia.

ALTERED FORMS. - Crystals altered to calcite, have been called Natrocalcite.



601

II. HYDROUS SULPHATES.

[As in the case of other hydrous minerals, there are but few species that be arranged in groups. For the most part, each of the Hydrous Sulphates longs to a distinct group, represented by a single species alone. The extions to this are the Alum Group, monometric, with the oxygen ratio for bases, acid and water, 1:3:6; the Vitriol Group, monoclinic, having ratio 1:3:7; the Epsomite Group, trimetric, with the same ratio. The somite and Vitriol Groups are mutually dimorphous. The species are I placed according to the oxygen ratio, commencing with that containing most acid and least water.]

	Oxygen ratio.	Formula.
	B+# F H	
MISENITE,	1:6:1	ks+HS.
POLYHALITE, III.	1:3:1	Ŕ§ + }Ĥ.
Gypsum, IV. (Gypsum Gr.),	1:8:2	CaS+2H.
Astrakanite,	1:3:2	(Mg, Na)5+2H.
MASCAGNINE, III. (MASCAGNINE	Gr.), 1:3:2	(NH'O)\$+2 Ĥ .
COQUIMBITE, VI. (COQUIMBITE G	PL), 1:3:3	Fe3°+9A.
Cyanosite, V. (Cyanosite Gr.),	1:3:5	Ċu§+5Ĥ.
Alunogen,	1:8:6	∄ Iг+18 Ĥ .
Alum, L (Alum Gr.),	1:3:6	ŔŜ +Ħ Ŝ* + 24Ħ.
Epsomite, III. (Epsomite Gr.),	1:3:7	Ѝg Ѕ +7Ĥ.
Goslabite, "	1:3:7	ŹnŠ+7Ĥ.
COPPERAS, IV. (VITRIOL GR.),	1:3:7	FeŠ+7Å.
Bieberite, "		(Čo, M g)\$ + 7 À .
† Pyromeline, "		Ňi, 🕏, Ĥ.
Johannite,		Ū, Ī, Ĥ.
GLAUBER SALT, IV.	1:3:10	ÑaS+10Ĥ.
Botryogene, IV.	1:2:3	(Ř³, ₹) г+9Ĥ.
Copiapite,		F e, S , U .
Apatelite,		
Alunite, VI. (Alunite Gr.),	1:6:3	ŔŜ +3 ₹1Ŝ+6Ĥ.
JAROSITE, VI.		Ř, ře or F e, S, Á
Websterite,	1:1:9	I 15+9Ĥ.

Composition.—Mg*C*+4H, or 3(MgC+H)+MgH=Magnesia 43.9, carbonic acid 36.3, water 19.8=100. Analyses: 1, Waltershausen, (K. V. Ac. H. 1827, 17); 2, Kobell, (J. f. pr. Ch. iv, 80); 3, 4, Smith and Brush, of crystalline varieties, (Am. J. Sei. [2], xv, 214):

Ö Mg H Si 36.82 42.41 18.53 0.57 Fe 0.27, earthy matter 1.39 1. Hoboken, =99-99, Walt.

2. Negroponte, 3. Texas, Pa., Wood's Mine, 36-69 43-20 19-43 Low's Mine, 36-74 42-30 20-10 36.00 43.96 19.68 0.36=100, Kobell. - Fe and Mn tr.=99.72, S. & B. " tr.=99.14,

B.B. infusible; yields moisture, and finally becomes pure magnesia. Effervesces and dissolves in acids.

Occurs at Hrubschitz, in Moravia in serpentine; in Negroponte near Kumi; in the United States, crystallized with serpentine and brucite, near Texas, Lancaster Co., Penn., at Wood's and Low's mines; also in a similar way at Hoboken, N. J., in acicular crystals like natrolite; at the latter place in earthy crusts. The Brucite of Hoboken sometimes changes on exposure to an earthy hydromagnesite.

The above angles and figure were taken by the author from a crystal one-fiftieth of an inch broad, in which the summit planes were smooth and brilliant, the prismatic striated. The rhombic prism in one crystal gave the angles 95° 20' and 84° 50'; but other crystals gave different results, and no constant value was obtained. The species is isomorphous with Wollastonite, (p. 156).

The Lancasterite of Silliman, (Am. J. Sci. [2], ix, 226), is shown by Smith and Brush to be a mixture of Brucite and Hydromagnesite.

Hydrodolomite. (Dolomite sinter, Kobell, J. pr. Ch. xxxvi, 304, Hydromagne-calcit, Ramm.) A hydromagnesite having part of the magnesia replaced by lime. Occurs in sinter-like globular or stalactitic masses yellowish and white, and earthy. Composition, 3[(Mg. Ca)C+H]+MgH, Ramm. Kobell obtained, Lime 25-22, magnesia 24-28, carbonic acid 38-10, water 17-40=100. From Somma, in isolated masses.

PREDAZZITE, Petzholdt. A kind of bitter spar mixed with Brucite, from Predazzo in the Southern Tyrol. H.=3.5. G.=2.634. J. Roth obtained, (J. f. pr. Chem. lii, 346):

 Ö
 Ća
 Mg
 Fe, Xl
 Ši
 Ĥ

 1. 27.45
 33.58
 23.27
 2.88
 3.28
 10.26=100.67.

 2. 33.35
 46.67
 14.54
 0.48
 6.96=100.

Analysis 1, corresponds to Ca C+MgH; 2, to 2CaC+MgH. Brucite occurs in plates in the Predazzite, and hence the water.

Pennite of Hermann (Hydronickelmagnesite of Shepard) is a carbonate of lime and magnesia, containing two per cent. or less of carbonate of nickel, with some water. It occurs in incrustations having a surface of minute spherules; color pale green to whitish. Hermann obtained C 44.54, Ca 20.10, Mg 27.02, Ni 1.25, Fe 0.70, Mn 0.40, Xl 0.15, H 5.84=100. Occurs with emerald nickel, into which it graduates, and also with chromic iron, at Texas, Lancaster Co., Pa.; and according to Mr. Heddle, at Swinaness in Unst, Shetland.

HYDROCALCITE. Hydrous Carbonate of Lime, Scheerer, Ann. der Ph. u. Ch. lxviii, 381. Hydrokonit, Haus.

In small rhombohedral crystals, and forming an incrustation on wood under


Composition.—CaC+5H=Carbonate of lime 52.4, and water 47.6. Exposed to the air, the water passes off and it becomes anhydrous. The crystals contain one per cent. of organic matter. By the action of absolute alcohol, it loses two equivalents of water.

A blue limestone from Vesuvius analyzed by Klaproth, (Beit. v, 91), has the formula 2CaC+CaH, consisting of Lime 58 00, carbonic acid 28 50, water 11 00,


earthy impurities 2.25=99.75.

Cleavage: ii eminent; I imperfect, fibrous; O imperfect, conchoidal. Twins: plane of composition O, as in f. 534, reëntering angle 104° 32'; also 1i or plane truncating edge 1:1, and re-

		0	(a)		
1i(d)		1(1)			
		2(v)			2.(m)
3i(e)	83(w)	3 (4)		33(y)	
					4i(h)
1-					6i(k)
ii(t)		I(n)	$i\hat{2}(x)$	i3(s)	ii (b)



entering angle 79° 32′, made by plane ii, form often lenticular. Lamellar-stellate, lamellar and granular; often massive, and some times nearly impalpable.



H.=1.5—2. G.=2.314—2.328, when pure crystals. Lustre of in pearly and shining, other faces subvitreous. Massive varieties often glistening, sometimes dull earthy. Color usually white; sometimes gray, flesh-red, honey-yellow, ochre-yellow, blue; impure varieties often black, brown, red, or reddish-brown. Streak white. Transparent—opaque.

Composition.—CaS+2H=Sulphuric acid 46.51, lime 32.56, water 20.93. De la Trobe found in the gypsum of the volcano of Albay, island of Luzon, 6.48 of silica, (Ramm. 4th Supp., 89). B.B. becomes opaque-white, exfoliates, and falls to powder. At a high heat it fuses with difficulty to a white enamel. The white powder obtained by heat, if moistened, soon becomes very firmly solid. No effervescence with acids when pure. Soluble in 400 to 500 parts of water.

The transparent varieties are called Selenite; the fine massive varieties, Alabaster:

The transparent varieties are called Selenite; the fine massive varieties, Alabaster; the fibrous, Satin Spar. Schaumkalk is a variety in small scales of a pearly lustre. Gypsum often forms extensive beds in secondary countries, and is also found in tertiary and recent deposits; occasionally in crystalline rocks. It is also a product of volcances, occurring about fumaroles, or where sulphur gases are escaping,

AZURITE, Beud. Blue Copper. Blue Carbonate of Copper. Blue Malachite. Chessy Copper. Kupferlasur, W. Chessylite, B. and M. Lasurite, Heid.

Monoclinic. $C=87^{\circ} 39'$; $I: I=99^{\circ} 32'$, $O: 1i=138^{\circ} 41'$; a: b: c=1.039: 1: 1.181.

 $O: I = 91^{\circ} 48'$ $0 = ii = 92^{\circ} 21'$. $0:1i=132^{\circ}43'.$ $0:1=125^{\circ} 8'.$ $\theta: 2=108^{\circ} 35'$ $O: -1 = 127^{\circ} 28'$. 1:1 (front)=116° 7'. -1: -1 " =118° 16'. $ii: 1i=134^{\circ} 56'.$ $ii: \frac{1}{2}i = 115^{\circ} 35'$ $1i : \bar{1}i \text{ (bas.)} = 82^{\circ} 38'.$ 2i : 2i (bas.) = 120° 46'. $i2:i2=134^{\circ}8'$. i}: i}=121° 10′. $i\hat{2}:i\hat{2}=118^{\circ}\ 50'.$ $ii: 2i = 153^{\circ} 51'$.


ii: I=139° 46′

				0			
	100				22 5		131
				23			3
						33	
					$\frac{4}{5}$ 2	1 - 4	1
1i				i			16
					$\frac{4}{3}$		
21		22		2			21
	44		1		42		
ii		<i>i</i> 2	$\frac{i3}{2}$	1	iè		ii
-2i				-2	-22	1	
					$-\frac{4}{3}\hat{2}$	1	
-1 <i>i</i>			4.1	-1		-	

Observed Planes. Add $\frac{1}{8}i, \frac{1}{6}i, \frac{1}{2}i, \frac{3}{2}i, 3i, -\frac{1}{2}i$.

Cleavage: 2i rather perfect; ii less distinct, I in traces. Also massive and presenting imitative shapes, having a columnar composition; also dull and earthy.

H.=3·5—4·25. G.=3·5—3·831. Lustre vitreous, almost adamantine. Color various shades of azure-blue, passing into Berlin-blue. Streak blue, lighter



than the color. Transparent—subtranslucent. Fracture conchoidal. Brittle.

Composition.—2ĈuĈ+ĈuĤ [=(Ĉu, Ĥ)³Ĉ]=Carbonie acid 25.6, protoxyd of copper 69.2, water 5.2. Analyses: 1, Phillips, (Jour. Roy. Institution, iv, 276); 2, Vauquelin, (Ann. du Mus. xx, 1):

1. Chessy, C 25.46 Ou 69.08 Ĥ 5.46=100, Phillips.
2. " 25.0 68.5 Ĥ 5-46=100, Phillips.
6.5=Vauquelin.

In a matrass yields water and blackens. B.B. on charcoal fuses, and affords a globule of copper, and in the forceps the flame is green. Borax is colored green. It dissolves with effervescence in the acids, and also in ammonia.

Azurite occurs in splendid crystallizations, at Chessy, near Lyons, whence it derived the name Chessy Copper. It also occurs in fine crystals in Siberia; at Moldawa, in the Bannat; at Wheal Buller, near Redruth, in Cornwall; at Porto Cabello, S. A.; also in small quantities at Alston Moor, and Wanlockhead, &c.

This mineral occurs in indifferent specimens at the Perkiomen lead mine, accociated with galena, blende, and white lead ore; also near Nicholson's gap, in the

```
O: \frac{1}{2}i=150^{\circ} 34'. \frac{1}{2}i: \frac{1}{2}i(\text{bas.})=58^{\circ}52'. i_{2}: i_{2}:=111^{\circ} 15'. O: \frac{3}{2}i=125^{\circ} 34'. \frac{1}{2}i: \frac{1}{2}(\text{over }I)=87^{\circ} 26'.
```

Usually in mealy crusts and stalactitic forms.

H.=2-2.5. (1.=1.72-1.73. Lustre when crystallized, vitreous. Color yellowish-gray, lemon-yellow. Translucent. Taste pungent and bitter.

Composition.—NH⁴OS+2H=Sulphuric acid 52·88, NH⁴O 34·67, water 12·00. Dissolves readily in water.

Occurs about volcanoes, in the fissures of the lava, as at Etna, Vesuvius, and the Lipari Isles, and is one of the products of the combustion of mineral coal. It was named in honor of Professor Mascagni, its discoverer, (v. Dei Lagoni del Sinesse del Valterrano in Siena, 1779).

COQUIMBITE. White Copperas. Neutrales Schwefelsaures Eisenoxyd.

Hexagonal. Prisms usually with the terminal edges deeply replaced. $O: 1=151^{\circ}, I: 1=119^{\circ}, 1: 1=128^{\circ}$ 8'. Cleavage: I imperfect. Also in fine granular masses.

H.=2-2.5. G.=2-2.1. Color white, yellowish, brownish, sometimes with a pale violet tint. Taste astringent.

Composition.—FeS++9H=Sulphuric acid 427, peroxyd of iron 28.5, water 28.8 =100. Analyses: 1, 2, H. Rose:


	8	₽e	Æl	Ċa	М́g	Bi	Ĥ
1. Crystalline,	43.55	24.11	0.92	078	0.83	0.81	80·10=100·04, Rose.
2. Granular,	48.55	35.21	078	0.14	0.51	0.87	29-98=100-24, "

Wholly soluble in cold water: if the solution be heated, peroxyd of iron is copiously precipitated. Dilute muriatic acid dissolves the whole, except a portion of silica.

Forms a bed in a feldspathic or trachytic rock, in the province of Coquimbo, about half a day's journey from Copiapo. The bed of salt is on the increase, and is probably derived from decomposing sulphurets. Pits twenty feet deep have been formed in it by the people of the country. Occurs also in Bolivia near Calama, constituting the greater part of a large hill.

J. H. Blake refers here octahedral crystals, (Blakeite of last edition of this work), from Coquimbo analyzed by him, (Jour. Bost. Soc. N. Hist.), as follows: S 41:37. Fe 26.79, H 1:05, Mg 0:30, Si 0:82, H 29:40=99:68. The same octahedral form was assumed on recrystallization. It is possible that the mineral examined was an iron alum. Requires further investigation.

CYANOSITE. Cyanose, Beud. Sulphate of Copper. Blue Vitriol. Copper Vitriol. Kupfervitriol. Chalcanthit, Glocker.



Triclinic. $O: I=109^{\circ} 32', O: I'=127^{\circ} 40', I: I'=123^{\circ} 10', O: 1=125^{\circ} 38', I: 1=126^{\circ} 10', O: i=120^{\circ} 50', O: i=103^{\circ} 27'$ and $76^{\circ} 33'$. Cleavage: I imperfect, I' very imperfect. Occurs also amorphous, stalactitic, reniform.

H.=2.5. G.=2.213. Lustre vitreous. Color Berlin-blue to sky-blue,

EMERALD NICKEL, Silliman, Jr.

Incrusting, and often small stalactitic or minute mammillary, and sometimes appearing prismatic with rounded summits. Also massive, compact.

H.=3-3.25. G.=2.57-2.693. Lustre vitreous. Color emerald-green; streak paler. Transparent-translucent. Brittle.

Composition.—Ni C+6H(or Ni C+2Ni H3)=Carbonic acid 11.66, oxyd of nickel 59 72, water 28 62; often containing magnesia in place of part of the oxyd of nickel. Analyses: 1, B. Silliman, Jr., (Am. J. Sci. [2], vi, 248); 2, Smith and Brush, (ib. xvi, 52):

Ñi 58-811, C 11.691, Ĥ 29·498. 56.82 11.68 29.87, Mg 1.68.

In a matrass yields water, and loses color. With borax affords a transparent bead of a dark yellow or reddish color when hot, and nearly colorless when cold. In the inner flame the bead is gray from the presence of particles of metallic nickel. Dissolves easily with effervescence in heated dilute muriatic acid.

Occurs on chromic iron at Texas, Lancaster Co., Pa., associated with serpentine; also at Swinaness in Unst, Shetland.

REMINGTONITE. J. C. Booth, Am. J. Sci. [2], xiv, 48.

A rose-colored incrustation, softy and earthy; opaque. Streak pale rose-colored.

Composition.—A hydrous carbonate of cobalt, but precise composition not ascertained. Dissolves in muriatic acid with a slight effervescence, making a green solution, the color due to iron. Cobalt reaction with borax.

Occurs as a coating on thin veins of serpentine, which traverse hornblende and

epidote, at a copper mine near Finksburg, Carroll Co., Maryland.

ZIPPEITE. Uranochre. Uranblüthe. Uraconise, Beud.

Earthy and pulverulent. Color sulphur-yellow, citron-yellow to brownish or reddish-yellow. Opaque.

Composition.—Probably # with water and some carbonic acid. It dissolves in soid, yielding a yellow solution, which affords a brown precipitate with prussiate of potash. Heated gently it becomes orange-yellow. In the reducing flame changes to green, but does not fuse.

Accompanies pitchblende in Cornwall, at Joachimstahl in Bohemia, and at Symphorien in France. At the Callington tin mine, Cornwall, it has been observed in masses of considerable size, which were said to be quite free from carbonic acid. It is found sparingly with columbite and uranite at the feldspar quarry near Middletown, Ct.

LIEBIGITE, J. L. Smith, Am. J. Sci. [2], v, 336, and xi, 259.

In mammillary concretions, or thin coatings: cleavage apparent in one direction.

H.=2-2.5. Lustre of fracture vitreous. Color beautiful apple-green. Transparent.

=100. Analysis by J. L. Smith, (loc. cit.):

₩ 88·0. Ö 10·2. Ĥ 45·2. Ča 80

The Heramohalite of J. Jurasky, (Ost. Blat. f. Lit. 1847), from near Königsberg is Hungary, has the same composition as alunogen. It occurs in crystalline crusts and also in six-sided tables, with two angles of 92° and four of 134°, the crystallination monoclinic. G.=16-17. Jurasky obtained for its composition, Al 1430, Re 2·15. \$ 36.75, \$\hat{H}\$ 44.60, insoluble 2·01=99.81.

Occurs in thick druses with iron vitriol.

NATIVE ALUM.

Under the head of Alum are included several compounds, monometric in crystallization, having the general formula RS+AB+ 24H. R standing for different bases, as potash, soda, magnesia, protoxyd of manganese, &c. Crystals octahedral, (f. 11, 16). Soluble in water. Taste astringent, more or less like common alum.

1. Potash Alum. Native Alum. Kalialaun.

Usually fibrous, or as an efflorescence. H = 2-2.5. G = 1.75. Vitreous, the fibrous varieties sometimes somewhat pearly. Color white. Transparent-opaque

Composition.—KB+KlB²+24H=Sulphate of potash 18.4, sulphate of alumine 36.2, and water 45.4. B.B. fuses in its water of crystallization, and froths, forming a spongy mass. Soluble in from 16 to 20 times its weight of cold water, and in little more than its weight of boiling water.

Effloresces on argillaceous minerals, and more particularly alum slate. Whithy, in Yorkshire, is a noted locality, also Hurlet and Campsie near Glasgow. Also tained at the volcances of the Lipari isles and Sicily. Cape Sable, Maryland, at fords large quantities of alum annually.

2. Soda Alum. Solfatarite, Shep. Alun sodifere, Duf. Natronalaun. In fibrous crusts or masses. H.=2-3. G.=188. Resembles the preceding, but more soluble.

Composition.—NaS+XIS+24H=Sulphate of soda 15.5, sulphate of alumina 374. water 47 1. Analysis by Thomson, (Ann. Lyc. N. Y., 1828): From St. Juan near Mendoza, Al 12 00, Na 7 96, S 37 70, H 41 96—99-62.

Occurs on the island of Milo, at the Solfatara near Naples, and near Mendoza, on the east of the Andes.

Thomson found for the composition of a soda alum from Southern Peru, which he called Subsesquisulphate of alumina (L. and E. Phil. Mag. xxii, 188), X1 22 55, Na and S 6.50, S 32.95, H 39.20=101.20. G.=1.584.

3. Magnesia Alum. Pickeringite, Hayes. Magnesia-alaun, Ramm. Talkerdealaun, Kobell.

In white fibrous masses, and in efflorescences like the preceding. Lustre silkt. Becomes opaque on exposure.

Composition.—MgS+XlS*+24H=Sulphate of magnesia 13.4, sulphate of alumina 88.3, and water 48.3. Analysis by A. A. Hayes, (Am. J. Sci. xlvi, 360):
From near Iquique, S. A., Xl 12.130, Mg 4.682, S 36.322, H 45.450, Fe and Ms 0.430, Ca 0.126, HCl 0.604=99.744.

Part of the magnesia is often replaced by protoxyd of manganese, producing a MANGANO-MAGNESIAN ALUM.

Stromeyer obtained (Pogg. xxxi, 187) for a specimen from a cave near Bosjesman river, southern Africa:

基1 11·515, Mg 3·690, Mn 2·167, 5 86·770, H 45·789, KCl 0·205=100·86.

It covers the floor of the cave to a depth of six inches. The roof is a reddish quartzose conglomerate, containing magnesia and pyrites. It rests on a bed of epsom salt, 11 inches thick.

MANGANESIAN ALUM. APJOHNITE, Glocker. Mn8+4183+24H=Sulphate of masganese 16:3, sulphate of potash 37:0, water 46.7. Occurs near Lagoa-Bay, in South Africa.

salt of phosphorus becomes dull yellow, and forms a colorless pearl, containing floating silica. Dissolves in nitric acid, and the solution is clouded on the addition of water.

Bismutite occurs at Schneeberg and Johanngeorgenstadt, with native hismuth, and near Hirschberg in Russian Voigtland, with brown iron ore, native bismuth, and bismuth glance. Also in the gold district of Chesterfield, S. C., in porous yellowish masses, sometimes reddish from oxyd of iron. Surface of fracture white and vitre-It resembles somewhat electric calamine. It is supposed to proceed from native bismuth.

III. CARBONATES WITH CHLORID OR FLUORID.

PARISITE, RC+RF!

CERASINE, Pb C+Pb Cl.

PARISITE, L. di Medici-Spada. Mussonite, Duf.

Hexagonal. In elongated double six-sided pyramids, with truncated apex; basal angle 164° 58', pyramidal 120° 34'. Cleavage:

basal, very perfect.
H.=4.5. G.=4.35. Vitreous; cleavage face pearly or resin-

ous. Color brownish-yellow; streak yellowish-white.

Composition.—8RC+2CaF+RH, in which R=Protoxyd of cerium, lanthanum and didymium, Bunsen. Perhaps RC+RF with CeH as impurity, Ramm. Analyses by Bunsen, (Ann. d. Ch. u. Pharm. liii, 147):

	Õ	Ce (with La and D)	Ĉa	Ĥ	CaF
1.	23.51	59.44	8.17	2·3 8	11.51
Q	22.84	60-26	₹-1 5	9.49	10.58

Yields on heating, carbonic acid and water, and becomes brownish, but does not fuse. A clear glass with borax, yellow while hot, and colorless cold. Dissolves slowly with effervescence in muriatic acid.

From the emerald mines of the Musso valley, New Grenada.


CERASINE, Beud. Corneous Lead. Murio-Carbonate of Lead. Chloro-Carbonate of Lead, Thomson. Plomb Chloro-Carbonate, Duf. Bleihornerz. Phosgenite, Breit, Hornblei, Haus.

Dimetric. $0:1i=132^{\circ}40'$; a=1.0847. Observed planes, as in the annexed figure, with also 22 and i2.

 $O: 1=123^{\circ} 6'$. $I: 1=146^{\circ} 54'$. 1:1 (pyr.)=107° 21′. *I*: *ii*=135°. $O:22=112^{\circ}24'.$

 $O: I=90^{\circ}.$

Cleavage: I and ii bright; also basal. H = 2.75 = 3. G = 6 = 6.3; 6.305, Ramm. Lustre adamentine. Color white, gray, and yellow. Streak white. Transparent—translucent. Rather sectile.



Composition.—Pb Cl+Pb C=Chlorid of lead 51, carbonate of lead 49=100. Analysis by Klaproth, corrected by Berzelius, (Beit. iii, 141, Schw. J. xxii, 281):

Muriatic acid 14.0, Carbonic acid 6.0=105.5. Oxyd of lead 85.5,

EPSOMITE, Boud Epsom salt. Bittermit, Worn. Sulphate of Magnesia.

Trimetric and generally hemihedral, in the octahedral modifications. $I: I=90^{\circ}$ 34′, $O: 11=150^{\circ}$ 2′; $a:b:c=0.5786: 1:101.15:11(basal)=59^{\circ}$ 27′, 11:11(basal)=59° 56°. Cleavage: brachydagonal, perfect. Also in botryoidal masses and delicately fibrosecrusts.

II.=2.25. G.=1.751. Lustre vitreous—earthy. Streak and color white. Transparent—translucent. Taste bitter and saline.

Composition.—Mg 3+7H, when pure—Magnesia 16-26, sulphurie acid 27H, water 51-22. B.B. deliquesces, but is difficultly fasible before the water of crystalization is driven off. Very soluble in water. Does not effervence with the scit. Common in mineral waters, and as an efforescence on rocks. In the forms static exists at Epsom. At Idria, in Carniola, it occurs in silky fibrea, and is hence called hairsalt by the workmen. Also obtained at the gypsum quarries of Matmartre, near Paris; in Fitou, Dep. of the Aude, France; in Aragon and Cambria Brica, where it forms a layer 1½ inches thick. The salt from this last locality was analyzed by Stromeyer, and found to contain sulphate of magnesia 42-654, sulphate of manganese 7-667, water 49-243—99-364. The roof of the grette is a quartzone conglomerate, containing manganese and pyrites.

The floors of the limestone caves of Kentucky, Tennessee, and Indiana, are in many instances covered with Epsomite, in minute crystals, mingled with the earth.

The floors of the limestone caves of Kentucky, Tennessee, and Indiana, are a many instances covered with Epsomite, in minute crystals, mingled with the eart. In the Mammoth Cave, Kentucky, it adheres to the roof in loose masses like move balls. It effloresces from the calcareous sandstone, ten miles from Coeymana, as the east face of the Helderberg, N. Y. Said to occur also over the California plains, east of San Diego, (Am. Jour. of Sci. [2], vi, 389). Also effloresces from a pytitierous serpentine at Marmora, Canada West.

Sulphate of magnesia is dimorphous. According to Haidinger and Mitscherlich, the above described form is produced when crystallization takes place below 15° C. (60° F), but a monoclinic form, between 25° C and 30° C.

GOSLARITE, Haid. Zinc Vitriol. Sulphate of Zinc. Zinc Sulfate, H. White Vitriol.

Trimetric: $I: I=90^{\circ} 42'; \ \theta: 1\overline{\imath}=150^{\circ} 10'; \ a:b:c=0.5735:1:1.0123.$ Observed planes $I, \ \widetilde{\imath}, \ \widetilde{\imath}, \ \widetilde{\imath}, \ \widetilde{\imath}, \ 1\overline{\imath}, \ 1\overline{\imath}, \ 1.2\overline{\imath}.$ $1\overline{\imath}: 1\overline{\imath} \text{ (top)} 120^{\circ} 20', 1\overline{\imath}: 1\overline{\imath} \text{ (top)} = 120^{\circ} 3', \ \theta: 1=140^{\circ} 57\frac{1}{2}', \ 1:1 \text{ (mac.)} = 127^{\circ} 27', \ 1:1 \text{ (brach.)} = 126^{\circ} 45'.$ Cleavage: $\widetilde{\imath}$ perfect.

II.=2-2.5. G.=2.036; 1.9-2.1. Lustre vitreous. Color white. reddish, bluish. Transparent—translucent. Brittle. Taste astringent, metallic and nauseous.

Composition.—ZnS+7f1=Sulphuric acid 27.9, oxyd of zinc 28.2, water 43.9=100. In a matrams yields water. B.B. intumesces, gives off its sulphuric acid, and covers the charcoal with a white coating of oxyd of zinc. Easily soluble in water.

This salt is supposed to be formed by the decomposition of blende. It occurs at the Rammelsberg mine in the Hartz, at Schemnitz in Hungary, at Fahlun in Sweden, and at Holywell in Wales. It is of rare occurrence in nature.

It is manufactured for the arts, and is very extensively employed in medicine and dyeing. White vitrol, as the term is used in the arts, is the sulphate of zinc in a granular state, like loaf sugar, produced by melting and agitation while cooling.

Blackens in the flame of a candle, and becomes attractable by the magnet. B.B. on charcoal yields a vegetable odor, and is decomposed, becoming at first yellow, then black, and finally red.

It occurs at Kolosoruk, in Bohemia, and in the opinion of Rivero, has resulted from the decomposition of succulent plants; also in brown coal at Gross-Almerode, in Hessia; and according to T. S. Hunt, at C. Ipperwash, Canada, in shales; soft, earthy, sulphur yellow, (Logan's Report, 1850).

CONISTONITE, R. P. Greg, Jr., Am. J. Sci. [2], xvii, 388, 440, 1854.

Trimetric. Observed angles, (Greg): $I: I=97^{\circ}$ 5', $1\bar{\imath}: 1\bar{\imath}$ (top) =86° 30', $1\bar{\imath}: 1\bar{\imath}$ (top)=96° 50', $I: 1\bar{\imath}=117^{\circ}$ 30', $1\bar{\imath}: 1\bar{\imath}=121^{\circ}$ 0'. Faces I brightest. Cleavage none.

H.=2. G.=2.052. Lustre vitreous. Colorless. Transparent to translucent. Slightly sectile. Fracture small conchoidal, uneven.

Composition.—Ca 6+7H, M. F. Heddle, who obtained in his analysis, Oxalic acid 28 017, lime 21 055, sods and magnesis 0 822, water 49 155=99 049.

Soluble without effervescence in muriatic or nitric acid. Heated gives off wa-

Soluble without effervescence in muriatic or nitric acid. Heated gives off water and carbonic oxyd, and is converted into a carbonate, and then effervesces with acids.

From the copper mine near Coniston in Cumberland. Largest crystals not more than one-eighth of an inch across, and in general form not unlike the double four-sided crystals of Edingtonite.

THIERSCHITE, Liebig, Ann. d. Ch. u. Pharm. lxxxvi, 118, April, 1858.

An oxalate of lime, occurring as a grayish, warty, and somewhat opaline incrustation, about a line thick, on the marble of the Parthenon, Athens. A complete analysis has not yet been made. Its origin is attributed to the action of some kind of vegetation on the marble. It is probably identical with whewellite.

· PYROMELINE, v. Kobell. Nickel Vitriol, T. S. Hunt.

In capillary interlacing crystals, apparently rhombic, or greenish-white efflorescence. Taste metallic astringent.

Composition.—A hydrated sulphate of nickel. Heated, gives off water, and the residue, which is perfectly soluble, is simply sulphate of nickel.

At Wallace mine, Lake Huron, upon a sulphuret of nickel and iron, mostly as

efforescence.

This description is from Hunt. Pyromeline of v. Kobell, (J. f. pr. Ch. lviii, 4 is probably the same species. It occurs as an earthy crust, pale yellow, with natibismuth and arsenical nickel at the Friekerichs mine near Bayreut. B.B. interest ces and shoots out into worm-like processes, (whence the name), becoming pale yo how; with a stronger heat fuses to a gray magnetic bead; gives reactions of a k drous sulphate of nickel mixed with some arsenic acid.

JOHANNITE. Sulphate of the Protoxyd of Uranium. Uranvitriol.

Monoclinic. $C=85^{\circ}$ 40', $I: I=69^{\circ}$. Crystals flattened, an nom one to three lines in length; arranged in concentric druses reniform masses.

H.=2-2.5. G.=3.19. Lustre vitreous. Color beautiful em rald-green, sometimes passing into apple-green. Streak pale Transparent—translucent; sometimes opaque. Taste bitter, rath than astringent.


Composition.—According to John's researches, a hydrous sulphate of the protest of uranium.

Somewhat soluble in water. Solution precipitated chestnut-brown by prusis of potash, yellowish-green by alkalies, and in brown flocks by an infusion

Discovered by John near Joschimstahl in Bohemia, after whom the species named. Found also at Johanngeorgenstadt; and reported from the Middletov feldspar quarry by Shepard.

URANGREEN, Hartmann, (Urangrün, Uranchalzit). A basic sulphate of the oxyof copper and uranium. From Joachimstahl.

GLAUBER SALT. Sulphate of Soda. Mirabilite, Haid. Exanthalose, Beude Soude Sulfatée, H. Glaubersalz.



Cleavage: ii perfect. Usually in efflorescent crusts. H.=1.5-2. G.=1.481. Lustre vitreous. Color white. Tran parent—opaque. Taste cool, then feebly saline and bitter.

It is used in the manufacture of a varnish, and for obtaining succinic acid and oil of amber, which it affords at a low temperature.

COPALINE, Hausmann. Fossil Copal, Highgate Resin, Aikin, Jameson.

Like the resin Copal in hardness, color, lustre, transparency, and difficult solubility in alcohol. Emits a resinous odor when broken.

Composition.—C46 H29 O. Analysis by Johnston, (Phil. Mag. xiv, 87, 1889):

Carbon 85.408, Hydrogen 11.787, Oxygen 2.669, Ashes 0.136=100. Volatilizes in the air by a gentle heat, and burns easily with a yellow flame and much smoke. Slightly acted upon by alcohol.

Comes from the blue clay of Highgate Hill, near London, from whence it is call-

ed Highgate resin.

Another resin, resembling the fossil copal in external appearance, has been examined by Johnston, and found to consist of Carbon 85·133, hydrogen 10·853, ashes 8·256=99·242, or nearly C⁴H². It occurs in the form of flattened drops or coatings on cale spar, on the walls of a dyke of trap, at the old lead mine in Northumberland, called Settling Stones. Color pale yellow to deep red, with a pale green opalescence. G.=1·16-1·54. Hard, but brittle. Does not melt at 400° F., but burns in the flame of a candle with an empyreumatic odor. Insoluble in water and nearly so in alcohol.

A pale honey-yellow resin from the East Indies, is described by Kengott, (Min. Unters. ii, 81, 153). H.=2. Streak white. G.=1.058. Heated, fuses to a clear fluid, burns with a yellow light and aromatic smell, and is consumed without residue. But little soluble in alcohol, and largely in concentrated sulphuric acid. Duflos found it to contain C 85.78, H 11.50, O 2.77=100, or near the Highgate resin.

MIDDLETONITE, J. F. W. Johnston, Phil. Mag. xii, 261, 1838.

In rounded masses, seldom larger than a pea, or in layers a sixteenth of an inch or less in thickness, between layers of coal.

Brittle. G.=1.6. Lustre resinous. Color reddish-brown by reflected light, and deep red by transmitted; powder light-brown. Transparent in small fragments. No taste or smell. Blackens on exposure.

Composition.—C²⁶ H²⁶+H O; Carbon 86:437, hydrogen 8:007, oxygen 5:568=100:007, Johnston. Not altered at 400° F., (210° C.); on a red cinder, burns like resin. Boiled in alcohol, ether, or oil of turpentine, the liquid becomes yellow, but dissolves only a mere trace of the resin. Softens and melts in boiling nitric acid, with the emission of red fumes; a brown flocky precipitate falls on cooling. Soluble in cold concentrated sulphuric acid.

Occurs about the middle of the main coal on Haigh Moor seam, at the Middleton

collieries, near Leeds; also at Newcastle.

RETINITE. Retinasphaltum, Hatchett, Phil. Trans. 1804.

Occurs in roundish masses.

H.=1—2.5. G.=1.135, Hatchett. Lustre often earthy externally, but slightly resinous in the fracture. Color light yellowishbrown, sometimes green, yellow, red or striped. Subtransparent—opaque. Fracture conchoidal. Often flexible and elastic, when first dug up; but it loses this property on exposure.

Composition .- Analyses: 1, 2, H. Rose, (Pogg. xxvii, 309); 3, Pridesux, (exrected):

Мg 3 ₽e ₩l Βi Ċĸ Ħ

1.95 26.11 29-67=101-34,Res 1. Foliated, Copiapite, 89.60 2.64 1.37 3178 28.11 0.28 1.43 1-91 36.56=100.58, "

2. Mbrous, Stypticite, 8. Chili, Mbroferrite. 86.7=100, Prideaux **28.9** 84.4

The first gives the formula Pe'S'+18H, and the second (called Stypticite) +21H. But it is doubted that they are pure chemical compounds. the Mbroferrite of Prideaux, formula Fe'S'+27H.

Found incrusting the Coquimbite, in the district of Copiapo, a prevince

Coquimbo.

The Pitticite of Beudant, from Fahlun, (or Vitriol Ochre), contains, according we Berzelius, Sulphuric acid 15-9, peroxyd of iron 62-4, water 21-7=Fe*S+6H.

A stalactitic iron sinter from Hackelsberg, (Pogg. lxxxix, 489), afforded Hodstetter, S 15-19, Fe 64-34, H 20-70, Pb 0-61, Cu and As, trace=100-84. Asothe. from Rammelsberg in the Hartz, afforded Jordan, (J. f. pr. Ch. ix, 95), S 97%, Fe 68-750, H 15-524, Zn 1-293, Cu 0-500, impurities 4-137=100.

Misy. At Rammelsberg, near Goslar in the Hartz, an impure sulphate of the peroxyd mixed with other sulphates is called Misy. It occurs in small crystaline scales pearly in lustre or subvitreous, color sulphur-yellow; scales rhombic table with the scute lateral edge truncated. Decomposed in water, but not properly selected to the scale of the uble. Analysis by Dr. List, (Ann. Chem. u. Pharm. lxxiv, 289):

 \vec{S} 42.922, \vec{F} e 30.066, \vec{Z} n 2.491, \vec{M} g 2.812, \vec{K} 0.818, \vec{H} 21.391=100.

In another trial \$\tilde{8}\$ 48.208, \$\tilde{F}e\$ 30.365. Excluding impurities, the composition becomes \$\tilde{8}\$ 47.075, \$\tilde{F}e\$ 40.622. \$\tilde{H}\$ 12.313=\$\tilde{F}e^2\tilde{S}i^2+6\tilde{H}\$, or Copiapite with two-third less of water.

APATELITE, Meillet, Ann. d. Mines, [4], iii, 808.


Resembles Copiapite.

Composition. -2Fe353+3H. Analysis by Meillet, (loc. cit.): S 42.90, Fe 58.30, H 3.96=100.16.

It occurs at Meudon and Auteuil, in small friable nodules or balls of a clear yellow color, disseminated in an argillaceous bed connected with the plastic clay.

TECTIZITE, Breit.—Supposed to be a hydrous sulphate of peroxyd of iron; be composition not ascertained. Occurs in small pyramidal and acicular crystals as massive. H.=15-2. Color clove-brown. Easily soluble in water, and attract moisture readily. From near Schwarzenberg in Saxony, and Bräunsdorf in the Erzgebirge.

ALUNITE. Alum Stone. Alaunstein. Alumine sous-sulfatée alkaline, H.



Rhombohedral. $R: R = 89^{\circ}$ 10', 0 $R = 124^{\circ} 40'$, Breit.; a = 1.2523. (i) served planes R, θ , and the rhombohe drons $\frac{6}{7}$, $\frac{1}{64}$, $-\frac{6}{5}$, and -2, Breit.

O: 2=109° 4'. $O: \frac{1}{64} = 178^{\circ} 42^{\circ}.$ $\frac{1}{6}: \frac{1}{6} = 82^{\circ} 26^{\circ}.$ $\frac{1}{2}: \frac{1}{2} = 70^{\circ} 8^{\circ}.$ $0:\frac{6}{3}=119^{\circ}\ 57'$. $O: \frac{3}{7} = 128^{\circ} 55.'$

Cleavage: basal nearly perfect; R indistinct. Also massive having a granular or impalpable texture.

II. =3.5 -4. (1. =2.58 -2.752. Lustre of R vitreous, base plane somewhat pearly. Color white, sometimes grayish of

PIAUZITE, Haidinger, Pogg. Ann. lxii, 275.

An earthy resin of a brownish-black color, occurring massive. Streak yellowish-brown.

H.=1.5; G.=1.220.

Fuses at 315° C. (600° F.), and burns with an aromatic odor and much smoke, leaving 5°96 per cent. of ash. Soluble in ether and caustic potash, also largely in absolute alcohol. Heated in a glass tube a yellowish oily fluid is distilled, having an acid reaction.

From brown coal at Piauze near Neustadt in Carniola.

WALCHOWITE, Haidinger.

In yellow translucent masses, often striped with brown. Lustre resinous. Fracture conchoidal. Translucent to opaque. H.=1·5—2. G.=1·0—1·069; an opaque variety 1·035.

Composition.—C12 H°O, Schrötter, or 3C4H³+O, Ramm.=80·41 C, 10·66 H, 8·93 O. Fuses to a yellow oil at 250° C., and burns readily: becomes transparent and elastic at 140° C. Forms a dark brown solution in sulphuric acid; slightly soluble in other.

In brown coal at Walchow, and formerly called Retinite. Boussingault found a

similar mineral near Bucaramanga in New Grenada.

BITUMEN. Asphaltum. Petroleum. Mineral Pitch. Bergpech. Bergtheer, Haus. Mineral Oil. Naphtha. Erdöl. Steinöl. Maltha. Seneca Oil. Naphte, Beud.

Bitumen includes several distinct species, the two prominent of which are Naphtha and Asphaltum.

NAPHTHA, (Steinöl).—Liquid and colorless when pure, with a bituminous odor. G.=0.7—0.84. Composition.—C. Ha. In nature often combined with asphaltum, and containing also parraffine and other substances.

Asphaltum.—Solid; black and brownish-black, with a conchoidal brilliant fracture. G,=1-1·2. Odor bituminous. Fuses at 100° C., and burns with a bright flame. An asphaltum from the island of Brazza, Dalmatia, consists, according to Kersten, (J. f. pr. Chem. xxxv, 271), of petrolene (volatile oil) 5·0, brown resin soluble in ether 20·0, asphaltene (bitumen insoluble in alcohol and ether) 74·0, yellow resin soluble in alcohol 1·0=100·0

There are also earthy varieties, called earthy and slaggy mineral pitch. Petroleum is a dark-colored fluid variety, containing much naphtha. Maltha or Mineral tar is a more viscid variety.

Asphaltum is abundant on the shores of the Dead Sea. It occurs also in reniform stalactitic masses at Matlock in Derbyshire; in granite, with quartz and fluor, at Poldice, in Cornwall; in cavities of chalcedony and calc spar, in Russia, and other places. Naphtha issues from the earth in large quantities in Persia and the Birman empire; at Rangoon there are upwards of five hundred naphtha wells, which afford annually 412,000 hhds. A remarkable lake of bitumen occurs on Trinidad, which is one and a half miles in circumference. The bitumen is solid and cold near the shores, but gradually increases in temperature and softness towards the centre, where it is boiling. The solidified bitumen appears as if it had cooled as the surface boiled in large bubbles. The ascent to the lake from the sea, a distance of three quarters of a mile, is covered with a hardened pitch, on which trees and vegetables flourish, and about Point La Braye the masses of pitch look like black rocks among the foliage. The lake is underlaid by a bed of mineral coal, (Manross).

In the peninsula of Apcheron, on the western shore of the Caspian, napitisrises in vapor through a marly soil, and is collected by sinking pits several varies in depth, into which the naphtha flows. Near Amians in the state of Parma, is a shundant spring. Near Alfreton, England, naphtha has been discovered.

Petroleum is met with at Kenhawa in Virginia, Scotsville, Ky., Oil Creek in Venango Co., Penn., Duck Creek, in Monroe Co., Ohio, and Liverpool, Ohio. R va formerly collected and sold by the Seneca and other Indians, and is hence called Seneca or Genesee oil. Also at Inniskillan, Canada West, the inspissated petroleum in some places is two feet deep. (Logan's Geol. Rep. 1852, 90.)

Naphtha affords both fuel and lights to the inhabitants of Badku, on the Capita.

Naphtha affords both fuel and lights to the inhabitants of Badku, on the Capita. It is also employed in Persia and the Burman empire as a lotion in cutasesseruptions, and as an embrocation in bruises and rheumatic affections. It is exployed for various purposes in the arts, particularly in the manufacture of variant, and as a substitute for oil in the formation of oil paint, it being preferred on access of its rapid evaporation and drying.

Bitumen, in all its varieties, was well known to the ancients. It is reported to have been employed in the construction of the walls of Babylon, and at Agrigatum it was burnt in lamps, and called Sicilian oil. The Egyptians also made used it in enbalming. Two ship loads of the Trinidad pitch were sent to England by Admiral Cochrane, but it was found that the oil required to render it fit for us, exceeded in expense the cost of pitch in England, and the project of employing it was therefore abandoned.

Asphaltum is a constituent of the kind of varnish called Japan; it is also make into a cement for lining cisterns, and with ground stone into a material for pavements.

Naphthadil. A substance derived from naphtha. It is black; weak, greasy laste; copper-brown in fracture. Does not change in the light. Fuses at the same temperature as wax, and burns with a clear flame, (Von Leonh. J. 1846, 84).

IDRIALINE. Idrialite, Schrötter, Nicol. Quecksilberbranders.

Massive, with a greasy lustre, a grayish or brownish-black color, and a blackish streak inclining to red. Opaque. H.=1-1.5. G.=1.4-1.6.

Composition.—According to Bödeeker, C 91 828, H 5 299, O 2873, (Kengett's Min. Forsch. i, 253); formula C4 H¹⁴+O. The distillation of the bituminous earth at Idria affords a product consisting of C 94 568, H 6 459, with the formula C4, which is the radical of the Idrialine. Insoluble in water, and little so in alcohol of ether. Fuses at 400° F.

Occurs mixed with cinnabar at Idria. It is sometimes called, from its combustibility, quecksilberbranders or inflammable cinnabar.

PYROPISSITE, Kengott, Min. Forsch., 1850, 1851, p. 148.

Like an earthy brown coal in appearance. G.=0.493-0.522. Color dull yellowish brown, opaque. Streak shining and greesy. Feel greasy. Fracture earthy.

Burns readily with a brownish-yellow flame and a weak aromatic odor. Heated, fuses to an asphaltum-like mass, which is porous, little soluble in alcohol and large ly in oil of turpentine. Burns like bitumen. Little soluble in muriatic or nitre acid, and largely so in sulphuric.

Forms a layer six to eight inches thick in brown coal near Weissenfels. According to Marchand, affords on distillation 62 per cent. of paraffine, one pound of the mass giving three cubic feet of illuminating gas.

BREWSTOLINE.

Fluid. Colorless. Transparent. Expands one-fourth its size by an increment of 30° F., or is nearly 32 times more expansible than water, by an increment of 30° of heat at the temperature of 50°.

Occurs in minute cavities in crystals of topaz, chrysoberyl, quartz crystals from Quebec, and amethyst from Siberia, where it was detected by Sir David Brewster. We have thought proper to recognize this fluid among minerals and name it, although yet imperfectly described. The fluid expands with the heat of the hand. Its refractive power is less than that of water. It was sometimes indurated in the cavity like a resin. On exposure, the fluid undergoes quick motions and changes, and finally leaves a residue of minute particles, which from the moisture of the hand alone, suddenly became fluid again, and extended and contracted as before. This was indefinitely repeated. The residue is volatilized by heat, and dissolves in the acids without efferrescence.

CRYPTOLINE.—A second fluid was also distinguished in the same crystals that contained the preceding, and often in the same cavities; yet they were not miscible, and remained distinct. On exposure it hardens speedily into a yellowish transparent resin-like substance, not volatilizable by heat, nor soluble in water or alcohol, but rapidly dissolving with effervescence in sulphuric acids. Nitric and muriatic acids also dissolve it. Refraction index nearly that of water. [See further Edinburgh Royal Trans. vol. x; also Am. J. Sci. xii, 214, 1827].

ELATERITE, Hausmann. Mineral Caoutchouc. Elastic bitumen: Elastisches Erdharz. Bitume elastique.

In soft flexible masses.

G.=0.9053—1.233, the Derbyshire variety. Lustre resinous. Color blackish-brown, of various shades. Subtranslucent; sometimes presents a brilliant dark orange-red color by transmitted light. Flexible or elastic.

 Composition.—Analyses by Johnston, (Brewst. J. xiii, 22, 1838);

 Carbon, 85:474
 84:385
 83:671

 Hydrogen, 13:288=98:757
 12:576=96:961
 12:535=96:206,

showing that it is probably allied to ozocerite and hatchettine. M. Henry (Ann. des M. vii, 269) found 36.75 to 40.10 per cent. of oxygen in his analyses, and the constant loss in Johnston's is supposed by him to have been oxygen. Takes fire readily, and hurns with a lively vellow flame giving out a hit unique oder.

and burns with a lively yellow flame, giving out a bituminous odor.

This species was first observed in Derbyshire, at the forsaken lead mine of Odin, by Dr. Lister, in 1678, who called it a subterranean fungus. In 1797, it was accurately described by Hatchett, in the Linnæan Transactions, iv, 146. It has since been found in a coal mine at Montrelais, at the depth of 230 feet; and according to Hausmann, (Handbuch, iii, 278), it occurs at Neufchatel and on the island of Zante. A similar material has been met with at Woodbury, Ct.

SCHEERERITE, Stromeyer.

Monoclinic. In loosely aggregated crystalline grains and folia; also in minute acicular crystals, deposited in small cavities in coal. Soft. G.=0.65, Macaire Prinsep. Lustre pearly or resinous; feebly shining. Color whitish or gray. More or less translucent. Easily frangible. Tasteless. Inodorous. Feel not greasy. At

small brilliant crystals with malachite in a quartzose rock near Roughten-Gil, is Cumberland; and at Retzbanya. The Krisuvigite occurs in small beds at Krisuvigit occurs in small beds at Krisuvigit occurs.

Brochantite was named by Levy after Brochant de Villiera.

LETTSOMITE, Percy. Velvet Copper Ore. Cuivre Velouté, Levy. Kupfersammen.

Occurs in spherical globules or in druses consisting of short delicate fibres, and having an appearance like velvet. Color des smalt-blue. Lustre pearly.

Composition.—(Cu⁶S+3Ĥ)+(ĂlS+9Ĥ) Rammelsberg=Sulphuric acid 16.78, and of copper 49.85, alumina 10.76, water 22.59. Analyses by J. Percy, (Phil. Mag. [3] xxxvi, 100):

 S
 Al
 Fe
 Cu
 Al

 15·39
 11·70
 43·16
 23·06=98·30.

 14·12
 11·06
 1·18
 46·59
 23·06, insol. 2·35=98·36.

Occurs sparingly at Moldawa in the Bannat, coating the cavities of an early indicated oxyd of iron; and according to Percy, a white amorphous substance comparingly with it, consisting of alumina and sulphuric acid.

MEDJIDITE, J. L. Smith, Am. J. Sci. 2d ser. v, 387. Sulphate of Uranium Lime.

Massive, with an imperfectly crystalline structure.

H.=2.5. Lustre vitreous in the fracture. Color dark amber Transparent.

Composition.— \$\overline{\text{CaS}} + \overline{\text{CaS}} + 15\overline{\text{H}}\$, according to Smith. In a matrass easily ries water. At redness blackens, being converted into oxyd of uranium and sulpsis of lime. Dissolves readily in dilute muristic acid.

of lime. Dissolves readily in dilute muriatic acid.

Occurs near Adrianople, Turkey, on pitchblende, associated with Liebigite's some places with crystals of sulphate of lime; also at Joachimstahl, with Liebigite on Uranium ore. Supposed to be due to the decomposition of pyrites. External often dull from loss of water. It was named in honor of the Turkish sultan Abs. Medjid.

IV. BORATES.

Boracic acid occurs in but few minerals; viz. Datholite, Danburite, Ar nite, Tourmaline and Warwickite, with the following. It is a remarkable fact that in all of them, as far as known, the crystallization is either hem hedral or oblique. Boracite and Rhodizite are hemihedral monometric Danburite, hemihedral trimetric; Tourmaline, hemihedral rhombohedral while Danburite and Axinite are triclinic. In Tourmaline and Axinite boracic acid acts the part of a base; and if the same may be admitted; be the case in Boracite, it is in composition as well as form, related to the protoxyds and magnetite.

609

ľ


HARTITE, Haidinger, Pogg. liv, 261.

Monoclinic. Angle I:I of oblique rhombic prism about 100° , P:a = about 120° . Cleavage only in traces. H.=1. G.=1.046. Lustre somewhat greasy. Color white. Translucent. Brittle.

Composition.—C⁶ H⁵; Carbon 87 478, hydrogen 12 048, Schrötter. Fuses at 165° F., (74° C.), to a clear fluid, and at a high temperature distills. Dissolves easily in ether, less readily in alcohol,

and crystallizes from each on evaporation.

Hartite resembles wax. It is distinguished from Scheererite by its crystallization and the temperature of fusion, as well as action before the blowpipe. It occurs in brown coal at Oberhart in Austria.



Resembles Hartite. Massive, but crystallizes from a naphtha solution in needles of the trimetric system. Color white. Without taste or smell. Pulverizes in the fingers. Fuses at 210° C., and distills at 260° C.

Composition.—C 86 H 17 O 2 . C 78-26, H 10-92, O 10-82, Schrötter. Little soluble in ether.

From the brown coal of Oberhart, Austria.

The Bogbutter of Williamson, (Butyrite, Glocker), from an Irish peat swamp, contains C 75-05, H 12-56, O 12-39=C**H**O*+HO. It fuses at 51° C., (124° F.), and dissolves easily in alcohol.

IXOLYTE. Ixolyt, Haidinger, Pogg. lvi, 845.

Amorphous. Occurs in bituminous coal.

H.=1. G.=1.008. Lustre greasy. Color hyacinth-red. Pulverized in the fingers, it becomes ochre-yellow and yellowish-brown. Thin fragments subtranslucent. Fracture imperfect conchoidal in the purer varieties.

Softens at 76 C., (169° F.), but is still tenacious at 100° C., (212° F.)—whence the name, from 166 and $\lambda \epsilon \omega$, to dissolve.

This species closely resembles the Hartite, but differs in the temperature of fusion and other characters. It occurs in a coal bed at Oberhart, near Gloggnitz.

HATCHETTINE, Conybears. Mineral Tallow.

Crystallized and amorphous in thin laminæ, like wax or spermaceti in consistency. G. at 60° F.=0.916. Lustre nacreous. Color white; black and opaque, after long exposure. Transparent. Feel greasy.

60

Composition.—Ca*B*+Mg*B*+18H=Boracic acid 477, lime 14.8, magnesia 103, water 27.7. Analyses by M. Hess, (Pogg. xxxi, 49):

B Ca Mg H
1. 49922 13298 10480 26330=100.
2. 4922 1374 1071 2638=100.

B.B. fuses to a clear glass, tinging the flame slightly green, and not becoming opaque. In a matrass affords water. Somewhat soluble in water, and yielding a slightly alkaline reaction. Dissolves easily in muriatic and nitric acids.

Hydroboracite was first observed by Hess, in a collection of Caucasian minerals. The specimen was full of holes filled with clay, containing different salts. It may be mistaken for gypsum, but is readily distinguished by its fusibility.

HAYESINE. Borate of Lime, Hayes. Borocalcite. Borsaurerkalk. Hydroborocalcit. Tiza.

In masses having a globular form, consisting of interwoven fibres. Opaque, snow-white, silky, and having a peculiar odor.

Composition.—CaB²+6H, Hayes—Boracic acid 45.98, lime 18.45, water 35.57. Analyses: 1, A. A. Hayes, (Am. Jour. Sci. [2], xviii, 95); 2, Bechi, (ib. xvii, 129):

B Oa H 1. Peru, 46:11 18:89 85:00=100. 2. Tuscany, 51:135 20:850 26:250=100.

Hayes observes in Am. J. Sci. xviii, 95, July, 1854, that the pure mineral does not contain soda, and the soda in the following analyses he attributes to impurities. Ulex obtained, (Ann. Ch. u. Pharm. lxx, 49), Boracic acid 49.5, lime 15-9, soda 84; water 25-8; and A. Dick, (Phil. Mag. [4], vi, 50), Boracic acid (by loss) 45-46, lime 14-82, soda 8-22, potash 0-51, sulphuric acid 1-10, NaCl 2-65, sand 0-32, I and P treez. Ulex gives the formula Na, 2Ca, 5B+10H. (Named Ulexite in last edition of this work, on the ground of a supposed difference in composition from the Hayesine).

Occurs over the dry plains near Iquique in Southern Peru, in white reniform masses, from the size of a hazlenut to that of a potato, where it is called tiza; the masses consist of interwoven silky fibres which rapidly absorb water, and have a slightly saline taste. It is associated with Pickeringite. The mineral analyzed by Professor Bechi forms an incrustation at the Tuscan lagoons.

BORAX. Tincal. Pounxa. Swaga. Zala. Borate of Soda.

 Monoclinic. $C=73^{\circ}\ 25'$, $I:I=87^{\circ}$, $O:2i=132^{\circ}\ 49'$; a:b:c=0.4906:1:0.9095. Observed planes as in the annexed figure, with also 4i. $O:I=78^{\circ}\ 40'$ and $101^{\circ}\ 20'$, $O:1=139^{\circ}\ 30'$, $O:2=115^{\circ}\ 53'$, $O:4i=114^{\circ}\ 51\frac{1}{2}$, O:ii=90', $ii:I=133^{\circ}\ 30'$. Cleavage: ii perfect; I less so; ii in traces. Plane of composition ii; $O:C=146^{\circ}\ 50'$.

H.=2-2.5. G.=1.716. Lustre vitreous-resinous; sometimes earthy. Color white; sometimes grayish, bluish or greenish. Streak white. Translucent — opaque. Fracture conchoidal. Rather brittle. Taste, sweetish-alkaline, feeble.

Composition.—NaB²+10H=Boracic 36.58, soda 16.25, water 47.17. B.B. puffs up, and afterwards fuses to a transparent globule, called the glass of borax. It is soluble in water; the solution changes vegetable blues to greens. With fluor spar and bisulphate of potash, it colors the flame around the powder a clear green.

Heated to 100° C., loses 78.5 per cent. of water. It resembles a black pitch. On heating the fresh mineral with potash, ammonia is given off.

Near Aussee, in Styria, in peat. The species is named after M. Doppler.

DINITE, Monoghini, Gaz. Med. Italiana, Firenze, Toscana, July, 1852.

An aggregation or druse of crystals. Cleavage none. Has the appearance of ice, with a yellow tinge due to a foreign substance. Tasteless. Fragile, and easily reduced to powder. Inodorous.

Insoluble in water; little soluble in alcohol, very soluble in ether, and in sulphuret of carbon. The ethereal solution on standing deposits large crystals of the dinite. Fuses with the warmth of the hand; heated in a close vessel distills over without undergoing any sensible decomposition. When melted it looks like a yellowish oil; crystallizes in large transparent crystals on cooling.

From a lignite deposit, at Lunigiana, Tuscany, where it was found by Prof. Dini.

MELLITE, H. Mellilite. Honey Stone. Mellate of Alumina. Honigstein, Werner.

Pyramidal edge=118° 4', and basal Dimetric; octahedral. edge 93° 22', Hauy; the latter 93° 1', Breithaupt; 93° 6', Kupffer. In short octahedrons, and also with the terminal or lateral solid angles or edges truncated. Cleavage octahedral, very indistinct. Also in massive nodules.

H.=2-2.5. G.=1.55-1.65; 1.636-1.642, Kenngott. Lustre resinous, inclining to vitreous. Streak white. Color honey-yellow, often reddish or brownish; rarely white. Transparent-translucent. Fracture conchoidal. Sectile.

Composition.—Āl m²+18Ĥ=Alumina 14·32, mellic acid 40·53, water 45·15. Anal-yees: 1, Klaproth, (Beit. iii, 114); 2, Wöhler, (Pogg. vii, 325):

Alumina, 16 14.5 Mellic acid, 46 Water, 98=100 K. 44·1=100, W.

Whitens in the flame of a candle, but does not take fire. Dissolves in nitric acid; decomposed by boiling water. In a matrass yields water.

Occurs in brown coal at Arten in Thuringia; at Luschitz near Bilin in Bohemia;

near Walchow in Moravia.

clear bead colored by iron; with salt of phosphorus a bead orange while hot, a purplish gray and opaque on cooling. Reaction of boracic acid.

Occurs in granular limestone two and a half miles S. W. of Edenville, N.1 with spinel, chondrodite, serpentine, etc. Crystals usually small and slender; so times over two inches long, and three-eighths of an inch broad.

V. PHOSPHATES, ARSENATES, ANTIMONATES, NITRATES.

1. ANHYDROUS.

1. APATITE GROUP.—Crystallization Hexagonal. Oxygen ratio of bases a saids, (exclusive of fluorid or chlorid), 8:5.

APATITE, Ĉa[®]P+[†]Ca(Cl,F). ZWIESELITE, (Fe, Mn)[®]P+[‡]Fe
OSTEOLITE, PYBOMORPHITE, Pb[®]P+[‡]PbCl.
CRYPTOLITE, Ĉe[®]P. MIMETENE, Pb[®]As+[‡]PbCl.

2. XENOTIME GROUP.—Crystallization Dimetric. Oxygen ratio 3:5.

XENOTIME, YP.

8 MONAZITE GROUP.—Monoclinic. Oxygen ratio 8:5 to 4:5.

Monazite, (Ĉe,La, Th)*P. Kuhnite, R*Ās

WAGNERITE, Mg P+Mg F. LAZULITE.

4. TRIPLITE GROUP.—Trimetric. Oxygen ratio 8:5 to 4:5.

TRIPHYLINE, RP! TRIPLITE, RP.

5. FISCHERITE GROUP.—Trimetric. Oxygen ratio 6:5.

Fischerite, \$\frac{1}{4}\hat{P}+8\hat{H}\$. Peganite, \$\frac{1}{4}\hat{P}+6\hat{H}\$.

Appendix. Hopeite, Amblygonite, Herderite, Carminite.

6. ROMEINE GROUP.

Romeine, R'SbSb.

APATITE, Werner. Phosphate of Lime. Spargelstein. Phosphorit, W. Aspara stone. Moroxite. Eupyrchroite, Emmons. Augustite. Pseudo-apatite, Br

Hexagonal: often hemihedral. $O:1=139^{\circ} 47'$; a=0.73? Figures 190, 191, and the annexed.

MAINE.

MT. ABRAHAM.—Andalusite, staurotide. ALBANY .- Beryl! green and black tourmaline, feldspar, rose quartz. ALBION.—Iron pyrites.

AROOSTOOK.—Red Hematite.

BINGHAM.—Massive pyrites, galena, blende, and alusite.

BLUE HILL BAY.—Arsenical iron, molybdenite! galena, apatite! fluor spar! black tourmaline, (Long Cove), black oxyd of manganese, (Osgood's farm), rhodonite, bog manganese, wolfram. BOWDOINHAM.—Beryl, molybdenite.

BRUNSWICK.—Green mica, garnet! black tourmaline! molybdenite. BUCKFIELD.—Garnet, (estates of Waterman and Lowe), iron ore. CAMDAGE FARM .- (Near the tide mills), molybdenite, (wolfram). CAMDEN. - Macle. CARMEL, (Penobscot Co.)-Gray Antimony. CORINNA.—Iron pyrites, arsenical pyrites. DEER ISLE - Serpentine, verd antique, abestus, diallage. DEXTER.—Galena, pyrites, blende, copper pyrites, green talc. DIXFIELD.—Native copperas, graphite.
FARMINGTON.—(Norton's ledge), pyrites, graphite, bog ore.
GEORGETOWN.—(Parker's island), beryl / black tourmaline.
GREENWOOD.—Graphite, black manganese. HARTWELL -Staurotide. LENOx.—Galena, pyromorphite. LEWISTON.—Garnet. Letohpield.—Sodalite, cancrinite, nepheline, zircon. LUBBO LEAD MINER.—Galena, copper pyrites, blende, pyromorphite, an ore of bismuth. MADRID. -Gold. NEWFIELD, (Bond's Mt.)-Mispickel, olive phosphate of iron in botryoidal masses. Paris. - Green ! red ! black, and blue tourmaline ! mica ! lepidolite ! feldspar, albite, quartz crystals ! rose quartz, blende. PARSONSFIELD.—Idocrase / yellow garnet, pargasite, adularia, scapolite, galena, blende. copper pyrites. Part.—Prehnite and calc spar, (above Loring's cove), quartz crystal, calc spar, analcime, apophyllite, agate, (Gin Cove). PERU.—Crystallized pyrites. Phipaburg. — Yellow garnet ! manganesian garnet, idocrase, pargasite, axinite, laumonite! chabazite, an ore of cerium? POLAND. —Idocrase. BAYMOND. - Magnetic iron, scapolite, pyroxene, lepidolite, tremolite, hornblende. RUMPORD.—Yellow garnet, idocrase, pyrozene, apatite, scapolite, graphite.
Sampord, York Co.—Idocrase! albite, calc spar, molybdenite, epidote. SEARSMONT. - Andalusite. STREAKED MOUNTAIN.—Beryl! black tourmaline, mica, garnet. THOMASTON.—Calc spar, tremolite, hornblende, sphene, arsenical iron, (Owl's head), black manganese, (Dodge's mountain). WARREN.-Galena, blende. WATERVILLE.—Crystallized pyrites.
WINDHAM, (near the bridge).—Staurotide, spodumene, garnet. WOODSTOCK, (New Brunswick). - Graphite, specular iron.

NEW HAMPSHIRE.

AGWORTH.—Beryl! | mica! tournaline, feldspar, albite, rose quartz, columbite!
ALBTRAD.—Mica! | albite, black tournaline.
AMHERST.—Idocrase! yellow garnet, pargasite, cale spar.
BARTLETT.—Magnetic iron, specular iron, brown iron ore in large veins near
Jackson, (on "Bald face mountain"), quartz crystals, smoky quartz.

Bath.—Galena, copper pyrites.
Bellows Falls.—Kyanite, wavellite, near Saxton's river.

Benton. — Quartz crystals. Campton. — Beryl!

CANAAN .- Gold in pyrites.

CHARLESTOWN .- Staurotide macle, andalusite macle, bog iron ore.

Cornish.—Gray antimony, antimonial argentiferous gray copper, rutile is quarte!

Eaton, (3 m S. of) .- Galena, blende I copper pyrites, limonite, (Six Mile Pond).

Franceston.—Scapstone, arsenical pyrites, ilmonite, (Six Mile Fond).

Franceston.—Scapstone, arsenical pyrites.

Franceston.—Hornblende, staurotide! epidote! zoisite, specular iron, magnetic iron, black and red manganesian garnets: mispickel! (Danaite), copper pyrites, molybdenite, prehnite; specimens now hardly obtainable.

Gilvord.—(Gunstock Mt.)—Magnetic iron ore, native "lodestone."

Goshen.—Graphite, black tournaline.

Graphites of the description and provided the control of t

GRAFTON .- Mica! (extensively quarried at Glass Hill, 2 m. S. of Orange Summit) albite ! asparagus stone, blue, green, and yellow beryls! (1 m. S. of O. Summit) tourmaline, garnets.

GRANTHAM .- Gray staurotide!

HANOVER.-Garnet, a boulder of quartz containing rutile! black tournaline, quartz.

HAVERHILL.—Garnet ! arsenical pyrites, native arsenic, galena, blende, iron and copper pyrites, magnetic and white iron pyrites.

HILLSBORO', (Campbell's mountain).—Graphite. HILLSBALE.—Rhodonite, black oxyd of manganese.

JACKSON.—Drusy quartz, tin ore, arsenical pyrites, native arsenic, fluor spar, spatite, magnetic iron ore, molybdenite, wolfram, copper pyrites, arsenate of iron.

JAFFREY.—(Monadnock Mt.)—Kyanite.

Keene.—Graphite, soapstone, milky quartz. Landars.—Molybdenite, lead and iron ores.

LEBANON. - Bog iron ore

LISBON.-Staurotide, black and red garnets, granular magnetic iron ore, here-

blende, epidote, zoisite, specular iron.

Lyme.—Kyanite, (N. W. part), black tourmaline, rutile, iron pyrites, copper py-

rites, (E. of E. village), sulphuret of antimony.

Merrimack.—Rutile I (in gneiss nodules in granite vein).

Moultonborough, (Red Hill).—Hornblende, bog ore, pyrites, tourmaline.

NEWPORT.-Molybdenite.

Orange.—Blue beryls ! Orange Summit, chrysoberyl, mica, (w. side of mountain.) Orford.—Brown tourmaline (now obtained with difficulty), steatite, rutile, kys nite, brown iron ore, native copper, green malachite, galena.

PELHAM. - Steatite.

PIERMONT. - Micaceous iron, heavy spar, green, white, and brown mica, apatits.

PLYMOUTH.-Columbite, beryl.

RICHMOND. - Iolite ! rutile, steatite, iron pyrites.

Saddleback Mr.—Black tourmaline, garnet, spinel.
Shelburne.—Argentiferous galena, black blende, copper pyrites, iron pyrites, man-

Springfield,-Beryls, (very large, eight inches diameter,) manganesian paraett in mica slate, albite mica.

SULLIVAN .- Tourmalines, (black), in quartz, beryl !

SURREY .- Amethyst, calcite.

SWANZEY, (near Keene). - Magnetic iron, (in masses in granite).

TAMWORTH, (near White Pond).-Galena.

UNITY, (estate of James Neal).—Copper and iron pyrites, chlorophyllite, green mice, magnetic iron, radiated actinolite, garnet, titaniferous iron ore, magnetic iron ore.

Walpole, (near Bellows Falls).—Macle.

WARREN. Copper pyrites, blende, epidote, quartz, iron pyrites, tremolite! galens, rutile, tale, molybdenite.

WESTMORELAND, (South part) .- Molybdenite ! apatite ! blue feldspar, bog mangases. (north village), quartz, fluor spar, copper pyrites, oxyd of molybdenum and ure

WHITE Mrs., (notch behind "old Crawford's house").-Green octahedral fluor, quartz crystals, black tourmaline, chiastolite.

WILMOT.--Beryl.

WINCHESTER.—Pyrolusite, diallogite, psilomelane, magnetic iron ore, granular quartz.

VERMONT.

Addison .-- Iron sand

Alburgh.—Quartz crystals on calc spar, iron pyrites.

ATHENS. - Steatite, rhomb spar, actinolite.

BARNET .- Graphite.

BELVIDERE.—Steatite, chlorite.

Bennington.—Pyrolusite, brown iron ore, pipe clay, yellow ochre.

Bethel .-- Actinolite ! tale, chlorite, octahedral iron, rutile, brown spar in steatite. Brandon.-Braunite, pyrolusite, psilomelane, limonite, lignite, white clay, statuary marble; fossil fruits in the lignite.

BRATTLEBOROUGH. -Black tourmaline in quartz.

BRIDGEWATER. - Tale, dolomite, magnetic iron, steatite, chlorite, gold, native copper, blende, galena, blue spinel, copper pyrites.

Bristol. -- Rutile, brown hematite, manganese ores.

BROOKFIELD .-- Mispickel, iron pyrites.

CABOT. -- Garnets, staurotide, hornblende, albite.

CASTLETON. - Roofing slate.

CAVENDISH. - Garnet, serpentine.

CHESTER.—Asbestus.

CHITTENDEN.-Psilomelane, pyrolusite, brown iron ore, specular and magnetic iron, galena.

COLCHESTER.—Brown iron ore, iron sand, jasper, alum.

CORINTH. -- Copper pyrites, (has been mined); magnetic iron pyrites.

COVENTRY. - Manganese spar.

CRAFTSBURY .- Mica in concentric balls.

DUMMERSTON.—Rutile.

FLETCHER.—Pyrites, octahedral iron, acicular tourmaline.

GRAFTON.—The steatite quarry referred to Grafton is properly in Athens.

Guilford.—Scapolite.

Hartford.—Calcite, pyrites ! kyanite in mica slate. Irasburgh.—Rhodonite, psilomelane.

JAY. - Chromic iron, serpentine, pierosmine, amianthua.

Lowell.—Picrosmine, amianthus.

MARLBORO.—Rhomb spar, steatite, garnet, magnetic iron. MENDON.—Octahedral Iron Ore.

MIDDLEBURY.—Zircon.

MIDDLESEX.—Rutile! (exhausted).

MONKTON.—Pyrolusite, brown iron ore.

Moskrown.—Smoky quartz / steatite, talc, wad, rutile.

Morrison. — Argentiferous galena.

Mount Holly. — Asbestus, chlorite.

NEW FANE - Glassy and abestiform actinolite, steatite, green quarts, (called chrysophrase at the locality), chalcedony, drusy quartz, garnet, chromic iron, rhomb spar.

NORWICH.—Actinolite, feldspar, brown spar in tale. Pittsford.—Brown iron ore, manganese ores.

PLYMOUTH.—Spathic iron, magnetic and specular iron, both in octahedral crystals.

PLYMPTON.—Massive hornblende.

PUTHEY .- Fluor, brown iron ore, rutile, and zoisite in boulders.

READING.—Glassy actinolite in talc.

READSBORO'. - Glassy actinolite, steatite.

Review. - Brown iron ore, augite in boulders, octahedral iron pyrites.

ROCHESTER.—Rutile, specular iron cryst., magnetic iron, in chlorite state.

ROXBURY. - Dolomite, tale, serpentine, asbestus.

SALISBURY .- Brown iron ore

SHABON. — Quartz crystals, kyanite.

Composition.—(Fe, Mn)P+1Fe F; FeP+Fe F, Rammelsberg. Analyses: 1, Fuchs, (J. f. pr. Ch. xviii, 499); 2, Rammelsberg, (4th Supp. 247):

 P
 Fe
 Mn
 F
 Fe
 Si

 35:60
 35:44
 20:34
 3:18
 476
 0:68, Fuchs.

 30:33
 41:42
 23:25
 6:00=100, Rammelsberg.

B.B. decrepitates, and finally melts to a bluish-black glass, attracted by the magnet.

This mineral was met with near Zwiesel in Bavaria, imbedded in granite.

PYROMORPHITE. Phosphate of Lead. Braunbleierz, Grünbleierz, Wern and Hef. Traubenblei, Haus. Buntbleierz. Nussierite, Danhauser. Polysphærite. Miceite, Beud.

Hexagonal. $O: 1=139^{\circ} 38'; a=0.7362$. Observed planes, O, I, i2, 1, 2, 4, 22.

 $O: 4=106^{\circ} 23'.$ $O: 22=124^{\circ} 11'.$ $1: 1(pyr.)=142^{\circ}12'.$ $O: 2=120^{\circ} 28'.$ $I: i2=150^{\circ}.$ $I: 22=135^{\circ} 46'.$

Cleavage: I and 1 in traces, I commonly striated horizontally. Often globular, (Polysphærite), reniform, and botryoidal, with a columnar structure; also fibrous and granular.

H.=3·5—4. G.=6·5871—7·048. Lustre resinous. Color green, yellow, and brown, of different shades, sometimes fine orange-yellow, owing to an intermixture with chromate of lead Streak white, sometimes yellowish. Subtransparent—subtranslucent. Fracture subconchoidal, uneven. Brittle.

Composition.—Essentially PbP+1Pb Cl, Ca F usually replacing some of the Pb Cl, and arsenic acid some of the phosphoric acid. Analyses: 1-5, Kersten, (Schw. J. lxii, 1, and Pogg. xxvi, 489); 6, 7, Lerch, (Ann. Ch. u. Pharm. xlv, 328):

```
PbP PbCl CaF
                                              Ċa*P
                                              11.05=100, Kersten.
1. Freiberg, brown,
                         77.02
                                10.84
                                       1.09
2. Mies, brown,
                         81.65
                                 10.64
                                        0.25
                                               7.46 = 100,
           " cryst.
                         89.27
                                        0.22
                                               0.85 = 100
                                  9.66
4. Bleistadt, brown cryst., 89.17
                                  9.92
                                        0.14
                                               077=100,
5. Poullaouen, cryst.,
                         89.91
                                 10.09
                                                   -=100,
                                               0.86, Fe3 P 0.77=90.31,L
6. Bleistadt, brown cryst., 87 88
                                10.28
                                        0.07
                                               1.58, " 0.50=100.27, L
                         88 42
                                 9.57
                                       0.50
```

B.B. on charcoal, melts without addition, and the globule on cooling assumes a polyhedral form, and a dark color; in the reducing flame, becomes bluish. Dissolves readily in heated nitric acid.

Pyromorphite occurs principally in veins, and acompanies other ores of lead. Fine specimens occur at Leadhills and Wanlockhead; and Poullaouen and Huelgoet in Brittany; at Zechopau and other places in Saxony; at Przibram, Mies, (Miesite, brown variety), and Bleistadt, in Bohemia; and at Sonnenwirbel near Freiberg; Clausthal in the Hartz; in fine crystals at Nassau; Beresof in Siberia; Cornwall and Wicklow in Ireland.

Pyromorphite has been found in good specimens at the Perkiomen lead mine near Philadelphia, and very fine at Phenixville; also in Maine, at Lubec and Lenox; in New York, a mile south of Sing Sing; sparingly at Southampton, Massachusetts. and Bristol, Conn.; in good crystallizations of bright green and gray colors, in Davidson Co., N. C.

Named from πυρ, fire, μορφη, form, alluding to the crystalline form the globule assumes on cooling. This species passes into the following.

Nussierite is considered by Dufrénoy an impure pyromorphite, containing some arsenate of lead. It is from Nussière, Dep. of Rhone, France.

ALTERED FORMS.—Occurs altered to Galena, (PbS), Calamine, (Zn°Si+11B', Calcite, and Limonite; to Galena, probably through the action of sulphuretted hydrogen.

```
GOBHEN.—Lithia mica, albite, spodumene ! blue and green tourmaline, beryl, zoisite,
smoky quartz, columbite, tin ore, galena.
    GREENFIELD, (in sandstone quarry, half mile east of village).—Allophane, white
 and greenish.
    HATFIELD.—Heavy Spar, yellow quartz crystals, galena, blende, copper pyrites.
    HAWLEY. - Micaceous iron, massive pyrites, magnetic iron, zoisite.
    HEATH.—Pyrites, zoisite.
    HINSDALE — Brown iron ore, apatite, zoisite.

HUBBARDSTON.—Massive pyrites.

LANCASTER.—Kyanite, chiastolite / apatite, staurotide, pinite, and alusite.
    LEE.—Tremolite! sphene! (east part).
LENOX.—Brown hematite, gibbeite, (f)
LEVERETT.—Heavy spar, galena, blende, copper pyrites.
    LEYDEN. - Zoisite, rutile.
    LITTLETON.—Spinel, scapolite, apatite.
LYNNFIELD.—Magnesite on serpentine.
    MARTHA'S VINEYARD.—Brown iron ore, amber, selenite, radiated pyrites.
    Mendon. - Mica / chlorite.
    MIDDLEFIELD. - Glassy actinolite, rhomb spar, steatite, serpentine, feldspar, drusy
quartz, apatite, zoiaite, nacrite, chalcedony, talc / MILBURY. — Vermiculite.
   MONTAGUE.—Specular iron.

NEWBURY.—Serpentine, chrysolite, epidote, massive garnet, carbonate of iron.
    NEWBURYPORT.—Sepentine, nemalite, uranite.
NEW BRAINTEER.—Black tourmaline.
    NORWICH.—Apatite! black tournaline, beryl, spodumene! triphyline (alte red)
 blende, quartz crystals.
    PALMER, (Three Rivers).—Feldspar, prehnite, calc spar.
   Pelham.—Asbestus, serpentine, quartz crystals, beryl, molybdonite, green hornstone. Plainfield.—Cummingtonite, pyrolusite, rhodonite. Richmond.—Brown iron ore, gibbsite!
    Rows.—Epidote, talc.
SOUTH ROYALSTON.—Beryl!! (now obtained with great difficulty), mica!! feld-spar! ilmenite, allanite. Four miles beyond old loc., on farm of Solomon Heywood,
mica! beryl! feldspar!
   Russer.—Schiller spar (diallage?) mica, serpentine, beryl, galena, copper pyritea. Saugus.—Porphyry.
   SHEFFIELD.—Asbestus, pyrites, native alum, pyrolusite. SHELBURNE.—Rutile.
   Shutesbury, (east of Locke's Pond).—Molybdenite.
   Southampton. — Galena, white lead ore, anglesite, molybdate of lead, fluor, heavy
spar, copper and iron pyrites, blende, corneous lead, pyromorphite.

Stelling.—Spodumene, chiastolite, spathic iron, mispickel, blende, galena, iron and
copper pyrites.
   STONEHAM. - Nephrite.
   STURBRIDGE.—Graphite, garnet, apatite, bog ore.
   TAUNTON, (one mile south).—Paracolumbite.
TURNER'S FALLS, (Conn. River.)—Copper pyrites, prehnite, chlorite, chlorophaite,
spathic iron, green malachite, magnetic iron sand, anthracite.
   Tyringham.—Pyroxene, scapolite.
Uzbridge.—Argentiferous galena.
Warwick.—Massive garnet, black tourmaline, magnetic iron, beryl, epidote.
Warhington.—Graphite.
Westfield.—Schiller spar, (diallage), serpentine, steatite, kyanite, scapolite,
actinolite.
    WESTFORD.—Andalusite!
   West Hampton.—Galena, argentine, pseudomorphous quartz.
West Springsield.—Prehmite, ankerite, satin spar, celestine, bituminous coal.
    WEST STOCKBRIDGE - Hematite, fibrous pyrolusite, spathic iron.
    WHATELY .- Native copper, galena.
```

galena, pyrolusite, copper pyrites.

WILLIAMSBURG.—Zoisite, pseudomorphous quartz, apatite, rose and smoky quartz,

Language of the Court of the Co Dell'alle alle

M. January Laure Frank Livering and Livering Stee

T=

로 로 함께 극대로 기 디르니다 제 기 디르니아 및 · === <u>...</u> = <u>...</u> . . . 1: 2= 15 N ==:: <u>;__ :</u>



Dyses usual farmers years and small CHESTRATE . T water, and hellians

Estate best in the maintain to remore TO DESCRIPTION OF THE PROPERTY The summer of the same

PLYMOUTH.—Galena, heulandite, fluor.
ROARING BROOK, (Cheshire).—Datholite! calc spar, prehnite, saponite.

READING, (near the line of Danbury).—Pyroxene, garnet.

ROXBURY. — Massive spathic iron, blende. Salisbury. — Brown iron ore, ochery iron, pyrolusite, triplite.

SATBROOK.—Molybdenite, stilbite, plumbago.

SIMSBURY.—Copper glance, green malachite.

SOUTHBURY.—Rose quartz, laumontite, prehnite, cale spar, heavy spar.

Southington.—Heavy spar, datholite, asteriated quartz crystals.

STAFFORD. - Massive pyrites.

STONINGTON. -Stilbite and chabazite on gneiss.

THATCHERSVILLE, (near Bridgeport).—Stilbite on gneiss, babingtonite!

TOLLAND. -Staurotide, massive pyrites.

TRUMBULL and Mongo.—Oldorophane, topaz, beryl, diaspore, magnetic pyrites, iron pyrites, tungstate of lime, wolfram, (pseudomorph of tungsten), rutile, native bismuth, tungstic acid, spathic iron, mispickel, argentiferous galena, blende, scapolite, tourmaline, garnet, albite, augite, graphic tellurium, (f) margarodite.

Washington.—Triplite, ilmenite! (Washingtonite of Shepard), diallogite, natrolite,

Washington.—Triplite, ilmenite! (Washingtonite of Shepard)
andalusite (New Preston), kyanite.
Waterrown, near the Naugatuck.—White sahlite, monazite.

WEST FARMS. —Asbestus.

WINCHESTER and WILTON.—Asbestus, garnet.

NEW YORK.

ALBANY CO.—CORYMAN'S LANDING.—Epsom salt.

Guilderland.—Petroleum.
Watervliet.—Quartz crystals.

ALLEGANY CO .- CUBA. -- Petroleum.

CATTARAUGUS CO .- FREEDOM .- Petroleum.

CAYUGA CO. -AUBURN. -Fluor, epsom salt.

CAYUGA LAKE.—Sulphur. LUDLOWVILLE.—Epsom salt.

Springville.—Nitrogen springs.

CHATAUQUE CO .- FREDONIA. -- Petroleum, carburetted hydrogen. LAONA.—Petroleum.

COLUMBIA CO .- ANCRAM LEAD MINE .- Galena, blende, copper pyrites, heavy spar.

Austerlitz.—Earthy manganese, molybdate of lead, copper mica.

Hudson.—Selenite!
LEBANON.—Nitrogen spring.

DUCHESS CO .- Dover .- Garnet (Foss ore bed).

FISHKILL -- Graphite, green actinolite ! talc, hydrous anthophyllite.

RHINEBECK.—Granular epidote.

Union Vall. — Gibbsite, (at Clove mine).

AMENIA.-Brown hematite.

ESSEX CO .- ALEXANDRIA. -- Kirby's graphite mine, graphite, pyroxene, scapolite,

CROWN POINT.—Apatite, (eupyrchroite of Emmons), brown tourmaline! in the apatite, chlorite, quartz crystals, pink and blue calcite, pyrites; a short distance south of J. C. Hammond's house, garnet, scapolite, copper pyrites, aventurine feldspar, zircon; magnetic iron (Peru).
LEWIS.—Tabular spar, colophonite, garnet, labradorite.

Long Pond.—Apatite, garnet, pyroxene, idocrase, coccolite!! scapolite, magnetic iron ore, blue calc spar.

yellow, of different shades; often grayish. Translucent.] ture uneven and splintery across the prism.

Composition - Mg P + MgF=Phosphorie acid 43-32, magnetia 37-54, finetine

Mg 7 69.
Analysis by Fuchs, Schweig, J. xxxiii, 269, revised by Rammeisberg, and meleberg. Ann. der Ph. u. Ch. lxiv, 251 and 405, and 2d Suppl. p. 162):

	P	Ýg	Ż.	Ĉa.	HF
l.	41 73	46 66	4-80		6-54=140-89, Punk
3	40.41	46-27	459	2-38	F 9-36=103-11. Reserv

B.R. fuses with difficulty, alone, to a dark greenish-gray glass: with because of phosphorus dissolves readily, and forms a colorious pearl. Nitric or only said gently beated, evolves from its powder fuses of hydrodinarie acid. This rare species occurs in the valley of Höllengraben, near Westlen, in burg, Austria, in irregular veins of quarts, traversing clay state.

KUHNITE, R and M. Magnesian Pharmacolite, Berneliit, Kulin, Ann. Ch. v. ? xxxiv. 211, Chanx ameniatés anhydre, Dugi.

Massive, with cleavage in one direction.


H.=3-6. G.=2.52. Lustre waxv. Color firty-white at ev-veilow. Brittle

Composition - Ca. Mg. Mn / La=Aremie seid 61 5. lime 22:5, magnessa id-: Analyses by Kihn, (loc. cit. :

B.B. infusible, but becomes gray. Affords the reaction of arsence, and if I ness with fluor span. Whelly soluble in name and

Occurs at Longbanahytta in Sweden, with an one of fron and granuar SPAF.

LAZULITE Aturite, P. Azurestone. Huirous liphosphate of alumina and nesse, Ptone. Since spar. Feidspain bleu, H. Formulae. Shaprotimes spain, W



manive.

Monoclinic. (= 35° 17. =2130、0:4=1365 45、 Observed planes as in the an ed igure. Prater. Nat. Wien. inth.

Twins: face of composition it. Cleavage, aterai, indistruct.

NEW YORK CO .- CORLARR'S HOOK. - Apatite.

KINGSBRIDGE.—Tremolite, pyrozene, mica, tourmaline, pyrites, rutile. HARLEM.—Epidote, apophyllite, stilbite, tourmaline, vivianite, lamellar feldspar,

NEW YORK .- Serpentine, amianthus, actinolite, talc, pyrozene, hydrous anthophyllite, garnet, staurotide, molybdenite, graphite.

NIAGARA CO.—Lewiston.—Epsom salt.
LOUKPORT.—Celestine, calc spar, selenite, anhydrite, fluor, pearl spar, blende. NIAGARA FALLS. - Calc spar, fluor, blende.

ONEIDA CO.—BOONVILLE.—Calc spar, tabular spar, coccolite. CLINTON.—Blende, lenticular argillaceous iron ore; in rocks of the Clinton Group, strontianite, celestine, the former covering the latter.

ONONDAGA CO .- CAMILLUS .- Selenite and fibrous gypsum.

Manlius.—Gypsum and fluor. Syracuse.—Serpentine, celestine.

ORANGE CO.—CORNWALL.—Zircon, chondrodite, hornblende, spinel, massive feld-spar, fibrous epidote, hudsonite, ilmenite, serpentine, boltonite.

DEER PARK.—Cryst. pyrites, galena.

MONEOR.—Mica! sphene! garnet, colophonite, epidote, chondrodite, allanite, bucholzite, brown spar, boltonite, spinel, hornblende, talc, ilmenite, magnetic pyrites, common pyrites, chromic iron, graphite.

At WILKS and O'NEIL Mine in Monroe. - Aragonite, magnetite, dimagnetite

(pseud f), jenkinsite.

At Two Ponds in Monroe.—Pyroxene! chondrodite, hornblende, scapolite! zircon, sphene, apatite.

At Greenwood Furnace in Monroe.—Chrondrodite, pyroxene! mica, hornblende, spinel, scapolite, biotite! ilmenite.

At Forest of Dean.—Pyroxene, spinel, zircon, scapolite, hornblende, boltonite.

Town of WARWICK.

WARWICK VILLAGE.—Spinel, zircon, serpentine! brown spar, pyrozene! hornblende! pseudomorphous steatite, feldspar! (Rock Hill), ilmenite, clintonite, tourmaline, (R. H.), rutile, sphene, molybdenite, mispickel, white iron pyrites, common pyrites, yellow iron sinter.

AMITT.—Spinel, garnet, scapolite, hornblende, idocrase, epidote ! clintonite! magnetic iron ! tourmaline, warwickite, apatite, chondrodite, ilmenite, talc ! pyroxene! rutile,

zircon, corundum, feldepar, sphene, calc spar, serpentine, schiller spar.(1)

EDENVILLE—Apatite, chondrodite! hair brown hornblende! tremolite, spinel, tour-maline, warwickite, pyroxene, sphene, mica, feldspar, mispickel, orpiment, rutile, ilmenite, scorodite, copper pyrites.
West Point. - Feldspar, mica, scapolite, sphene, hornblende, allanite.

PUTNAM CO.—CARMEL, (Brown's quarry).—Anthophyllite, schiller spar, (1) orpiment, mispickel.

COLD SPRING.—Chabazite, mica, sphene.

PATTERSON. - White pyroxene ! calc spar, asbestus, tremolite, dolomite, massive py-

PHILLIPSTOWN.—Tremolite, amianthus, serpentine, sphene, diopside, green crocolite, hornblende, scapolite, stilbite, mica, laumontite, gurhofite, cale spar, magnetic iron, chromic iron.

PHILLIPS Ore Bed.—Hyalite, actinolite, massive pyrites.

RENSSELAER CO .- Hoosic, -- Nitrogen springs.

LANSINGBURGH.-Epsom salt, quartz crystals, iron pyrites.

TROY. — Quartz crystals, iron pyrites, selenite.

RICHMOND CO.—Rossville.—Lignite, cryst. pyrites.

QUARANTINE.—Asbestus, amianthus, aragonite, dolomite, gurhofite, brucite, serpentine, talc.

ROCKLAND CO .- CALDWELL .- Calc spar ! GRASSY POINT.—Serpentine, actinolite.

HATERSTRAW.—Hornblende.
LADENTOWN.—Zircon, red copper ore, green malachite.

PIERMONT.—Datholite, stilbite, apophyllite, stellite, prehnite, thomsonite, ak

STONY POINT.—Kerolite, lamellar hornblende, asbestus.

ST. LAWRENCE CO .-- CANTON .- Massive pyrites, cale spar, brown tourneline sphene, serpentine, tale, rensselaerite, pyroxene, specular iron, copper pyrites.

Dekalb.—Hornblende, heavy spar, fluor, tremolite, tourmaline, blende, graphite,

pyroxene, quartz (spongy), serpentine.

EDWARDS.—Brown and silvery mica! scapolite, apatite, quartz crystals, actinolite, tremolite, specular iron, serpentine, magnetite.

FINE. —Black mica, hornblende.

FOWLER.—Heavy spar, quartz crystals! specular iron, blende, galena, tremelite, chalcedony, bog ore, satin spar, (assoc. with serpentine), iron and copper pyrite.

actinolite, rensselaerite, (near Somerville).

GOUVERNEUR. - Calc spar! serpentine! hornblende! scapolite! orthoclase, tourse line l idocrase, (one mile south of G.), pyroxene, apatite, rensselaerite, serpentine, sphene, fluor, heavy spar (farm of Judge Dodge), black mica, phlogopite, tremolist asbestus, specular iron, graphite, idocrase; (near Somerville in serpentine), prind, houghite, scapolite, phiogopite, dolomite; three quarters of a mile west of Somerville, chondrodite, spinel; two miles north of Somerville, apatite, pyrites.

Hammond.—Apatite! zircon! (farm of Mr. Hardy), orthoclase, pargasite, heavy

spar, pyrites, purple fluor, dolomite. Негмон.—Quartz crystals, specular iron, spathic iron, pargasite, pyroxene, sergestine, tourmaline, bog iron ore.

MACOMB.—Blende, mica, galena (on land of James Averil), sphene.

MINERAL POINT, Morristown.—Fluor, blende, galena, phlogopite, (Pope's Mills), heavy spar.

OGDENSBURG.—Labradorite.

PITCAIRN.—Satin spar, associated with serpentine.
Potsdam.—Hornblende!—eight miles from Potsdam on road to Pierrepont, file

spar, tourmaline, black mica, hornblende.

Rossie, (Iron Mines).—Heavy spar, specular iron, corralloidal aragonite in mines near Somerville, limonite, quartz, (sometimes stalactitic at Parish iron mine), pyrites, pearl spar.

Rossie Lead Mine.—Calc spar, galena, pyrites, celestine, copper pyrites, spathic

iron / white lead ore, anglesite.

Elsewhere in Rossie.—Calc spar, heavy spar, quartz crystals, chondrodite (near Yellow Lake), feldspar! pargasite! apatite, pyroxene, hornblende, sphene, zircos, mica, fluor, serpentine, automolite, pearl spar, graphite.

Russel.—Pargasite, specular iron, quartz (dodec.), calcite, serpentine, renseelserite.

magnetite.

SARATOGA CO.—Greenfield.—Chrysoberyl! garnet, tourmaline! mica, feldeper, apatite, graphite, aragonite, (in iron mines).

SCOHARIE CO.—Ball's Cave, and others.—Calc spar, stalactites CARLINLE.—Fibrous sulphate of baryta, cryst. and fib. carbonate of lime. Sconarie. -- Fibrous celestine, strontianite! cryst. pyrites!

SENECA CO .- CANOGA .-- Nitrogen springs.

SULLIVAN CO .- Wurtzboro' .- Galena, blende, pyrites, copper pyrites.

ULSTER CO .- ELLENVILLE .- Galena, blende, copper pyrites ! quartz, brookite. MARBLETOWN .- Pyrites.

WARREN CO .- CALDWELL .- Massive feldspar. Chester. - Pyrites, tourmaline, rutile, copper pyrites. DIAMOND ISLE, (Lake George.)—Calc spar, quartz crystals. GLENN'S FALLS.—Rhomb spar. JOHNSBURG.—Fluor ! zircon !! graphite, serpentine, pyrites.

WASHINGTON CO .- FORT ANN .- Graphite. -Granville.—Lamellar pyrozene, massive feldspar, epidote.

WAYNE CO .- WOLCOTT .- Heavy spar.

WESTCHESTER CO. Anthony's Nos.—Apatite, pyrites, calcite! in very large tabular crystals, grouped and sometimes incrusted with drusy quartz.

DAVENPORT'S NEOR.—Serpentine, garnet, sphene.

EASTCHESTER.—Blende, copper and iron pyrites, dolomite.

Hastings.—Tremolite, white pyroxene.

New Rochelle.—Serpentine, brucite, quartz, mica, tremolite, garnet.

Prekskill.—Mica, feldspar, hornblende, stilbite.

RTE.—Serpentine, chlorite, black tourmaline, tremolite, kerolite.

Singsing.—Pyroxene, tremolite, iron pyrites, copper pyrites, beryl, azurite, green malachite, white lead ore, pyromorphite, anglesite, vauquelinite, galena, native ailver.

WEST FARMS. - Apatite, tremolite, garnet, stilbite, heulandite, chabazite, epidote, sphene.

YONKERS.—Tremolite, apatite, calc spar, analcime, pyrites, tourmaline. YORKTOWN. - Sillimanite, monazite, magnetic iron.

NEW JERSEY.

Andovee Iron Mine. (Sussex Co).—Willemite, brown garnet. Allentown, (Monmouth Co.)—Vivianite.

BELVILLE.—Copper mines.

BERGEN.—Cale spar, datholite, thomsonite, pectolite (called stellite), analcime, apophyllite, prehnite, sphene, stilbite, natrolite, heulandite, laumontite, chabazite, pyrites, pseudomorphous steatite imitative of apophyllite.

Brunswick.—Copper mines; native copper, malachite, mountain leather.

BRYAM.—Chondrodite.

CANTWELL'S BRIDGE, Newcastle Co., three miles west.—Vivianite.

DANVILLE, (Jemmy Jump Ridge). - Graphite, chondrodite, augite, mica.

FLEMINGTON.—Copper mines.

FRANKFORT. - Serpentine.

Franklin and Sterling.—Spinel! garnet! rhodonite! willemite! franklinite! red zinc ore! dysluite! hornblende, tremolite, chondrodite, white scapolite, black tourmaline, epidote, pink calc spar, mica, actinolite, augite, sahlite, coccolite, asbestus, jeffersonite (augite), calamine, graphite, fluor, beryl, galena, serpentine, honey-colored sphene, quartz, chalcedony, amethyst, zircon, molydenite, vivianite. Also algerite in gran. limestone. The zinc ores and franklinite, especially at Sterling Hill in Sterling, the jeffersonite at Mine Hill, in Franklin.

Franklin and Warwick Mrs.—Pyrites.

GREENBROOK.—Copper mines.

GRIGGSTOWN.—Copper mines.

HAMBURGH.—One mile north, spinel!, tourmaline!, phlogopite, hornblende, &c., limonite, specular iron.

HOBOKEN.—Serpentine, brucite! nemalite (or fibrous brucite), aragonite, dolomite.

HURDSTOWN.—Apalite, magnetic pyrites, magnetite.

IMLETTOWN.—Vivianite.

Lockwood.—Graphite, chondrodite, talc, augite, quartz, green spinel.

MONTVILLE, Morris Co.—Serpentine, chrysotile.

MULLICA HILL, Gloucester Co. - Vivianite lining belemnites and other fossils.

NEWTON.—Spinel, blue and white corundum, (exhausted), mica, idocrase, horn-blende, tourmaline, scapolite, rutile, pyrites, talc, calc spar, heavy spar, pseudomorphous steatile.

PATTERSON.—Datholite.

Schuyler's Mines.—Green malachite, red copper ore, native copper, chrysocalla, green malachite, bitma (two miles to the northeast).

SPARTA.—Chondrodite ! spinel, sapphire, green tale, graphite, epidote, augita.
Suckasummy, on the Morris canal.—Brown apatite in magnetic pyrites.

Trenton.—Zircon, amber, lignite.

VERNON.—Green spinel, chondrodite, red sapphire, hornblende, pyrites, phiegopia graphite, limonite, rutile, sphene, ilmenite, zircon, fluor, margarite. WOODBRIDGE.—Copper mine.

Norz.—From Amity, N. Y., to Andover, N. J., a distance of about thirty miles the outeropping limestone, at different points, affords more or less of the mineral enumerated as occurring at Franklin. (See Geol. Rep. on N. J., by H. D. Regen)

PENNSYLVANIA.

ADAMS CO .- READING .- Molybdenite in quartz, zircon, magnetic iron ore.

BERKS CO .- At Jones's Mines, near Morgantown, green melechite! cerusita, chrysocolla I, oct. and dodec. magnetic iron, iron pyrites, copper pyrites;—two miles to the northeast, graphite, sphene; at Steel's Mines, octahedral and miceson iron ore, coccolite.

BUCK'S CO .- Opposite New Hope, tournaline !; near Attleboro', at Vaner dale's limestone quarry, saklite, scapolite, sphene, green coccolite, graphite, green

CARBON CO .- At Mauch Chunk, cryst. iron pyrites, selenite.

CHESTER CO .- BIRMINGHAM .- Kerolite, amethyst, quartz cryst., serpentise. E. Bradford.-On Minorcus Hill, green, blue and gray kyenite, apatite, allasite; on A. Taylor's farm, sphene, cryst, smoky quartz; on the farms of B. Jones, R. Price, L. Sharpless, and S. Entrikin, amethyst; near Strode's mill, asbestus, magnetic, marmolite, garnet; near T. Hoope's saw mill, epidote, asbestus; on Osbors's Hill, sphene, manganesian garnet, wad, tourmaline, actinolite, anthophyllite, feld-spar, fetid calcite; near the Black Horse Inn, rutile.

W. Bradford.—Near A. Jackson's limestone quarry, green kyanite, rutile, scapelite, iron pyrites; near Marshall's mill, chromic iron, serpentine; at Poor Ho (limestone) quarry, (called also Baldwin's), four miles north of Unionville, and ax west of Westchester, ratile ! in brilliant scicular crystals; cryst. calc spar, cryst. dolomite, zoisite in quartz, tale in implanted crystals on dolomite, chesterlite! (in

fine crystals implanted on dolomite), quartz crystals.

CHESTER Springs.—Gibbsite, in an iron mine; near Coventryville, in Chrisman's limestone quarry, augite, sphene, graphite, zircon ! in iron ore about half a mile

from the village on French Creek.

West Goshen.—Amianthus, asbestus, precious serpentine, cellular quartz, jasper, chalcedony, drusy quartz, chlorite, marmolite, dolomite, cryst. carb. magnetic chromic iron | magnetic iron; near Westchester Water Works, zoisite, (rare, not found now).

KEIM'S IRON MINE near Knauertown.—Flos-ferri, pyroxene, metaxite, micaca iron ore, aplome ! ! actinolite, yellow octahedral pyrites, copper pyrites in tetrahedrons, red garnet ! malachite, hornblende (var. byssolite).

KENNET TOWNSHIP.—Actinolite! (rare on Gregg's farm), brown tourmaline, brown mica, epidote, tremolite, scapolite, aragonite; at Pearce's paper mill, zoisite, epidote, sunstone; on R. Lamborne's farm, chabazite in small browniah yellow crystals, (rare), zeolite; at Gause's corner, epidote.

KNAUERTOWN.—North of Pughtown, graphite, sphene, cryst. magnetic iron; in

Chrismard's Iron Mine, zircon.
London Grove.—In Jackson's limestone quarry, yellow tourmaline! (rare), fib.

tremolite; at Pusey's quarry, rutile, tremolite.

New Garden Township. -At Nevin's limestone quarry, brown tourmaline! scapelite, brown and green mica, rutile, aragonite, kaolin.

NEWLIN. - See Unionville, below.

East Marlbono .- Epidote, and nearly white tourmaline, (rare).

Oxford.—Iron pyrites, garnets.
Nortingham.—At Scott's chrome mine, chromic iron, foliated tale, marmolite, serpentine, chalcedony; at the Magnesian Quarry, magnesite, marmolite, serpentine.

PARKSBURG, (in township of Sadsbury).—In the soil for seven miles along the valley, rutile!; northeast of the village, amethyst, tourmaline, epidote, (in a boulder).

PENN.—Garnets, figure stone.

Pennsbury Township .- On Cephas Cloud's farm, brown garnets !; J. Dilworth's farm, near Pennsville, mical! (in six-sided prisms from one quarter to seven inches across); at Harvey's lime quarry, on the Brandywine, chondrodite; quarter of a mile above the last, at Wm. Burnett's lime quarry, sphene, diopside, augite, coc-

PHENIXVILLE.—In Railroad Tunnell, pearl spar (exhausted), dolomite, yellow blende, iron pyrites; at Wheatley's Mine, pyromorphite! cerusite! cryst. quartz, galena,

iron pyrites; at Wheatley's Mine, pyromorphite! cerusite! cryst. quartz, galena, anglesite! copper pyrites, heavy spar, fluor, mulfenite! calamine, cerasine!, vanadinite!, phosphate of copper, chromate of lead.

Porrsrown, near French Cr.—(Elizabeth Mine).—Iron pyrites! (in octahedrons), copper pyrites, magnetite, dark brown garnet, molybdenite.

Unionville.—One and a half miles northeast, on Serpentine Barrens, corundum! massive and cryst. (often in loose crystals and also in albite, the loose crystals mostly covered with a thin coating of steatite, sometimes with gibbsite), talc, green tourmaline (with flat or pyramidal terminations), ligniform asbestus, yellow beryl (rare), serpentine, brucite, chromic iron, quartz crystals, green quartz, actinolite, clinochlore in cryst., diallage, granular albite (H.=7), adularia, oligoclase, halloysite, margarite, euphyllite, allanite, hematite, chalcedony; half a mile southwest. loysite, margarite, euphyllite, allanite, hematite, chalcedony; half a mile southwest, loysite, margarite, suphyllite, allanite, hematite, chalcedony; half a mile southwest, on T. Webb's farm, serpentine, chromic iron, (mas.); two and a half miles southwest, in R. Bailey's lime quarry, fib. tremolite, mussite; kyanite, margarodite; two miles southwest, at Pusey's saw mill, zircon (cryst. small, loose in the soil, rare), rutile; one mile south, on the farm of Baily and Brothers, bright valow and nearly white tourmaline! (rare), orthoclase (chesterlite), albite! (inaccessible); two miles cast, near Marlborough meeting house, epidote! (rare), serpentine, acicular black tourmaline in white quartz; one mile west, near Logan's quarry, staurotide, kyanite, yellow tourmaline, (rare); at Edward's lime quarry near the last, purple fluor, rutile; four miles west, in limestone quarries of West Marlborough, near Doe Rivery Villege, seepolite, rutile, tremplite. er Village, scapolite, rutile, tremolite.

WESTCHESTER. - One and a half mile north, hydromagnesite, clinochlore, brucite, in serpentine, zircon, two miles west; one and a half mile northwest, pitch-black allanite; B.B. intumesces very readily (G. 2.5); 3 m. south, clinochlore, phlogopite.
Willistown.—Magnetic iron, chromic iron, actinolite.

COLUMBIA CO.-At Webb's mine, yellow blende in cale spar; near Bloomburg, cryst. magnetic iron.

DAUPHIN CO.—Near Hummerstown, green garnets, cryst. smoky quartz, cryst. feldspar.

DELAWARE CO.-Aston.-Near Village Green, amethyst, corundum, emerylite, staurotide, sillimanite, black tourmaline, pearl mica, asbestus, anthophyllite; near Tyson's Mill, garnet, staurotide; at head of Peter's Mill Dam, in a brook, garnet

BIRMINGHAM.—At Bullock's quarry, zireon, bucholzite, fibrolite, nacrite.

CHESTER.—Amethyst, black tourmaline; in Burk's quarry, beryl!! black tourmaline!! feldspar! manganesian garnet, cryst. pyrites; on Chester Creek, at Carter's, molybdenite, molybdic ochre, copper pyrites, tourmaline, kaolin; at Little's quarry, brown garnets, tourmaline; near Henvi's quarries, amethyst in geodes.


CHICHESTER.—Near Trainer's Mill Dam, beryl, tourmaline, cryst. feldspar, kaolin;

on W. Eyre's farm, tourmaline ! !

Occurs at Chursdorf and Arnsdorf, near Penig in Saxony, where it is assess with tourmaline and garnet in granite: also at Arendal, Norway.

The name is from εμέλυς, blunt, and yere, angle.

HERDERITE, Haid. Allogonit, Breit.



Trimetric. $I: I=115^{\circ} 53'$, O:17=51'; a:b:c=0.6783:1:1.5971. Obserplanes as in the annexed figure, with al 4 and 6.

O: 1=141° 19'. 1:1 (mac.) 141° 1'. O: 3=112° 35'. 1:1 (brach.)=116' O: \$\frac{1}{2}=147° 30'. O: I=90°.

Cleavage: I interrupted. Surfaces I avery smooth, and delicately lined parall

their edge of intersection.

H.=5. G.=2.985. Lustre vitreous, inclining to subresis Streak white. Color various shades of yellowish and gree white. Translucent. Fracture small conchoidal. Very br. Index of refraction 1.47.

Composition.—Probably, according to trials by Turner and Plattner, and drous phosphate of alumina and lime with fluorine. B.B. fuses with difficult white enamel; becomes blue with cobalt solution. Dissolves when finely posed in muriatic acid.

Very rare at the tin mines of Ehrenfriedersdorf in Saxony. Resembles to paragus variety of apatite.

Named after Baron von Herder, director of the Saxon mines.

CARMINITE. Carmine Spar. Carminspath, Sandberger, Pogg. 1xxx, 89:

Trimetric? In clusters of fine needles; also in spheroidal for with a columnar structure. Cleavage parallel to the faces rhombic prism.

II.=2.5. Lustre vitreous, but cleavage pearly. Color carr to tile-red; powder reddish-yellow. Translucent. Brittle.

Composition.—Probably an anhydrous arsenate of lead and iron.

B.B. on charcoal fuses easily to a steel-gray globule, giving out arsenical va with soda, a globule of lead, and with borax an iron reaction. Heated in a tube, no change. Soluble in nitric acid.

From Horhausen in Saxony, with Beudantite in quartz and brown iron ore

ROMEINE, Damour, Ann. des Mines, [8], xx, 247, [5], iii, 179. Romeit.

Dimetric. In octahedrons; basal angle, according to Dufré 110° 50′—111° 20′; angle over the summit 68° 10′—69° 10′. curs in groups of minute crystals.

Scratches glass. G. in grains 4.714; in powder 4.675. C hyacinth or honey-yellow.

BURKE Co.-Gold, monazite, zircon, beryl, corundum, garnet, sphene, graphite,

Cabarrus Co.—Phenix mine, gold, barytes, copper pyrites, auriferous pyrites, quartz pseudomorph after barytes, tetradymite; Pioneer Mines, gold, limonite, pyrolusite, barnhardtite, wolfram, scheelite, tungstate of copper, wolframine, diamond, chrysocolla, copper glance, molybdenite, copper pyrites, iron pyrites; White Mine, needle ore, copper pyrites, barytes; Long and Muse's Mine, argentiferous galena, iron pyrites, copper pyrites, limonite; Boger Mine, tetradymite; Fink Mine, valuable copper ores; Mt. Makins, tetrahedrite? magnetite, talc, blende, pyrites, galena.

Caldwell Co.—Chromic iron,

Charman Co.—Chromic from,
Charman Co.—Mineral coal, pyrites.
Cherorer Co.—Iron ores, gold, galena, corundum, rutile.
Davidson Co.—King's now Washington Mine, native silver, cerusite, anglesite, scheelite, pyromorphite, galena, blende, malachite, black copper, wavellite, garnet, stilbite. Five miles from Washington Mine, on Faust's Farm, gold, tetradymite, stilbite. oxyd of bismuth and tellurium, copper pyrites, limonite, spathic iron, epidote; near Squire Ward's, gold in crystals, electrum. Gaston Co.—Iron ores, corundum, margarite. Near Crowder's Mountain (in what

was formerly Lincoln Co.), lasulite, kyanite, garnet, graphite; also twenty miles northeast, near south end of Clubb's Mtn., lazulite, kyanite, tale.

Gulford Co.—McCullock copper and gold mine, twelve miles from Greensboro, gold, pyrites, copper pyrites (worked for copper), quarts, spathic iron. The North Carolina Copper Co. are working the copper ore at the old Fentress mine.

Henderson Co.—Zircon.

Lincoln Co .- Diamond; at Randleman's, amethyst !, rose quartz.

Macon Co.-Chromic iron.

McDowell Co .- Brookite, monazite, corundum in small crystals red and white,

zircons, garnet, beryl, sphene, xenotime, rutile, elastic sandstone, iron ores.

Mecklenerg Co.—Near Charlotte (Rhea and Cathay Mines) and elsewhere, cop per pyrites, gold; chalcotrichite at McGinn's Mine; barnhardtite near Charlotte; pyrophyllite in Cotton Stone Mountain, diamond.

Rowan Co.—Gold Hill Mines, thirty eight miles northeast of Charlotte, and four-

teen from Salisbury, gold, auriferous pyrites; ten miles from Salisbury, feldspar in

RUTHERFORD Co.—Gold, graphite, bismuthic gold, diamond, cuclase, pseudomorphous quartz, chalcedony, corundum in small crystals, epidote, pyrope, brookite, zircon, monazite, rutherfordite, samarskite, quartz crystals, itacolumite; on the road to Cooper's gap, kyanite.

STOKES AND SURREY Cos.—Iron ores, graphite.
UNION Co.—Lemmond Gold Mine, eighteen miles from Concord, (at Stewart's and Moore's Mine), gold, quartz, blende, argentiferous galena (containing 29.4 oz. of gold, and 86.5 oz. silver to the ton, Genth), pyrites, some copper pyrites.

YANCEY Co .- Iron ores, amianthus, chromic iron.

SOUTH CAROLINA.

ABBEVILLE DIST. - Oakland Grove, Gold, (Dorn Mine), galena, pyromorphite, amethyst, garnet.

Anderson Dist.-At Pendleton, actinolite, galena, kaolin, tourmaline.

CHARLESTON. - Selenite.

CHECWEE VALLEY.—Galena, tourmaline, gold.
CHESTERFIELD DIST.—Gold, (Brewer's mine), tale, chlorite, pyrophyllite, pyrites, native bismuth, carbonate of bismuth, red and yellow ochre, whetstone.

DABLINGTON. - Kaolin.

EDGEFIELD DIST .- Psilomelane.

GREENVILLE DIST.-Galena, phosphate of lead, kaolin, chalcedony in burhstone, beryl, plumbago, epidote, tourmaline. Kershaw Dist.—Rutile.

LANCASTER DIST.—Gold (Hale's mine), talc, chlorite, kyanite, elastic sandstone, pyrites; gold also at Blackman's mine, Massey's mine, Ezell's mine.

NEWBERRY DIST.-Leadhillite (?).

Picken's Dist.—Gold, manganese cres, kaolin. Richland Dist.—Chiastolite, novaculite.

SPARTANBURG DIET .-- Magnetic iron ore, chalcedony, hometite; at the Cowpens, brown hematite, graphite, limestone, copperas.

SUMTER DIST.—Agate.
Union DIST.—Fairforest gold mines, pyrites, copper pyrites.
YORK DIST.—Limestones, whetstones, witherite, heavy spar.

GEORGIA.

Burke and Scriven Cos.—Hyalite. Clark Co., near Clarksville.—Gold, xenotime, zircon, rutile, kyanite, specular

iron, garnet, quartz.

Habersham Co.—Gold, iron and copper pyrites, galena, hornblende, garnet, quartz, kaolin, soapstone, chlorite, rutile, iron ores, galena, tourmaline, staurotide,

HALL Co.—Gold, quartz, kaolin, diamond. HANCOCK Co.—Agate, chalcedony. LUMPKIN Co.—Gold, quartz crystals.

RABUN Co.—Gold, copper pyrites.
Washington Co. near Saundersville.—Wavellite, fire epal.

ALABAMA.

BIBB Co., CENTREVILLE.—Iron ores, marble, heavy spar, coal, cobalt.
TUSCALCOSA Co.—Coal, galena, pyrites, vivianite, limonite, calcite, dolomite, kyanite, steatite, quartz crystals, manganese ores.
BENTON Co.—Antimonial lead ore (Boulangerite?)

FLORIDA.

NEAR TAMPA BAY.—Limestone, sulphur springs, chalcedony, carnelian, agate, silicified shells and corals.

KENTUCKY.

Mammoth Cave.—Gypsum, in imitative forms, stalactites, nitre, epsom salt. Near the line between Livingston and Union Cos., galena, copper pyrites.

TENNESSEE.

BROWN'S CREEK.—Galena, blende, heavy spar, celestine. CARTER'S Co. foot of Roan Mt.—Sahlite, magnetic iron.

CLAIBORNE Co. — Calamine, galena, smithsonite, chlorite, steatite, and magnetic

COCKE Co., near Brush Creek.—Cacoxene, kraurite, iron sinter, stilpnosiderite, brown hematite.

DAVIDSON Co.—Selenite, with granular and snowy gypsum, or alabaster, crystallized and compact anhydrite, fluor in crystals! cale spar in crystals. Near Nashville, blue celestine, (crystallized, fibrous, and radiated), with Accry spar in limestone. Haysboro', galena, blende, with heavy spar as the gangue of the ore.

DICKSON Co.—Manganite.

JEFFERSON Co.—Calamine, galena, fetid heavy spar.

KNOV Co.—Manganite.

KNOX Co.—Magnesian limestone.
MAURY Co.—Wavellite in limestone.

MORGAN Co.—Epsom salt, nitrate of lime.

POLE Co., Hiwassee mine, southeast corner of state, near Occee river. Black copper ! copper pyrites, iron pyrites, (mines valuable).

ROAN Co., eastern declivity of Cumberlands Mts.—Wavellite in limestone. SEVERN Co, in caverns.—Epsom salt, soda alum, saltpetre, nitrate of lime. SMITH Co. -Fluor. SMOKY Mr., on declivity.—Hornblende, garnet, staurotide.

OHIO.

BAINBRIDGE, (Copperas Mt., a few miles east of B.)—Calc spar, heavy spar, iron. pyrites, copperas, alum.

CANFIELD,—Gypsum /
DUCK CREEK, Monroe Co.—Petroleum.

LIVERPOOL.—Petroleum.

MARIETTA.—Argillaceous iron ore; iron ore abundant also in Scioto and Law-

POLAND .- Gypsum!

MICHIGAN.

LAKE SUPERIOR MINING REGION.—The four principal regions are Keweenaw Point, Isle Royale, the Ontonagon, and Portage Lake. The mines of Keweenaw Point are along two ranges of elevation, one known as the Greenstone Range and the other as the Southern or Bohemian Range, (Whitney). The copper occurs in the trap or amygdaloid, and in the associated conglomerate. Native copper! native silver! amygaloid, and in the associated conglomerate. Native copper, name silver, copper pyrites, horn silver, gray copper, manganese ores, epidote, prehnite, laumon-tite, datholite, heulandite, stilbite, analcime, chabazite, mesotype, (Copper Falls mine), leonhardite, (ib.), analcime, (ib.), apophyllite, (at Cliff Mine), wollastonite, (ib.), calc spar, quartz (in crystals, at Minesota mine), saponite, black oxyd of copper, (near Copper Harbor, but exhausted), chrysocolla; on Chocolate river, galena and sulphuret of copper; copper pyrites and native copper at Presqu' Isle. At Albion mine, domeykite; at Prince Vein, amethyst; at Michipicoten Ids., copper nickel, stilbite, analcime. stilbite, analcime.

IBLE ROYALE, 48° N., 89° W.—Native copper, epidote, harmotome (†) datholite, wollastonite (exhausted), pectolite, chlorastrolite.

ILLINOIS.

GALLATIN Co., on a branch of Grand Pierre Creek, sixteen to thirty miles from Shawneetown, down the Ohio, and from half to eight miles from this river .- Violet fluor spar ! in carboniferous limestone, heavy spar, galena, blende, brown iron ore; near Rosiclare, calcite, galena, blende; five miles back from Elizabethtown, bog iron; one mile north of the river, between Elizabethtown and Rosiclare, nitre.

In Northern Illinois, townships 27, 28, 29, several important mines of galena. Pope Co.-Pyromorphite.

INDIANA.

LIMESTONE CAVERNS; Corydon Caves, &c.—Epsom salt.

In most of the southwest counties, pyrites, sulphate of iron, and feather alum pon Sugar Creek, pyrites and sulphate of iron; in sandstone of Lloyd Co., near the Ohio, gypsum; at the top of the blue limestone formation, brown spar, calc spar.

MINESOTA.

NORTH SHORE OF L. SUPERIOR, (range of hills running nearly northeast and southwest, extending from Fond du Lac Superieure to the Kamanistiqueia river in Upper Canada).—Scolecite, apophyllite, prehnite, stilbite, laumontite, heulandite, harmotome, thomsonite, fluor spar, sulphate of baryta, tourmaline, epidote, hornblende, calcareous spar, quartz crystals, iron pyrites, magnetic iron ore, steatite, blende, black oxyd of copper, malachite, native copper, copper pyrites, amethystine quartz, ferruginous quartz, chalcedony, carnelian, agate, drusy quartz, hyalite? fibrous quartz, jasper, prase, (in the debris of the lake shore), dogtooth spar, augite, native silver, spodumene?, arsenite? of cobalt, chlorite; between Pigeon Point and Fond du Lac, near Baptism river, saponite, (thalite), in amygdaloid.

KETTLE RIVER TRAN RANGE.—Epidote, nail-head calc spar, amethystine quartz,

calcareous spar, undetermined zeolites, saponite.
STILLWATER.—Blende.

FALLS OF THE St. Choix.—Green carbonate of copper, native copper, epidote, nailhead spar.

RAINY LAKE.—Actinolite, tremolite, fibrous hornblende, garnet, iron pyrites, magnetic iron, steatite.

WISCONSIN.

At MINERAL POINT and elsewhere, copper and lead ores, principally silicate and carbonate of copper, copper pyrites, and galena, (only the last abundant). Also pyrites, capillary pyrites, blende, white lead ore, leadhillite (?), smithsonite (carbonate of zinc), anglesite, heavy spar, and calc spar.

SANK CO.—Specular iron! malachite, copper pyrites.

MONTERAL PRINCIPAL OF CALONE in gainered graphics.

MONTREAL RIVER PORTAGE.—Galena in gneissoid granite. Lac Du Flambeau R.—Garnet, kyanite

BIG BULL FALLS, (near).—Bog iron.

LEFT HAND R., (near small tributary).—Malachite, copper glance, native copper, red copper ore, earthy malachite, epidote, chlorite? quarts crystals.

IOWA.

Du Buque Lead Mines, and elsewhere.—Galena! cale spar, black oxyd of manganese; at Ewing's and Sherard's diggings, calamine ! or smithsonite; at Des Moines, quartz crystals, selenite; Mahoqueta R., brown iron ore.

CEDAR RIVER, a branch of the Des Moines .- Selenite in crystals, in the bituminous shale of the coal measures; also elsewhere on the Des Moines, gypsum abundant; argillaceous iron ore, spathic iron; copperas in crystals on the Des Moines, above the mouth of Saap and elsewhere, iron pyrites, blende.

MISSOURI.

BIRMINGHAM.—Limonite.

JEFFERSON Co., at Valle's Diggings.—Galona, white lead ore, anglesite, calamine, pyritous copper, blue and green malachite, carbonate of baryta.

MINE A BURTON .- Galena, white lead ore, anglesite, heavy spar, calc spar.

DEEP DIGGINGS.—Carbonate of copper, white lead ore in crystals, and manganese

MINE LA MOTTE. - Galena / malachite, earthy cobalt and nickel, bog manganese, sulphuret of iron and nickel, white lead ore in crystals, caledonite, plumboreainite, wolfram.

PERRY'S DIGGINGS, and elsewhere.—Galena, &c.
Forty miles west of the Mississippi and ninety south of St. Louis, the iron mountains, specular iron, limonite.

ARKANSAS.

BATERVILLE.—In bed of white R., some miles above Batesville, Gold.

OUACHITA Springs .- Quartz / Whetstones.

MAGNET COVE. - Brookite / schorlomite, elaclite, magnetic iron, quartz, green cocco lite, garnet, apatite.

CALIFORNIA.

Along the Sierra Nevada, gold, platinum (rare), iridosmine, molybdenite, molybdine, zircon, magnetic iron; near bay of San Francisco, actinolite, tale, serpentine, jasper, salt, gypsum, (island in the Caquines Straits); ridges of Sierra Azul, south of San José, cinnabar. Gold also found in the Umpqua region, Oregon, and the Shasty Mountains.

CANADA.

CANADA EAST.

ABERCROMBIE. -- Labradorite. BAY St. PAUL -Ilmenite!, apatite, allanite, rutile (or brookite!) AUBERT.—Gold, iridosmine, platinum. Bolton. - Chromic iron, magnesite, serpentine, pierolite, steatite, bitter spar, wad. BOUCHERVILLE. - Augite in trap. Brome. - Magnetic iron, copper pyrites, sphene, ilmenite, phyllite, sodalite, cancrinite, galena. CHAMBLY.—Analcime, chabazite and calcite in trachyte. CHATEAU RICHER.—Labradorite, ilmenite, hypersthene. DAILLEBOUT.—Blue spinel, with clintonite. GRENVILLE.—Tabular spar, sphene, idocrase, calcite, pyroxene, garnet (cinnamon stone), zircon, graphite, scopolite. HAM.—Chromic iron in serpentine. Inverness. - Varie jated copper. LAKE St. FRANCIS.—Andalusite in mica slate. Landsdowne.—Barytes.
MILLE Isles.—Labradorite! ilmenite, hypersthene, andesine, zircon. MONTREAL — Calcite, augite, sphene in trap. MORIN.—Sphene, apatite, labradorite. Polton.—Chromic iron, steatite, serpentine, amianthus. ROUGEMONT MTs.—Augite in trap. St. Armand.—Micaceous iron ore with quartz, epidote. St. François Brauck.—Gold, platinum, iridosmine, ilmenite, magnetite, serpentine, chromic iron, soapstone, magnetite, heavy spar. St. Jeboue.—Sphene, apatite, chondrodite, phlogopite, tourmaline, zircon, molybdenite, magnetic pyrites. St. Norbert.—Amethyst in greenstone. STURLEY .- Serpentine, verde antique / schiller spar. Surron. - Magnetic iron in fine crystals, specular iron, rutile, dolomite, magnesite, chromiferous talc, bitter spar, steatite. UPTON.—Copper pyrites, malachite, calcite. VAUDREUIL.—Limonite, vivianite. VAUDREUIL.—Limonite, vivi YAMASKA.—Sphene in trap.

CANADA WEST.

BALSAM LAKE.—Molybdenite, scapolite, quartz.
BRANTFORD.—Sulphuric acid spring, (4.2 parts of pure sulphuric acid in 1000).
BATHURST.—Heavy spar, black tourmaline, perthite (orthoclase), peristerite (albite), bytownite.
BROME.—Magnetite.
BURGESS.—Pyrozene, albite, mica, sapphire, sphene, copper pyrites, apatite, black spinel! spodumene, (in a boulder).
BYTOWN.—Calcite, bytownite, chondrodite, spinel.
CAPE IPPERWASH, Lake Huron.—Oxalite in shales.
CLARENDON.—Idocrase.
DALHOUSIE—Hornblende, dolomite.

DRUMMOND.—Labradorite.

and yielding a globule which becomes crystalline on cooling. On charcoal an arsenical odor. With the fluxes gives the reaction of cobalt. Occurs at berg in Saxony, with cobalt and iron ores.

ANNABERGITE, Haid. Nickel Green. Nickelocker. Nickleblüthe. Nick niaté, H.

Monoclinic. In capillary crystals; also massive and di nated.

Soft. Color fine apple-green. Streak greenish-white. ture uneven, or earthy.

Composition.—Ni³Ās+8Ĥ=Arsenic acid 38 41, oxyd of ni kel 37 59, water 100. Analyses: 1, Berthier, (Ann. Ch. Phys. xiii, 52); 2, Stromeyer, (Schw. 220); 8, 4, 5, Kersten, (Pogg. lx, 251):

Äв Ñi Ċо Ĥ 2.5 25.5=100, Berthier. 1. Allemont, 868 86.3 24 32, Pe 1 13, 8 0 23 = 100, S.; some Co 1 2. Riechelsdorf, 86.97 87.35 1.58 23.91, Fe trace=99.94, Kersten. —— 24.02, "2.21=100.13, Kersten. 8. Schneeberg, 88.30 · 86.20 88.90 85.00 37.21 86.10 trace 23.92, " 1.10, As 0.52=98.85, Kerster

B.B. darkens in color or becomes dull yellow; on charcoal gives out the reaction with the fluxes. This species is propably isomorphous with cobalt Occurs on white nickel at Allemont in Dauphiny, and is supposed to rest the decomposition of this ore; also at Kamsdorf, near Saalfeld, at Annal

Riechelsdorf, and other mines of nickel ores. It has been occasionally o associated with copper nickel in the cobalt mine at Chatham, Connecticut,

KÖTTIGITE, D. Zinkarseniat, Otto Köttig, J. f. pr. Chem. xlviii, 183, 184 Naumann, ib. 256.

Monoclinic, according to Naumann, and isomorphous wi balt bloom. Massive, or in crusts with crystalline surfac fibrous structure. Cleavage: perfect in one direction.

H=2.5-3. G.=3.1. Lustre of surface of fracture silky. light carmine and peach-blossom red, of different shades. § reddish white. Translucent to subtranslucent.

Composition.—(Zn, Co, Ni,) As+8H, or analogous to cobalt bloom. Anal Köttig, (loc. cit.):

Ās (by loss) 87-17, Žn 80-52, Čo 6-91, Ni 2-00, Ča trace, Ĥ 28-40=10

In a matrass yields water and becomes pale smalt blue. B.B. on charcos outer flame changes color and fuses to a pearl, gives out fumes of arsenic, and a slag of oxyd of zinc. Gives a cobalt and nickel reaction. In dilute acid dissolved.

Occurs with smaltine at the cobalt mine Daniel, near Schneeberg. The owing partly to the arsenate of cobalt in the mineral.

SYMPLESITE, Breithaupt, J. f. prakt. Chemie, x, 501.

Monoclinic; in form resembling Cobalt Bloom. fect parallel with the larger lateral face. In minute pris crystals; also aggregated.

H=2.5, nearly. G=2.957. Lustre of cleavage face pe elsewhere vitreous. Color pale indigo, inclined to celandines

APPENDIX.

APPENDIX TO FIRST VOLUME.

Mathematical Crystallography.—P. 75, fifth line from top, the formula ma tan $\frac{1}{2}V_{\frac{1}{2}}$ should read ma=tan $\frac{1}{2}V_{\frac{1}{2}}$.

P. 87. In the Monoclinic System, the values of the axes, (the clinodiagonal b being a unit), are readily obtained by the following equations; X being half the front angle of the prism (or half of I:I) and X' half the angle above of the clinodome $1-\infty$ (or half of 1i: 1i over O):

> c=Tan $X \sin C$, $a=\operatorname{Tan} X+\operatorname{tan} X'=\operatorname{tan} X\operatorname{cot} X'.$

The proportion $a:b = \sin \mu: \sin \nu$, in the seventeenth line from bottom of this page should be $a:b=\sin \nu:\sin \mu$.

P. 92. The heading Monoclinic System should be Monometric System.

Atomic Weight of Glucinum.—J. Weeren has obtained for the atomic weight of Glucinum 86.50. Pogg. xcii, 128, 1854.

P. 189. Homeomorphism.—In a paper on the relations between Chemical Composition and Crystalline Form, (Paris, 1852), by M. Ladrey, from whom it has been just now received, the author reviews many different classes of compounds, principally minerals, and shows that all or nearly all of the forms may be obtained from fundamental forms, near 90° in angle, by assuming as the fundamental form where necessary, one having some simple relation to that usually so adopted. Relations to the monometric system are thus brought out, and also homosomorphisms independent of composition. In deducing the relations, cleavage, twin composition, and all other points bearing on the actual or potential dimensions of a species, are disregarded; points which are dwelt upon in the chapter on homeomorphism, and which have led the author to a similar general conclusion by a different, and, as we believe, by a more consistent method.

Rammelsberg has published an important paper in Pogg. xci, 321, on the Crystallization of Isomorphous Salts together. In the Ann. de Ch. et de Phys. [3], xxxix, 404, 1853, M. J. Nicklès has a valuable memoir "On Polymorphism."

Pseudomorphs, p. 222.—Add the following to the catalogue. They are mostly from a paper by Prof. Reuss of Prague, (1853):

Hematite	after	Cerusite.	Pyrites	after	Brown Spar.
"	"	Feldspar.	Marcasite	"	Barytes.
Galena	"	Cerusite.	Chalcopyrite	**	Magnetite.
Pharmacolite	**	Realgar.	ā*	"	Nagyagite. Orthoclase.
Garnet	**	Calcite.	Thorite	**	Orthoclase.
Carneita	44	Calcita			

P. 250. In the Classification of Minerals, the Fluorids are arranged along side of the Chlorids, where some chemists place them. The element Fluorine appears to be intermediate in character between Oxygen and Chlorine; and it is probably better to make for it a separate division, arranging the species (p. 250) as follows:

III. CHLOBIDS, BROMIDS, IODIDS.

1. Calomel Division, &c.—Calomel.
2. Rock Salt Division, &c.—Rock Salt Group, Sylvine, Rock Salt, Sal Ammoniae, Kerargyrite, Bromyrite; Iodyrite Group, Iodyrite; Cotunnite Group, Cotunnite.

I. BINARY COMPOUNDS.—1. Fluor Group, Fluor Spar, Yttrocerite; Fluorerite Group, Fluocerite. II. DOUBLE BINARY COMPOUNDS, Cryolite, Chiolite. Then v. oxygen compounds, and so on.

APPENDIX TO SECOND VOLUME.

1. New or Unarranged Species.

BARNHARDTITE, Genth, (communicated to the author).—Massive, and of a pale bronze-yellow color, near that of pyrites, but Iustre less bright, and tarnishe easily to pinchbeck and pavonine tints. Cleavage none. Streak black, slightly shining.

Composition.—2 CuS+Fe'S'. Analyses, by P. Keyser and W. J. Taylor, under the direction of Dr. F. A. Gepth:

1. Pioneer Mills, Sulphur 30:50 Copper 48:40 Iron 21:08, Keyser.

2. Dan Barnhardt's, 29:40 47:61 22:23, Ag trace, Taylor.

B.B. gives sulphur fumes, and fuses to an iron-black magnetic globule; with the fluxes, reactions of iron, copper, and sulphur.

From a mine on the land of Dan Barnhardt, Cabarras Co., North Carolina; also near Pioneer Mills, and at the Phenix and Vanderberg Mines in the same county, and in the neighborhood of Charlotte in Mecklenburg Co.

CAROLATHINE, F. L. Sonnenschein, (J. f. pr. Ch. lx, 268, 1853).—Massive, or in rounded balls. Color honey-yellow to wine-yellow. Subtranslucent. H.=24 G.=1.515. Fracture conchoidal.

Composition.—Analysis afforded H 2·41,O 19·39.C 1·33, for the volatile part, (water included) with \$\frac{1}{4}\$1 47·25 and \$\tilde{S}\$i 29·62 for the fixed. This last corresponds to the formula \$\frac{1}{4}\$I\$\tilde{S}\$i\frac{1}{2}\$, as in Andalusite. Heated it affords water, which is neutral in its reactions, and decrepitates at a higher temperature, the color becomes darker, and a black shining mass is obtained. B.B. ignites somewhat without flame, and affords the reaction of alumina and silica.

From a bed of mineral coal near Gleiwitz in Upper Silesia. Somewhat resembles Mellite. Named after the Prince of Carolath.

CHALCODITE, Shepard. (Shep. Min. 3d. ed. 153).—Chalcodite appears to be near Anthosiderite, (p. 804). It occurs in minute thin laminse, aggregated in tufts, and forming very short velvety coatings, on hematite; color yellow and brownish-yellow, with a pearly bronze lustre; laminse tender, flexible. Dissolves easily in hot muriatic acid. B.B. like Anthosiderite. Occurs at the Sterling Iron Mine, Antwerp, Jefferson Co., N. York.

DELANOVITE, Kenngott, (Jahrb. k. k. Geol. Reicha., iv, 633).—A reddish amorphous earthy mineral, H.=1-1.5; fracture splintery to earthy; adheres to the tongue; streak reddish, a little shining; B.B. infusible. Analysis by C. von Hauer, (loc. cit):

14.03 per cent. of water was driven off at 100° C. The oxygen ratio for R. R. Si, H, is nearly 1:2:6:15=R*Si²+2HSi²+45H, or (1R²+1H)Si²+15H, a composition which suggests that it may have proceeded like Cimolite from the alteration of Augite. From the department of Dordogne, France. Kenngott places it near Montmorillonite.

IODO-BROMID OF SILVER.—M. Louis Semann announces by letter to the author, that he has distinguished an iodo-bromid of silver among the minerals of Chili.

LINDACKERITE, J. F. Vogl. (Jahrb. k. k. Geol. Reichs., iv, 552).—In oblong rhombohedral tables, probably trimetric, grouped in rosettes and reniform masses. H.=2-2.5; G.=2-2.5. Vitreous; verdigris to apple-green; streak pale-green to white. Composition.—2Cu²As+Ni²S+8H. Analysis by Lindacker, (loc. cit.): As 28.58, S 6.44, Cu 36.34, Ni 16.15, Fe 2.90, H 9.32=99.73. B.B. on charcoal

APPENDIX. 501

alliaceous fumes, and fuses to a black mass. With borax and salt of phosphorus a copper reaction. Soluble after long heating in muriatic acid, the solution giving a yellowish brown precipitate with sulphuretted hydrogen.

LÖWEITE.—A yellowish saline mineral, from Ischl, approaching Astrakanite, (p. 379), affording the formula MgS+NaS+24H=Sulphuric acid 51.94, magnesia 13.20, soda 20.27, water 14.59=100. Karafiat obtained, (Haid. Ber. Wien, 1846, 266), Sulphuric acid 52.35, magnesia 12.78, soda 18.97, water 14.45, peroxyd of iron and alumina 0.66=99.21. G.=2.376.

MANGAN-VITRIOL, or Sulphate of Manganese.—Announced by Glocker, but imperfectly known.

MENEGHINITE, Bachi, (Am. J. Sci. [2], xiv, 60.—In compact fibrous forms, very lustrous; H. =2.5. Composition.—PbS+4SbS, Bechi, whose analysis afforded (loc. cit.), S 17.522, Sb 19.284, Pb 59.214, Cu 3.540, Fe 0.844=99.904.

From Bottino in Tuscany, where it was obtained by Prof. Meneghini, along with Boulangerite and Jamesonite. The atomic proportions are those of tetrahedrite.

PARACOLUMBITE, Shepard, (Proc. Amer. Assoc., iv, 313, and Amer. Jour. Sci. [2], xii. 209).—In grains and short irregular seams, of an iron-black color, with a tinge of purple and a black streak; lustre imperfectly metallic. H. about 5. B.B. fuses readily to a black glass, which is not magnetic. With borax dissolves rapidly, the glass yellowish-brown while hot, but paler on cooling. Easily attacked by sulphuric acid, and gives reaction for fluorine; a heavy white precipitate falls, "unmixed with silica." The solution filtered was not rendered milky by boiling; it was decomposed by ammonia, and the precipitate "of mixed oxyds of uranium and iron was treated with carbonate of ammonia, which dissolved the latter, and showed its proportion to be small when compared with the former." Whence it is stated to consist probably of oxyds of iron and uranium, with some metallic acid not the titanic.

Occurs about a mile southwest of the village of Taunton, Mass., disseminated in very minutes quantities through a very large boulder, lying in a field contiguous to the highway.

PARTSCHIN, Haidinger, (Haid. Ber. iii, 440).—Found in grains in small monoclinic crystals, somewhat resembling Monazite. H.=6-6.5; G.=4-4.1. Color reddish-brown. Lustre greasy. Fracture splintery.


reddish-brown. Lustre greasy. Fracture splintery.
In sand from Olahpian in Hungary with Rutile, Ilmenite, Zircon, Kyanite. Named after P. Partsch, of the Vienna Museum.

PERCYLITE, H. J. Brooks, (Phil. Mag. [3], xxxvi, 131, 1850).—Monometric. In minute cubes; planes O, 1, I, i2. H.=2·5. Color sky-blue; streak similar.

Composition.—Contains, according to Percy, (loc. cit.), lead, chlorine, and copper, and probably oxygen; the quantity under analysis was too small for complete results. The examination gave, besides some water, chlorine 0.84, lead 2.66, copper 0.77, corresponding to equal atomic equivalents of these ingredients. Mr. Percy supposes that an equivalent of oxygen should be added, and writes the formula (PbCl+PbO)+(CuCl+CuO)+Aq. B.B. by slight heat the blue color changes to emerald-green, and reappears on cooling; in the outer flame, the flame is green within and blue at the edges; fuses very easily, and in a tube fumes were given off, but no odors were perceived. On charcoal in the inner flame metallic globules are obtained, which dissolve without residue in dilute nitric acid. With borax in the outer flame, a transparent bluish-green bead is obtained, which in the inner flame becomes turbid and brownish-red.

Accompanies gold in a matrix of quartz and red oxyd of iron, and is said to have come from La Sonora, in Mexico.

PRASOCHROME, Landerer.—A result of the alteration of chromic iron on the island Scyro, Grecian Archipelago, forming a dull green incrustation. Contains carbonate of lime colored by oxyd or chrome.



PROSOPITE, Scheerer, (Pogg. xc, 315).—Supposed from some qualitative trials on portions that were unaltered, to comin of aluminium, calcium, fluorine, and water. Occurs at the tin mines of Altenberg, in crystals which are mostly altered to Kaolin. Scheerer points out a relation in some angles to Berytes; but the form is in fact very much like that of Datholita as shown in the angles and in the annexed figure, altered in position from that given by Scheerer; 3: 3 =77° to 78°, (78° 44, in Datholite); 0: 21=185°, (same in D.); 2: 2=182°, (181° 52' in D.); 21: 21 (top)=1161°, (115° 26' in D.); 23: 23 =118°. (118° 9' in D.)

Is it possible that the fluorine has been introduced through the process of alteration, and that the mineral is when unat-tered, nothing but Datholite! The name is from **possurus**, a mask, and alludes to its deceptive or masked condition.


RIOLITE, Probel.—A selenid of silver, consisting according to Del Rio, of Silver 57 66, selenium 42 34—Ag Se³. Occurs in small hexagonal tables of a lead gray color and malleable, at Tasco in Mexico. Requires further examination. The composition and form would place the species in the Covelline Group, p. 54.

STRAKONITZITE, von Zepharovich.—A yellowish green steatite-like miseral, forming pseudomorphs at Mutenitz, near Strakonitz in Bohemia, with fluor spar which is partly incrusted with quartz, and also sphene and pyrites in orthoclass and quartz. It is soft with a greasy feel, and G.=1-91. Analysis afforded von Zepharovich, (Jahrb. f. k. k. Reicha, iv, 695):

Fe 15:41 Bi 53.42 ₹r 7.00 Ča 1.37 Mg 2.94 The powder is pale yellowish, and becomes dull brown on heating.

TELLURIC OCHRE, (Tellurite, Nicol, Tellurige Saure, Petz).-Occurs with native Tellurium at Facebay and Zalathna in Transylvania, in small yellowish or whitish spherical masses, with a radiated structure; also as an earthy coating. Supposed to be Tellurous acid.

TUNGSTATE OF COPPER.—Announced by Dr. Genth, as occurring at Dr. Cosby's mine near Pioneer Mills, Cabarras Co., North Carolina, along with Wolframine, Wolfram and Scheelite, the last in large, but not very distinct, crystals.



TURNERITE, Levy, (Ann. of Phil. xviii, 241).—Monoclinic. M: M=86° 10', P: M=99° 40'; M: &= 188° 5'; P: &=133° 50. Cleavage parallel with both diagonals of the prism, one more perfect than the other.

H. above 4. Lustre adamantine. Streak white or grayish. Color yellow or brown. Transparent translucent.

Composition.-According to Children, it contains alumina, lime, magnesia, and a little iron; and it differs from sphene, of which it has been considered a

variety, in containing very little silica and no titanium. It requires further exam-

ination, in order to determine its place in the system.

Accompanies quartz, albite, feldspar, crichtonite, and anatase, at Mount Sorel in Dauphine. It was distinguished by Lewy, and named in honor of Mr. Turner, is whose collection it was first found.

URANIUM, BASIC SULPHATE OF, H. Dauber, (Pogg. xcii, 251, June, 1854)—Occurs in citron-yellow microscopic, rhombic or hexagonal tables, and in spherical aggregations. An analysis afforded Sulphuric acid 40, oxyd of uranium 79.9, water 14.3=98.2, corresponding to 50, 15, 15H. Is it a simple chemical compound?

WILSONITE, T. S. Hunt, (Logan's Geol. Survey of Canada, 1853).—Massive. Cleavage perfect in two directions at right angles with one another, and giving square prisms; a cross cleavage at right angles with one of those cleavages and inclined 110° to 115° to the other. [According to the examination of fragments by the author, this last cleavage may be only a fracture, a supposition sustained by the wide variation mentioned in the angle of inclination]. H.=3.5. G.=2.765—2.776. Lustre vitreous, shining, occasionally pearly on cleavage surfaces. Color reddish, rose-red to peach-blossom-red. Subtranslucent. Fracture uneven.

Composition.—Analysis by T. S. Hunt:

B.B. whitens, becoming opaque, and losing water; fuses with intumescence to a white enamel. Occurs at Bathurst, C. W., with apatite, calcite, and pyroxene. Some resemblance in appearance to scapolite.

Mineral from Italy, (Sitzungsb. Wien. x, 179).—This mineral substance is probably a mechanical mixture. It is crystalline; light greenish to wine yellow; translucent; shining with a waxy lustre; streak white. H.=5.5. G.=2.969.

It affords no probable formula. Wholly soluble in sulphuric acid, and but little attacked by muriatic acid. B.B. on charcoal melts easily to a colorless blebby glass, phosphorescing. With borax easily forms a colorless glass.

Meteoric Minerals.—Several substances occurring in meteorites have been named by C. U. Shepard as minerals, which are imperfectly described and little known. See Am. J. Sci., [2], ii, 377, vi, 402. xv. 363. They are called Apatoid, Sphenomite, (so called from Sphene), Dyslytite, Iodolite, Chladnite, Chantonnite, Schreibersite, (changed by Haidinger to Shepardite), Hyposulphite of Soda, Hyposulphite of Magnesia, (Am. J. Sci., ii, 377), Olivinoid, (so called because like Olivine), Howardite, (ib. vi, 402), Partschite, (ib. xv, 366).

2. Additional notices of described species.

Amber.—According to Prof. Goeppert, Amber is derived from at least eight species of plants besides the Pinites succinifer. The resin is supposed to have been altered to Amber through fossilization. Prof. Goeppert enumerates 163 species of plants represented by remains in Amber.—Monatsb. Akad., Berlin, 1853, and Am. J. Sci., [2], zviii.

ANATASE, p. 121.—Kenngott obtains for O: 1, 111° 42′, 1:1 (pyr.) 97° 51′, O: 1i ==119° 22′.—Min. Russl., 49.

BERTHIERITE, p. 73.—Specimens from the mine Neue Hoffnung Gottes, near Freiberg, afforded C. v. Hauer (Jahrb. k. k. Geol. Reichs., iv, 635), Sulphur 30.53, iron 10.16, antimony 59.30—99.99.

BISMUTHINE, p. 33.—An artificial sulphuret of Bismuth afforded G. Rose the following angles: $I: I=90^{\circ} 40'$, ii: $i=53^{\circ} 40'$ and $126^{\circ} 20'$, $I: i=135^{\circ} 20'$.—Pogg. xci, 402, 1854.

Bolz, p. 252.—Analyses by C. von Hauer, (Jahrb. k. k. Geol. Reichs., iv, 684):

- 1. C. di Bove, Si 45.64 \(\frac{1}{4}\) 29.33 \(\frac{1}{4}\) 8.88 \(\hat{O}\) 0.60 \(\hat{Mg}\) trace \(\hat{H}\) 14.27=98.72.
- 2. N. Holland, 38.22 81.00 11.00 trace trace 18.81=99.08.
- 3. Discovery Id., 87:12 20:00 22:47 2:99 trace 17:62=100:20.

Probably results of alteration of feldspathic or some aluminous mineral.

Sinopite, Hausm. is the Bolus of Sinope; Stolpenite, Kenngott, is the bole of Stolpen; Oropion, Glocker, is Bergseife, p. 252. The right to a name in each of these so-called species is very questionable.

CALAMINE, p. 313.—Altenberg crystals of Calamine have been measured by H. Dauber, Pogg. xcii, 245, June, 1854.

CALCITE, p. 435.—The Fontainbleau crystals contain, according to Delesse, upwards of fifty per cent. of sand. In one crystal, G.=2.84, he found fifty-seven per

cent. of mixed sand; in another sixty-two per cent.; another G.=2.53, sixty-three per cent.; in a less perfectly crystallized spheroidal mass, eighty-three per cent. Halle Zeitschr, 1854, 215. F. W. Wimmer describes a crystal of Calcite affording the scalenohedron $-\frac{87}{7^2}$, ib., 1854, 334.

CATAPLETITE.—The crystallization of Catapleiite, according to H. Dauber, is hexagonal. The crystals have the edges replaced by the planes 1, 2, 4; $O:1=142^{\circ}$ 1½', $O:2=122^{\circ}$ 38½', $O:4=107^{\circ}$ 45½'.—Pogg. xcii, 239, June, 1854.

CHILETE.—Domeyko's vanadate of lead and copper, p. 363, is named Chileite by Kenngott. This is the second species so called, the name being a synonyme under Göthite.

Chloropal, p. 337.—Named *Unghwarite* by Glocker, and regarded as a good species by Kenngott. Occurs amorphous; H=2.5-3; G=2.10-2.16; greenish-yellow; streak greenish-white; lustre weak waxy. B.B. infusible, but becomes brown to black in a glass tube, and gives off water. Muriatic acid takes up the hydrate of iron. Von Hauer obtained in an analysis, (Kenngott's Min. Notizen, ix),

Si 5776 Fe 20.86 Ca 177 H 1978=100.17.

This result differs considerably from other analyses.

CHRYSOCOLLA.—L. Sæmann communicates to the author that he has specimens of Chrysocolla from Chili, which have in the interior the fibrous structure and composition of pure malachite, showing that the whole was once malachite.

In an earthy Chrysocolla-incrustation from Chili, Berthier found sulphuric acid, (analysis p. 310); and in another Kittredge (anal. 11, p. 310) obtained neither carbonic nor sulphuric acid.

The Chrysocolla analyzed by Scheerer, (anal. 8, p. 310), occurs with feldspar, and is supposed to have resulted from the action of sulphate of copper on the feldspar.

Bischof observes (Lehrb. ii, 1885) that silicate of copper may be formed through the action of an alkaline-, lime-, or magnesia-silicate on sulphate or nitrate of copper in solution. He also shows that this silicate is decomposed by carbonated waters, producing carbonate of copper. The silicate is slightly soluble in pure water, and therefore may act in forming the pseudomorphs after carbonate of lead and libethenite, which have been described. Its solubility and formation by the methods stated, account for its occurrence in hydrous silicates, as Allophane. The alkaline silicates are furnished by the decomposing granite, and the sulphate of copper by altered pyritous copper.

CLAY AND CLAYET EARTHS, EARTHY HYDROUS ALUMINOUS SILICATES.—Various compounds of this nature are described on pp. 165, 249 to 263, and 337 to 346. The following are others:

Sphragide, Hausm.—A yellowish-gray earth or clay, speckled with red, called Lemnian earth; Anunca oppayers of the Greeks; Siegelerde of the Germans. Adheres but little to the tongue, and falls to pieces in water. Analysis by Klaproth, Beit iv, 338, specimen from Stalimene, the ancient Lemnos.

Fuller's Earth, (Walkerde, Wern; Walkthon, Haussn).—Earthy with a shining streak; greenish-gray, oil-green, white, yellowish, reddish, red, brown; G=17-24; feel either greasy or harsh; adheres a little to the tongue; falls to pieces in water. Analysis by Klaproth, Beit. iv, 338, and Thomson.

Occurs in connection with the chalk, oolite, &c. Found in England at Nutfield near Riegate, in Sussex; near Maidstone, in Kent; Woburn, in Bedfordshire; at Vahls, near Aix la Chapelle; Rosswein, in Saxony; Zwikowetz, in Bohemia; and elsewhere.

Potter's Clay.—Analyses of Potter's Clay by Klaproth, Beit. vi. 281, and by Aubert and Berthier, Dict. Tech. xvii.

Secretic. - A variety of halloysite, analysis by Pelletier, Beud. Tr. ii, 36.

Onkosia, Kobell.—In roundish pieces, having an apple-green color; sometimes grayish or brownish; lustre weak, greasy; translucent; H.—2; G.—2.8; fracture fine splintery. Analysis by Kobell, J. f. pr. Chem. ii, 295. From Salzburg. B.B. fuses with intumescence to a white blebby glass; in sulphuric acid soluble, but not in muriatic.

505

				S i	Æl	₽e	Мg	Ča	Ňа	茁	
1.	Sphragic	le, Sta	limene,	66.00	14.50	6.00	0.25	0.25	8.50	8.50, Klaproth.	
2	Fuller's.	Earth	, Riegate,	58.00	10.00	9.75	1.25	0.20		24 00, K trace,	
										NaCl 0.10, Klap.	
3.	"	"	Silesia,	48.50	15.20	6.20	1.20	0.20	_	25.50, Klap.	
4.	"	"	Maxton,	57.105	31.850	2.615				7.280, Thom.	
5.	Potter's	Clay,	Silesia,	61.	27 ·	1.				11, Klap.	
6.	"	"	France,	57· 0	37·0	4.0		17		—, • Aubert.	
7.	"	"	44	60.0	80.0	7.6		2.4	.—	, Berthier.	
8.	Onkosin			52.52	30.88		8.82F	e0.80	K 6·38	4.60, Kobell.	
9.	Severite,			50.	22.					26, Pelletier.	
a Water excluded.											

Anauxite, Breith.—Anauxite is greenish-white, pearly, granular, with cleavage in one direction; translucent; H.=2·3; G.=2·26. Plattner obtained, (J. f. pr. Ch. xv, 325), 55·7 silica, 11·5 water, with much alumina, a little magnesia and protoxyd of iron. A doubtful if not bad species. From Bilin, in Bohemia.

CLINTONITE, p. 297.—Two recent analyses of this mineral by G. A. Brush, (communicated to the author, by letter dated München, Aug. 7, 1854), afforded,

 Si
 Al
 Fe
 Zr
 Ca
 Mg
 Na
 K
 H

 1.
 20.24
 89.13
 8.27
 0.75
 13.69
 20.84
 1.14
 0.29
 1.04=100.89.

 Oxygen, 10.74
 18.29
 0.98
 0.20
 3.89
 8.34
 0.29
 0.03
 0.92.

 2.
 20.18
 38.68
 3.48
 0.68
 18.35
 21.65
 1.14
 0.29
 1.05=100.45.

 Oxygen, 10.69
 18.07
 1.04
 0.18
 3.80
 8.66
 0.29
 0.03
 0.98.

These results of Mr. Brush give for the oxygen ratio of R, H, Si, 12:55:19:47:10:74 and 12:78:19:29:10:69. Adding the oxygen of the protoxyds and peroxyds, the ratio for R+H, Si becomes 32:02:10:74 and 32:73:10:69, or very closely 3:1, while the ratio for the oxygen of the protoxyds and peroxyds is 2:8; the former of which ratios, however expressed in a formula, appears to be the characteristic of the species. Kobell's Disterrite afforded the oxygen ratio for R, H, Si, 11:24:21:26:10:60, and for R+H, Si, 32:50:10:60, which gives the same oxygen ratio 3:1 nearly for the bases and silica. Both correspond to (R', H)Si¹+Aq, with R': H as 2:8 in the Clintonite, and 1:2 in the Disterrite. The water is nearly wanting in the Clintonite, according to Brush.

in the Chitonite, according to Brush.

If we regard one third of the peroxyds in Brush's analysis as replacing silica, the oxygen ratio for B, H, (Si), becomes 12.78: 12.86: 17.12; 'or between the bases and the rest 25.64: 17.12=3: 2, giving the formula (\(\frac{1}{2}\)\)B*+\(\frac{1}{2}\)H) (\(\overline{8}\)i, \(\overline{1}\)H); which is the formula deduced on pp. 289, 297.

COPPER GLANCE, p. 46.—A crystal weighing half a pound has been found in the mines near Angina, Tuscany. The Mount Catini Mine affords Copper Glance, and also Native Copper, Red Copper, and Copper Pyrites.

COVELLINE, p.65.—The Covelline of Leogang, in Salzburg, occurs mostly massive, but affords minute crystals, according to Kenngott, which present faces of two hexagonal pyramids; the acuter pyramid has for its basal edges the angle 155° 24'; and the inclination of a face of this pyramid on one of the other is 150° 24'. Color: indigo-blue, with submetallic somewhat greasy lustre, a little pearly on the cleavage face; streak black; H.=1.5—2. G.=1.636—4.590. Analysis afforded Sulphur 34.30, copper 64.56, iron 1.14.—Kenngott's Min. Notizen, No. ix.

DEWEYLITE, p. 285.—A variety from Fleims (called Gymnite by the author, but correctly Deweylite, as this is the earlier name) afforded von Widtermann, (Jahrb. k. k. Geol. Reichs., iv, 525), Si 40.82, Mg 36.06, water 21.72, Fe 0.42, C 0.59=99.61, agreeing closely with Œllacher's analyses of this mineral from the same locality, (Anal. 4, p. 286).

An earthy variety from the same place affords Si 49 06, Mg 28 50, H 16 25, Fe 0 69, C 4 76 = 99 28, affording the oxygen ratio for H, R, Si, nearly 3:2:5.

ELIASITE, p. 108.—This species differs widely from Pitchblende in its lower specific gravity and the large proportion of water.

Enargite, p. 87.—Crystals of Enargite, which are trimetric, have been messed by H. Dauber. He obtained for I:I, 97° 53′. Other observed planes, it, it, it, 1%, 1%, with the pyramids 1 and $\frac{1}{2}$. $O:1\%=140^{\circ}$ 29′; whence by calculation, 0:1 $=186^{\circ}$ 87′, $O:\frac{1}{2}$ =154° 43′, $O:2\%=117^{\circ}$ 53′, $O:1=147^{\circ}$ 55′.—Pogg. xcii, 237.

FELDSPAR.—M. Scheerer obtains for an albite from Snarum the oxygen ratio for R, E, Si, 1:3:11; and as the ratio is intermediate between that of albite and efgoclase, he proposes to call it oligoclase-albite. A feldspar from the xircon-symite of Norway, analyzed by C. Gmelin, he regards as consisting of 1 of oligoclase; albite, and 1 of orthoclase; another from the Syenite of Ballons, as composed of 1 of oligoclase and 2 of orthoclase; and the same for another from Plombières, as lyzed by Delesse. Bull. Soc. Geol. de France, [2], xi, 146.—T. S. Hunt offered same theoretical views on the composition of the Feldspars to the American Association, at the meeting in 1854, at Washington. See Am. J. Sci., [2], xviii, 269.

GABRONITE, Beudant (Traité, ii, 94).—L. Sæmann observes that he has seen in the School of Mines, Paris, truncated square prism of the gabronite, which show that the mineral is Scapolite. (Communicated to the author).

GALENA, p. 89.—A variety in cubes, containing manganese, probably from Hartenrod, near Gladenbach, afforded Sandmann, S 18-80, Pb 83-52, Fe 0-83, M 1-20, Ag 0-14=99-49. H.=2-5. G.=7-11. B.B. a strong manganese reaction. Ass. Ch. u. Pharm. lxxxix, 364.

GIBBSITE, p. 134.—The Villa Rica (Brasil) Gibbsite afforded von Hauer, Alumins 64-35, water 35-65, phosphoric acid, a trace=100.—Jahrb. f. k. k. Reiche., iv, 397.

HEMATITE, p. 113.—Kokscharov has elegantly figured and describes several form of hematite crystals in his Materialen zur Min. Russlands. Besides the plane enumerated on p. 113, he mentions $\frac{2}{3}$ as presented by Russian crystals. He eltained for R: R 86°; for $\frac{2}{3}$, terminal edges 147° 23′ 13″, 111° 40′ 23″, and for the middle (or basal) edge 114° 46′ 20″.

HESSITE, p. 44.—This species, according to Kenngott, (Sitzb. Wien. xi, 20, 1853), is trimetric; the crystals show the faces it, it, I, besides another vertical prism undetermined.

HYDROHALITE, Mitscherlich.—A hydrous Chlorid of Sodium. Composition Ns Cl+4 H=Chlorid of Sodium 62:0, water 88:0=100.

HYDROPHILITE, Glocker .- A name applied to Chlorid of Calcium.

IDOCRASE, p. 197.—Kohscharov has published an elaborate memoir with many fine figures on the Russian idocrase, in his Min. Russlands, p. 92. From crystals from the Poljakowsk mine he found $O:1=142^{\circ}$ 464° . Jefreinoffite is a variety of idocrase from Finland, containing according to Ivanoff, Si 37-41, Ca 34-20, \pm 1 2000. Fe 4-60, K 1-16, Na 1-70=99-07. It is usually yellowish-brown, but sometimes colorless. Kohscharov's Min. Russlands, 116.

ILMENITE, p. 115.—Kokscharov mentions the rhombohedron Russian ilmenite. Min. Russl. 20.

IODYRITE, p. 95.—Two analyses of this silver ore have afforded J. Lawrence Smith the following results, (communicated to the author by letter, dated Louiville, Ky., Aug. 23, 1854):

Iodine, 52-934 58-109 Silver, 46-521=99-455 46-380=99-489,

with traces of copper and chlorine.

KAOLIN.--The author is indebted for the mode of presenting the analyses of Kaolin, on p. 249, to M. Louis Sæmann of Paris. M. Sæmann observes that the hydrous silicates of alumina proceeding from the decomposition of the feldspars never

507 APPENDIX.

contain more alumina than silica, and they mostly come under the formula \$1.5i+2H\$. The species Collyrite, Allophane, Scarbroite, and Miloschine, which contain much less silica, have not proceeded from the decomposition of feldspars, but through sulphates of alumina produced by the alteration of pyrites. The earthy silicates constitution of the decomposition of th taining two or more equivalents of silica have probably proceeded from the decomposition of aluminous pyroxenes.

LAVENDULAN, p. 417.—According to trials by J. Lindacker, (Jahrb. k. k. Geol. Reichs., iv, 555), Lavendulan contains oxyd of copper, arsenous acid, and water, with also oxyd of cobalt, lime, and sulphuric acid. It is a result of alteration of different ores, and occurs with arsenates of cobalt and nickel, nickel ochre, copper black, and cobalt pyrites.

LEADHILLITE, p. 371.--Fig. 1 of Leadhillite, is taken from Mohs, (pl. 13), but altered by the addition (though of reduced size) of the planes wanting through hemihedrism, (the right hand $I, \frac{8}{32}, \frac{2}{22}, \frac{2}{12}, \frac{2}{12}$), in order to exhibit the relations of the planes.

LEEDSITE, Thomson.—Regarded as a mechanical mixture of sulphates of lime and baryta. Thomson's analysis afforded 71.9 of the former to 28.1 of the latter. From near Leeds, Yorkshire, England.

LEUCOPYRITE, p. 61.—The Sätersbergite of Kenngott includes analyses 4 and 5, p. 61.

LIMESTONE FOR HYDRAULIC PURPOSES; SUBCARBONATE OF LIME — According to Villeneuve, (Bull. Soc. Geol. de France, [2], x, 842), the hydraulic mortar owes its character to the formation of subsalts of lime, magnesia, alumina, or iron, with carbonic acid and silica, that is, salts containing an excess of base. Lime may form a subcarbonate (containing two equivalents of lime and one of acid) which is insoluble, and has hydraulic characters. This subcarbonate contains half an equivalent of water; with the silica a subsilicate forms containing 5 of water; and he observes also that there is a subaluminate with 7½ equivalents of water. These subsalts are stable only below a temperature of 212° F. The virtue therefore of the hydraulic rock depends on the excess of bases or earthy ingredients. M. Delesse has detected a hydrated subcarbonate of lime in bone caverns of the Jura beds.

A specimen from Madras afforded Pfeiffer, (Ann. Ch. u. Pharm, lxxxix, 219), C 50.64, Mg 46.12, Ca 0.35, Na 0.42, K 0.67, Al 0.26, Si 0.28, H 0.16, P and Cl trace=98.85.

Mica.—An elaborate paper by Joseph Grailich, on the optical characters of the micas, has recently appeared in the Sitzungsberichte der kais. Akad. der Wissenschaften at Vienna, (vol. xi, p. 46). It contains the following measurements of the optical angles of micas:

1. Angle of Divergence of the Axes small.

1. Plane of the axes in the line of the shorter diagonal.—Green in limestone, Vesuvius 0°-1°; dull-green to colorless, ib., 1°; brownish-green. ib., 2°; bluish, ib., 3°; white, from Easton, Pa., 1°-2°; green, ib., 3°-4°; brown, from Upper Hungary, in calcite, 4° 30′; brown in feldspar, from Warwick, 4°-5°; gold yellow, from Baritti, Brazil, 5° 30′; meroxene, from Fassa Valley, 1°-8°.

2. Angle between the optical axes 0°.—Dark green mica of Zillerthal; ib. from Norway; dark olive green, from Kariat; blood red in thin plates, from Besztereze, in quartz; from Retzbanya, in calcite with chalcopyrite; dark-green from Goshen, (New York probably), submetallic in lustre; liver-brown, from Anaksirksarklik; black, in thin leaves blood-red, from Leonfelden; dark-greenish, from Kingiktorsoak, Greenland; dull-red, from Magura, in granite; bluish, from Altenberg; black, from Horn, Upper Austria.

3. Optical axes in the plane of the longer diagonal.—Brown mica, from Frascati, in six-sided tables, 0°-1°; brown, six-sided pyramids, from Cayuga-lake, N. Y., 1°-2°; hexag. tables, from Pellegrino, Tyrol, in calcite, 0°-1°; blackish-green, from Greenwood Furnace, 0°-1°; sea-green, from Karosulik, 1°-2°; chesnut-brown, from L. Baikal, 1°-2°; liver-brown, in large tables, 5°.

4. Doubtful as to which diagonal coincides with the plane of the optical axes.—

Brown, from Moravia, 6°; liver-brown, from Gargenberg, Suabia, 5°; dark-brown,

from Eden, Orange Co., N. Y., 2°; pistachio-green, from Gömör, 2° 30'; pinchbeck-brown, from Siberia, 2° 40', G.=2.582; sea-green, from Norway, 2°, G.=2.533; chesnut brown, in granite, 0°-1°.

2. Angle of Divergence above 50°.

1. Plane of the axes in the line of the shorter diagonal. — Gray mica, from Kolia, in granite, 50° 12'; from Zinnwald and Schlackenwald, in granite, 51° 50'; grsj.

from the Tyrol, in granite, 52° 12'; colorless, from Siberia, 60° 30'.

2. Plane of the axes in the line of the longer diagonal.—Greenish-brown, from Arendal, 58°; yellowish-brown, from Warwick, 59°; from Airolo, Switzerland, 60°; from Miask, in yellow feldspar, 62° 50'; pale greenish, from Schwarzenbeck, 61° 12'; from Nertschinsk, in granite, 65°; green, from Rothenkopf, Tyrol, 66° colorless, from Gloria, Brazil, 66° 36'; from Skogbollt, near Kimito, Finland, with red albite, 67° 25'; from Weathersfield,* Connecticut, in coarse-grained grasit, G.=2.836, 67° 40'; colorless, from Josefs-Alpe, G.=2.713, 69° 10'; pinchbeck-brown, from Trachiros, Cape Goyaz, Brazil, 69° 25'; brownish to colorless, from Middletown, Connecticut, G.=2.852, 70°, (No. 6 of Silliman, p. 218); from Nulluk, Greenland, 70° 36'; blonde, from Pressburg, Hungary, 70° 40'; green, from Kassigergoyt, Greenland, 71°; pinchbeck-brown, from Kakunda, Brazil, 71° 25'; blonde, from Cam, Bohemia, 71° 40'; light-green, from Greenland, 71° 50'; pale-brown, from Minas Geraes, Brazil, 72° 20'; pinchbeck-brown, from Hörlberg, Bavaria, in granite, 72° 25'; greenish-yellow, from Chester, Mass., G.=2.827, 72° 30°-72° 30'; white, from Zwiesel, Bavaria, 74°; greenish-white, from Conceiçao, Brazil, 74°; colorless, from the Ural, 74°; gray, from Galmeikirchen, Upper Austria, 74° 36'; pinchbeck-brown, from Miask, Urals, 75° 25'; gray to colorless, from Sibaria, G.=2.802, 75°-76°; colorless, from Pressburg, Hungary, 76° 12'; pinchbeck-brown, from Engenhos Corallinhos, Brazil, 64°-65° and 68°-69°. red albite, 67° 25'; from Weathersfield,* Connecticut, in coarse-grained granits,

3. In the following, crystals not well defined, and position of the longer diagonal inferred from the cleavage forms. From Irkutsk, 68°; from Fogaras, in Transylvania, inferred from the cleavage forms. From Irkutsk, 68°; from Fogaras, in Transylvania, in granite, 69°; colorless, from Lobming, Austria, 69° 20'; wine-yellow, from Balmsin granite, 69°; colorless, from Lobming, Austria, 69° 20'; wine-yellow, from Balmarusa, 69° 45'; sea-green, from Elfdal, Sweden, 69° 58'; silver gray, from Schlackenwald, Bohemia, 70°; from Pressburg, 69° 42' to 72° 24'; from Pojanska, 70°-71°; from Grobo, Bannat, 70°-70° 36'; from Gomör, Hungary, 70° 24'; from Neuberg, Bavaria, 70° 40'; from Jamaica, 70° 54'; from Wottava, Bohemia, 71° 15'; from Brazil, 71° 36'; from Mursinka, Poland, 71° 50'; greenishyellow, from Utö, Sweden, 72° 50'; pale yellowish-green, from Paris, Me, 72° 51' (No. 41 and 42 of Silliman); from Ronsberg, Bohemia, 73°; from Skuttrand, Norway, 73° 30'; greenish, from Norway, 74° 10'; pale-green, from Chillon, Switzerland, 74° 24'; yellowish-white, from Zwiesel, Bavaria, 75° 10'; yellowish-green, from Serra de Conceiçao, Brazil, 76°.

4. Rose red Lithia Micas.—From Maine, 74°, (No. 45 of Silliman): from Chaster

4. Rose red Lithia Micas.—From Maine, 74°, (No. 45 of Silliman); from Chester field, Mass, 75°; from Siberia, 75° 40'; from Rozena, 76°; from Pennig, Saxony, 76° 30'; from Massachusetts, in granite, (Goshen? No. 50 of Silliman), 76° 10'-76° 40.

From a review of all the observations and the analyses, as far as they have been made, it appears that there are at least two great groups—one including the biotites and phlogopites, the other the muscovites and lepidolites. The line between the hast two is not at present distinct either in composition or optical characters. Between the two former there is a difference of composition, according to the analyse made, and, as far as known, the optical angle of the phlogopites is hardly below 5°.

Judging from the descriptions of the specimens examined by Grailich, there were but few phlogopites among them. The color and general habit of the phlogopites. as well as their occurrence in granular limestone, will usually distinguish them from either the biotites or muscovites. But more analyses are required to clear up the whole subject of the micas, and especially to ascertain what importance, if any, attaches to the distinction whether the plane of the optical axes lies in the longer or shorter diagonal. M. Grailich shows that, with slight exceptions, the angle iservance with the specific gravity in the mice of a given locality. Thus seven mices from Procedurg, Hungary, have respectively the following specific gravities and optical angles:

Specific gravity, 2714 2785 2785 2782 2790 2798 2796, Angles, 697 700 705 712 723 724 720 70.5 71.2 72.4 720 We refer to M. Grailich's paper for his mathematical details.

[.] This must be an error, as we know of no mice in granite at Weathersfield.

Migrickel, p. 62.—A variety from near Mühlbach, in Transylvania, afforded von Hauer, Arsenic 45:00, sulphur 21:36, iron 33:52=99:88. Jahrb. f. k. k. Reichs., iv, 400.

NACRITE, TALCITE.—Nacrite has the feel of a soft earthy tale, and consists of minute grains or scales, white and pearly, with a greasy feel, much like Pholerite, although anhydrous. Talcite from Wicklow, Ireland, is similar. Analyses: Thomson, (Rec. Gen. Sci. May, 1836), 2, 3, Short and Tennant, (Thom. Min. i, 244):

δi Ċа Мg 1.0, Thomson. 1. Nacrite, Brunswick, Me., 64.44 28.84 4.48 Talcite, Wicklow, 46.00 35.20 2.88 9.61 3.94 2.0. Short. 3.80 2.25 6.25, Tennant. 44.55 83.80 7.70 1.30

Vauquelin's analysis of Nacrite is referred to mica by Rammelsberg. It is anhydrous.

OTTRELITE.—Reported as occurring in Tuscany.

PARALUMINITE, Steinberg.—Includes anal. 12, 13, of Websterite, p. 390. A very doubtful species.

PENCATITE, Roth.—Analysis 1, of Predazzite; but not a good species.


Rocks, (p. 247).—The following are recent analyses of different rocks:

- 1. Granite, from the Valorsin Valley, consisting of quartz, oligoclase, and white or brownish mica: Delesse, Bull. Geol. France, [2], vii, 424.
- 2. Red Syenite of Egypt, consisting of quartz, red orthoclase, white oligoclase, and black mica: Delesse, ib., vii, 484.
- 3. Protogine of Mt. Blanc, consisting of quartz, orthoclase, oligoclase, tale, and mica: Delesse, ib., vi, 230.
- 4. Porphyry of Lessines, having a green base, and the disseminated crystals being oligoclase: Delesse, ib., vii, 310.
- 5, 6. Diorites of the Vosges; 5, from Frondromé, fine crystalline, nearly compact in texture, consisting of feldspar and hornblende; G.=2.945;—6, from Clefcy, consisting of oligoclase, hornblende, and mica; color black; G.=2.902: Delesse.
- 7. Granulite (Weissstein), fine-grained, grayish-white color, from Krems; only 0.70 p. c. soluble in muriatic acid: E. Hornig, Wien. Akad., vii, 583.
- 8. Hornblende Slate, consisting of feldspar and hornblende, with some chlorite; G.=3.008; from Militiz in Saxony; contains small acicular crystals of hornblende: Bischof, Lehrb. de Geol.
- 9, 10. Mica Slate; 9, grayish, from Libethen in Hungary;—10, ib., from Ora-witza, Hungary: Bischof and Kjerulf, Bisch. Lehrb.
- 11, 12, Clay Slate;—11, from Siegen;—12, from Rothwaltersdorf, color bluishblack: Bischof, Lehrb.
- 13. 15. of violet color and having a silky lustre, from Nerothal, near Wiesbaden; G.=2.822; B.B. fuses on the edges to a gray enamel; muriatic acid decomposes 17.89 p. c., removing a fourth of the silica and alumina, all the peroxyd of iron, nearly all the magnesia, all the lime, and less than one-third of the potash: List, Ann. Ch. u. Pharm., lxxxi, 267. List obtained from this slate the sericite, (see p. 223), which is the source of the silky lustre.
 - 14. Clay Slate of greenish color from Naurod; G.=2792; List, ib.
- 15, 16, 17, 18. Roofing Slate;—15, purplish-blue, feebly glimmering lustre; G.—2.884; Lower Silurian, of Kingsey, Canada East;—16, greenish-blue, silky surface; G.—2.711; Upper Silurian from Westburg, C. E.;—17, Welsh roofing-slate, resembling No. 15; G.—2.824;—18, from Angers, France, and resembling No. 16, but more pearly in lustre and somewhat talcose; G.—2.882; T. S. Hunt, Phil. Mag. [4], vii, 237. Part of the iron in 15 and 17 he suggests may be peroxyd.
- 19. Variolite of Durance, in Savoy;—a, the base of the rock; G.=2.896—2.934; general appearance somewhat like Euphotide, of a greenish to dark-green color. Contains disseminated spherules, (analysis 19 b), which are feldspathic, white or

B.B. loses color and transparency, emits arsenical fumes, and on charcoal best a black, friable scoria, containing some metallic globules. With borax a great bule, and a partial reduction. Dissolves in nitric acid without effervescesses.

Crystals occasionally an inch in diameter; usually quite small. (Necurs with use ores of copper, pyrites, and quartz, at Huel Gorland and Huel Unity, in Q wall; also in minute crystals at Herrengrund in Hungary, and in Voigtland.

URANITE. Uran Mica. Uranglimmer. Uranoxyd, Haus. Urane Oxydt, Uranphyllit.



Dimetric. $O: 1i=128^{\circ} 35'; a=125$ Observed planes as in the annexed figure $0: \frac{1}{2}i=147^{\circ} 56', O: \frac{3}{2}i=140^{\circ} 7', 0: 2i$ 111° 45'. Cleavage: basal, highly process. Surface O smooth, ii rough.

Lustre of O pearly, of other faces a adamantine. Transparent—subtransluce Fracture not observable. Sectile. Lan næ brittle and not flexible.

VAR. 1. URANITE. Lime-Uranite. Kalk-Uranit. Autunite.

H.=2—2.5. G.=3.05—3.19. Color citron to sulphur-yello Composition.—Ča P+TP+16H=Phosphoric scid 15.7. oxyd of uranium & lime 6.1, water 15.5=100. Analysis by Berzelius, (Jahresb. xxii, 212):

P U Ca Mg and Mn Ba Sn H 15-20 61-73 5-88 0-20 1-57 0-06 15-48=10c

B.B. fuses to a blackish mass like pitchblende. A yellow solution in nitric at Uranite is found with other ores of uranium, associated with silver, tin, and it ore.

Occurs in the Siebengebirge in the hornstone of a trachytic range; at John georgenstadt and Eibenstock; at Lake Onega, Wolf Island, Russia; also near Limo and at St. Symphorien near Autun. Occurs sparingly at the Middletown felds quarries, associated with columbite and pitchblende, in minute tabular crystals at thin scales of light green and lemon yellow colors; also in minute crystals at their field, Mass., on the quartz or albite, and sometimes in the red centres of tour lines, and at Ackworth, N. H., straw-yellow and light green; also in a gneiss qua on the Schuylkill near Philadelphia, about a quarter of a mile above the suspens bridge.

VAR. 2. CHALCOLITE. Copper-Uranite, Kupfer-Uranit. Torberite.

H.=2-2.5. G.=3.5-3.6. Color emerald and grass-green, a sometimes leek, apple, and siskin-green. Streak somewhat pathan the color.

Composition.—CuT+UT+16H, or same as above, with copper in place of li = Phosphoric acid 15·1, oxyd of uranium 61·2, oxyd of copper 8·4, water 15·8=1 Analyses: 1, Berzelius, (loc. cit): 2, Werther, (J. f. pr. Ch. xliii, 334):

 P
 Cu
 H

 1. 15.57
 61.29
 8.44
 15.05=100.45, Berzelius.

 2. 14.34
 59.08
 8.27
 15.39, Si 0.49, Earthy substance 0.41, Werther.

513

It is remarkable that analyses apparently equally trustworthy, recent as well as old, give for Andalusite the two formulas Al Sit and Al Sit; for Staurotide the two KI Sit, KI Sit; for Sillimanite, KI Sit and KI Sit, and perhaps others; and now topaz in the present state of chemistry of the species, is divided between Al Sil and Al Sil-Moreover Sphene, (R) Sit is homocomorphous with Euclase (R) Sit; and all the above are pleomorphous with Tourmaline, (R3, H, B) Sil. Kyanite, alone appears to give to all recent analysts the same uniform result, Al Si²; and the uniformity on this species makes it more incredible that the variations in the case of the other species should be all attributable to errors of analysis.

TOURMALINE, p. 270.—Kenngott has deduced essentially the same formulas for Tourmaline as that given on page 271, except that he writes B² O⁵ for boracic acid, and regards it as replacing alumina. Min. Notizen, No. ix.

TRIPHYLINE, p. 406 .- Altered forms of triphyline are mentioned on page 407. Seemann states that Melanchlor (p. 428) is also a result of the alteration of Triphyline, and occurs as an incrustation on unaltered Triphyline; that Heterosite, Pseudo-triplite and the Norwich mineral are the results of a further change; that Hureaulite and Alluaudite are connected with Triplite in origin. (Communicated to the Author.)

Tunquois, p. 405 .- The bone Turquois, or Odontolite, according to L. Sæmann owes its color to a phosphate of iron, as stated by Dufrénoy, (Min. ii, 361). turquois, when decomposed by muriatic acid gives a fine blue color with ammonia, which is not the case with the odontolite. This mineral has a fine turquois blue color, and a very compact but earthy texture. It is formed along with fossil bones or teeth, being like vivianite connected with organic phosphates in its origin.

Volgerite, p. 142.—Cumenge's mineral, p. 142, is named Cumengite by Kenngott.

Weissigite, p. 254.—The following are additional particulars respecting this minwassioris, p. 201.—The following are additional particulars respecting this mineral, from a note by M. Jenzsch, communicated to the author by L. Sæmann.—Cleavage parallel to a hemidome pertaining to the brachydiagonal; also in two vertical directions meeting at 118°; also parallel to the macrodiagonal. Crystals small and not very distinct. Composition, Si 64.5, ¾1 17.0, Mg 0.9, K 14.6, (Na, Li), 2.2, ign. 0.8. Insoluble in muriatic acid. From Weissig in Saxony.

The proportion of silica, alumina, and alkalies, differs little from the same in Orthoclase; and is it not that species?

Wöhlerite, p. 343.—H. Dauber has figured and described a crystal of Wöhlerite, (Pogg. xcii, 242). He gives the crystal the same position as that by the author. Adopting the lettering of f. 494, it contains the planes—

12 13 19 Dauber's lettering, a 9 -0

All but two of which planes are in Desloizeaux's figure, from which f. 494 was taken, and one of these two, 31, is probably the correct symbol for that lettered 11, from Descloizeaux. The angles according to Dauber vary considerably as the faces are not very brilliant; and in fact he makes the brachydiagonal what Descloizeaux makes the macrodiagonal. The latter gives for I on the broad face lettered it, 135° 27', whence I; I=90° 54', while Dauber obtained 134° 51', giving 89° 42' for the same I: I. Using the lettering of f. 494, the angles obtained are as follows:

Dauber, $ii: \frac{1}{4}i=109^{\circ} 28'$. $ii: 12=106^{\circ} 54'$. $ii: \frac{3}{2}\frac{3}{2}=130^{\circ} 45'$. Descloizeaux, 109° 57'. 106° 27'. 131° 32'. it: ig=116° 17'. 1160 56'.

Dauber's measurements of I; it however varied from 134° 21' to 135° 24'.

Wolkonskoite, p. 339.—This species has H.=2-2.5; G.=2.213-2.303, Breithaupt. Analysis by Ivanoff, (Kokscharov's Min. Russl. 145): Ši 36.84, Ür 18.85, Fe 17.85, Xl 3.50, Mn trace, Ča 1.39, Ĥ 22.46=100.89.

ZING BLOOM, p. 460.—Occurs with ores of zinc and lead at Bleiberg and Raibel in Carinthia, and has probably resulted from the decomposition of Calamine.

ANNOTATED INDEX TO THE USEFUL METALS AND METALLIC ORES.

GOLD.—Native Gold, (p. 7). Distinguished from all minerals it resembles by in flattening under a hammer; its cutting like lead, although considerably hards; its resisting the action of nitric acid, hot or cold; its high specific gravity.

Gold also occurs in Gold Amalgam, (p. 15), Sylvanite, (p. 64) and Nagyagite, (p. 65). Also sometimes in traces in Pyrites, Galena, Chalcopyrite, Native Tellurium.

PLATINUM.—IRIDIUM.—PALLADIUM.—Native Platinum, (p. 12), the source of the platinum of commerce, is distinguished by the same tests as gold; and it is mainly on account of its malleability that it occurs in flattened grains or scales. Platiniridium (p. 13) is another ore somewhat harder. Iridosmine (p. 19) results platinum; but it scretches glass, and gives the reaction of osmium, builds being rather brittle. Native Palladium, (p. 14).

SILVER.—The important Silver minerals are: 1, Native Silver, (p. 15), wetile and malleable like gold, the only one that has a white color; 2, Silver Glence we Sulphwret of Silver, (p. 37), blackish lead gray, cutting (unlike the following) seally like pure lead, cubic in crystallization; 3, Pyrargyrite and Proustite or Ruby Silver Ore, (pp. 77-78), ruby red to black, always giving a bright red powder; 4, Prisibbenite or Gray Silver ore, (p. 79), steel gray, rather brittle and powder steel-gray; 5, Stephanite or Brittle or Black Silver ore, (p. 86), iron black, and giving an irea black powder; 6, Kerargyrite or Horn Silver, (p. 92), resembling a dark colored gray or greenish wax, and cutting like wax; 7, Embolite or Chloro-bromid of Silver, (p. 98), like the last, but more greenish. These ores yield silver easily, when heated on charcoal. Besides these, Tetrakedrite or Gray Copper, (p. 82), is often a valuable silver ore; Galena, (p. 39), which, although seldom yielding over seventy-five ounces to the ton, affords a considerable part of the silver of commerce. For other rarer silver ores, see pp. 16, 35, 43, 44, 48, 64, 71, 74, 76, 85, 87, 95.

COPPER.—The more valuable species are: 1, Native Copper, (p. 17); 2, Chalce pyrite or Copper pyrites, (p. 68), of a brass yellow color, scratched easily with the point of a knife blade and giving a greenish black powder; 3, Barnhardtite, p. 500, and Cuban, (p. 68), which are similar to the last but paler: 4, Krubescite or Purple Copper. p. 38), pale yellowish, with a slight coppery tinge, but tarnishing externally to purple, blue, and reddish tints; easily scratched with a knife blade, and powder grayish; 5. Copper Glance or Vitrous Copper, (p. 46), of a dark lead-gray color, and powder similar, resembling some silver ores, but yielding copper and set silver, when heated on charcoal; 6, Tetrahedrite or Gray Copper, (p. 82), of a some what paler steel-gray color and powder: 7, Red Copper, (p. 101); 8, Black Copper, (p. 109, 136); 9. Malachite or Green Carbonate of Copper, (p. 458), of a bright gress color, sometimes earthy in the fracture and sometimes silky: 10, Azurite or Blue Malachite, (p. 459), of a rich deep blue color, either earthy or vitreous in lustre. All the above are acted on by nitric acid, and the solution deposits a red coating of copper on a strip of polished iron; 11, Chrysocolla, (p. 309;, a silicate of copper. resembling the Green Carbonate, but paler green, and usually having a close texture. (never fibrous), a smoother surface and somewhat waxy lustre, although occurring usually only as an incrustation: 12, Atacamite or Chlorid of Copper, (p. 138), of deeper green than Malachite: 13, Sulphate of Copper, in solution, (p. 380) For rarer ores, see pages 36, (areenical); 43, selenid); 48, 65, 73, 80, 82, 84, 85, 81, (different sulphur, arsenical and antimonial ores); 309, (silicate); 360, 362, 343, (chromates, vanadate); 375, 380, (sulphates); 412, 420, 421, 426, (phosphates and arsenates).

QUICKSILVER.—The only valuable ore is Cinneber, (p. 48), of a bright red to brownish black color, with always a red powder, and affording fumes of quicksilve

when heated on charcoal. There are also Native Quicksilver, (p. 14); Amalgam, (p. 15); Selenid, (p. 52); Chlorid and Iodid, (p. 89, 96). Tetrahedrite (p. 82) sometimes contains this metal.

LEAD.—Galena (p. 39) is the only abundant lead ore; it is a lead-gray brittle ore, yielding lead, when heated with charcoal. For other ores see pp. 42, 44, 65, (Selenid and Tellurids); 109, 117, 126, 127, 128, (Oxyds); 359, 361, 362, (Chromate and Vanadate); 348, (Tungstate); 370, 371, 372, 374, 375, 390, (Sulphates), of which Anglesite (p. 370) is the common one; 400, 401, (phosphate and arsenate); 452, (carbonate).

ZINC.—The most important ores are: 1, Smithsonite or Carbonate of Zine, (p. 447), and 2, Calamine or Silicate of Zine, (p. 313); they are alike in a white, grayish-white, or greenish-white color, commonly a slight waxy lustre and smooth look, (often stalactitic or mammillary), yet sometimes earthy; and a hardness such that the surface is scratched with a knife blade with some little difficulty. They differ in their action with muriatic acid; when the surface is drusy, the silicate shows projections of minute rectangular prisms. Zincite or Red Zinc ore, (p. 110), is also important; it is bright red and very distinctly foliated. Blende or Sulphuret of Zinc, (p. 45), is a common ore, having a yellow to black color and resinous lustre, and distinctly cleavable; the black varieties are sometimes a little metallic in lustre, but the powder is nearly or quite white. For other Zinc Ores, see pp. 127, (oxysulphuret); 156, 189, (silicate); 384, (sulphate); 409, (phosphate); 418, (arsenate); 460, carbonate).

COBALT, NICKEL.—The ores of cobalt of first importance are, Smaltine, (p. 56), and Cobaltine, (p. 57), both of nearly a tin-white color, with the powder grayish-black, color sometimes verging slightly to gray. The Black Oxyd of Cobalt, (p. 136), a kind of bog ore and very impure, is sometimes sufficiently abundant to be valuable. The useful ores of nickel are Chloanthite or the nickeliferous smaltine, (p. 56), Gersdorffite or Nickel Glance, (p. 58), and Copper Nickel, (p. 52), the latter distinguished by a pale copper red color. For other ores of Cobalt, see pp. 41, 44, 63, 67, (sulphuret or arseniuret); 385, (sulphate); 416, (arsenate); 461, (carbonate); of Nickel, 42, 49, (sulphuret); 53, 59, (arsenical or antimonial); 339, (silicate); 386, (sulphate); 418, (arsenate); 461, (carbonate).

MANGANESE.—Common, as Pyrolusite, (p. 125), and Psilomelane. (p. 135), both black or grayish-black ores, and having little lustre, and a blackish streak or powder, in which last particular they are distinct from the iron ore called Limonite, with which they are often associated, and also from Hematite or Specular Iron. Wad (p. 136) is an earthy bog manganese, sometimes abundant and valuable. Manganite (p. 130) is abundant in certain mines, but is of little value in the arts, because of its containing so little oxygen, (one third less than Pyrolusite), to which fact Beudant alludes in his name for the species, Acerdese; it differs from pyrolusite in its reddish brown powder. For other manganese ores, see pp. 41, 56, (sulphuret); 53, (arsenical); 117, 118, (oxyds); 167, 186, (silicates); 399, 406, 408, (phosphates); 446, 452, (carbonate).

CHROMIUM.—Chromic Iron, (p. 106), a grayish-black little lustrous ore, occurring mostly in Serpentine, is the source of chrome in the arts. For different chromates, see p. 359.

IRON.—The important iron ores are: 1, Hematite or Specular Iron, (the auartras or bloodstone of Theophrastus), (p. 113), characterized by its blood-red powder, and occurring either earthy and red, or metallic and dark steel gray; in the latter condition very hard, a knife point making no impression;—2. Magnetite, or magnetic iron ore, (p. 105), as hard as the preceding, but having a black powder, and being attractable by a magnet;—3, Limonite, called also brown hematite, (p. 181), a softer hydrous ore, affording a brownish yellow powder, earthy or semimetallic in appearance, and often in-mammilary or stalactitic forms;—4, Chalybite, or Spathic Iron, (p. 444), a sparry ore, of grayish, grayish-brown, and brown colors, very distinctly cleavable, turning brown to black on exposure. The common clayey iron ores are

impure ores, either of Spathic Iron, Limonite, or Hematite; when the last they are red; when brown, reddish-brown, or yellowish-brown to black, they may be either of the two former. One of the most common ores of iron is Pyrites or suphuret of iron, (p. 54), a pale yellow brase-like ore, hard enough to strike fire with steel, and thus unlike any copper ore, and all similar ores of other metals. Marcost the (p. 60) is similar, but is prismatic and often crested in its forms. Pyrrhotine, of Magnetic Pyrites, (p. 50), is less hard and paler, or more grayish in color. Locopyrite and Mispickel, (pp. 61, 62), are white metallic arsenical ores, somewhat resembling ores of Cobalt. Ilmenite, or Titonic Iron, (p. 115), resembles specular iron closely, but has not a red powder; it is abundant in some regions, but not valued For other iron ores see pp. 380, 385, 387, 389, (Sulphates); 399, 406-408, 415, 424, 427, 431, (phosphates); 422, (arsenate); 464, (oxalate).

TIN.—The only valuable ore is the Oxyd of Tin or Cassiterite, (p. 118), a very hard mineral of a dark brown to black color, sometimes gray or grayish-brown without any metallic appearance; the crystals usually have a very brilliant lastre. Tin also occurs as a sulphuret, (p. 70), and is sparingly found in ores of tatalum, and some other mineral species.

TITANIUM.—The only ore of this metal of any value is Rutile, (p. 120).

ARSENIC.—Native Arsenic (p. 22) is one source of arsenic, but it is too rare to be of much avail; also Orpiment, (p. 32), a sulphur-yellow foliaceous and somewhat pearly mineral, and Realgar, (p. 31), bright red and vitreous. Arsenic is mostly derived for the arts from the arsenical ores of iron, cobalt, and nickel.

ANTIMONY.—Stibnite, or Gray Antimony, (p. 33), is the source of the antimony of commerce. It is a lead gray ore, usually fibrous or in prismatic crystals, and distinguished from a similar ore of manganese by its perfect diagonal cleavage and its easy fusibility. Antimony occurs also in numerous ores of lead and silver, (p 72), and of nickel, (pp. 53, 59); also as oxyds, 140, 141.

BISMUTH.—Native Bismuth, (p. 20), the source of the metal in the arts, i whitish, with a faint reddish tinge, has a perfect cleavage, and is very fusible. For other bismuth ores, see pp. 16, 21, 33, 44, 73, 77, 81, 88; 141, (oxyd); 181, (silicate) 462, (carbonate).

GENERAL INDEX.*

Abichite, 428. Ammiolite, 142. Allagite, 167. Allanite, 208.
Allemontite, Arsenical An-Ammonia, Bicarbonate, 454.
Muriate, 92. Abrazite, 322. Acadiolite, 319. Acerdese, 180. timony, 22. Muriate, 92. Achates, 151. Allochroite, 191. Phosphate, 418. Achirite, 809. Allogonite, 410. Sulphate, 879. Achmatit, 206. Allomorphite, 866. Amoibite, 58. Allophane, 836. Allophane, Opal, 837. Alluaudite, 407, 518. Amphibole, 170. Achmite, 176. Achroite, 271. Acicular Bismuth, 81. Amphibolite, 172. Amphigéne, 281. Amphodelite, 234. Aciculite, 81. Almagrerite, 371. Acid, Antimonous, 141, 142. Almandine, 191. Anagenite, v. Chrome ochre. Arsenous, 139. Alstonite, 451. Analcime, 318. Boracic, 144. Analcime carnea, 200. Altaite, 44. Alum, Native, 382. Carbonic, 144. Anamesite, 247. Ammonia, 383. Muriatic, 97. Anatase, 121, 508. Anauxite, 505. Sulphuric, 148. Feather, 881. Andalusite, 257. Sulphurous, 148. Iron, Magnesia, Man-Tungstic, 143. ganese, Sods, 382. Andesine, 236. Acmite, 165, 176. Andreasbergolite, 323. Alumina, 111. Actinolite, Actinote, 170. Adamant, 24. Fluate, 98. Fluosilicate, 259. Andreolite, 328. Fluosilicate, 259.

Anglarite, 416.

Anglarite, 470.

Hydrous Silicates (ear-Anglesite, Cupreous, 890. Adamantine spar, 111. Adinole, 248. Adularia, 242. thy), 165, 249 to 253, Anhydrite, 869. Ædelforsite, 155, 808. 337 to 340, 504. Ankerite, 441. Annabergite, 418. Mellate, 475. Aerhenstein, 366. Anorthite, 284. Anthophyllite, 172. Phosphates, 428, 432. Sulphate, 881, 888. Ægirin, 160, 172. Ærosite, 77. Alumine fluatée alcaline, 97. Hydrous, 175. Æschynite, 357. Anthosiderite, 304. Aftonite, 82. sulfatée, 381. Agalmatolite, 252, 276. phosphatée, 424. Anthracite, 26. Aluminite, 389. Alumocalcite, 151. Agaphite, 405. Anthraconite, 489. Agaric mineral, 488. Antiedrit, 828. Alumetone, 888. Antigorite, 281. Agate, 145. Antimoine natif, 21. Agnesite, 462. Alun, 382. Aikinite, 81. Alunite, 388. oxidé 140, 141, 142. Agustite, 896. Akanticon, 206. Alunogen, 881. oxidé sulfuré, 141. Amalgam, Native, 15. sulfuré, 88. Akmit, 176. Alabandine, 41. Gold, 15. sulfuré nickelifère, 59. sulfuré plombo-cupri-Amausite, 242. fëre, 80. Antimon, Gediegen, 21. Alabaster, 877, 489. Amazon Stone, 242. Amber, 466, 508. Alalite, 159. Alaun, 382. Amblygonite, 409. Antimon-arsen, 22. Amethyst, 145. Oriental, 111. Alaunstein, 388. Antimonate of lead, 142. Antimonblende, 141. Albin, 304. Amiant, 172. Amianthoide, 174. Antimonblüthe, 140. Albite, 240. Antimonglanz, 83. Alexandrite, 122. Amianthoide magnesite, 183. Antimonite of lime, 410. Algerite, 208. Alizite, 339. Amianthus, 172 of quicksilver, 142.

^{*}The numbers in this Index refer to the Second Volume. For an Index to the First Volume, see Table of Contents, following the Preface.

Antimonial copper, 78. Argentine, 489. Argentite, 87. copper glance, 82. Argyrose, 87. lead ores, 72-87. nickel, 53. Aricite, 322. ochre, 141, 142. Arkansite, 128. sil∳er, 35. Arpidelite, 268. sulphuret of silver, 77 Arquerite, 15. Arragonite, 448. Arsenate of lime, 414. 79. Antimonite, 33. Antimonkupferglanz, 82. ARSENATES, 396. Antimonnickel, 53. ANHYDROUS, 396. Antimonnickelglanz, 59. Hydrous, 411. Antimonocher, 141. Antimonophyllite, 140. Arseneisen, 61. Arseneisensinter, 432. Antimonoxyd, 140, 141. Arsenglanz, 22. Antimonsaures bleioxyd,142 Arsenic, Native, 22. Antimonsilber, 35. oxydé, 139. Antimonsilberblende, 77. sulfuré, 31. Antimony, Native, 21. Sulphuret, 31, 82. Arsenical, 22. White, 139. Arsenical antimony, 22. Gray, 88. Oxyd of, 140, 141. Arsenicite, v. Pharmacolite, Plumose ore of, 76. 414. Arsenikalkies, 61, Red, 141. Arsenikantimon, 22. Sulphuret of, 33. White, 140.
Antimony blende, 141.
bloom, 140. Arsenikbleispath, v. Mime-Arsenikbismuth, v. Eulytine. Arsenikblüthe, 189, 414. glance, 33. Antrimolite, 329. Arsenikeisen, 61. Arsenikglanz, v. Arsenglanz. Arsenikkies, 62. Arsenikkobaltkies, 67. Apatelite, 388. Apatite, 396. Apatoid, 503. Arsenikmangan, 58. Aphanesite, 428. Arsenikkupfer, 36. Aphrite, Aphrizite, 270, 439 Arseniknickel, 52, 56. Aphrodite, 281. Aphrosiderite, 297. Arseniksilber, 36. Aphthalose, Apthitalite, 365. Arseniksilberblende, 78. Aphthonite, 82. Arsenik-sinter, 419. Apjohnite, 382. Arseniosiderite, 61, 422 ARSENIURETS, 80-88. Aplome, 192. Apophyllite, 304. Arsenite, 139. Arsenocrocite, 422. Aquamarine, 178. Aræoxene, 364. Arsenolite, 189. Arsenopyrite, 62. Aragonite, 448. Aragonspath, 448. Arsenous acid, 139. Arsenphyllite, 140. Arcanite, 865. Asbestus, 159, 172. Arendalite, 206. Arfvedsonite, 172. Asbolan, 136. Argent antimonial, 35. Asparagus-stone, 396. antimonié sulfuré,77,79. Aspasiolite, 215. Asphaltum, 469. ioduré, 95. gris antimonial, 79. Asteria, 111. muriaté, 92. Astrakanite, 379. Atacamite, 138. natif. 15. noir, 86. Atelesite, 182. sulfuré, 87. Atlaserz, 458. sulfuré flexible, 71. Atheriastite, 203. sulfuré fragile, 86. Atramenstein, v. Misy. sulfuré antimonifère et Augite, 158. cuprifère, 79. Augustite, 396.

Auina, 230.

fragile, 542.

Aurichalcite, 460. Auripigmentum, 82. Aurotellurite, 64. Automolite, 108. Autunite, 430. Aventurine quartz, 147. feldspar, 245. Axinite, 218. Azorite, 350. Azure spar, or stone, 404. Azurite, 459, 404. Babingtonite, 178. Bagrationite, 208. Baierine, 853. Baikalit, 159. Balas ruby, 103, Ballesterosite, 55. Baltimorite, 282. Bamlite, 264. Baralite, 340. Barnhardtite, 500. Barolite, 449. Baroselenit, 366. Barsowite, 286. Barystrontianite, 451. Baryta, Carbonate, 449. Carb. of lime and, 451. Sulphate, 366. Sulphato-carb., 450. Barytes, 366. Barytine, 366. Barytocalcite, 458. Baryto-celestine, 869. Barytophyllit, 298. Basalt, 162, 247. Basanite, 148. Basanomelan, 115. Basicerine, 96. Bastite, 165. Batrachite, 184. Baudisserite, 441. Baulite, 248. Beaumontite, 330. Beilstein, 175. Beinbrech, v. Tufa. Bell-metal ore, 70. Belonit, 81. Beraunite, 427. Berengelite, 468. Beresite, 246. Berg-crystal, 145. Bergholz, 285. Bergmannite, \$27. Bergpech, 469. Bergseife, 252. Bergtheer, 469. Bernerde, v. Retinita Bernstein, 466. Beryl, 178.

Berthierite, 78, 503.

Berzelianite, 43.

GENERAL INDEX.

Berzeliit, 404. Bleimolybdat, 849. Breunnerite, 448. Berzeline, 48, 282. Bleinière, 142. Bleinierite, 142. Bleioxyd, 109. Berzelite, 128. Beudantite, 282, 428. Bieberite, 385. Bleischeelat, 848. Bildstein, 252. Bleischimmer, 75, Bimsstein, 246. Bleisulphotricarbonat, 871 Biotine, 285. Bleischweif, 40. Biotite, 225. Bleivitriol, 370. Birousa, 405. Bismuth, 20. Blende, 45. Blödite, 879. Acicular, 81. Bloodstone, 148. Carbonate, 462. Blue asbestus, 279. Cupreous, 78, 88. copper, 459. Oxyd, 141. feldspar, 404. iron earth, 415. Silicate, 181. sulfuré plombo-argenti-fère, 16. iron stone, 279. john, 94. malachite, 459. sulfuré plumbo-cuprifère, \$1. spar, 404. Sulphuret, 83, 78, 77. vitriol, 380. Blutstein, 113. Telluric, 21. Bodenite, 210. Bismuth-glance, 38. blende, 181. nickel. 44. Bohnerz, 181. Bog butter, 478. ochre, 141. Bog iron ore, 181. silver, 16. manganese, 186. Bismuthine, 83, 508. Bole, 252, 503. Bismutite, 462. Bitterkalk, 441. Bolognian spar, 866. Boltonite, 167. Bolus, 252, 503. Bittersalz, 884. Bonsdorffite, 215. Bitter spar, 441, 443. Bitterspath, 441. Boracic acid, 144. Bitumen, 469. Boracite, 893. Elastic, 471. BORATES, 392. Borax, 394. Borazit, 893. Bituminoses holz, 26. Bituminous coal, 26. Bornite, 21, 88. Black copper, 109, 117, 136. hematite, 135. Börnstein, v. Bernstein. manganese, 185. Borocalcite, 394. silver, 86. Borosilicate of lime, 884. lead, 29. Borsaurerkalk, 394. Botryogen, 887. Botryolite, 834. jack, 45. Blakeite, 380. Boulangerite, 81. Blättererz, 65. Blätterkies, v. Marcasite. Bournonite, 80. Blättertellur, 65. Bournonit-nickelglanz, 59. Blätterzeolith, 830. Bowenite, 283. Blaubleierz, 39. Branchité, 472. Blaueisenerz, 415. Branderz, v. Idrialine. Blaueisenstein, 279. Brandisite, 297. Blauspath, 404. Braunbleierz, 400. Blei, 17. Brauneisenstein, 131. Bleierde, 452. Braunite, 117. Braunspath, 441, 448. Bleifahlerz, 80. Braunstein, 118. Bleigelb, 349. Bleiglanz, 89. Piemontischer, 206. Bleiglas, v. Anglesite. Grauer, 180. Bleiglätte, 109, Schwarzer, 185. Bleigummi, 431. Bleilasur, 890. Braunsteinkiesel, 190. Breislakite, 160. Caporcianite, 384. Bleihornerz, 463. Breithauptite, 58.

Brevicite, 827. Brewsterite, 882. Brewstoline, 471. Brittle silver ore, 86. Brochantite, 891. Bromic silver, 98. BROMIDS, 89. Bromite, 93. Bromlite, 451. Bromsilber, 98. Brogniardite, 76. Brogniartin, 874. Bronzite, 160. Brookite, 123. Brossite, 442. Brown coal, 26. iron ore, 131. hematite, 181. ochre, 131. spar, 443, 441. Brucite, 188, 186. Bucholzite, 265. Bucklandite, 206. Buhrstone, 148. Buntbleierz, 400. Buntkupfererz, 88. Buratite, 460. Bustamite, 167. Buttermilcherz, 92. Butyrite, 473. Byssolith, 170. Bytownite, 287. Cacholong, 151. Cacoxene, 424. Cadmium, Sulphuret of, 51. Cairngorm stone, 147. Calaite, 405. Calamine, 813, 447, 503. Cupriferous, 426. Electric, 313. Green, 460. Calamite, 172. Calcareous spar, 485. tufa, 489. Calcedony, 145. Calcite, 435, 508. Caledonite, 372. Callais, 405. Calomel, 89. Calstronbaryte, 366. Calyptolite, 195. Canaanite, 208. Cancrinite, 288. Candite, 108. Canebletein, 191. Cantalite, 145. Caoutchouc, Mineral, 471. Capillary pyrites, 49. Capnite, 447.

Carbocerine, 456. CARBONATES, 434. ANHYDROUS, 434. Hydrous, 454. Carbonic acid, 144. Carbunculus, 190. Carinthine, 172. Carminite, 410. Carminspath, 410. Carnat, 250. Carnelian, 147. Carolathine, 500. Carpholite, 316. Carphosiderite, 431. Carphostilbite, 326. Carrollite, 67. Cassiterite, 118. Cassiterotantalite, 351. Castelnaudite, 432. Castor, 253. Catapleiite, 308, 504. Catlinite, 252. Cat's eye, 148. Cavolinite, 232. Cawk, 366. Celestine, 368. Cerasine, Cerasite, 463. Cerer, v. Cerium. Cerine, 208. Cerinstein, 312. Cerite, 312. Cerium, Carbonate, 456. Fluorid, 96. Silicate, 312. Cerolith, v. Kerolith. Ceroxydulkohlensaures,456 Cerusite, Ceruse, 452. Cervantite, 141. Ceylanite, 103. Chabazite, Chabasie, 319. Chalcanthit, 380. Chalcedony, 147. Chalcodite, 500. Chalcolite, 430. Chalcophacite, 429. Chalcophyllite, 428. Chalcopyrite, 68. Chalcostibite, 73. Chalcotrichite, 122. Chalilite, 325. Chalk, 438. Chalkosin, 46. Chalybite, 441. Chamoisite, 299. Chantonnite, 503. Chathamite, 56, 512. Chaux arseniatee, 404, 414. boratée siliceuse, 834. carbonatee, 485. fluatée, 94. Chenocoprolite, 432.

Chert, 148,

Chesterlite, 246. Chessy copper, 459. Chessylite, 459. Chiastolite, 257. Childrenite, 424. Chileit, 129, 504. Chiltonite, 314. Chimborazite, v. Aragonite. Chiolite, 98. Chiviatite, 77 Chladnite, 503. Chloanthite, 56. Chlorastrolite, 315. Chlorhydric acid, 97. CHLORIDS, 89. Chlorite, 294, 296. ferrugineuse, 296. spar, 298. Chloritoid, 298. Chloritspath, 298. Chlormerkur, 89. Chloromelan, 299. Chloropal, 337, 504. Chlorophæite, 278. Chlorophane, 94. Chlorophyllite, 215. Chlorospinel, 103. Chlorquecksilber 89. Chodneffite, 97. Chondrodite, 186. Chonikrite, 291. Chrismatine, 474. Christianite, 234, 824. CHROMATES, 359. Chromeisenstein, 106. Chrome ochre, 339. Chromic iron, 106. Chryolith, v. Cryolite. Chrysoberyl, 122. Chrysocolla, 309, 504. Chrysolite, 184. Chrysophane, 297. Chrysoprase, 147. Chrysoprase earth, 840. Chrysotile, 282. Chusite, 184. Cimolite, 165. Cinnabar, 48. Cinnamon stone, 191. Cipolino, 439. Clausthalite, 42. Clay, 249 to 252, 387 to 340, 504, 510. Clay slate, 509. Cleavelandite, 240. Cleiophane, 45. Clingmanite, 300. Clinkstone, 246. Clinoclase, 428. Clinochlore, 293. Clintonite, 297, 505. Cluthalite, 318.

Coal, Mineral, 26. Cobalt, Arsenate of, 416. Arsenical, 56, 57, 63, 67. Carbonate, 461. Earthy, 136. Glance, 57. Gray, 56. gris, 56, 57. oxide noir, 136. Red, 416. Sulphate, 385. Sulphoarseniuret, 63. Sulphuret, 41, 67. White, 56, 57. Cobalt bloom, 416. Cobaltine, 57 Cobalt-mica, 416. Cobalt pyrites, 67. Cobalt vitriol, 385. Coccinite, 96. Coccolite, 159, 160. Cölestein, 368. Collyrite, 388. Colophonite, 190. COLUMBATES, 844. Columbite, 353. Comptonite, 325. Condrodite, 186. Condurrite, 36. Conichalcite, 421. Conistonite, 465. Conite, 441. Connellite, 375. Copal, Fossil, Copaline, 467. Copiapite, 387. Copper, Native, 17. Antimonial, 78, 82 Arsenates, 419, 421,425, 429. Arsenical, 36. Black, 109, 17, 134. Blue, 65, 459. Capillary red, 122 Carbonates, 458. Chromate, 860. Emerald, 309. Glance, 46. Gray, 82. Indigo, 65. Muriate, 138. Oxychlorid, 188. Oxyd, 101, 109,117,121 Phosphate, 412, 420 425. Purple, 38. Pyritous, 68. Red, 101, 122. Selenid, 43. Silicate, 309. Sulphate, 380, 391. Sulphato-chlorid, \$74 Sulphuret, 38, 46,65,6

GENERAL INDEX.

Copper, Tungstate, 502. Vanadate, 362, 863. Variegated, 88. Vitreous, 46, 505. Copper and Lead, Selenid of, 42. Copper froth, 426. Copper glance, 46, 505. Copper green, 809. Copper mica, 428. Copper nickel, 52. Copper ore, Black, 109, 117. Blue, 459. Emerald, 309. Gray, 82, 512. Green, 458. Indigo, 65. Octahedral, 101. Variegated, 38. Velvet, 392. Yellow, 68. Copper pyrites, 68. Copperas, 380, 385, 887. Soda, 389. Potash, 389. Coquimbite, 380. Coracite, 108. Coral, 440. Corallinerz, 48. Cordierite, 214. Corindon, 111. Cork, Mountain, 172. Corneine, 172. Corneous lead, 463. Cornite, 246. Cornubianite, 246. Cornwallite, 425. Corundellite, 800. Corundophilite, 298. Corundum, 111. Cotunnite, 97. Couzeranite, 206. Covelline, 65, 505. Crednerite, 126. Crichtonite, 115. Crispite, 120. Crocidolite, 279. Crocoisite, 359. Cronstedtite, 299. Cross stone, 257. Crucite, 257. Cryolite, 97. Cryptolite, 399. Cryptoline, 471. Cuban, 68. Cube ore, 422. Cube spar, 369. Cubizit, 318. Cuboite, 818. Cuivre arseniate, 420-429. arsenical, 36. carbonate, 458.

Cuivre gris, 82. hydrosiliceux, 309. muriaté, 138. natif. 17. oxidé rouge, 101. phosphate, 420, 425. pyriteux, 68. pyriteux hepatique, 38. Diopside, 159. selenié, 43. sulfaté, 380. sulfuré, 46. sulfuré argentifère. 48. Diphanite, 301. vanadaté, 862. veloute, 892. Cumengite, Cummingtonite, 174. Cupreous anglesite, 390. manganese, 186. Cuprite, 101. Cuproplumbite, 41. Cyanite, 263. Cyanosite, Cyanose, 380. Cyanotrichite, v. Lettsomite. Dolomite, 441. Cyclopite, 254. Cymophane, 122. Cyprine, 197. Dalarnite, v. Mispickel. Damourite, 223. Danaite, 62. Danburite, 212. Datholite, Datolith, 334. Daourit, v. Rubellite. Davidsonite, 178. Davyne, 282. Davyt, 881. Dechenite, 861. Delanovite, 500. Delessite, 296. Delphinite, 206. Delvauxene, 427. Demant, 24. Demantspath, 111. Dendrachates, 151. Dermatin, 280. Descloizite, 361. Desmin, 332. Devonite, 428. Deweylite, 285, 505. Diabase, 162. Diaclasite, 160. Diadochite, 438. Diagonite, 832. Diallage, Talkartiger, 160. Green, 160, 170. Metalloidal, 160. Diallogite, 446. Diamant, 24. Diamond, 24. Diaphorite, w. Allagite. Diaspore, 128. Diastatite, 172.

Dichroite, 214. Digenite, 48. Dihydrite, 425. Dillnite, 338. Dimagnetite, 106. Dimorphine, 82. Dinite, 475. Dioptase, 309. Diorite, 247, 509. Dioxylite, 874. Diploite, 284. Dipyre, 205. Discrasite, 85. Disomose, 58. Disterrite, 297. Disthene, 263. Dog Tooth Spar, v. Calcite, 435. Dolerine, 246. Dolerite, 162, 247, 510. Dolomite sinter, 457. Domeykite, 36. Domite, 246. Dopplespath, v. Calcite. Dopplerite, 474. Dreelite, 373. Dufrenite, 427. Dufrénoysite, 77. Dyoxylite, 374. Dysclasite, 806. Dyskolite, v. Saussurite. Dysluite, 108. Dyslytite, 53. Dysanite, 167. Dysyntribite, 252. Earthy cobalt, 136. manganese, 136. Edelforsite, 155, 808. Edelith, 314. Edingtonite, 823. Edwardsite, 402. Egeran, 197. Ehlite, 426. Ehrenbergite, 380. Eisen, Gediegen, 17. Eisenapatit, 399. Eisenalaun, 888. Eisenblau, 415. Eisenblüthe, 448.

Eisenchlorit, 296. Eisenchrom, 106. Eisenerde, Blaue, 415. Grüne, 182. Eisenerz, Trappisches, 116. Eisenerz, Hystatisches, 115. Eisenglanz, 113. Eisenglimmer, 118. Eisengymnite, 286.

Eisenkies, 54. Rhombischer, 60. Eisenkiesel, 145. Eisenkobalterz, v. Safflorite, 511. Eisenmulm, 105. Eisennatrolith, 327. Eisennickelkies, 42. Eisenopal, 151. Eisenoxyd, 118. Eisenoxydhydrat, 131. Eisenoxyd, Schwefelsaures, 880, 885, 887. Eisenpecherz, 408, 482. Eisenperidot, 185. Eisenphyllit, 415. Eisenresin, 464. Eisensinter, 419. Eisenspath, 444. Eisenrahm, v. Red ochre. Eisenrose, 116. Eisenrutil, 129. Eisensteinmark, 512. Eisentitan, 120. Eisenvitriol, 385. Eisspath, 242. Eisstein, 97. Ekebergite, 201. Elæolite, 282. Elasmose, 65. Elaterite, 471. Electrum, 8. Eliasite, 108, 505. Embolite, 93. Embrithite, 81. Emerald, 178. Emerald nickel, 461. Emeraude, 178. Emery, 111. Emerylite, 800. Emmonite, 450. Enargite, 87, 506. Enceladite, 395. Endellionite, 80. Ephesite, 801. Epichlorite, 288. Epidote, 206. Epistilbite, 380. Epsom salt, Epsomite, 384. Erdkobalt, 136. Erdharz, 469, 471. Erdmannite, 195, 840. Erdől, 469. Erdwachs, 474. Eremite, 402. Erinite, 425. Erlanite, 191. Erubescite, 38. Erythrine, 416. Erythrite, 215. Eschenite, 357. Kamarkite, 205, 215, 834.

ĺ

Essonite, 191. Etain oxydé, 118. sulfuré, 70. Eucairite, 43. Euchroite, 421. Euchysiderite, v. Pyroxene. Fettbol, 252. Euclase, 267. Eudialyte, 181. Eudnophite, 318. Eugenesite, v. Selenpalladite. Eugenglanz, 85. Eukairite, 43. Euklas, 267. Eukolite, 343. Eulytine, 181. Eumanite, 123. Euphyllite, 291. Eupyrchroite, 396. Eurite, 246. Euxenite, 358. Euzeolith, 380. Exanthalose, 386. Exitèle, 140. Fahlerz, 82. Fahlunite, 215. Hard, 214. Fäserzeolith, 327. Fassaite, 159. Faujasite, 329. Fayalite, 185. Feather alum, 381. Feather ore, 76. Federalaun, 381, 388. Federerz, 76. Feldspar, 228, 506. Common, 242. Labrador, 237. Potash, 242. Soda, 240. Feldstein, 242. Felsite, 242. Felsobanyite, 184. Felspath, 242. apyre, 257. blue, 404. tenace, 254. Fer azuré, 415. arseniaté, 422. arsenical, 61, 62. carbon até, 444. chromaté, 106. hydro-oxidé, 131. natif, 17. oligiste, 113. oxidé, 118. oxidul6, 105. magnetique, 105. muriate, 810. phosphate, 415.

sulfaté, 880, 885, 887.

Fer sulfuré, 54, 60. sulfuré magnetique, 50. Fergusonite, 350. Ferrocobaltine, 58. Ferrotantalite, 351. Fettstein, 232 Feuerblende, 88. Fibroferrite, 388. Fibrolite, 265. Fichtelite, 472. Figure stone, 252. Fiorite, 151. Fireblende, 88. Fischaugenstein, 304. Fischerite, 408. Flexible silver ore, 71. Fliegenstein, v. Arsenie. Flint, 145. Float stone, 148. Flockenerz, w. Mimetene. Flos ferri, 448. Flucerine, 96. Fluellite, 98. Fluocerine, 96. Fluocerite, 96. Fluochlore, 345. Fluor, Fluor Spar, 94. FLUORIDS, 89. Flussepath, 94. Foliated tellurium, 65. Fontainbleau limestone, 439. Forsterite, 184. Fowlerite, 167. Francolite, v. Apatite, (Analysis, 4), 396. Franklinite, 106. Frauenglas, v. Mica. Freibergite, 512. Freislebenite, 79. Frugardit, 197. Fuchsite, 222. Fuller's Earth, 504. Fullonite, v. Onegite. Funkite, 160. Fuscite, v. Scapolite. Gabronite, 506. Gadolinite, 211. Gagates, 27

Gahnite, 103.

Gallicinite, 120.

Gallitzenstein, 120. Galmey, 313, 447. Ganomatit, 432.

Gänseköthig erz. 482.

Bohemian, 194

Garbenstilbit, 882

Garnet, 190.

Galapektite, v. Halloysite Galena, 39, 506.

Garnet, Tetrahedral, 194. Garnsdorffite, 390. Gay-Lussite, 455. Gedrite, 175. Gehlenite, 256, 205. Gekrösetein, 369. Gelbbleierz, 349. Gelbeisenerz, 389. Gelberde, 131. Gelberz, 64. Gelferz, v. Chalcopyrite. Geocronite, 85. Gersdorffite, 58. Geyserite, 151. Gibbsite, 134, 506. Gieseckite, 233. Giftkies, v. Mispickel. Gigantolite, 215. Gilbertite, 223. Gillingite, 290. Giobertite, 441. Girasol, 151. Gismondine, 822. Glance copper, 46. Glanzarsenikkies, 61. Glanzkobalt, 57. Glanzkohle, 26. Glaserite, 365. Glaserz, Glanzerz, 113, 131. Grünerde, 165. Grünerite, 160. Glätte, 109. Glauber salt, 386. Glauberite 374. Glaucodot, 68. Glaucolite, 201. Glauconite, 288. Glaucophane, 177. Glaukosiderit, 415. Glimmer, 217-227. Glinkite, 184. Glottalite, 319. Gmelinite, 321. Gneiss, 246. Gökumite, 197. Gold, 7. Gold amalgam, 15. Gashenite, 178. Goslarite, 384. Göthite, 129. Gotthardite, 77. Grammatite, 172. Grammite, 156. Granat, 190. Granite, 246, 509. Granulite, 246, 509. Graphic gold, 64. tellurium, 64. Graphite, 29. Graubräunsteinerz, 125. Grauerz, v. Galena. Graukobalterz, 41. Graugiltigerz, 82

Graukupfererz, 84. Graulite, v. Tectizite, 388. Grausilber, v. Selbite. Grauspiessglanzerz, 38. Grauspiessglaserz, 33. Gray antimony, 33. copper, 82, 512. Green diallage, 160. earth, 165, 511. iron ore, 427. lead ore, 401. malachite, 458. sand, 288. vitriol, 385. Greenlandite, 190. Greenockite, 51. Greenovite, 268. Greenstone, 162, 247. Grenat, 190. Grenatite, 261. Grengesite, 296. Groppite, 287. Groroilite, 136. Grossular, 191. Granauite, 44. Grünbleierz, 400, 401. Grüneisenerde, 182. Grüneisenstein, 427. Grünerite, 160. Guanite, 413. Gummierz, 107. Gummispath, 431. Gurhofian, Gurhofite, 442. Gurolite, 305. Guyaquillite, 468. Gymnite, 285, 505. Gypsum, 377. Gyrolite, 305. Haarkies, 49. Haarsalz, 381, 383. Hæmachates, 151. Hæmatite, 113. Hafnefjordit, 239. Haidingerite, 418, 78. Hair-salt, 381. Halbazurblei, 372. Hallite, 389. Hallovlite, 251. Halloysite, 251. Halotrichine, 388. Halotrichite, 381, 383. Hampshirite, 277. Harmotome, 323, 824. Harringtonite, 328. Hartbraunstein, 117. Hartine, 473. Hartite, 473. Hartkobaltkies, 67. Hartmanganerz, 135. Hatchettine, 473.

Hauerite, 56. Hausmannite, 118. Häuyne, 230. Haydenite, 319. Hayesine, 394. Haytorite, 148. Heavy spar, 366. Hebetine, 189. Hedenbergite, 160. Hedyphane, 401. Helleflinta, 245. Heliotrope, 148. Helminth, 294. Helvin, 194. Hematite, 113, 506. Brown, 131. Hepatinerz, 310. Hepatite, 366. Hercinite, 103. Herderite, 410. Hermannite, v. Mangan-amphibole, Herschelite, 321, Hessite, 44, 506. Hetepozite, 407. Heteroclin, 127. Heteromerite, 199. Heteromorphite, 76. Heterosite, 407, 513. Heulandite, 330. Highgate resin, 467. Himbeerspath, v. Diallogite. Hisingerite, 290. Hohlspath, 257. Holmesite, 297. Holz, Bituminöses, 26. Holzkupfererz, 421. Holzopal, v. Wood opal. Honey stone, 475. Honigstein, 475. Hopeite, 409. Hornblei, 463. Hornblende, 170. Hornblende slate, 509. Hornerz, 92. Hornfels, 148, 246 Hornmangan, v. Rhodonite. Horn quicksilver, 89. Horn silver, 92. Hornstone, 148. Horse-flesh ore, 38. Houghite, 135. Howardite, 503. Houille, 26. Hudsonite, 160. Humboldtine, 464. Humboldtilite, 205. Humboldtite, 334. Humite, 186. Hureaulite, 407, 513. Huronite, 217. Hversalt, 383.

1

Hyacinth, 195. Hyalite, 151. Hyalomelan, 177. Hyalosiderite, 184. Hyblite, 166. Hydrargillite, 184. Hydraulic limestone, 440, 507. Hydroborocalcit, 894. Hydrobucholzite, 265. Hydroboracite, 393. Hydrocalcite, 457. Hydrochlore, 345. Hydochloric acid, 97. Hydrodolomite, 457. Hydrohalite, 506. Hydrolite, 821. Hydromagnesite, 456. Hydromagnocalcit, 457. Hydronickelmagnesite, 457. Hydrophane, 151. Hydrophite, 286. Hydrosilicite, 165. Hydrophilite, 506. Hydrous anthophyllite, 175. Hydrosteatite, 276. Hydrotalcite, 185. Hydrozincite, v. Zine Bloom. Hypersyrite, 75. Hypersthene, 160. Hypochlorite, 182. Hyposclerite, 241. Hypostilbite, 333. Hystatite, 115.

Isspachates, 151. Iberite, 217. Ice spar, 245. Iceland spar, 438. Ichthyophthalmite, 304. Idocrase, 197, 506. Idrialine, Idrialite, 470. Iglesiasite, 452. Igloite, Iglite, 448. Ildefonsite, 355. Illuderite, v. Zoisite. Ilmenite, 115, 356, 506. Ilvait, 262. Indianite, 235. Indicolite, 270. Indigo copper, 65. Inolite, 485. Iodie silver, 95. quicksilver, 96. IODIDS, 89. Iodite, 95. Iodolite, 503. lodyrite, 95, 506. Iolita 214. Hydrous, 215. Iridium, Native, 13, 19. Iridoemine, 19.

Irite, 108. Iron, 17. Arsenate, 422. Antimonial sulphuret, 78. Arsenical, 61, 62, 63. Borate, 395. Carbonate, 444. Chromic, 106. Columbate, 358. Cupreous arsenate,419. Jefreinoffite, 506. Hydrous oxyds,129,181 Jenkinsite, 286. Magnetic, 105. Meteoric, 17. Oxalate, 464. Oxydulated, 105. Peroxvd, 102, 113. Phosphate, 399, 406-408,415,424,427,431. Silicates, 160, 185, etc. Sulphate, 880, 385, 387, 889. Sulphuret, 50, 54, 60. Tantalate, 351. Titaniferous, 115. Tungstate, 851. Iron alum, 383. Iron earth, Blue, 415. Iron natrolite, 327. Iron ore, Argillaceous, 113, Kalisulphat, 865 131, 444. Axotomous, 115. Bog, 131. Brown, 131. Green, 427. Jaspery, 113. Lenticular, 113. Magnetic, 105. Micaceous, 113. Ochreous, 113, 131. Octahedral, 105. Pitchy, 182, 408. Red, 113. Sparry, 444. Specular, 118. Titaniferous, 115. Iron pyrites, 54. Magnetic, 50. White, 60. Iron rutile, 129. Iron sinter, 419, 432 Ironstone, Clay, 113, 131. Blue, 415. Iserine, 102. Isophane, r. Franklinite. lsopyre, 255. Itaberite, 113.

Jade, Common, 175.

Itacolumite, 24.

Ittnerite, 319.

Ixolyte, 478.

Jade tenace, 254. Jamesonite, 75. Jargionite, 40. Jargon, 195. Jarosite, 389. Jasper, 148, 151. Jaspery iron ore, 113. Jayet, 26. Jeffersonite, 160. Jelletite, 194. Jet, 26. Jewreinowite, 506. Johannite, 386. Johnite, 405. Junkerite, 446. Jurinite, 123.

N.B. Many names spelt with an initial K in German, begin with C in Eng-

Kakochlor, 186. Kakoxene, 424. Kalait, 405. Kalamit, 172. Kalialaun, 382. Kalisalpeter, 433. Kalisalzsaures, 90. Kaliphite, 133. Kalk-Malachit, 458. Kalksalpeter, 434. Kalkspath, 435. Kallochrom, v. Crocoisite. Kalzedon, 147. Kämmererit, 291. Kammkies, 60. Kampylite, 401. Kancelstein, 191. Kaneite, 53. Kaolin, 249, 506. Kapnite, 447. Karneol, v. Carnelian. Karpholite, 316. Karphosiderit, 431. Karstenite, 869. Kastor, 253. Katapleiit, 308, 504. Kausimkies, 61. Keilhauite, 841. Keramohalite, 382 Kerasite, 463. Keraphyllite, r. Carinthine Kerargyrite, 92 Kerate, 92. Kermes, Kermesite, 141. Kermesome, 141. Kerolite, 280.

Kibdelophan, 115.

Kieselgalmey, 813. Kieselkupfer, 809. Kieselmalachit, 809. Kieselmangan, 167. Kieselschieffer, 148. Kieselspath, 240. Kieselwismuth, 181. Kieselzinkerz, 313. Kilbrickenite, 85. Killinite, 170. Kirwanite, 288. Klaprothine, 404. Klinoclas, 428. Knebelite, 186. Knistersalz,v. Common Salt. Kobaldine, 67. Kobaltbeschlag, 417. Kobaltblüthe, 416. Kobalt-glanz, 57. Kobaltkies, 67. Kobaltsulfuret, 41. Kobaltvitriol, 385. Kobellite, 82. Kochsalz, 90. Kohle, 26. Kohlensaurer Kalk, 435. Kokkolit, 158. Kollyrite, 338. Kolophonit, 190. Konichalcit, 421. Konigine, 391. Könleinite, 472. Könlite, 472. Korite, 166. Köttigite, 418. Korund, 111. Koupholite, 314. Krablite, 248. Kraurite, 427. Kreittonite, 108. Kremersite, 90. Kreuzstein, 323. Krisoberil, 122. Krisolith, 184. Krisuvigite, 391. Krokidolite, 279. Krokoit, 359. Kryolite, 97. Kühnite, 404. Kupaphrite, 426. Kupfer, Gediegen. 17. Kupferantimonglanz, 78. Kupferbleiglanz, 41. Kupferbleispath, 890. Kupferblende, 84. Kupferblüthe, 101, 122. Kuppferdiaspore, 425. Kupferfahlerz, 82. Kupferglanz, Kupferglas, 46. Kupferglimmer, 428. Kupfergran, 309. Kupferindig, 65.

Kupferkies, 68. Kupferlasur, 459. Kupfermanganerz, 186. Kupfernickel, 52. Kupferpecherz, 310. Kupferphyllit, 428. Kupfersammterz, 892. Kupferschaum, 426. Kupferschwärze, 109, 187. Kupfer-smaragd, 809. Kupfer-vitriol, 380. Kupferwismutherz, 73, 88. Kupferwismuthglanz, 78. Kyanite, 263. Kymatine, 170. Kypholite, 282. Kyrosite, 60.

Labradorite, 287. Labrador feldspar, 237. Labrador hornblende, 160. Lagonite, 895. Lampadite, 186. Lanarkite, 874. Lancasterite, 456. Lanthanite, 456. Lapis-lazuli, 229. Lapis ollaris, 276. Larderellite, 395. Lardite, 252, 276. Lasionite, 423. Lasurite, 459. Lasurstein, 229. Latrobite, 284. Laumonite, Laumontite, 307. Lepolite, 235.

Lava, 510. Lavendulan, 417, 507. Lazulite, 404. Lead, 17.

Antimonial sulphurets, Leucolite, v. Pycnite. Antimonate, 142.

Argentiferous, 89. Arsenate, 401. Black, 29. Carbonate, 452. Chlorid, 97. Chloro-carbonate, 463. Libethenite, 420. Chromate, 859, 861.

Corneous, 463. Cupreous sulphate, 890. Lievrite, 262. Cupreous sulphato-car- Lignite, 26. bonate, 372.

Molybdate, 349 Murio-carbonate, 468. Oxychlorid, 127, 128. Oxyds, 109, 117, 126. Phosphate, 400.

Selenate, 375. Seleniets, 42. Sulphate, 870. Lead, Sulphato-carbonate, 874. Sulphato-chlorid, 875. Sulphato-tricarbonate, 871. Supersulphuretted, 40. Sulphuret, 39, 506. Tellurid, 44, 65. Tungstate, 849. Vanadate, 862. White, 452. Lead glance, 39. Lead ochre, 109.

Lead ore, Green, 401. Red, 859. White, 452. Yellow, 349.

Lead vitriol, 370. Leadhillite, 871, 507. Leberblende, 46. Leberkies, 60. Ledererite, 321. Lederite, 268. Leedsite, 507. Leelite, 245, 248. Lehmanite, 359. Lehrbachite, 43. Lehuntite, 327. Lemnian Earth, 504.

Lenzinite, 251. Leonhardite, 808. Lepidokrokite, 129. Lepidolite, 226, 508. Lepidomelane, 227. Leptynite, 246. Lettsomite, 892. Leuchtenbergite, 294. Leucite, 281.

Leucocyclite, v. Apophyl-lite. Leucophane, 182. Leucopyrite, 61, 507.

Leuzit, 231. Levyne 821. Lherzolite, 160. Liebenerite, 215. Liebigite, 461. Ligurite, 270. Hydro-aluminous, 431. Limbelite, 184.

Lime, Anhydrous sulphate, 869.

Arsenate, 414. Borate, 394. Borosilicate, 884. Carbonate, 435. Fluate, 94. Hydrous carbonate,457 Lime, Subcarbonate, 507. Nitrate, 434. Oxalate, 464, 465. Phosphate, 396. Silicate, 155, 156. Sulphate, 369, 877. Titanate, 845. Tungstate, 347. Limestone, 439. Hydraulic, 439, 507. Magnesian, 441. Limonite, 181. Linarite, 390. Lincolnite, 880. Lindackerite, 500. Lindsavite, 235. Linnæite, 67. Linseite, 285. Linsenerz, 429. Linsenkupfer, 429. Liparite, 94. Liroconite, 429. Litheospore, \$66. Lithionglimmer, 226, 508. Lithomarge, 250. Loboit, 197. Loganite, 293. Lölingite, 61. Lomonit, 807. Lonchidite, 61. Lophoite, 296. Lotalite, 170. Löweite, (Löveite), 501. Loxoclase, 244. Lumachelle, 439. Lunnite, 425. Lupus metallorum, 33. Lydian stone, 148. Lyncurion, 466.

Macle, 257. Maclurite, 186. Magnesia, Pure, 101. Borate, 393. Carbonate, 441. Fluophosphate, 403. Fluosilicate, 188. Hydrate, 133. Hydro-carbonate, 456. Sulphate, 384. Magnesia alum, 382. Magnesian limestone, 441. pharmacolite, 404. Magnésie hydratée, 133. Magnesite, 441, 277, 507. Magneteisenstein, 105. Magnetic iron ore, 105. Magnetic pyrites, 50. Magnetite, 105. Magnetkies, 50. Malachite, Blue, 459. Green, 458.

Malachite, Lime, 459. Malacolite, 158. Malacone, Malakon, 196. Maltha, 469. Malthacite, 340. Mancinite, 156. Mangan, Kohlensaures, 446. Mangan-amphibole, 168. Manganblende, 41. Manganese, Oxyd of, 117, Mellite, 475. 118, 125. Melopsite, 2 Hydrous oxyds, 180, Menaccanite, 115. 135, 136. Arseniuret, 58. Black, 185. Bog, 186. Carbonate, 446, 452. Cupreous, 136. Earthy, 186. Gray, 125, 130. Phosphate, 399, 406, 408. Red. 446. Silicates, 167, 186. Sulphate, 501. Sulphuret, 41. Manganese spar, 167. Manganglanz, 41. Manganite, 130. Mangankiesel, 167. Mangankupfererz, 126. Mangankupferoxyd, 126. Manganocalcite, 452. Manganopal, 151. Manganschaum, 186. Manganspath, 446. Manganvitriol, 501. Marasmolite, 45. Marble, 439. Verd antique, 284. Marcasite, 60. Marceline, 118, 167. Marekanite, v. Pearlstone, Miargyrite, 74. 248. Margarite, 300. Margarodite, 228. Marialite, 280. Marl, 489. Marmatite, 45. Marmolite, 282. Martinsite, 90. Martite, 102. Mascagnine, 879. Masonite, 298. Matlockite, 127. Mauilite, 287. Medjidite, 392. Meerschaum, 277, 284. Meionite, 200. Melaconite, 109. Melanasphalt, 27.

Melanchlor, 428, 518.

Melanglanz, 86. Melanite, 192. Melanochroite, 361. Melanolite, 288. Melanterite, 385. Melaphyre, 162. Melinophane, 183. Mellate of alumine, 475. Mellilite, 205. Melopsite, 250. Menakerz, 268. Mendipite, 128. Meneghinite, 501. Mengite, 356. Menilite, 151. Mennige, 126. Mercurblende, 48 Mercure argentif, 14. sulfuré, 48. ioduré, 96. Mercury, Antimonite, 142. Amalgam, 15. Chlorid, 89. Iodic, 96. Native, 14 Selenid, 52 Sulphuret, 48. Merkurglanz, 52. Meroxene, 225. Mesitine spar, 443. Mesitinspath, 443. Mesole, \$28. Mesolin, 322 Mesolite, 328. Mesotype, 327, 328. epointée, 804. Metachlorite, 297. Metaxite, 283, 285. Meteoric minerals, 503. Miascite, 246. Mica, 217-227, 507. Oblique, 221. Rhombic, 224 Hexagonal, 225. Lithia, 226. Mica slate, 246, 509. Michaelite, 151. Microlite, 845. Middletonite, 467. Miemite, 441. Miesite, 400. Mikroklin, 242. Millerite, 49. Miloschin, 389. Mimetene, 401. Mineral caoutchouc, 471. coal, 26. resin, oil, pitch, 468. tallow, 473.

GENERAL INDEX.

Minium, 126. Natro-calcite, 438. Mirabilite, 386. Miscnite, 377. Mispickel, 62, 509. Misy, 388. Mizzonite, 200. Mocha Stone, 147. Modumite, 67. Mohsine, 61. Mohsite, 115. Molybdänglanz, 66. Molybdänochre, 144. Molybdansilber, v. Tetrady- Nemalite, 133. mite, Anal., 3, Molybdate of lead, 349. Molybdate of iron, 144. Molybdène sulfuré, 66. Molybdenite, 66. Molybdic ochre, 144. Molybdine, 144. Monazite, 402. Monazitoid, 403. Mondstein, v. Moonstone, Monheimite, v. Kapnite, 447. Nickel, Antimonial, 53. Monophan, 330. Monradite, 280. Monrolite, 268. Monticellite, 84. Montmorillonite, 840. Moonstone, 240, 244. Morasterz, 131. Moroxite, 396, Morvenite, 323. Mosandrite, 342. Mountain green, 458. cork, 172. leather, 172 Müller's glass, 151. Mullerite, 64. Mullicite, 415. Mundie, 54. Murchisonite, 245. Muriacite, 369. Muriatic acid, 97. Muromontite, 210. Muscovite, 221, 508. Muscovy glass, 221. Müsenite, v. Siegenite. Mussite, 159. Mussonite, 463. Myelin, 250. Mysorin, 458. Nacrite, 509.

Nadeleisenerz, 129. Nadelerz, 81 Nagyager-erz, 65. Nagyagite, 65. Naphtha, 469. Naphthadil, 470. Napoleonite, 242. Nasturan, 107.

Natrolite, 327. Natron, 455. alaun, 382. salpeter, 433. Natron-spodumen, 239. Naumannite, 43. Necronite, 244. Needle ore, 81. Needle spar, 448. Needlestone, 327, 328. Nefelina, 232. Neoctese, 419. Neolite, 278. Neoplase, 387. Neotokite, 169. Neotype, 438. Nepheline, 232. Nephrite, 175. Magerer, 254. Newjanskite, 19. Newkirkite, 130, 136. Arsenical, 52, 56, 58, 6 Bismuth, 44. Carbonate, 461. Copper, 52. Emerald, 461. Silicate, 339. Sulphate, 386. Sulphuret, 49. White, 56. Nickel glance, 57. green, 418. ochre, 418. stibine, 59. vitriol, 386. Nickel and iron, Sulphure of, 42. Nickelantimonglanz, 59. Nickelarsenikglanz, 58. Nickelarsenikkies, 58. Nickel-blüthe, 418. Nickel-bournonit, 81. Nickelglanz, 58. Nickel-gymnite, 286. Nickeliferous gray antimo ny, 59. Nickelkies, 52. Nickelocker, 418. Nickelspiessglanzerz, 59. Nickelwismuthglanz, 44. Nigrine, 120. Niobite, 353. NITRATES, 433. Nitratine, 433.

Nitre, 433.

Nitrocalcite, 434.

Nosean, Nosin, 230.

Nontronite, 337.

Notite, 166. Nussierite, 400. Nuttallite, 201. Obsidian, 248. Ochran, 252. Ochre, Iron, 113, 131. Bismuth, 141. Chrome, 339. Molybdic, 144. Plumbie, 109. Telluric, 502. Tungstic, 148. Uranie, 461. Ochroite, 312. Octahedrite, 121. Odontolite, 513. Erstedtite, 197. Ogcoite, 296. Oil, Genesee or Seneca, 469. Oisanite, 121. Okenite, 306. Oligiste iron, 113. Oligoclase, 239, 506. Oligon spar, 445. Olivenchaleit, 420. Olivenerz, 420. Olivenite, 420. Olivine, 184. Olivinoid, 503. Omphazit, 159. Onegite, 129. Onkosin, 504. Onofrite, 52. Onyx, 148. Oolite, 438. Oosite, 216. Opal, 151. Opal allophane, 387. Operment, 32, Ophite, 284. Opsimose, 167. Or natif, 7. Orangite, 312. Orawitzite, v. Halloysite. Oropion, 508. Orpiment, 32. Orthite, 208. Orthoclase, 242, 506, 513. Orthose, 242, Osteolite, 398. Ostranite, 196. Ostreocolla, 435. Osmelite, 305. Osmiridium, 19. Ottrelite, 287, 509. Ouvarovite, 192. Owenite, 290. Oxacalcite, 464. OXALATES, 464. Oxalite, 464.

Oxhaverite, 304.

OXYDS. Monometric, 101. HEXAGONAL, 110. DIMETRIC, 117. TRIMETRIC, 122. WITH SULPHURETS. CHLORIDS, 127. HYDROUS, 128. of Arsenic Group, 189. Petzite, 44. Ozarkite, 326. Ozocerite, Ozokerit, 474. Pagedite, 252. Paisbergite, 167. Palagonite, 166. Palladium, Native, 14. Palladium gold, 9. Palladium ochre, 14. Panabase, 82. Paracolumbite, 501. Paraluminite, 509. Paranthine, 201. Parastilbite, 332 Pargasite, 172. Parisite, 463. Parophite, 252. Partschin, 501. Partschite, 503. Patrinite, v. Aikinite. Paulit, 160. Pearl-mica, 300. Pearl sinter, 151. Pearl-spar, 441. Pearlstone, 248. Peastone, 438. Pecheisenerz, 129. Pecherz, 107. Pechkohle, 26. Pechopal, 151. Pechstein, 248. Pechuran, 107. Pectolite, 305. Peganite, 408. Pegmatite, 246. Pegmatolite, 242. Pektolite, 305. Péle's Hair, 248. Peliom, 214. Pelokonite, 186. Pencatite, 509. Pennine, 295. Pennite, 457. Pentaklasit, 158. Percylite, 501. Periclase, 101. Peridot, 184. Periklas, 101.

Periklin, 240.

Perlit, 248.

Perlstein, 248.

Peristerite, 241. Perlglimmer, 800.

Perthite, 242. Perofskite, 345. Perowskine, 406. Perowskite, 345. Petalite, 253. on Petroleum, 469. Petrosilex, 248. Petuntze, 250. Pfeifenstein, 252. Phacolite, 319. Pharmacolite, 414. Pharmakochalcit, 420. Pharmakosiderit, 422, 426. Phenacite, Phenakit, 189. Phengite, 221. Phillipsite, 38, 824. Phlogopite, 224. Phœnicite, 361. Phœnikochroite, 361. Pholerite, 251. Phonolite, 246. Phosgenite, 463. PHOSPHATES, 896. Anhydrous, 396. Hydrous, 411. Phosphocerite, 399. Phosphochalcite, 425. Phosphorblei, v. Pyromor-Plombgomme, 431. phite. Phosphor-eisensinter, 433. Phosphorit, 396. Photizit, 167. Phthanite, 148. Phyllite, 287. Phylloretin, 472. Physalite, 259. Piauzite, 469. Pickeringite, 382. Picranalcime, 318. Picrolite, Pikrolit, 282. Picropharmacolite, 415. Picrophyll, Pikrophyll, 165, Polychroilite. 255. 280. Picrothomsonite, 326. Pictite, 268. Piedmontite, r. Mangane sian epidote, 206. Pierre grasse, 232. Pihlite, 295. Pimelite, 339. Pinguite, 338. Pinite, 215. Piotine, 282. Pipestone, 252. Pirenäit, 192, Pirop, 194. Pisolite, 438. Pissophane, 390. Pistacite, 206. Pistomesite, 443.

Pitch, Mineral, 469. Pitchblende, 107. Pitchstone, 248. Pitchy iron ore, 132,408,432. Piticite, Pittizit, 432, 388. Pittinerz, 107. Plagionite, 75. Plasma, 148. Plaster of Paris, 377. Plata azul, 511. Plata verde, 93. Platinum, Native, 12. Platiniridium, 13. Plattnerite, 117. Platyophthalmon, 34. Pleonaste, 103. Pleuroclase, 403. Plinian, 62. Plomb antimonié sulfure, 81. carbonaté, 452 chloro-carbonaté, 468. chromate, \$59. hydro-alumineux, 431. natif, 17. oxydé, 109, 117, 126. seleniuré, 42 sulfuré, 39. See farther, Lead Plumbago, 29. Plumbic ochre, 109. Plumbocalcite, 438. Plumbe "esinite, 431. Plumbostib, 81. Plumose ore, 76. Plumosit, 76. Polianite, 131. Pollux, 255. Polyadelphite, 193. Polyargite, 236. Polybasite, 85. Polycrase, 357 Polyhalite, 377. Picrosmine, Pikrosmin, 281. Polyhydrite, r. Hisingerite Polykras, 357. Polylite, 160. Polymignyte, 356. Polysphærite, 400. Polytelite, 82. Polyxen, 12. Poonahlite, 329. Porcelain spar, 201. Porphyry, 246, 509. Porpezite, 9. Porricin, r. Pyroxene. Portite, 311. Potash alum, 382. Potash, Muriate, 90. Nitrate, 433. Sulphate, 365, 377. Potstone, 276.

GENERAL INDEX.

Potter's clay, 504. Pounxa, 894. Pozzuolana, 510. Prase, 147. Praseolite, 215. Prasochrome, 501. Predazzite, 457, 509. Prehnite, 314. Prosopite, 502. Protheite, 197. Protogine, 246, 509. Proustite, 73. Prunnerite, 439. Prussian blue, Native, 415. Przibramite, 45, 180. Paathyrin, 473. Pseudo-albite, 286. Pseudo-apatite, 398. Pseudomalachit, 425. Pseudo-nepheline, 282. Pseudo-sommite, 282. Pseudotriplite, 407. Psilomelane, 135. Pumice, 246. Purple copper, 88. Puschkinite, 206. Pycnite, 259. Pyrallolite, 165. Pyrantimonite, 141. Pyrargillite, 215. Pyrargyrite, 77. Pyrenaite, 192. Pyrgom, 159. Pyrites, Arsenical, 61, 62. Auriferous, 54. Capillary, 49. Cellular, 60. Cockscomb, 60. Copper, 68. Hepatic, 60. Hydrous, 61. Iron, 54. Magnetic, 50. Radiated, 60. Spear, 60. Tin, 70. Variegated, 38. White iron, 60. Pyrochlore, 845. Pyrolusite, 125. Pyromeline, 886. Pyromeride, 246. Pyromorphite, 400. Pyrope, 194. Pyropissite, 470. Pyrophyllite, 808. Pyrophysalite, 259. Pyrorthite, 209. Pyrosclerite, 291. Pyrosiderite, 129. Pyrosmalite, 810. Pyrostibite, 141.

Pyroxene, 158. Pyroxenite, 246. Pyrrhite, 346. Pyrrhosiderite, 129. Pyrrhotine, 50. Quartz, 145. Granular, 148. nectique, 148. resinite, 151. Tabular, 148. Quecksilberfahlerz, 82. Quecksilberbranderz, 470. Quecksilberhornerz, 89. Quecksilber lebererz, 48. Quellerz, 131. Quicksilver, Native, 14. Antimonite, 142. Chlorid, 89. Sulphuret, 48. Iodid, 96. Selenid, 52. Quincite, 281. Rabenglimmer, v. Lepidomelane. Radelerz, 80. Radiated pyrites, 60. Radiolite, 327. Rammelsbergite, 56, 61. Randanite, 152. Raphanosmite, 42. Raphilite, 172 Raseneisenstein, 131. Ratoffkit, 94. Rauhkalk, 442. Rauschgelb, 31, 32. Rautenspath, 441. Razoumoffskin, 340. Realgar, 31. Red antimony, 141. chalk, 113. copper ore, 101, 122. hematite, 113. iron ore, 118. iron vitriol. 887. lead ore, 859. manganese, 446. ochre, 118. silver ore, 77, 78. vitriol, 885. zinc ore, 110. Reddle, 118. Redruthite, 46. Remingtonite, 461. Remolinite, 188. Rensselaerite, 165. Resigallum, 81, 82. Resin, Mineral, 467, etc. Highgate, 467. Retinasphalt, 467. Retinalite, 288.

Retinite, 467. Retzite, v. Ædelforsite, 808. Reussin, 375. Rhætizit, 263. Rhodalose, 385. Rhodium gold, 9. Rhodizit, 393. Rhodochrome, 291. Rhodochrosite, 446. Rhodonite, 167. Rhodophyllite, 291. Rhombenglimmer, 225. Rhomb-spar, 441. Rhyacolite, 245. Riemannite, 336. Riolite, 502. Ripidolite, 296, 294. Risigallo, 31. Rittingerite, 87. Rock-cork, 172. crystal, 145. milk, 438. salt, 90. soap, 252. Rochlandite, v. Serpentine. Romanzovit, 191. Romeine, 410. Roofing slate, 509. Rose quartz, 145. Roselite, 417. Rosellan, Rosite, 286. Rothbleierz, 859. Rotheisenerz, 118. Rother vitriol, 887. Rothgültigerz, 77, 78. Rothkupfererz, 101, 122. Rothnickelkies, 52. Rothoffit, 190. Rothspiessglanzerz. 141. Rothspiesglaserz, 141. Rothzinkerz, 110. Rubellan, 226. Rubellite, 270. Rubicelle, 108. Rubin, 111. Rubinglimmer, 129. Ruby, Spinel, Balas, Almandine, 103. Oriental, 111. Ruby-blende, 77. Ruby silver, 77, 78. Ruby sulphur, 81. Rutherfordite, 858. Rutile, 120. Ryacolite, 245. Saccharite, 286. Safflorite, 511. Sagenite, 120. Sahlite, 159. Sal ammoniac, 92. gemme, 90.

Salamstein, 111. Salmiak, 92. Salt, Common, 90. Saltpeter, 433. Salzkupererz, 188. Samarskite, 355. Sammetblende, 129. Samoite, 251. Sandaraca, 31 Sandstone, 148. Sanidin, 245. Saponite, 165, 258, 282. Sappar, 263. Sapphire, 111. d'eau, 214. Sapphirine, 266. Sarcolite, 200. Sard, 147. Sardachates, 151. Sardonyx, 148. Sassolin, 144. Satin spar, 377, 438. Sätersbergite, 507. Saualpit, v. Zoisita. Savite, 316. Saussurite, 254. Saynite, 44. Scarbröite, 838. Scapolite, 201. Schaalstein, 156. Schabasit, 319. Schapbachite, v. Bismuth Selenmolybdena, 43. Silver, 16. Schaumkalk, 377. Scheelbleispath, 848. Scheeletine, 348. Scheelin calcaire, 847. ferruginé, 351. Scheelite, 347. Scheelsaure, 148. Scheelsaures blei, 848. Scheererite, 471. Schilfglaserz, 79. Schillernder asbest, 282. Schiller-spar, 160, 165. Schillerstein, 160. Schmelzstein, 201, 205. Schmirgel, 111. Schneiderite, 816. Schörl, 270. Schorlartiger beril, 259. Schorlite, 259. Schorlomite, 342. Schreibersite, 53, 511. Schrifterz, Schrift-tellur, 64. Sideroschisolite, 299. Schrötterite, 837. Schulzit, 85. Schützit, v. Celestine. Schwarzbraunstein, 185. Schwarzerz, 41, 82. Schwarzgiltigerz, 82.

Schwarzmanganerz, 185.

Ì

Schwarzspiessglaserz, 80. Schwatzite, 512. Schwefel, 22. Schwefelantimonblei, 81. Schwefelkies, 54. Schwefelkobalt, 67. Schwefelnickel, 49. Schwerbleierz, 117. Schwerspath, 366. Schwerstein, 347. Schwimmkiesel, 151. Scleretinite, 468. Scolecite, 328. Anhydrous, 237. Scolexerose, 288. Scorodite, 419, 511. Scorza, 206. Scoulerite, 326. Secerz, v. Limonite. Seifenstein, 282. Seladonite, 165, 511. Selbite, 511. Selenblei, 42. Selenbleikupfer, 42. Selenbleispath, 375. Selenite, 377. Selenium, 23. Selenkobaltblei, 42. Selenkupfer, 43. Selenkupferblei, 42. Selenkupfersilber, 43. Selenpalladite, 14. Selenquecksilberblei, 43. Selenschwefelquecksilber, 52. Selensilber, 43. Selensulphur, 24. Semelin, v. Sphene. Semi-opal, 151. Senarmontite, 140. Seneca oil, 469. Sepiolite, 277. Serbian, 339. Sericite, 223, 509. Serikolite, v. Satin spar. Serpentine, 282, 511. of Aker, 292. Severite, 504. Seybertite, 297. Shepardite, 58. Siberite, v. Rubellite. Siderite, 147, 422, 444. Sideromelane, 248. Siderose, 444. Siderochalcit, 428. Siderotantal, 851. Siegelerde, 504. Siegenite, 67. Sienite, 246. Silber-und-antimon, 79.

Silberfahlerz, 83. Silberglanz, 37. Biegsamer, 71. Silberhornerz, 92. Silber-kupferglanz, 48. Silberphyllinglanz, 43. Silber spieseglanz, 35. Silberwismuthglanz, 16. Silex, 145. SILICATES, ANHYDROUS 154, 1. EDELFORSITE SECTION, 155. 2. AUGITE SECTION, 156. 3. EULYTINE SECTION. 181. 4. GARNET SECTION, 183 5. MICA SECTION, 217. 6. FELDSPAR SECTION, 228. 7. ANDALUMITE SECTION, 256. SILICATES, HYDROUS, 275. 1. Talo Section, 275. 2. SERPENTINE SECTION, 8. CHLORITE SECTION, 289. 1. Pyrophyllite Sec-TION, 303. 2. PECTOLITE SECTION, 804. 3. CALAMINE SECTION, 311. 4. ZEOLITE SECTION, 317. 5. DATHOLITE SECTION, 834. Silice gelatineuse, 152. Silicified wood, 148. Silicious sinter, 148, 151. Silicite, 237. Sillimanite, 265, 513. Silvanite, 64. Silver, Antimonial, 35. Antimonial sulphuret, 77, 79, 86, Arsenical, 78. Bismuthic, 16. Black, 86. Brittle sulphuret, 86. Bromic, 98. Carbonate, 511. Chlorid, 92. Cupreous sulphuret, 4& Flexible sulphuret, 71 Gray (Freislebenite)71 Horn, 92. Iodic, 95, 506.

Iodo-bromid, 500.

Muriate, 92.

Native, 15.

Silver, Red, or Ruby, 77, 78. Spherostilbite, 332. Selenic, 43. Sulphuret, 87. Sulphuret of Copper and, 48. Telluric, 44. Vitreous, 87. Silver glance, 37,86. Silver ore, Brittle, 86. Flexible, 71. Red, or Ruby, 77, 78. Sinopite, 503. Sinter, Siliceous, 148, 151. Sismondine, 298. Sisserskite, 19. Skapolith, 201. Skolecite, 328. Skolopsite, 231. Skorodit, 419, 511. Skutterudite, 67. Slate-spar, 439. Sloanite, 329. Smaltine, 56, 511. Smaragd, 178. Smaragdite, 170. Smaragdo-chalcit, 309. Smectite, 251, 340. Smelite, 250. Smirgel, 111. Smithsonite, 447. Soapstone, 275, 282. Soda, Borate of, 894. Carbonate of, 454. Muriate of, 90. Nitrate of, 438. Sulphate, 365, 886. Soda alum, 382. Soda copperas, 389. Soda spodumene, 289. Sodalite, 229. Soimonite, v. Corundum. Solfatarité, 382. Somervillite, 205. Sommite, 232. Sonnenstein, v. Sunstone. Soude, v. Soda. Sordawalite, 177. Soufre, 22. Spadaite, 278. Spaniolite, 83. Spargelstein, 396. Spärkies, 60. Sparry or Spathic iron, 444. Spartalite, 110. Spatheisenstein, 444. Spear Pyrites, 60. Speckstein, 275. Specular Iron, 118. Speerkies, 60. Spessartine, 192. Speiskobalt, weisser, 56. Sphærosiderite, 444.

Sphærulite, 248. Sphalerite, 45. Sphene, 268. Sphenomatite, 503. Sphragide, 504. Spiessglanz, Gediegen, 21. Spiessglanzocher, 142. Spiesglanzweiss, 140. Spiessglanzbleierz, 80. Spiesglas, 21. Spiesglas-silber, 35. Spinel, 108. Spinel ruby, 108. Spinellane, 280. Spinelle zincifère, 108. Spinthere, 268. Spodumene, 169. Soda, 239. Spreustein, 327. Sprödglanzerz, 86. Sprödglaserz, 86. Sprudelstein, 449. Stahlkobalt, 58. Stahlstein, 444. Stalactite, 439. Stalagmite, 439. Stangenkohle, 26. Stangenspath, 366. Stangenstein, 259. Stannine, 70. Stannite, 512. Stanzait, 257. Staurolite, 261, 323. Staurotide, 261. Steatite, 275, 282, Steinheilite, 214. Steinmannite, 41, 40. Steinmark, 250. Steinöl, 469. Steinsalz, 90. Stellite, 306. Stephanite, 86, 128. Stercorite, 418. Sternbergite, 71. Stibiconise, 142. Stibine, 88. Stibium, 38. Stiblite, Stibilite, 142. Stibnite, 38. Stilbite, 882. Stilbit anamorphique, 380. Blättriger, 830. Stillolite, v. Opal. Stilpnomelane, 287. Stilpnosiderite, 129. Stinkstone, 489. Stolpenite, 503. Stolzit, 848. Strahlenkupfer, 428. Strahlerz, 428. Strahlkies, 60,

Strahlstein, 170. Strahlzeolith, 382. Strakonitzite, 502. Stratopeite, 169. Stroganowite, 203. Stromeyerite, 48. Stromnite, v. Barystrontianite, 451. Strontia, Carbonate, 450. Sulphate, 368. Strontianite, 450. Strontianocalcite, 489. Struvite, 413. Stylobite, 256. Stypticite, 388. Succinite, 191, 466. SULPHATES, 364. Anhydrous, 364. HYDROUS, 876. Sulphur, Native, 22. Selenic, 24. SULPHURETS, 30-88. Sulphuric acid, 143. Sulphurous acid, 143. Sumpferz, 131. Sunstone, 239, 244. Susannite, 378. Swaga, 894. Swinestone, 489. Syenite, 246. Syepoorite, 41. Sylvan, Gediegen, 20. Sylvanite, 64. Sylvine, 90. Symplesite, 418. Tabergite, 291. Tabular spar, 156. Tachylite, 177. Tachyaphaltite, 197. Tafelspath, 156. Tagilite, 426. Talc, 275. Talc-apatite, 398. Talc phosphorsäurer, 408. Talc zographique, 295. Talcite, 509.
Talkerde, v. Magnesia. Talkerdealaun, 882. Talkspath, 441. Talkhydrat, 133. Talksteinmark, 250. Tallow, Mineral, 478. Tamarite, 428. TANTALATES, 344 Tankite, v. Chiastolite. Tannenite, 73, 512. Tantale oxydé yttrifère, 359 Tantalite, 851. Tarnowitzite, 448. Tautolite, 185. Tectizite, 388.

Tekoretin, 472 Télésie, 111. Tellur, Gediegen, 20. Tellurblei, 44 Tellure auro-argentifére, 64. auro-plombifère, 65. Tellurgoldsilber, 44. Telluric bismuth, 21. Telluric ochre, 502. Telluric silver, 44. Tellurige saure, 502. Tellurite, 502 Tellurium, 20. Black, 65. Foliated, 65. Graphic, 64. White, yellow, 64. Tellurium glance, 65. Tellurous acid, 502. Tellursilber, 44. Tellursilberblei, v. Sylvan ite. Tellurwismuth, 21. Tennantite, 84. Tenorite, 117. Tephroite, 186. Teratolite, 512. Terenite, 201. Ternärbleierz, 871. Terre verte, 165. Tesselite, 304. Tesseralkies, 56, 67. Tetartine, 240. Tetradymite, 21, 512. Tetrahedrite, 82, 512. Tetraklasit, 201. Tetraphyline, 406. Texasite, Kenngott, v. Emerald Nickel. Thalite, 165, 282. Thallite, 206. Tharandite, 441. Thenardite, 865 Thermonatrite, 455. Thierschite, 465. Thiorsauite, 235. Thomaite, 452. Thomsonite, 325. Thoneisenstein, 181. Thon, v. clay.
Thonerde Schwefelsaure, 381. Thonerde, v. Alumina. Thorite, 312, 512. Thraulite, 290. Thrombolite, 412. Thulite, 206. Thumite, Thummerstein, 206. Thuringite, 290. Tile ore, 101. Tilkerodite, 42.

T

L

Tin, 19. Oxyd of, 118. Sulphuret of, 70. Tin ore, 118. Tin pyrites, 70. Tincal, 894. Tinder ore, 76. Tirolite, 426. Titanate of lime, 345. Titaneisen, 115. Titane anatase, 121. oxydé, 120, 121, 123. silico-calcaire, 268. Titanic acid, 120, 121, 123. iron, 115. Titanite, 268. Tiza, 394. Tombazite, 58. Topaz, 259, 512. False, 147. Oriental, 111. Topazolite, 191. Topfstein, v. Potstone. Torberite, 430. Torrelite, 353. Touchstone, 148. Tourmaline, 270, 513. Towanite, 68. Trachyte, 246, 510. Trap, 247, 510. Trass. 510. Traubenblei, 400. Travertine, 435. Tremenheerite, 30. Tremolite, 172. Triklasit, v. Fahlunite. Trinacrite, 166. Tripe stone, 369. Triphane, 169. Triphyline, 406, 513. Triplite, 408. Triploklas, 825. Tritomite, 311. Trona, 454. Troostite, 189. Techeff kinite, 341. Tschermigite, 888. Tuesite, 250. Tufa, Calcareous, 439. Tungstate of iron, 351. of copper, 502. of lead, 848. of lime, 847. Tungsten, 347. Tungstic acid or ochre, 148. Turgite, 182. Türkis, 405, 51& Turmalin, 270. Turnerite, 502. Turquois, 405, 518. Tyrolite, 426.

Clexite, 394 Ullmannite, 59. Ultramarine, 229. Unghwarite, 504. Unionite, 239. Uraconise, 461. Cralite, 166, 172 Uralorthite, 208. Uranbläthe, 461. Urane oxydule, 107. Uranglimmer, 430. Urangreen, 386. Urangran, 386. Uranin, v. Pitchblenda Uranite, 430. Uranium, Carbonate, #1. 462 Oxyd, 107. Phosphate, 430. Sulphate, 386, 38, 581 Uranmica, 430. Uranochre, 461. Uranotantal, 355. Uranoxyd, 107. Uranpecherz, 107. Uranphyllit, 480. Uranvitriol, 386. Urao, 454. Uwarowite, 192. Valencianite, 212 Valentinite, 140. VANADATES, 362, 363. Vanadinbleierz, 362. Vanadinite, 362 Variegated copper, 38. Variolite, 245, 509. Variscite, 408. Varvacite, 131 Vauquelinite, 360. Velvet copper ore, 392 Verde antique, 284 Vermiculite, 292. Vermontite. v. Mispickel. Vesuvian, 197. Vesuvian salt, 365. Villarsite, 285. Violan, 177. Vitreous copper, 46. silver, 37. Vitriol, Blue, 380. Copper, 380. Green, 385. Lead, 370. Nickel, 386. Red, or Cobalt, 385. White, or Zinc, 284. Uranium, 386. Vitriol ochre, 388. Vitriolbleierz, 370.

Vivianite, 415.

Voglite, 462.

i

GENERAL INDEX.

Völknerite, 134.
Volborthite, 362.
Volcanite glass, 248.
Volcanite, v. Selensulphur.
Volgerite, 142, 513.
Voltaite, 383.
Voltzite, Voltzine, 127.
Voraulite, 404.
Vosgite, 238.
Vulpinite, 369.

Wacke, 247. Wad, 136. Wagnerite, 403. Walchowite, 469. Walmstedtite, v. Breunner

ite.
Warwickite, 395.
Washingtonite, 115.
Wasserblei, 66.
Wasserglimmer, 223.
Wasserkies, 61.
Water, 110.
Wavellite, 423.
Websterite, 389.
Wehrlite, 263.
Weichbraunstein, 125.
Weicheisenkies, v. Wasser

kies. Weichmangan, 125. Weissbleierz, 452. Weissgültigerz, 82. Weissian, v. Scolecite. Weissigite, 254, 513. Weissite, 215. Weisskupfererz, 86, 60. Weissnickelkies, 56, 61. Weisspiessglanzerz, 140. Weissstein, 246. Weisstellur, 64. Wernerite, 201. Wheel-ore, 80. Whewellite, 464. White antimony, 140. arsenic, 139. copperas, 380. iron pyrites, 60. lead ore, 452. tellurium, 64.

vitriol, 384.
Wichtine, Wichtisite, 177.
Wiesenerz, v. Bog iron ore,
181.
Wilhelmite, 189.

Wilhelmite, 189. Willemite, 189. Williamsite, 284. Wilsonite, 502. Wiluite, 191, 197. Wiserite, 447

Wismuth, Gediegen, 20.

Wismuthbleierz, 16. Wismuthglanz, 33. Wismuthochre, 141. Wismuthoxyd, Kolens., 462. Wismuthsilber, 16. Wismuthspath, 462. Withamite, 206. Witherite, 449. Wittichite, 88. Wittingite, 169.
Wodankies, v. Gersdorffite. Zinc, Wærthite, 265. Wöhlerite, 343, 513. Wolchite, 82. Wolchonskoite, 339, 513. Wolfram, 351. Wolframine, 143. Wolframbleierz, 848. Wolframochre, 148. Wolfsbergite, 73. Wollastonite, 156. Wood, petrified, 148. Wood-opal, 152. Würfelerz, 422. Wulfenite, 349. Wundererde, v. Teratolite.

Xanthocone, 87.
Xanthophyllite, 297.
Xanthorthit, 209.
Xanthosiderite, 138.
Xenolite, 265.
Xenotime, 401.
Xylite, Xylotile, 285.
Xylochlore, 805.
Xylokryptit,v. Scheererite!

Xanthite, 197.

Yanolite, 213.
Y ellow copperas, 387.
copper ore, 68.
lead ore, 349.
tellurium, 64.
Yenite, 262.
Ytterbite, 211.
Yttererde, Phosph. 401.
Ytterspath, 401.
Yttria, Phosphate 401.
Tantalate, 399.
Silicate, 255.
Yttrocerite, 95.
Yttroclumbite, 359.
Yttroilmenite, 355.
Ytrro-tantalite, 359.

Zala, 894. Zengonite, 822. Zeasite, v. Opal. Zeilanit, 108.

Yttro-titanite, 841.

Zellkies, 60.
Zeolite, Feather. 327, 328.
Foliated, 330, 332.
Efflorescing, 307.
Needle, 327, 328.
Pyramidal, 304.
Zeuxite, 270.
Zianite, v. Kyanite.
Ziegelerz, 101.
Zigueline, 101.
Zine.

Arsenate, 418.
Carbonate, 447, 460.
hydraté cuprifére, 426.
lodid and Bromid, 97.
oxidé, 110.
oxidé silicifère, 189.
Oxysulphuret, 127.
Phosphate, 409.
Red oxyd, 110.
Silicate, 156, 189.
Silicious oxyd, 189,813.
sulfaté, 884.
sulfuré, 45.
Sulpharet, 45.
te blende, 45.

Zinc blende, 45. Zinc bloom, 460, 518. Zincfahlerz, 85. Zinc vitriol, 884. Zinc ore, Red, 110. Zincite, 110. Zinconise, 460. Zinkarseniat, 418. Zinkblüthe, 460. Zinkenite, 74. Zinkglas, 818. Zinkkieselerz, 818. Zinkoxyd, 110. Zinkphyllit, 409. Zinkspath, 447. Zinkvitriol, 884. Zinn, 19. Zimperz, 118. Zinnkies, 70. Zinnober, 48. Zinnstein, 118. Zinnwaldite, 227. Zippeite, 461. Zircon, 195. Zirconite, 195. Zoisite, 211, 206. Zölestein, 868. Zootinsalz, v. Nitratina Zorgite, 42. Zundererz, 76.

Zurlite, 205.

Zwieselite, 399.

Zygadite, 254.

ERRATA AND ADDENDA.

```
VOL. I. p. 7, add after l. 1, "Number I, being the first part, of the third edition of Prof. C. U. Shepard's Treatise on Mineralogy (1852)."
p. 75, 4th l. fr. top, for ma tan ½Zν½, read ma=tan ½Zν½.
p. 87, 17th l, fr. top, for a: b=sin μ: sin ν, read a: b=sin ν: sin μ.
p. 92, 8th l, fr. top, for Monoclinic System, read Monometric System.

VOL. II. p. 82, in f. 270A, for the lower 11 (to right), read it, and for 11, below this.
                        read l'L
                p. 44, under Grunauite, add, Streak dark gray.
                p. 80, 4th l. fr. top, for Antimonie read Antimoine.
                p. 100, 3d l. fr. top, dele Chalcotrichite.
p. 140, in f. 334, 1i should be 1k.
p. 153, 6th l. fr. bottom, for Columbates, Niobates, read Tantalates
                        COLUMBATES.
                p. 156, 12th l. fr. bottom, for 2i read 2i.
p. 188, 17th l. fr. top, in part of edition, for 1:, read 1: $.
                p. 242, 28d l. fr. top, for Sunadin, read Sanidin.
p. 261, in f. 461, for ii, read ii.
p. 309, 3d l. fr. bottom, for 18, read 118.
                p. 816, under Savite, 9: 9: 26; 2, should be 9: 9: 26: 6; and 9: 9: 25: 2, should be 9: 9: 25: 8.
                p. 382, 17th l. fr. bottom, dele all of paragraph after "silica."
p. 343, To description of Mosandrite, add, Occurs with Albite and viole
                        fluor at Brevig.
                p. 845, To Pyrochlore, add, Streak light-brown to yellow.
               p. 851, at top, for Columbate, read Tantalate.
p. 413, 22d l fr. top, for i2, read i3.
p. 419, 12th l fr. top, for i2, read i3.
                p. 448, 15th l. fr. top, for Eisenbluth, read Eisenblüthe.
                p. 450, 12th l. fr. bottom, for 4 read 1.
```

p. 452, to description of Manganocalcite, add, From Schemnitz.









LANTHANITE, Haid. Carbonate of Cerium. Carbocérine, Bendant. Cakohlensaures, Berz., Ramm.

Trimetric. $I: I=93^{\circ} 30'-94^{\circ}$, Blake. In thin four plates or minute tables, with beveled edges, as in the annexe ures. Also fine granular or earthy.





H.=2.5—3. G.=2.666, (1) Blake. Lustre dull or 1 Color grayish-white, faint pink, or yellowish.

Composition.—LaC+3H=Lanthana 52.24, carbonic acid 21.11, water Analysis by J. L. Smith, of American specimen, (Am. J. Sci., [2], xvi, 230):

La (with ox. didymium) 54.90 C 22.58 H 24.09=101.57.

Blake obtained, La 54-27, 54-98, 54-64. C 19-13, C+H (by ign.) 45-07, 451 Hisinger found in a Swedish specimen, probably impure, La 75-7, C 10-8, whence the formula La C+3H.

B.B. infusible; but whitens and becomes opaque, silvery and brownis borax, a glass slightly bluish, reddish, or amethystine on cooling; w of phosphorus, a glass bluish amethystine while hot, red cold, the bead b opaque when but slightly heated and retaining a pink color. Effervesce side.

acids. In a matrass affords water.

Found coating cerite at Bastnäs, Sweden; also in silurian limestone v zinc ores of the Saucon valley, Lehigh Co., Pa., in masses consisting of agg minute tables.

HYDROMAGNESITE, Kobell. Hydrocarbonate of Magnesia, Thomson. terite, in part, Silliman.



Monoclinic. $C=82^{\circ}-83^{\circ}$, $I:I=87^{\circ}$ 88° , O:2i=137; a:b:c=(nearly)0.45 1.0973. Observed planes as in the annex ure. $22:-22:(\text{adj.})=143\frac{1}{2}^{\circ}$ to 145° , $ii:113\frac{1}{2}^{\circ}$ to 112° , $ii:-22=105^{\circ}$. Culminant between edges y, y (or 2i:2i)= 94° , edge edge y (or ii:2i)= 133° . Crystals small ally accoular or bladed, and tufted. amorphous, or as chalky crusts.

H. of crystals 3.5. G.=2.145—2.18, and Brush. Lustre vitreous to silky or pearly; also earthy. Color and streak Brittle.

Composition.—Mg*C*+4H, or 3(MgC+H)+MgH=Magnesia 43.9, carbonic acid 36.3, water 19.8=100. Analyses: 1, Waltershausen, (K. V. Ac. H. 1827, 17); 2, Kobell, (J. f. pr. Ch. iv, 80); 3, 4, Smith and Brush, of crystalline varieties, (Am. J. Sci. [2], xv, 214):

C Mg H Si 36.82 42.41 18.53 0.57 Fe 0.27, earthy matter 1.39 1. Hoboken, 99.99, Walt.

Negroponte, 36.00 43.96 Texas, Pa., Wood's Mine, 36.69 43.20 36.00 43.96 19.68 0.36=100, Kobell. 19.48 - Fe and Mn tr.=99-72, S. & B. Low's Mine, 36-74 42-30 20.10 " tr.=99.14.

B.B. infusible; yields moisture, and finally becomes pure magnesia. Effervesces and dissolves in acids.

Occurs at Hrubschitz, in Moravia in serpentine; in Negroponte near Kumi; in the United States, crystallized with serpentine and brucite, near Texas, Lancaster Co., Penn., at Wood's and Low's mines; also in a similar way at Hoboken, N. J., in account crystals like natrolite; at the latter place in earthy crusts. The Brucite of Hoboken sometimes changes on exposure to an earthy hydromagnesite.

The above angles and figure were taken by the author from a crystal one-fiftieth of an inch broad, in which the summit planes were smooth and brilliant, the prismatic striated. The rhombic prism in one crystal gave the angles 95° 20' and 84° 50'; but other crystals gave different results, and no constant value was obtained. The species is isomorphous with Wollastonite, (p. 156).

The Lancasterite of Silliman, (Am. J. Sci. [2], ix, 226), is shown by Smith and Brush to be a mixture of Brucite and Hydromagnesite.

Hydrodolomite. (Dolomite sinter, Kobell, J. pr. Ch. xxxvi, 304, Hydromagnocalcit, Ramm.) A hydromagnesite having part of the magnesia replaced by lime. Occurs in sinter-like globular or stalactitic masses yellowish and white, and earthy. Composition, 3[(Mg, Ca)C+H]+MgH, Ramm. Kobell obtained, Lime 25-22, magnesia 24-28, carbonic acid 33-10, water 17-40=100. From Somma, in isolated masses.

PREDAZZITE, Petzholdt. A kind of bitter spar mixed with Brucite, from Predazzo in the Southern Tyrol. H.=3.5. G.=2.634. J. Roth obtained, (J. f. pr. Chem. lii, 346):

Č Ča Mg Fe, Xl Ši 1. 27.45 33.53 23.27 2.88 3.28 2. 33.35 46.67 14.54 0.48 Ča Ĥ 3.28 10.26=100.67. 6.96=100.

Analysis 1, corresponds to Ca C+MgH; 2, to 2CaC+MgH. Brucite occurs in plates in the Predazzite, and hence the water.

Pennite of Hermann (Hydronickelmagnesite of Shepard) is a carbonate of lime and magnesia, containing two per cent. or less of carbonate of nickel, with some water. It occurs in incrustations having a surface of minute spherules; color pale green to whitish. Hermann obtained C 44.54, Ca 20.10, Mg 27.02, Ni 1.25, Fe 0.70, Mn 0.40, Al 0.15, H 5.84=100. Occurs with emerald nickel, into which it graduates, and also with chromic iron, at Texas, Lancaster Co., Pa.; and according to Mr. Heddle, at Swinaness in Unst, Shetland.

HYDROCALCITE. Hydrous Carbonate of Lime, Scheerer, Ann. der Ph. u. Ch. lxviii, 381. Hydrokonit, Haus.

In small rhombohedral crystals, and forming an incrustation on wood under

Composition.—CaC+5H=Carbonate of lime 52.4, and water 47.6. Exposed to the air, the water passes off and it becomes anhydrous. The crystals contain one per cent. of organic matter. By the action of absolute alcohol, it loses two equivalents of water.

A blue limestone from Vesuvius analyzed by Klaproth, (Beit. v, 91), has the formula 2CaC+CaH, consisting of Lime 58 00, carbonic acid 28 50, water 11 00,

earthy impurities 2.25=99.75.

MALACHITE. Green Carbonate of Copper. Cui Green. Atlaser



Monoclinic; C= Observed planes as sometimes ii. I: basal, highly perfectinct. Twins: plane massive or incrusti botryoidal, or stalac ent; often delicat banded in color; fre

H.=3:5-4. G. mantine, inclining

often silky; often d green. Streak paler green. Translucen Fracture subconchoidal, uneven.

Composition.—Cu²C+H=Carbonic acid 19²9, Analyses: 1, Klaproth, (Beit. ii, 287); 2, Vau Phillips, (Jour. Royal Inst. iv, 276):

1. 0 180 Ču 70.5 H11: 70.10 2 21.25 72.2 3. 18:5

B.B. like Azurite,

B.B. like Azurite.

Green malachite usually accompanies the other are quite rare. The fibrous variety occurs at France, in the old mine at Sandlodge, in at Schwartz in the Tyrol; also in Cornwa occur at Grimberg, near Siegen in Germany.

Tagilsk, belonging to M. Demidoff, a bed of many tons of malachite; one mass measured at uncovered contained at least half a million publing agree masses on the west coast of Africa. handsome masses on the west coast of Africa.

Neat specimens occur with vitreous copper at omines, and still better at New Brunswick, New Taneytown, Md., east of the Monocacey; also i the Blue Ridge, in Pennsylvania, near Nicholson County, Penn., in good specimens; at the Perk and at the copper mines of Wisconsin; at Miner Green malachite admits of a high polish, at

tables, snuff boxes, vases, &c.

Mysorin, -Massive. G .= 2.62. Soft. Color b

Composition, according to Thomson, (Min. i, copper 60.75, peroxyd of iron (mechanically Gives no water in a glass tube. Occurs at Mys pure malachite.

LIME-MALACHITE. (Kalk-malachit, Zincken structure fibrous and foliated.

H=2.5. Lustre silky. Color verdigris-gree From Zincken's trials it is a hydrous carbona and sulphate of lime and iron. From Lauterber

AZURITE, Bend. Blue Copper. Blue Carbonate of Copper. Blue Malachite. Chessy Copper. Kupferlasur, W. Chessylite, B. and M. Lasurite, Haid.

Monoclinic. $C=87^{\circ}$ 39'; $I: I=99^{\circ}$ 32', $O: 1i=138^{\circ}$ 41'; a: b: c=1.039: 1: 1.181.

```
0: I = 91^{\circ} 48'
           O● ii=92° 21′.
7
          0:1i=132^{\circ}43'.
          0:1=125^{\circ} 8'.
          O: 2=108^{\circ} 35'
          O: -1 = 127^{\circ} 28'.
          1:1 (front)=116° 7'.
          -1:-1 " =118° 16'.
          ii: 1i=134° 56'.
          ii: 1i=115^{\circ} 35'.
          1i : \bar{1}i \text{ (bas.)} = 82^{\circ} 38'.
          2i: 2i \text{ (bas.)} = 120^{\circ} 46'.
          i2:i2=134^{\circ}8'.
          i3: i3=121° 10'.
          i_2^5:i_2^5=118^\circ\ 50'.
          ii: 2i=153^{\circ} 51'.
```


 $ii: I=139^{\circ} 46'$

					22		1 3 1
				3			31
						28	
					42		
11				i			li
					$\frac{4}{3}$ 2		
2i		22		2	107		28
	44				42		
ii		12	$i\frac{3}{2}$	I	12		ii
2i				-2	-22		
					$-\frac{4}{3}\hat{2}$		
-1 <i>i</i>	1			-1			

Observed Planes. Add $\frac{1}{8}i, \frac{1}{6}i, \frac{1}{2}i, \frac{3}{2}i, \frac{3}{6}i, -\frac{1}{2}i$.

Cleavage: 2i rather perfect; ii less distinct, I in traces. Also massive and presenting imitative shapes, having a columnar composition; also dull and earthy.

H.=3·5—4·25. G.=3·5—3·831. Lustre vitreous, almost adamantine. Color various shades of azure-blue, passing into Berlin-blue. Streak blue, lighter



than the color. Transparent—subtranslucent. Fracture conchoidal. Brittle.

Composition.—2ĈuĈ+ĈuĤ [=(Ĉu,Ĥ)²Ĉ]=Carbonic acid 25.6, protoxyd of copper 69.2, water 5.2. Analyses: 1, Phillips, (Jour. Roy. Institution, iv, 276); 2, Venquelin, (Ann. du Mus. xx, 1):

H 5:46=100, Phillips. 6:5=Vauquelin.

In a matrass yields water and blackens. B.B. on charcoal fuses, and affords a globule of copper, and in the forceps the flame is green. Borax is colored green. It dissolves with effervescence in the acids, and also in ammonia.

Azurite occurs in splendid crystallizations, at Chessy, near Lyons, whence it derived the name Chessy Copper. It also occurs in fine crystals in Siberia; at Moldawa, in the Bannat; at Wheal Buller, near Redruth, in Cornwall; at Porto Cabello, S. A.; also in small quantities at Alston Moor, and Wanlockhead, &c.

Cabello, S. A.; also in small quantities at Alston Moor, and Wanlockhead, &c.
This mineral occurs in indifferent specimens at the Perkiomen lead mine, acceciated with galena, blende, and white lead ore; also near Nicholson's gap, in the

Blue Ridge, Penn., and near Sing Sing, N. Y.; near New Brunswick, crystals coating red shale at Cornwall, Pa.

When abundant, azurite is a valuable ore of copper.

When ground to a

When abundant, azurite is a valuable ore of copper. When ground to a pable powder, it forms a blue paint of a bright tint; but it is of little valuable, on account of its liability to turn green.

ALTERED FORMS,—Azurite occurs altered to Malachite, through the ad-

AURICHALCITE, Böttger, Pogg. xlviii, 495. Green Calamine, Pat

In acicular crystals forming drusy incrustations; also col and granular; also laminated.

H.=2. Lustre pearly. Color verdigris-green. Trans

Composition.—2(Zn, Cu) C+8 (Zn, Cu) Ĥ, G. Rose=Oxyd of copper 29 of zinc 447, carbonic acid 162, water 99. Analyses: 1, 2, Böttger, (loc. Connel:

	Zn	Ou	Ca	σ	H
1. Altai,	45.889	28.192		16 056	9-951=100-057, Bi
2 "	45.620	28.857		16-077	9-938== 99-987, Bi
8. Matlock.	42.7	82.5	trace	27	5 =102.07. Con

B.B. in a matrass gives out water, which has neither acid nor alkaline; and the green crystals become brownish-black. In the outer flame, the becomes darker, but it does not fuse; in the reduction flame, forms a slag melting, yellow while hot, and white on cooling. With borax and salt of parts, intumesces and affords a green glass. With equal quantities of soda as becomes reduced, affording a globule of copper in a slag of zinc oxyd. Somuriatic acid with effervescence.

Aurichalcite occurs at Loktefskoi, at a copper mine of the Altai, where it ciated with calc spar and brown iron ore, sometimes forming a drusy coverithese minerals; also near Kleopinski, (Patrin's green calamine), in cavi Retzbanya in Hungary; also at Matlock, in Derbyshire, of a pale-gree laminated structure and pearly lustre, and at Roughten-Gill in Cumberland.

BURATITE, Delesse, Ann. Ch. Phys. 3d ser. xviii, 478.

In radiated account crystals or plumose aggregations. Color verdigr. G.=3.32.

Composition.—(½2n+½0u+½0a)* 0+ft. Perhaps a mechanical mixture, being carbonate of lime. Analysis by Delesse, (loc. cit.):

C 21 45, Zn 32 02, Cu 29 46, Ca 8 62, H 8 45=10).

Associated with calamine at Loktefskoi in the Altai Mountains; said also at Chessy, near Lyons; at Campiglia in Tuscany; Framont in Tyrol. related to aurichalcite and probably the same species. The Chessy ore C 19 88, Zn 41 19, Cu 29, Ca 2 16, H 7 62=99 85.

ZINC BLOOM, Smithson. Dicarbonate of Zinc. Zinconise, Bend. Zin.

Earthy incrustations, and reniform.

II.=2-2.5. G.=3.58-3.6. Lustre dull. Color white ish or yellowish. Streak shining. Opaque.

Composition.—Zn³ C+8H or Zn C+Zn² H²=Carbonic acid 12.89, oxyd 71.28, water 15.83. Analysis by Smithson, (loc cit.), C 18.50, Zn 69.38, H .97.98.

EMERALD NICKEL, Silliman, Jr.

Incrusting, and often small stalactitic or minute mammillary, and sometimes appearing prismatic with rounded summits. Also massive, compact.

H.=3-3.25. G.=2.57-2.693. Lustre vitreous. Color emerald-green; streak paler. Transparent-translucent. Brittle.

Composition.—Ni³ C+6H(or Ni C+2Ni H²)=Carbonic acid 11.66, oxyd of nickel 59.72, water 28.62; often containing magnesis in place of part of the oxyd of nickel. Analyses: 1, B. Silliman, Jr., (Am. J. Sci. [2], vi, 248); 2, Smith and Brush, (ib. xvi, 52):

> Ni 58-811, C 11.691, H 29.498. 29.87, Mg 1.68. 56.82 11.63

In a matrass yields water, and loses color. With borax affords a transparent bead of a dark yellow or reddish color when hot, and nearly colorless when cold. In the inner flame the bead is gray from the presence of particles of metallic nickel. Dissolves easily with effervescence in heated dilute muriatic acid.

Occurs on chromic iron at Texas, Lancaster Co., Pa., associated with serpentine;

also at Swinaness in Unst, Shetland.

REMINGTONITE. J. C. Booth, Am. J. Sei. [2], xiv, 48.

A rose-colored incrustation, softy and earthy; opaque. Streak pale rose-colored.

Composition.—A hydrous carbonate of cobalt, but precise composition not ascertained. Dissolves in muriatic acid with a slight effervescence, making a green solution, the color due to iron. Cobalt reaction with borax.

Occurs as a coating on thin veins of serpentine, which traverse hornblende and

epidote, at a copper mine near Finksburg, Carroll Co., Maryland.

ZIPPEITE. Uranochre. Uranblüthe. Uraconise, Beud.

Earthy and pulverulent. Color sulphur-yellow, citron-yellow to brownish or reddish-yellow. Opaque.

Composition.-Probably & with water and some carbonic acid. It dissolves in acid, yielding a yellow solution, which affords a brown precipitate with prussiate of potash. Heated gently it becomes orange-yellow. In the reducing flame changes to green, but does not fuse.

Accompanies pitchblende in Cornwall, at Joachimstahl in Bohemia, and at Symphorien in France. At the Callington tin mine, Cornwall, it has been observed in masses of considerable size, which were said to be quite free from carbonic acid. It is found sparingly with columbite and uranite at the feldspar quarry near Middle-

LIEBIGITE, J. L. Smith, Am. J. Sci. [2], v, 336, and xi, 259.

In mammillary concretions, or thin coatings: cleavage apparent in one direction.

H.=2-2.5. Lustre of fracture vitreous. Color beautiful ap-

ple-green. Transparent.

town, Ct.

Composition.—€Ö+CaÖ+20H=Carbonic acid 11·1, oxyd of uranium 36·3, lime 7·1, water 45·5; or 2 CaÖ+€°C+36H, Ramm. =Č 9·02, € 39·12, Ca 7·67, H 44·19 =100. Analysis by J. L. Smith, (loc. cit.):

₩ 38.0, Òa 8.0 0 10.2, H 45-2

In. R. A. Smith obtained from a specimen from near Mathack, Chlori \$1754 cariorasts of real 4-215—49-199; and Rammelsberg from the set of the former, to 47-48 of the inter. Pogg laxar, 141, R.E. make readily to a vallow giobule, which an osciling becomes white talling. On charotal lead is obtained. Dissalves with effect weapones in at At Crawford, near Mathack, in Derbyshire, where some of the crystals or three inches long: very rare in Cornwall; in minute crystals at a loser Eight is Southand. Some crystals recently obtained at Crawford, so teen to twenty pounds sterling each.

VIL OXALATES.

WHENELLITE

GIALITE.

2fe €+3fL

CASSIVATION

Ca E+7AL

WHEWELLITE, B. and M. Oxalate of Lime, H. T. Brooke, Phil. Mag. 1 Oxacalcite, Shepard.



Monoclinic. $C=72^{\circ}$ 41', $I:I=100^{\circ}$ 3 $1i=127^{\circ}$ 25'; a:b:c=1.5745:1:1.1499served planes as in the annexed figure. (103° 14′, O: 1i=109° 28′, O: -1=141° ii=129° 42′. Cleavage parallel with Operfect parallel with I, and the longer dia All the planes bright except I and $\frac{1}{2}$, whi vertically striated. Twins: composition find H.=2.5-2.75. Lustre like sulphate of Very brittle. Fracture conchoidal.

This species, an Oxalate of lime, was observed by Brooke in crystals tenth to a fourth of an inch broad on calc spar; the locality of the spar is not

OXALITE, Haus. Oxalate of Iron. Humboldtine, Mariano de Rivero, Ant et de Ph. xviii, 207. Eisen-resin, Breithaupt.

In capillary forms; also botryoidal and in plates, or ea structure fibrous or compact.

H.=2. $G.=2\cdot13-2\cdot489.$ Dull or slightly resinous. yellow. Fracture uneven, earthy. Acquires negative elec by friction, when insulated.

Composition.—2FeC+3H=Protoxyd of iron 41 40, oxalic acid 42 69, wat = 100. Analysis by Rammelsberg, (Pogg. xlvi, 283):

Fe 41·18, Oxalic acid 42.40, (loss) 16·47=100. Mariano de Rivero obtained, Oxalic acid 46:14, and protoxyd of iron 53:36 melaherg (Pogg. liii, 631, 1841) has confirmed his former analysis and sho the iron is all protoxyd.

OXALATES. 465

Blackens in the flame of a candle, and becomes attractable by the magnet. B.B. on charcoal yields a vegetable odor, and is decomposed, becoming at first yellow, then black, and finally red.

It occurs at Kolosoruk, in Bohemia, and in the opinion of Rivero, has resulted from the decomposition of succulent plants; also in brown coal at Gross-Almerode, in Hessia; and according to T. S. Hunt, at C. Ipperwash, Canada, in shales; soft, earthy, sulphur yellow, (Logan's Report, 1850).

CONISTONITE, R. P. Greg, Jr., Am. J. Sci. [2], xvii, 838, 440, 1854.

Trimetric. Observed angles, (Greg): $I: I = 97^{\circ} 5'$, 1i: 1i (top) = $96^{\circ} 30'$, 1i: 1i (top) = $96^{\circ} 50'$, $I: 1i = 117^{\circ} 30'$, $1i: 1i = 121^{\circ} 0'$. Faces I brightest. Cleavage none.

II.=2. G.=2.052. Lustre vitreous. Colorless. Transparent to translucent. Slightly sectile. Fracture small conchoidal, uneven.

Composition.—Ca C+7H, M. F. Heddle, who obtained in his analysis, Oxalic acid 28-017, lime 21-055, soda and magnesia 0-822, water 49-155=99-049. Soluble without effervescence in muristic or nitric acid. Heated gives off wa-

Soluble without effervescence in muriatic or nitric acid. Heated gives off water and carbonic oxyd, and is converted into a carbonate, and then effervesces with acids.

From the copper mine near Coniston in Cumberland. Largest crystals not more than one-eighth of an inch across, and in general form not unlike the double four-sided crystals of Edingtonite.

THIERSCHITE, Liebig, Ann. d. Ch. u. Pharm. lxxxvi, 118, April, 1858.

An oxalate of lime, occurring as a grayish, warty, and somewhat opaline incrustation, about a line thick, on the marble of the Parthenon, Athens. A complete analysis has not yet been made. Its origin is attributed to the action of some kind of vegetation on the marble. It is probably identical with whewellite.

It is used in the manufacture of a varnish, and for obtaining succinic acid and oil of amber, which it affords at a low temperature.

COPALINE, Hausmann. Fossil Copal, Highgate Resin, Aikin, Jameson.

Like the resin Copal in hardness, color, lustre, transparency, and difficult solubility in alcohol. Emits a resinous odor when broken.

Composition. - C40 H22 O. Analysis by Johnston, (Phil. Mag. xiv, 87, 1839): Carbon 85.408. Hydrogen 11 787, Oxygen 2.669, Ashes 0.136=100. Volatilizes in the air by a gentle heat, and burns easily with a yellow flame and much smoke. Slightly acted upon by alcohol.

Comes from the blue clay of Highgate Hill, near London, from whence it is call-

ed Highgate resin.

Another resin, resembling the fossil copal in external appearance, has been examined by Johnston, and found to consist of Carbon 85'133, hydrogen 10'853, ashes 3'256=99'242, or nearly C'H'. It occurs in the form of flattened drops or coatings on calc spar, on the walls of a dyke of trap, at the old lead mine in Northumberland, called Settling Stones. Color pale yellow to deep red, with a pale green opalescence. G.=1'16-1'54. Hard, but brittle. Does not melt at 400° F., but burns in the flame of a candle with an empyreumatic odor. Insoluble in water and near-

A pale honey-yellow resin from the East Indies, is described by Kengott, (Min. Unters. ii, 81, 153). H.=2. Streak white. G.=1-053. Heated, fuses to a clear fluid, burns with a yellow light and aromatic smell, and is consumed without residue. But little soluble in alcohol, and largely in concentrated sulphuric acid. Duflos found it to contain C 85 73, H 11 50, O 2 77=100, or near the Highgate resin.

MIDDLETONITE, J. F. W. Johnston, Phil. Mag. xii, 261, 1838.

In rounded masses, seldom larger than a pea, or in layers a sixteenth of an inch or less in thickness, between layers of coal.

Brittle. G.=1.6. Lustre resinous. Color reddish-brown by reflected light, and deep red by transmitted; powder light-brown. Transparent in small fragments. No taste or smell. Blackens on

Composition.—C²⁰ H¹⁰+H O; Carbon 86 437, hydrogen 8 007, oxygen 5 563=100 007, Johnston. Not altered at 400° F., (210° C.); on a red cinder, burns like resin. Boiled in alcohol, ether, or oil of turpentine, the liquid becomes yellow, but dissolves only a mere trace of the resin. Softens and melts in boiling nitrie acid, with the emission of red fumes; a brown flocky precipitate falls on cooling. Soluble in cold concentrated sulphuric acid.

Occurs about the middle of the main coal or Haigh Moor seam, at the Middleton

collieries, near Leeds; also at Newcastle.

RETINITE. Retinasphaltum, Hatchett, Phil. Trans. 1804.

Occurs in roundish masses.

H.=1-2.5. G.=1.135, Hatchett. Lustre often earthy externally, but slightly resinous in the fracture. Color light vellowishbrown, sometimes green, yellow, red or striped. Subtransparent -opaque. Fracture conchoidal. Often flexible and elastic, when first dug up; but it loses this property on exposure.

Composition .- According to Hatchett, (Phil. Trans. 1804, p. 404):

Vegetable resin 55, Bitumen 41, Earthy matter 3=99,

Johnston, after drying it at 300° F., obtained, (Phil. Mag. xii, 560, 183 soluble in alcohol 59°32, insoluble organic matter 27°45, white ash 13°28 takes fire in a candle, and burns with a bright flame and fragrant odor. luble matter, heated in a tube, blackens and gives off an empyreumatic or red heat, it burns. The whole is soluble in alcohol, excepting an unctuo

luble matter, heated in a tube, blackens and gives off an empyreumatic or red heat, it burns. The whole is soluble in alcohol, excepting an unctuor This species was first observed near Devonshire, by Dr. Milles, according to the property of the property

A retinite from Halle afforded Bucholz, (Schweig. J. i, 290), 91 parts alcohol, and 9 parts insoluble.

SCLERETINITE, J. W. Mallet, (Phil. Mag. [4], 4, 261).

In small drops or tears, from the size of a pea to that of nut.

H.=3. G.=1·136. Translucent in thin splinters. Colo but by transmitted light reddish-brown; streak cinnamon Lustre between vitreous and resinous, rather brilliant. fracture conchoidal.

Composition .- Analyses by J. W. Mallet, (loc. cit.)

	Carbon	Hydrogen	Oxygen	Ash	
1.	76.74	8.86	10.72	3.68	
2.	77.15	9.05	10:12	3:68	

Affords the ratio C¹⁰H⁴O=Carbon 77.05, hydrogen 8.99, oxygen 10.28, Taking the number of atoms of carbon at 40, which exists in so many reformula becomes C⁴⁰H²⁸O⁴. It is nearest in composition to amber, which C⁴⁰H²²O⁴.

Heated in platinum foil, it swells up, burns like pitch, with a disagree pyreumatic smell, and a smoky flame, leaving a coal rather difficult to t finally a little gray ash. In a glass tube, yields a yellowish brown oily p a nauseous empyreumatic odor. Insoluble in water, alcohol, ether, ca carbonated alkalies or dilute acids; and even strong nitric acid acts slow! From the coal measures of Wigan, England.

GUYAQUILLITE, Johnston, Phil. Mag. xiii, 1838, 329.

Amorphous.

Yields easily to the knife, and may be rubbed to powder. 1.092. Color pale yellow. Lustre not resinous, or imperfe

Composition.—C²⁰H¹⁰O³; Carbon 76.665, hydrogen 8.174, oxygen 15.1 Johnston. Slightly soluble in water, and largely in alcohol, forming solution, which is intensely bitter. Begins to melt at 157° F., but does easily till near 212°. As it cools, becomes viscid, and may be drawn tenacious threads. Soluble in cold sulphuric acid, forming a dark reddisolution. A few drops of ammonia put into the alcoholic solution, darken and finally change it to a dark brownish-red.

It is said to form an extensive deposit near Guyaquil in South America. The Berengelite of Prof. Johnston is near Guyaquillite. Analysis: C 9:198, O 18:330=C 40H210. Forms a bitter solution with cold alcohol. C ration the resin obtained has a clear red color, and remains soft and visc ordinary temperature. Fracture and lustre resinous. Color dark brow tinge of green. Powder yellow. Odor resinous, disagreeable. Taste a lit It is said to form a lake like that of Trinidad, in the province of St. Juan is gela, about one hundred miles from Arica, Peru, and is used at Arica fo boats and yessels.

PIAUZITE, Haidinger, Pogg. Ann. lxii, 275.

An earthy resin of a brownish-black color, occurring massive. Streak yellowish-brown.

H.=1.5; G.=1.220.

Fuses at 315° C. (600° F.), and burns with an aromatic odor and much smoke, leaving 5°96 per cent. of ash. Soluble in ether and caustic potash, also largely in absolute alcohol. Heated in a glass tube a yellowish oily fluid is distilled, having an acid reaction.

From brown coal at Piauze near Neustadt in Carniola.

WALCHOWITE, Haidinger.

In yellow translucent masses, often striped with brown. Lustre resinous. Fracture conchoidal. Translucent to opaque. H.=1.5—2. G.=1.0—1.069; an opaque variety 1.035.

Composition.—C12 H°O, Schrötter, or 3C4H°+O, Ramm.=80.41 C, 10.66 H, 8.93 O. Fuses to a yellow oil at 250° C., and burns readily: becomes transparent and elastic at 140° C. Forms a dark brown solution in sulphuric acid; slightly soluble in ether.

In brown coal at Walchow, and formerly called Retinite. Boussingault found a similar mineral near Bucaramanga in New Grenada.

BITUMEN. Asphaltum. Petroleum. Mineral Pitch. Bergpech. Bergtheer, Haus. Mineral Oil. Naphtha. Erdöl. Steinöl. Maltha. Seneca Oil. Naphte, Beud.

Bitumen includes several distinct species, the two prominent of which are Naphtha and Asphaltum.

Narhtha, (Steinöl).—Liquid and colorless when pure, with a bituminous odor. G.=0.7—0.84. Composition.—C⁶ H⁵. In nature often combined with asphaltum, and containing also parraffine and other substances.

Asphaltum.—Solid; black and brownish-black, with a conchoidal brilliant fracture. G.=1-1.2. Odor bituminous. Fuses at 100° C., and burns with a bright flame. An asphaltum from the island of Brazza, Dalmatia, consists, according to Kersten, (J. f. pr. Chem. xxxv, 271), of petrolene (volatile oil) 50, brown resin soluble in ether 20.0, asphaltene (bitumen insoluble in alcohol and ether) 74.0, yellow resin soluble in alcohol 1.0=100.0

There are also earthy varieties, called earthy and slaggy mineral pitch. Petroleum is a dark-colored fluid variety, containing much naphtha. Maltha or Mineral tar is a more viscid variety.

Asphaltum is abundant on the shores of the Dead Sca. It occurs also in reniform stalactitic masses at Matlock in Derbyshire; in granite, with quartz and fluor, at Poldice, in Cornwall; in cavities of chalcedony and cale spar, in Russia, and other places. Naphtha issues from the earth in large quantities in Persia and the Birman empire; at Rangoon there are upwards of five hundred naphtha wells, which afford annually 412,000 hhds. A remarkable lake of bitumen occurs on Trinidad, which is one and a half miles in circumference. The bitumen is solid and cold near the shores, but gradually increases in temperature and softness towards the centre, where it is boiling. The solidified bitumen appears as if it had cooled as the surface boiled in large bubbles. The ascent to the lake from the sea, a distance of three quarters of a mile, is covered with a hardened pitch, on which trees and vegetables flourish, and about Point La Braye the masses of pitch look like black rocks among the foliage. The lake is underlaid by a bed of mineral coal, (Manross).

In the peninsula of Apcheron, on the western shore of the Caspi rises in vapor through a marly soil, and is collected by sinking pits so in depth, into which the naphtha flows. Near Amians in the state of abundant spring. Near Alfreton, England, naphtha has been discovery Petroleum is met with at Kenhawa in Virginia, Scotsville, Ky., (Venango Co., Penn., Duck Creek, in Monroe Co., Ohio, and Liverpool, (formerly collected and sold by the Seneca and other Indians, and is

Seneca or Genesee oil. Also at Inniskillan, Canada West, the inspissate

Seaces of Genezee oil. Also at Inniskillan, Canada west, the Inspessace in some places is two feet deep. (Logan's Geol. Rep. 1852, 90.)

Naphtha affords both fuel and lights to the inhabitants of Badku, on It is also employed in Persia and the Burman empire as a lotion is eruptions, and as an embrocation in bruises and rheumatic affection ployed for various purposes in the arts, particularly in the manufactur and as a substitute for oil in the formation of oil paint, it being preferred of its rapid evaporation and drying.

Bitumen, in all its varieties, was well known to the ancients. It is have been employed in the construction of the walls of Babylon, and nave been employed in the construction of the waits of Babylou, and tum it was burnt in lamps, and called Sicilian oil. The Egyptians also it in enbalming. Two ship loads of the Trinidad pitch were sent to Admiral Cochrane, but it was found that the oil required to render i exceeded in expense the cost of pitch in England, and the project of was therefore abandoned.

Asphaltum is a constituent of the kind of varnish called Japan ; it into a cement for lining cisterns, and with ground stone into a mater ments.

Naphthodil. A substance derived from naphtha. It is black; weak, g copper-brown in fracture. Does not change in the light. Fuses at the perature as wax, and burns with a clear flame, (Von Leonh. J. 1846, 8

IDRIALINE. Idrialite, Schrötter, Nicol. Quecksilberbrande

Massive, with a greasy lustre, a grayish or brownish-bl and a blackish streak inclining to red. Opaque. H G.=1.4-1.6.

Composition.—According to Bödeeker, C 91 828, H 5-299, O 2-87; Min. Forsch. i, 253); formula C H H+O. The distillation of the bitus at Idria affords a product consisting of C 94 568, H 6-459, with the f which is the radical of the Idrialine. Insoluble in water, and little so i ether. Pases at 400° P.

Occurs mixed with einnabar at Idria. It is sometimes called, from bility, quecksilberbranders or inflammable cinnabar.

PYROPISSITE, Kengott, Min. Forsch., 1850, 1851, p. 148.

Like an earthy brown coal in appearance. G .= 0.49 Color dull yellowish brown, opaque. Streak shining an Feel greasy. Fracture earthy.

Burns readily with a brownish-yellow flame and a weak aromatic od-fuses to an asphaltum-like mass, which is porous, little soluble in alcoh-ly in oil of turpentine. Burns like bitumen. Little soluble in muriat acid, and largely so in sulphuric.

Forms a layer six to eight inches thick in brown coal near Weissenfe ing to Marchand, affords on distillation 62 per cent of paraffine, one I mans giving three cubic feet of illuminating gas.

BREWSTOLINE.

Fluid. Colorless. Transparent. Expands one-fourth its size by an increment of 30° F., or is nearly 32 times more expansible than water, by an increment of 30° of heat at the temperature of 50°.

Occurs in minute cavities in crystals of topaz, chrysoberyl, quartz crystals from Quebec, and amethyst from Siberia, where it was detected by Sir David Brewster.

We have thought proper to recognize this fluid among minerals and name it, although yet imperfectly described. The fluid expands with the heat of the hand. Its refractive power is less than that of water. It was sometimes indurated in the eavity like a resin. On exposure, the fluid undergoes quick motions and changes, and finally leaves a residue of minute particles, which from the moisture of the hand alone, suddenly became fluid again, and extended and contracted as before. This was indefinitely repeated. The residue is volatilized by heat, and dissolves in the acids without effervescence.

CRYPTOLINE.—A second fluid was also distinguished in the same crystals that contained the preceding, and often in the same cavities; yet they were not miscible, and remained distinct. On exposure it hardens speedily into a yellowish transparent resin-like substance, not volatilizable by heat, nor soluble in water or alcohol, but rapidly dissolving with effervescence in sulphuric acids. Nitric and muriatic acids also dissolve it. Refraction index nearly that of water. [See further Edinburgh Royal Trans. vol. x; also Am. J. Sci. xii, 214, 1827].

ELATERITE, Hausmann. Mineral Caoutchouc. Elastic bitumen. Elastisches Erdharz. Bitume elastique.

In soft flexible masses.

G.=0.9053-1.233, the Derbyshire variety. Lustre resinous. Color blackish-brown, of various shades. Subtranslucent; sometimes presents a brilliant dark orange-red color by transmitted light. Flexible or elastic.

Composition .- Analyses by Johnston, (Brewst. J. xiii, 22, 1-38):

Carbon, 85:474 84:085 83:671 Hydrogen, 13:253=98:757 12:576=96:061 12:505=96:216,

showing that it is probably allied to ozocerite and hatchettine. M. Henry (Ann. des M. vii, 260, found 2675 to 40710 per cent, of oxygen in his analyses, and the constant loss in Johnston is supposed by him to have been oxygen. Takes fire readily, and huma with a lively vellow flame giving out a hitunizous odor.

and burns with a lively yellow flame, giving out a bituminous odor.

This species was first observed in Derbyshire, at the forsaken lead mine of Odin, by Dr. Lister, in 1673, who called it a subterranean fungus. In 1797, it was accurately described by Hatchett, in the Linnsean Transactions, iv, 146. It has since been found in a coal mine at Montrelais, at the depth of 220 feet; and according to Hausmann, (Handbuch, ii), 273), it occurs at Neufchatel and on the island of Zante A similar material has been met with at Woodbury, 0.1.

SCHEERERITE, Stromeyer.

Monoclinic. In locaely aggregated crystalline grains and toling also in minute account crystals, deposited in small cavities in cont. Soft. G.=005, Macaire Prinsep. Lustre pearly or resinous, feebly shining. Color whitish or gray. Moreon has touche and Easily frangible. Tasteless. Incherons. Feel not greaty. At

111° F., (44° C.), according to M. Prinsep, it melts fused state resembles a fatty oil, and like it pent these spots however, may be removed by heat these spots, however, may be removed by heat. On these spots, however, may be removed acicular crystallizes in four-sided acicular crystallizes point is at 197½° F.

Composition.—According to Prinsep, (Pogg. Ann. xv, 294), Composition.—According to Prinsep, (Pogg. Ann. xv, 294), Composition.

Gen 24, nearly—C H². It takes fire easily, and is completely composite and a feeble aromatic odor.

It was found by Capt. Scheerer, in the year 1822, in a bed.

It was found by Capt. Scheerer, in Switzerland.

It was found by Capt. Scheerer, in 1842. 459).

Branchite, Sayi, (Leonh. and Bronn. 1842. 459).

Branchite, Savi, (Leonh. and Bronn, 1842, 459).

Stance resembling Scheererite, from the brown coal of Mount fuses at 75° C. (167° F.), but does not crystallize on coling in alcohol.

Tekoretin and Phylloretin, Forchammer, (J. f. pr. Ch. xx, 4 wood in Denmark.

Tekoretin is crystallized; it fuses at 45 wood in Denmark.

Tekoretin is crystallized; it fuses at 45 wood in Denmark.

Tekoretin is crystallized; it fuses at 45 wood in Denmark.

Tekoretin and Ch. xx, 4 wood in Denmark.

Tekoretin is crystallized; it fuses at 45 wood in Denmark.

Tekoretin and Phylloretin, Forchammer, (J. f. pr. Ch. xx, 4 wood in Denmark.) but little in alcohol, and consists of U 87 19, 11 12 81 20 1 86° -87° C. Dissolves easily in alcohol, and appears to 11°.

KÖNLITE, Schrötter, Pogg. Ann. lix

Resembles Scheererite. In white crystalli Soft. G.=0.88. Fuses at 114° C., Kraus, 107 Very slightly soluble in cold cleebel, more so Very slightly soluble in cold alcohol, more so

Composition.—C 92·429, H 7·571, Schrötter—C²H. K tained C 92·49, H 7·42, specimen from Uznach; and T xxi, 126), C 92·429, H 7·571, specimen from Redwitz, Bayari In brown coal at Uznach, and near Redwitz, Bayari so in ether.

FICHTELITE, Bromeis, Ann. der Pharm. xxxvi,

Resembles the preceding. Fuses readily crystalline on cooling.

Composition.—C 83.9, H 11.1=C4 H. Bromeis 304), obtained carbon 89.3, hydrogen 10.7. Occubing. ether. birge.

KÖNLEINITE, Kengott, Min. U

In thin plates, consisting of an aggregate of orthometric. Perfectly soluble in ether and addition of water becomes white and opaque, addition of alcohol. Wholly soluble in concernic and not at all in muriatic acid. Partly tine. From the brown coal of Fossa, in the

Composition.—According to Johnston, (Phil. Mag. xii, 338), Carb hydrogen 14.624=100.534. Melts at 115° F., (46° C.) Heated cautious over without change. Sparingly dissolves in boiling alcohol, and precip on cooling. Cold ether dissolves a small quantity, and hot ether more in solution on cooling coagulates into a mass of minutely pearly fibres, from

occurs with the iron ores of the coal measures in Glamorganshire; sitz in Moravia; H.=1; G.=0.892, Patera. A variety from Loch Fynerary, fuses at 117° F., (47° C.) Another allied mineral from Merthyr Ty

at 170° F., (76° 6, C.)

OZOCERITE. Ozokerit. Erdwachs, Ramm.

Like a resinous wax in consistency and translucency; sometimes foliated. Color brown or brownish-yellow mitted light; leek-green by reflected light. Odor please matic. G.=0.94-0.97.

Composition.—According to Magnus, Ann. d. Ch. et de Ph. lv); Schr Univ. 1886), and Johnston, (Phil. Mag. xii, 389, 1838):

Moldavia. Moldavia. Hydrogen, 15.15 8575=100.90, M. 86.204=99.991, S. 86.80=10 Carbon,

Fuses at 62° C., (144° F.), Schrötter, 84° C., (188° F.), Malaguti. and bo C., Schrötter, 300° C., Malaguti. According to Johnston a variety from ear Newcastle, fuses at 60° C., (140° F.), and boils at 121° C. Distills a parent decomposition. No change in the strong acids, and very little centrated alcohol. The Moldavia ozocerite dissolves but slightly in a that from Urpeth dissolves about four-fifth of the whole, which it decomposition is because deals that really 100° E.

evaporation, in brown flocks, that melt at 102° F. to a yellowish-bro
Three or four substances are supposed to be here included.

Ozocerite was discovered by Meyer in a sandstone in Moldavia, in to
of coal and rock salt. It also occurs in Austria at Gresten near Gamin
Truskawicz in Galicia, (a variety fusing at 52° C., and boiling at 300° C.

the Urpeth colliery, Newcastle-on-Tyne, England.

CHRISMATINE, Germar. Leonb. u. Bronn's Jahrb, 1851, 353

Color oil-green to yellowish. Shining. Translucent translucent. Unchanged at 68 to 78° F., but softens a

Burns with flame without smell. Near Ozocerite. From a red argillaceous sandstone of the coal formation at Wettin ner

DOPPLERITE.

In thin plates or massive. When fresh, brownish-black dull brown streak and greasy subvitreous lustre; and whe plates, reddish-brown by transmitted light. G.=1-089. elastic on exposure to the light.

Composition.—C* H*O*. According to Schrötter, a homogeneous peat from whose cellulose, two parts of water are removed. Analysis by (Wien. Acad. Ber. 1849, 285):

> H 5.34 0 43 03.

Heated to 100° C., loses 78.5° per cent. of water. It resembles a black pitch. On heating the fresh mineral with potash, ammonia is given off.

Near Aussee, in Styria, in peat. The species is named after M. Doppler.

DINITE, Meneghini, Gaz. Med. Italiana, Firenze, Toecana, July, 1852.

An aggregation or druse of crystals. Cleavage none. Has the appearance of ice, with a yellow tinge due to a foreign substance. Inodorous. Tasteless. Fragile, and easily reduced to powder.

Insoluble in water; little soluble in alcohol, very soluble in ether, and in sulphuret of carbon. The ethereal solution on standing deposits large crystals of the dinite. Fuses with the warmth of the hand; heated in a close vessel distills over without undergoing any sensible decomposition. When melted it looks like a yellowish oil; crystallizes in large transparent crystals on cooling.

From a lignite deposit, at Lunigiana, Tuscany, where it was found by Prof. Dini.

MELLITE, H. Mellilite. Honey Stone. Mellate of Alumina. Honigstein, Werner.

Dimetric; octahedral. Pyramidal edge=118° 4', and basal edge 93° 22', Hauy; the latter 93° 1', Breithaupt; 93° 6', Kupffer. In short octahedrons, and also with the terminal or lateral solid angles or edges truncated. Cleavage octahedral, very indistinct. Also in massive nodules.

H.=2-2.5. G.=1.55-1.65; 1.636-1.642, Kenngott. Lustre resinous, inclining to vitreous. Streak white. Color honey-yellow, often reddish or brownish; rarely white. Transparent-translucent. Fracture conchoidal. Sectile.

Composition. — Il H=+18H=Alumina 14.82, mellic acid 40.53, water 45.15. Analyees: 1, Klapreth, (Beit. iii, 114); 2, Wöhler, (Pogg. vii, 825):

> Alumina, 16 Mellic acid, 46 Water, 88=100 K. 44.1=100, W.

Whitens in the flame of a candle, but does not take fire. Dissolves in nitric soid; decomposed by boiling water. In a matrass yields water.

Occurs in brown coal at Arten in Thuringia; at Luschitz near Bilin in Bohemia; near Walchow in Moravia.

SUPPLEMENT.

CATALOGUE OF AMERICAN LOCALITIES OF MINER

THE following catalogue may aid the mineralogical tourist in selecting

and arranging the plan of his journey. Only important localities, afford specimens, are in general included. The list is an abstract of the fuller i with regard to localities, scattered through the Descriptive part of this For the facts included, the country is especially indebted to the Repo Shepard of the Connecticut survey, Profs. Beck, Emmons, and Mather, Muxem and Hall of New York, Prof. Hitchcock of the Massachusetts, Dr. the Maine, New Hampshire, and Rhode Island surveys, Prof. H. D. Rog New Jersey, Prof. W. B. Rogers of the Virginia survey, Profs. Troost and and Mr. Owen of the Western States, Prof. C. B. Adams of the Verme Prof. M. Tuomey of the South Carolina, Messrs. Foster and Whitney of Superior Region: some distinguished names among the State Geologis omitted, as their regions were not mineral regions. The American Jourence and Arts, and the Transactions of the various scientific societies of the second seco ence and Arts, and the Transactions of the various scientific societies of the various scientific societies of the various constributed essentially to this part of the work: and among the these Journals conspicuous in this department, in addition to the above of I would especially mention Messrs A. Bruce, P. Cleaveland, B. Silliman, G. Gibbs, C. Dewey, J. F. Dana, F. Hall, T. Nutall, H. H. Hayden, J. G. T. Bowen, D. Olmsted, H. Seybert, C. U. Shepard, S. Fowler, T. G. Delafield, J. Torrey, J. E. Teschemacher, C. B. Hayden, D. D. Owen of I Troost of Tennessee, O. P. Hubbard, B. Silliman, Jr., J. C. Booth, P. P. Finch, J. B. Crawe, J. Johnson, G. W. Benedict, J. Gebhard, J. D. Whith B. Hough. The author would also acknowledge here his indebtedness private communications in this department, especially from Prof. B. Si B. Hough. The author would also acknowledge here his indebtedness private communications in this department, especially from Prof. B. Si Messrs. J. E. Teschemacher, and C. T. Jackson, Boston; Thomas F. Seal S. Vaux, Philadelphia; L. White Williams, of Westchester, Pa.; Hon. T man, of North Carolina; D. Dale Owen and J. G. Norwood, of Ind F. A. Genth of Philadelphia, J. D. Whitney, and W. P. Blake. The Pe list is largely prepared from information furnished the author, mostly Williams and Seal; the Minesota and Wisconsin, through contributions

Williams and Seal; the Minesota and Wisconsin, through contributions Owen and Norwood; the North Carolina, from manuscript catalogue from the Hon. Mr. Clingman and Dr. Genth.

In the catalogue, the names of those minerals which are obtained specimens in the several localities, are distinguished by italics, specimens are remarkably good, an exclamation mark (!) is added, these marks (!!) when the specimens are quite unique. The more exact localities may in most instances be ascertained by reference to the describe appears in the preceding part of the Treatise. the species in the preceding part of the Treatise.

MAINE.

Mt. Abraham .- Andalusite, staurotide. Albany.—Beryl! green and black tourmaline, feldspar, rose quartz.
Albion.—Iron pyrites. ABCOSTOOK.—Red Hematite.
BINGHAM.—Massive pyrites, galena, blende, andalusite.
BLUE HILL BAY.—Arsenical iron, molybdenite! galena, apatite! fluor spar! black tourmaline, (Long Cove), black oxyd of manganese, (Osgood's farm), rhodonite, bog manganese, wolfram. Bowdoinham.—Beryl, molybdenite.

Brunswick.—Green mica, garnet! black tourmaline! molybdenite. Buckrield.—Garnet, (estates of Waterman and Lowe), iron ore. CAMDAGE FARM.—(Near the tide mills), molybdenite, (wolfram). CAMDEN.—Macle. CARMEL, (Penobecot Co.)-Gray Antimony. CORINNA. - Iron pyrites, arsenical pyrites. DEER ISLE —Serpentine, verd antique, abestus, diallage.

DEXTER.—Galena, pyrites, blende, copper pyrites, green talc. DIXFIELD.—Native copperas, graphite.
FARMINGTON.—(Norton's ledge), pyrites, graphite, bog ore.
GEORGETOWN.—(Parker's island), beryl! black tourmaline. GEORGETOWN.—(Parker's island), beryl! bl GREENWOOD.—Graphite, black manganese. HARTWELL.—Staurotide. LENOx.—Galena, pyromorphite. LEWISTON .- Garnet LITCHYIELD.—Sodalite, cancrinite, nepheline, zircon. LUBBO LEAD MINER.—Galena, copper pyrites, blende, pyromorphite, an ore of bismuth. MADRID. -Gold. NEWFIELD, (Bond's Mt.)-Mispickel, olive phosphate of iron in botryoidal masses. Paris. - Green ! red ! black, and blue tourmaline ! mica ! lepidolite ! feldspar, albite, quarts crystals ! rose quarts, blende. Parsonnerield.—Idocrase! yellow garnet, pargasite, adularia, scapolite, galena, blende, copper pyrites. ERRY.—Prehnite and calc spar, (above Loring's cove), quartz crystal, calc spar, analcime, apophyllite, agate, (Gin Cove). PERU.—Crystallized pyrites. PHISBURG.—Yellow garnet | manganesian garnet, idocrase, pargasite, axinite, laumonite | chabaxite, an ore of cerium? POLAND. - Idocrase. RAYMOND.—Magnetic iron, scapolite, pyroxene, lepidolite, tremolite, hornblende.
RUMFORD.—Yellow garnet, idocrase, pyroxene, apatite, scapolite, graphite.
Samford, York Co.—Idocrase! albite, calc spar, molybdenite, epidote. BEARSMONT. - Andalusite. STREAMED MOUNTAIN.—Beryl! black tourmaline, mica, garnet. THOMASTON.—Calc spar, tremolite, hornblende, sphene, arsenical iron, (Owl's head), black manganese, (Dodge's mountain). WARREN.-Galena, blende. WATERVILLE - Crystallized pyrites. WINDHAM, (near the bridge).—Staurotide, epodumene, garnet. WOODSTOCK, (New Brunswick).—Graphite, specular iron.

NEW HAMPSHIRE.

AGWORTH.—Beryl!! mica! tourmaline, feldspar, albite, rose quartz, columbite!
ALSTRAD.—Mica!! albite, black tourmaline.
AMMERIST.—Idocrase! yellow garnet, pargasite, cale spar.
BARTLETT.—Magnetic iron, specular iron, brown iron ore in large veins near
Jackson, (on "Bald face mountain"), quartz crystals, smoky quartz.

WHITE Mrs., (notch behind "old Crawford's house").—Green estabedral fluor, quartz crystals, black tourmaline, chiastolite.

WILMOT .- Beryl.

Winchester.—Pyrolusite, diallogite, psilomelane, magnetic iron ore, granular quartz.

VERMONT.

Addison,—Iron sand Alburgh — Quartz crystals on cale spar, iron pyrites. Athena.—Steatite, rhomb spar, actinolite. BARNET .- Graphite. BELVIDERE.-Steatite, chlorite. BENNINGTON.—Pyrolusite, brown iron ore, pipe clay, yellow ochre.

BETHEL—Actinolite! tale, chlorite, octahedral iron, rutile, brown spar in steatite. Brandon.—Braunite, pyrolusite, psilomelane, limonite, lignite, white clay, statuary marble; fossil fruits in the lignite. BRATTLEBOROUGH.—Black tourmaline in quartz. BRIDGEWATER.—Talc, dolomite, magnetic iron, steatite, chlorite, gold, native copper, blende, galena, blue spinel, copper pyrites.

BRISTOL.--Rutile, brown hematite, manganese ores. BROOKFIELD.—Mispickel, iron pyrites.
CABOT.—Garnets, staurotide, hornblende, albite. CASTLETON. - Roofing slate. CAVENDISH. -- Garnet, serpentine. CHESTER.—Asbestus. CHITTENDEN. -- Psilomelane, pyrolusite, brown iron ore, specular and magnetic iron, galena COLCHESTER.—Brown iron ore, iron sand, jasper, alum.
CORINTH.—Copper pyrites, (has been mined; magnetic iron pyrites.
COVENTRY.—Manganese spar. CRAFTEBURY .- Mica in concentric balls. Dummerston.—Rutile. FLETCHER.—Pyrites, octahedral iron, acicular tourmaline.
GRAFTON.—The steatite quarry referred to Grafton is properly in Athena. GUILFORD.—Scapolite. HARTFORD. -- Calcite, pyrites ! kyanite in mica slate. Inasburgh. -- Rhodonite, psilomelane. JAY .- Chromic iron, serpentine, picrosmine, amiauthua. LOWELL -Picrosmine, amianthus. MARLBORO.—Rhomb spar, steatite, garnet, magnetic iron. MENDON.—Octahedral Iron Ore. MIDDLEBURY.—Zircon. MIDDLESEX.—Rutile! (exhausted). MONKTON.—Pyrolusite, brown iron ore.

MOCKTOWN.—Smoky quartz | steatite, tale, wad, rutile. Morrierown.—Argentiferous galena.
Mount Holly.—Asbestus, chlorite. NEW FANE - Glassy and abestiform actinolite, steatite, green quarts, (called chrysophrase at the locality), chalcedony, drusy quartz, garnet, chromic iron, rhomb spar. NORWEL.—Actinolite, feldspar, brown spar in tale.

Pressure.—Brown iron ore, manganese ores. PLYMOUTH. - Spathic iron, magnetic and specular iron, both in octahedral crystals. PLYMPTON.—Massive hornblende. PUTREY .- Fluor, brown iron ore, rutile, and zoisite in boulders. READING .- Glassy actinolite in talc. READABORO'. - Glassy actinolite, steatite. Repress. - Brown iron ore, augite in boulders, octahedral iron pyrites. ROCHESTER.—Rutile, specular iron cryst., magnetic iron, in chlorite state.

ROXBURY.—Dolomite, tale, serpentine, asbestus.

SALIBBURY.—Brown iron ore.

SHABON. - Quartz crystals, kyanite.

SHOREHAM. - Iron pyrites.

Shrewsbury.—Magnetic iron and copper pyrites.
Somerser.—Magnetic iron, native gold.

Starrond.-Magnetic iron and copper pyrites, (has been worked), nati hornblende.

STARKSBORO'.-Brown iron ore.

STIBLING.—Copper pyrites, tale, serpentine. STOCKBRIDGE.—Mispickel, magnetic iron ore.

Turronn.—Blende, galena, kyanite; chrysolite in basalt.
Trov.—Magnetic iron, talc, serpentine, picrosmine, amianthus, steatite
southeast of village of South Troy, on the farm of Mr. Pierce, east side of chromic iron.

WARREN.—Actinolite, magnetic iron ore, wad. WATERBURY.—Mispickel, copper pyrites, rutile, quartz. WATERVILLE.—Steatite, actinolite, talc.

Wells River. - Graphite.

Westfield.—Steatite, chromic iron, serpentine. Westminster.—Zoisite in boulders. Wardsboro'.—Zoisite.

WINDHAM. - Glassy actinolite, steatite.

Woodbury. - Massive pyrites,

WOODSTOCK .- Quartz crystals.

MASSACHUSETTS.

Alford.—Galena, iron pyrites.
Athol.—Allanite, fibrolite, (1) epidote! babingtonite.

AUBURN. - Masonite.

Barre — Rutile ! mica, pyrites, beryl, feldspar, garnet. Great Barrington,—Tremolite.

BEDFORD. - Garnet.

Belchertown,—Allanite.
Bernandston,—Magnetic oxyd of iron.

Beverly.—Polymignyte, columbite, green feldspar, tin ore.
Blanford.—Marmolite, schiller spar, serpentine, anthophyllite, actimolite

iron, kyanite, rose quartz in boulders.

BOLTON. - Scapolite I petalite, sphene, pyroxene, nuttalite, diopside, bolton ite, apatite, magnesite, rhomb spar, allanite, yttrocerite, cerium ochre, (on

BoxBorough.-Scapolite, spinel, garnet, augite, actinolite, spatite.

BRIGHTON. - Asbestus.

Brimfield, (road leading to Warren).—Iolite, adularia, molybdenite, mic Carlisle.—Tourmaline, garnet! scapolite, actinolite.

CHARLESTOWN .- Prehnite, laumonite, stilbite, chabazite, quartz crystals CHELMSFORD.—Scapolite, chondrodite, blue spinet, amianthus ! rose quart CHESTER.—Hornblende, scapolite, zoisite, spodumene, indicolite, apatite-iron and chromic iron, (west part)—stilbite, healandite, smalehme and chr

CHESTERFIELD.—Blue, green, and red tourmaline, cleavelandite, (albite), his smoky quartz, microlite, spodumene, kyanite, apatite, rose beryi, garrecrystola, staurotide, tin ore, columbite, erubescite, zoisite, uranite, (eumanite).

CONWAY.—Pyrolusite, fluor spar, zoisite, rutile!! native alum, galena.
CUMMINGTON.—Rhodonite! cummingtonite (hornblende), white iron garnet.

Deduam.—Asbestus, galena.

Deersteld.—Chabazite, heulandite, stilbite, amethyst, carnelian, cha agate.

FITCHIBURG, (Pearl Hill).—Beryl, staurotide! garnets, molybdenite. Foxborough. - Iron pyrites, anthracite. Franklis. - Amethyst.

```
GOBHEN.—Lithia mica, albite, spodumene! blue and green tourmaline, beryl, zoisite.
  amoky quartz, columbite, tin ore, galena.
      GREENFIELD, (in sandstone quarry, half mile east of village).—Allophane, white
  and greenish.
      HATFIELD. - Heavy Spar, yellow quartz crystals, galena, blende, copper pyrites.
      HAWLEY. - Micaceous iron, massive pyrites, magnetic iron, zoisite.
      HEATH.—Pyrites, zoisite.
      HINSDALE - Brown iron ore, apatite, zoisite.
      HUBBARDSTON.—Massive pyrites.

LANGASTER.—Kyanite, chiastolite / apatite, staurotide, pinite, andalusite.
      LEE. - Tremolite | sphene | (east part).
     LENOX.—Brown hematite, gibbeite, (f)
LEVERETT.—Heavy spar, galena, blende, copper pyrites.
     LEYDEN. - Zoisite, rulile.
     LITTLETON.—Spinel, scapolite, apatite.
LYNNFIELD.—Magnesite on serpentine.
                       -Magnesite on serpentine.
     MARTHA'S VINEYARD.—Brown iron ore, amber, selenite, radiated pyrites.
     MENDON. - Mica / chlorite.
     MIDDLEFIELD. - Glassy actinolite, rhomb spar, steatite, serpentine, feldspar, drusy
 quartz, apatite, zoisite, nacrite, chalcedony, talc !
     MILBURY .- Vermiculite.
     MONTAGUE - Specular iron.
    NEWBURY.—Serpentine, chrysolite, epidote, massive garnet, carbonate of iron.
NEWBURY.—Sepentine, nemalite, uranite.
     NEW BRAINTREE. - Black tourmaline.
     NORWICH.—Apatite! black tourmaline, beryl, spodumene! triphyline (alte 1ed)
 blende, quartz crystala.
    PALMER, (Three Rivers).—Feldspar, prehnite, calc spar.
    PELHAN. — Asbestus, serpentine, quartz crystals, beryl, molybdenite, green hornstone.
    PLAINFIELD.—Cummingtonite, pyrolusite, rhodonite.
RICHMOND.—Brown iron ore, gibbsite!
    Rows. - Epidote, talc.
SOUTH ROYALSTON.—Beryl!! (now obtained with great difficulty), mica!! feld-
spar! ilmenite, allanite. Four miles beyond old loc., on farm of Solomon Heywood,
mica! beryl! feldspar!
   RUSSEL.—Schiller spar (diallage ?) mica, serpentine, beryl, galena, copper pyritea.

SAUGUS.—Porphyry.

SHEFFIELD.—Asbestus, pyrites, native alum, pyrolusite.

SHELBURNE.—Rutile.
   SHUTEBBURY, (east of Locke's Pond).-Molybdenite.
SOUTHAMPTON.—Galena, white lead ore, anglesite molybdate of lead, fluor, heavy spar, copper and iron pyrites, blende, corneous lead, pyromorphite.
   STERLING. - Spodumene, chiaetolite, spathic iron, mispickel, blende, galena, iron and
sopper pyrites.
   STONEHAM. - Nephrite.
STONEHAM.—Nepartic.
STURBRIDGE.—Graphite, garnet, apatite, bog ore.
TAUNTON, (one mile south).—Paracolumbite.
TURNER'S FALLS, (Conn. River.)—Copper pyrites, prehuite, chlorite, chlorophaite,
pathic iron, green malachite, magnetic iron sand, anthracite.
TYRINGHAM.—Pyroxene, scappolite.
UXBRIDGE.—Argentiferous galena.

Westing a genetic forms of the house of the country iron hard saides.
   WARWICK.—Massive garnet, black tourmaline, magnetic iron, beryl, epidota.
WABHINGTON.—Graphita.
    WESTFIELD.—Schiller spar, (diallage), serpentine, steatite, kyanite, scapolite,
etinolita
    WESTFORD.—Andalusite!
    WEST HAMPION.—Galena, argentine, pseudomorphous quarts.
WEST Springfield.—Prehnite, ankerite, satin spar, celestine, bituminous coal.
    WEST STOCKBRIDGE. - Hematite, fibrous pyrolusite, spathic iron.
    WHATELY .- Native copper, galena.
    WILLIAMSBURG.—Zoisite, pseudomorphous quartz, apatite, rose and smoky quarts,
galena, pyrolusite, copper pyrites.
```

PLYMOUTH. -Galena, heulandite, fluor.

ROARING BROOK, (Cheshire).—Datholite ! calc spar, prehnite, saponite.

READING, (near the line of Danbury). - Pyroxene, garnet.

ROXBURY.—Massive spathic iron, blende.
Salisbury.—Brown iron ore, ochery iron, pyrolusite, triplite.
Saybbook.—Molybdenite, stilbite, plumbago.

Simsbury.—Copper glance, green malachite.
Southbury.—Rose quartz, laumontite, prehnite, calc spar, heavy spar.

Southington.—Heavy spar, datholite, asteriated quartz crystals.

STAFFORD. - Massive pyrites.

STONINGTON.—Stilbite and chabazite on gneiss.

THATCHERSVILLE, (near Bridgeport).—Stilbite on gneiss, babingtonite!

TOLLAND. -Staurotide, massive pyrites.

TRUMBULL and Mondor.—Chlorophane, topaz, beryl, diaspore, magnetic pyrites, iron pyrites, tungstate of lime, wolfram, (pseudomorph of tungsten), rutile, native bismuth, tungstic acid, spathic iron, mispickel, argentiferous galena, blende, scapolite, tourmaline, garnet. albite, augite, graphic tellurium, (1) margarodite.

Washington.—Triplite, ilmenite! (Washingtonite of Shepard), diallogite, natrolite, andalusite (New Preston), kyanite.

Watertown, near the Naugatuck.—White sahlite, monazite.

WEST FARMS.—Asbestus.

WINCHESTER and WILTON. - Asbestus, garnet.

NEW YORK.

ALBANY CO .- COEYMAN'S LANDING .- Epsom salt.

GUILDERLAND.—Petroleum.
WATERVLIET.—Quartz crystals.

ALLEGANY CO .- CUBA. - Petroleum.

CATTARAUGUS CO .- FREEDOM .- Petroleum.

CAYUGA CO.-Auburn.-Fluor, epsom salt.

CAYUGA LARE.—Sulphur.
LUDLOWVILLE.—Epsom salt.
Springville.—Nitrogen springs.

CHATAUQUE CO .- FREDONIA .- Petroleum, carburetted hydrogen. LAGNA .- Petroleum.

COLUMBIA CO .- ANCRAM LEAD MINE .- Galena, blende, copper pyrites, heavy spar.

Austerlitz.—Earthy manganese, molybdate of lead, copper mica.

Hudson.—Selenite! LEBANON.—Nitrogen spring.

DUCHESS CO .- Dover .- Garnet (Foss ore bed).

FISHKILL -- Graphite, green actinolite ! tale, hydrous anthophyllite.

RHINEBECK.—Granular epidote.

Union Vall. - Gibbsite, (at Clove mine).

AMENIA.-Brown hematite.

ESSEX CO .- ALEXANDRIA .- Kirby's graphite mine, graphite, pyrozene, ecapolite,

sphene.

CROWN POINT.—Apatite, (eupyrchroite of Emmons), brown tourmaline! in the apatite, chlorite, quartz crystals, pink and blue calcite, pyrites; a short distance south of J. C. Hammond's house, garnet, scapolite, copper pyrites, aventurine feldspar, zircon; magnetic iron (Peru).

Lewis. - Tabular spar, colophonite, garnet, labradorite.

Long Pond.-Apatite, garnet, pyrozene, idocrase, coccolite!! scapolite, magnetic iron ore, blue calc spar.

NEW YORK CO .- CORLARD'S HOOK. -- Apatite.

KINGSBEIDGE.—Tremolite, pyrozene, mica, tournaline, pyrites, rutile.
HABLEM.—Epidote, apophyllite, stilbite, tournaline, vivianite, lamellar feldspar, mica.

NEW YORK .- Serpentine, amianthus, actinolite, talc, pyrozene, hydrous anthophyllite, garnet, staurotide, molybdenite, graphite.

NIAGARA CO.—Lewiston.—Epsom salt.

LOCKPORT. — Celestine, calc spar, selenite, anhydrite, fluor, pearl spar, blende. NIAGARA FALLS.—Calc spar, fluor, blende.

ONEIDA CO.—BOONVILLE.—Calc spar, tabular spar, coccolite.

CLINTON. -Blende, lenticular argillaceous iron ore; in rocks of the Clinton Group, strontianite, celestine, the former covering the latter.

ONONDAGA CO .- CAMILLUS .- Selenite and fibrous gypsum.

Manlius.—Gypsum and fluor.
Syracuse.—Serpentine, celestine.

ORANGE CO .- Connwall .- Zircon, chondrodite, hornhlende, spinel, massive feldspar, fibrous epidote, hudsonite, ilmenite, serpentine, boltonite.

DEER PARK.—Cryst. purites, galena.

Monror.—Mica! sphene! garnet, colophonite, epidote, chondrodite, allanite, bucholzite, brown spar, boltonite, spinel, hornblende, talc, ilmenite, magnetic pyrites, common pyrites, chromic iron, graphite.

At WILKS and O'NEIL Mine in Monroe.—Aragonite, magnetite, dimagnetite

(pseud!), jenkinsite.

At Two Ponds in Monros. - Pyroxene! chondrodits, hornblende, scapolite! zircon, sphene, apatite.

At GREENWOOD FURNACE in Monroe.—Chrondrodite, pyroxene! mica, hornblende, spinel, scapolite, biotite / ilmenite.

At Forest of DEAN.—Pyroxene, spinel, zircon, scapolite, hornblende, boltonite.

Town of WARWICK.

WARWICK VILLAGE — Spinel, zircon, serpentine! brown spar, pyroxene! hornblends! pseudomorphous steatite, feldspar! (Rock Hill), ilmenite, clintonite, tourmaline, (R. H.), rutile, sphene, molybdenite, mispickel, white iron pyrites, common pyrites, yellow iron sinter.

AMITY. - Spinel, garnet, scapolite, hornblende, idocrase, epidote ! clintonite! magnetic iron! tourmaline, war wickite, apatite, chondrodite, ilmenite, tale! pyroxene! rutile, sircon, corundum, feldspar, sphene, calc spar, serpentine, schiller spar.(1)

EDENVILLE. - Apatite, chondrodite! hair brown hornblende! tremolite, spinel, tourmaline, warwickite, pyrozene, sphene, mica, feldspar, mispickel, orpiment, rutile, il-

menile, scorodite, copper pyrites. West Point.—Feldspar, mica, scapolite, sphene, hornblende, allanite.

PUTNAM CO.—CARMEL, (Brown's quarry).—Anthophyllite, schiller spar, (f) orpiment, mispickel.

COLD SPRING.—Chabazite, mica, sphene.

PATTRESON .- White pyrozene ! calc spar, asbestus, tremolite, dolomite, massive pyrites.

PHILLIPSTOWN .- Tremolite, amianthus, serpentine, sphene, diopside, green crocolite, hornblende, scapolite, stilbite, mica, laumontite, gurhofite, calc spar, magnetic iron, chromic iron.

PHILLIPS Ore Bed. - Hyalite, actinolite, massive pyrites.

RENSSELAER CO .- Hoosic ,- Nitrogen springs

LANSINGBURGH .-- Epsom salt, quartz crystals, iron pyrites.

TROY .- Quartz crystals, iron pyrites, selenite.

RICHMOND CO .- Rossville. - Lignite, cryst. pyrites.

QUARANTINE. - Asbestus, amianthus, arngonite, dolomite, gurhofite, brucite, serpentine, talc

ROCKLAND CO .- CALDWELL .- Calc spar ! Grassy Point.—Serpentine, actinolite. Haverstraw.—Hornblende.

LADENTOWN.—Zircon, red copper ore, green malachite.
Piermont.—Datholite, stilbite, apophyllite, stellite, prehnite, thoms

STONY POINT.-Kerolite, lamellar hornblende, asbestus.

ST. LAWRENCE CO .-- CANTON .- Massive pyrites, cale spar, brown t sphene, serpentine, tale, rensselaerite, pyroxene, specular iron, copper pyro Dekale.—Hornblende, heavy spar, fluor, tremolite, tourmaline, blende, pyroxene, quartz (spongy), serpentine.

EDWARDS.—Brown and silvery mica! scapolite, apatite, quartz crystals, tremolite, specular iron, serpentine, magnetite.

FINE -Black mica, hornblende.

FOWLER.—Heavy spar, quartz crystals! specular iron, blende, galena, chalcedony, bog ore, satin spar, (assoc. with serpentine), iron and copp actinolite, rensselaerite, (near Somerville).

GOUVERNEUR.—Cale spar! serpentine! hornblende! scapolite! orthoclas line! idoerase, (one mile south of G.), pyroxene, apatite, reusselaerite, sphene, fluor, heavy spar (farm of Judge Dodge), black mica, phlogopite, asbestus, specular iron, graphite, idocrase; (near Somerville in serpentir houghite, scapolite, phlogopite, dolomite; three quarters of a mile west ville, chondrodite, spinel; two miles north of Somerville, apatite, pyrites. Hammond.—Apatite! zircon! (farm of Mr. Hardy), orthoclase, pargas

spar, pyrites, purple fluor, dolomite.

Hermon.—Quartz crystals, specular iron, spathic iron, pargasite, pyroxes

tine, tourmaline, bog iron ore.

MACOMB.—Blende, mica, galena (on land of James Averil), sphene. MINERAL POINT, Morristown.-Fluor, blende, galena, phlogopite, (Por heavy spar.

OGDENSBURG. - Labradorite.

PITCAIRN.—Satin spar, associated with serpentine.
Potsdam.—Hornblende!—eight miles from Potsdam on road to Pierre;

spar, tourmaline, black mica, hornblende.

Rossie, (Iron Mines).—Heavy spar, specular iron, correlloidal aragonite near Somerville, limonite, quartz, (sometimes stalactitic at Parish in pyrites, pearl spar.
Rossie Lead Mine.—Cale spar, galena, pyrites, celestine, copper pyrite

iron! white lead ore, anglesite.

Elsewhere in Rossie.—Cale spar, heavy spar, quartz crystals, chondro Yellow Lake), feldspar! paryasite! apatite, pyrozene, hornblende, sphere mica, fluor, serpentine, automolite, pearl spar, graphite.
RUSSEL.—Pargasite, specular iron, quartz (dodec.), calcite, serpentine, ren

magnetite.

SARATOGA CO .- Greenfield .- Chrysoberyl ! garnet, tourmaline ! mica apatite, graphite, aragonite, (in iron mines).

SCOHARIE CO.—Ball's Cave, and others.—Cale spar, stalactites.

Carlisle.—Fibrous sulphate of baryta, cryst. and fib. carbonate of lime. Scoharie .-- Fibrous celestine, strontianite! cryst. pyrites!

SENECA CO .- CANOGA .- Nitrogen springs.

SULLIVAN CO .- WURTZBORO' .- Galena, blende, pyrites, copper pyrites.

ULSTER CO .- ELLENVILLE .- Galena, blende, copper pyrites ! quartz, br MARBLETOWN. - Pyrites.

WARREN CO .- CALDWELL .- Massive feldspar. CHESTER. - Pyrites, tourmaline, rutile, copper pyrites. DIAMOND IALE, (Lake George.)—Calc spar, quartz crystals. GLENN'S FALLS.—Rhomb spar. JOHNSBURG. - Fluor! zircon!! graphite, serpentine, pyrites.

WASHINGTON CO .- FORT Ann .- Graphite. -GRANVILLE. — Lamellar pyroxene, massive feldspar, epidote.

WAYNE CO .- WOLCOTT .- Heavy spar.

WESTCHESTER CO. Anthony's Nose.—Apatite, pyrites, calcite! in very large tabular crystals, grouped and sometimes incrusted with drusy quartz.

DAVENPORT'S NECK.—Serpentine, garnet, sphene.

Eastchester.—Blende, copper and iron pyrites, dolomite.

HASTINGS.—Tronolite, white pyrozene.

NEW ROCHELLE.—Serpentine, brucite, quartz, mica, tremolite, garnet.

PERESKILL.—Mica, feldspar, hornblende, stilbite.

RYE - Serpentine, chlorite, black tourmaline, tremolite, kerolite.

Singsing.—Pyrozene, tremolite, iron pyrites, copper pyrites, beryl, azurite, green malachite, white lead ore, pyromorphite, anglesite, vauquelinite, galena, native silver.

WEST FARMS. - Apatite, tremolite, garnet, stilbite, heulandite, chabazite, epidote, sphene.

YONKERS .- Tremolite, apatite, calc spar, analcime, pyrites, tourmaline.

Yorktown.—Sillimanite, monazite, magnetic iron.

NEW JERSEY.

Andover Iron Mine (Sussex Co).-Willemite, brown garnet.

ALLENTOWN, (Monmouth Co.)—Vivianite.

BELVILLE.—Copper mines.

Bergen. — Calc spar, datholite, thomsonite, pectolite (called stellite), analcime, apophyllite, prehnite, sphene, stilbite, natrolite, heulandite, laumontite, chabazite, pyrites, pseudomorphous steatite imitative of apophyllite.

BRUNSWICK.—Copper mines; native copper, malachite, mountain leather.

BRYAN.-Chondrodite.

CANTWELL'S BRIDGE, Newcastle Co., three miles west.—Vivianite.

DANVILLE, (Jemmy Jump Ridge). - Graphite, chondrodite, augite, mica.

FLEMINGTON.—Copper mines. FRANKFORT.—Serpentine.

Franklin and Sterling.—Spinel! garnet! rhodonite! willemite! franklinite! red zinc ore! dysluite! hornblende, tremolite, chondrodite, white scapolite, black tourmaline, epidote, pink cale spar, mica, actinolite, augite, sahlite, coccolite, asbestus, jeffersonite (augite), calamine, graphite, fluor, beryl, galena, serpentine, honey-colored sphene, quartz, chalcedony, amethyst, zircon, molydenite, vivianite. Also algerite in gran. limestone. The zinc ores and franklinite, especially at Sterling Hill in Sterling, the jeffersonite at Mine Hill, in Franklin.

FRANKLIN and WARWICK MTS.—Pyrites.

GREENBROOK.—Copper mines.

GRIGGSTOWN.—Copper mines.

HAMBURGH.—One mile north, spinel !, tourmaline !, phlogopite, hornblende, &c., limonite, specular iron.

Hoboken. - Scrpentine, brucite! nemalite (or fibrous brucite), aragonite, dolomite.

Hubbstown.—Apatite, magnetic pyrites, magnetite.

Imleytown.—Vivianite.

Lockwood.—Graphite, chondrodite, talc, augite, quartz, green spinel.

MONTVILLE, Morris Co.—Serpentine, chrysotile.

MULLICA HILL, Gloucester Co.- Virianite lining belemnites and other fossils.

NEWYON.—Spinel, blue and white corundum, (exhausted), mica, idocrase, Aorablende, tourmaline, scapolite, rutile, pyrites, tale, cale spar, heavy spar, pseudomorphous steatite.

PATTERSON. - Datholite.

битты Кин.—Этек паледы, гей сер SOURCE THE PARTY OF THE SECOND PROPERTY OF THE SECOND SECO

SPARTA - Therefore : spend, saggire grees -breez epi SOMESTRY, IS the Micha Male Transa-Airea anter bette

Verses.—Green spend, chemistralise red negal replace, lemente, retile, spinete, limente, area FOR SERVICE THE PARTY OF THE PA

Nove.—From Amiry, N. Y., to Amirver, N. i the outeropping dimentone, at different points, a commental to occurring at Frankin.—See Goo

PEXXSTLTAX

ADAMS CO .- Readesc .- Molybienite in qua

BERKS CO.-A: Joyes's Mixes, zear Moss. ryssocile .. oct and doder. magnetic iron, is es to the northeast, graphite, sphene : at Ste ires err. coccoiise

BUCK'S CO.-Opposite New Hope, tournel dale's imestone quarry, sadite, sempolite, sphe-

CARBON CO .- At Manch Chunk, cryst. iron

CHESTER CO .- BIRMINGHAM .- Kerolite, amet E. Bradevan.-On Minoreus Hill, green, blue on A. Taylor's farm, sphene, cryst, smoky que Price. L. Sharpless, and S. Entrikin, amethyst; site, marmonte, garnet; near T. Hoope's saw n Hiil, sphene, manganesian garnet, wai, tourmal spar, feti-l calcite; near the Black Horse Inn, ru

W. Bradsond.—Near A. Jackson's limestone q lite, iron pyrites; near Marshail's mill, chromic (limestone) quarry, (cailed also Baldwin's), four west of Westchester, ratile! in brilliant aciculdolomite, zoisite in quartz, tale in implanted cry fine crystals implanted on dolomites, quartz crys

CHESTER PRINGS .- Gibbeite, in an iron mine; 1 limestone quarry, augite, sphene, graphite, zirce from the village on French Creek.

WEST GOSHEN.-Amianthus, asbestus, precious chalcedony, drusy quartz, chlorite, marmolite, chronic iron! magnetic iron; near Westchester found now,

KEIM's IRON MINE near Knauertown. - Flos-fer iron ore, aplome!! actinolite, yellow octahedral p drons, red yarnet! malachite, hornblende (var. b Kennet Township.—Actinolite! (rare on Gregi

mica, epidote, tremolite, scapolite, aragonite; at dote, sunstone; on R. Lamborne's farm, chabazit als. (rare), zeolite; at Gause's corner, epidote.
Knauestown.—North of Pughtown, graphite,

Chrismard's Iron Mine, zircon.

LONDON GROVE.—In Jackson's limestone quari tremolite; at Pusey's quarry, rutile, tremolite.

NEW GARDEN TOWNSHIP.—At Nevin's limestone lite, brown and green mica, rutile, aragonite, kao

NEWLIN. - See Unionville, below.

East Marlbono. - Epidote, and nearly white tourmaline, (rare).

Oxford.—Iron pyrites, garnets.
Nottingham.—At Scott's chrome mine, chromic iron, foliated tale, marmolite, serentine, chalcedony; at the Magnesian Quarry, magnesite, marmolite, serpen-

PARKSBURG, (in township of Sadsbury).-In the soil for seven miles along the valley, rutile !; northeast of the village, amethyst, tourmaline, epidote, (in a boulder).

Penn.-Garnets, figure stone.

PENNSBURY TOWNSHIP .- On Cephas Cloud's farm, brown garnets !; J. Dilworth's farm, near Pennsville, mica ! (in six-sided prisms from one quarter to seven inches across); at Harvey's lime quarry, on the Brandywine, chondrodite; quarter of a mile above the last, at Wm. Burnett's lime quarry, sphene, diopside, augite, coc-

PHENIXVILLE.—In Railroad Tunnell, pearl spar (exhausted), dolomite, yellow blende, iron pyrites; at Wheatley's Mine, pyromorphite! cerusite! cryst. quartz, galena, anglesite! copper pyrites, heavy spar, fluor, aulfenite! calamine, cerasine!, vanadinite!, phosphate of copper, chromate of lead.

Porrsrown, near French Cr.—(Elizabeth Mine).—Iron pyrites! (in octahedrons).

copper pyrites, magnetite, dark brown garnet, molybdenite.
UNIONVILLE.—One and a half miles northeast, on Serpentine Barrens, corundum! massive and cryst. (often in loose crystals and also in albite, the loose crystals mostly covered with a thin coating of steatite, sometimes with gibbsite), tale, green tourmaline (with flat or pyramidal terminations), ligniform asbestus, yellow beryl (rare), serpentine, brucite, chromic iron, quartz crystals, green quartz, actinolite, clinochlore in cryst, diallage, granular albite (H.=7), adularia, oligoclase, halloysite, margarite, euphyllite, allanite, hematite, chalcedony; half a mile southwest, on T. Webb's farm, serpentine, chromic iron, (mas.); two and a half miles southwest, in R. Bailey's lime quarry, fib. tremolite, mussite; kyanite, margarodite; two miles southwest, at Pusey's saw mill, zircon (cryst. small, loose in the soil, rare), rutile; one mile south, on the farm of Baily and Brothers, bright valow and nearly white tourmaline! (rare), orthoclase (chesterlite), albite! (inaccessible); two miles east, near Marlborough meeting house, epidote! (rare), serpentine, acicular black tourmaline in white quartz; one mile west, near Logan's quarry, staurotide, kyanite, yellow tourmaline, (rare); at Edward's lime quarry near the last, purple fluor, rutile; four miles west, in limestone quarries of West Marlborough, near Doe River Village, scapolite, rutile, tremolite. massive and cryst. (often in loose crystals and also in albite, the loose crystals

Westchester.—One and a half mile north, hydromagnesite, clinochlore, brucite, in serpentine, zircon, two miles west; one and a half mile northwest, pitch-black allanite; B.B. intumesces very readily (G. 2.5); 3 m. south, clinochlore, phlogopite.

WILLISTOWN.-Magnetic iron, chromic iron, actinolite.

COLUMBIA CO.-At Webb's mine, yellow blende in calc spar; near Bloomburg, cryst. magnetic iron,

DAUPHIN CO .- Near Hummerstown, green garnets, cryst. smoky quarts, cryst. feldspar.

DELAWARE CO .- Asron .- Near Village Green, amethyst, corundum, emerylite, staurotide, sillimanite, black tourmaline, pearl mica, asbestus, anthophyllite; near Tyson's Mill, garnet, staurotide; at head of Peter's Mill Dam, in a brook, garnet resembling pyrope.

BIBMINGHAM.—At Bullock's quarry, zircon, bucholzite, fibrolite, nacrite.

CHESTER.—Amethyst, black tourmaline; in Burk's quarry, beryl!! black tourmaline!! feldspar! manganesian garnet, cryst. pyrites; on Chester Creek, at Carter's, molybdenite, molybdic ochre, copper pyrites, tourmaline, kaolin; at Little's quarry, brown garnets, tourmaline; near Henvi's quarries, amethyst in geodes.

CHICHESTER.—Near Trainer's Mill Dam, beryl, tourmaline, cryst, feldspar, kaolin;

on W. Eyre's farm, tourmaline !!

Cooprown, Harford Co .- Olive-colored tourmaline, diallage, tale of and rose colors, ligniform asbestus, chromic iron, serpentine.

Deer Creek.—Magnetic iron ! in chlorite slate.

FREDERICK CO.—Old Liberty Mine, near Liberty Town, black copper, copper glance, specular iron; at Dollyhyde Mine, erubescite, copper p pyrites, argentiferous galena in dolomite.

Montgomery Co.—Oxyd of manganese.

Somerser and Workster Cos., north part.—Bog iron ore, visianite.

St. Mary's River. - Gypsum / in clay.

VIRGINIA AND DISTRICT OF COLUMBIA.

ALBEMARIE Co., a little west of the Green Mts.—Steatite, graphite; g.
AMHERST Co., along the west base of Buffalo ridge.—Copper ores, etc.
AUGUSTA Co.—At Weyer's (or Weir's) cave, sixteen mile northeast o
and eighty-one miles northwest of Richmond, cale spar, and stalactites
BUCKINGHAM Co.—Gold at Garnett and Moseley Mines, largely worke
rites, pyrrhotine, calcite, garnet; at the Eldridge Mine (now London a)

Mines) near by, and the Buckingham Mines near Maysville, gold, aurifercopper pyrites, tennantite, heavy spar; kyanite, tourmaline, actinolite.

CHESTERFIELD CO.—Near this and Richmond Co., bituminous coal, nat

CHISPERPER Co., on Rapidan river.—Gold, pyrites.

Franklin Co.—Grayish steatite.

Fauquier Co., Barnet's Mills.—Asbestus; gold mines, barytes, calcite.

Fluvanna Co.—Gold at Stockton's Mine; also tetradymite at "Telluri PHENIX Copper Mines .- Copper pyrites, etc.

Georgetown, D. C .- Rutile.

GOOCHLAND CO.—Gold mines, (Moss and Busby's).
HARPER'S FERRY, on both sides of the Potomac.—Thuringite (owe quartz.

JEFFERSON Co., at Shepherdstown.—Fluor.

KENAWHA Co.—At Kenawha, petroleum, brine springs, cannel cosl.

Loudon Co.—Tabular quartz, prase, pyrites, tale, chlorite, soapstone chromic iron, actinolite, quartz crystals; micaceous iron, erubescite, mal dote, near Leesburg, (Potomac Mine).

Louisa Co.—Walton gold mine, gold, pyrites, copper pyrites, argent lena, spathic iron, blende, anglesite; boulangerite, blende (at Tinder's Montagor Co.—Galena, copper pyrites, malachite.

NELSON Co.—Galena, copper pyrites, malachite.
ORANGE Co.—Western part, Blue Ridge, specular iron; gold at the Orange Vaucluse gold mines, worked by the "Freehold" and "Libert Companies.

ROCKBRIDGE Co., three miles southwest of Lexington. - Heavy spar.

Shenandoah Co., near Woodstock .-- Fluor spar. Mr. Alto, Blue Ridge.—Argillaceous iron ore.

SPOTSYLVANIA Co., two miles northeast of Chancellorville.- Kyanite; at the junction of the Rappahannock and Rapidan ("Gardiner" Co.); opahannock (Marshall Mine); Whitehall Mine, affording also tetradymits Stafford Co., eight or ten miles from Falmouth.—Micaceous iron, gol

mite, silver, galena, vivianite.

Washingron Co., eighteen miles from Abingdon.—Rock salt with gyps
Wyтне Co., (Austin's mines).—Cerusite, minium, plumbic ochre, blende

On the Potomac, twenty-five miles north of Washington City .- Nati in gray compact limestone.

NORTH CAROLINA.

ASHE Co.—Malachite, copper pyrites.
Buncombe Co.—Corundum (from a boulder), margarite, corundophil chromic iron, barytes, fluor, rutile, iron ores, oxyd of manganese.

BURKE Co.—Gold, mongrite, zircon, beryl, corundum, garnet, sphene, grephite, iron ores.

Cararres Co.—Phenix mine, gold, barytes, copper pyrites, auriferous pyrites, quartz pseudomorph after barytes, tetradymite; Pioneer Mines, gold, limonite, pyrolusite, barnherdtite, wolfram, scheelite, tungstate of copper, wolframine, diamond, chrysocolla, copper glance, molybdenite, copper pyrites; White Mine, needle ore, copper pyrites, barytes; Long and Muse's Mine, argentiferous galena, pyrites corpor pyrites limonite. Roger Mine tetradymits: Fink Mine value.

needle ore, copper pyrites, barytes; Long and Muse's Mine, argentiferous galena, iron pyrites, copper pyrites, limonite; Boger Mine, tetradymite; Fink Mine, valuable copper ores; Mt. Makins, tetrahedrite! magnetite, talc, blende, pyrites, galena.

CALDWELL Co.—Chromic iron,
CHATBAM Co.—Mineral coal, pyrites.

CHEROREE Co.—Iron ores, gold, galena, corundum, rutile.

DAVIDSON Co.—King's now Washington Mine, native silver, cerusite, anglesite, scheelite, pyromorphite, galena, blende, malachite, black copper, sevellite, garnet, stilbite. Five miles from Washington Mine, on Faust's Farm, gold, tetradymite, cover of hismuth and tallurium comper pyrites limonite, anather iron emidets near oxyd of bismuth and tellurium, copper pyrites, limonite, spathic iron, epidote; near

Squire Ward's, gold in crystals, electrum.

Gasrow Co.—Iron ores, corundum, margarite. Near Crowder's Mountain (in what was formerly Lincoln Co.), lasulite, kyanite, gernet, graphite; also twenty miles northeast, near south end of Clubb's Mtn., lasulite, kyanite, tale.

GUILFORD Co.—McCullock copper and gold mine, twelve miles from Greensboro, gold, pyrites, copper pyrites (worked for copper), querts, spathic iron. The North Carolina Copper Co. are working the copper ore at the old Fentress mine.

HENDERSON Co.-Zircon.

Lincoln Co.-Diamond; at Randleman's, amethyst /, rose quarts.

MACON Co.—Chromic iron.

McDowell Co .- Brookite, monazite, corundum in small crystals red and white, sircons, garnet, beryl, sphene, xenotime, rutile, elastic sandstone, iron ores.

MECELEWBERG Co.—Near Charlotte (Rhes and Cathay Mines) and elsewhere, cop-

per pyrites, gold; chalcotrichite at McGinn's Mine; barnhardtite near Charlotte; pyrophyllite in Cotton Stone Mountain, diamond.

Rowan Co.—Gold Hill Mines, thirty eight miles northeast of Charlotte, and fourteen from Salisbury, gold, auriferous pyrites; ten miles from Salisbury, feldepar in

RUTHERFORD Co.—Gold, graphite, biamuthic gold, diamond, euclase, pseudomorphous quarts, chalcedony, corundum in small crystals, epidote, pyrope, brookite, zircon, monazite, rutherfordite, samarskite, quarts crystals, itacolumite; on the road to Cooper's gap, kyanite.

STOKES AND SURREY COa.—Iron ores, graphite.
UNION CO.—Lemmond Gold Mine, eighteen miles from Concord, (at Stewart's and Moore's Mine), gold, quartz, blende, argentiferous galena (containing 284 oz. of gold, and 86 5 oz. silver to the ton, Genth), pyrites, some copper pyrites.

YARCET Co .- Iron ores, amianthus, chromic iron.

SOUTH CAROLINA.

ARREVILLE DIST. - Oakland Grove, Gold, (Dorn Mine), galena, pyromorphite, amethyst, garnet.

ANDERSON DIST .- At Pendleton, actinolite, galena, kaolin, tourmalina

CHARLESTON.—Selenite.

CHEOWEE VALLEY.—Galena, tourmaline, gold.

CHESTERVIELD DIST.—Gold, (Brewer's mine), tale, chlorite, pyrophyllite, pyrites, native bismuth, carbonate of bismuth, red and yellow ochre, whetstone.

DARLINGTON. - Kaolin.

EDGEFIELD DIST.-Psilomelane.

GREENVILLE DIST.—Galena, phosphate of lead, kaolin, chalcedony in burhatone, beryl, plumbago, epidote, tourmaline. KERSHAW DIST.—Rutile.

LANCASTER DIST.—Gold (Hale's mine), tale, chlorite, kyanite, elastic sandstone, pyrites; gold also at Blackman's mine, Massey's mine, Esell's mine.

NEWBERRY DIST.—Leadhillite (1).

PICKEN'S DIST.—Gold, manganese ores, kaolin. RICHLAND DIST.—Chiastolite, novaculite.

SPARTANBURG DIST .- Magnetic iron ore, chalcedony, hematite; at the brown hematite, graphite, limestone, copperas.

SUMTER DIST .- Agate. Union Disr.—Fairforest gold mines, pyrites, copper pyrites. York Disr.—Limestones, whetstones, witherite, heavy spar.

GEORGIA.

Burke and Scriven Cos .- Hyalite.

CLARK Co., near Clarksville.-Gold, xenotime, zircon, rutile, kyanit iron, garnet, quartz.

HABERSHAM Co.—Gold, iron and copper pyrites, galena, hornblen quartz, kaolin, soapstone, chlorite, rutile, iron ores, galena, tourmaline,

HALL Co .- Gold, quartz, kaolin, diamond. HANCOCK Co.—Agate, chalcedony. LUMPKIN Co.—Gold, quartz crystals.

RABUN Co .- Gold, copper pyrites. Washington Co. near Saundersville. - Wavellite, fire opal.

ALABAMA.

Bibb Co., Centreville.—Iron ores, marble, heavy spar, coal, cobalt. Tuscaloosa Co.—Coal, galena, pyrites, vivianite, limonite, calcite, dol anite, steatite, quartz crystals, manganese ores.
Benton Co.—Antimonial lead ore (Boulangerite?)

FLORIDA.

NEAR TAMPA BAY.-Limestone, sulphur springs, chalcedony, carneli silicified shells and corals.

KENTUCKY.

MAMMOTH CAVE.—Gypsum, in imitative forms, stalactites, nitre, epsom s Near the line between Livingston and Union Cos., galena, copper pyrit

TENNESSEE.

BROWN'S CREEK.—Galena, blende, heavy spar, celestine. CARTER'S Co. foot of Roan Mt.—Sahlite, magnetic iron.

CLAIBORNE Co .- Calamine, galena, smithsonite, chlorite, steatite, and

Cocke Co., near Brush Creek.-Cacoxene, kraurite, iron sinter, stilpn brown hematite.

DAVIDSON Co.-Selenite, with granular and snowy gypsiem, or alabaster bized and compact anhydrite, fluor in crystals? cale spar in crystals. No ville, blue celestine, (crystallized, fibrous, and radiated), with heavy spar stone. Haysboro', galena, blende, with heavy spar as the gangue of the control

JEFFERSON Co .- Calamine, galena, fetid heavy spar.

Knox Co.-Magnesian limestone. MAURY Co. - Wavellite in limestone.

Morgan Co.—Epsom salt, nitrate of lime.

Polk Co., Hiwassee mine, southeast corner of state, near Ococe river copper ! copper pyrites, iron pyrites, (mines valuable).

ROAN Co., eastern declivity of Cumberlands Mts.—Wavellite in limestone. SEVERN Co, in caverna.—Epsom salt, soda alum, saltpetre, nitrate of lime. SMITH Co.—Fluor.
SMOKY Mt., on declivity.—Hornblende, garnet, staurotide.

OHIO

BAINBRIDGE, (Copperas Mt., a few miles east of B.)—Calc spar, heavy spar, iron pyrites, copperas, alum.

CANFIELD,—Gypsum!
Duck Creek, Monroe Co.—Petroleum.

LIVERPOOL.—Petroleum.

MARIETTA.—Argillaceous iron ore; iron ore abundant also in Scioto and Lawrence Cos.

POLAND .- Gypsum!

MICHIGAN.

LAKE SUPERIOR MINING REGION.— The four principal regions are Keweenaw Point, Isle Royale, the Ontonagon, and Portage Lake. The mines of Keweenaw Point are along two ranges of elevation, one known as the Greenstone Range and the other as the Southern or Bohemian Range, (Whitney). The copper occurs in the trap or amygdaloid, and in the associated conglomerate. Native copper! native silver! copper pyrites, horn silver, gray copper, manganese ores, epidote, prehnite, laumontite, datholite, houlandite, stilbite, analcime, chabazite, mesotype, (Copper Fallamine), teonhardite, (ib.), analcime, (ib.), apophyllite, (at Cliff Mine), scullastomite, (ib.), cale spar, quartz (in crystale, at Minesota mine), saponite, black ozyd of copper, (near Copper Harbor, but exhausted), chrysocolla; on Chocolate river, galena and sulphuret of copper; copper pyrites and native copper at Presqu' Isle. At Albion mine, domeykite; at Prince Vein, amethyst; at Michipicoten Ida., copper nickel, stilbite, analcime.

IBLE ROYALE, 48° N., 89° W.—Native copper, epidote, harmotome (1) dathelite, wollastonite (exhausted), pectolite, chlorastrolite.

ILLINOIS.

GALLATIV Co., on a branch of Grand Pierre Creek, sixteen to thirty miles from Shawneetown, down the Ohio, and from half to eight miles from this river.—Violet fluor spar! in carboniferous limestone, heavy spar, galena, blende, brown iron ore; near Rosiclare, calcite, galena, blende; five miles back from Elizabethtown, bog iron; one mile north of the river, between Elizabethtown and Rosiclare, nitra.

In Northern Illinois, townships 27, 28, 29, several important mines of galena. Pope Co.—Pyromorphite.

INDIANA.

LIMESTONE CAVERNS; Corydon Caves, &c.—Epsom salt.
In most of the southwest counties, pyrites, sulphate of iron, and feather alum p on Sugar Creek, pyrites and sulphate of iron; in sandstone of Lloyd Co., near the Ohio, gypsum; at the top of the blue limestone formation, brown spar, cale spar.

MINESOTA.

NORTH SHORE OF L. SUPERIOR, (range of hills running nearly northeast and southwest, extending from Fond du Lac Superieure to the Kamanistiqueia river in Upper Canada).—Scolecite, apophyllite, prehnite, stilbite, laumontite, heulandite, harmotome, thomsonite, fluor spar, sulphate of baryta, tourmaline, epidote, hornblende, caleareous spar, quartz crystals, iron pyrites, magnetic iron ore, steatite, blende, black oxyd of copper, malachite, native copper, copper pyrites, amethystine quartz, ferru-

ginous quartz, chalcedony, carnolian, agate, drusy quartz, hyalite ! fibrous q jasper, prace, (in the debris of the lake shore), degtooth spar, sugite, native : spedamene!, arsenite! of cobalt, chlorite; between Pigeon Point and Fon Lac, near Baptism river, saponite, (thalite), in smygdaloid.

KETTLE RIVER THAP RANGE.—Epidote, nail-head calc spar, amothystine qu

calcareous spar, undetermined zeolites, saponite.
STILLWATER.—Blende.

Falls of the St. Chorx.—Green carbonate of copper, native copper, epidote, heed spar.

RAINT LAKE - Actinolite, tremolite, fibrous horablende, garnet, iron pyrites, natic iron, steatite.

WISCONSIN.

At MINERAL POINT and elsewhere, copper and lead ores, principally silicat carbonate of copper, copper pyrites, and galens, (only the last abundant), pyrites, capillary pyrites, blends, white load ore, leadhillite (?), smitheonite (carb pyriles, captury pyruca, war, and calc spar. of zine), anglosite, hossy spar, and calc spar.

SANK Co.—Specular iron! malachite, copper pyrites.

MONTERAL RIVER PORTAGE.—Galena in gaeissoid granite.

Lac DC PLANDRAU R.-Garnet, kyanite

Big Btill Falls, (near).—Bog fron.
LET HAYD R., (near small tributary).—Malachite, copper glance, native cored copper ore, earthy malachite, epidote, chlorite! quartz crystals.

IOWA.

DU BUGUE LEAD MINES, and elsewhere.—Galens! cale spar, black oxyd of a ganese; at Ewing's and Sherard's diggings, calemine! or smithsonite; at Des Me quartz crystals, selenite; Mahoqueta R., brown iron ore.

CEDAR RIVER, a branch of the Des Moinea.-Selenite in crystals, in the bitum shale of the coal measures: also elsewhere on the Des Moines, gypsum abund argillaceous iron ore, spathic iron: copperas in crystals on the Des Moines, a the mouth of Saap and elsewhere, iron pyrites, blends.

MISSOURI.

BIRMINGHAM.—Limonite.

JEFFERSON Co., at Valle's Diggings .- Galena, white lead ore, anglesite, calar pyritous copper, blue and green malachite, carbonate of baryta.

MINE A BURTON.—Galena, white lead ore, anglesite, heavy spar, cale spar.
DEEP DIGGINGS.—Carbonate of copper, white lead ore in crystals, and mange

MINE LA MOTTE.—Galena ! malachite, carthy cobalt and nickel, bog manga: sulphuret of iron and nickel, white lead ore in crystals, caledonite, plumboresi

PERRY's Discrisce, and elsewhere.-Galena, &c.

Forty miles west of the Mississippi and ninety south of St. Louis, the iron m tains, specular iron, limonite.

ARKANSAS

BATESVILLE.—In bed of white R., some miles above Batesville, Gold.

OTACHITA SPRINGS -- Quertz! whetstones.

MAGNET COVE - Brookite! schorlomite, elssolite, magnetic iron, quartz, green ce lite, garnet, apatite.

CALIFORNIA.

Along the Sierra Nevada, gold, platinum (rare), iridosmine, molybdenite, molybdine, zircon, magnetic iron; near bay of San Francisco, actinolite, tale, serpentine, jasper, salt, gypsum, (island in the Caquines Straits); ridges of Sierra Aml, south of San José, cimabar. Gold also found in the Umpqua region, Oregon, and the Shasty Mountains.

CANADA.

CANADA EAST.

ABERCROMBIE — Labradorite. BAY ST. PAUL.—Ilmenite!, apatite, allanite, rutile (or brookite!) AUBERT.—Gold, iridosmine, platinum. BOLTON. - Chromic iron, magnesite, serpentine, picrolite, steatite, bitter spar, wad. BOCCHERVILLE - Augite in trap. Brown. - Magnet ic iron, copper pyrites, sphene, ilmenite, phyllite, sodalite, cancrinite, galena. CHAMBLY. - Analcime, chabazite and calcite in trachyte. CHATEAU RICHER. - Labradorite, ilmenite, hyperathene. DAILLEBOUT. - Blue spinel, with clintonite. GRENVILLE.—Tabular apar, sphene, idocrase, calcite, pyroxene, garnet (cinnamon stone), zircon, graphite, scupolite. HAM. - Chromic iron in serpentine. INVERNESS. - Varie jated copper. LAKE St. FRANCIS. - Andalusite in mica slate. LANDBOWNE — Barytes.
MILLE ISLES. — Labradorite ! ilmenite, hypersthene, andesine, zircon. MONTREAL — Calcite, augite, sphene in trap.

MONTREAL — Calcite, augite, labradorite.

POLTON. — Chromic iron, steatite, serpentine, amianthus. ROUGEMONT Mrs.—Augite in trap. St. Armand.—Micaceous iron ore with quartz, epidote. St. François Beauce. - Gold, platinum, iridosmine, ilmenite, magnetite, serpentine, chromic iron, soapstone, magnetite, heavy spar.
Sr. JEROME.—Sphene, apatite, chondrodite, phlogopite, tourmaline, zircon, molybdenite, magnetic pyrites. St. Norbert.-Amethyst in greenstone. STUKLET .- Serpentine, verde antique / schiller spar. Surron. - Magnetic iron in fine crystals, specular iron, rutile, dolomite, magnetite, chromiferous tale, bitter spar, steatite. UPTON.—Copper pyrites, malachite, calcite. VAUDREUIL—Limonite, vivianite. YAMASKA.—Sphene in trap.

('ANADA WEST.

Balsam Lake — Molybdenite, scapolite, quartz.
Brantford.—Sulphuric acid spring, (4"2 parts of pure sulphuric acid in 1000).
Bathurst.—Heavy spar, black tourmaline, perthite (orthoclase), peristerite (albite), bytownite.
Brown.—Magnetite.
Brown.—Pyroxene, albite, mica, sapphire, sphene, copper pyrites, apatite, black spine! ! spodumene, (in a boulder).
Bytown.—Calcite, bytownite, chondrodite, spinel.
Cape Ipperwash, Lake Huron.—Oxalite in shales.
Clarendon.—Idocrase.
Dalhousie.—Hornblende, dolomite.
Drummond.—Labradorite.

APPENDIX.

APPENDIX TO FIRST VOLUME

P. ST. In the Monoclinic System, the values of the axes, (the clinediagonal 5 being a unit, are readily obtained by the following equations: X being half the front angle of the prism or half of I: I and X half the angle above of the cline-dome $1-\infty$ (or half of I: I) over (I):

The proportion $a:b=\sin a:\sin s$, in the seventeenth line from bottom of this page should be $a:b=\sin s:\sin s$.

P. 92. The heading Monoclinic System should be Monometric System.

Atomic Weight of Gluciaum.—J. Weeren has obtained for the atomic weight of Gluciaum 66-50. Pogg. xcii, 128, 1884.

P. 189. Homeromorphism.—In a paper on the relations between Chemical Composition and Crystalline Form, (Paris, 1852), by M. Ladrey, from whom it has been just now received, the author reviews many different classes of compounds, principally minerals, and shows that all or nearly all of the forms may be obtained from fundamental forms, near 20° in angle, by assuming as the fundamental form where necessary, one having some simple relation to that usually so adopted. Relations to the monometric bystem are thus brought out, and also homeomorphisms independent of composition. In deducing the relations, cleavage, twin composition, and all other points bearing on the a-tual or potential dimensions of a species, are disregarded: points which are dwelt upon in the chapter on homeomorphism, and which have led the author to a similar general conclusion by a different, and, as we believe, by a more consistent method.

Rammelsberg has published an important paper in Pogg. xci, \$21, on the Crystallization of isomorphous Salts together. In the Ann. de Ch. et de Phya [3], xxxix, 404, 1553, M. J. Nickles has a valuable memoir "On Polymorphism."

Pseudomorphs, p. 222.—Add the following to the catalogue. They are mostly from a paper by Prof. Reuse of Prague. (1853):

Hematite	after	Cerusite. Feldspar.	Pyrites Marcasite	after 	Brown Spar. Barvtes.
Galena	••	Cerusite.	Chalcopyrite		Magnetite.
Pharmacolite	••	Realgar.		••	Nagyagite. Orthoclass.
(Farnet	••	Calcite.	Thorite	••	Orthoclass.
Committe	••	Calaita			

P. 250. In the Classification of Minerals, the Fluorids are arranged along side of the Chlorids, where some chemists place them. The element Fluorine appears to be intermediate in character between Oxygen and Chlorine: and it is probably better to make for it a separate division, arranging the species (p. 250) as follows:

HL CHLORIDS, BROMIDS, 10DIDS

1. Calomel Division, &c.—Calomel.
2. Rock Salt Division, &c.—Rock Salt Group, Sylvine, Rock Salt, Sal Ammoniac, Kerargyrite, Bromyrite; Iodyrite Group, Iodyrite; Columnite Group, Cotunnite.

L BINARY COMPOUNDS.—1. Fluor Group. Fluor Spar, Yttrocerite: Fluorerite
Group, Fluorerite. IL Double Binaer Compounds, Cryolite, Chiolite.

Then v. oxygen compounts, and so on

APPENDIX TO SECOND VOLUM

1. New or Unarranged Species.

BARNHARDTITE, Genth, (communicated to the author).—Massive, a bronze-yellow color, near that of pyrites, but lustre less bright, an easily to pinchbeck and pavonine tints. Cleavage none. Streak black

Composition .- 2 CuS+Fe S3. Analyses, by P. Keyser and W. J. Taylo direction of Dr. F. A. Genth:

1. Pioneer Mills, Sulphur 30:50 Copper 48:40 Iron 21:08, Keyser 22-23, Ag tra 2. Dan Barnhardt's, 29.40 47.61

B.B. gives sulphur fumes, and fuses to an iron-black magnetic globule

Fluxes, reactions of iron, copper, and sulphur.

From a mine on the land of Dan Barnhardt, Cabarras Co., North Cannear Pioneer Mills, and at the Phenix and Vanderberg Mines in the sa and in the neighborhood of Charlotte in Mecklenburg Co.

CAROLATHINE, F. L. Sonnenschein, (J. f. pr. Ch. lx, 268, 1853) .- M. rounded balls. Color honey-yellow to wine-yellow. Subtranslucen G .= 1.515. Fracture conchoidal.

Composition .- Analysis afforded H 2.41,0 19.39,C 1.33, for the volatile included) with #1 47.25 and Si 29.62 for the fixed. This last corresponds to AlSit, as in Andalusite. Heated it affords water, which is neutral in it and decrepitates at a higher temperature, the color becomes darker, a shining mass is obtained. B.B. ignites somewhat without flame, and aff action of alumina and silica.

From a bed of mineral coal near Gleiwitz in Upper Silesia. Somewha Mellite. Named after the Prince of Carolath.

CHALCODITE, Shepard. (Shep. Min. 3d. ed. 153).—Chalcodite appear Anthosiderite, (p. 304). It occurs in minute thin laminæ, aggregated if forming very short velvety coatings, on hematite; color yellow and yellow, with a pearly bronze lustre; laminæ tender, flexible. Dissolve hot muriatic acid. B.B. like Anthosiderite. Occurs at the Sterling Antwerp, Jefferson Co., N. York.

DELANOVITE, Kenngott, (Jahrb. k. k. Geol. Reichs., iv, 633).—A rephous earthy mineral, H.=1-1:5; fracture splintery to earthy; adhetongue; streak reddish, a little shining; B.B. infusible. Analysis Hauer, (loc. cit):

Si 50.55 Mn 4.40 H 24.05=98 Al 19·15 Ca 0.63

14.03 per cent. of water was driven off at 100° C. The oxygen ratio Si, H, is nearly 1:2:6:15=R³Si³+2\ff Si²+45\ff H, or (\frac{1}{2}R^2+\ff R^2 Si^2+15\ff Si \frac{1}{2}H \frac{1}{2}H \frac{1}{2}Si^2+15\ff Si \frac{1}{2}H \frac{1}{2}Si^2+15\ff Si \frac{1}{2}H \frac{1}{2}Si^2+15\ff Si \frac{1}{2}H \frac{1}{2}Si^2+15\ff H \frac{1}{2}Si^2+15\ Montmorillonite.

IODO-BROMID OF SILVER .- M. Louis Sæmann announces by lette thor, that he has distinguished an iodo-bromid of silver among the Chili.

LINDACKERITE, J. F. Vogl. (Jahrb. k. k. Geol. Reichs., iv, 552) .rhombohedral tables, probably trimetric, grouped in rosettes and renife, H.=2-2.5; G.=2-2.5. Vitreous; verdigris to apple-green; streak pa white. Composition.—2Cu²As+Ni²S+8H. Analysis by Lindacker, As 28.58, S 6.44, Cu 36.34, Ni 16.15, Fe 2.90, H 9.32=99.73. B.B. or APPENDIX. 501

alliaceous fumes, and fuses to a black mass. With borax and sait of phosphorus a copper reaction. Soluble after long heating in muriatic acid, the solution giving a yellowish brown precipitate with sulphuretted hydrogen.

LÖWEITE.—A yellowish saline mineral, from Ischl, approaching Astrakanite, (p. 379), affording the formula MgS+NaS+21H=Sulphuric acid 51'94, magnesia 13'20, soda 20'27, water 14'59=100. Karafiat obtained, (Haid. Ber. Wien, 1846, 266), Sulphuric acid 52'35, magnesia 12'78, soda 18'97, water 14'45, peroxyd of iron and alumina 0'66=99'21. G.=2'376.

MANGAN-VITRIOL, or Sulphate of Manganese.—Announced by Glocker, but imperfectly known.

MENEGHINITE, Bechi, (Am. J. Sci. [2], xiv, 60.—In compact fibrous forms, very lustrous; H. =2·5. Composition.—PbS+4SbS, Bechi, whose analysis afforded (loc cit.), S 17·522, Sb 19·284, Pb 59·214, Cu 3·540, Fe 0·344=99·904.

From Bottino in Tuscany, where it was obtained by Prof. Meneghini, along with Boulangerite and Jamesonite. The atomic proportions are those of tetrahedrite.

PARACOLUMBITE, Shepard, (Proc. Amer. Assoc., iv, 313, and Amer. Jour. Sci. [2], xii. 209).—In grains and short irregular seams, of an iron-black color, with a tinge of purple and a black streak; lustre imperfectly metallic. II. about 5. B.B. fuses readily to a black glass, which is not magnetic. With borax dissolves rapidly, the glass yellowish-brown while hot, but paler on cooling. Easily attacked by sulphuric acid, and gives reaction for fluorine; a heavy white precipitate falls, "unmixed with silica." The solution filtered was not rendered milky by boiling; it was decomposed by ammonia, and the precipitate "of mixed oxyds of uranium and iron was treated with carbonate of ammonia, which dissolved the latter, and showed its proportion to be small when compared with the former." Whence it is stated to consist probably of oxyds of iron and uranium, with some metallic acid not the titanic.

Occurs about a mile southwest of the village of Taunton, Mass., disseminated in very minutes quantities through a very large boulder, lying in a field contiguous to the highway.

PARTSCHIN, Haidinger, (Haid. Ber. iii, 440).—Found in grains in small monoclinic crystals, somewhat resembling Monazite. H.=6—6.5; G.=4—4.1. Color reddish-brown. Lustre greasy. Fracture splintery.

In sand from Olahpian in Hungary with Rutile, Ilmenite, Zircon, Kyanite. Named after P. Partsch, of the Vienna Museum.

PERCYLITE, H. J. Brooke, (Phil. Mag. [3], xxxvi, 181, 1850).—Monometric. In minute cubes; planes O, 1, I, i2. H.=2.5. Color sky-blue; streak similar.

Composition.—Contains, according to Percy, (loc. cit.), lead, chlorine, and copper, and probably oxygen; the quantity under analysis was too small for complete results. The examination gave, besides some water, chlorine 0.84, lead 2.66, copper 0.77, corresponding to equal atomic equivalents of these ingredients. Mr. Percy supposes that an equivalent of oxygen should be added, and writes the formula (PbCl-PbO)+(CuCl+CuO)+Aq. B.B. by slight heat the blue color changes to emerald-green, and reappears on cooling; in the outer flame, the flame is green within and blue at the edges; fuses very easily, and in a tube fumes were given off, but no odors were perceived. On charcoal in the inner flame metallic globules are obtained, which dissolve without residue in dilute nitric acid. With borax in the outer flame, a transparent bluish-green bead is obtained, which in the inner flame becomes turbid and brownish-red.

Accompanies gold in a matrix of quartz and red oxyd of iron, and is said to have come from La Sonora, in Mexico.

PRASOCHROME, Landerer.—A result of the alteration of chromic iron on the island Scyro, Grecian Archipelago, forming a dull green incrustation. Contains carbonate of lime colored by oxyd or chrome.



PROSOPITE, Scheerer, (Pogg. xc, 315).—Supposed qualitative trials on portions that were unaltered, taluminium, calcium, fluorine, and water. Occurs mines of Altenberg, in crystals which are mostly Raciin. Scheerer points out a relation in some an rytes; but the form is in fact very much like that of as shown in the angles and in the annexed figure, position from that given by Scheerer; \$\frac{12}{3} : \$\frac{12}{3} = 77^\circ\$; \$44, in Datholite); \$\tilde{O} : \$21=135^\circ\$, (same in D.); \$2: 2=52' in D.); \$2: 21 (top)=116\frac{1}{2}^\circ\$, (115^\circ\$ 26' in D.); \$23 (118^\circ\$ 9' in D.)

Is it possible that the fluorine has been introduce the process of alteration, and that the mineral is tered, nothing but Datholite? The name is from mask, and alludes to its deceptive or masked conditions.


RIOLITE, Fröbel.—A selenid of silver, consisting according to Del R 57.66, selenium 42.34—Ag Se². Occurs in small hexagonal tables of color and malleable, at Tasco in Mexico. Requires further examination. position and form would place the species in the Covelline Group, p. 54.

STRAKONITZITE, von Zepharovich.—A yellowish green steatite-li forming pseudomorphs at Mutenitz, near Strakonitz in Bohemia, with which is partly incrusted with quartz, and also sphene and pyrites in and quartz. It is soft with a greasy feel, and G.=1.91. Analysis at Zepharovich, (Jahrb. f. k. k. Reichs., iv, 695):

Si 53:42 At 7:00 Fe 15:41 Ca 1:37 Mg 2:94 The powder is pale yellowish, and becomes dull brown on heating.

TELLURIC OCHRE, (Tellurite, Nicol, Tellurige Saure, Petz), -Occurtive Tellurium at Facebay and Zalathna in Transylvania, in small ye whitish spherical masses, with a radiated structure; also as an earthy coposed to be Tellurous acid.

TUNGSTATE OF COPPER.—Announced by Dr. Genth, as occurr Cosby's mine near Pioneer Mills, Cabarras Co., North Carolina, along framine, Wolfram and Scheelite, the last in large, but not very distinct,



TURNERITE, Levy, (Ann. of Phil. xviii, noclinie. M: M=86° 10', P: M=99° 4' 138° 5'; P: e=138° 50. Cleavage par both diagonals of the prism, one more pe the other.

H. above 4. Lustre adamantine. Street grayish. Color yellow or brown.

Composition .- According to Children, alumina, lime, magnesia, and a little iron :

fers from sphene, of which it has been co variety, in containing very little silica and no titanium. It requires fur ination, in order to determine its place in the system.

Accompanies quartz, albite, feldspar, crichtonite, and anatase, at Mour Dauphine. It was distinguished by Levy, and named in honor of Mr. whose collection it was first form? whose collection it was first found.

URANIUM, BASIC SULPHATE OF, H. Dauber, (Pogg. xeii, 251, Jun Occurs in citron-yellow microscopic, rhombic or hexagonal tables, and is aggregations. An analysis afforded Sulphuric acid 40, oxyd of uranium ter 14.2=98.2, corresponding to 50, 18, 18H. Is it a simple chemical

WILSONITE, T. S. Hunt, (Logan's Geol. Survey of Canada, 1853). Cleavage perfect in two directions at right angles with one another.

square prisms; a cross cleavage at right angles with one of those cleavages and inclined 110° to 115° to the other. [According to the examination of fragments by the author, this last cleavage may be only a fracture, a supposition sustained by the wide variation mentioned in the angle of inclination]. H.=3.5. G.=2.765—2.776. Lustre vitreous, shining, occasionally pearly on cleavage surfaces. Color reddish, rose-red to peach-blossom-red. Subtranslucent. Fracture uneven.

Composition .- Analysis by T. S. Hunt:

B.B. whitens, becoming opaque, and losing water; fuses with intumescence to a white enamel. Occurs at Bathurst, C. W., with apatite, calcite, and pyroxene. Some resemblance in appearance to scapolite.

Mineral from Italy, (Sitzungsb. Wien. x, 179).—This mineral substance is probably a mechanical mixture. It is crystalline; light greenish to wine yellow; translucent; shining with a waxy lustre; streak white. II.=5.5. G.=2.969.

Composition.— Si #1 Ca Na P H
38.42 5.30 34.23 7.72 6.72 6.00

It affords no probable formula. Wholly soluble in sulphuric acid, and but little attacked by muriatic acid. B.B. on charcoal melts easily to a colorless blebby glass, phosphorescing. With borax easily forms a colorless glass.

Meteoric Minerals.—Several substances occurring in meteorites have been named by C. U. Shepard as minerals, which are imperfectly described and little known. See Am. J. Sci., [2], ii, 377, vi, 402. xv. 363. They are called Apatoid, Sphenomite, (so called from Sphene), Dyslytite, Iodolite, Chladnite, Chantonnite, Schreibersite, (changed by Haidinger to Shepardite), Hyposulphite of Soda, Hyposulphite of Magnesia, (Am. J. Sci., ii, 377), Olivinoid, (so called because like Olivine), Howardite, (ib. vi, 402), Partschite, (ib. xv, 366).

2. Additional notices of described species.

AMBER.—According to Prof. Goeppert, Amber is derived from at least eight species of plants besides the Pinites succinifer. The resin is supposed to have been altered to Amber through fossilization. Prof. Goeppert enumerates 168 species of plants represented by remains in Amber.—Monateb. Akad., Berlin, 1853, and Am. J. Sci., [2], zviii.

Anatasz, p. 121.—Kenngott obtains for O:1, 111° 42′, 1:1 (pyr.) 97° 51′, O:1i =119° 22′.—Min. Russl., 49.

BERTHIERITE, p. 78.—Specimens from the mine Neue Hoffnung Gottes, near Freiberg, afforded C. v. Hauer (Jahrb. k. k. Geol. Reichs., iv, 635), Sulphur 80.53, iron 10.16, antimony 59.30—99.99.

BISMUTHINE, p. 33.—An artificial sulphuret of Bismuth afforded G. Rose the following angles: $I: I=90^{\circ}$ 40', $i3: i2=53^{\circ}$ 40' and 126° 20', $I: i1=135^{\circ}$ 20', Pogg. xei, 402, 1854.

Bolz, p. 252.—Analyses by C. von Hauer, (Jahrb. k. k. Geol. Reichs., iv, 684):

- 1. C. di Bove, Si 45.64 \$\frac{1}{4}\$1 29.33 Fe 8.88 Ca 0.60 Mg trace \$\hat{H}\$ 14.27=98.72.
- 2. N. Holland, 38.22 81.(N) 11.00 trace trace 18.81=99.08.
- 3. Discovery Id., 87:12 20:00 22:47 2:99 trace 17:62=100:20.

Probably results of alteration of feldspathic or some aluminous mineral.

Sinopite, Hausm. is the Bolus of Sinope; Stolpenite, Kenngott, is the bole of Stolpen; Oropion, Glocker, is Bergseife, p. 252. The right to a name in each of these so-called species is very questionable.

CALAMINE, p. 313.—Altenberg crystals of Calamine have been measured by H. Dauber, Pogg. xcii, 245, June, 1854.

CALCITE, p. 435.—The Fontainbleau crystals contain, according to Delesse, upwards of fifty per cent. of sand. In one crystal, G. =2.84, he found fifty-seven per

cent. of mixed sand; in another sixty-two per cent.; another G.=2.58, per cent.; in a less perfectly crystallized spheroidal mass, eighty-thre Halle Zeitschr, 1854, 215. F. W. Wimmer describes a crystal of Calcite a sealenohedron -83, ib., 1854, 334.

CATAPLEITE.—The crystallization of Catapleiite, according to H. Dan agonal. The crystals have the edges replaced by the planes 1, 2, 4; 1½', 0: 2=122° 38½', 0: 4=107° 45½'.—Pogg. xcii, 239, June, 1854.

CHILDITE.—Domeyko's vanadate of lead and copper, p. 363, is named Kenngott. This is the second species so called, the name being a synon Göthite.

CHLOROPAL, p. 337 .- Named Unghwarite by Glocker, and regarded as cies by Kenngott. Occurs amorphous; H=25-3; G=2·10-2·16; grees streak greenish-white; lustre weak waxy. B.B. infusible, but become black in a glass tube, and gives off water. Muriatic acid takes up the iron. Von Hauer obtained in an analysis, (Kenngott's Min. Notizen, i

> Ĥ 1978=100·17. Fe 20.86

This result differs considerably from other analyses.

Chrysocolla from Chili, which have in the interior the fibrous structure a

tion of pure malachite, showing that the whole was once malachite. In an earthy Chrysocolla-incrustation from Chili, Berthier found sul (analysis p. 310); and in another Kittredge (anal. 11, p. 310) obtained

bonic nor sulphurie acid.

altered pyritous copper.

The Chrysocolla analyzed by Scheerer, (anal. 8, p. 310), occurs with is supposed to have resulted from the action of sulphate of copper on the Bischof observes (Lehrb. ii, 1885) that silicate of copper may be form the action of an alkaline-, lime-, or magnesia-silicate on sulphate or nitra in solution. He also shows that this silicate is decomposed by carbon in solution. He also snows that this sinches is decomposed by producing carbonate of copper. The silicate is slightly soluble in purtherefore may act in forming the pseudomorphs after carbonate of leatheuite, which have been described. Its solubility and formation by stated, account for its occurrence in hydrons silicates, as Allophane. silicates are furnished by the decomposing granite, and the sulphate of

CLAY AND CLAYEY EARTHS, EARTHY HYDROUS ALUMINOUS SILICATES .- V ounds of this nature are described on pp. 165, 249 to 253, and 327 to following are others:

Sphragide, Hausm.—A yellowish-gray earth or clay, speckled with Lemnian earth; Λημνια σφοαγις of the Greeks; Siegelerde of the German but little to the tongue, and falls to pieces in water. Analysis by Klaiv, 333, specimen from Stalimene, the ancient Lemnos.

Fuller's Earth, (Walkerde, Wern; Walkthon, Hausm) .- Farthy wil streak; greenish-gray, oil-green, white, yellowish, reddish, red, brown; G feel either greasy or harsh; adheres a little to the tongue; falls to piece Analysis by Klaproth, Beit. iv, 338, and Thomson.

Occurs in connection with the chalk, colite, &c. Found in England near Riegate, in Sussex; near Maidstone, in Kent; Woburn, in Bedfe Vahls, near Aix la Chapelle; Rosswein, in Saxony; Zwikowetz, in Bo

elsewhere.

Potter's Clay .- Analyses of Potter's Clay by Klaproth, Beit. vi, 2

Aubert and Berthier, Dict. Tech. xvii.

Severite. —A variety of halloysite, analysis by Pelletier, Beud. Tr. ii. Onkosin, Kobell. —In roundish pieces, having an apple-green color grayish or brownish; lustre weak, greasy; translucent; H.=2; G.=2 fine splintery. Analysis by Kobell, J. f. pr. Chem. ii, 295. From Sala fuses with intumescence to a white blebby glass; in sulphuric acid solu

5.15

	3	-	Ŧŧ	ì	i.	Z.	Ē
1. Sairemir Stalimene	FOR "- M	- 51	2 TH M		1 2	- 31	in. Throne
2 Fuller : Larth Liegale	- 1	3 - 124	₹1	144	- 5:		Serv. E mark
-							Na. 7 11 King.
Sean		11.5		5	1.75	_	Ting.
4 Marion	T 100		2411		_		Thousand Thousand
& Patter's Class Streets	t I	_	-				Xiar.
							Tripecs
7.							
& Charles	14:11			كنجز		Ti iz	. A. Inhal.
							ir. Polisine.
s Valet extincel.							

Assume French—Ansurate is greenest-white pearly grantist with distrage in one direction translinent E = 1 i = 20 i Parties of another of pe Ca. av. 121. If alone 114 water with most alumina a little magnesia and protocycle. of rou. A doubtle if not took species. From Bills, in Bobonius.

```
Chryster 1 mt — Two recent analyses of this materially 6. A Sreak, communicated to the author, by server dated Minister. Ang. 1.1884, affected,

5. £ F. Ze Ca Mg Na E E

1. 2056 2013 207 071 1188 2084 114 025 1184-218028.

Chygen 1074 18me as a tro-384 025 006 025

2. 2013 2888 148 036 1185 1185 1186 118 026 188-21808.

Chygen 1074 1807 184 018 186 1186 1187 114 026 188-21808.

Chygen 1074 1807 184 018 186 586 025 08 088.
```

These results of Mr. Boush give for the express ratio of R. R. St. 1988; 1987; 1074 and 1276 1920: 1966. Alling the expect of the protoxyle and peccayda, the rate for L-R S, tenders for 1.1 % and Rift. 1. % or very closely \$: 1. while the ratio for the expect of the product is and kill 1. We of very concept to 1, while the ratio for the expect of the product is and proving it is 1 to 1; the former of which ratios it, were expressed in a formula appears to be the characteristic of the species. Extends Insternate afforded the expect ratio for 1, R. S. 1124, 2126; 1076, and for R.-R. S. 200, 1. S. which gives the same expect ratio 5:1 meanly for the chases and alicha. Both o prespond to R. R.S. 2-Aq, with R. S. 2:2 in the Chinomite and I in the Insternate. The water is nearly wanting in the Chinamite according to Brush.

If we repard the third of the perturb in Brush's analysis as replacing silica, the oxygen ratio for B. H. Son becomes 1205; 1206 17 12; or between the bases and the rest 2504 1702=1 2; giving the formula (250-28), 2186 which is the formula leduced on pp. 289, 287.

Correx Glance, p. 46 —A crystal weighing half a pound has been found in the mines mear Angina. Tue-sayy. The Myunt Catty: Mine affords Copper Glance, and also Native Copper, Bed Copper, and Copper Pyrites.

COVERLINE, p.65.—The Govelline of Longenz in Saleburg, occurs mostly massive, but affords minute errestals, according to Kenneytt, which present faces of two hexagenal pyramids; the acuter pyramid has for its basal edges the angle 1855 24; and the inclination of a face of this pyramid on one of the other is 1860 24. Color: indigo-blue, with submetally conswhat greasy lustre, a little pearly on the cleavage face; streak black: H.=16-2. G=1806-4804. Analysis afforded Sulphur 84'30, copper 64'56, iron 1'14.-- Konngott's Min Notina, No. in.

DEWEYLITE, p. 255.-A variety from Fields (called Gyments by the author, but correctly Deweylite, as this is the earlier name; afforded you Wildermann, Jahrk k. k. Gool. Reiches, iv. 525. 51 4052, Mr. 6056, water 2172, Fe 042, C 052 2041. agreeing closely with Ellacher's analyses of this mineral from the same locality, (Anal. 4, p. 196).

An earthy variety from the same place affords Si 4936, Mg 28:30, R 16:23, Fe 0-69, C 476=99:25, affording the oxygen ratio for H. R. Si, nearly 8: 2: &

ELIASITE, p. 105.-This species differs widely from Pitchblende in its lower specific gravity and the large proportion of water.

Enargite, p. 87.—Crystals of Enargite, which are trimetric, have by H. Dauber. He obtained for I:I, 97° 53′. Other observed plane 21, 11, with the pyramids 1 and $\frac{1}{2}$. $O:11=140^{\circ}$ 29′; whence by calcul 136° 37′, $O:\frac{1}{2}=154^{\circ}$ 43′, $O:21=117^{\circ}$ 53′, $O:1=147^{\circ}$ 55′.—Pogg:2

Felderar.—M. Scheerer obtains for an albite from Snarum the oxic R, R, Si, 1:3:11; and as the ratio is intermediate between that of a goclase, he proposes to call it oligoclase-albite. A feldspar from the sof Norway, analyzed by C. Gmelin, he regards as consisting of 1 of o albite, and 1 of orthoclase; another from the Syenite of Ballons, as e of oligoclase and 2 of orthoclase; and the same for another from Ple lyzed by Delesse. Bull. Soc. Geol. de France, [2], xi, 146.—T. S. Hunar theoretical views on the composition of the Feldspars to the American at the meeting in 1854, at Washington. See Am. J. Sci., [2], xviii, 26

Gabronite, Beudant (Traité, ii, 94).—L. Sæmann observes that he has School of Mines, Paris, truncated square prism of the gabronite, wh the mineral is Scapolite. (Communicated to the author).

Galena, p. 39.—A variety in cubes, containing manganese, p. Hartenrod, near Gladenbach, afforded Sandmann, S. 18-80, Pb 83-52, 1-20, Ag 0-14=99-49. H.=2-5. G.=7-11. B.B. a strong manganese resonance. Ch. u. Pharm. lxxxix, 364.

Gibbsite afforded von Ha 64.35, water 35.65, phosphoric acid, a trace=100.—Jahrb. f. k. k. Reich

HEMATITE, p. 113.—Kokscharov has elegantly figured and describes of hematite crystals in his Materialen zur Min. Russlands. Besid enumerated on p. 113, he mentions $\frac{2}{3}$ as presented by Russian crystained for R: R 86°; for $\frac{2}{3}$, terminal edges 147° 23′ 13″, 111° 40′ the middle (or basal) edge 114° 46′ 20″.

HESSITE, p. 44.—This species, according to Kenngott, (Sitzb. Wien. x trimetric; the crystals show the faces it, it, I, besides another vertical termined.

Hydrous Chlorid of Sodium. Con Cl+4 H=Chlorid of Sodium. Con Cl+4 H=Chlorid of Sodium 62.0, water 38.0=100.

HYDROPHILITE, Glocker .- A name applied to Chlorid of Calcium.

IDOGRASE, p. 197.—Kohscharov has published an elaborate memoi fine figures on the Russian idocrase, in his Min. Russlands, p. 92. From the Poljakowsk mine he found O: 1=142° 46½. Jefreinoffite is idocrase from Finland, containing according to Ivanoff, Si 37'41, Ca 34 Fe 4'60, K 1'16, Na 1'70=99'07. It is usually yellowish-brown, be colorless. Kohscharov's Min. Russlands, 116.

ILMENITE, p. 115.—Kokscharov mentions the rhombohedron ‡R as Russian ilmenite. Min. Russl. 20.

IDDYRITE, p. 95.—Two analyses of this silver ore have afforded Smith the following results, (communicated to the author by letter, ville, Ky., Aug. 23, 1854):

Iodine, 52:934 53:109 Silver, 46:521=99:455 46:380=99:489,

with traces of copper and chlorine.

Kaolin.—The author is indebted for the mode of presenting the Kaolin, on p. 249, to M. Louis Sæmann of Paris. M. Sæmann observes drous silicates of alumina proceeding from the decomposition of the fel 300

THE THE THE PROPERTY OF THE PR position a size that the size

Exercise to the larger than the second of the second approach a tensor.

Exercise to the larger law or than the second approach a larger water with any larger than the second of the se different offer and offere with another to the last outside about a report Busch at a feature to the

The second of the Fourier conditions as the second of the

LEFFERD TARREST-REFERDS BY EVILLE AS INSTITUTE OF AUTOMOSIUS BY BETTER TO THE STANDARD FOR BY AND THE STANDARD CONTRACTOR OF AUTOMOSIUS BY AND BEST LOOK TOTAL TO THE STANDARD BY AND AUTOMOSIUS BANKS.

Latin retrained the Tile Surrection of Estimate in allowers and a president

Limitation will Enthalphic Principles Sciences with our limit of Associating to Villements. But Societies of Principles in Societies for the communication of States of the Indian termination of States of Line Integration of the Williams. Buther and and so, a that is sails. That hing at oxides or have, done than form a maintaine half containing TW is all facelity of the at done or a soil. Which is insare make and has furthern that out the soil has been expected as a full has been expected as a full has been expected. where made and the allowing many terms of the entropy of the terms are obtained and the property of the entropy

Markette—A specimen from Nauras afforded Phisfer. Ann. On the Pharms hasked the Thorse Mp 45 in Tall to Na and Kind & the Silvik Kinds. Plant I transfer to

 $M_0(a)=ax$ supremate there the second small it on the spheral characters of the games has been the attended of the minute has been supremated at the first part of the second part of the first at Victoria into x_i the second of the following measurements of the ಆಧರ್ಶಿಯ ಮತ್ತರದ ನಿರ್ಮಾಹಕ

Li Ange of Difference of the Axes small

1. Plane of the ages in the line of the shorter diagonal —threat it innectors Nominal States of the agency to exchange the first property of the shorter of

2. And e temperature spring, are: 7 - Park greet three of Liberthal , the from Norway , tark is vegreen from Karlat , the direct in this plates from Besterore. in quartz, from Betzbanya in ball to with thalesty vote, dark green from Gosber. (New York probably a strong tall) in instruction in strong and from Araks resarkitables in this leaves business, from Leonfelden i dark greenest, from Kingak

black in this leaves busidered from Leonfelderi dark grounds, from Kingik torstak directional; duliered from Magura in granite, black from Altenberg black from Him. Upter Austria.

3. Optical ages in the plane of the imper diagonal—Rown most from Prascata in six-sided tables, of-15; hown ages ind pyramids, from Cavings, ake N. N. 15, 22; hexag tables from Federalia, Tyrological alone. The back of groon from Greenwood Formals, peliti scalarees, from Karosulk, 15-25; chosent brown, from L. Balkal, 15-25; liver-brown, in large tables, 55.

4. Doubtful as to which diagonal computes with the mann of the option, and a

4. Doubtful as to which discount commune with the many of the options and Brown, from Moravia, 6°; liver-brown, from Gargenberg, Sushua, 5°, dark brown.

from Eden, Orange Co., N. Y., 2°; pistachio-green, from Gömör, 2° 30′; brown, from Siberia, 2° 40′, G.=2·582; sea-green, from Norway, 2°, chesnut brown, in granite, 0°-1°.

2. Angle of Divergence above 50°.

Plane of the axes in the line of the shorter diagonal. — Gray mics, f in granite, 50° 12'; from Zinnwald and Schlackenwald, in granite, 51°

1. Plane of the axes in the line of the shorter diagonal.—Gray mics, in granite, 50° 12′; from Zinnwald and Schlackenwald, in granite, 51° from the Tyrol, in granite, 52° 12′; colorless, from Siberia, 60° 30′.

2. Plane of the axes in the line of the longer diagonal.—Greenish-b Arendal, 58°; yellowish-brown, from Warwick, 59°; from Airolo, Schw 61° 12′; from Nertschinsk, in granite, 65°; green, from Rothenkopf, 7 colorless, from Gloria, Brazil, 66° 36′; from Skogbollt, near Kimito, Fin red albite, 67° 25′; from Weathersfield, * Connecticut, in coarse-grain G.=2*836, 67° 40′; colorless, from Josefs-Alpe, G.=2*713, 69° 10′; pinchb from Trachiros, Cape Goyaz, Brazil, 69° 25′; brownish to colorless, frown, Connecticut, G.=2*852, 70°, (No. 6 of Silliman, p. 218); from Null land, 70° 36′; blonde, from Pressburg, Hungary, 70° 40′; green, from goyt, Greenland, 71°; pinchbeck-brown, from Kakunda, Brazil, 71° 2 from Cam, Bohemia, 71° 40′; light-green, from Greenland, 71° 50′; p from Minas Geraes, Brazil, 72° 20′; pinchbeck-brown, from Hörlberg, 1 granite, 72° 25′; greenish-yellow, from Chester, Mass., G.=2*827, 72° 30 white, from Zwiesel, Bavaria, 74°; greenish-white, from Conceiçao, B colorless, from the Ural, 74°; gray, from Galmeikirchen, Upper Austri pinchbeck-brown, from Miask, Urals, 75° 25′; gray to colorless, from =2*802, 75°-76°; colorless, from Pressburg, Hungary, 76° 12′; pinchb from Engenhos Corallinhos, Brazil, 64°-65° and 68°-69°.

3. In the following, crystals not well defined, and position of the longe informed from the cleavage forms. From Lexuke 6° from Fourgers in Technology of the cleavage forms. From Lexuke 6° from Fourgers in Technology of the cleavage forms. From Lexuke 6° from Fourges in Technology of the cleavage forms. From Lexuke 6° from Fourges in Technology of the cleavage forms.

 In the following, crystals not well defined, and position of the long, inferred from the cleavage forms. From Irkutsk, 68°; from Fogaras, in Tri inferred from the cleavage forms. From Irkutsk, 68°; from Fogaras, in Train granite, 69°; colorless, from Lobming, Austria, 69° 20′; wine-yellow, from sas, 69° 45′; sea-green, from Elfdal, Sweden, 69° 58′; silver gray, from enwald, Bohemia, 70°; from Pressburg, 69° 42′ to 72° 24′; from 70°-71°; from Grobo, Bannat, 70°-70° 36′; from Gömör, Hun 24′; from Neuberg, Bavaria, 70° 40′; from Jamaica, 70° 54′; from Bohemia, 71° 15′; from Brazil, 71° 36′; from Mursinka, Poland, 71° 50′ yellow, from Utō, Sweden, 72° 50′; pale yellowish-green, from Paris, 1 (No. 41 and 42 of Silliman); from Ronsberg, Bohemia, 73°; from Skuttram 73° 30′; greenish, from Norway, 74° 10′; pale-green, from Chillon, St. 74° 24′; yellowish-white, from Zwiesel, Bavaria, 75° 10′; yellowish-g Serra de Conceiçao, Brazil, 76°.

4. Rose-red Lithia Micas.—From Maine, 74°, (No. 45 of Silliman); from

4. Rose-red Lithia Micas. - From Maine, 74°, (No. 45 of Silliman); fro field, Mass, 75°; from Siberia, 75° 40'; from Rozena, 76°; from Pennig, S 30'; from Massachusetts, in granite, (Goshen 1 No. 50 of Silliman), 76° 1

From a review of all the observations and the analyses, as far as they made, it appears that there are at least two great groups-one including and phiogopites, the other the muscovites and lepidolites. The line be last two is not at present distinct either in composition or optical charatween the two former there is a difference of composition, according to t made, and, as far as known, the optical angle of the phlogopites is hardly Judging from the descriptions of the specimens examined by Grailieh, but few phlogopites among them. The color and general habit of the p as well as their occurrence in granular limestone, will usually disting from either the biotites or muscovites. But more analyses are required the whole subject of the micas, and especially to ascertain what importa attaches to the distinction whether the plane of the optical axes lies in or shorter diagonal. M. Grailich shows that, with slight exceptions, the creases with the specific gravity in the mica of a given locality. Thus a from Pressburg, Hungary, have respectively the following specific gravit

Specific gravity, 2-714 2-735 2-755 2-782 2-790 2-793 2-7 Angles, 69-7 70-0 70-5 71-2 72-3 72-4 7 72.3 We refer to M. Grailich's paper for his mathematical details.

^{*} This must be an error, as we know of no mica in granite at Weather

MISPICKEL, p. 62.—A variety from near Mühlbach, in Transylvania, afforded von Hauer, Arsenic 45.00, sulphur 21.36, iron 33.52=99.88. Jahrb. f. k. k. Reichs., iv, 400.

NACRITE, TALCITE.—Nacrite has the feel of a soft earthy tale, and consists of minute grains or scales, white and pearly, with a greasy feel, much like Pholerite, although anhydrous. Taleite from Wicklow, Ireland, is similar. Analyses: Thomson, (Rec. Gen. Sci. May, 1836), 2, 3, Short and Tennant, (Thom. Min. i, 244):

Si X1 Fe Ca Mg Mn Nacrite, Brunswick, Me.,
 Talcite, Wicklow, 64.44 28.84 4.43 — 46.00 35.20 2.88 9.61 1.0, Thomson. 3.94 2.0, Short. 44.55 33.80 7.70 1.30 3.30 2.25 6.25, Tennant.

Vauquelin's analysis of Nacrite is referred to mica by Rammelsberg. It is anhydrous.

OTTRELITE. - Reported as occurring in Tuscany.

PARALUMINITE, Steinberg.—Includes anal. 12, 13, of Websterite, p. 390. A very doubtful species.

PENCATITE, Roth.—Analysis 1, of Predazzite; but not a good species.

ROCKS, (p. 247).—The following are recent analyses of different rocks:

- 1. Granite, from the Valorsin Valley, consisting of quartz, oligoclase, and white or brownish mica: Delesse, Bull. Geol. France, [2], vii, 424.
- Red Syenite of Egypt, consisting of quartz, red orthoclase, white oligoclase, and black mica: Delesse, ib., vii, 484.
- 3. Protogine of Mt. Blane, consisting of quartz, orthoclase, oligoclase, tale, and mica: Delesse, ib., vi, 230.
- 4. Porphyry of Lessines, having a green base, and the disseminated crystals being oligoclase: Delesse, ib., vii, 310.
- 5, 6. Diorites of the Vosges; 5, from Frondromé, fine crystalline, nearly compact in texture, consisting of feldspar and hornblende; G .= 2.945;-6, from Clefcy, consisting of oligoclase, hornblende, and mica; color black; G .= 2 902; Delesse.
- 7. Granulite (Weissstein), fine-grained, grayish-white color, from Krems; only 070 p. c. soluble in muriatic acid: E. Hornig, Wien. Akad., vii, 583.
- 8. Hornblende Slate, consisting of feldspar and hornblende, with some chlorite; G .= 3.008; from Miltitz in Saxony; contains small acicular crystals of hornblende: Bischof, Lehrb. de Geol.
- 9, 10. Mica Slate; 9, grayish, from Libethen in Hungary;—10, ib., from Ora-witza, Hungary: Bischof and Kjerulf, Bisch. Lehrb.
- 11, 12, Clay State; -11, from Siegen; -12, from Rothwaltersdorf, color bluish-
- black: Bischof, Lehrb.

 13. Ib. of violet color and having a silky lustre, from Nerothal, near Wiesbaden; G.=2.822; B.B. fuses on the edges to a gray enamel; muriatic acid decomposes 17.89 p. c., removing a fourth of the silica and alumina, all the peroxyd of iron, nearly all the magnesia, all the lime, and less than one-third of the potash: List, Ann. Ch. u. Pharm., lxxxi, 257. List obtained from this slate the sericite, (see p. 223), which is the source of the silky lustre.
 - 14. Clay Slate of greenish color from Naurod; G .= 2792; List, ib.
- 15, 16, 17, 18. Roofing Slate;—15, purplish-blue, feebly glimmering lustre; G.=2*884; Lower Silurian, of Kingsey, Canada East;—16, greenish-blue, silky surface; G.=2*711; Upper Silurian from Westburg, C. E;—17, Welsh roofing slate, resembling No. 15; G.=2*824;—18, from Angers, France, and resembling No. 16, but more pearly in lustre and somewhat talcose; G.=2*882; T. S. Hunt, Phil. Mag. [4]. vii, 237. Part of the iron in 15 and 17 he suggests may be peroxyd.
- Variolite of Durance, in Savoy; -a, the base of the rock; G.=2896-2934;
 general appearance somewhat like Euphotide, of a greenish to dark-green color. Contains disseminated spherules, (analysis 19 b), which are feldspathie, white or

greenish-white, and often changed to Kaolin; G.=2-923: Delesse, Ann xvii, 116.

20. Dolerite from Meissner, consisting, according to the analysis, of dorite, and 49.60 Augite: Heusser, Pogg. lxxxv, 298.

21. Trap, or Dolerite, from Eskifjord-Bucht, Iceland; A, composition soluble in muriatic acid (25:39 p. c.); B, of the part insoluble (74:13 p. c.) Bull. Geol. de France, [2], vii.

22, 23. Trap; 22, of Giants Causeway; 23, of Fingal's Cave: A. Strsen's Laboratory, Lieb. u. Kopp., 1852, 953.

24. Lava, from Hecla, Iceland, eruption of 1845; A, part soluble in n (83.25 p. c.); B, part insoluble (64.92 p. c.); the feldspar was easily deacids, and is supposed by the analyst to be Anorthite: Damour, loc. ci

25. Lava of Etna, from the eruption of 1852; consisting, according to of about 95 parts of Labradorite and Augite, 2 of Olivine, and 3 of May von Hauer, Sitz. Akad. Wien., xi, 87, 1853. (Abich obtained from the 148.83 Silica and a closely related composition, making the lava to comof Labradorite, 34.16 augite, 7.98 olivine, 3.08 magnetic iron).

26. Trachyte, from Külsbrunnen; G .= 2.701: Bischof.

27, 28. Pozzuolana from Vesuvius; A, part soluble in muriatie acid; soluble: L. Elsner, J. f. pr. Ch., xxxiv, 438.

 Trass, or Rhine Cement; A, part soluble in muriatic acid; B, par L. Elsner, ib., xxxiii, 21.

30. Clay, of a reddish fawn-color, from the river à la Graisse, Rigar yields to heated muriatie acid 12.95 p. c. of alumina and peroxyd of lime, and 1.92 of magnesia: T. S. Hunt, Phil. Mag. [4], vii, 238.

For other analyses see Bischof's Lehrb. der Geol., passim; Delesse's p. Bull. Geol. de France, [2]; and Ann. des Mines, [4]; Bunsen, on Vele (a paper of great interest), Pogg., lxxxiii, 197; E. Wolff on porphyrytic pr. Chem., xxxiv, 193; Damour, on volcanic rocks of Iceland, Bull. Geol [2], vii, 83; A. Streng, (paper referred to above); von Waltershausen ischen Gesteine," Göttingen, 1853.

		Si	X 1	Fe	Fe	Ca	Mg	Na	K	Ho
							-	~		
	Granite,		12.90	1.10		1.26		loss 9		0.40
	Red Syenite,	70.25		2.50		1.60			[00]	0.65
	Protogine,	74.25			Mn tr.	1.08	[,	4.17	01]	0.67
	Porphyry,	57.60		.00		3.23	['		92]	4.25
	Diorite,	48.50	17.10	-	Fe16.26		[6.10]			0.80
6.		48.90	18.50	-	11-92		[9.70]	2.35		1.40
	Granulite,	73.04	8-23	1.35	6.27	1.18	-	-	7-11	-
	Horn, Slate,	48.65	16.42	18:62	4.69	7.16	2.32	0.89	0.56	0.21
9.	Mica Slate,	52.01	13.64	19.72	-	0.67	5.42	0.55	5.22	2.49:
10.	"	50.88	26.69	8.48	-		1.19	272	4.52	4.19:
11.	Clay Slate,	50.01	34.74	_	3.73	-	0.87	0.04	7-21	3.27
12.	"	6172	19.55	-	8.54	0.55	1.08	_	4.81	374:
13.	"	55.84	15.62	4.86	8.25	1.40	0.50	170	6:13	5.19:
14.	"	59.93	15.01	1.85	5.62	4:56	1.43	6.08	2.44	2.43:
15.	Roofi'g Slate,	54.80	23.15	_	9.58	1.06	2:16	2.22	3.37	3:90:
16.	"	65.85	16.65	_	5.31	0.59	2.95	1.31	3-74	3.10:
17.		60-05	19.70	_	7.83	1.12	2.20	2.20		3.30:
18.	"	57.00	20.10	_	10.98	1.23	3.39	1.30	1-78	4.40:
	r (a.	52.79	11.76		11:07	5:90	9.01	8.07	1.16	4:38
19.	Variolite, $\begin{cases} a. \\ b. \end{cases}$	56.12	17:40	7.79	Er 0.51	8.74	3-41	372	0.24	1'98:
20.	Dolerite,	48.00	16.28	_	Fe15.55	9.50	3.85	2:01	2.01	2.800
21.	Trap,	64.28		_	11:43	3.19	0.45	4.76		1-09
	" (A.	13.18			8.49	0.63	0.45			b
	" B,		12.25	-	2.94	2.56	_	476	0.52	
22.	Trap,	52.18	14.87	_	11:40	10.56	6:46	2.60	0.69	
23.	a de	700 500	14.80		13.08	12.89	6.84	2.48	0.86	
					-500			-	- 00	

```
X1
                                   Fe
                                            Fe
                                                    Ca Mg Na K
                                                                            H or ign.
24. Lava, Heela, 54.76 13.61
                                                                       1.21 0.07°=98.17, D.
                                                    6.44 1.35 3.41
                                           15.60
                A;
                   16.61 0.16 10.08
                                                    2.44 1.21
                                                                0.99
                                                                       0.45
                                                                             -d =33·25.
             A, 16.61 0.16
B, 38.15 13.45
                                                    4.00 0.14 2.42
                                                                       0.76 -
                                                                                _e =64.92.
                                                                                   Mn0.63, H.
25. Lava, Etna, 49.63 22:47
                                           10.80
                                                    9.05 2.68
                                                                3.07
                                                                       5.13 1.00=99.09, Bi.
26. Trachyte,
                    64.21 16.98
                                   6.69
                                                    0.49 0.18 4.41
27. Pozzuolana,
                                   4.76
                                                                6.23
                                                                       4.37 - Na Cl2.56, S.
                   59.15 21.28
                                                    1.90
             \left\{ egin{array}{c} A, \\ B, \end{array} \right.
                   10.25
                           9.01
                                   476
                                                    1.90
                                                                       1.50
                                                                             -=27.42.
                   48.90 12.27
                                                                6.23
                                                                       2.87 -
                                                                                 =70.27.
28. Pozzuolana,
                    59.81 16.36
                                   4.56
                                                    1.58
                                                                      14.16
                                                                             - NaCl3-25, R.
             A, 10.25 2.57
B, 49.56 13.79
                                   4.56
                                                          1.58
                                                                       1.50 -
                                                                                -=20.46.
                                                                                <del>-76.01</del>.
                                                                       12.66
29. Trass,
                                                    5.41 2.42 3.56
                    48.94 18.95 12.34
                                                                        0.37 7.66(Am incl) E.
                A, 11.50 17.70 11.77
                                                    3.15 2.15 2.44
                                                                       0.29 -=49.01.
       ic
              B, 37.44 1.25
                                                    2.25 0.27 1.20
                                                                       0.08
                                                                                    42.98.
                                  0.57
30. Clay,
                                                   5.32 2.62 2.61 2.85 7.75f Po.74, H.
                   50.81 21.70 5.60
    a. Add 0.05 oxyd of copper.
d. Add titanic acid 1.24.
                               b. Add titanic acid 0.80. c. Add titanic acid 1.72,
e. Add titanic acid 0.48. f. Iocludes 3.25 of carbonic acid.
```

M. G. von Helmersen has a paper on the conductibility of heat of different rocks, in Pogg. Ann., lxxxviii, 461. Despretz published results on the same subject in the Ann. de Ch. et de Phys., vols. xix and xxxvi; and in the Compt. Rend., xxxv, 1844.

SCORDITE, p. 419.—Crystals from Nertschinsk afforded Kokscharov the planes in figure 561, with also 27 and 27. The faces 37 are vertically striated, and 1 are mostly rough.

SELADONITE (Terre Verte), p. 165.—A green earth accompanying the specular iron of Framont afforded Delesse—

```
Si H Fe Fe Mn Mg Ca K Na H
43:50 16:61 8:88 11:83 0:80 6:66 trace 3:14 0:69 7:15=99:26
```

It occurs in pyroxene rocks with garnet, and results as Delesse observes from their decomposition. Boiled in concentrated muriatic acid it is discolored and the silica separates as a powder.

Delesse states that in attacking the mineral with acids, the bases which resist the action longest are the alkalies; the magnesia, oxyds of iron, and alumina yielding first.

Bischof observes the same fact with mica slate; and it explains why minerals containing alkalies are often attacked by acids with difficulty.—L' Institut, June 14, 1854.

SCHREIBERSITE, p. 53.—Dr. J. Lawrence Smith finds that the Schreibersite (Patera) is quite common in meteorites, being often mistaken for magnetic pyrites. The following are the results of three analyses, two of them incomplete:

```
Cu Si
                                      <del>X</del>1
     P
           Fe
                 Ni
                       Co
                                            Ca
          57-22
                       0.32
                            tr. 1.62 1.63 trace
   13.92
                25.82
                                                   0.13=100.66.
2. 14.86
         56.04 26.43 0.41 tr.
                                   Not estimated.
```

Not estimated.

No. 1 was detached in small pieces from the meteorite: No. 2 by dissolving away the iron and separating with great care; the silica, alumina, and lime were almost entirely absent. The mineral, according to Smith, consists of 1 P, 2 Ni, 4 Fe—Phosphorus 15.47, nickel 29.17, iron 55.36—100. (Communicated to the author).

3. 14.53 56.53 28.02 0.28 tr.

Selbite, Haidinger.—Regarded as a carbonate of silver, but probably only a mechanical mixture. Color ash-gray to black. Reported from Wolfach, in Baden, and the Mexican mines where it is called Plata Azul.

SERFENTINE, p. 282.—On supposed pseudomorphs of serpentine after hornblende, pyroxene, and olivine, Th. Scheerer, in Pogg. xell, 287.

SMALTINE, p. 56.—The Smaltine containing 11 to 19 per cent. of iron, from Schneeberg in Saxony, (analyses 3, 4, p. 57), is the Safflorite of Haidinger, (Handb. bestim. Min. 1845) or Eisenkobaltkies. It is essentially the same mineral in composition with the Chathamite of Shepard, (Shepard's Min. 1844).

4

The Chathamite of a new opening at Chatham, Ct., has been recently Dr. F. A. Genth, with the following results, (Rep. Cryst. Palace of N. Y.

Fe 11-85 Co 3-82 Ni 9 As 70-11 S 478 67-16 (loss) 5-62 12-92 3-85 10-

The Eisenkobaltkies of Modum, according to Kenngott, is trimetric ins ometric. It afforded him a vertical prism of 155°, parallel to whose p age took place; there were also two macrodomes and a brachydome for tin-white; streak black. Chathamite has not been observed in ea The name Smaltine is sometimes written Smaltite.

STANNITE, Breith.—Amorphous, of a pale yellowish white color, with l H.=65; G.=3-545; fracture conchoidal. Contains according to Plat hix, 435), Silica, alumina, and 36.5 per cent. of oxyd of tin. B.B. infubably a mechanical mixture. From Cornwall.

TANNENTER, p. 73.—Forms trimetric, according to H. Dauber, the flatt presenting the planes I, ii, 11,\frac{1}{2}. ii: 1\frac{1}{2}=129° 14', ii: \frac{1}{2}=105° 13\frac{1}{2}', I: \frac{1}{2} $O: 11=140^{\circ}$ 46'. [Or doubling the vertical axis, the planes are I, it ing for O: 11, 131° 28', and making the dimensions very near those α that is, $I: I=102^{\circ}$ 50½', $11:11=62^{\circ}$ 56'.]—Pogg. xeii, 241.

TERATOLITE, (Eisensteinmark, Terra miraculosa Saxonise).—Pale vice grayish; compact earthy; H.=2·5—3; G.=2·5. Composition, Si 41-6 Pe 12·98, Mn 1·68, Ca 3·04, Mg 2·55, K 0·93, H 14·20, Schüler. From the near Zwickau, Saxony.

TETRADYMITE, p. 21.—The Tetradymite of the "Tellurium Mine," Fi Virginia, affords Dr. F. A. Genth, (communicated to the author by letter adelphia, August 23, 1854),

Bismuth 53 85,

Tellurium 46-67=100-52,

after deducting about a half per cent. of gold and quartz. Only a traium was found. This is the same mineral analyzed by Fisher. The min locality is broad foliated, and occurs in mica slate.

Tetradymite occurs also, according to Dr. F. A. Genth, near Pioneer arras Co., N. C., at Monroe Mine, in Stafford Co., and at Rogers' Gold M

Tetrahedrite, p. 82.—I, from Mornshausen, near Biedenkopf:—Occurs of quartz and barytes in greenstone; H.=4; color light steel-gray; cherry-red. II, from Stahlberg near Musen, with spathic iron; H.=4 streak black, somewhat brownish. Analyses by Sandmann, (each me analyses, Ann. Ch. u. Pharm. lxxxix, 364),

S Sb As Cu Fe Zn Ag Ni 24.61 25.65 1.65 38.17 1.59 6.28 0.62 trace=98.57. 25.52 19.71 4.98 38.41 2.29 6.50 0.69 trace, quartz 0.36

Schwatzite, Kenngott, includes anal. 20, p. 84; and Freibergite, the ar Tetrahedrite or Polytelite of Glocker.

THORITE, p. 312.—The following method is proposed by Sæmann for dis the species Thorite. The powder is decomposed easily by muriatic acid, e heated; after adding some drops of sulphuric acid to the solution, it evaporated to dryness; then turn some cold water on the white residue solves out the sulphate of thoria-a salt which has the property of forr cipitate in flocks which collect at the bottom of the platinum crucible, the liquid gelatinous if the solution is a strong one.—A pseudomorph (orangite) after orthoclase is described by H. Dauber, Pogg. xcii, 250, .

TOPAZ, p.259.—According to a recent memoir by H. St. Claire Deville and topaz and some other silicates containing fluorine, when highly heated. orine as fluorid of silicium. Topaz thus loses 28 per cent of this fluc arrive at \$187 as the formula of topaz, part of the oxygen of the silic placed by fluorine. Compt. Rend. xxxviii, 817.

513

It is remarkable that analyses apparently equally trustworthy, recent as well as old, give for Andalusite the two formulas \$\frac{1}{2} \text{if}^{\frac{1}{2}}\$ and \$\frac{1}{2} \text{Si}^{\frac{1}{2}}\$; for Staurotide the two \$\frac{1}{2} \text{Si}^{\frac{1}{2}}\$, \$\frac{1}{2} \text{Si}^{\frac{1}{2}}\$; for Sillimanite, \$\frac{1}{2} \text{Si}^{\frac{1}{2}}\$ and perhaps others; and now topaz in the present state of chemistry of the species, is divided between \$\frac{1}{2} \text{Si}^{\frac{1}{2}}\$ and \$\frac{1}{2} \text{Si}^{\frac{1}{2}}\$. Moreover Sphene, (\$\frac{1}{2}\$) \$\text{Si}^{\frac{1}{2}}\$ is homeomorphous with Euclase (\$\frac{1}{2}\$) \$\text{Si}^{\frac{1}{2}}\$; and all the above are pleomorphous with Tourmaline, (\$\text{R}^{2}\$, \$\frac{1}{2}\$, \$\text{B}\$) \$\text{Si}^{\frac{1}{2}}\$; and the uniformity on this species makes it more incredible that the variations in the case of the other species should be all attributable to errors of analysis.

TOURMALINE, p. 270.—Kenngott has deduced essentially the same formulas for Tourmaline as that given on page 271, except that he writes B² O⁵ for boracic acid, and regards it as replacing alumina. Min. Notizen, No. ix.

TRIPHYLINE, p. 406.—Altered forms of triphyline are mentioned on page 407. L. Sæmann states that Melanchlor (p. 428) is also a result of the alteration of Triphyline, and occurs as an incrustation on unaltered Triphyline; that Heterosite, Pseudotriplite and the Norwich mineral are the results of a further change; that Hursults and Alluaudite are connected with Triplite in origin. (Communicated to the Author.)

Tunquois, p. 405.—The bone Turquois, or Odontolite, according to L. Sæmann owes its color to a phosphate of iron, as stated by Dufrénoy, (Min. ii, 361). True turquois, when decomposed by muriatic acid gives a fine blue color with ammonis, which is not the case with the odontolite. This mineral has a fine turquois blue color, and a very compact but earthy texture. It is formed along with fossil bones or teeth, being like vivianite connected with organic phosphates in its origin.

Volgerite, p. 142.—Cumenge's mineral, p. 142, is named Cumengite by Kenngott.

Weissigite, p. 254.—The following are additional particulars respecting this mineral, from a note by M. Jenzsch, communicated to the author by L. Sæmann.—Cleavage parallel to a hemidome pertaining to the brachydiagonal; also in two vertical directions meeting at 118°; also parallel to the macrodiagonal. Crystals small and not very distinct. Composition, Si 64.5. 21 17.0, Mg 0.9, K 14.6, (Na, Li), 2.2 ign. 0.8. Insoluble in muriatic acid. From Weissig in Saxony.

The proportion of silica, alumina, and alkalies, differs little from the same in

Orthoclase; and is it not that species !

Wöhlkeite, p. 343.—H. Dauber has figured and described a crystal of Wöhlerite, (Pogg. xcii, 242). He gives the crystal the same position as that by the author. Adopting the lettering of f. 494, it contains the planes—

Oauber's lettering, a m g h b k d o p d

All but two of which planes are in Desloizeaux's figure, from which f. 494 was taken, and one of these two, $\frac{3}{2}I$, is probably the correct symbol for that lettered $\frac{1}{8}I$, from Deseloizeaux. The angles according to Dauber vary considerably as the faces are not very brilliant; and in fact he makes the brachydiagonal what Deseloizeaux makes the macrodiagonal. The latter gives for I on the broad face lettered iI, 135° 27', whence I: I=90° 54', while Dauber obtained 134° 51', giving 89° 42' for the same I: I. Using the lettering of I, 494, the angles obtained are as follows:

Dauber, it: \$\frac{1}{4} = 109\circ 28'. Descloizeaux, 109\circ 57'.

it: \$\frac{3}{4} = 130\circ 45'. \$130\circ 32'. \$116\circ 56'. \$16\circ 56'.

Dauber's measurements of I: it however varied from 134° 21' to 135° 24'.

Wolkonskoite, p. 339.—This species has H.=2-2·5; G.=2·213-2·303, Breithaupt, Analysis by Ivanoff, (Kokscharov's Min. Russl. 145): Ši 36·84, Čr 18·85, Fe 17·85, № 3·50, № trace, Ča 1·39, Й 22·46=100·89.

Zinc Bloom, p. 460.—Occurs with ores of zinc and lead at Bleiberg and Raibel in Carinthia, and has probably resulted from the decomposition of Calamine.

ANNOTATED INDEX TO THE USEFUL METAL METALLIC ORES.

GOLD.—Native Gold, (p. 7). Distinguished from all minerals it resistant under a hammer; its cutting like lead, although consider its resisting the action of nitric acid, hot or cold; its high specific graduals occurs in Gold Amalgam, (p. 15), Sylvanite, (p. 64) and Naga Also sometimes in traces in Pyrites, Galena, Chalcopyrite, Native Telling

PLATINUM.—IRIDIUM.—PALLADIUM.—Native Platinum, (p. 12 of the platinum of commerce, is distinguished by the same tests as go mainly on account of its malleability that it occurs in flattened grain Platiniridium (p. 13) is another ore somewhat harder. Iridosmine (bles platinum; but it scratches glass, and gives the reaction of osm being rather brittle. Native Palladium, (p. 14).

SILVER.—The important Silver minerals are: 1, Native Silver, (1) and malleable like gold, the only one that has a white color; 2, Sile Sulphuret of Silver, (p. 37), blackish lead gray, cutting (unlike the follo like pure lead, cubic in crystallization; 3, Pyrargyrite and Pronatite or Ore, (pp. 77-78), ruby red to black, always giving a bright red powde benite or Gray Silver ore, (p. 79), steel gray, rather brittle and powde 5, Stephanite or Brittle or Black Silver ore, (p. 86), iron black, and gived black powder; 6, Kerargyrite or Horn Silver, (p. 92), resembling a gray or greenish wax, and cutting like wax; 7, Embolite or Chloro-briver, (p. 93), like the last, but more greenish. These ores yield silver heated on charcoal. Besides these, Tetrahedrite or Gray Copper, (p. 8 valuable silver ore; Galena, (p. 39), which, although seldom yielding of five ounces to the ton, affords a considerable part of the silver of comother rarer silver ores, see pp. 16, 35, 43, 44, 48, 64, 71, 74, 76, 85, 87, 5

COPPER.—The more valuable species are: 1, Native Copper, (p. 17) pyrite or Copper pyrites, (p. 68), of a brass yellow color, scratched eas point of a knife blade and giving a greenish black powder; 3, Barnhard and Cuban, (p. 68), which are similar to the last but paler; 4, Erubese Copper, (p. 38), pale yellowish, with a slight coppery tinge, but tarnishily to purple, blue, and reddish tints; easily scratched with a knife blad der grayish; 5, Copper Glance or Vitreous Copper, (p. 46), of a dark le or, and powder similar, resembling some silver ores, but yielding copy silver, when heated on charcoal; 6, Tetrahedrite or Gray Copper, (p. 88), what paler steel-gray color and powder; 7, Red Copper, (p. 101); 8, B (p. 109, 136); 9, Malachite or Green Carbonate of Copper, (p. 458), of a color, sometimes earthy in the fracture and sometimes silky; 10, Azurites achite, (p. 459), of a rich deep blue color, either earthy or vitreous in the above are acted on by nitric acid, and the solution deposits a recopper on a strip of polished iron; 11, Chrysocolla, (p. 309), a silicat resembling the Green Carbonate, but paler green, and usually having a clever fibrous), a smoother surface and somewhat waxy lustre, althoug usually only as an incrustation; 12, Alacamite or Chlorid of Copper, deeper green than Malachite; 13, Sulphate of Copper, in solution, (p. rarer ores, see pages 36, (arsenical); 43, (selenid); 48, 65, 73, 80, 82, (different sulphur, arsenical and antimonial ores); 309, (silicate); 36 (chromates, vanadate); 375, 380, (sulphates); 412, 420, 421, 425, (phe arsenates).

QUICKSILVER.—The only valuable ore is Cinnabar, (p. 48), of a b brownish black color, with always a red powder, and affording fumes of when heated on charcoal. There are also Native Quicksilver, (p. 14); Amalgam, (p. 15); Selenid, (p. 52); Chlorid and Iodid, (p. 89, 96). Tetrahedrite (p. 82) sometimes contains this metal.

LEAD.—Galena (p. 39) is the only abundant lead ore; it is a lead-gray brittle ore, yielding lead, when heated with charcoal. For other ores see pp. 42, 44, 65, (Selenid and Tellurids); 109, 117, 126, 127, 128, (Oxyds); 359, 361, 362, (Chromate and Vanadate); 348, (Tungstate); 370, 371, 372, 374, 375, 390, (Sulphates), of which Anglesite (p. 370) is the common one; 400, 401, (phosphate and arsenate); 452, (carbonate).

ZINC.—The most important ores are: 1, Smithsonite or Carbonate of Zinc, (p. 447), and 2, Calamine or Silicate of Zinc, (p. 313); they are alike in a white, gray-ish-white, or greenish-white color, commonly a slight waxy lustre and smooth look, (often stalactitic or mammillary), yet sometimes earthy; and a hardness such that the surface is scratched with a knife blade with some little difficulty. They differ in their action with muriatic acid; when the surface is drusy, the silicate shows projections of minute rectangular prisms. Zincite or Red Zinc ore, (p. 110), is also important; it is bright red and very distinctly foliated. Blende or Sulphuret of Zinc, (p. 45), is a common ore, having a yellow to black color and resinous lustre, and distinctly cleavable; the black varieties are sometimes a little metallic in lustre, but the powder is nearly or quite white. For other Zinc Ores, see pp. 127, (oxysulphuret); 156, 189, (silicate); 384, (sulphate); 409, (phosphate); 418, (arsenate); 460, carbonate).

COBALT, NICKEL.—The ores of cobalt of first importance are, Smaltine, (p. 56), and Cobaltine, (p. 57), both of nearly a tin-white color, with the powder grayish-black, color sometimes verging slightly to gray. The Black Oxyd of Cobalt, (p. 136), a kind of bog ore and very impure, is sometimes sufficiently abundant to be valuable. The useful ores of nickel are Chloanthite or the nickeliferous smaltine, (p. 56), Gersdorffite or Nickel Glance, (p. 58), and Copper Nickel, (p. 52), the latter distinguished by a pale copper red color. For other ores of Cobalt, see pp. 41, 44, 63, 67, (sulphuret or arseniuret); 385, (sulphate); 416, (arsenate); 461, (carbonate); of Nickel, 42, 49, (sulphuret); 53, 59, (arsenical or antimonial); 339, (silicate); 386, (sulphate); 418, (arsenate); 461, (carbonate).

MANGANESE.—Common, as Pyrolusite, (p. 125), and Psilomelane. (p. 135), both black or grayish-black ores, and having little lustre, and a blackish streak or powder, in which last particular they are distinct from the iron ore called Limonite, with which they are often associated, and also from Hematite or Specular Iron. Wad (p. 136) is an earthy bog manganese, sometimes abundant and valuable. Manganite (p. 130) is abundant in certain mines, but is of little value in the arts, because of its containing so little oxygen, (one third less than Pyrolusite), to which fact Beudant alludes in his name for the species, Accrdese; it differs from pyrolusite in its reddish-brown powder. For other manganese ores, see pp. 41, 56, (sulphuret); 53, (arsenical); 117, 118, (oxyds); 167, 186, (silicates); 399, 406, 408, (phosphates); 446, 452, (carbonate).

CHROMIUM.—Chromic Iron, (p. 106), a grayish-black little lustrous ore, occurring mostly in Serpentine, is the source of chrome in the arts. For different chromates, see p. 359.

IRON.—The important iron ores are: 1, Hematite or Specular Iron, (the asparing or bloodstone of Theophrastus), (p. 113), characterized by its blood-red powder, and occurring either earthy and red, or metallic and dark steel gray; in the latter condition very hard, a knife point making no impression;—2. Magnetite, or magnetic iron ore, (p. 105), as hard as the preceding, but having a black powder, and being attractable by a magnet;—3, Limonite, called also brown hematite, (p. 131), a softer hydrous ore, affording a brownish yellow powder, earthy or semimetallic in appearance, and often in-mammillary or stalactitic forms;—4, Chalybite, or Spathic Iron, (p. 444), a sparry ore, of grayish, grayish-brown, and brown colors, very distinctly cleavable, turning brown to black on exposure. The common clayey iron ores are

many one either of fracture from immune, or Remander when his receiver when property resident property or released regions for his first a figure of from the first prince of the many common area of from a figure of from his are common area of from a figure and the prince are common as all aminer over of other from the figure for a similar first a property and Hospitals, in G. C., are white from his figure from his figure of the figure from the figure of the fi

TIV—The only valuate one is the local of I'm or Connection, 3, but miners of a tieft record to track many structures great or gravitations may metallic apparation the crystal monthly have a very tree. In any scenes is a supported 1, 700, and a spacingly found in this. and some other miners, species.

THAVITE -The only one of the name of any value is Route. In 1

AMENTI.—Native Arway 1. 22 is one source of arsenie, but it to be of much arall and deposited 1.22, a single-related following what yearly mineral and Lamper 1. It, impute red and vibraconal mostly between the site arts from the armanesi was of iron, colonia, and t

ANTIMONY — Minera, or 5-res Antonome, p. 31, is the source of the commerce. It is a least great are monelly friends or in principality distinguished from a similar are of management by its perfect diagrams of its easy finishing. Antonomy society and it improves over of head an 72, and of metals, pg. 54, 56; and as cay in 146, 141.

BENITE — Native Benneth p. 2: , the source of the metal in winner, with a faint reddied tings, has a perfect deavage, and is very i state manner, are see pp. 14 in 33, 44 if 71.51.58.141, oxy i . 15 44; cartenate,

GENERAL INDEX.

Abichite, 428. Allagite, 167. Ammiolite, 142. Ammonia alum, 388. Abrazite, 322. Allanite, 208. Acadiolite, 819. Allemontite, Arsenical An-Ammonia, Bicarbonate, 454. timony, 22. Acerdese, 130. Muriate, 92. Allochroite, 191. Achates, 151. Phosphate, 413. Sulphate, 879. Achirite, 809. Allogonite, 410. Achmatit, 206. Allomorphite, 366. Amoibite, 58. Achmite, 176. Allophane, 836. Amphibole, 170. Allophane, Opal, 837. Alluaudite, 407, 518. Achroite, 271. Amphibolite, 172. Acicular Bismuth, 81. Amphigéne, 281. Almagrerite, 871. Amphodelite, 234. Aciculite, 81. Almandine, 191. Alstonite, 451. Anagenite, v. Chrome ochre. Analcime, 318. Acid, Antimonous, 141, 142. Arsenous, 139. Boracic, 144. Altaite, 44. Analcime carnea, 200. Carbonic, 144. Alum, Native, 382. Anamesite, 247. Muriatic, 97. Ammonia, 383. Anatase, 121, 508. Feather, 381. Iron, Magnesia, Manganese, Soda, 382. Sulphuric, 148. Anauxite, 505. Sulphurous, 143. Andalusite, 257. Tungstic, 143. Acmite, 165, 176. Andesine, 236. Andreasbergolite, 323. Alumina, 111. Andreolite, 328. Actinolite, Actinote, 170. Fluate, 98. Adamant, 24. Fluosilicate, 259. Anglarite, 416. ydrate, 128.
Anglesite, 370.
ydrous Silicates (car-Anglesite, Cupreous, 390.
thy), 165, 249 to 258, Anhydrite, 369. Adamantine spar, 111. Hydrate, 128. Hydrous Silicates (ear-Adinole, 248. Adularia, 242. Ankerite, 441. Annabergite, 418. 837 to 840, 504. Ædelforsite, 155, 308. Aerhenstein, 366. Mellate, 475. Phosphates, 423, 432. Anorthite, 234. Ægirin, 160, 172. Ærosite, 77. Sulphate, 381, 388. Anthophyllite, 172. Æschynite, 857. Alumine fluatée alcaline, 97. Hydrous, 175. Aftonite, 82. sulfatée, 381. Anthosiderite, 304. phosphatée, 424. Agalmatolite, 252, 276. Anthracite, 26. Aluminitė, 889. Anthraconite, 489. Agaphite, 405. Agaric mineral, 488. Alumocalcite, 151. Antiedrit, 828. Agate, 145. Alumstone, 388. Antigorite, 281 Agnesite, 462. Aikinite, 81. Alun, 382. Antimoine natif, 21. Alunite, 388. oxid6 140, 141, 142. Alunogen, 381. Amalgam, Native, 15. Gold, 15. Agustite, 896. Akanticon, 206. oxidé sulfuré, 141. sulfuré, 38. sulfuré nickelifère, 59. Akmit, 176. Alabandine, 41. Amausite, 242. sulfuré plombo-cupri-Amazon Stone, 242. Alabaster, 377, 489. fere, 80. Alalite, 159. Amber, 466, 508. Antimon, Ġediegen, 21. Amblygonite, 409. Amethyst, 145. Oriental, 111. Alaun, 382. Antimon arsen, 22. Antimonate of lead, 142. Alaunstein, 388. Antimonblende, 141. Albin, 304. Albite, 240. Amiant, 172. Antimonblüthe, 140. Alexandrite, 122. Amianthoide, 174. Antimonglanz, 83. Algerite, 208. Amianthoide magnesite, 183. Antimonite of lime, 410. Alizite, 339. Amianthus, 172. of quicksilver, 142.

The numbers in this Index refer to the Second Volume. For an Index to the First Volume, see Table of Contents, following the Preface.

Argentine, 439.

Aurichalcit

Auripigmen

Aurotelluri

Automolite

Autunite, 4

:Aventurine

Axinite, 211

Azorite, 350

Azure spar,

Azurite, 459

Babingtonit

Bagrationite

Baierine, 35

Baikalit, 15

Balas ruby.

Ballesterosit

Baltimorite.

Bamlite, 264

Baralite. 54.

Barolite, 44:

Bareseletit.

Barsowite, :

Barvia, Car

Barytier, if

Saryt Hallet

Party Figure 19 Party Figure 1

<u>...</u> +2.7± Batta crite ... Barrers

Ball to Lev

DARIO TELLANDO DARIO DE TRADES SALLANDOS SALLA

34 - 34 - 34 - 34

المستعدية

Cart. of

Su ; Eat

Sulphat

feldspa

Antimonial copper, 73. copper glance, 82. lead ores, 72-87. nickel, 53. ochre, 141, 142. ail∳er, 35. sulphuret of silver, 77, Arquerite, 15. 79. Antimonite, 33. Antimonkupferglanz, 82. Antimonnickel, 53. Antimonnickelglanz, 59. Antimonocher, 141. Antimonophyllite, 140. Antimonoxyd, 140, 141. Antimonsaures bleioxyd,142 Arsenic, Native, 22 Antimonsilber, 35. Antimonsilberblende, 77. Antimony, Native, 21. Arsenical, 22. Gray. 83. Oxyd of, 140, 141. Plumose ore of, 76. Red. 141. Sulphuret of, 82, White, 140. Antimony blende, 141. bloom, 140. glance, SK Antrimolite, S29, Apatelite, 888. Aparite, 893 Abatotil, 5. 3. Absorbation 8. Absorb Applicate 82. Applicate 82. Applicate 882. Applicate 882. Applicate 82. Applicate 834. Applicate 834. Christian 🔻 🛦 Charles of the Charles VN C 32 388 18 18 1 B. Charles a street A CONTRACTOR SALES TO THE SECOND SE 9016 - 12 5 S and the second s particle of the same of the amplied of their sides 74. W. 74.5 Allin, Sh.

Argentite, 37. Argyrose, 87. Aricite, 822. Arkansite, 128. Arpidelite, 268. Arragonite, 448. Arsenate of lime, 414. ARSENATES, 396. ANHYDROUS, 396. Hyprous, 411. Arseneisen, 61. Arseneisensinter, 432. Arsenglanz, 22. oxydé, 139. sulfuré, 31. Sulphuret, 31, 32. White, 189. Arsenical antimony, 22. Arsenicite, c. Pharmacolite, Barnhardtit 414. Arsenikalkies, 61. Arsenikantimon, 22. Arsenikbleispath, e. Mime Barystroutu tene. Arsenikhismuth, e Eulytine. Arse: iki-i :: he, 189, 414. Arser ikeisen, 61. Arsenikgianne Arsengland Barytes, or Arsenskáles, éz Arenikolalikies 67. Amerika Assertic senter 412 Assertic forth floats ASSENII SYTS, 5,-55 Asserts 137 American market and ages American Charles American in 1986 American in 14 American in 176 American in 176 American in 176 Ballamazora en el plan. Advantage of my foliation of the control of the con 5 (1.8) 51, (1.1.8) 1. 2. 7 (8) 1 × 2. 4. to the second of

Carbocerine, 456. CARBONATES, 434. ANHYDROUS, 434. Hydrous, 454. Carbonic acid, 144. Carbunculus, 190. Carinthine, 172. Carminite, 410. Carminspath, 410. Carnat, 250. Carnelian, 147. Carolathine, 500. Carpholite, 316. Carphosiderite, 431. Carphostilbite, 326. Carrollite, 67. Cassiterite, 118. Cassiterotantalite, 351. Castelnaudite, 432. Castor, 253. Catapleiite, 308, 504. Catlinite, 252. Cat's eye, 148. Cavolinite, 232. Cawk, 366. Celestine, 368. Cerasine, Cerasite, 463. Cerer, v. Cerium. Cerine, 208. Cerinstein, 312. Cerite, 312. Cerium, Carbonate, 456. Fluorid, 96.

Silicate, 312. Cerolith, v. Kerolith. Ceroxydulkohlensaures, 456 Chrome ochre, 339. Cerusite, Ceruse, 452. Cervantite, 141. Ceylanite, 103. Chabazite, Chabasie, 319. Chalcanthit, 380. Chalcedony, 147. Chalcodite, 500. Chalcolite, 430. Chalcophacite, 429. Chalcophyllite, 428. Chalcopyrite, 68. Chalcostibite, 73. Chalcotrichite, 122. Chalilite, 325. Chalk, 438. Chalkosin, 46. Chalybite, 444. Chamoisite, 299. Chantonnite, 503. Chathamite, 56, 512. Chaux arseniatée, 404, 414

boratée siliceuse, 334. carbonatée, 435. fluatée, 94. Chenocoprolite, 432. Chert, 148.

Chesterlite, 246. Chessy copper, 459. Chessylite, 459. Chiastolite, 257. Childrenite, 424 Chileit, 129, 504. Chiltonite, 314. Chimborazite, v. Aragonite. Chiolite, 98. Chiviatite, 77, Chladnite, 503. Chloanthite, 56. Chlorastrolite, 315. Chlorhydrie aeid, 97.

CHLORIDS, 89. Chlorite, 294, 296. ferrugineuse, 296. spar, 298. Chloritoid, 298. Chloritspath, 298. Chlormerkur, 89. Chloromelan, 299. Chloropal, 337, 504. Chlorophæite, 278. Chlorophane, 94. Chlorophyllite, 215. Chlorospinel, 103. Chlorquecksilber, 89. Chodneffite, 97. Condurrite, Chondrodite, 186. Conichalcite Chonikrite, 291. Conistonite, Chrismatine, 474. Conite, 441. Christianite, 234, 324. Connellite, 3 CHROMATES, 359. Copal, Fossil Chromeisenstein, 106. Copiapite, 3 Copper, Nati Chromic iron, 106. Chryolith, v. Cryolite. Chrysoberyl, 122. Chrysocolla, 309, 504. Chrysolite, 184. Chrysophane, 297. Chrysoprase, 147. Chrysoprase earth, 340. Chrysotile, 282. Chusite, 184. Cimolite, 165.

Cipolino, 439. Clausthalite, 42. Clay, 249 to 252, 337 to 340, 504, 510. Clay slate, 509. Cleavelandite, 240. Cleiophane, 45. Clingmanite, 300.

Clinkstone, 246. Clinoclase, 428. Clinochlore, 293. Clintonite, 297, 505. Cluthalite, 318.

Cinnabar, 48.

Cinnamon stone, 191.

Coal, Miner Cobalt, Arse Arsenie Carboni

Earthy, Glance, Gray, 5 gris, 56. oxide n Red, 41 Sulphat Sulphos Sulphur White, Cobalt bloor Cobaltine, 5 Cobalt-mica Cobalt pyrit Coccinite, 9 Coccolite, 15 Cölestein, 36 Collyrite, 33 Colophonite COLUMBAT Columbite, & Comptonite, Condrodite,

> Arsenat 429. Arsenica Black, 1 Blue, 65 Capillar Carbons Chroma Emerald Glance, Gray, 85 Indigo, Oxychlo Oxyd, 10 Phospha 425. Purple, Pyritous Red, 101 Selenid, Silicate, Sulphat Sulphur Sulphur

GENERAL INDEX.

Cuivre gris, 82. hydrosiliceux, 309.

muriaté, 138.

Copper, Tungstate, 502. anadate, 362, 863. Variegated, 38. Vitreous, 46, 505. Copper and Lead, Selenid of, 42. Copper froth, 426. Copper glance, 46, 505. Copper green, 809. Copper mica, 428. Copper nickel, 52. Copper ore, Black, 109, 117. Blue, 459. Emerald, 309. Gray, 82, 512. Green, 458. Indigo, 65. Octahedral, 101. Variegated, 38. Velvet, 892. Yellow, 68. Copper pyrites, 68. Copperas, 380, 385, 887. Soda, 389. Potash, 389. Coquimbite, 380. Coracite, 108. Coral, 440. Corallinerz, 48. Cordierite, 214. Corindon, 111. Cork, Mountain, 172. Corneine, 172. Corneous lead, 463. Cornite, 246. Cornubianite, 246. Cornwallite, 425. Corundellite, 800. Corundophilite, 298. Corundum, 111. Cotunnite, 97. Couzeranite, 206. Covelline, 65, 505. Crednerite, 126. Crichtonite, 115. Crispite, 120. Crocidolite, 279. Crocoisite, 359. Cronstedtite, 299. Cross stone, 257. Crucite, 257. Cryolite, 97. Cryptolite, 399. Cryptoline, 471. Cuban, 68. Cube ore, 422. Cube spar, 869. Cubizit, 318. Cuboite, 318. Cuivre arseniate, 420-429. arsenical, 36. carbonaté, 458.

natif. 17. oxide rouge, 101. phosphaté, 420, 425. pyriteux, 68. pyriteux hepatique, 38. Diopeide, 159. selenié, 48. sulfate, 380. sulfuré, 46. sulfuré argentifère. 48. Diphanite, 801. vanadatė, 862. veloute, 892. Cumengite, Cummingtonite, 174. Cupreous anglesite, 390. manganese, 186. Cuprite, 101. Cuproplumbite, 41. Cyanite, 263. Cyanosite, Cyanose, 880. Cyanotrichite, v. Lettsomite. Dolomite, 441. Cyclopite, 254. Cymophane, 122. Cyprine, 197. Dalarnite, v. Mispickel. Damourite, 228. Danaite, 62. Danburite, 212. Datholite, Datolith, 334. Daourit, v. Rubellite. Davidsonite, 178. Davyne, 282. Davyt, 381. Dechenite, 861. Delanovite 500. Delessite, 296. Delphinite, 206. Delvauxene, 427. Demant, 24. Demantspath, 111. Dendrachates, 151. Dermatin, 280. Descloizite, 361. Desmin, 832 Devonite, 428. Deweylite, 285, 505. Diabase, 162. Diaclasite, 160. Diadochite, 438. Diagonite, 382. Diallage, Talkartiger, 160. Green, 160, 170. Metalloidal, 160. Diallogite, 446. Diamant, 24. Diamond, 24. Diaphorite, v. Allagite. Diaspore, 128. Diastatite, 172.

Dichroite, 214. Digenite, 48. Dihydrite, 425. Dillnite, 338. Dimagnetite, 106. Dimorphine, 82. Dinite, 475. Dioptase, 309. Diorite, 247, 509. Dioxylite, 374. Diploite, 284. Dipyre, 205. Discrasite, 85. Disomose, 58. Disterrite, 297. Disthene, 263. Dog Tooth Spar, v. Calcite, 485. Dolerine, 246. Dolerite, 162, 247, 510. Dolomite sinter, 457. Domeykite, 36. Domite, 246. Dopplespath, v. Calcite. Dopplerite, 474. Dreelite, 378. Dufrenite, 427. Dufrénoysite, 77. Dyoxylite, 874. Dysclasite, 806. Dyskolite, v. Saussurite. Dysluite, 108. Dyslytite, 53. Dysenite, 167. Dysyntribite, 252. Earthy cobalt, 186. manganese, 186. Edelforsite, 155, 808. Edelith, 814. Edingtonite, 823. Edwardsite, 402. Egeran, 197. Ehlite, 426. Ehrenbergite, 380. Eisen, Gediegen, 17. Eisenapatit, 399. Eisenalaun, 388. Eisenblau, 415. Eisenbluthe, 448. Eisenchlorit, 296. Eiseuchrom, 106. Eisenerde, Blaue, 415. Grüne, 182. Eisenerz, Trappisches, 116. Eisenerz, Hystatisches, 115. Eisenglanz, 113. Eisenglimmer, 118.

Eisengymnite, 286.

66

Emerica 181 Energy Translation and Translation 118 Ter elitari d Empley in Mary The State of the Barrier server 60. Friends . Errane. Si Energy after a Sufficient Experies 41. ويسر المتحسد استوق Farmer and **I** _ Turner et Inchrationa · Prince Inche 22 Frankrick 195 Inches 200 Essentativina J-----Endame. Formeriner Se : Erani arkin 4 Emerican II. Lumigner CL F. 10-16-2-1-2 3 Experience e belengalla- Fitmur- 265. Energy divines, 271 dire. Energy 1. Seiveleinnen, Engenfanz SI. Torizon C Figure state ! b- 341 35. Inches & Francisco M. Enem-ner 44 45 Inches of Lucuita (4) Lucita (6) Lucita (5) Emerican 155 Programme 15. 2 ---- 4 4 H Engine Hin CL Emeriment with PARTIE STAP Lucy in M. Lucy in M. Lucie M. Engineer 414 Engineeric 444 Francis . Fig. 147. Energym, e Let terre. Energym III Energym III From stone 14 Emercia 156. Fueikez-12 e. Institute and Pine ferri. 448. Engagenmark 7.2 Translation M. Tarrent . M. Emerican 129. Ixrae . Tre_te_ ... Promerize #4 Emeration 1988. Taken !! Proposition 45 Emperil 141 Fairmite 111. From: Te 34 Emen F Exemple 31 Emical 9 Fine Fine S Pinerscolità, PF Familie, 15t Emilia :: Emmune (I Timerail A. Fernesse 121. Foliated tellar. Europe F Electrical & Stellar to 1 to 5'es. Line to 1 to 5'es. Faraire 181 Feature aron, 281 Feature the 75 Fertal: tlear 414 Firster.14, 154 Energia I Federalstz. 581 582 Fowlerns 147 Fairwitz 16 Francisco A: Feldener 225 Sich Vale. 4 Franklinne, 1 e Enter I take 41. Emergial Te Emergial Emergial No Emmission 450 Ormers 242 Lates 1, 27. France place. . P :442 . 245 Frederic El. Freisielerlite, 7 Frazariit, 197 N. 14. Ectron 50 Feligiele, 142 Fale bire 175 Furbsite 212 Fuller's Earth, Fullouite, v. Or Feleste, 242 Endellante & Epitellante & Epitellante & Epitellante Et Epitellant Felentarytte, 184. Felepath, 242 a; vre. 257. b.se. 4-4. Funkite, 16% Fuscite, r Scap Epistic te. 23%. tenace, 254. Epistic te. 23%. Epistic, 254. Fer azuré, 415. tetade, 254. Gabronite, 57-5. Erikole. 128. arseniaté, 422 Gadolirite, 211 Erdhan, 469, 471. arsenical, 61, 62 Gagates, 27. Erdmannite, 195, 246. carbonate, 444. Gabnite, 105, Erdol, 469. chromaté, 1.6. Galapektite, r Erdwache, 474. hydro-oxide, 131. Galena, 32, 5 A. Gallicinite, 12 . Bremite, 4/12 natif. 17. Gallitzenstein. oligiste, 113. Erinite 425. Erlanite, 191. oxidé, 113. Galmey, 313, 44 Ernbewite, 38. oxidulé, 105. Ganomatit, 432 Erythrine, 416. magnetique, 105. Gansekothig era Garbenstilbit, 3 Erythrite, 215. muriate, 810. Eschenite, 357. phosphaté, 415. Garnet, 190 Remarkite, 205, 215, 884. sulfaté, 880, 885, 887. Bohemian,

Hauerite, 56.

Garnet, Tetrahedral, 194. Garnsdorffite, 390, Gay-Lussite, 455. Gedrite, 175. Gehlenite, 256, 205. Gekrösetein, 369. Gelbbleierz, 349. Gelbeisenerz, 389. Gelberde, 181. Gelberz, 64. Gelferz, v. Chalcopyrite. Geocronite, 85. Gersdorffite, 58. Geyserite, 151. Gibbsite, 134, 506, Gieseckite, 238. Giftkies, v. Mispickel. Gigantolite, 215. Gilbertite, 223. Gillingite, 290. Giobertite, 441. Girasol, 151. Gismondine, 322. Glance copper, 46. Glanzarsenikkies, 61. Glanzkobalt, 57. Glanzkohle, 26. Glaserite, 365. Glaserz, Glanzerz, 113, 131. Grünerde, 165. Glaskopf, 13, 131. Glätte, 109. Glauber salt, 886. Glauberite, 374. Glaucodot, 68. Glaucolite, 201. Glauconite, 288. Glaucophane, 177. Glaukosiderit, 415. Glimmer, 217-227. Glinkite, 184. Glottalite, 319. Gmelinite, 321. Gnei-8, 246. Gökumite, 197. Gold, 7. Gold amalgam, 15. G.shenite, 178. Goslarite, 384. Göthite, 129. Gotthardite, 77. Grammatite, 172 Grammite, 156. Granat, 190L Granite, 246, 509. Granulite, 246, 509. Graphic gold, 64. tellurium, 64. Graphite, 29. Graubräunsteinerz, 125. Grauerz, v. Galena. Graukobalterz, 41. Graugiltigerz, 82.

Graukupfererz, 84. Graulite, v. Tectizite, 388. Grausilber, v. Selbite Grauspiessglanzerz, 33. Grauspiessglaserz, 33. Gray antimony, 33, copper, 82, 512. Green diallage, 160, earth, 165, 511. iron ore, 427. lead ore, 401. malachite, 458. sand, 288. vitriol, 385. Greenlandite, 190. Greenockite, 51. Greenovite, 268. Greenstone, 162, 247. Grenat, 190. Grenatite, 261. Grengesite, 296. Groppite, 287. Groroilite, 136. Grossular, 191. Grünauite, 44. Grünbleierz, 400, 401. Grüneisenerde, 182. Grüneisenstein, 427. Grünerite, 160. Guanite, 413. Gummierz, 107. Gummispath, 431. Gurhofian, Gurhofite, 442. Gurolite, 305. Guyaquillite, 468. Gymnite, 285, 505. Gypsum, 377. Gyrolite, 805.

Haarkies, 49. Haarsalz, 381, 388. Hæmachates, 151. Hæmatite, 118. Hafnefjordit, 289. Haidingerite, 413, 78. Hair-salt, 381. Halbazurblei, 372 Hallite, 389. Halloylite, 251. Halloysite, 251. Halotrichine, 388. Halotrichite, 381, 383. Hampshirite, 277. Harmotome, 323, 824. Harringtonite, 328. Hartbraunstein, 117. Hartine, 47%. Hartite, 478. Hartkobaltkies, 67. Hartmanganerz, 135. Hatchettine, 478.

Hausmannite, 118. Häuyne, 230. Haydenite, 319. Hayesine, 394. Haytorite, 148. Heavy spar, 366. Hebetine, 189. Hedenbergite, 160. Hedyphane, 401. Helleflinta, 245. Heliotrope, 148. Helminth, 294. Helvin, 194. Hematite, 113, 506. Brown, 131. Hepatinerz, 310. Hepatite, 366. Hercinite, 103. Herderite, 410. Hermannite, v. Mangan-amphibole, Herschelite, 321. Hessite, 44, 506. Hetepozite, 407. Heteroclin, 127. Heteromerite, 199. Heteromorphite, 76. Heterosite, 407, 513. Heulandite, 330. Highgate resin, 467. Himbeerspath, v. Diallogite. Hisingerite, 290. Hohlspath, 257. Holmesite, 297. Holz, Bituminöses, 26. Holzkupfererz, 421. Holzopal, v. Wood opal. Honey stone, 475. Honigstein, 475. Hopeite, 409. Hornblei, 463. Hornblende, 170. Hornblende slate, 509. Hornerz, 92. Hornfels, 148, 246. Hornmangan, v. Rhodonite. Horn quicksilver, 89. Horn silver, 92. Hornstone, 148. Horse-flesh ore, 38 Houghite, 135. Howardite, 503. Houille, 26. Hudsonite, 160. Humboldtine, 464. Humboldtilite, 205. Humboldtite, 334. Humite, 186. Hureaulite, 407, 513, Huronite, 217. Hversalt, 388.

Lead, Sulphato-carbonate,

Kieselgalmey, 818. Kieselkupfer, 809. Kieselmalachit, 809. Kieselmangan, 167. Kieselschieffer, 148. Kieselspath, 240. Kieselwismuth, 181. Kieselzinkerz, 313. Kilbrickenite, 85. Killinite, 170. Kirwanite, 288. Klaprothine, 404. Klinoclas, 428. Knebelite, 186. Knistersalz, c. Common Salt, Kymatine, 170. Kobaldine, 67. Kobaltbesching, 417. Kobaltblüthe, 416. Kobalt-glanz, 57. Kobaltkies, 67. Kobaltsulfuret, 41. Kobaltvitriol, 385. Kobellite, 82. Kochsalz, 90. Kohle, 26. Kohlensaurer Kalk, 485. Kokkolit, 158. Kollyrite, 388. Kolophonit, 190. Konichalcit, 121. Konigine, 391. Könleinite, 172. Konlite, 472. Korite, 166. Kottigite, 418. Korund, 111. Koupholite, 314. Krablite, 248. Kraurite, 427. Kreittonite, 103. Kremersite, 90. Kreuzstein, 323. Krisoberil, 122. Krisolith, 184. Krisuvigite, 391. Krokidolite, 279. Krokoit, 359. Kryolite, 97. Kühnite, 404. Kupaphrite, 426. Kupfer, Gediegen, 17. Kupferantimonglanz, 78. Kupferbleiglanz, 41. Kupferbleispath, 890. Kupferblende, 84. Kupferblüthe, 101, 122. Kuppferdiaspore, 425. Kupferfahlerz, 82. Kupferglanz, Kupferglas, 46. Kupferglimmer, 428. Kupfergran, 309. Kupferindig, 65.

Kupferkies, 68. Kupferlasur, 459. Kupfermanganerz, 136. Kupfernickel, 52. Kupferpecherz, 810. Kupferphyllit, 428. Kupfersammterz, 892. Kupferschaum, 426. Kupferschwärze, 109, 187. Kupfer-smaragd, 309. Kupfer-vitriol, 380. Kupferwismutherz, 73, 88. Kupferwismuthglanz, 78. Kyanite, 268. Kypholite, 282. Kyrosite, 60. Labradorite, 287. Labrador feldspar, 237. Labrador hornblende, 160. Lagonite, 895. Lampadite, 186. Lanarkite, 374. Lancasterite, 456. Lanthanite, 456. 'Lapis-lazuli, 229. Lapis-ollaris, 276. Larderellite, 895. Lardite, 252, 276. Lasionite, 423. Lasurite, 459. Lasurstein, 229. Latrobite, 284. Laumonite, Laumontite, 307. Lepolite, 285. Lava, 510. Lavendulan, 417, 507. Lazulite, 404. Lead, 17. Antimonial sulphurets, Antimonate, 142. Argentiferous, 39. Arsenate, 401. Black, 29. Carbonate, 452. Chlorid, 97. Chloro-carbonate, 463. Chromate, 359, 861. Corneous, 463. Cupreous sulphate, 890. Lievrite, 262. Cupreous sulphato-car- Lignite, 26. bonate, 372. Hydro-aluminous, 431. Limbelite, 184. Molybdate, 849 Murio-carbonate, 468. Oxychlorid, 127, 128. Oxyds, 109, 117, 126.

Phosphate, 400.

Selenate, 875.

Sulphate, 370.

Seleniets, 42.

Sulphato-chlorid, 375. Sulphato-tricarbonate, 871. Supersulphuretted, 40. Sulphuret, 89, 506. Tellurid, 44, 65. Tungstate, 849. Vanadate, 362. White, 452. Lead glance, 39. Lead ochre, 109. Lead ore, Green, 401. Red, 859. White, 452. Yellow, 849. Lead vitriol, 370. Leadhillite, 871, 507. Leberblende, 46. Leberkies, 60. Ledererite, 321. Lederite, 268. Leedsite, 507. Leelite, 245, 248. Lehmanite, 359. Lehrbachite, 43. Lehuntite, 827. Lemnian Earth, 504. Lenzinite, 251. Leonhardite, 808. Lepidokrokite, 129, Lepidolite, 226, 508. Lepidomelane, 227. Leptynite, 246. Lettsomite, 392. Leuchtenbergite, 294. Leucite, 281. Leucolite, v. Pycnite. Leucocyclite, v. Apophyl-lite. Leucophane, 182. Leucopyrite, 61, 507. Leuzit, 231. Levyne. 821. Lherzolite, 160. Libethenite, 420. Liebenerite, 215. Liebigite, 461. Ligurite, 270. Lime, Anhydrous sulphate, 869. Arsenate, 414. Borate, 394. Borosilicate, 884. Carbonate, 485. Fluate, 94. Hydrous carbonate,457 Lime, Subcarbonate, 507. Nitrate, 434. Oxalate, 464. 465. Phosphate, 396. Silicate, 155, 156. Sulphate, 369, 877. Titanate, 845. Tungstate, 347. Limestone, 439. Hydraulic, 439, 507. Magnesian, 441. Limonite, 181. Linarite, 390. Lincolnite, 330. Lindackerite, 500. Lindsayite, 235. Linnæite, 67. Linseite, 235. Linsenerz, 429. Linsenkupfer, 429. Liparite, 94. Liroconite, 429. Litheospore, \$66. Lithionglimmer, 226, 508. Lithomarge, 250. Loboit, 197. Loganite, 293. Lölingite, 61. Lomonit, 307. Lonchidite, 61. Lophoite, 296. Lotalite, 170. Löweite, (Löveite), 501. Loxoclase, 244. Lumachelle, 439. Lunnite, 425. Lupus metallorum, 33. Lydian stone, 148. Lyncurion, 466. Macle, 257.

Maclurite, 186. Magnesia, Pure, 101. Borate, 393. Carbonate, 441. Fluophosphate, 403. Fluosilicate, 188. Hydrate, 133. Hydro-carbonate, 456. Sulphate, 384. Magnesia alum, 382. Magnesian limestone, 441. pharmacolite, 404. Magnésie hydratée, 133. Magnesite, 441, 277, 507. Magneteisenstein, 105. Magnetic iron ore, 105. Magnetic pyrites, 50. Magnetite, 105. Magnetkies, 50. Malachite, Blue, 459. Green, 458.

Malachite, Lime, 459.
Malacolite, 158.
Malacone, Malakon, 196.
Maltha, 469.
Malthacite, 340.
Mancinite, 156.
Mangan, Kohlensaures, 446.
Mangan-amphibole, 168.
Manganese, Oxyd of, 117, Mellitte, 275.
Hydrous oxyds, 180, Menaccanite, 1

135, 136.

Arseniuret, 58. Black, 185. Bog, 186. Carbonate, 446, 452. Cupreous, 136. Earthy, 186. Gray, 125, 130.

Phosphate, 399, 406, 408. Red, 446. Silicates, 167, 186.

Sulphate, 501.
Sulphuret, 41.
Manganese spar, 167.
Manganglanz, 41.
Manganite, 130.
Mangankiesel, 167.
Mangankupfererz, 126.
Mangankupferoxyd, 126.
Mangankupferoxyd, 126.

Manganocalcite, 452.
Manganopal, 151.
Manganschaum, 136.
Manganspath, 446.
Manganvitriol, 501.
Marasmolite, 45.
Marble, 439.

Verd antique, 284. Metaxite, 283, Marcasite, 60. Meteoric miner Misscite, 246. Marekanite, v. Pearlstone, Miargyrite, 74. Mica, 217-227. Mica, 217-227.

Margarite, 300. Margarodite, 228. Marialite, 230. Marl, 439. Marmatite, 45. Marmolite, 282. Martinsite, 90. Martite, 102. Mascagnine, 379. Masonite, 298. Matlockite, 127. Mauilite, 237. Medjidite, 392. Meerschaum, 277, 284. Meionite, 200. Melaconite, 109. Melanasphalt, 27. Melanchlor, 428, 518.

Melanglanz, 86. Melanite, 192. Melanochroite. Melanolite, 286 Melanterite, 38 Melaphyre, 162 Mellate of alun Mellilite, 205. Melopsite, 250. Menakerz, 268. Mendipite, 128 Meneghinite, 5 Mengite, 356. Menilite, 151. Mennige, 126. Mercurblende, Mercure argen sulfuré, 48 ioduré, 96 Mercury, Anti Amalgam, Chlorid, 8 Iodic, 96. Native, 14 Selenid, 5: Sulphuret, Merkurglanz, 5

Mesitine spar, Mesitinspath, 4 Mesole, 328. Mesolin, 322. Mesolite, 328. Mesotype, 327, epointée, ? Metachlorite, 2 Metaxite, 283, : Meteoric miner Miascite, 246. Mica, 217-227, Oblique, 2: Rhombie, Hexagonal Lithia, 226 Mica slate, 246, Michaelite, 151 Microlite, 345. Middletonite, 4 Miemite, 441. Miesite, 400. Mikroklin, 242 Millerite, 49. Miloschin, 389.

Meroxene, 225.

Mimetene, 401.
Mineral caoute
coal, 26.
resin, oil, 1
tallow, 47

GENERAL INDEX.

Minium, 126. Natro-calcite, 438. Notite, 166. Mirabilite, 386. Nussierite, 400. Natrolite, 327. Misenite, 377. Mispickel, 62, 509. Natron, 455. Nuttallite, 201. alaun, 382. Obsidian, 248. Misy, 388. salpeter, 433. Mizzonite, 200. Natron-spodumen, 289. Ochran, 252. Mocha Stone, 147. Naumannite, 43. Ochre, Iron, 113, 131. Bismuth, 141. Modumite, 67. Necronite, 244. Needle ore, 81. Mohsine, 61. Chrome, 339 Molybdie, 144. Mohsite, 115. Needle spar, 448. Needlestone, 327, 328. Plumbie, 109. Molybdanglanz, 66. Molybdanochre, 144. Nefelina, 232. Telluric, 502. Molybdänsilber, v. Tetrady-Nemalite, 133. Tungstic, 143. Uranic, 461. mite, Anal., & Neoctese, 419. Molybdate of lead, 849. Neolite, 278. Neoplase, 387 Ochroite, 312. Molybdate of iron, 144. Octahedrite, 121. Neotokite, 169. Odontolite, 513. Molybdène sulfure, 66. Erstedtite, 197. Molybdenite, 66. Neotype, 438. Nepheline, 232. Molybdic ochre, 144. Ogcoite, 296. Oil, Genesee or Seneca, 469. Nephrite, 175. Molybdine, 144. Monazite, 402. Magerer, 254. Oisanite, 121. Okenite, 306. Newjanskite, 19. Newkirkite, 130, 186. Monazitoid, 403. Mondstein, v. Moonstone, Oligiste iron, 113. Monheimite, v. Kapnite, 447. Nickel, Antimonial, 58. Oligoclase, 239, 506. Arsenate, 418. Oligon spar, 445. Arsenical, 52, 56, 58, 61. Olivenchalcit, 420. Monophan, 330. Monradite, 280. Monrolite, 263. Bismuth, 44. Olivenerz, 420. Monticellite, 84. Carbonate, 461. Olivenite, 420. Olivine, 184. Olivinoid, 508. Montmorillonite, 840. Copper, 52. Emerald, 461. Moonstone, 240, 244. Omphazit, 159. Morasterz, 31. Silicate, 889. Moroxite, 396. Sulphate, 386. Onegite, 129. Morvenite, 323. Sulphuret, 49. Onkosin, 504. Mosandrite, 342. White, 56. Onofrite, 52. Nickel glance, 57. Onyx, 148. Mountain green, 458. green, 418. ochre, 418. Oolite, 438. Oosite, 216. cork, 172. leather, 172. Opal, 151. Müller's glass, 151. stibine, 59. vitriol, 386. Opal allophane, 337. Mullerite, 64. Nickel and iron, Sulphuret Operment, 32. Mullicite, 415. of, 42. Ophite, 284. Mundic, 54. Nickelantimonglanz, 59. Murchisonite, 245. Opsimose, 167. Nickelarsenikglanz, 58. Nickelarsenikkies, 58. Or natif, 7. Muriacite, 369. Muriatic acid, 97. Orangite, 312. Nickel-blüthe, 418. Orawitzite, v. Halloyaite. Muromontite, 210. Nickel-bournonit, 81. Muscovite, 221, 508. Oropion, 503. Muscovy glass, 221. Nickelglanz, 58. Orpiment, 32. Nickel-gymnite, 286. Nickeliferous gray antimo-Orthoclase, 242, 506, 518. Müsenite, v. Siegenite. Mussite, 159. ny, 59. Nickelkies, 52. Orthose, 242. Mussonite, 463. Osteolite, 398. Myelin, 250. Ostranite, 196. Mysorin, 458. Nickelocker, 418. Nickelspiessglanzerz, 59 Ostreocolla, 435. Nickelwismuthglanz, 44 Osmelite, 305. Nacrite, 509. Osmiridium, 19. Nadeleisenerz, 129. Nigrine, 120. Nadelerz, 81 Niobite, 353. Ottrelite, 287, 509. Nagyager-erz, 85. NITRATES, 433. Ouvarovite, 192. Owenite, 290. Nagyagite, 65. Nitratine, 433. Oxacalcite, 464. Naphtha, 469. Nitre, 433. Naphthadil, 470. Nitrocalcite, 434. OXALATES, 464.

Nontronite, 337.

Nosean, Nosin, 230.

Oxalite, 464.

Oxhaverite, 304.

Napoleonite, 242.

Nasturan, 107.

OXYDS. Mosomeren, 101.

HETAGOSAL, 110. DESCRIBE, 117. TRIMITTEE, 122

WITH SCLPBERERS, CHLORIDS, 127. Hyperes, 128.

or ABSENC GROUP, 139. Petzite, 44. Ozarkite, 326. Ozocerite, Ozokerit, 474.

Pagodite, 252 Paisbergite, 167. Palagonite, 166.

Palladium, Native, 14. Palladium gold, 9.

Palladium ochre, 14. Panabase, 82 Paracolumbite, 501.

Paraluminite, 509. Paranthine, 201.

Parastilbite, 332 Pargasite, 172.

Parisite, 463. Parophite, 252

Partichin, 501. Partschite, 503.

Patrinite, r. Aikinite.

Paulit, 160.

Pearl-mica, 300. Pearl sinter, 151.

Pearl-spar, 441.

Pearlstone, 248.

Peastone, 438.

Pecheisenerz, 129. Pecherz, 107.

Pechkohle, 26.

Pechopal, 151.

Pechstein, 248.

Pechuran, 107.

Pectolite, 305.

Peganite, 408.

Pegmatite, 246.

Pegmatolite, 242.

Pektolite, 305.

Péle's Hair, 248.

Peliom, 214. Pelokonite, 186.

Pencatite, 509.

Pennine, 295.

Pennite, 457.

Pentaklasit, 158.

Percylite, 501.

Periclase, 101.

Peridot, 184.

Periklas, 101.

Periklin, 240.

Peristerite, 241. Perlglimmer, 800.

Perlit, 248.

Perlstein, 248.

Perthite, 242

Perofskite, 345. Perowskine, 496.

Perowakite, 345. Petalite, 253.

Petroleum, 469. Petrosilex, 248.

Petuntze, 250.

Pfeifenstein, 252.

Phaeolite, 319. Pharmacolite, 414.

Pharmakochaleit, 420.

Pharmakosiderit, 422, 426. Phenacite, Phenakit, 189.

Phengite, 221.

Phillipsite, 38, 324.

Phlogopite, 224. Phoenicite, 361.

Phœnikochroite, 361.

Pholerite, 251. Phonolite, 246.

Phosgenite, 463.

PHOSPHATES, 396.

Anhydrous, 396. Hydrors, 411.

Phosphocerite, 399.

Phosphochalcite, 425.

Phosphorblei, v. Pyromor-Plombgomme, 4:

phite. Phosphor-eisensinter, 433.

Phosphorit, 396.

Photizit, 167.

Phthanite. 148. Phyllite, 287.

Phylloretin, 472.

Physalite, 259.

Piauzite, 469.

Pickeringite, 382.

Picranalcime, 318.

Picrolite, Pikrolit, 282. Picropharmacolite, 415.

Picrophyll, Pikrophyll, 165, Polychroilite, 25

280.

Picrothomsonite, 326.

Pictite, 26%.

Piedmontite, v. Mangane-

sian epidote, 206.

Pierre grasse, 232.

Pihlite, 295.

Pimelite, 339. Pinguite, 338.

Pinite, 215.

Piotine, 282.

Pipestone, 252.

Pirenäit, 192.

Pirop, 194.

Pisolite, 438.

Pissophane, 390. Pistacite, 206.

Pistomesite, 443.

Pitchblende, 107 Pitchstone, 248. Pitchy iron ore.1 Piticite, Pittizit, Pittinerz, 107. Plagionite, 75. Plasma, 148. Plata azul, 511.

Pitch, Mineral, 4

Plaster of Paris, Plata verde, 93. Platinum, Nativ Platiniridium, 1: Plattnerite, 117.

Platyophthalmo Pleonaste, 103.

Pleuroclase, 403. Plinian, 62

Plomb antimonic carbonaté, chloro-carb

chromate, 1 hydro-alum

natif, 17.

oxydé, 109, seleniuré, 4

sulfuré, 39, See farther.

Plumbago, 29.

Plumbic ochre, 1 Plumbocalcite, 4

Plumbe resinite,

Plumbostib, 51. Plumose ore, 76.

Plumosit, 76.

Polianite, 131.

Pollux, 255.

Polyadelphite, 1:

Polyargite, 236.

Polybasite, 25.

Polycrase, 357

Polyhalite, 377.

Picrosmine, Pikrosmin, 281. Polyhydrite, r. F.

Polykras, 357. Polylite, 160.

Polymignyte, 35

Polyspharite, 40 Polytelite, 82.

Polyxen, 12.

Poonahlite, 329.

Porcelain spar, 2

Porphyry, 246, 5

Porpezite, 9.

Porricin, r. Pyro Portite, 311.

Potash alum, 382

Potash, Muriate.

Nitrate, 433. Sulphate, 36 Potstone, 276.

Potter's clay, 504. Pounxa, 394. Pozzuolana, 510. Prase, 147. Praseolite, 215. Prasochrome, 501. Predazzite, 457, 509. Prehnite, 314. Prosopite, 502. Protheite, 197. Protogine, 246, 509. Proustite, 78. Prunnerite, 439. Prussian blue, Native, 415. Przibramite, 45, 180. Paathyrin, 473. Pseudo-albite, 236. Pseudo-apatite, 398. Pseudomalachit, 425. Pseudo-nepheline, 232. Pseudo-sommite, 232. Pseudotriplite, 407. Psilomelane, 135. Pumice, 246. Purple copper, 38. Puschkinite, 206. Pycnite, 259. Pyrallolite, 165. Pyrantimonite, 141. Pyrargillite, 215. Pyrargyrite, 77. Pyrenaite, 192. Pyrgom, 159. Pyrites, Arsenical, 61, 62. Auriferous, 54. Capillary, 49. Cellular, 60. Cockscomb, 60. Copper, 68. Hepatic, 60. Hydrous, 61. Iron, 54. Magnetic, 50. Radiated, 60. Spear, 60. Tin, 70. Variegated, 88. White iron, 60. Pyrochlore, 845. Pyrolusite, 125. Pyromeline, 886. Pyromeride, 246. Pyromorphite, 400. Pyrope, 194. Pyropissite, 470. Pyrophyllite, 808. Pyrophysalite, 259. Pyrorthite, 209.

Pyrosclerite, 291.

Pyrosiderite, 129.

Pyrosmalite, 810.

Pyrostibite, 141.

Retinite, 467. Pyroxene, 158. Retzite, v. Ædelforsite, 308. Pyroxenite, 246. Pyrrhite, 346. Reussin, 375. Pyrrhosiderite, 129. Rhætizit, 263. Pyrrhotine, 50. Rhodalose, 385. Rhodium gold, 9. Rhodizit, 898. Quartz, 145. Granular, 148. Rhodochrome, 291. nectique, 148. Rhodochrosite, 446. resinite, 151. Rhodonite, 167. Tabular, 148. Quecksilberfahlerz, 82. Rhodophyllite, 291. Rhombenglimmer, 225. Rhomb-spar, 441. Quecksilberbranderz, 470. Quecksilberhornerz, 89. Rhyacolite, 245. Quecksilber lebererz, 48. Riemannite, 386. Quellerz, 131. Riolite, 502. Quicksilver, Native, 14. Ripidolite, 296, 294. Risigallo, 31. Antimonite, 142. Chlorid, 89. Rittingerite, 87. Sulphuret, 48. Rock-cork, 172. lodid, 96. crystal, 145. Selenid, 52. mílk, 438. Quincite, 281. salt, 90. soap, 252. Rochlandite, v. Serpentine. Romanzovit, 191. Rabenglimmer, v. Lepidomelane. Radelerz, 80. Romeine, 410. Radiated pyrites, 60. Roofing slate, 509. Radiolite, 327. Rose quartz, 145. Rammelsbergite, 56, 61. Roselite, 417. Randanite, 152. Rosellan, Rosite, 286. Raphanosmite, 42. Rothbleierz, 859. Rotheisenerz, 113. Raphilite, 172. Rother vitriol, 887. Raseneisenstein, 181. Rothgültigerz, 77, 78. Ratoffkit, 94. Rauhkalk, 442. Rothkupfererz, 101, 122. Rauschgelb, 31, 32. Rothnickelkies, 52. Rothoffit, 190. Rautenspath, 441. Rothspiessglanzerz, 141. Rothspiesglaserz, 141. Razoumoffskin, 340. Realgar, 31. Red antimony, 141. Rothzinkerz, 110. chalk, 118. Rubellan, 226. Rubellite, 270. Rubicelle, 108. copper ore, 101, 122. hematite, 113. Rubin, 111.
Rubinglimmer, 129.
Ruby, Spinel, Balas, Almandine, 103. iron ore, 118. iron vitriol, 887. lead ore, 859. manganese, 446. ochre, 118. Oriental, 111. silver ore, 77, 78. Ruby-blende, 77. Ruby silver, 77, 78. vitriol, 385. Ruby sulphur, 31. zinc ore, 110. Reddle, 118. Rutherfordite, 858. Redruthite, 46. Rutile, 120. Remingtonite, 461. Ryacolite, 245. Remolinite, 188. Rensselaerite, 165. Resigallum, 81, 82. Resin, Mineral, 467, etc.

Saccharite, 286. Safflorite, 511. Segenite, 120. Sahlite, 159. Sal ammoniac, 92. gemme, 90.

Highgate, 467. Retinasphalt, 467. Retinalite, 288.

iemen in a remark Sat Commun. M. Sattemer, 433. PERDETER ... methernin, 35 mande. Wi. il servene minum, 36 iomiin. 145. posite is in 181 ODEC 353 ppers 🗀 7 mm. 414 Seprimental Miles Servaire and Sari. 16. Series and Service Att. miin. : 44 Sann spac III. 1886. Sitersoonpia, 5/7. Semina e Lineau Serie Lid Samurine 154 FAIRE H Secretaria 138 Seepoiice, Mil. Senanacan, ISC. Schoolent, 3:4 Seinephueinta, a Biamath Seisenmulybeisena 43. Silver, 14. Senammica & J. Scheechierspach, 34% Seineistan. 143. Scheelin micatre, 347 ierragine, iil Schwitz, M. Scheeissare, 143. Scheematres hier. 348. Seinererise, 471. Schilligiasera, 73. Schillernder asbest, 182 Schiller-spar. 160, 165. Schillerstein, 1993 Schmeinstein, 201, 203. Schmirgel, III. Schneiderite, 31% School, 27 V Schorlartiger beril, 25% Schorlite, 259. Schorlomite, 342 Schreibersite, 53, 511. Sehrifterz, Sehrift-tellur, 64. Sideroschisolite, 299. Schrotterite, 337. Schulzit, 85. Schutzit, r. Celestine. Schwarzbraunstein, 135. Schwarzerz, 41, 82 Schwarzgiltigerz, 82.

Schwarzmanganerz, 135.

Seir war moissagisseers, 30. Sen value all Sen werin. 44 Sen wereign amorablei, SL Sen verinicus. SA. Sen venekudnit. 67. Sen Verienrunkei, 44. Senverhimers, 117. Sen werspeth, 366. Senverstein, Mi. Senwimmkienel, 151. Scientellunce, 168 Somette 125 Andrirona 37. Serieserune 33% Searchite, 413, 511. Dit annè Servicence, 136 Severa a Limonite Summetein, 252 Seindonite, 145, 511. Seibner 51L Seienoiei. 43 Seienbieikupfer, 42 Seinebinmputh 3.5. Seiente. 3.... Seimium, 13. Seimknosithiet 42 Seienkupter, 43. Seinenkupüerbini, 42 Seienkuptersüber, 43. Selan palladite. 14 Seleniguecksi berbiel, 43. Seiensen wefen zeeksinder. 31 Seienstiber, 43. Seleaszipäur. 24. Semena, v. Sphene. Semi-scal, 151. Senarmontite, 140. Seneca ci., 469. Sepiolite, 277. Sertuan, 339. Serieite, 223, 509. Serikolite, v. Satin spar. Serpentine, 192, 511. of Aker, 292 Severite. 5:14 Serbertite, 297. Shepardite, 53. Siberite, r. Rubellite. Siderite, 147, 422, 444. Sideromelane, 24% Siderose, 444. Siderochalcit, 428. Siderotantal, 351. Siegelerde, 504. Siegenite, 67. Sienite, 246. Silber-und-antimon, 79.

Silberfahlerz, 8 Silberglanz, 37 Biegsamer Silberhornerz, Silber-kupfergl Silberphylling Süber-spiesegh Silberwismuth Silex, 145. SILICATES,A' 154, 1. EDELFOR 155. 2. Averts 3. Etlym 181. 4 GARNEI 5. MICA SI 6. FELDER 228. 7. ANDALE 256. SILICATES, I 275 L. TALC SI 2 SERPET 279 \$ CHLORE 259. 1. Precent TROX. 30% 2. PECTOLE 3114 S. CALAMIN 311. 4. ZEOLITE 5. DATEGIA 334 Silice gelatinen Silicified wood Silicious sinter. Silicite, 237. Sillimanite, 265 Silvanite, 64 Silver, Antimos Antimonia 77, 79, 5 Arsenical Bismuthic, Black, Sc. Brittle sul Bromie, 93 Carbonate. Chlorid, 9:

Cabiena e

Flexible st Gray Frei

Horn, 92

Iodic, 95, 5

Iodo-brom

Muriate, y

Native, 15

Silver, Red, or Ruby, 77, 78 Spherostilbite, 332. Selenic, 43. Sulphuret, 87. Sulphuret of Copper and, 48. Telluric, 44 Vitreous, 87. Silver glance, 37,86. Silver ore, Brittle, 86. Flexible, 71. Red, or Ruby, 77, 78. Sinopite, 503. Sinter, Siliceous, 148, 151. Sismondine, 298. Sisserskite, 19. Skapolith, 201. Skolecite, 828. Skolopsite, 231 Skorodit, 419, 511. Skutterudite, 67. Slate-spar, 439. Sloanite, 329. Smaltine, 56, 511. Smaragd, 178. Smaragdite, 170. Smaragdo-chalcit, 809. Smectite, 251, 340. Smelite, 250. Smirgel, 111. Smithsonite, 447. Soapstone, 275, 282. Soda, Borate of, 394. Carbonate of, 454. Muriate of, 90. Nitrate of, 438. Sulphate, 365, 386. Soda alum, 382. Soda copperas, 889. Soda spodumene, 289. Sodalite, 229. Soimonite, v. Corundum. Solfatarité, 882. Somervillite, 205. Sommite, 232. Sonnenstein, v. Sunstone. Soude, v. Soda. Sordawalite, 177. Soufre, 22. Spadaite, 278. Spaniolite, 83. Spargelstein, 396. Sparkies, 60. Sparry or Spathic iron, 444. Spartalite, 110. Spatheisenstein, 444. Spear Pyrites, 60. Speckstein, 275. Specular Iron, 118. Speerkies, 60. Spessartine, 192. Speiskobalt, weisser, 56. Spherosiderite, 444.

Sphærulite, 248. Sphalerite, 45. Sphene, 268. Sphenomatite, 508. Sphragide, 504. Spieraglanz, Gediegen, 21. Spieseglanzocher, 142. Spiesglanzweiss, 140. Spiessglanzbleierz, 80. Spiesglas, 21. Spiesglas-silber, 35. Spinel, 108. Spinel ruby, 108. Spinellane, 230. Spinelle zincifère, 108. Spinthere, 268. Spodumene, 169. Soda, 239. Spreustein, 827. Sprödglanzerz, 86. Sprödglaserz, 86. Sprudelstein, 449. Stahlkobalt, 58. Stahlstein, 444. Stalactite, 439. Stalagmite, 439. Stangenkohle, 26. Stangenspath, 366. Stangenstein, 259. Stannine, 70. Stannite, 512. Stanzait, 257. Staurolite, 261, 323. Staurotide, 261. Steatite, 275, 282, Steinheilite, 214. Steinmannite, 41, 40. Steinmark, 250. Steinöl, 469. Steinsalz, 90. Stellite, 306. Stephanite, 86, 128. Stercorite, 418. Sternbergite, 71. Stibiconise, 142. Stibine, 88. Stibium, 83 Stiblite, Stibilite, 142 Stibnite, 38. Stilbite, 382. Stilbit anamorphique, 380. Blättriger, 330. Stillolite, v. Opal. Stilpnomelane, 287. Stilpnosiderite, 129. Stinkstone, 489. Stolpenite, 508. Stolzit, 848. Strahlenkupfer, 428. Strahlerz, 428. Strahlkies, 60,

Strahlstein, 170. Strahlzeolith, 382. Strakonitzite, 502. Stratopeite, 169. Stroganowite, 208. Stromeyerite, 48. Stromnite, v. Barystrontianite, 451. Strontia, Carbonate, 450. Sulphate, 868. Strontianite, 450. Strontianocalcite, 439. Struvite, 413. Stylobite, 256. Stypticite, 388. Succinite, 191, 466. SULPHATES, 864. ANHYDROUS, 364. HYDROUS, 376. Sulphur, Native, 22. Selenic, 24. SULPHURÉTS, **3**0–88. Sulphuric acid, 148. Sulphurous acid, 143. Sumpferz, 181. Sunstone, 289, 244. Susannite, 373. Swaga, 894. Swinestone, 439. Syenite, 246. Syepoorite, 41. Sylvan, Gediegen, 20. Sylvanite, 64. Sylvine, 90. Symplesite, 418. Tabergite, 291. Tabular spar, 156. Tachylite, 177. Tachyaphaltite, 197. Tafelspath, 156. Tagilite, 426. Talc, 275. Talc-apatite, 398. Tale phosphorsäurer, 408. Tale zographique, 295. Talcite, 509. Talkerde, v. Magnesia. Talkerdealaun, 882 Talkspath, 441. Talkhydrat, 188. Talksteinmark, 250. Tallow, Mineral, 478. Tamarite, 428. TANTALATES, 344 Tankite, v. Chiastolite. Tannenite, 78, 512. Tantale oxydé yttrifère, 859 Tantalite, 851. Tarnowitzite, 448. Tautolite, 185. Tectizite, 388.

GENERAL INDEX.

Völknerite, 134. Zellkies, 60. Wismuthbleierz, 16. Volborthite, 362. Wismuthglanz, 33. Volcanie glass, 248, Wismuthochre, 141. Volcanite, v. Selensulphur. Wismuthoxyd, Kolens., 462. Volgerite, 142, 513. Wismuthsilber, 16. Voltaite, 383. Voltzite, Voltzine, 127. Wismuthspath, 462. Withamite, 206. Voraulite, 404. Vosgite, 238. Witherite, 449. Wittichite, 88. Vulpinite, 369. Wittingite, 169. Wodankies, v. Gersdorffite. Zinc, Wacke, 247. Wærthite, 265. Wad, 136. Wöhlerite, 343, 513. Wagnerite, 403. Wolchite, 82. Wolchonskoite, 839, 513. Walchowite, 469. Walmstedtite, r. Breunner-Wolfram, 351. ite. Wolframine, 143. Warwickite, 395. Wolframbleierz, 348. Washingtonite, 115. Wolframochre, 143. Wasserblei, 66. Wolfsbergite, 73. Wasserglimmer, 223. Wollastonite, 156. Wasserkies, 61. Wood, petrified, 148. Water, 110. Wood-opal, 52. Wavellite, 423. Würfelerz, 422. Websterite, 389. Wulfenite, 349. Wehrlite, 263. Wundererde, v. Teratolite. Weichbraunstein, 125. Weicheisenkies, v. Wasser-Xanthite, 197. kies. Xanthocone, 87. Weichmangan, 125. Xanthophyllite, 297. Xanthorthit, 209. W. isableierz, 452. Weissgültigerz, 82. Xanthosiderite, 138. Weissian, v. Scolecite. Xenolite, 265. Weissigite, 254, 513. Xenotime, 401. Weissite, 215. Xylite, Xylotile, 285. Weisskupfererz, 86, 60. Xylochlore, 305. Weissnickelkies, 56, 61. Xylokryptit, v. Scheererite | Zinkglas, 313. Weisspiessglanzerz, 140. Weissstein, 246. Yanolite, 213. Weisstellur, 64. Yellow copperas, 387. Wernerite, 201. copper ore, 68. Wheel-ore, 80. lead ore, 349. Whewellite, 464. tellurium, 64. White antimony, 140. Yenite, 262. arsenic, 139. Ytterbite, 211. Yttererde, Phosph. 401. copperas, 380. iron pyrites, 60. Ytterspath, 401. lead ore, 452. Yttria, Phosphate 401. tellurium, 64. Tantalate, 399. vitriol, 384. Silicate, 255. Wichtine, Wichtisite, 177. Yttrocerite, 95.

Wiesenerz, r. Bog iron ore, Yttrocolumbite, 359. Yttroilmenite, 355. Ytrro-tantalite, 359. Yttro-titanite, 341. Zala, 894. Zengonite, 322. Zeasite, r. Opal. Zeilanit, 103.

131.

Wilhelmite, 189.

Williamsite, 284.

Wiluite, 191, 197.

Wismuth, Gediegen, 20.

Willemite, 189.

Wilsonite, 502.

Wiserite, 447

Zeolite, Feather, 327, 328. Foliated, 830, 382. Efflorescing, 307. Needle, 827, 328. Pyramidal, 804. Zeuxite, 270. Zianite, v. Kyanite. Ziegelerz, 101. Zigueline, 101. Arsenate, 418. Carbonate, 447, 460. hydraté cuprifére, 426. Iodid and Bromid, 97. oxidé, 110. oxidé silicifère, 189. Oxysulphuret, 127. Phosphate, 409. Red oxyd, 110. Silicate, 156, 189. Silicious oxyd, 189,818. sulfate, 884. sulfure, 45. Sulphate, 384. Sulphuret, 45. Zinc blende, 45. Zine bloom, 460, 513. Zincfahlerz, 85. Zine vitriol, 384. Zinc ore, Red, 110. Zincite, 110. Zinconise, 460. Zinkarseniat, 418. Zinkblüthe, 460. Zinkenite, 74. Zinkkieselerz, 313. Zinkoxyd, 110. Zinkphyllit, 409. Zinkspath, 447. Zinkvitriol, 384. Zinn, 19. Zinnerz, 118. Zinnkies, 70. Zinnober, 48. Zinnstein, 118 Zinnwaldite, 227. Zippeite, 461. Zircon, 195. Zirconite, 195. Zoisite, 211, 206. Zölestein, 368. Zootinsalz, v. Nitratine. Zorgite, 42. Zundererz, 76. Zurlite, 205. Zwieselite, 399. Zygadite, 254.

ERRATA AND ADDENDA.

VOL. I. p. 7, add after l. 1, "Number I, being the first part, of the of Prof. C. U. Shepard's Treatise on Mineralogy (1852)."
p. 75, 4th l. fr. top, for ma tan ½Zν½, read ma=tan ½Zν½.
p. 87, 17th l, fr. top, for a: b=sin μ: sin ν, read*a: b=sin ν: p. 92, 8th l, fr. top, for Monoclinic System, read Monometric System.

VOL. II. p. 32, in f. 270A, for the lower 11 (to right), read it, and for read 1%.

p. 44, under Grunauite, add, Streak dark gray.
p. 80, 4th l. fr. top, for Antimonie read Antimoine.
p. 100, 3d l. fr. top, dele Chalcotrichite.
p. 140, in f. 334, li should be 1%
p. 153, 6th l. fr. bottom, for Columbates, Niobates, read COLUMBATES.

D. 156, 12th l. fr. bottom, for 2i read 2i.
p. 183, 17th l. fr. top, in part of edition, for 1:, read 1: 1.
p. 242, 23d l. fr. top, for Sunadin, read Sanidin.
p. 261, in f. 461, for ii, read ii.
p. 309, 3d l. fr. bottom, for 18, read 118.

p. 316, under Savite, 9: 9: 26; 2, should be 9: 9: 26: 6; and 2, should be 9:9:25:3.

p. 332, 17th l. fr. bottom, dele all of paragraph after "silica."
p. 343, To description of Mosandrite, add, Occurs with Albite fluor at Brevig.

p. 345, To Pyrochlore, add, Streak light-brown to yellow.
p. 351, at top, for Columbate, read Tantalate.
p. 413, 22d l. fr. top, for i2, read i2.
p. 419, 12th l. fr. top, for i2, read i2.
p. 448, 15th l. fr. top, for Esenbluth, read Eisenblüthe.

p. 450, 12th l. fr. bottom, for 4 read 4. p. 452, to description of Manganocalcite, add, From Schemnit

